


## Appendix A      Figures


---























## **Appendix B      Investigation Logs**

---



Level 4, 139 Carlton Gore Road  
PO Box 9762, Newmarket  
Auckland, New Zealand  
Tel: +64 9 520 6019  
www.aurecongroup.com

Client: **Ngati Whatua Orakei Whai Rawa Ltd**  
Project: **Eastcliffe Retirement Village**  
Location: **217 Kupe Street, Auckland**  
Project Reference: **255232**

**BH01**

Sheet 1 of 3

**BOREHOLE INFORMATION**  
Method: Rotary Core Wireline  
Equipment: Tracked Rig  
Contractor: Pro-Drill Ltd

**CO-ORDINATES: Mt Eden Circuit 2000**  
Easting: 405347.8m  
Northing: 803113.9m  
Reduced level: 45m  
(Auckland MSL 1946 Datum)

Date started: 3/04/2018  
Date completed: 3/04/2018  
Inclination: -90°  
Azimuth: N/A

Logged by: BGW  
Input by: BGW  
Checked by: RAB  
Verified by: MFSL

Method	R.L. (m)	Length (m)	Graphic Log	Layer Code	Material Description	Weathering/USC	Testing	TCR (%)	SCR (%)	RQD (%)	Fracture Log	Stratigraphy Defect Description Additional Notes	Installation
Box 1 HA	44	1		F	0m: SILT with minor clay and trace building debris; brown. Stiff; moist; non-plastic. [FILL]	ML		100			<div><div>VWS</div><div>WWS</div><div>CS</div><div>VCS</div><div>ECS</div></div>	0m: FILL	
Box 2 SPT	43	2		Va	1.4m: Fine ASH; light greyish brown, spotted brownish orange. Stiff; moist; high plasticity. (Silty CLAY with trace completely weathered fine gravel)	CH	1.5m: SPT 6// 2,3,3,3 N = 11	100				1.4m: AUCKLAND VOLCANIC FIELD	
Box 2 OB	42	3		Va	3.4m to 4.2m:...Minor sand; banded brownish orange.	CH	3m: SPT 4// 3,4,4,4 N = 15 3m: IBHSV 148/54 kPa	100					
Box 2 OB	41	4		Va		CH	4.5m: SPT 5// 3,3,3,4 N = 13 4.5m: IBHSV 76/34 kPa	70				4.2m: EAST COAST BAYS FORMATION	
Box 3 SPT	40	5		ERC	4.2m: Sandy CLAY; grey banded orange. Stiff; moist; high plasticity. [RESIDUAL ECBF]	CH		100					
								0					

REMARKS:  
1) Hole depth specified in Water Level Readings is the bottom of the piezometric screen.  
2) IBHSV = In Barrel Hand Shear Vane, SPT = Standard Penetration Test, SPTC = Solid Cone Standard Penetration Test.  
3) Locations were estimated using Auckland Council GeoMaps and are in terms of Mount Eden 2000 Circuit with an approximate accuracy of +/- 5m.  
4) Reduced level reading was obtained from an existing LIDAR dataset with an approximate accuracy of +/- 1.0m.  
5) ECBF = East Coast Bays Formation.

**Water Level Readings:**  
Date Time | Hole Depth | Water Level  
(1) 04/04/18 08:15 | 6.00m | 2.08 m bgl  
(2) 05/04/18 08:00 | 6.00m | 4.2 m bgl  
(3) 06/04/18 07:30 | 6.00m | 5.23 m bgl  
(4) 09/04/18 07:45 | 6.00m | 5.41 m bgl  
(5) 23/04/18 11:42 | 6.00m | 3.89 m bgl



<b>BOREHOLE INFORMATION</b> Method: Rotary Core Wireline Equipment: Tracked Rig Contractor: Pro-Drill Ltd	<b>CO-ORDINATES: Mt Eden Circuit 2000</b> Easting: 405347.8m Northing: 803113.9m Reduced level: 45m (Auckland MSL 1946 Datum)	Date started: 3/04/2018 Date completed: 3/04/2018 Inclination: -90° Azimuth: N/A	Logged by: BGW Input by: BGW Checked by: RAB Verified by: MFSL
--	---	---	---

Method	R.L. (m)	Length (m)	Graphic Log	Layer Code	Material Description	Weathering/USC	Testing	TCR (%)	SCR (%)	RQD (%)	Fracture Log	Stratigraphy Defect Description Additional Notes	Installation
OB	39	6		ERx	4.95m: CORELOSS.			0					
SPT				ERz	6m: Sandy SILT with trace clay; light brown mottled brownish orange. Firm; moist; low plasticity.	ML	6m: SPT 4// 2,2,2,2 N = 8	100					
OB	38	7		ERc	6.75m: CLAY; yellowish brown mottled light grey. Stiff; moist; high plasticity. [Completely weathered ECBF]	CH		100					
				CH	7.05m: Silty CLAY; light brown mottled orange. Stiff; moist; high plasticity.	CH							
					7.3m to 7.4m: Silty SAND.								
SPT	37	8		ERs	7.45m: Silty SAND; light brown mottled orange. Loose; wet.	SM	7.5m: SPT 3// 1,2,2,2 N = 7	100					
OB	36	9		EWz	8.3m: Highly weathered, grey, SILTSTONE; extremely weak (very stiff).			100					
SPT						HW	9m: SPT 4// 2,3,4,4 N = 13	0					
OB	35	10			9.65m to 9.7m: CLAY.			100	13	13			

REMARKS:  
1) Hole depth specified in Water Level Readings is the bottom of the piezometric screen.  
2) IBHSV = In Barrel Hand Shear Vane, SPT = Standard Penetration Test, SPTC = Solid Cone Standard Penetration Test.  
3) Locations were estimated using Auckland Council GeoMaps and are in terms of Mount Eden 2000 Circuit with an approximate accuracy of +/- 5m.  
4) Reduced level reading was obtained from an existing LIDAR dataset with an approximate accuracy of +/- 1.0m.  
5) ECBF = East Coast Bays Formation.

**Water Level Readings:**  
**Date Time | Hole Depth | Water Level**  
(1) 04/04/18 08:15 | 6.00m | 2.08 m bgl  
(2) 05/04/18 08:00 | 6.00m | 4.2 m bgl  
(3) 06/04/18 07:30 | 6.00m | 5.23 m bgl  
(4) 09/04/18 07:45 | 6.00m | 5.41 m bgl  
(5) 23/04/18 11:42 | 6.00m | 3.89 m bgl



Level 4, 139 Carlton Gore Road  
PO Box 9762, Newmarket  
Auckland, New Zealand  
Tel: +64 9 520 6019  
www.aurecongroup.com

Client: **Ngati Whatua Orakei Whai Rawa Ltd**  
Project: **Eastcliffe Retirement Village**  
Location: **217 Kupe Street, Auckland**  
Project Reference: **255232**

**BH01**

Sheet 3 of 3

<b>BOREHOLE INFORMATION</b> Method: Rotary Core Wireline Equipment: Tracked Rig Contractor: Pro-Drill Ltd		<b>CO-ORDINATES: Mt Eden Circuit 2000</b> Easting: 405347.8m Northing: 803113.9m Reduced level: 45m (Auckland MSL 1946 Datum)		Date started: 3/04/2018 Date completed: 3/04/2018 Inclination: -90° Azimuth: N/A		Logged by: BGW Input by: BGW Checked by: RAB Verified by: MFSL	
--	--	---	--	---	--	---	--

Method		R.L. (m)	Length (m)	Graphic Log	Layer Code	Material Description	Weathering/USC	Testing	TCR (%)	SCR (%)	RQD (%)	Fracture Log	Stratigraphy Defect Description Additional Notes	Installation	
Box 4	B			XXXXXX XXXXXX XXXXXX		8.3m: Highly weathered, grey, SILTSTONE; extremely weak (very stiff).	HW		100	13	13	VWS WS MWS CS VCS ECS			
	Rock Level														
Box 5	SPTC	34	11	XXXXXX XXXXXX XXXXXX	EWZ	10.5m: Moderately weathered, grey, SILTSTONE; very weak.	MW	10.5m: SPTC 50// for 140mm N = 50+	N/A				10.5m: SPT test terminated in seating penetration.		
	HQ3	33	12	XXXXXX XXXXXX XXXXXX	EUs	11.05m: Slightly weathered, grey, SANDSTONE; weak. Well cemented. 11.23m to 12.19m:...Very weak. Moderately cemented.	SW		97	88	72				
	SPTC			XXXXXX XXXXXX XXXXXX	EUz	12.19m: Slightly weathered, grey, SILTSTONE; very weak.	SW		N/A				12.5m: SPT test terminated in seating penetration.		
	SPTC			XXXXXX XXXXXX XXXXXX	EUs	12.57m: Slightly weathered, grey, SANDSTONE; weak. Well cemented. 12.68m to 12.8m:...Very weak. Moderately cemented.	SW	12.5m: SPTC 50// for 65mm N = 50+							
	HQ3	32	13	XXXXXX XXXXXX XXXXXX	EUz	12.8m: Slightly weathered, grey, SILTSTONE; very weak. Laminated with very thin sandstone lenses.	SW		100	100	90				
SPTC			XXXXXX XXXXXX XXXXXX	EUs	13.42m: Slightly weathered, grey, SANDSTONE; weak. Well cemented. 13.51m to 13.56m:...Very weak.	SW		N/A				14m: SPT test terminated in seating penetration.			
						13.56m: Slightly weathered, grey, silty fine SANDSTONE; weak. Well cemented. 13.76m to 13.9m:...SILTSTONE.	SW								
						13.9m to 14m:...Weak. Well cemented.	SW	14m: SPTC 50// for 65mm N = 50+	N/A						
End of borehole at 14.07m (Target Depth)															

REMARKS:

- Hole depth specified in Water Level Readings is the bottom of the piezometric screen.
- IBHSV = In Barrel Hand Shear Vane, SPT = Standard Penetration Test, SPTC = Solid Cone Standard Penetration Test.
- Locations were estimated using Auckland Council GeoMaps and are in terms of Mount Eden 2000 Circuit with an approximate accuracy of +/- 5m.
- Reduced level reading was obtained from an existing LIDAR dataset with an approximate accuracy of +/- 1.0m.
- ECBF = East Coast Bays Formation.

Water Level Readings:

Date Time	Hole Depth	Water Level
(1) 04/04/18 08:15	6.00m	2.08 m bgl
(2) 05/04/18 08:00	6.00m	4.2 m bgl
(3) 06/04/18 07:30	6.00m	5.23 m bgl
(4) 09/04/18 07:45	6.00m	5.41 m bgl
(5) 23/04/18 11:42	6.00m	3.89 m bgl



## Eastcliffe Retirement Village Redevelopment Ground Investigation

**aurecon**

Borehole Reference: **BH01**

Date Drilled:

**03/04/2018**

Photographed By: **RAB**

Date Photographed:

**03/04/2018**



Box 1. - Depth: 0.00m to 1.50m.



Box 2. - Depth: 1.50m to 4.50m.



# Eastcliffe Retirement Village Redevelopment Ground Investigation

**aurecon**

Borehole Reference: BH01

Date Drilled:

03/04/2018

Photographed By: RAB

Date Photographed:

03/04/2018



Box 3. - Depth: 4.50m to 7.95m.



Box 4. - Depth: 7.95m to 10.36m.



## Eastcliffe Retirement Village Redevelopment Ground Investigation

**aurecon**

Borehole Reference: **BH01**

Date Drilled:

**03/04/2018**

Photographed By: **RAB**

Date Photographed:

**03/04/2018**



**Box 5. - Depth: 10.36m to 12.90m.**



**Box 6. - Depth: 12.90m to 14.07m.**

Client: **Ngati Whatua Orakei Whai Rawa Ltd**  
Project: **Eastcliffe Retirement Village**  
Location: **Outside 65 Te Arawa Street, Auckland**  
Project Reference: **255232**

Sheet 1 of 3

## BOREHOLE INFORMATION

Method: Rotary Core Wireline  
Equipment: Tracked Rig  
Contractor: Pro-Drill Ltd

**CO-ORDINATES: Mt Eden Circuit 2000**

Easting: 405415m  
Northing: 803159.1m  
Reduced level: 41m  
(Auckland MSL 1946 Datum)

Date started: 5/04/2018  
Date completed: 6/04/2018  
Inclination: -90°  
Azimuth: N/A

Logged by: AGM  
 Input by: AGM  
 Checked by: RAB  
 Verified by: MFS

ox 2

## REMARKS:

- 1) Hole depth specified in Water Level Readings is the bottom of the piezometric screen.
- 2) IBHSV = In Barrel Hand Shear Vane, SPT = Standard Penetration Test, SPTC = Solid Cone Standard Penetration Test.
- 3) Locations were estimated using Auckland Council GeoMaps and are in terms of Mount Eden 2000 Circuit with an approximate accuracy of +/- 5m.
- 4) Reduced level reading was obtained from an existing LIDAR dataset with an approximate accuracy of +/- 1.0m.
- 5) ECBF = East Coast Bays Formation.

## Water Level Readings:

Date	Time	Hole Depth	Water Level
(1)	09/04/18 07:50	6.00m	2.86 m bgl
(2)	23/04/18 11:48	6.00m	2.32 m bgl

**CO-ORDINATES: Mt Eden Circuit 2000**  
Easting: 405415m  
Northing: 803159.1m  
Reduced level: 41m  
(Auckland MSL 1946 Datum)

Logged by: AGM  
 Input by: AGM  
 Checked by: RAB  
 Verified by: MFS

#### Box 4

REMARKS:

- 1) Hole depth specified in Water Level Readings is the bottom of the piezometric screen.
- 2) IBHSV = In Barrel Hand Shear Vane, SPT = Standard Penetration Test, SPTC = Solid Cone Standard Penetration Test.
- 3) Locations were estimated using Auckland Council GeoMaps and are in terms of Mount Eden 2000 Circuit with an approximate accuracy of +/- 5m.
- 4) Reduced level reading was obtained from an existing LIDAR dataset with an approximate accuracy of +/- 1.0m.
- 5) ECBF = East Coast Bays Formation.

Water Level Readings:

Date	Time	Hole Depth	Water Level
(1)	09/04/18 07:50	6.00m	2.86 m bgl
(2)	23/04/18 11:48	6.00m	2.32 m bgl



Level 4, 139 Carlton Gore Road  
PO Box 9762, Newmarket  
Auckland, New Zealand  
Tel: +64 9 520 6019  
www.aurecongroup.com

Client: **Ngati Whatua Orakei Whai Rawa Ltd**  
Project: **Eastcliffe Retirement Village**  
Location: **Outside 65 Te Arawa Street, Auckland**  
Project Reference: **255232**

**BH02**

Sheet 3 of 3

<b>BOREHOLE INFORMATION</b> Method: Rotary Core Wireline Equipment: Tracked Rig Contractor: Pro-Drill Ltd	<b>CO-ORDINATES: Mt Eden Circuit 2000</b> Easting: 405415m Northing: 803159.1m Reduced level: 41m (Auckland MSL 1946 Datum)	Date started: 5/04/2018 Date completed: 6/04/2018 Inclination: -90° Azimuth: N/A	Logged by: AGM Input by: AGM Checked by: RAB Verified by: MFSL
--	---	---	---

Method	R.L. (m)	Length (m)	Graphic Log	Layer Code	Material Description	Weathering/USC	Testing	TCR (%)	SCR (%)	RQD (%)	Fracture Log	Stratigraphy Defect Description Additional Notes	Installation
Box 4 HQ3	31			EWs	8.3m: Moderately weathered, dull grey, SANDSTONE; extremely weak (dense). Interbedded siltstone beds up to 200mm thick.	MW		95	91	91		10.13m: JT -45° PlSm Cn	
					10.5m to 10.77m:...SILTSTONE.								
Box 5 HQ3	11			EWz	10.85m to 10.87m:...Thin black carbonaceous material. 10.9m: Moderately weathered, light grey, SILTSTONE; very weak. Interbedded with moderately thin sandstone beds with disseminated black carbonaceous material.	SW	11m: SPTC 48// 8 for 50mm N = 50+	N/A					
					11.84m to 11.89m:...SANDSTONE. Well cemented.								
	29												

End of borehole at 12.5m (Target Depth)

REMARKS:

- Hole depth specified in Water Level Readings is the bottom of the piezometric screen.
- IBHSV = In Barrel Hand Shear Vane, SPT = Standard Penetration Test, SPTC = Solid Cone Standard Penetration Test.
- Locations were estimated using Auckland Council GeoMaps and are in terms of Mount Eden 2000 Circuit with an approximate accuracy of +/- 5m.
- Reduced level reading was obtained from an existing LIDAR dataset with an approximate accuracy of +/- 1.0m.
- ECBF = East Coast Bays Formation.

Water Level Readings:

Date Time | Hole Depth | Water Level  
(1) 09/04/18 07:50 | 6.00m | 2.86 m bgl  
(2) 23/04/18 11:48 | 6.00m | 2.32 m bgl



## Eastcliffe Retirement Village Redevelopment Ground Investigation

Borehole Reference: BH02

Photographed By: RAB

Date Drilled:

Date Photographed:

**aurecon**

05/04/2018 – 06/04/2018

05/04/2018 – 06/04/2018



Box 1. - Depth: 0.00m to 2.47m.



Box 2. - Depth: 2.47m to 5.43m.



## Eastcliffe Retirement Village Redevelopment Ground Investigation

Borehole Reference: BH02

Date Drilled:

**aurecon**

05/04/2018 – 06/04/2018

Photographed By: RAB

Date Photographed:

05/04/2018 – 06/04/2018



Box 3. - Depth: 5.43m to 8.16m.



Box 4. - Depth: 8.16m to 11.00m.

## Eastcliffe Retirement Village Redevelopment Ground Investigation

**aurecon**

Borehole Reference: **BH02**

Date Drilled:

**05/04/2018 – 06/04/2018**

Photographed By: **RAB**

Date Photographed:

**05/04/2018 – 06/04/2018**



Box 5. - Depth: 11.0m to 12.50m.

Water Level Readings:		
Date Time	Hole Depth	Water Level
No water level recorded		



## BOREHOLE INFORMATION

Method: Rotary Core Wireline  
Equipment: Tracked Rig  
Contractor: Pro-Drill Ltd

**CO-ORDINATES: Mt Eden Circuit 2000**

Easting: 405443.4m  
Northing: 803186.7m  
Reduced level: 37m  
(Auckland MSL 1946 Datum)

Date started: 6/04/2018  
Date completed: 6/04/2018  
Inclination: -90°  
Azimuth: N/A

Logged by: RAB  
 Input by: RAB  
 Checked by: MFSL  
 Verified by: EMR

[illegible]

## REMARKS:

- 1) Hole depth specified in Water Level Readings is the bottom of the piezometric screen.
- 2) IBHSV = In Barrel Hand Shear Vane, SPT = Standard Penetration Test, SPTC = Solid Cone Standard Penetration Test.
- 3) Locations were estimated using Auckland Council GeoMaps and are in terms of Mount Eden 2000 Circuit with an approximate accuracy of +/- 5m.
- 4) Reduced level reading was obtained from an existing LIDAR dataset with an approximate accuracy of +/- 1.0m.
- 5) ECBF = East Coast Bays Formation.
- 6) No piezometer was installed for recording water levels.

## Water Level Readings:

Date Time	Hole Depth	Water Level
No water level recorded		

## Eastcliffe Retirement Village Redevelopment Ground Investigation

**aurecon**

Borehole Reference: **BH03**

Date Drilled:

**06/04/2018**

Photographed By: **RAB**

Date Photographed:

**06/04/2018**



Box 1. - Depth: 0.00m to 3.45m.



Box 2. - Depth: 3.45m to 5.90m.

## Eastcliffe Retirement Village Redevelopment Ground Investigation

**aurecon**

Borehole Reference: **BH03**

Date Drilled:

**06/04/2018**


Photographed By: **RAB**

Date Photographed:

**06/04/2018**



**Box 3. - Depth: 5.90m to 9.05m.**



**Box 4. - Depth: 9.05m to 9.62m.**



Water Level Readings:		
Date Time	Hole Depth	Water Level
No water level recorded		

<b>BOREHOLE INFORMATION</b>	<b>CO-ORDINATES: Mt Eden Circuit 2000</b>	Date started: 9/04/2018	Logged by: AGM
Method: Rotary Core Wireline	Easting: 405498.8m	Date completed: 9/04/2018	Input by: AGM
Equipment: Tracked Rig	Northing: 803167.7m	Inclination: -90°	Checked by: RAB
Contractor: Pro-Drill Ltd	Reduced level: 31m	Azimuth: N/A	Verified by: MFSL
	(Auckland MS1 1946 Datum)		

Box 1													Box 2													Box 3												
Method	R.L. (m)	Length (m)	Graphic Log	Layer Code	Material Description	Weathering/USC	Testing	TCR (%)	SCR (%)	RQD (%)	Fracture Log	Stratigraphy Defect Description Additional Notes	Installation																									
HQ3	26			EWx	4.89m: CORELOSS.		6.5m: SPTC 42// 10 for 0mm N = 50+	100	89	60	<div>WGS WS MWS CS VCS ECS</div>																											
			EWz	5.34m: Moderately weathered, grey, sandy SILTSTONE; extremely weak (very stiff).	MW																																	
	6			5.72m: Moderately weathered, grey, SILTSTONE; extremely weak (very stiff).  6m to 6.06m:...Moderately weathered, grey, SANDSTONE; very weak. Moderately cemented.	MW																																	
	25		EWs	6.2m: Moderately weathered, grey, SANDSTONE; very weak. Moderately cemented.	MW																																	
SPTC					6.57m: Moderately weathered, grey, SILTSTONE; very weak.		6.5m: SPTC 42// 10 for 0mm N = 50+	N/A																														
HQ3	7			EWz	7.67m to 7.71m:...Moderately weathered, grey, SANDSTONE; very weak. Moderately cemented.	MW	8m: SPTC 25// 25,15,10 for 30mm N = 50+	93	93	72	<div>WGS WS MWS CS VCS ECS</div>																											
	24																																					
	8																																					
SPTC	23							N/A																														
HQ3	9			EU/s	8.6m: Slightly weathered, light grey, SANDSTONE; weak.	SW	9.5m: SPTC 50// for 115mm N = 50+	97	97	86	<div>WGS WS MWS CS VCS ECS</div>	8.71m: JT -75° StSm Cn 8.73m: JT -80° UnRo Vn(CLAY)																										
			8.9m to 9.5m:...SILTSTONE.																																			
	22																																					
SPTC								N/A				9.5m: SPT test terminated in seating penetration. 9.615m to 10m: JT -90° UnRo Cg(IRON)																										
HQ3	10							90	90	81	<div>WGS WS MWS CS VCS ECS</div>																											

REMARKS:

- 1) Hole depth specified in Water Level Readings is the bottom of the piezometric screen.
- 2) IBHSV = In Barrel Hand Shear Vane, SPT = Standard Penetration Test, SPTC = Solid Cone Standard Penetration Test.
- 3) Locations were estimated using Auckland Council GeoMaps and are in terms of Mount Eden 2000 Circuit with an approximate accuracy of +/- 5m.
- 4) Reduced level reading was obtained from an existing LIDAR dataset with an approximate accuracy of +/- 1.0m.
- 5) ECBF = East Coast Bays Formation.
- 6) No piezometer was installed for recording water levels.

Water Level Readings:		
Date Time	Hole Depth	Water Level
No water level recorded		

<b>BOREHOLE INFORMATION</b> Method: Rotary Core Wireline Equipment: Tracked Rig Contractor: Pro-Drill Ltd	<b>CO-ORDINATES: Mt Eden Circuit 2000</b> Easting: 405498.8m Northing: 803167.7m Reduced level: 31m (Auckland MSL 1946 Datum)	Date started: 9/04/2018 Date completed: 9/04/2018 Inclination: -90° Azimuth: N/A	Logged by: AGM Input by: AGM Checked by: RAB Verified by: MFSL
--	---	---	---

Method	R.L. (m)	Length (m)	Graphic Log	Layer Code	Material Description	Weathering/USC	Testing	TCR (%)	SCR (%)	RQD (%)	Fracture Log	Stratigraphy Defect Description Additional Notes	Installation
HQ3	21			EUs	8.6m: Slightly weathered, light grey, SANDSTONE; weak.	SW		90	90	81		10m: JT -85° UnRo Cg(IRON)	
	11				10.91m to 11m:...SILTSTONE.							10.65m: JT -60° PISm Cn	

End of borehole at 11m (Target Depth)

REMARKS:  
1) Hole depth specified in Water Level Readings is the bottom of the piezometric screen.  
2) IBHSV = In Barrel Hand Shear Vane, SPT = Standard Penetration Test, SPTC = Solid Cone Standard Penetration Test.  
3) Locations were estimated using Auckland Council GeoMaps and are in terms of Mount Eden 2000 Circuit with an approximate accuracy of +/- 5m.  
4) Reduced level reading was obtained from an existing LIDAR dataset with an approximate accuracy of +/- 1.0m.  
5) ECBF = East Coast Bays Formation.  
6) No piezometer was installed for recording water levels.

**Water Level Readings:**  
Date Time | Hole Depth | Water Level  
No water level recorded



# Eastcliffe Retirement Village Redevelopment Ground Investigation

**aurecon**

Borehole Reference: **BH04**

Date Drilled:

**09/04/2018**

Photographed By: **RAB**

Date Photographed:

**09/04/2018**



Box 1. - Depth: 0.00m to 5.52m.



Box 2. - Depth: 5.52m to 8.33m.

## Eastcliffe Retirement Village Redevelopment Ground Investigation

**aurecon**

Borehole Reference: **BH04**

Date Drilled:

**09/04/2018**

Photographed By: **RAB**

Date Photographed:

**09/04/2018**



Box 3. - Depth: 8.33m to 11.00m.

Water Level Readings:			
Date	Time	Hole Depth	Water Level
(1)	06/04/18	07:48	6.00m   1.28 m bgl
(2)	09/04/18	08:02	6.00m   2.24 m bgl
(3)	23/04/18	12:18	6.00m   2.15 m bgl



<b>BOREHOLE INFORMATION</b>	<b>CO-ORDINATES: Mt Eden Circuit 2000</b>	Date started: 5/04/2018	Logged by: RAB
Method: Rotary Core Wireline	Easting: 405521.7m	Date completed: 5/04/2018	Input by: RAB
Equipment: Tracked Rig	Northing: 803228.1m	Inclination: -90°	Checked by: MFSL
Contractor: Pro-Drill Ltd	Reduced level: 33m (Auckland MSL 1946 Datum)	Azimuth: N/A	Verified by: EMR

Method	R.L. (m)	Length (m)	Graphic Log	Layer Code	Material Description	Weathering/USC	Testing	TCR (%)	SCR (%)	RQD (%)	Fracture Log	Stratigraphy Defect Description Additional Notes	Installation
Box 2	OB	27	XXXXXX	EWz	5.05m: Highly weathered, grey, SILTSTONE; extremely weak (very stiff).	HW	6m: SPT 5// 3,4,4,4 N = 15	86	86	73	VWS WS NWS CS VCS ECS		
					6.45m: Moderately weathered, grey, SILTSTONE; very weak.	MW		85	85	85			
Box 3	OB	26	XXXXXX	EUz	7.1m: Slightly weathered, grey, SILTSTONE; very weak.	SW	7.5m: SPT 14// 8,10,12,12 N = 42	100	100	100			
					7.95m: CORELOSS.								
Box 4	HQ3	24	XXXXXX	EUz	8.45m: Slightly weathered, grey, SANDSTONE; very weak. Moderately cemented.	SW	9.5m: SPTC 15// 10,10,12,10 N = 42	68	66	49		9.17m: JT 70° PlSm Cn	
					8.76m to 9.4m:...Weak.								
	SPTC	23	XXXXXX			SW		N/A					
		10	XXXXXX					97	60	14			

## REMARKS:

- 1) Hole depth specified in Water Level Readings is the bottom of the piezometric screen.
- 2) IBHSV = In Barrel Hand Shear Vane, SPT = Standard Penetration Test, SPTC = Solid Cone Standard Penetration Test.
- 3) Locations were estimated using Auckland Council GeoMaps and are in terms of Mount Eden 2000 Circuit with an approximate accuracy of +/- 5m.
- 4) Reduced level reading was obtained from an existing LIDAR dataset with an approximate accuracy of +/- 1.0m.
- 5) ECBF = East Coast Bays Formation.

**Water Level Readings:**

Date	Time	Hole Depth	Water Level
(1)	06/04/18 07:48	6.00m	1.28 m bgl
(2)	09/04/18 08:02	6.00m	2.24 m bgl
(3)	23/04/18 12:18	6.00m	2.15 m bgl

## BOREHOLE INFORMATION

Method: Rotary Core Wireline  
Equipment: Tracked Rig  
Contractor: Pro-Drill Ltd

**CO-ORDINATES: Mt Eden Circuit 2000**

Easting: 405521.7m  
Northing: 803228.1m  
Reduced level: 33m  
(Auckland MSL 1946 Datum)

Date started: 5/04/2018  
Date completed: 5/04/2018  
Inclination: -90°  
Azimuth: N/A

Logged by: RAB  
 Input by: RAB  
 Checked by: MFSL  
 Verified by: EMR

[illegible]

End of borehole at 11.325m (Target Depth)

## REMARKS:

- 1) Hole depth specified in Water Level Readings is the bottom of the piezometric screen.
- 2) IBHSV = In Barrel Hand Shear Vane, SPT = Standard Penetration Test, SPTC = Solid Cone Standard Penetration Test.
- 3) Locations were estimated using Auckland Council GeoMaps and are in terms of Mount Eden 2000 Circuit with an approximate accuracy of +/- 5m.
- 4) Reduced level reading was obtained from an existing LIDAR dataset with an approximate accuracy of +/- 1.0m.
- 5) ECBF = East Coast Bays Formation.

Water Level Readings:
-----------------------

Date	Time	Hole Depth	Water Level
(1)	06/04/18 07:48	6.00m	1.28 m bgl
(2)	09/04/18 08:02	6.00m	2.24 m bgl
(3)	23/04/18 12:18	6.00m	2.15 m bgl



# Eastcliffe Retirement Village Redevelopment Ground Investigation

**aurecon**

Borehole Reference: **BH05**

Date Drilled:

**05/04/2018**

Photographed By: **RAB**

Date Photographed:

**05/04/2018**



Box 1. - Depth: 0.00m to 2.48m.



Box 2. - Depth: 2.48m to 5.52m.



## Eastcliffe Retirement Village Redevelopment Ground Investigation

**aurecon**

Borehole Reference: **BH05**

Date Drilled:

**05/04/2018**

Photographed By: **RAB**

Date Photographed:

**05/04/2018**



Box 3. - Depth: 5.52m to 8.76m.



Box 4. - Depth: 8.76m to 11.33m.





Level 4, 139 Carlton Gore Road  
PO Box 9762, Newmarket  
Auckland, New Zealand  
Tel: +64 9 520 6019  
www.aurecongroup.com

Client: **Ngati Whatua Orakei Whai Rawa Ltd**  
Project: **Eastcliffe Retirement Village**  
Location: **138 Rukutai Street, Auckland**  
Project Reference: **255232**

**BH06**

Sheet 1 of 3

<b>BOREHOLE INFORMATION</b> Method: Rotary Core Wireline Equipment: Tracked Rig Contractor: Pro-Drill Ltd		<b>CO-ORDINATES: Mt Eden Circuit 2000</b> Easting: 405588.6m Northing: 803179.3m Reduced level: 26m (Auckland MSL 1946 Datum)		Date started: 4/04/2018 Date completed: 4/04/2018 Inclination: -90° Azimuth: N/A		Logged by: RAB Input by: RAB Checked by: MFSL Verified by: EMR	
--	--	---	--	---	--	---	--

Method	R.L. (m)	Length (m)	Graphic Log	Layer Code	Material Description	Weathering/USC	Testing	TCR (%)	SCR (%)	RQD (%)	Fracture Log	Stratigraphy Defect Description Additional Notes	Installation
HA	25	1		T	0m: Clayey SILT with some rootlets; dark brown. Firm; moist; low plasticity. [TOPSOIL]	CL-ML		100			<div>WVS</div> <div>WS</div> <div>MWS</div> <div>CS</div> <div>VCS</div> <div>EC3</div>	0m: TOPSOIL	
				Fc	0.3m: Silty CLAY with trace rootlets; dark brown. Firm; moist; medium plasticity. [FILL]	CL-ML						0.3m: FILL	
SPT	24	2		ERc	0.65m: CLAY; brownish yellow. Firm; moist; high plasticity. [RESIDUAL ECBF]	CL	1.5m: SPT 2// 2,2,2,3 N = 9	0				0.65m: EAST COAST BAYS FORMATION	
				ERx	1.5m: CORELOSS.								
OB	23	3		ERc	2.41m: Silty CLAY; yellowish orange and light grey streaks. Stiff; moist; high plasticity.	CL-ML	3m: SPT 2// 1,1,2,2 N = 6 3m: IBHSV 73/34 kPa	56					
				ERz	2.88m: Clayey SILT; light grey mottled brownish orange. Stiff; moist; medium plasticity.	CL-ML							
OB	22	4		ERc	3.72m: CLAY; brownish orange mottled light grey. Stiff; moist; high plasticity.	CL		90					
					4.31m: CLAY; yellowish brown. Stiff; moist; high plasticity.	CL							
SPT	21	5		ERz	4.5m: SILT; grey. Stiff; moist; low plasticity. [Completely Weathered ECBF]	CW	4.5m: SPT 4// 2,2,3,3 N = 10 4.5m: IBHSV 46/15 kPa	100	100	29			
								100	100	100			

REMARKS:  
1) Hole depth specified in Water Level Readings is the bottom of the piezometric screen.  
2) IBHSV = In Barrel Hand Shear Vane, SPT = Standard Penetration Test, SPTC = Solid Cone Standard Penetration Test.  
3) Locations were estimated using Auckland Council GeoMaps and are in terms of Mount Eden 2000 Circuit with an approximate accuracy of +/- 5m.  
4) Reduced level reading was obtained from an existing LIDAR dataset with an approximate accuracy of +/- 1.0m.  
5) ECBF = East Coast Bays Formation.

**Water Level Readings:**  
Date Time | Hole Depth | Water Level  
(1) 06/04/18 07:42 | 6.00m | 3.73 m bgl  
(2) 09/04/18 07:55 | 6.00m | 4.41 m bgl  
(3) 23/04/18 12:11 | 6.00m | 4.78 m bgl

Water Level Readings:			
Date	Time	Hole Depth	Water Level
(1)	06/04/18	07:42	6.00m   3.73 m bgl
(2)	09/04/18	07:55	6.00m   4.41 m bgl
(3)	23/04/18	12:11	6.00m   4.78 m bgl



End of borehole at 11.125m (Target Depth)

Date	Time	Hole Depth	Water Level
(1)	06/04/18 07:42	6.00m	3.73 m bgl
(2)	09/04/18 07:55	6.00m	4.41 m bgl
(3)	23/04/18 12:11	6.00m	4.78 m bgl

## Eastcliffe Retirement Village Redevelopment Ground Investigation

**aurecon**

Borehole Reference: **BH06**

Date Drilled:

**04/04/2018**

Photographed By: **RAB**

Date Photographed:

**04/04/2018**



Box 1. - Depth: 0.00m to 3.00m.



Box 2. - Depth: 3.00m to 5.7m.



# Eastcliffe Retirement Village Redevelopment Ground Investigation

**aurecon**

Borehole Reference: **BH06**

Date Drilled:

**04/04/2018**

Photographed By: **RAB**

Date Photographed:

**04/04/2018**



Box 3. - Depth: 5.7m to 8.27m.



Box 4. - Depth: 8.27m to 11.13m.



<b>BOREHOLE INFORMATION</b>		<b>CO-ORDINATES: Mt Eden Circuit 2000</b>		Date started:	21/02/2019	Logged by:	AD
Method: Rotary Core Wireline		Easting: 405509m		Date completed:	22/02/2019	Input by:	AD
Equipment: Excavator Mounted Rig		Northing: 803225m		Inclination:	90°	Checked by:	JME
Contractor: Pro-Dill Ltd		Reduced level: 33.3m		Azimuth:	N/A	Verified by:	BL
		(Auckland MSL 1946 Datum)					

Method	R.L. (m)	Length (m)	Graphic Log	Layer Code	Material Description	Weathering/USC	Testing	TCR (%)	SCR (%)	RQD (%)	Stratigraphy Defect Description Additional Notes	Installation
OB	33			T	0m: SILT with some sand and medium gravel and trace rootlets; brown. Firm, dry, low plasticity. [TOPSOIL]	ML		100			0m: TOPSOIL	
					0.1m: CLAY; brownish yellow mottled grey. Very stiff, dry, high plasticity. [RESIDUAL ECBF]						0.1m: EAST COAST BAYS FORMATION	
					0.5m to 1.1m: ...moist	CH						
					1.1m: Silty CLAY; brownish yellow mottled grey. Soft, moist, high plasticity.	CH						
					2m: Sandy CLAY with some silt; brownish yellow mottled grey. Firm, moist, low plasticity. Sand, fine to medium grained.	CL						
OB	1			ERc			1.5m: SPT 0// 0,1,0,1 N = 2	100				
SPT		2						100				
OB	31			ERz				100				
					2.5m: Clayey SILT; brownish yellow mottled grey. Firm, moist, low plasticity.	ML						
					2.8m: Completely weathered, grey, SILTSTONE. Extremely weak (very stiff) [Completely weathered ECBF].		3m: SPT 2// 1,2,3,4 N = 10	100				
SPT	30			ERc								
OB	4							86	77	55		
					4.1m to 4.2m: ...stained with black carbonaceous material							
					4.2m: Highly weathered, grey, SILTSTONE. Very weak.							
HQ3	29			EWz				100	100	100		
	5											

REMARKS:  
1) OB = Open Barrel drilling.  
2) Borehole locations and reduced levels were surveyed and provided Woods.

Water Level Readings:  
Date Time | Hole Depth | Water Level  
No water level recorded

**BOREHOLE INFORMATION**  
Method: Rotary Core Wireline  
Equipment: Excavator Mounted Rig  
Contractor: Pro-Dill Ltd

**CO-ORDINATES: Mt Eden Circuit 2000**  
Easting: 405509m  
Northing: 803225m  
Reduced level: 33.3m  
(Auckland MSL 1946 Datum)

Date started: 21/02/2019  
Date completed: 22/02/2019  
Inclination: 90°  
Azimuth: N/A

Logged by: AD  
Input by: AD  
Checked by: JME  
Verified by: BL

Method	R.L. (m)	Length (m)	Graphic Log	Layer Code	Material Description	Weathering/USC	Testing	TCR (%)	SCR (%)	RQD (%)	Stratigraphy Defect Description Additional Notes	Installation
SPTC	28			EWs	5m: Highly weathered, grey, SANDSTONE. Very weak.	HW	5m: SPTC 11// 7,8,8,9 N = 32	N/A				
HQ3	6			EWz	5.3m: Highly weathered, grey, SILTSTONE. Very weak.	HW		100	100	65		
SPTC	7				7m to 7.1m: ...black carbonaceous material		6.5m: SPTC 8// 6,6,7,8 N = 27	N/A			6.95m: Corebound	
HQ3	26							100	100	80		
HQ3	8			EWs	7.5m: Moderately weathered, grey, SANDSTONE. Very weak.	MW	8m: SPTC 18// 17,20,13 for 40mm N = 50+	100	100	58		
SPTC	25							N/A				
HQ3	9			EUs	8.5m: Slightly weathered, grey, SANDSTONE. Very weak.	SW		100	100	90		
SPTC	24						9.5m: SPTC 8// 3,3,4,5 N = 15	N/A				
	10							100	100	81		

**REMARKS:**  
1) OB = Open Barrel drilling.  
2) Borehole locations and reduced levels were surveyed and provided Woods.

**Water Level Readings:**  
Date Time | Hole Depth | Water Level  
No water level recorded

Client: **Ngati Whatua Orakei Whai Rawa Ltd**  
Project: **Eastcliffe Retirement Village**  
Location: **Phase 1 - Block A**  
Project Reference: **255232**

# BH41

Sheet 3 of 4

### BOREHOLE INFORMATION

Method: Rotary Core Wireline  
Equipment: Excavator Mounted Rig  
Contractor: Pro-Dill Ltd

**CO-ORDINATES: Mt Eden Circuit 2000**

Easting: 405509m  
 Northing: 803225m  
 Reduced level: 33.3m  
 (Auckland MSL 1946 Datum)

Date started: 21/02/2019

Date started: 21/02/2019  
Date completed: 22/02/2019  
Inclination: 90°  
Azimuth: N/A

Logged by: AD

Logged by: AD  
 Input by: AD  
 Checked by: JME  
 Verified by: BL

[illegible]

REMARKS:

- REMARKS:  
1) OB = Open Barrel drilling.  
2) Borehole locations and reduced levels were surveyed and provided Woods.

Water Level Readings:
-----------------------

Date	Time	Hole Depth	Water Level
No water level recorded			





Level 4, 139 Carlton Gore Road  
PO Box 9762, Newmarket  
Auckland, New Zealand  
Tel: +64 9 520 6019  
www.aurecongroup.com

Client: **Ngati Whatua Orakei Whai Rawa Ltd**  
Project: **Eastcliffe Retirement Village**  
Location: **Phase 1 - Block A**  
Project Reference: **255232**

**BH41**

Sheet 4 of 4

<b>BOREHOLE INFORMATION</b> Method: Rotary Core Wireline Equipment: Excavator Mounted Rig Contractor: Pro-Dill Ltd	<b>CO-ORDINATES: Mt Eden Circuit 2000</b> Easting: 405509m Northing: 803225m Reduced level: 33.3m (Auckland MSL 1946 Datum)	Date started: 21/02/2019 Date completed: 22/02/2019 Inclination: 90° Azimuth: N/A	Logged by: AD Input by: AD Checked by: JME Verified by: BL
---	---	--	---

Method	R.L. (m)	Length (m)	Graphic Log	Layer Code	Material Description	Weathering/USC	Testing	TCR (%)	SCR (%)	RQD (%)	Stratigraphy Defect Description Additional Notes	Installation
HQ3	18		XXXXXXXXXXXXXXXXXXXX	EUz	13.2m: Slightly weathered, grey, SILTSTONE. Weak.	SW	15.5m: SPTC 50// for 100mm N = 50+	100	90	45		
SPTC			XXXXXXXXXXXXXXXXXXXX					N/A				
			XXXXXXXXXXXXXXXXXXXX									
			XXXXXXXXXXXXXXXXXXXX									
HQ3	17		XXXXXXXXXXXXXXXXXXXX	EUz	16.8m: Slight weathered, grey, SANDSTONE, weak.	SW	17m: SPTC 50// for 70mm N = 50+	100	98	48		
SPTC			XXXXXXXXXXXXXXXXXXXX					N/A				
			XXXXXXXXXXXXXXXXXXXX									
			XXXXXXXXXXXXXXXXXXXX									
			XXXXXXXXXXXXXXXXXXXX									
			XXXXXXXXXXXXXXXXXXXX									
			XXXXXXXXXXXXXXXXXXXX									
			XXXXXXXXXXXXXXXXXXXX									
HQ3	16		XXXXXXXXXXXXXXXXXXXX	EUz	17.5m to 17.7m:....black carbonaceous material	SW	18.5m: SPTC 50// for 130mm N = 50+	100	100	77		
SPTC			XXXXXXXXXXXXXXXXXXXX					N/A				
			XXXXXXXXXXXXXXXXXXXX									
			XXXXXXXXXXXXXXXXXXXX									
			XXXXXXXXXXXXXXXXXXXX									
			XXXXXXXXXXXXXXXXXXXX									
			XXXXXXXXXXXXXXXXXXXX									
			XXXXXXXXXXXXXXXXXXXX									
HQ3	15		XXXXXXXXXXXXXXXXXXXX	EUz		SW		100	100	52		
SPTC			XXXXXXXXXXXXXXXXXXXX					N/A				
			XXXXXXXXXXXXXXXXXXXX									
			XXXXXXXXXXXXXXXXXXXX									
			XXXXXXXXXXXXXXXXXXXX									
			XXXXXXXXXXXXXXXXXXXX									
			XXXXXXXXXXXXXXXXXXXX									
			XXXXXXXXXXXXXXXXXXXX									
HQ3	14		XXXXXXXXXXXXXXXXXXXX	EUz		SW		100	100	52		
SPTC			XXXXXXXXXXXXXXXXXXXX					N/A				
			XXXXXXXXXXXXXXXXXXXX									

**Eastcliffe Phase 1  
Ground Investigation**

**aurecon**

Borehole Reference: **BH41**  
Photographed By: **AD**

Date Drilled:  
Date Photographed:

**21/02/2019 – 22/02/2019**  
**21/02/2019 – 22/02/2019**



**Box 1. - Depth: 0 m to 1.5 m.**



**Box 2. - Depth: 1.5 m to 4 m.**


Eastcliffe Phase 1  
Ground Investigation

**aurecon**

Borehole Reference: **BH41**  
Photographed By: **AD**

Date Drilled:  
Date Photographed:

21/02/2019 – 22/02/2019  
21/02/2019 – 22/02/2019



Box 3. - Depth: 4. m to 8 m.



Box 4. - Depth: 8 m to 12 m.



Eastcliffe Phase 1  
Ground Investigation

**aurecon**

Borehole Reference: BH41  
Photographed By: AD

Date Drilled:  
Date Photographed:

21/02/2019 – 22/02/2019  
21/02/2019 – 22/02/2019



Box 5. - Depth: 12 m to 15.5 m.



Box 6. - Depth: 15.5 m to 18.5 m.

**Eastcliffe Phase 1  
Ground Investigation**

**aurecon**

Borehole Reference: **BH41**

Date Drilled:

**21/02/2019 – 22/02/2019**

Photographed By: **AD**

Date Photographed:

**21/02/2019 – 22/02/2019**



**Box 7. - Depth: 18.5 m to 20 m.**

<b>BOREHOLE INFORMATION</b> Method: Rotary Core Wireline Equipment: Excavator Mounted Rig Contractor: Pro-Drill Ltd	<b>CO-ORDINATES: Mt Eden Circuit 2000</b> Easting: 405514m Northing: 803210m Reduced level: 33.0m (Auckland MSL 1946 Datum)	Date started: 22/02/2019 Date completed: 25/02/2019 Inclination: 90° Azimuth: N/A	Logged by: AD Input by: AD Checked by: JME Verified by: BL
--	---	--	---

Method	R.L. (m)	Length (m)	Graphic Log	Layer Code	Material Description	Weathering/USC	Testing	TCR (%)	SCR (%)	RQD (%)	Fracture Log	Stratigraphy Defect Description Additional Notes	Installation
OB	33				0m: Coarse GRAVEL; dark grey. Very loose, dry. [FILL]	GP		100				0m: FILL	
OB				Fg	0.3m: Coarse GRAVEL with some sand and silt; dark grey and brown. Very loose, dry.	GP		100					
OB	32	1			0.8m: CLAY; brownish yellow mottled grey. Firm, moist, high plasticity. [RESIDUAL ECBF]		1m: IBHSV 82/45 kPa	100				0.8m: EAST COAST BAYS FORMATION	
SPT						CH	1.5m: SPT 1// 0,1,0,1 N = 2 1.5m: IBHSV 75/42 kPa	100					
OB	31	2		ERc				100					
SPT	30	3			2.7m: Silty CLAY with some fine sand; grey. Firm, moist, high plasticity.	CH	3m: SPT 1// 0,1,1,1 N = 3 3m: IBHSV 60/12 kPa	100					
OB					3.5m: Silty CLAY, trace organics; grey. Very stiff, moist, high plasticity.	CH							
SPT	29	4		EWs	4m: Highly weathered, grey, fine to medium SANDSTONE. Extremely weak (very stiff) [Highly weathered ECBF].	HW	4.5m: SPT 5// 4,6,9,10 N = 29	0					
	5							100	100	80			

**REMARKS:**  
1) Hole depth specified in Water Level Readings is the bottom of the piezometric screen. Readings taken post-drilling.  
2) OB = Open Barrel drilling.  
3) Borehole locations and reduced levels were surveyed and provided by Woods.

**Water Level Readings:**  
**Date Time | Hole Depth | Water Level**  
(1) 28/02/19 17:11 | 9.00m | 5.39 m bgl  
(2) 01/03/19 10:00 | 9.00m | 5.48 m bgl  
(3) 04/03/19 16:27 | 9.00m | 5.4 m bgl  
(4) 06/03/19 14:51 | 9.00m | 5.39 m bgl  
(5) 12/03/19 10:08 | 9.00m | 5.42 m bgl  
(6) 13/03/19 12:08 | 9.00m | 5.43 m bgl  
(7) 15/03/19 12:30 | 9.00m | 5.48 m bgl



**BOREHOLE INFORMATION**  
Method: Rotary Core Wireline  
Equipment: Excavator Mounted Rig  
Contractor: Pro-Drill Ltd

**CO-ORDINATES: Mt Eden Circuit 2000**  
Easting: 405514m  
Northing: 803210m  
Reduced level: 33.0m  
(Auckland MSL 1946 Datum)

Date started: 22/02/2019  
Date completed: 25/02/2019  
Inclination: 90°  
Azimuth: N/A

Logged by: AD  
Input by: AD  
Checked by: JME  
Verified by: BL

Method	R.L. (m)	Length (m)	Graphic Log	Layer Code	Material Description	Weathering/USC	Testing	TCR (%)	SCR (%)	RQD (%)	Stratigraphy Defect Description Additional Notes	Installation
HQ3	28				<b>4m:</b> Highly weathered, grey, fine to medium SANDSTONE. Extremely weak (very stiff) [Highly weathered ECBF].	HW		100	100	80		
HQ3	27	6			<b>5.6m:</b> Moderately weathered, grey, fine to medium SANDSTONE. Extremely weak (hard).			100	100	80		
SPTC							6.5m: SPTC 9// 12,10,11,13 N = 46	N/A				
HQ3	26	7						97	100	65		
SPTC	25	8			<b>8m:</b> Slightly weathered, grey, fine to medium SANDSTONE. Weak.		8m: SPTC 20// 18,32 for 75mm N = 50+	N/A				
HQ3	24	9						100	100	58		
SPTC							9.5m: SPTC 20// 24,26 for 60mm N = 50+	N/A				
HQ3	10				<b>9.8m:</b> CORELOSS			84	100	70		

**REMARKS:**  
1) Hole depth specified in Water Level Readings is the bottom of the piezometric screen. Readings taken post-drilling.  
2) OB = Open Barrel drilling.  
3) Borehole locations and reduced levels were surveyed and provided by Woods.

**Water Level Readings:**  
Date Time | Hole Depth | Water Level  
(1) 28/02/19 17:11 | 9.00m | 5.39 m bgl  
(2) 01/03/19 10:00 | 9.00m | 5.48 m bgl  
(3) 04/03/19 16:27 | 9.00m | 5.4 m bgl  
(4) 06/03/19 14:51 | 9.00m | 5.39 m bgl  
(5) 12/03/19 10:08 | 9.00m | 5.42 m bgl  
(6) 13/03/19 12:08 | 9.00m | 5.43 m bgl  
(7) 15/03/19 12:30 | 9.00m | 5.48 m bgl

<b>BOREHOLE INFORMATION</b> Method: Rotary Core Wireline Equipment: Excavator Mounted Rig Contractor: Pro-Drill Ltd	<b>CO-ORDINATES: Mt Eden Circuit 2000</b> Easting: 405514m Northing: 803210m Reduced level: 33.0m (Auckland MSL 1946 Datum)	Date started: 22/02/2019 Date completed: 25/02/2019 Inclination: 90° Azimuth: N/A	Logged by: AD Input by: AD Checked by: JME Verified by: BL
--	---	--	---

Method	R.L. (m)	Length (m)	Graphic Log	Layer Code	Material Description	Weathering/USC	Testing	TCR (%)	SCR (%)	RQD (%)	Stratigraphy Defect Description Additional Notes	Installation
HQ3	23			EUu	10m: Slightly weathered, grey, fine to medium SANDSTONE. Weak.	SW		84	100	70		
SPTC	22	11					11m: SPTC 19// 13,11,16,10 for 25mm N = 50+	N/A				
HQ3				EUx	11.4m: CORELOSS			0			11.4m: Corebound	
HQ3	21	12			11.9m: Slightly weathered, grey, SILTSTONE. Very weak.			100	100	75		
SPTC							12.5m: SPTC 29// 50 for 45mm N = 50+	N/A				
HQ3	20	13		EUz		SW		100	100	55		
SPTC	19	14					14m: SPTC 50// for 140mm N = 50+	N/A				
HQ3					14.6m to 15.2m: ...weak			100	100	41		
	15											

REMARKS:  
1) Hole depth specified in Water Level Readings is the bottom of the piezometric screen. Readings taken post-drilling.  
2) OB = Open Barrel drilling.  
3) Borehole locations and reduced levels were surveyed and provided by Woods.

**Water Level Readings:**

Date Time	Hole Depth	Water Level
(1) 28/02/19 17:11	9.00m	5.39 m bgl
(2) 01/03/19 10:00	9.00m	5.48 m bgl
(3) 04/03/19 16:27	9.00m	5.4 m bgl
(4) 06/03/19 14:51	9.00m	5.39 m bgl
(5) 12/03/19 10:08	9.00m	5.42 m bgl
(6) 13/03/19 12:08	9.00m	5.43 m bgl
(7) 15/03/19 12:30	9.00m	5.48 m bgl

<b>BOREHOLE INFORMATION</b> Method: Rotary Core Wireline Equipment: Excavator Mounted Rig Contractor: Pro-Drill Ltd	<b>CO-ORDINATES: Mt Eden Circuit 2000</b> Easting: 405514m Northing: 803210m Reduced level: 33.0m (Auckland MSL 1946 Datum)	Date started: 22/02/2019 Date completed: 25/02/2019 Inclination: 90° Azimuth: N/A	Logged by: AD Input by: AD Checked by: JME Verified by: BL
--	---	--	---

Method	R.L. (m)	Length (m)	Graphic Log	Layer Code	Material Description	Weathering/USC	Testing	TCR (%)	SCR (%)	RQD (%)	Stratigraphy Defect Description Additional Notes	Installation
HQ3 SPTC	18		x x x x	EUz	11.9m: Slightly weathered, grey, SILTSTONE. Very weak.	SW						
			x x x x		15.2m: Slightly weathered, grey, SILTSTONE. Weak.		15.5m: SPTC 50// for 100mm N = 50+	100	100	41		
			x x x x				N/A					
			x x x x									
HQ3 SPTC	17	16	x x x x	EUz		SW		100	100	63		
			x x x x									
			x x x x									
			x x x x									
HQ3 SPTC	16	17	x x x x	EUz			17m: SPTC 50// for 90mm N = 50+	N/A				
			x x x x									
			x x x x									
			x x x x									
HQ3 SPTC	15	18	x x x x	EUz	17.6m: Slightly weathered, grey, fine to medium SANDSTONE. Weak.	SW		100	98	66		
			x x x x									
			x x x x									
			x x x x									
HQ3	14	19	x x x x	EUz	18.9m: Slightly weathered, grey, SILTSTONE. Weak.	SW						
			x x x x									
			x x x x									
			x x x x									
	20		x x x x									

REMARKS:  
1) Hole depth specified in Water Level Readings is the bottom of the piezometric screen. Readings taken post-drilling.  
2) OB = Open Barrel drilling.  
3) Borehole locations and reduced levels were surveyed and provided by Woods.

**Water Level Readings:**

Date Time	Hole Depth	Water Level
(1) 28/02/19 17:11	9.00m	5.39 m bgl
(2) 01/03/19 10:00	9.00m	5.48 m bgl
(3) 04/03/19 16:27	9.00m	5.4 m bgl
(4) 06/03/19 14:51	9.00m	5.39 m bgl
(5) 12/03/19 10:08	9.00m	5.42 m bgl
(6) 13/03/19 12:08	9.00m	5.43 m bgl
(7) 15/03/19 12:30	9.00m	5.48 m bgl





Level 4, 139 Carlton Gore Road  
PO Box 9762, Newmarket  
Auckland, New Zealand  
Tel: +64 9 520 6019  
www.aurecongroup.com

Client: **Ngati Whatua Orakei Whai Rawa Ltd**  
Project: **Eastcliffe Retirement Village**  
Location: **Phase 1 - Block A**  
Project Reference: **255232**

**BH42**

Sheet **5** of **5**

<b>BOREHOLE INFORMATION</b> Method: Rotary Core Wireline Equipment: Excavator Mounted Rig Contractor: Pro-Drill Ltd	<b>CO-ORDINATES: Mt Eden Circuit 2000</b> Easting: 405514m Northing: 803210m Reduced level: 33.0m (Auckland MSL 1946 Datum)	Date started: 22/02/2019 Date completed: 25/02/2019 Inclination: 90° Azimuth: N/A	Logged by: AD Input by: AD Checked by: JME Verified by: BL
--	---	--	---

Method	R.L. (m)	Length (m)	Graphic Log	Layer Code	Material Description	Weathering/USC	Testing	TCR (%)	SCR (%)	RQD (%)	Stratigraphy Defect Description Additional Notes	Installation
SPTC	13				20m: Slightly weathered, grey, fine to medium SANDSTONE. Weak.	SW	20m: SPTC 50// for 95mm N = 50+	N/A				
HQ3				EUs				100	99	88		
SPTC	12	21			21.6m: CORELOSS		21.5m: SPTC 50// for 90mm N = 50+	N/A				
HQ3					21.8m: Slightly weathered, grey, SILTSTONE. Weak.			85	98	100		
SPTC	11	22										
HQ3												
SPTC	10	23					23m: SPTC 50// for 110mm N = 50+	N/A				
HQ3				EUs				100	100	100		
SPTC	9	24										
HQ3												
SPTC					End of borehole at 24.62m (Target Depth)		24.5m: SPTC 50// for 45mm N = 50+	N/A				

REMARKS:  
1) Hole depth specified in Water Level Readings is the bottom of the piezometric screen. Readings taken post-drilling.  
2) OB = Open Barrel drilling.  
3) Borehole locations and reduced levels were surveyed and provided by Woods.

Water Level Readings:		
Date Time	Hole Depth	Water Level
(1) 28/02/19 17:11	9.00m	5.39 m bgl
(2) 01/03/19 10:00	9.00m	5.48 m bgl
(3) 04/03/19 16:27	9.00m	5.4 m bgl
(4) 06/03/19 14:51	9.00m	5.39 m bgl
(5) 12/03/19 10:08	9.00m	5.42 m bgl
(6) 13/03/19 10:08	9.00m	5.43 m bgl
(7) 15/03/19 12:30	9.00m	5.48 m bgl

Eastcliffe Phase 1  
Ground Investigation

**aurecon**

Borehole Reference: **BH42**

Date Drilled:

22/02/2019 – 25/02/2019


Photographed By: **AD**

Date Photographed:

22/02/2019 – 26/02/2019



Box 1. - Depth: 0 m to 2 m.



Box 2. - Depth: 2 m to 4.5 m.



Eastcliffe Phase 1  
Ground Investigation

**aurecon**

Borehole Reference: **BH42**  
Photographed By: **AD**

Date Drilled:  
Date Photographed:

22/02/2019 – 25/02/2019  
22/02/2019 – 26/02/2019



Box 3. - Depth: 4.5 m to 8 m.



Box 4. - Depth: 8 m to 11.5 m.



Eastcliffe Phase 1  
Ground Investigation

**aurecon**

Borehole Reference: BH42

Date Drilled:

22/02/2019 – 25/02/2019


Photographed By: AD

Date Photographed:

22/02/2019 – 26/02/2019



Box 5. - Depth: 11.5 m to 15.5 m.



Box 6. - Depth: 15.5 m to 18.5 m.

Eastcliffe Phase 1  
Ground Investigation

**aurecon**

Borehole Reference: **BH42**


Date Drilled:

22/02/2019 – 25/02/2019

Photographed By: **AD**

Date Photographed:

22/02/2019 – 26/02/2019



Box 7. - Depth: 18.5 m to 22m.



Box 8. - Depth: 22 m to 24.5 m.



**BOREHOLE INFORMATION**  
Method: Rotary Core Wireline  
Equipment: Excavator Mounted Rig  
Contractor: Pro-Drill Ltd

**CO-ORDINATES: Mt Eden Circuit 2000**  
Easting: 405516m  
Northing: 803196m  
Reduced level: 32.4m  
(Auckland MSL 1946 Datum)

Date started: 25/02/2019  
Date completed: 27/02/2019  
Inclination: 90°  
Azimuth: N/A

Logged by: AD  
Input by: AD  
Checked by: JME  
Verified by: BL

Method	R.L. (m)	Length (m)	Graphic Log	Layer Code	Material Description	Weathering/USC	Testing	TCR (%)	SCR (%)	RQD (%)	Stratigraphy Defect Description Additional Notes	Installation
OB	32			Fx	0m: CORELOSS			20				
				Fc	0.4m: SILT with some fine gravel; dark brown. Low plasticity.	ML					0.4m: FILL	
OB	1				0.6m: Silty CLAY, brownish yellow mottled grey. Stiff, dry, high plasticity [RESIDUAL ECBF].						0.6m: EAST COAST BAYS FORMATION	
					0.9m to 2.8m:...Firm, moist.			100				
SPT	31			ERc		CH	1.5m: SPT 3// 1,1,2,1 N = 5	100				
OB	30							89				
					2.8m: CLAY; grey. Soft, moist, high plasticity.	CH	3m: SPT 1// 0,1,1,1 N = 3	100				
SPT	29			ERs	3.2m: Silty SAND; grey. Very loose, moist. Fine to medium grained.	SM						
OB	4							100				
				ERc	4m: Silty CLAY; grey. Very stiff, moist, high plasticity.	CH						
					4.2m: Highly weathered, grey, SILTSTONE. Extremely weak (hard). [Highly weathered ECBF]							
				EWz	4.4m to 4.5m:...black carbonaceous material	HW	4.5m: SPTC 7// 7,10,12,15 N = 44	N/A				
SPTC	28											
	5							100	100	88		

**REMARKS:**

- 1) Refer to masterplan Drawing No. SK-012 dated 22/02/2019 provided by Klein.
- 2) Hole depth specified in Water Level Readings is the bottom of the piezometric screen. Readings taken post-drilling.
- 3) IBHSV = In Barrel Hand Shear Vane, SPT = Standard Penetration Test, SPTC = Solid Cone Standard Penetration Test.
- 4) Borehole locations and reduced levels were surveyed and provided by Woods.

**Water Level Readings:**

**Date Time | Hole Depth | Water Level**  
(1) 28/02/19 17:06 | 6.00m | 2.8 m bgl  
(2) 01/03/19 09:58 | 6.00m | 2.87 m bgl  
(3) 04/03/19 04:31 | 6.00m | 2.89 m bgl  
(4) 06/03/19 14:52 | 6.00m | 2.89 m bgl  
(5) 12/03/19 12:30 | 6.00m | 2.8 m bgl  
(6) 13/03/19 12:10 | 6.00m | 2.81 m bgl  
(7) 15/03/19 12:30 | 6.00m | 2.87 m bgl



### BOREHOLE INFORMATION

Method: Rotary Core Wireline  
Equipment: Excavator Mounted Rig  
Contractor: Pro-Drill Ltd

**CO-ORDINATES: Mt Eden Circuit 2000**

CO-ORDINATES: Mt Eden Circuit 2000  
Easting: 405516m  
Northing: 803196m  
Reduced level: 32.4m  
(Auckland MSL 1946 Datum)

Date started: 25/02/2019  
Date completed: 27/02/2019  
Inclination: 90°  
Azimuth: N/A

Logged by: AD  
 Input by: AD  
 Checked by: JME  
 Verified by: BL

(Auckland MSL 1946 Datum)														
Method	R.L. (m)	Length (m)	Graphic Log	Layer Code	Material Description	Weathering/USC	Testing	TCR (%)	SCR (%)	RQD (%)	Stratigraphy Defect Description Additional Notes	Installation		
HQ3	27			EWz	<b>4.2m:</b> Highly weathered, grey, SILTSTONE. Extremely weak (hard). [Highly weathered ECBF]	HW		100	100	88				
HQ3	6				<b>5.8m:</b> Moderately weathered, grey, fine to medium SANDSTONE. Weak.  <b>6.1m to 6.5m:</b> ...fine to coarse SANDSTONE  <b>6.5m to 8.4m:</b> ...fine to medium SANDSTONE			100	100	88				
SPTC	7					6.5m: SPTC 21// 11,8,11,12 N = 42	N/A							
HQ3	25				EWs		MW		100	97	78			
	8				<b>7.5m to 7.7m:</b> ...black carbonaceous material									
SPTC	24					8m: SPTC 11// 13,15,22 for 65mm N = 50+	N/A							
HQ3	9			EUz	<b>8.4m:</b> Slightly weathered, grey, SILTSTONE. Weak.	SW		91	100	94				
	23													
SPTC	10									9.5m: SPTC 12// 9,16,15,10 for 30mm N = 50+	N/A			
					<b>9.9m:</b> CORELOSS			0						

## REMARKS:

- 1) Refer to masterplan Drawing No. SK-012 dated 22/02/2019 provided by Klein.
- 2) Hole depth specified in Water Level Readings is the bottom of the piezometric screen. Readings taken post-drilling.
- 3) IBHSV = In Barrel Hand Shear Vane, SPT = Standard Penetration Test, SPTC = Solid Cone Standard Penetration Test.
- 4) Borehole locations and reduced levels were surveyed and provided by Woods.

## Water Level Readings:

	Date	Time	Hole Depth	Water Level
(1)	28/02/19	17:06	6.00m	2.8 m bgs
(2)	01/03/19	09:58	6.00m	2.87 m bgs
(3)	04/03/19	04:31	6.00m	2.89 m bgs
(4)	06/03/19	14:52	6.00m	2.89 m bgs
(5)	12/03/19	12:30	6.00m	2.8 m bgs
(6)	13/03/19	12:10	6.00m	2.81 m bgs
(7)	15/03/19	12:30	6.00m	2.87 m bgs

**BOREHOLE INFORMATION**  
Method: Rotary Core Wireline  
Equipment: Excavator Mounted Rig  
Contractor: Pro-Drill Ltd

**CO-ORDINATES: Mt Eden Circuit 2000**  
Easting: 405516m  
Northing: 803196m  
Reduced level: 32.4m  
(Auckland MSL 1946 Datum)

Date started: 25/02/2019  
Date completed: 27/02/2019  
Inclination: 90°  
Azimuth: N/A

Logged by: AD  
Input by: AD  
Checked by: JME  
Verified by: BL

Method	R.L. (m)	Length (m)	Graphic Log	Layer Code	Material Description	Weathering/USC	Testing	TCR (%)	SCR (%)	RQD (%)	Stratigraphy Defect Description Additional Notes	Installation
HQ3	22			EUx	9.9m: CORELOSS			0				
HQ3	11			EUx	10.5m: Slightly weathered, grey, fine to medium SANDSTONE. Weak.	SW	11m: SPTC 27// 24,8,9 for 50mm N = 50+	100	100	58	10.5m: Corebound	
SPTC	21							N/A				
HQ3	12			EUz	11.6m: Slightly weathered, grey, SILTSTONE. Weak.	SW	12.5m: SPTC 17// 15,19 for 55mm N = 50+	73	100	17		
SPTC	13							N/A				
HQ3	19							95	100	100		
SPTC	14							N/A				
HQ3	18						14m: SPTC 50// for 85mm N = 50+	100	100	70		
	15											

**REMARKS:**

- 1) Refer to masterplan Drawing No. SK-012 dated 22/02/2019 provided by Klein.
- 2) Hole depth specified in Water Level Readings is the bottom of the piezometric screen. Readings taken post-drilling.
- 3) IBHSV = In Barrel Hand Shear Vane, SPT = Standard Penetration Test, SPTC = Solid Cone Standard Penetration Test.
- 4) Borehole locations and reduced levels were surveyed and provided by Woods.

**Water Level Readings:**

Date Time	Hole Depth	Water Level
(1) 28/02/19 17:06	6.00m	2.8 m bgl
(2) 01/03/19 09:58	6.00m	2.87 m bgl
(3) 04/03/19 04:31	6.00m	2.89 m bgl
(4) 06/03/19 14:52	6.00m	2.89 m bgl
(5) 12/03/19 12:30	6.00m	2.8 m bgl
(6) 13/03/19 12:10	6.00m	2.81 m bgl
(7) 15/03/19 12:30	6.00m	2.87 m bgl

**BOREHOLE INFORMATION**  
Method: Rotary Core Wireline  
Equipment: Excavator Mounted Rig  
Contractor: Pro-Drill Ltd

**CO-ORDINATES: Mt Eden Circuit 2000**  
Easting: 405516m  
Northing: 803196m  
Reduced level: 32.4m  
(Auckland MSL 1946 Datum)

Date started: 25/02/2019  
Date completed: 27/02/2019  
Inclination: 90°  
Azimuth: N/A

Logged by: AD  
Input by: AD  
Checked by: JME  
Verified by: BL

Method	R.L. (m)	Length (m)	Graphic Log	Layer Code	Material Description	Weathering/USC	Testing	TCR (%)	SCR (%)	RQD (%)	Stratigraphy Defect Description Additional Notes	Installation
HQ3	17		XXXXXX	EUz	11.6m: Slightly weathered, grey, SILTSTONE. Weak.	SW		100	100	70		
SPTC			XXXXXX				15.5m: SPTC 50// for 95mm N = 50+	N/A				
	16		XXXXXX	EUs	15.6m: Slightly weathered, grey, fine to medium SANDSTONE. Weak.	SW						
HQ3	16		XXXXXX	EUz	16m: Slightly weathered, grey, SILTSTONE. Weak.	SW		94	100	75		
SPTC	17		XXXXXX				17m: SPTC 50// for 130mm N = 50+	N/A				
	15		XXXXXX									
HQ3	18		XXXXXX	EUs	17.5m: Slightly weathered, grey, fine to medium SANDSTONE. Weak.	SW		95	100	56		
SPTC HQ3	14		XXXXXX		18.1m: Slightly weathered, grey, SILTSTONE. Weak.			100	100	100	18.3m: Corebound	
			XXXXXX				18.5m: SPTC 50// for 110mm N = 50+	N/A				
	19		XXXXXX	EUz		SW						
HQ3	13		XXXXXX					94	100	81		
	20		XXXXXX									

**REMARKS:**

- 1) Refer to masterplan Drawing No. SK-012 dated 22/02/2019 provided by Klein.
- 2) Hole depth specified in Water Level Readings is the bottom of the piezometric screen. Readings taken post-drilling.
- 3) IBHSV = In Barrel Hand Shear Vane, SPT = Standard Penetration Test, SPTC = Solid Cone Standard Penetration Test.
- 4) Borehole locations and reduced levels were surveyed and provided by Woods.

**Water Level Readings:**

Date Time	Hole Depth	Water Level
(1) 28/02/19 17:06	6.00m	2.8 m bgl
(2) 01/03/19 09:58	6.00m	2.87 m bgl
(3) 04/03/19 04:31	6.00m	2.89 m bgl
(4) 06/03/19 14:52	6.00m	2.89 m bgl
(5) 12/03/19 12:30	6.00m	2.8 m bgl
(6) 13/03/19 12:10	6.00m	2.81 m bgl
(7) 15/03/19 12:30	6.00m	2.87 m bgl



Logged by: AD  
 Input by: AD  
 Checked by: JME  
 Verified by: BL

End of borehole at 24.64m (Target Depth)

Water Level Readings			
Date	Time	Hole Depth	Water Level
(1)	28/02/19	17:06	6.00m 2.8 m bgl
(2)	01/03/19	09:58	6.00m 2.87 m bgl
(3)	04/03/19	04:31	6.00m 2.89 m bgl
(4)	06/03/19	14:52	6.00m 2.89 m bgl
(5)	12/03/19	12:30	6.00m 2.8 m bgl
(6)	13/03/19	12:10	6.00m 2.81 m bgl
(7)	15/03/19	12:30	6.00m 2.87 m bgl

Eastcliffe Phase 1  
Ground Investigation

**aurecon**

Borehole Reference: **BH43**

Date Drilled:

26/02/2019 – 27/02/2019

Photographed By: **AD**

Date Photographed:

26/02/2019 – 27/02/2019



Box 1. - Depth: 0 m to 3 m.



Box 2. - Depth: 3 m to 6.5 m.



Eastcliffe Phase 1  
Ground Investigation

**aurecon**

Borehole Reference: BH43


Date Drilled:

26/02/2019 – 27/02/2019

Photographed By: AD

Date Photographed:

26/02/2019 – 27/02/2019



Box 3. - Depth: 6.5 m to 11 m.



Box 4. - Depth: 11 m to 15.5 m.



Eastcliffe Phase 1  
Ground Investigation

**aurecon**

Borehole Reference: BH43


Date Drilled:

26/02/2019 – 27/02/2019

Photographed By: AD

Date Photographed:

26/02/2019 – 27/02/2019



Box 5. - Depth: 11.5 m to 15.5 m.



Box 6. - Depth: 15.5 m to 18.5 m.



Eastcliffe Phase 1  
Ground Investigation

**aurecon**

Borehole Reference: BH43

Date Drilled:

26/02/2019 – 27/02/2019

Photographed By: AD

Date Photographed:

26/02/2019 – 27/02/2019



Box 7. - Depth: 18.5 m to 21.5m.



Box 8. - Depth: 22 m to 24.5 m.

**BOREHOLE INFORMATION**  
Method: Rotary Core Wireline  
Equipment: Excavator Mounted Rig  
Contractor: Pro-Drill Ltd

**CO-ORDINATES: Mt Eden Circuit 2000**  
Easting: 405527m  
Northing: 803174m  
Reduced level: 31.3m  
(Auckland MSL 1946 Datum)

Date started: 28/02/2019  
Date completed: 28/02/2019  
Inclination: 90°  
Azimuth: N/A

Logged by: AD  
Input by: AD  
Checked by: JME  
Verified by: BL

Method	R.L. (m)	Length (m)	Graphic Log	Layer Code	Material Description	Weathering/USC	Testing	TCR (%)	SCR (%)	RQD (%)	Stratigraphy Defect Description Additional Notes	Installation
OB	31			F	0m: Gravelly SILT; dark brown. Firm, dry, low plasticity. Gravel, medium. [FILL]	ML					0m: FILL	
OB				Fc	0.2m: SILT with some medium gravel; brown. Very stiff, dry, low plasticity.	ML	0.5m: IBHSV UTP	100				
OB	1				0.9m: Silty CLAY; brownish yellow mottled grey. Firm, moist, high plasticity. [RESIDUAL ECBF]		1m: IBHSV UTP	100			0.9m: EAST COAST BAYS FORMATION	
OB	30				1.5m to 3.3m: ...trace fine gravel		1.5m: SPT 2// 1,1,2,2 N = 6 1.5m: IBHSV 120/60 kPa	49				
SPT		2		ERc		CH						
OB	29							90				
SPT		3					3m: SPT 1// 0,1,1,1 N = 3 3m: IBHSV 45/18 kPa	100				
OB				ERs	3.3m: Silty SAND; grey. Very loose, moist.	SM						
OB	4				4m: Silty CLAY; grey. Very stiff, moist, high plasticity.			95				
SPT		5		ERc		CH	4.5m: SPT 5// 5,4,5,5 N = 19 4.5m: IBHSV 200+ kPa	100				
								100				

**REMARKS:**

- 1) Refer to masterplan Drawing No. SK-012 dated 22/02/2019 provided by Klein.
- 2) Hole depth specified in Water Level Readings is the bottom of the piezometric screen. Readings taken post-drilling.
- 3) IBHSV = In Barrel Hand Shear Vane, SPT = Standard Penetration Test, SPTC = Solid Cone Standard Penetration Test.
- 4) Borehole locations and reduced levels were surveyed and provided by Woods.

**Water Level Readings:**

**Date Time | Hole Depth | Water Level**  
(1) 06/03/19 15:03 | 6.00m | 4.44 m bgl  
(2) 12/03/19 10:01 | 6.00m | 3.87 m bgl  
(3) 13/03/19 12:12 | 6.00m | 3.89 m bgl  
(4) 15/03/19 12:30 | 6.00m | 3.94 m bgl



<b>BOREHOLE INFORMATION</b> Method: Rotary Core Wireline Equipment: Excavator Mounted Rig Contractor: Pro-Drill Ltd	<b>CO-ORDINATES: Mt Eden Circuit 2000</b> Easting: 405527m Northing: 803174m Reduced level: 31.3m (Auckland MSL 1946 Datum)	Date started: 28/02/2019 Date completed: 28/02/2019 Inclination: 90° Azimuth: N/A	Logged by: AD Input by: AD Checked by: JME Verified by: BL
--	---	--	---

Method	R.L. (m)	Length (m)	Graphic Log	Layer Code	Material Description	Weathering/USC	Testing	TCR (%)	SCR (%)	RQD (%)	Stratigraphy Defect Description Additional Notes	Installation
OB				ERc	4m: Silty CLAY; grey. Very stiff, moist, high plasticity.	CH		100				
HQ3	26			ERx	5.2m: CORELOSS							
				EWz	5.5m: Moderately weathered, grey, SILTSTONE. Weak [Moderately weathered ECBF].	MW						
	6			EUz	5.7m: Slightly weathered, grey, SILTSTONE. Very weak.	SW		77	100	97		
	25			EUz	6m: Slightly weathered, grey, fine to medium SANDSTONE.	SW	6.5m: SPTC 22// 18,14,14,14 for 20mm N = 50+	N/A			6m to 6.5m: JT 75-90° UnRo Sn(Fe)	
SPTC	7				7m: Slightly weathered, grey SILTSTONE. Weak.							
HQ3	24				7.4m to 7.5m: ...black carbonaceous material			100	100	90		
	8											
SPTC	23			EUz		SW	8m: SPTC 8// 10,10,14,16 for 15mm N = 50+	N/A				
HQ3	9							95	100	77		
	22											
SPTC	10			EUz	9.4m: Slightly weathered, grey, medium to coarse SANDSTONE. Very weak.	SW	9.5m: SPTC 35// 17,11,10,12 for 75mm N = 50+	N/A				
								100	100	86		

**REMARKS:**

- 1) Refer to masterplan Drawing No. SK-012 dated 22/02/2019 provided by Klein.
- 2) Hole depth specified in Water Level Readings is the bottom of the piezometric screen. Readings taken post-drilling.
- 3) IBHSV = In Barrel Hand Shear Vane, SPT = Standard Penetration Test, SPTC = Solid Cone Standard Penetration Test.
- 4) Borehole locations and reduced levels were surveyed and provided by Woods.

**Water Level Readings:**

Date Time	Hole Depth	Water Level
(1) 06/03/19 15:03	6.00m	4.44 m bgl
(2) 12/03/19 10:01	6.00m	3.87 m bgl
(3) 13/03/19 12:12	6.00m	3.89 m bgl
(4) 15/03/19 12:30	6.00m	3.94 m bgl

<b>BOREHOLE INFORMATION</b>		<b>CO-ORDINATES: Mt Eden Circuit 2000</b>		Date started:	28/02/2019	Logged by:	AD
Method: Rotary Core Wireline		Easting: 405527m		Date completed:	28/02/2019	Input by:	AD
Equipment: Excavator Mounted Rig		Northing: 803174m		Inclination:	90°	Checked by:	JME
Contractor: Pro-Drill Ltd		Reduced level: 31.3m		Azimuth:	N/A	Verified by:	BL
		(Auckland MSL 1946 Datum)					

Method	R.L. (m)	Length (m)	Graphic Log	Layer Code	Material Description	Weathering/USC	Testing	TCR (%)	SCR (%)	RQD (%)	Stratigraphy Defect Description Additional Notes	Installation
HQ3	21			EUs	9.4m: Slightly weathered, grey, medium to coarse SANDSTONE. Very weak.	SW		100	100	86		
					10.5m: Slightly weathered, grey, SILTSTONE. Very weak.							
SPTC	20				10.8m to 15.4m: ...weak		11m: SPTC 21// 22,28 for 75mm N = 50+	N/A				
HQ3	12						12.5m: SPTC 12// 14,18,18 for 70mm N = 50+	N/A				
SPTC	13					SW						
HQ3	18						14m: SPTC 50// for 140mm N = 50+	N/A				
SPTC	14											
HQ3	17							100	100	28		
	15											

REMARKS:  
1) Refer to masterplan Drawing No. SK-012 dated 22/02/2019 provided by Klein.  
2) Hole depth specified in Water Level Readings is the bottom of the piezometric screen. Readings taken post-drilling.  
3) IBHSV = In Barrel Hand Shear Vane, SPT = Standard Penetration Test, SPTC = Solid Cone Standard Penetration Test.  
4) Borehole locations and reduced levels were surveyed and provided by Woods.

**Water Level Readings:**  
Date Time | Hole Depth | Water Level  
(1) 06/03/19 15:03 | 6.00m | 4.44 m bgl  
(2) 12/03/19 10:01 | 6.00m | 3.87 m bgl  
(3) 13/03/19 12:12 | 6.00m | 3.89 m bgl  
(4) 15/03/19 12:30 | 6.00m | 3.94 m bgl

**BOREHOLE INFORMATION**  
Method: Rotary Core Wireline  
Equipment: Excavator Mounted Rig  
Contractor: Pro-Drill Ltd

**CO-ORDINATES: Mt Eden Circuit 2000**  
Easting: 405527m  
Northing: 803174m  
Reduced level: 31.3m  
(Auckland MSL 1946 Datum)

Date started: 28/02/2019  
Date completed: 28/02/2019  
Inclination: 90°  
Azimuth: N/A

Logged by: AD  
Input by: AD  
Checked by: JME  
Verified by: BL

Method	R.L. (m)	Length (m)	Graphic Log	Layer Code	Material Description	Weathering/USC	Testing	TCR (%)	SCR (%)	RQD (%)	Stratigraphy Defect Description Additional Notes	Installation
HQ3	16		x x x x x	EUz	10.5m: Slightly weathered, grey, SILTSTONE. Very weak.	SW		100	100	28		
SPTC			x x x x x	EUz	15.4m: Slightly weathered, grey, medium to coarse SANDSTONE. Weak.	SW	15.5m: SPTC 50// for 120mm N = 50+	N/A				
HQ3	15		x x x x x	EUz	16.1m: Slightly weathered, grey, SILTSTONE. Weak.	SW		94	100	68		
SPTC			x x x x x	EUz	16.5m: Slightly weathered, grey, fine to medium SANDSTONE. Weak.	SW						
HQ3	14		x x x x x	EUz	16.9m: Slightly weathered, grey, SILTSTONE. Weak.	SW	17m: SPTC 50// for 70mm N = 50+	N/A				
SPTC			x x x x x	EUz				100	100	87		
HQ3	13		x x x x x	EUz	18.1m: Slightly weathered, grey, fine to medium SANDSTONE. Weak.	SW						
SPTC			x x x x x	EUz	18.4m: Slightly weathered, grey, SILTSTONE. Weak.	SW	18.5m: SPTC 50// for 130mm N = 50+	N/A				
HQ3	12		x x x x x	EUz				93	100	95		
	20		x x x x x	EUz								

**REMARKS:**

- 1) Refer to masterplan Drawing No. SK-012 dated 22/02/2019 provided by Klein.
- 2) Hole depth specified in Water Level Readings is the bottom of the piezometric screen. Readings taken post-drilling.
- 3) IBHSV = In Barrel Hand Shear Vane, SPT = Standard Penetration Test, SPTC = Solid Cone Standard Penetration Test.
- 4) Borehole locations and reduced levels were surveyed and provided by Woods.

**Water Level Readings:**

**Date Time | Hole Depth | Water Level**  
(1) 06/03/19 15:03 | 6.00m | 4.44 m bgl  
(2) 12/03/19 10:01 | 6.00m | 3.87 m bgl  
(3) 13/03/19 12:12 | 6.00m | 3.89 m bgl  
(4) 15/03/19 12:30 | 6.00m | 3.94 m bgl





Level 4, 139 Carlton Gore Road  
PO Box 9762, Newmarket  
Auckland, New Zealand  
Tel: +64 9 520 6019  
www.aurecongroup.com

Client: **Ngati Whatua Orakei Whai Rawa Ltd**  
Project: **Eastcliffe Retirement Village**  
Location: **Phase 1 - Block C**  
Project Reference: **255232**

**BH44**

Sheet **5** of **5**

<b>BOREHOLE INFORMATION</b> Method: Rotary Core Wireline Equipment: Excavator Mounted Rig Contractor: Pro-Drill Ltd		<b>CO-ORDINATES: Mt Eden Circuit 2000</b> Easting: 405527m Northing: 803174m Reduced level: 31.3m (Auckland MSL 1946 Datum)	Date started: 28/02/2019 Date completed: 28/02/2019 Inclination: 90° Azimuth: N/A	Logged by: AD Input by: AD Checked by: JME Verified by: BL
--	--	---	--	---

Method	R.L. (m)	Length (m)	Graphic Log	Layer Code	Material Description	Weathering/USC	Testing	TCR (%)	SCR (%)	RQD (%)	Stratigraphy Defect Description Additional Notes	Installation
SPTC							20m: SPTC 50// for 150mm N = 50+	N/A				

End of borehole at 20.15m (Target Depth)

REMARKS:

- 1) Refer to masterplan Drawing No. SK-012 dated 22/02/2019 provided by Klein.  
2) Hole depth specified in Water Level Readings is the bottom of the piezometric screen. Readings taken post-drilling.  
3) IBHSV = In Barrel Hand Shear Vane, SPT = Standard Penetration Test, SPTC = Solid Cone Standard Penetration Test.  
4) Borehole locations and reduced levels were surveyed and provided by Woods.

Water Level Readings:

Date	Time	Hole Depth	Water Level
(1)	06/03/19 15:03	6.00m	4.44 m bgl
(2)	12/03/19 10:01	6.00m	3.87 m bgl
(3)	13/03/19 12:12	6.00m	3.89 m bgl
(4)	15/03/19 12:30	6.00m	3.94 m bgl

Eastcliffe Phase 1  
Ground Investigation

**aurecon**

Borehole Reference: BH44

Date Drilled:

28/02/2019 – 28/02/2019

Photographed By: AD

Date Photographed:

28/03/2019 – 1/03/2019



Box 1. - Depth: 0 m to 3 m.



Box 2. - Depth: 3 m to 5.5 m.



Eastcliffe Phase 1  
Ground Investigation

**aurecon**

Borehole Reference: **BH44**

Date Drilled:

28/02/2019 – 28/02/2019

Photographed By: **AD**

Date Photographed:

28/03/2019 – 1/03/2019



Box 3. - Depth: 5.5 m to 9 m.



Box 4. - Depth: 9 m to 12.5 m.



Eastcliffe Phase 1  
Ground Investigation

**aurecon**

Borehole Reference: BH44  
Photographed By: AD

Date Drilled:  
Date Photographed:

28/02/2019 – 28/02/2019  
28/03/2019 – 1/03/2019



Box 5. - Depth: 12.5 m to 16 m.



Box 6. - Depth: 16 m to 19 m.

**Eastcliffe Phase 1  
Ground Investigation**

**aurecon**

Borehole Reference: **BH44**

Date Drilled:

**28/02/2019 – 28/02/2019**

Photographed By: **AD**

Date Photographed:

**28/03/2019 – 1/03/2019**



**Box 7. - Depth: 19 m to 20m.**

**BOREHOLE INFORMATION**  
Method: Rotary Core Wireline  
Equipment: Excavator Mounted Rig  
Contractor: Pro-Drill Ltd

**CO-ORDINATES: Mt Eden Circuit 2000**  
Easting: 405556m  
Northing: 803200m  
Reduced level: 28.8m  
(Auckland MSL 1946 Datum)

Date started: 13/03/2019  
Date completed: 13/03/2019  
Inclination: 90°  
Azimuth: N/A

Logged by: AD  
Input by: AD  
Checked by: JME  
Verified by: BL

Method	R.L. (m)	Length (m)	Graphic Log	Layer Code	Material Description	Weathering/USC	Testing	TCR (%)	SCR (%)	RQD (%)	Stratigraphy Defect Description Additional Notes	Installation
VAC EX	28	1			0m: CORELOSS			0			0m: Vacuum excavation.	
SPT	27	2		ERc	1.5m: Silty CLAY; brownish yellow mottled grey. Soft, moist, high plasticity [RESIDUAL ECBF].	CH	1.5m: SPT 1// 0,1,0,1 N = 2	100			1.5m: EAST COAST BAYS FORMATION	
OB				ERs	1.9m: Sandy CLAY; grey. Firm, moist, low plasticity.	CL						
OB	26			ERs	2.2m: Clayey SAND; grey. Very loose, moist.	SC		100				
SPT		3		ERc	2.7m: Silty CLAY; grey. Firm, moist, high plasticity.	CH						
OB	25			ERs	2.9m: Silty SAND; grey. Very loose, moist.	SM	3m: SPT 0// 0,1,0,1 N = 2	100				
OB		4		ERc	4m: Silty CLAY; grey. Stiff, moist, high plasticity [Completely weathered ECBF].			100				
SPT	24	5		ERc	4.5m to 5.5m: ...very stiff	CW	4.5m: SPT 2// 2,3,1,3 N = 9	100				
								100				

**REMARKS:**

- 1) Refer to masterplan Drawing No. SK-012 dated 22/02/2019 provided by Klein.
- 2) Hole depth specified in Water Level Readings is the bottom of the piezometric screen. Water level readings taken post drilling.
- 3) IBHSV = In Barrel Hand Shear Vane, SPT = Standard Penetration Test, SPTC = Solid Cone Standard Penetration Test.
- 4) Borehole locations and reduced levels were surveyed and provided Woods.
- 5) No piezometer was installed for recording water levels.

**Water Level Readings:**  
Date Time | Hole Depth | Water Level  
(1) 13/03/19 16:30 | m | 6.26 m bgl



**BOREHOLE INFORMATION**  
Method: Rotary Core Wireline  
Equipment: Excavator Mounted Rig  
Contractor: Pro-Drill Ltd

**CO-ORDINATES: Mt Eden Circuit 2000**  
Easting: 405556m  
Northing: 803200m  
Reduced level: 28.8m  
(Auckland MSL 1946 Datum)

Date started: 13/03/2019  
Date completed: 13/03/2019  
Inclination: 90°  
Azimuth: N/A

Logged by: AD  
Input by: AD  
Checked by: JME  
Verified by: BL

Method	R.L. (m)	Length (m)	Graphic Log	Layer Code	Material Description	Weathering/USC	Testing	TCR (%)	SCR (%)	RQD (%)	Stratigraphy Defect Description Additional Notes	Installation
OB												
HQ3	23	6		ERc	4m: Silty CLAY: grey. Stiff, moist, high plasticity [Completely weathered ECBF].	CW		100		0		
SPT	22			EWs	6.5m: Highly weathered, grey, medium to coarse SANDSTONE. Extremely weak (dense).	HW	6.5m: SPT 2// 1,2,2,3 N = 8	100	100	100		
HQ3	7				6.9m: Highly weathered, grey, SILTSTONE. Extremely weak (very stiff).	HW		86	100	53		
SPTC	21	8					8m: SPTC 2// 1,2,3,4 N = 10	N/A				
HQ3	20	9		EWz	8.5m: Moderately weathered, grey, SILTSTONE. Extremely weak (hard).	MW		100	100	100		
SPTC	19						9.5m: SPTC 10// 9,10,10,11 N = 40	N/A				
	10							100	100	100		

**REMARKS:**

- 1) Refer to masterplan Drawing No. SK-012 dated 22/02/2019 provided by Klein.
- 2) Hole depth specified in Water Level Readings is the bottom of the piezometric screen. Water level readings taken post drilling.
- 3) IBHSV = In Barrel Hand Shear Vane, SPT = Standard Penetration Test, SPTC = Solid Cone Standard Penetration Test.
- 4) Borehole locations and reduced levels were surveyed and provided Woods.
- 5) No piezometer was installed for recording water levels.

**Water Level Readings:**

Date Time | Hole Depth | Water Level  
(1) 13/03/19 16:30 | m | 6.26 m bgl

## BOREHOLE INFORMATION

Method: Rotary Core Wireline  
Equipment: Excavator Mounted Rig  
Contractor: Pro-Drill Ltd

**CO-ORDINATES: Mt Eden Circuit 2000**

Easting: 405556m  
Northing: 803200m  
Reduced level: 28.8m  
(Auckland MSL 1946 Datum)

Date started: 13/03/2019  
Date completed: 13/03/2019  
Inclination: 90°  
Azimuth: N/A

Logged by: AD  
 Input by: AD  
 Checked by: JME  
 Verified by: BL

[illegible]

## REMARKS:

- 1) Refer to masterplan Drawing No. SK-012 dated 22/02/2019 provided by Klein.
- 2) Hole depth specified in Water Level Readings is the bottom of the piezometric screen. Water level readings taken post drilling.
- 3) IBHSV = In Barrel Hand Shear Vane, SPT = Standard Penetration Test, SPTC = Solid Cone Standard Penetration Test.
- 4) Borehole locations and reduced levels were surveyed and provided Woods.
- 5) No piezometer was installed for recording water levels.

<b>Water Level Readings:</b>
------------------------------

Date	Time	Hole Depth	Water Level
(1) 13/03/19	16:30	m	6.26 m bgl

<b>BOREHOLE INFORMATION</b> Method: Rotary Core Wireline Equipment: Excavator Mounted Rig Contractor: Pro-Drill Ltd	<b>CO-ORDINATES: Mt Eden Circuit 2000</b> Easting: 405556m Northing: 803200m Reduced level: 28.8m (Auckland MSL 1946 Datum)	Date started: 13/03/2019 Date completed: 13/03/2019 Inclination: 90° Azimuth: N/A	Logged by: AD Input by: AD Checked by: JME Verified by: BL
--	---	--	---

Method	R.L. (m)	Length (m)	Graphic Log	Layer Code	Material Description	Weathering/USC	Testing	TCR (%)	SCR (%)	RQD (%)	Stratigraphy Defect Description Additional Notes	Installation
HQ3				EUz	15m: Slightly weathered, grey, fine to medium SANDSTONE. Weak.	SW						
				EUz	15.2m: Slightly weathered, grey, SILTSTONE. Weak.	SW		100	100	100		
SPTC							15.5m: SPTC 50// for 130mm N = 50+	N/A				

End of borehole at 15.63m (Target Depth)

REMARKS:

- 1) Refer to masterplan Drawing No. SK-012 dated 22/02/2019 provided by Klein.
- 2) Hole depth specified in Water Level Readings is the bottom of the piezometric screen. Water level readings taken post drilling.
- 3) IBHSV = In Barrel Hand Shear Vane, SPT = Standard Penetration Test, SPTC = Solid Cone Standard Penetration Test.
- 4) Borehole locations and reduced levels were surveyed and provided Woods.
- 5) No piezometer was installed for recording water levels.

**Water Level Readings:**  
Date Time | Hole Depth | Water Level  
(1) 13/03/19 16:30 | m | 6.26 m bgl



Eastcliffe Phase 1  
Ground Investigation

**aurecon**

Borehole Reference: **BH45**

Date Drilled:

13/03/2019 – 13/03/2019

Photographed By: **AD**

Date Photographed:

13/03/2019 – 13/03/2019



Box 1. - Depth: 0 m to 4 m.



Box 2. - Depth: 4 m to 7.5 m.

Eastcliffe Phase 1  
Ground Investigation

**aurecon**

Borehole Reference: **BH45**

Date Drilled:

13/03/2019 – 13/03/2019

Photographed By: **AD**

Date Photographed:

13/03/2019 – 13/03/2019



Box 3. - Depth: 7.5 m to 12 m.



Box 4. - Depth: 12 m to 15.5 m.



**BOREHOLE INFORMATION**  
Method: Rotary Core Wireline  
Equipment: Excavator Mounted Rig  
Contractor: Pro-Drill Ltd

**CO-ORDINATES: Mt Eden Circuit 2000**  
Easting: 405545m  
Northing: 803222m  
Reduced level: 28.9m  
(Auckland MSL 1946 Datum)

Date started: 4/03/2019  
Date completed: 4/03/2019  
Inclination: 90°  
Azimuth: N/A

Logged by: AD  
Input by: AD  
Checked by: JME  
Verified by: BL

Method	R.L. (m)	Length (m)	Graphic Log	Layer Code	Material Description	Weathering/USC	Testing	TCR (%)	SCR (%)	RQD (%)	Stratigraphy Defect Description Additional Notes	Installation
SSA				Fx	0m: CORELOSS			0			0m: No material recovered from auger; drillers observed gravel between 0-0.8m.	
OB	28	1		ERc	0.8m: Silty CLAY with some gravel; brownish yellow mottled grey. Moist, firm, high plasticity [RESIDUAL ECBF].	CH	1.5m: SPT 1// 0,1,0,1 N = 2	100			0.8m: EAST COAST BAYS FORMATION	
SPT	27	2		ERx	2m: CORELOSS							
OB					2.5m: CLAY trace gravel; grey. Firm, moist, high plasticity. Gravel, fine.	CH		50				
SPT	26	3			3m: Silty CLAY; grey. Firm, moist, high plasticity.		3m: SPT 1// 1,0,1,2 N = 4	100				
OB	25	4		ERc	4.2m to 4.5m: ...iron staining	CH		100				
SPT	24	5			4.5m: Sandy CLAY; grey. Stiff, moist, high plasticity.	CH	4.5m: SPT 1// 0,1,1,2 N = 4 4.5m: IBHSV 135/30 kPa	100				
								100				

**REMARKS:**

- 1) Refer to masterplan Drawing No. SK-012 dated 22/02/2019 provided by Klein.
- 2) Hole depth specified in Water Level Readings is the bottom of the piezometric screen. Readings taken post-drilling.
- 3) IBHSV = In Barrel Hand Shear Vane, SPT = Standard Penetration Test, SPTC = Solid Cone Standard Penetration Test.
- 4) Borehole locations and reduced levels were surveyed and provided by Woods.

**Water Level Readings:**

Date Time	Hole Depth	Water Level
(1) 06/03/19 14:33	m	2.75 m bgl
(2) 12/03/19 10:20	m	2.72 m bgl
(3) 13/03/19 11:45	m	3.7 m bgl
(4) 15/03/19 12:25	m	2.61 m bgl



<b>BOREHOLE INFORMATION</b> Method: Rotary Core Wireline Equipment: Excavator Mounted Rig Contractor: Pro-Drill Ltd	<b>CO-ORDINATES: Mt Eden Circuit 2000</b> Easting: 405545m Northing: 803222m Reduced level: 28.9m (Auckland MSL 1946 Datum)	Date started: 4/03/2019 Date completed: 4/03/2019 Inclination: 90° Azimuth: N/A	Logged by: AD Input by: AD Checked by: JME Verified by: BL
--	---	--	---

Method	R.L. (m)	Length (m)	Graphic Log	Layer Code	Material Description	Weathering/USC	Testing	TCR (%)	SCR (%)	RQD (%)	Stratigraphy Defect Description Additional Notes	Installation
OB	23	6		ERc	4.5m: Sandy CLAY; grey. Stiff, moist, high plasticity.	CH	6m: SPT 3// 2,2,2,2 N = 8 6m: IBHSV 135/36 kPa	100	100			
OB	22	7			6.5m: Silty CLAY; grey. Very stiff, moist, high plasticity.	CH		100				
HQ3	21	8		EWz	7m: Highly weathered, grey, SILTSTONE. Extremely weak (hard) [Highly weathered ECBF].	HW						
SPT					7.2m: Moderately weathered, grey, SILTSTONE. Very weak.	MW	8m: SPT 4// 4,5,7,10 N = 26	100	100	100		
HQ3	20	9						100	98	87		
				EUs	9.1m: Slightly weathered, fine to medium SANDSTONE. Weak.	SW						
SPTC	19	10		EUz	9.4m: Slightly weathered, grey, SILTSTONE. Very weak.	SW	9.5m: SPTC 17// 13,14,12,11 for 60mm N = 50+	N/A				
								100	100	85		

**REMARKS:**

- 1) Refer to masterplan Drawing No. SK-012 dated 22/02/2019 provided by Klein.
- 2) Hole depth specified in Water Level Readings is the bottom of the piezometric screen. Readings taken post-drilling.
- 3) IBHSV = In Barrel Hand Shear Vane, SPT = Standard Penetration Test, SPTC = Solid Cone Standard Penetration Test.
- 4) Borehole locations and reduced levels were surveyed and provided by Woods.

**Water Level Readings:**

Date Time	Hole Depth	Water Level
(1) 06/03/19 14:33	m	2.75 m bgl
(2) 12/03/19 10:20	m	2.72 m bgl
(3) 13/03/19 11:45	m	3.7 m bgl
(4) 15/03/19 12:25	m	2.81 m bgl

### BOREHOLE INFORMATION

Method: Rotary Core Wireline  
Equipment: Excavator Mounted Rig  
Contractor: Pro-Drill Ltd

**CO-ORDINATES: Mt Eden Circuit 2000**

CO-ORDINATES: Mt Eden Circuit 2000  
Easting: 405545m  
Northing: 803222m  
Reduced level: 28.9m  
(Auckland MSL 1946 Datum)

Date started: 4/03/2019  
Date completed: 4/03/2019  
Inclination: 90°  
Azimuth: N/A

Logged by: AD  
 Input by: AD  
 Checked by: JME  
 Verified by: BL

[illegible]

## REMARKS:

- 1) Refer to masterplan Drawing No. SK-012 dated 22/02/2019 provided by Klein.
- 2) Hole depth specified in Water Level Readings is the bottom of the piezometric screen. Readings taken post-drilling.
- 3) IBHSV = In Barrel Hand Shear Vane, SPT = Standard Penetration Test, SPTC = Solid Cone Standard Penetration Test.
- 4) Borehole locations and reduced levels were surveyed and provided by Woods.

## Water Level Readings:

Date	Time	Hole	Depth	Water Level
(1)	06/03/19	14:33	m	2.75 m bgl
(2)	12/03/19	10:20	m	2.72 m bgl
(3)	13/03/19	11:45	m	3.7 m bgl
(4)	15/03/19	12:25	m	2.81 m bgl

### BOREHOLE INFORMATION

Method: Rotary Core Wireline  
Equipment: Excavator Mounted Rig  
Contractor: Pro-Drill Ltd

**CO-ORDINATES: Mt Eden Circuit 2000**

CO-ORDINATES: Mt Eden Circuit 2000  
Easting: 405545m  
Northing: 803222m  
Reduced level: 28.9m  
(Auckland MSL 1946 Datum)

Date started: 4/03/2019  
Date completed: 4/03/2019  
Inclination: 90°  
Azimuth: N/A

Logged by: AD  
 Input by: AD  
 Checked by: JME  
 Verified by: BL

[illegible]

End of borehole at 15.61m (Target Depth)

15.5m: SPTC  
50//  
for 110mm  
N = 50+

## REMARKS:

- REMARKS:
- 1) Refer to masterplan Drawing No. SK-012 dated 22/02/2019 provided by Klein.
  - 2) Hole depth specified in Water Level Readings is the bottom of the piezometric screen. Readings taken post-drilling.
  - 3) IBHSV = In Barrel Hand Shear Vane, SPT = Standard Penetration Test, SPTC = Solid Cone Standard Penetration Test.
  - 4) Borehole locations and reduced levels were surveyed and provided by Woods.

## Water Level Readings:

Date	Time	Hole	Depth	Water Level
(1)	06/03/19	14:33	m	2.75 m bgl
(2)	12/03/19	10:20	m	2.72 m bgl
(3)	13/03/19	11:45	m	3.7 m bgl
(4)	15/03/19	12:25	m	2.81 m bgl



Eastcliffe Phase 1  
Ground Investigation

**aurecon**

Borehole Reference: **BH46**

Date Drilled:

05/03/2019 – 05/03/2019

Photographed By: **AD**

Date Photographed:

05/03/2019 – 05/03/2019



Box 1. - Depth: 0 m to 4 m.



Box 2. - Depth: 4 m to 6 m.

Eastcliffe Phase 1  
Ground Investigation

**aurecon**

Borehole Reference: **BH46**  
Photographed By: **AD**

Date Drilled:  
Date Photographed:

05/03/2019 – 05/03/2019  
05/03/2019 – 05/03/2019



Box 3. - Depth: 6 m to 9 m.



Box 4. - Depth: 9 m to 12.5 m.



**Eastcliffe Phase 1  
Ground Investigation**

**aurecon**

Borehole Reference: **BH46**

Date Drilled:

**05/03/2019 – 05/03/2019**

Photographed By: **AD**

Date Photographed:

**05/03/2019 – 05/03/2019**



**Box 5. - Depth: 12.5 m to 15.5 m.**



### BOREHOLE INFORMATION

Method: Rotary Core Wireline  
Equipment: Excavator Mounted Rig  
Contractor: Pro-Drill Ltd

**CO-ORDINATES: Mt Eden Circuit 2000**

CO-ORDINATES: Mt Eden Circuit 2000  
Easting: 405559m  
Northing: 803234m  
Reduced level: 28.6m  
(Auckland MSL 1946 Datum)

Date started: 27/02/2019  
Date completed: 27/02/2019  
Inclination: 90°  
Azimuth: N/A

Logged by: AD  
 Input by: AD  
 Checked by: JME  
 Verified by: BL

Method	R.L. (m)	Length (m)	Graphic Log	Layer Code	Material Description	Weathering/USC	Testing	TCR (%)	SCR (%)	RQD (%)	Stratigraphy Defect Description Additional Notes	Installation
OB				T	0m: Clayey SILT; dark brown. Firm, dry, low plasticity.	ML					0m: TOPSOIL	
					0.2m: Silty CLAY; brown. Stiff, dry, low plasticity.	CL		80			0.2m: FILL	
					0.4m: Clayey SILT with some gravel, trace rootlets; brown. Firm, moist, low plasticity. Gravel, medium.	CL						
OB	28			Fc	0.6m: Silty CLAY; brown. Firm, moist, high plasticity.	CH		90				
					0.8m: CLAY with some sand and minor gravel; brown. Firm, moist, high plasticity.	CH						
		1			1m: Silty CLAY; brown. Firm, moist, high plasticity.	CH		100				
OB					1.3m: Sandy CLAY with some silt; brown with mottled dark brown and grey. Firm, moist, high plasticity.	CH						
SPT	27				1.5m: Silty CLAY trace rootlets; brownish yellow mottled grey and dark red. Firm, moist, high plasticity [RESIDUAL ECBF].	CH 1.5m: SPT 2// 1,1,1,1 N = 4		100			1.5m: EAST COAST BAYS FORMATION	
		2			1.8m: CLAY; brownish yellow mottled grey. Firm, moist, high plasticity.	CH						
OB					2m: Silty CLAY; brownish yellow mottled grey and dark red. Firm, moist, high plasticity.			100			1.95m: Driller advised of trouble drilling through the material. Rods were pull out and a new run was undertaken from 2.7m	
	26					CH						
OB		3		ERC				100				
SPT	25				3.7m: CLAY; brownish yellow mottled grey. Firm, moist, high plasticity.			100			3.7m: Water loss of 50%	
OB		4				CH		100				
SPT	24				4.8m to 4.9m:...grey			100				
		5			4.9m: Silty SAND; grey. Loose, moist.	SM		100				

## REMARKS:

- 1) Refer to masterplan Drawing No. SK-012 dated 22/02/2019 provided by Klein.
- 2) Hole depth specified in Water Level Readings is the bottom of the piezometric screen. Water level readings taken post drilling.
- 3) IBHSV = In Barrel Hand Shear Vane, SPT = Standard Penetration Test, SPTC = Solid Cone Standard Penetration Test.
- 4) Borehole locations and reduced levels were surveyed and provided Woods.
- 5) No piezometer was installed for recording water levels.

## Water Level Readings:








Date	Time	Hole Depth	Water Level
No water level recorded			

**BOREHOLE INFORMATION**  
Method: Rotary Core Wireline  
Equipment: Excavator Mounted Rig  
Contractor: Pro-Drill Ltd

**CO-ORDINATES: Mt Eden Circuit 2000**  
Easting: 405559m  
Northing: 803234m  
Reduced level: 28.6m  
(Auckland MSL 1946 Datum)

Date started: 27/02/2019  
Date completed: 27/02/2019  
Inclination: 90°  
Azimuth: N/A

Logged by: AD  
Input by: AD  
Checked by: JME  
Verified by: BL

Method	R.L. (m)	Length (m)	Graphic Log	Layer Code	Material Description	Weathering/USC	Testing	TCR (%)	SCR (%)	RQD (%)	Stratigraphy Defect Description Additional Notes	Installation
OB	23	6		ERs	4.9m: Silty SAND; grey. Loose, moist.	SM		100			4.95m: Wider casing placed	
				ERc	5.2m: CLAY; grey. Firm, moist, high plasticity.	CH						
SPTC				ERx	5.9m to 6m: ...stiff 6m: CORELOSS	6m: SPTC 2// 2,3,3,3 N = 11		N/A				
OB	22	7		ERz	6.3m: Clayey SILT; grey. Very stiff, moist, high plasticity [Completely weathered ECBF].	CW		100				
				HW	6.9m: Highly weathered, grey, SILTSTONE. Very weak.	HW						
HQ3	21	8		EWz	7.5m: Moderately weathered, grey, SILTSTONE. Weak.			93	95	85		
SPTC						8m: SPTC 6// 8,8,8,10 N = 34		N/A				
HQ3	20	9		EUz	9.4m: Slightly weathered, grey, SILTSTONE. Very weak.	SW	9.5m: SPTC 22// 36, 14 for 15mm N = 50+	100	100	100		
SPTC	19				9.7m: Slightly weathered, grey, fine to medium SANDSTONE. Weak.	SW						
HQ3	10			EUs				94	100	53		

**REMARKS:**

- 1) Refer to masterplan Drawing No. SK-012 dated 22/02/2019 provided by Klein.
- 2) Hole depth specified in Water Level Readings is the bottom of the piezometric screen. Water level readings taken post drilling.
- 3) IBHSV = In Barrel Hand Shear Vane, SPT = Standard Penetration Test, SPTC = Solid Cone Standard Penetration Test.
- 4) Borehole locations and reduced levels were surveyed and provided Woods.
- 5) No piezometer was installed for recording water levels.

**Water Level Readings:**  
Date Time | Hole Depth | Water Level  
No water level recorded

<b>BOREHOLE INFORMATION</b> Method: Rotary Core Wireline Equipment: Excavator Mounted Rig Contractor: Pro-Drill Ltd	<b>CO-ORDINATES: Mt Eden Circuit 2000</b> Easting: 405559m Northing: 803234m Reduced level: 28.6m (Auckland MSL 1946 Datum)	Date started: 27/02/2019 Date completed: 27/02/2019 Inclination: 90° Azimuth: N/A	Logged by: AD Input by: AD Checked by: JME Verified by: BL
--	---	--	---

Method	R.L. (m)	Length (m)	Graphic Log	Layer Code	Material Description	Weathering/USC	Testing	TCR (%)	SCR (%)	RQD (%)	Stratigraphy Defect Description Additional Notes	Installation
HQ3	18	11	[Graphic Log]	EU <sub>s</sub>	9.7m: Slightly weathered, grey, fine to medium SANDSTONE. Weak.	SW	11m: SPTC 29// 21,29 for 30mm N = 50+	94	100	53		
				EU <sub>z</sub>	10.5m: Slightly weathered, grey, SILTSTONE. Weak.	SW		N/A				
HQ3	17	12	[Graphic Log]	EU <sub>s</sub>	12.2m: Slightly weathered, grey, fine to medium SANDSTONE. Moderately strong.	SW	12.5m: SPTC 50// for 110mm N = 50+	92	100	95		
				EU <sub>z</sub>	12.8m: Slightly weathered, grey, SILTSTONE. Weak.	SW		N/A				
HQ3	15	14	[Graphic Log]	EU <sub>s</sub>			14m: SPTC 50// for 140mm N = 50+	100	100	90		
				EU <sub>z</sub>				N/A				
HQ3	14		[Graphic Log]					100	100	93		

**REMARKS:**  
1) Refer to masterplan Drawing No. SK-012 dated 22/02/2019 provided by Klein.  
2) Hole depth specified in Water Level Readings is the bottom of the piezometric screen. Water level readings taken post drilling.  
3) IBHSV = In Barrel Hand Shear Vane, SPT = Standard Penetration Test, SPTC = Solid Cone Standard Penetration Test.  
4) Borehole locations and reduced levels were surveyed and provided Woods.  
5) No piezometer was installed for recording water levels.

**Water Level Readings:**  
Date Time | Hole Depth | Water Level  
No water level recorded



### BOREHOLE INFORMATION


Method: Rotary Core Wireline  
Equipment: Excavator Mounted Rig  
Contractor: Pro-Drill Ltd

**CO-ORDINATES: Mt Eden Circuit 2000**

CO-ORDINATES: Mt Eden Circuit 2000  
Easting: 405559m  
Northing: 803234m  
Reduced level: 28.6m  
(Auckland MSL 1946 Datum)

Date started: 27/02/2019  
Date completed: 27/02/2019  
Inclination: 90°  
Azimuth: N/A

Logged by: AD  
 Input by: AD  
 Checked by: JME  
 Verified by: BL

(Auckland MISL 1946 Datum)												
Method	R.L. (m)	Length (m)	Graphic Log	Layer Code	Material Description	Weathering/USC	Testing	TCR (%)	SCR (%)	RQD (%)	Stratigraphy Defect Description Additional Notes	Installation
SPTC	HQ3	13		EUs	12.8m: Slightly weathered, grey, SILTSTONE. Weak.	SW	15.5m: SPTC 50// for 110mm N = 50+	100	100	93		
	15.1m: Slightly weathered, grey, fine to medium SANDSTONE. Weak.				SW	N/A						
End of borehole at 15.61m (Target Depth)												

End of borehole at 15.61m (Target Depth)

15.5m: SPTC  
50//  
for 110mm  
N = 50+

## REMARKS:

- REMARKS:
- 1) Refer to masterplan Drawing No. SK-012 dated 22/02/2019 provided by Klein.
  - 2) Hole depth specified in Water Level Readings is the bottom of the piezometric screen. Water level readings taken post drilling.
  - 3) IBHSV = In Barrel Hand Shear Vane, SPT = Standard Penetration Test, SPTC = Solid Cone Standard Penetration Test.
  - 4) Borehole locations and reduced levels were surveyed and provided Woods.
  - 5) No piezometer was installed for recording water levels.

## Water Level Readings:

**Water Level Readings:**  
**Date Time | Hole Depth | Water Level**  
 No water level recorded

Eastcliffe Phase 1  
Ground Investigation

**aurecon**

Borehole Reference: **BH47**  
Photographed By: **AD**

Date Drilled:  
Date Photographed:

27/02/2019 – 27/02/2019  
27/02/2018 – 27/02/2019



Box 1. - Depth: 0 m to 2 m.



Box 2. - Depth: 2 m to 4.5 m.



Eastcliffe Phase 1  
Ground Investigation

**aurecon**

Borehole Reference: **BH47**

Date Drilled:

27/02/2019 – 27/02/2019

Photographed By: **AD**

Date Photographed:

27/02/2018 – 27/02/2019



Box 3. - Depth: 4.5 m to 7 m.



Box 4. - Depth: 7 m to 10.5 m.



Eastcliffe Phase 1  
Ground Investigation

**aurecon**

Borehole Reference: **BH47**  
Photographed By: **AD**

Date Drilled:  
Date Photographed:

27/02/2019 – 27/02/2019  
27/02/2018 – 27/02/2019



Box 5. - Depth: 10.5 m to 14 m.



Box 6. - Depth: 14 m to 15.5 m.

<b>BOREHOLE INFORMATION</b> Method: Rotary Core Wireline Equipment: Excavator Mounted Rig Contractor: Pro-Drill Ltd	<b>CO-ORDINATES: Mt Eden Circuit 2000</b> Easting: 405585m Northing: 803225m Reduced level: 27.2m (Auckland MSL 1946 Datum)	Date started: 5/03/2019 Date completed: 5/03/2019 Inclination: 90° Azimuth: N/A	Logged by: AD Input by: AD Checked by: JME Verified by: BL
--	---	--	---

Method	R.L. (m)	Length (m)	Graphic Log	Layer Code	Material Description	Weathering/USC	Testing	TCR (%)	SCR (%)	RQD (%)	Fracture Log	Stratigraphy Defect Description Additional Notes	Installation
OB	27			Fg	0m: Silty fine GRAVEL; dark brown. Loose, moist, low plasticity [FILL].	GM						0m: FILL	
				Fc	0.2m: SILT with some fine gravel; brown. Very stiff, moist, low plasticity.	ML		80					
OB				Fx	0.5m: CORELOSS		0.5m: IBHSV UTP			24		0.5m: Core affected by drilling; shear vane result not representative.	
	1			CH	0.9m: Silty CLAY with some gravel; brown. Hard, moist, high plasticity. 1m: CLAY trace rootlets; olive brown mottled dark grey. Firm, moist, high plasticity.	CH	1m: IBHSV 200+ kPa					1m: Core affected by drilling; shear vane result not representative.	
OB	26			Fc		CH		100					
	2			Fc		CH	2m: SPT 1// 0,1,1,1 N = 3 2m: IBHSV 90/30 kPa			100			
OB				CH	2.5m: Silty CLAY; olive brown mottled dark grey. Firm, moist, high plasticity.	CH				100			
	3			CH	2.9m: Silty CLAY; brown mottled grey. Firm, moist, high plasticity.	CH	3m: SPT 0// 0,1,0,1 N = 2 3m: IBHSV 45/33 kPa			100			
OB				ERc	3.8m: Silty CLAY; brownish yellow mottled grey. Firm, moist, high plasticity [RESIDUAL ECBF]. 4.1m to 4.5m: ...with some sand, soft	CH	4m: IBHSV 60/20 kPa  4.5m: SPT 0// 0,0,0,1 N = 1			100		3.8m: EAST COAST BAYS FORMATION	
SPT	5									86			

**REMARKS:**

- 1) Refer to masterplan Drawing No. SK-012 dated 22/02/2019 provided by Klein.
- 2) Hole depth specified in Water Level Readings is the bottom of the piezometric screen. Readings taken post-drilling.
- 3) IBHSV = In Barrel Hand Shear Vane, SPT = Standard Penetration Test, SPTC = Solid Cone Standard Penetration Test.
- 4) Borehole locations and reduced levels were surveyed and provided by Woods.

**Water Level Readings:**

Date Time	Hole Depth	Water Level
(1) 06/03/19 14:30	m	3.53 m bgl
(2) 12/03/19 10:21	m	3.47 m bgl
(3) 13/03/19 11:41	m	3.38 m bgl
(4) 15/03/19 12:20	m	3.72 m bgl

**BOREHOLE INFORMATION**  
Method: Rotary Core Wireline  
Equipment: Excavator Mounted Rig  
Contractor: Pro-Drill Ltd

**CO-ORDINATES: Mt Eden Circuit 2000**  
Easting: 405585m  
Northing: 803225m  
Reduced level: 27.2m  
(Auckland MSL 1946 Datum)

Date started: 5/03/2019  
Date completed: 5/03/2019  
Inclination: 90°  
Azimuth: N/A

Logged by: AD  
Input by: AD  
Checked by: JME  
Verified by: BL

Method	R.L. (m)	Length (m)	Graphic Log	Layer Code	Material Description	Weathering/USC	Testing	TCR (%)	SCR (%)	RQD (%)	Fracture Log	Stratigraphy Defect Description Additional Notes	Installation
OB	22			ERc	3.8m: Silty CLAY; brownish yellow mottled grey. Firm, moist, high plasticity [RESIDUAL ECBF].	CH							
SPT	21	6			5.5m: Silty CLAY; grey. Stiff, moist, high plasticity.	CH	6m: SPT 2// 2,1,2,2 N = 7 6m: IBHSV 76/20 kPa	86					
OB	7			ERz	6.5m: Completely weathered, grey, SILTSTONE. Extremely weak (very stiff) [Completely weathered].								
SPT	20				7.1m to 7.2m:....black carbonaceous material	CW	7.5m: SPT 5// 4,4,5,6 N = 19 7.5m: IBHSV 200+ kPa	100	100	100			
HQ3	8				7.95m: Highly weathered, grey, SILTSTONE. Extremely weak (hard).	HW		100	100	100			
HQ3	19				8.5m: Moderately weathered, grey, fine to medium SANDSTONE. Extremely weak (hard).	MW		99	100	72			
SPTC	18				9.55m: Slightly weathered, grey, SILTSTONE. Very weak.	SW	9.5m: SPTC 13// 10,12,12,16 for 65mm N = 50+	N/A					
	10							100	100	100			

**REMARKS:**

- 1) Refer to masterplan Drawing No. SK-012 dated 22/02/2019 provided by Klein.
- 2) Hole depth specified in Water Level Readings is the bottom of the piezometric screen. Readings taken post-drilling.
- 3) IBHSV = In Barrel Hand Shear Vane, SPT = Standard Penetration Test, SPTC = Solid Cone Standard Penetration Test.
- 4) Borehole locations and reduced levels were surveyed and provided by Woods.

**Water Level Readings:**

Date Time	Hole Depth	Water Level
(1) 06/03/19 14:30	m	3.53 m bgl
(2) 12/03/19 10:21	m	3.47 m bgl
(3) 13/03/19 11:41	m	3.38 m bgl
(4) 15/03/19 12:20	m	3.72 m bgl



<b>BOREHOLE INFORMATION</b> Method: Rotary Core Wireline Equipment: Excavator Mounted Rig Contractor: Pro-Drill Ltd	<b>CO-ORDINATES: Mt Eden Circuit 2000</b> Easting: 405585m Northing: 803225m Reduced level: 27.2m (Auckland MSL 1946 Datum)	Date started: 5/03/2019 Date completed: 5/03/2019 Inclination: 90° Azimuth: N/A	Logged by: AD Input by: AD Checked by: JME Verified by: BL
--	---	--	---

Method	R.L. (m)	Length (m)	Graphic Log	Layer Code	Material Description	Weathering/USC	Testing	TCR (%)	SCR (%)	RQD (%)	Fracture Log	Stratigraphy Defect Description Additional Notes	Installation
HQ3	17		XXXXXX	EUz	9.55m: Slightly weathered, grey, SILTSTONE. Very weak.	SW					TMS WS MMS CS VCS ECS		
			XXXXXX	EUs	10.3m: Slightly weathered, grey, fine to medium SANDSTONE. Very weak.	SW		100	100	100			
SPTC	16		XXXXXX	EUz	10.7m to 10.8m:....medium to coarse SANDSTONE 10.8m: Slightly weathered, grey, SILTSTONE. Very weak.	SW	11m: SPTC 14// 8,9,17,16 for 40mm N = 50+	N/A					
			XXXXXX	EUs	11.5m: Slightly weathered, grey, fine to medium SANDSTONE. Very weak.	SW	100	100	78				
SPTC	13		XXXXXX	EUz	12m: Slightly weathered, grey SILTSTONE. Very weak.  12.4m to 12.5m:....black carbonaceous material	SW	12.5m: SPTC 21// 12,12,10,12 N = 46	N/A					
			XXXXXX	EUz		SW	100	100	100				
HQ3	14		XXXXXX	EUz		SW	14m: SPTC 50// for 110mm N = 50+	N/A					
			XXXXXX	EUs	14.3m: Slightly weathered, grey, fine to medium SANDSTONE. Weak.		SW	100	100	80			
HQ3	15		XXXXXX	EUz		SW							
			XXXXXX	EUs									

**REMARKS:**

- 1) Refer to masterplan Drawing No. SK-012 dated 22/02/2019 provided by Klein.
- 2) Hole depth specified in Water Level Readings is the bottom of the piezometric screen. Readings taken post-drilling.
- 3) IBHSV = In Barrel Hand Shear Vane, SPT = Standard Penetration Test, SPTC = Solid Cone Standard Penetration Test.
- 4) Borehole locations and reduced levels were surveyed and provided by Woods.

**Water Level Readings:**

Date Time	Hole Depth	Water Level
(1) 06/03/19 14:30	m	3.53 m bgl
(2) 12/03/19 10:21	m	3.47 m bgl
(3) 13/03/19 11:41	m	3.38 m bgl
(4) 15/03/19 12:20	m	3.72 m bgl

<b>BOREHOLE INFORMATION</b> Method: Rotary Core Wireline Equipment: Excavator Mounted Rig Contractor: Pro-Drill Ltd	<b>CO-ORDINATES: Mt Eden Circuit 2000</b> Easting: 405585m Northing: 803225m Reduced level: 27.2m (Auckland MSL 1946 Datum)	Date started: 5/03/2019 Date completed: 5/03/2019 Inclination: 90° Azimuth: N/A	Logged by: AD Input by: AD Checked by: JME Verified by: BL
--	---	--	---

Method	R.L. (m)	Length (m)	Graphic Log	Layer Code	Material Description	Weathering/USC	Testing	TCR (%)	SCR (%)	RQD (%)	Fracture Log	Stratigraphy Defect Description Additional Notes	Installation
HQ3	12		x x x x x	EUz	15m: Slightly weathered, grey, SILTSTONE. Weak.	SW		100	100	80	VWS WS MS CS VCS ES3		
SPTC			x x x x x	EUz	15.5m: Slightly weathered, grey, fine to medium SANDSTONE. Weak.	SW	15.5m: SPTC 50// for 90mm N = 50+	N/A					
HQ3	11		x x x x x	EUz	16m: Slightly weathered, grey, SILTSTONE. Weak.	SW		100	100	90			
SPTC	17		x x x x x	EUz	End of borehole at 17.09m (Target Depth)		17m: SPTC 50// for 90mm N = 50+	N/A					

<b>REMARKS:</b> 1) Refer to masterplan Drawing No. SK-012 dated 22/02/2019 provided by Klein. 2) Hole depth specified in Water Level Readings is the bottom of the piezometric screen. Readings taken post-drilling. 3) IBHSV = In Barrel Hand Shear Vane, SPT = Standard Penetration Test, SPTC = Solid Cone Standard Penetration Test. 4) Borehole locations and reduced levels were surveyed and provided by Woods.	<b>Water Level Readings:</b> Date Time   Hole Depth   Water Level (1) 06/03/19 14:30   m   3.53 m bgl (2) 12/03/19 10:21   m   3.47 m bgl (3) 13/03/19 11:41   m   3.38 m bgl (4) 15/03/19 12:20   m   3.72 m bgl
--	--

Eastcliffe Phase 1  
Ground Investigation

**aurecon**

Borehole Reference: **BH48**

Date Drilled:

05/03/2019 – 05/03/2019

Photographed By: **AD**

Date Photographed:

05/03/2019 – 05/03/2019



Box 1. - Depth: 0 m to 2.5 m.



Box 2. - Depth: 2.5 m to 4.5 m.



Eastcliffe Phase 1  
Ground Investigation

**aurecon**

Borehole Reference: **BH48**

Date Drilled:

05/03/2019 – 05/03/2019

Photographed By: **AD**

Date Photographed:

05/03/2019 – 05/03/2019



Box 3. - Depth: 4.5 m to 7 m.



Box 4. - Depth: 7 m to 9 m.

Eastcliffe Phase 1  
Ground Investigation

**aurecon**

Borehole Reference: **BH48**

Date Drilled:

05/03/2019 – 05/03/2019


Photographed By: **AD**

Date Photographed:

05/03/2019 – 05/03/2019



Box 5. - Depth: 9 m to 13 m.



Box 6. - Depth: 13 m to 16 m.

**Eastcliffe Phase 1  
Ground Investigation**

**aurecon**

Borehole Reference: **BH48**

Date Drilled:

**05/03/2019 – 05/03/2019**

Photographed By: **AD**

Date Photographed:

**05/03/2019 – 05/03/2019**



**Box 7. - Depth: 16 m to 17 m.**



<b>BOREHOLE INFORMATION</b> Method: Rotary Core Wireline Equipment: Excavator Mounted Rig Contractor: Pro-Drill Ltd	<b>CO-ORDINATES: Mt Eden Circuit 2000</b> Easting: 405581m Northing: 803209m Reduced level: 27.4m (Auckland MSL 1946 Datum)	Date started: 27/02/2019 Date completed: 27/02/2019 Inclination: 90° Azimuth: N/A	Logged by: AD Input by: AD Checked by: JME Verified by: BL
--	---	--	---

Method	R.L. (m)	Length (m)	Graphic Log	Layer Code	Material Description	Weathering/USC	Testing	TCR (%)	SCR (%)	RQD (%)	Stratigraphy Defect Description Additional Notes	Installation
SSA	27				0m: CORELOSS			0			0m: No material recovered from auger; drillers noted gravel between 0-0.6m.	
OB	1			Fc	0.9m: CLAY; dark green mottled dark grey. Firm, moist, high plasticity.	CH		100			0.9m: FILL	
SPT	26				1.2m: CLAY brownish yellow mottled grey. Stiff, moist, high plasticity [RESIDUAL ECBF].		1.5m: SPT 2// 1,1,2,2 N = 6 1.5m: IBHSV 195/105 kPa	89			1.2m: EAST COAST BAYS FORMATION	
OB	25					CH		86				
SPT	24				2.8m to 3.9m: ...Stiff		3m: SPT 1// 1,0,1,1 N = 3 3m: IBHSV 75/42 kPa	100				
OB	23				3.9m: Silty CLAY with some sand; brownish yellow mottled grey. Firm, moist, low plasticity.	CL		76				
SPT	22				4.5m: Silty SAND; grey mottled brownish yellow. Very loose, moist.	SM	4.5m: SPT 0// 0,0,0,0 N = 0	100				
	21							64				

**REMARKS:**

- 1) Refer to masterplan Drawing No. SK-012 dated 22/02/2019 provided by Klein.
- 2) Hole depth specified in Water Level Readings is the bottom of the piezometric screen. Water level readings taken post drilling.
- 3) IBHSV = In Barrel Hand Shear Vane, SPT = Standard Penetration Test, SPTC = Solid Cone Standard Penetration Test, SSA = Solid Stem Auger.
- 4) Borehole locations and reduced levels were surveyed and provided Woods.
- 5) No piezometer was installed for recording water levels.

**Water Level Readings:**

Date Time | Hole Depth | Water Level  
No water level recorded

<b>BOREHOLE INFORMATION</b> Method: Rotary Core Wireline Equipment: Excavator Mounted Rig Contractor: Pro-Drill Ltd	<b>CO-ORDINATES: Mt Eden Circuit 2000</b> Easting: 405581m Northing: 803209m Reduced level: 27.4m (Auckland MSL 1946 Datum)	Date started: 27/02/2019 Date completed: 27/02/2019 Inclination: 90° Azimuth: N/A	Logged by: AD Input by: AD Checked by: JME Verified by: BL
--	---	--	---

Method	R.L. (m)	Length (m)	Graphic Log	Layer Code	Material Description	Weathering/USC	Testing	TCR (%)	SCR (%)	RQD (%)	Stratigraphy Defect Description Additional Notes	Installation
OB	22		[Graphic Log: Silty SAND]	ERs	4.5m: Silty SAND; grey mottled brownish yellow. Very loose, moist.	SM	6m: SPT 2// 1,1,1,1 N = 4 6m: IBHSV 81/27 kPa	65				
	6				5.9m to 6.9m: ...grey, loose to medium dense				100			
SPT	21											
OB	7		[Graphic Log: SILTSTONE]	EWz	6.9m: Highly weathered, grey, SILTSTONE. Extremely weak (very stiff); widely spaced [Highly weathered ECBF].	HW	7.5m: SPTC 7// 4,7,6,8 N = 25 7.5m: IBHSV UTP	100				
	20											
SPTC	8								N/A			
HQ3	19		[Graphic Log: SANDSTONE]	EWs	8.1m: Moderately weathered, grey, fine to medium SANDSTONE. Very weak.	MW		100				
				EWz	8.3m: Moderately weathered, grey, SILTSTONE. Very weak.	MW						
				EWs	8.8m: Moderately weathered, grey, fine to medium SANDSTONE. Very weak.	MW		100				
	9											
SPTC	18		[Graphic Log: SILTSTONE]	EWz	9.1m: Moderately weathered, grey, SILTSTONE. Very weak. 9.15m to 9.3m: ...black carbonaceous material.	MW	9.5m: SPTC 9// 8,7,8,10 N = 33					
	10							N/A				

**REMARKS:**

- 1) Refer to masterplan Drawing No. SK-012 dated 22/02/2019 provided by Klein.
- 2) Hole depth specified in Water Level Readings is the bottom of the piezometric screen. Water level readings taken post drilling.
- 3) IBHSV = In Barrel Hand Shear Vane, SPT = Standard Penetration Test, SPTC = Solid Cone Standard Penetration Test, SSA = Solid Stem Auger.
- 4) Borehole locations and reduced levels were surveyed and provided Woods.
- 5) No piezometer was installed for recording water levels.

**Water Level Readings:**

Date Time | Hole Depth | Water Level  
No water level recorded

## BOREHOLE INFORMATION

Method: Rotary Core Wireline  
Equipment: Excavator Mounted Rig  
Contractor: Pro-Drill Ltd

**CO-ORDINATES: Mt Eden Circuit 2000**

Easting: 405581m  
Northing: 803209m  
Reduced level: 27.4m  
(Auckland MSL 1946 Datum)

Date started: 27/02/2019  
Date completed: 27/02/2019  
Inclination: 90°  
Azimuth: N/A

Logged by: AD  
 Input by: AD  
 Checked by: JME  
 Verified by: BL

[illegible]

## REMARKS:

- 1) Refer to masterplan Drawing No. SK-012 dated 22/02/2019 provided by Klein.
- 2) Hole depth specified in Water Level Readings is the bottom of the piezometric screen. Water level readings taken post drilling.
- 3) IBHSV = In Barrel Hand Shear Vane, SPT = Standard Penetration Test, SPTC = Solid Cone Standard Penetration Test, SSA = Solid Stem Auger.
- 4) Borehole locations and reduced levels were surveyed and provided Woods.
- 5) No piezometer was installed for recording water levels.

<b>Water Level Readings:</b>
------------------------------

Date	Time	Hole Depth	Water Level
No water level recorded			



<b>BOREHOLE INFORMATION</b>		<b>CO-ORDINATES: Mt Eden Circuit 2000</b>		Date started:	27/02/2019	Logged by:	AD
Method: Rotary Core Wireline		Easting: 405581m		Date completed:	27/02/2019	Input by:	AD
Equipment: Excavator Mounted Rig		Northing: 803209m		Inclination:	90°	Checked by:	JME
Contractor: Pro-Drill Ltd		Reduced level: 27.4m		Azimuth:	N/A	Verified by:	BL
		(Auckland MSL 1946 Datum)					

Method	R.L. (m)	Length (m)	Graphic Log	Layer Code	Material Description	Weathering/USC	Testing	TCR (%)	SCR (%)	RQD (%)	Stratigraphy Defect Description Additional Notes	Installation
HQ3	12			EUs	14.5m: Slightly weathered, grey, fine to medium SANDSTONE. Very weak.	SW		93	100	97		
SPTC					End of borehole at 15.61m (Target Depth)		15.5m: SPTC 50// for 110mm N = 50+	N/A				

**REMARKS:**  
 1) Refer to masterplan Drawing No. SK-012 dated 22/02/2019 provided by Klein.  
 2) Hole depth specified in Water Level Readings is the bottom of the piezometric screen. Water level readings taken post drilling.  
 3) IBHSV = In Barrel Hand Shear Vane, SPT = Standard Penetration Test, SPTC = Solid Cone Standard Penetration Test, SSA = Solid Stem Auger.  
 4) Borehole locations and reduced levels were surveyed and provided Woods.  
 5) No piezometer was installed for recording water levels.

**Water Level Readings:**  
 Date Time | Hole Depth | Water Level  
 No water level recorded

Eastcliffe Phase 1  
Ground Investigation

**aurecon**

Borehole Reference: **BH49**  
Photographed By: **AD**

Date Drilled:  
Date Photographed:

05/03/2019 – 05/03/2019  
05/03/2019 – 05/03/2019



Box 1. - Depth: 0 m to 3.5 m.



Box 2. - Depth: 3.5 m to 6.5 m.



Eastcliffe Phase 1  
Ground Investigation

**aurecon**

Borehole Reference: **BH49**

Date Drilled:

05/03/2019 – 05/03/2019

Photographed By: **AD**

Date Photographed:

05/03/2019 – 05/03/2019



Box 3. - Depth: 6.5 m to 9.5 m.



Box 4. - Depth: 9.5 m to 13.5 m.



**Eastcliffe Phase 1  
Ground Investigation**

**aurecon**

Borehole Reference: **BH49**

Date Drilled:

**05/03/2019 – 05/03/2019**

Photographed By: **AD**

Date Photographed:

**05/03/2019 – 05/03/2019**



**Box 5. - Depth: 13.5 m to 15.5 m.**

<b>BOREHOLE INFORMATION</b> Method: Rotary Core Wireline Equipment: Excavator Mounted Rig Contractor: Pro-Drill Ltd	<b>CO-ORDINATES: Mt Eden Circuit 2000</b> Easting: 405558m Northing: 803178m Reduced level: 29.1m (Auckland MSL 1946 Datum)	Date started: 7/03/2019 Date completed: 7/03/2019 Inclination: 90° Azimuth: N/A	Logged by: AD Input by: AD Checked by: JME Verified by: BL
--	---	--	---

Method	R.L. (m)	Length (m)	Graphic Log	Layer Code	Material Description	Weathering/USC	Testing	TCR (%)	SCR (%)	RQD (%)	Stratigraphy Defect Description Additional Notes	Installation
OB	29			Fx	0m: CORELOSS						0m: Driller noted that material may have been compressed.	
				Fc	0.3m: SILT with some gravel; dark brown. Stiff, moist, low plasticity.	ML		40			0.3m: FILL	
OB				ERz	0.4m: Clayey SILT with some gravel; dark brown. Firm, moist, low plasticity [RESIDUAL ECBF].	ML		90			0.4m: EAST COAST BAYS FORMATION	
					0.8m: Silty CLAY; brownish yellow mottled grey. Very stiff, high plasticity.	CH						
OB	28				1m: Sandy CLAY with some silt; brownish yellow mottled grey. Stiff, moist, low plasticity.	CL	1m: IBHSV 127/60 kPa					
					1.2m: CLAY; brownish yellow mottled grey. Stiff, moist, high plasticity.	CH		100				
					1.5m: Sandy CLAY with some silt; brownish yellow mottled grey. Stiff, moist, low plasticity.	CL						
					1.7m: Silty CLAY; brownish yellow mottled grey. Soft, moist, high plasticity. Locally stiff.		2m: SPT 0// 0,0,0,0 N = 0 2m: IBHSV 67/21 kPa	100				
SPT	27											
OB				ERc				100				
					3m to 4.2m: ...grey	SM	3m: SPT 0// 0,1,1,1 N = 3 3m: IBHSV 48/15 kPa	100				
SPT	26											
OB								97				
					4.1m to 4.2m: ...black carbonaceous material							
					4.2m: Silty CLAY with some sand; grey. Very stiff, moist, low plasticity.	CL					4.2m to 4.2m: 0° UnRo Black carbonaceous material	
SPT				ERs	4.6m: Clayey SAND; grey. Loose, moist, low plasticity.	SC	4.5m: SPT 2// 2,2,2,3 N = 9 4.5m: IBHSV 108/30 kPa	100				
	5							86				

REMARKS:  
1) Refer to masterplan Drawing No. SK-012 dated 22/02/2019 provided by Klein.  
2) Hole depth specified in Water Level Readings is the bottom of the piezometric screen. Readings taken post-drilling.  
3) IBHSV = In Barrel Hand Shear Vane, SPT = Standard Penetration Test, SPTC = Solid Cone Standard Penetration Test.  
4) Borehole locations and reduced levels were surveyed and provided by Woods.

**Water Level Readings:**  
Date Time | Hole Depth | Water Level  
No water level recorded

<b>BOREHOLE INFORMATION</b> Method: Rotary Core Wireline Equipment: Excavator Mounted Rig Contractor: Pro-Drill Ltd	<b>CO-ORDINATES: Mt Eden Circuit 2000</b> Easting: 405558m Northing: 803178m Reduced level: 29.1m (Auckland MSL 1946 Datum)	Date started: 7/03/2019 Date completed: 7/03/2019 Inclination: 90° Azimuth: N/A	Logged by: AD Input by: AD Checked by: JME Verified by: BL
--	---	--	---

Method	R.L. (m)	Length (m)	Graphic Log	Layer Code	Material Description	Weathering/USC	Testing	TCR (%)	SCR (%)	RQD (%)	Stratigraphy Defect Description Additional Notes	Installation
OB	24			ERs	4.6m: Clayey SAND; grey. Loose, moist, low plasticity.	SC						
					5.4m: Highly weathered, grey, SILTSTONE. Extremely weak (hard) [Highly weathered ECBF].			86				
SPTC		6		EWz		HW	6m: SPTC 9// 5,6,6,6 N = 23	N/A				
OB	23				6.5m: Moderately weathered, grey, SILTSTONE. Very weak.			100				
						MW						
HQ3	22			EWs	7.3m: Moderately weathered, grey, fine to medium SANDSTONE. Weak.	MW		100	100	92		
					7.7m: Moderately weathered, grey, SILTSTONE. Weak.							
	8			EWz		MW	8m: SPTC 12// 8,6,5,7 N = 26	N/A				
SPTC	21				8.5m: Moderately weathered, grey, fine to medium SANDSTONE. Very weak.							
				EWs		MW		88	100	100		
	9											
	20				9.6m: Moderately weathered, grey, SILTSTONE. Very weak.							
				EWz		MW	9.5m: SPTC 19// 17,16,11,6 for 30mm N = 50+	N/A				
								100	100	85		
	10											

**REMARKS:**

- 1) Refer to masterplan Drawing No. SK-012 dated 22/02/2019 provided by Klein.
- 2) Hole depth specified in Water Level Readings is the bottom of the piezometric screen. Readings taken post-drilling.
- 3) IBHSV = In Barrel Hand Shear Vane, SPT = Standard Penetration Test, SPTC = Solid Cone Standard Penetration Test.
- 4) Borehole locations and reduced levels were surveyed and provided by Woods.

**Water Level Readings:**

Date Time | Hole Depth | Water Level  
No water level recorded



**BOREHOLE INFORMATION**  
Method: Rotary Core Wireline  
Equipment: Excavator Mounted Rig  
Contractor: Pro-Drill Ltd

**CO-ORDINATES: Mt Eden Circuit 2000**  
Easting: 405558m  
Northing: 803178m  
Reduced level: 29.1m  
(Auckland MSL 1946 Datum)

Date started: 7/03/2019  
Date completed: 7/03/2019  
Inclination: 90°  
Azimuth: N/A

Logged by: AD  
Input by: AD  
Checked by: JME  
Verified by: BL

Method	R.L. (m)	Length (m)	Graphic Log	Layer Code	Material Description	Weathering/USC	Testing	TCR (%)	SCR (%)	RQD (%)	Stratigraphy Defect Description Additional Notes	Installation
HQ3	19		x x x x	EWz	9.6m: Moderately weathered, grey, SILTSTONE. Very weak.	MW		100	100	85		
SPTC	18		x x x x		11m to 13.5m: ...extremely weak (hard)		11m: SPTC 8// 5,5,6,9 N = 25	N/A				
HQ3	17		x x x x					100	100	100		
SPTC	13		x x x x				12.5m: SPTC 12// 7,7,6,12 N = 32	N/A				
HQ3	16		x x x x	EUz	13.5m: Slightly weathered, grey, SILTSTONE. Very weak.	SW		100	100	63		
SPTC	15		x x x x				14m: SPTC 27// 23,27 for 75mm N = 50+	N/A				
HQ3			.....	EUs	14.3m: Slightly weathered, grey, medium to coarse SANDSTONE. Weak.	SW		100	100	100		
	15		x x x x	EUz	14.8m: Slightly weathered, grey, SILTSTONE. Weak.	SW						

**REMARKS:**

- 1) Refer to masterplan Drawing No. SK-012 dated 22/02/2019 provided by Klein.
- 2) Hole depth specified in Water Level Readings is the bottom of the piezometric screen. Readings taken post-drilling.
- 3) IBHSV = In Barrel Hand Shear Vane, SPT = Standard Penetration Test, SPTC = Solid Cone Standard Penetration Test.
- 4) Borehole locations and reduced levels were surveyed and provided by Woods.

**Water Level Readings:**  
Date Time | Hole Depth | Water Level  
No water level recorded

### BOREHOLE INFORMATION

Method: Rotary Core Wireline  
Equipment: Excavator Mounted Rig  
Contractor: Pro-Drill Ltd

**CO-ORDINATES: Mt Eden Circuit 2000**

Easting: 405558m  
 Northing: 803178m  
 Reduced level: 29.1m  
 (Auckland MSL 1946 Datum)

Date started: 7/03/2019  
Date completed: 7/03/2019  
Inclination: 90°  
Azimuth: N/A

Logged by: AD  
 Input by: AD  
 Checked by: JME  
 Verified by: BL

(Auckland MSL 1946 Datum)												
Method	R.L. (m)	Length (m)	Graphic Log	Layer Code	Material Description	Weathering/USC	Testing	TCR (%)	SCR (%)	RQD (%)	Stratigraphy Defect Description Additional Notes	Installation
HQ3	14		x x									

## REMARKS:

- REMARKS:
- 1) Refer to masterplan Drawing No. SK-012 dated 22/02/2019 provided by Klein.
  - 2) Hole depth specified in Water Level Readings is the bottom of the piezometric screen. Readings taken post-drilling.
  - 3) IBHSV = In Barrel Hand Shear Vane, SPT = Standard Penetration Test, SPTC = Solid Cone Standard Penetration Test.
  - 4) Borehole locations and reduced levels were surveyed and provided by Woods.

## Water Level Readings:

**Water Level Readings:**  
**Date Time | Hole Depth | Water Level**  
 No water level recorded

Eastcliffe Phase 1  
Ground Investigation

**aurecon**

Borehole Reference: **BH50**  
Photographed By: **AD**

Date Drilled:  
Date Photographed:

07/03/2019 – 07/03/2019  
07/03/2019 – 07/03/2019



Box 1. - Depth: 0 m to 2.5 m.



Box 2. - Depth: 2.5 m to 4.5 m.



Eastcliffe Phase 1  
Ground Investigation

**aurecon**

Borehole Reference: **BH50**

Date Drilled:

07/03/2019 – 07/03/2019

Photographed By: **AD**

Date Photographed:

07/03/2019 – 07/03/2019



Box 3. - Depth: 4.5 m to 8 m.



Box 4. - Depth: 8 m to 12 m.

Eastcliffe Phase 1  
Ground Investigation

**aurecon**

Borehole Reference: **BH50**

Date Drilled:

07/03/2019 – 07/03/2019

Photographed By: **AD**

Date Photographed:

07/03/2019 – 07/03/2019




Box 5. - Depth: 12 m to 17 m.



Box 6. - Depth: 17 m to 17.5 m.

Classification by  
Robertson 1986

Clay (3)
Silty clay to clay (4)
Clayey silt to silty clay (5)
Sandy silt to clayey silt (6)
Silty sand to sandy silt (7)
Sand to silty sand (8)



**PRO-DRILL**  
GEOTECHNICAL CONSULTING




Cone No: S10CFIIP.S14547  
Tip area [cm<sup>2</sup>]: 10  
Sleeve area [cm<sup>2</sup>]: 150

Location: Orakei	Position: X: 0 m, Y: 0 m	Ground level: 0.000	Test No.: CPT06
Project ID: Aurecon Eastcliffe 25523	Client: Aurecon	Date: 3/04/2018	Scale: 1 : 87
Project: Aurecon Eastcliffe 25523		Page: 1/1	Fig.:
		File: Aurecon Eastcliffe 25523_CPT06.G	



Classification by  
Robertson 1986

Clay (3)
Silty clay to clay (4)
Clay (3)
Clayey silt to silty clay (5)
Sandy silt to clayey silt (6)
Silty sand to sandy silt (7)
Sand to silty sand (8)
Silty sand to sandy silt (7)
Sand to silty sand (8)




PRO-DRILL

Cone No: S10CFIIP.S14547  
Tip area [cm<sup>2</sup>]: 10  
Sleeve area [cm<sup>2</sup>]: 150

Location:	Orakei	Position:	X: 0 m, Y: 0 m	Ground level:	0.000	Test No.:	CPT07
Project ID:	Aurecon Eastcliffe 25523	Client:	Aurecon	Date:	3/04/2018	Scale:	1 : 87
Project:	Aurecon Eastcliffe 25523			Page:	1/1	Fig.:	
				File:	Aurecon Eastcliffe 25523_CPT07.GEF		

Classification by  
Robertson 1986

- Clay (3)
- Silty clay to clay (4)
- Clay (3)
- Sensitive fine grained (1)
- Silty clay to clay (4)
- Clayey silt to silty clay (5)
- Sandy silt to clayey silt (6)
- Silty sand to sandy silt (7)



**PRO-DRILL**  
GEOTECHNICAL TESTING EQUIPMENT




Cone No: S10CFIIP.S14547  
Tip area [cm<sup>2</sup>]: 10  
Sleeve area [cm<sup>2</sup>]: 150

Location: Orakei	Position: X: 0 m, Y: 0 m	Ground level: 0.000	Test No.: CPT08
Project ID: Aurecon Eastcliffe 25523	Client: Aurecon	Date: 3/04/2018	Scale: 1 : 87
Project: Aurecon Eastcliffe 25523		Page: 1/1	Fig.:
		File: Aurecon Eastcliffe 25523_CPT08.G	

Classification by  
Robertson 1986

	Sandy silt to clayey silt (6)
	Clay (3)
	Silty clay to clay (4)
	Clay (3)
	Silty clay to clay (4)
	Clayey silt to silty clay (5)
	Sandy silt to clayey silt (6)
	Silty sand to sandy silt (7)
	Sand to silty sand (8)
	Silty sand to sandy silt (7)
	Sand to silty sand (8)



**PRO-DRILL**  
GEOTECHNICAL TESTING EQUIPMENT



Cone No: S10CFIIP.S14547  
Tip area [cm²]: 10  
Sleeve area [cm²]: 150

Location: Orakei	Position: X: 0 m, Y: 0 m	Ground level: 0.000	Test No.: CPT09
Project ID: Aurecon Eastcliffe 25523	Client: Aurecon	Date: 3/04/2018	Scale: 1 : 87
Project: Aurecon Eastcliffe 25523		Page: 1/1	Fig.:
		File: Aurecon Eastcliffe 25523_CPT09.G	



Classification by  
Robertson 1986




Clay (3)

Clayey silt to silty clay (5)

Sandy silt to clayey silt (6)

Silty sand to sandy silt (7)

Sand to silty sand (8)





**PRO-DRILL**  
GEOTECHNICAL TESTING & ANALYSIS



Cone No: S10CFIIP.S14547  
Tip area [cm<sup>2</sup>]: 10  
Sleeve area [cm<sup>2</sup>]: 150

Location: Orakei	Position: X: 0 m, Y: 0 m	Ground level: 0.000	Test No.: CPT10
Project ID: Aurecon Eastcliffe 25523	Client: Aurecon	Date: 3/04/2018	Scale: 1 : 87
Project: Aurecon Eastcliffe 25523		Page: 1/1	Fig.:
		File: Aurecon Eastcliffe 25523_CPT10.G	

Classification by  
Robertson 1986





**PRO-DRILL**

Cone No: S10CFIIP.S14547  
Tip area [cm<sup>2</sup>]: 10  
Sleeve area [cm<sup>2</sup>]: 150

Location:	Orakei	Position:	X: 0 m, Y: 0 m	Ground level:	0.000	Test No.:	CPT11
Project ID:	Aurecon Eastcliffe 25523	Client:	Aurecon	Date:	3/04/2018	Scale:	1 : 87
Project:	Aurecon Eastcliffe 25523			Page:	1/1	Fig.:	
				File:	Aurecon Eastcliffe 25523_CPT11.GEF		

Classification by  
Robertson 1986



PRO-DRILL

Cone No: S10CFIIP.S14547  
Tip area [cm<sup>2</sup>]: 10  
Sleeve area [cm<sup>2</sup>]: 150

Location: Orakei	Position: X: 0 m, Y: 0 m	Ground level: 0.000	Test No.: CPT12
Project ID: Aurecon Eastcliffe 25523	Client: Aurecon	Date: 3/04/2018	Scale: 1 : 87
Project: Aurecon Eastcliffe 25523		Page: 1/1	Fig.:
		File: Aurecon Eastcliffe 25523_CPT12.G	



# BOREHOLE LOG

BOREHOLE No.:

**BH01**

SHEET: 1 OF 2

DRILLED BY: SCZH

LOGGED BY: SCZH

CHECKED: RXSW

START DATE: 09/06/2025

FINISH DATE: 09/06/2025

CONTRACTOR: SCZH

PROJECT: The Point Development

JOB No.: 1098049.0000

LOCATION: 52-64 Rukutai Street

CO-ORDINATES: 5920109 mN  
(NZTM2000) 1762714 mE

DIRECTION:  
ANGLE FROM HORIZ.: -90°

R.L. GROUND: 38.3m

R.L. COLLAR:

DATUM: NZVD2016

SURVEY: Handheld GPS

GEOLOGICAL UNIT	MATERIAL DESCRIPTION	Rock Weathering	Rock Strength	Sampling Method	Core Recovery (%)	Testing	RL (m)	Depth (m)	Graphic Log	ROCK MASS DISCONTINUITIES				Description & Additional Observations	Water Level / Fluid Loss (%)	Casing	Installation	Core Box No
										Defect Log	Fracture Spacing (mm)	RQD (%)						
Fill	0.00m: Silty fine to medium GRAVEL; light grey mottled brown. Loosely packed, moist. [FILL].							38										
								0.5										
Residual East Coast Bays Formation	0.65m: Silty CLAY; yellowish brown mottled light grey. Stiff to very stiff, moist, high plasticity. [RESIDUAL ECBF].							1.0										
								1.5										
								2.0										
	2.10m: CLAY, some silt; brownish grey. Stiff, moist, high plasticity.							2.5										
	2.40m: SILT, some sand, trace clay; grey and brownish grey. Very stiff, moist to wet, non-plastic to low plasticity. Sand, fine.							3.0										
East Coast Bays Formation	2.75m: CLAY, some silt; grey. Stiff, moist, high plasticity.							3.5										
	3.00m: SILT, some sand, trace clay; dark grey. Hard, moist to wet, non-plastic to low plasticity. Sand, fine.							4.0										
	3.45m: Highly to completely weathered, dark grey, SANDSTONE. Extremely weak. Recovered as: Silty fine SAND; dark grey. Hard, wet. [HW ECBF].							4.5										
East Coast Bays Formation	3.85 - 3.90m: Crush zone																	
	4.88m: Unweathered to slightly weathered, dark grey,																	

COMMENTS:

Hole Depth  
9.15m

Scale 1:25

Rev.: A

Rev.: A

# CORE PHOTOS

BOREHOLE No.: <b>BH01</b>
Hole Location: 52-64 Rukutai Street
SHEET: 1 OF 2

PROJECT: The Point Development	LOCATION: 110-160 Rukutai Street	JOB No.: 1098049.0000
CO-ORDINATES: 5920109 mN (NZTM2000) 1762714 mE	DRILL TYPE: MST-600VD	HOLE STARTED: 09/06/2025
R.L.: 38.3m	METHOD: Rotary cored	HOLE FINISHED: 09/06/2025
DATUM: NZVD2016		DRILLED BY: SCZH
		LOGGED BY: SCZH
		CHECKED: RXSW



0.00-3.65m



3.65-6.80m



# CORE PHOTOS

BOREHOLE No.: <b>BH01</b>
Hole Location: 52-64 Rukutai Street
SHEET: 2 OF 2

PROJECT: The Point Development	LOCATION: 110-160 Rukutai Street	JOB No.: 1098049.0000
CO-ORDINATES: 5920109 mN (NZTM2000) 1762714 mE	DRILL TYPE: MST-600VD	HOLE STARTED: 09/06/2025
R.L.: 38.3m	METHOD: Rotary cored	HOLE FINISHED: 09/06/2025
DATUM: NZVD2016		DRILLED BY: SCZH
		LOGGED BY: SCZH
		CHECKED: RXSW



6.80-9.00m

# BOREHOLE LOG

BOREHOLE No.:

**BH02**

SHEET: 1 OF 3

DRILLED BY: SCZH

LOGGED BY: SCZH

CHECKED: RXSW

START DATE: 10/06/2025

FINISH DATE: 10/06/2025

CONTRACTOR: SCZH

PROJECT: The Point Development

JOB No.: 1098049.0000

LOCATION: 82 Aotea Street

CO-ORDINATES: 5920110 mN  
(NZTM2000) 1762965 mE

DIRECTION:

ANGLE FROM HORIZ.: -90°

R.L. GROUND: 16.6m

R.L. COLLAR:

DATUM: NZVD2016

SURVEY: Handheld GPS

GEOLOGICAL UNIT	MATERIAL DESCRIPTION  SOIL: Classification, colour, consistency / density, moisture, plasticity ROCK: Weathering, colour, fabric, name, strength, cementation	Rock Weathering <div>UW SW HW VW CW RW</div>	Rock Strength <div>UCS σ<sub>1</sub> σ<sub>3</sub> σ<sub>2</sub> σ<sub>1</sub> σ<sub>3</sub> σ<sub>2</sub> σ<sub>1</sub></div>	Sampling Method Core Recovery (%)	Testing	RL (m)	Depth (m)	Graphic Log	ROCK MASS DISCONTINUITIES				Description & Additional Observations	Water Level / Fluid Loss (%) <div>25 50 75</div>	Casing	Installation	Core Box No
									Defect Log	Fracture Spacing (mm) <div>2000 1000 500 200 100 50 20</div>	RQD (%)						
Fill	0.00m: Silty fine to medium GRAVEL, minor clay; grey mottled orange. Loosely packed, moist, low plasticity. [FILL].																
	0.75m: Clayey SILT; orange mottled dark brown and light grey. Stiff to very stiff, moist to wet, medium to high plasticity.																
	1.95m: Fine GRAVEL. Loosely packed, wet.																
Residual East Coast Bays Formation	2.20m: Silty CLAY; orange mottled light grey. Stiff, moist, high plasticity. [RESIDUAL ECBF].																
	3.50m: CLAY, some silt; orange mottled grey. Stiff, moist, high plasticity.																
	3.80m: Colour becomes dark brownish grey																
	4.05m: SILT, minor organic and minor clay; blackish grey. Very stiff, moist, low plasticity.																
East Coast Bays Formation	4.50m: Completely weathered, dark grey, MUDSTONE. Extremely weak. Recovered as: CLAY, some silt; dark grey. Hard, moist to wet, high plasticity. [CW ECBF].																

COMMENTS:

Hole Depth  
13.8m

Scale 1:25

Rev.: A

# BOREHOLE LOG

BOREHOLE No.:

**BH02**

SHEET: 2 OF 3

DRILLED BY: SCZH

LOGGED BY: SCZH

CHECKED: RXSW

START DATE: 10/06/2025

FINISH DATE: 10/06/2025

CONTRACTOR: SCZH

PROJECT: The Point Development

JOB No.: 1098049.0000

LOCATION: 82 Aotea Street

CO-ORDINATES: 5920110 mN  
(NZTM2000) 1762965 mE

DIRECTION:  
ANGLE FROM HORIZ.: -90°

R.L. GROUND: 16.6m

R.L. COLLAR:  
DATUM: NZVD2016  
SURVEY: Handheld GPS

GEOLOGICAL UNIT	MATERIAL DESCRIPTION		Rock Weathering	Rock Strength	Sampling Method Core Recovery (%)	Testing	RL (m)	Depth (m)	Graphic Log	ROCK MASS DISCONTINUITIES					Description & Additional Observations	Water Level / Fluid Loss (%)	Casing	Installation	Core Box No
	SOIL: Classification, colour, consistency / density, moisture, plasticity	ROCK: Weathering, colour, fabric, name, strength, cementation								Defect Log	Fracture Spacing (mm)	RQD (%)							
East Coast Bays Formation	[CONT] 4.50m: Completely weathered, dark grey, MUDSTONE. Extremely weak. Recovered as: CLAY, some silt; dark grey. Hard, moist to wet, high plasticity. [CW ECBF].		SW SW 																

COMMENTS:

Hole Depth  
13.8m

Scale 1:25

Rev.: A



**BOREHOLE LOG**

BOREHOLE No.:  
**BH02**

SHEET: 3 OF 3

DRILLED BY: SCZH  
LOGGED BY: SCZH  
CHECKED: RXSW  
START DATE: 10/06/2025  
FINISH DATE: 10/06/2025  
CONTRACTOR: SCZH

PROJECT: The Point Development  
JOB No.: 1098049.0000  
LOCATION: 82 Aotea Street

CO-ORDINATES: 5920110 mN  
(NZTM2000) 1762965 mE

DIRECTION:  
ANGLE FROM HORIZ.: -90°

R.L. GROUND: 16.6m  
R.L. COLLAR:  
DATUM: NZVD2016  
SURVEY: Handheld GPS

GEOLOGICAL UNIT	MATERIAL DESCRIPTION	Rock Weathering		Rock Strength		Sampling Method	Core Recovery (%)	Testing	RL (m)	Depth (m)	Graphic Log	ROCK MASS DISCONTINUITIES				Description & Additional Observations	Water Level / Fluid Loss (%)	Casing	Installation	Core Box No
	SOIL: Classification, colour, consistency / density, moisture, plasticity ROCK: Weathering, colour, fabric, name, strength, cementation	UW SW HW CW CRW	VS+ S VS- W VW	VS+ S VS- W VW	VS+ S VS- W VW	HQTT						2000 Fracture Spacing (mm) 200 200 50 20	RQD (%)				25 50 75			
East Coast Bays Formation	[CONT] 9.41m: Unweathered to slightly weathered, dark grey, SILTSTONE. Very weak. Interbedded with: Unweathered to slightly weathered, dark grey, SANDSTONE. Very weak, fine grained. [SW-UW ECBF].					HQTT	100						45			10.40-10.90m: J, 80-85°, PL, R, C				Box 7.40-10.40m
							0	21/50// for 0 mm N≥50 Solid Cone	6	10.5										
						HQTT	100			11.0			11							
							0	16/50// for 0 mm N≥50 Solid Cone	12.0											
						HQTT	100			12.5			14							
							0	16/22// 34/16 for 0mm N≥50	13.5											
										14.0										
										14.5										
	13.8m: Target depth																			

COMMENTS:

Hole Depth  
13.8m

Scale 1:25

# CORE PHOTOS

BOREHOLE No.: **BH02**  
Hole Location: 82 Aotea Street  
SHEET: 1 OF 2

PROJECT: The Point Development		LOCATION: 110-160 Rukutai Street	JOB No.: 1098049.0000
CO-ORDINATES: (NZTM2000)	5920110 mN 1762965 mE	DRILL TYPE: MST-600VD METHOD: Rotary cored	HOLE STARTED: 10/06/2025 HOLE FINISHED: 10/06/2025 DRILLED BY: SCZH LOGGED BY: SCZH CHECKED: RXSW
R.L.:	16.6m		
DATUM:	NZVD2016		



0.00-4.60m



4.60-7.40m



# CORE PHOTOS

BOREHOLE No.: **BH02**  
Hole Location: 82 Aotea Street  
SHEET: 2 OF 2

PROJECT: The Point Development		LOCATION: 110-160 Rukutai Street	JOB No.: 1098049.0000
CO-ORDINATES: (NZTM2000)	5920110 mN 1762965 mE	DRILL TYPE: MST-600VD	HOLE STARTED: 10/06/2025
R.L.:	16.6m	METHOD: Rotary cored	HOLE FINISHED: 10/06/2025
DATUM:	NZVD2016		DRILLED BY: SCZH LOGGED BY: SCZH CHECKED: RXSW



7.40-10.40m



10.40-13.50m



# HAND AUGER LOG

HOLE Id: **HA01**  
Hole Location: 217 Kupe Street, south  
SHEET: 1 OF 1

PROJECT: The Point Development				LOCATION: 110-160 Rukutai Street				JOB No.: 1098049.0000											
CO-ORDINATES:		5920058 mN (NZTM2000) 1762661 mE		DRILL TYPE: 50mm hand auger				HOLE STARTED: 08/04/2025											
R.L.:		45m		METHOD: Hand auger				HOLE FINISHED: 08/04/2025											
DATUM:		NZVD2016						DRILLED BY: SCZH		CHECKED: RXSW									
GEOLOGICAL		METHOD OBSERVATIONS						ENGINEERING DESCRIPTION											
STRATIGRAPHY / ENG GEOLOGICAL UNIT / ADDITIONAL OBSERVATIONS		WATER	CORE RECOVERY (%)	METHOD	SCALA PENETROMETER (Blows/100mm)		TESTS	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	WEATHERING CLASSIFICATION	MOISTURE CLASSIFICATION	CONSISTENCY / DENSITY CLASSIFICATION	ESTIMATED SHEAR STRENGTH (Su, kPa)		DESCRIPTION		
					0	1	2	3	4	5	6	7	8	9					
Fill		08/04/2025 ▼	100	HA											D	H	0.00m: SILT, some gravel; light brown. Hard, dry, non-plastic. Gravel, fine. [FILL].		
																			0.70m: SILT, some clay; light brown mottled orange. Hard, dry, low to medium plasticity. [AUCKLAND VOLCANIC FIELD - ASH].
Auckland Volcanic Field																	M	TP	1.80m: Silty fine GRAVEL. Tightly packed, moist. [AUCKLAND VOLCANIC FIELD - TUFF].
																	M-W	St	2.20m: Clayey SILT; yellowish grey mottled dark brown. Stiff, moist to wet, medium to high plasticity. [RESIDUAL ECBF].
East Coast Bays Formation																			
																	3m: Target depth		

COMMENTS:

Hole Depth  
3m

Scale 1:30

Rev.: A

# HAND AUGER PHOTOS

BOREHOLE No.: <b>HA01</b>
Hole Location: 217 Kupe Street, south
SHEET: 1 OF 1

PROJECT: The Point Development		LOCATION: 110-160 Rukutai Street	JOB No.: 1098049.0000
CO-ORDINATES: (NZTM2000)	5920058 mN 1762661 mE	DRILL TYPE: 50mm hand auger	HOLE STARTED: 08/04/2025
R.L.:	45m	METHOD: Hand auger	HOLE FINISHED: 08/04/2025
DATUM:	NZVD2016		DRILLED BY: SCZH
			LOGGED BY: SCZH
			CHECKED: RXSW



0.00-3.00m

# HAND AUGER LOG

HOLE Id: **HA02**  
Hole Location: 217 Kupe Street, north  
SHEET: 1 OF 1

PROJECT: The Point Development	LOCATION: 110-160 Rukutai Street	JOB No.: 1098049.0000
CO-ORDINATES: 5920113 mN (NZTM2000) 1762605 mE	DRILL TYPE: 50mm hand auger	HOLE STARTED: 08/04/2025
R.L.: 45m	METHOD: Hand auger	HOLE FINISHED: 08/04/2025
DATUM: NZVD2016		DRILLED BY: SCZH
		LOGGED BY: SCZH CHECKED: RXSW

GEOLOGICAL		METHOD OBSERVATIONS										ENGINEERING DESCRIPTION																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
STRATIGRAPHY / ENG GEOLOGICAL UNIT / ADDITIONAL OBSERVATIONS		WATER	CORE RECOVERY (%)	METHOD	SCALA PENETROMETER (Blows/100mm)										TESTS	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	WEATHERING CLASSIFICATION	MOISTURE CLASSIFICATION	CONSISTENCY / DENSITY CLASSIFICATION	ESTIMATED SOIL SHEAR STRENGTH (kPa)										DESCRIPTION																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																								
					0	1	2	3	4	5	6	7	8	9									12	25	50	100	200																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																														
Topsoil		DRY 08/04/2025	100	HA														M	F																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																						



# HAND AUGER PHOTOS

BOREHOLE No.: **HA02**

Hole Location: 217 Kupe Street, north

SHEET: 1 OF 1

PROJECT: The Point Development		LOCATION: 110-160 Rukutai Street	JOB No.: 1098049.0000
CO-ORDINATES: (NZTM2000)	5920113 mN 1762605 mE	DRILL TYPE: 50mm hand auger	HOLE STARTED: 08/04/2025
R.L.:	45m	METHOD: Hand auger	HOLE FINISHED: 08/04/2025
DATUM:	NZVD2016		DRILLED BY: SCZH
			LOGGED BY: SCZH
			CHECKED: RXSW



0.00-3.00m

# HAND AUGER LOG

HOLE Id: **HA03**  
Hole Location: 63 Rukutai Street  
SHEET: 1 OF 1

PROJECT: The Point Development	LOCATION: 110-160 Rukutai Street	JOB No.: 1098049.0000
CO-ORDINATES: 5920070 mN (NZTM2000) 1762723 mE	DRILL TYPE: 50mm hand auger	HOLE STARTED: 09/06/2025
R.L.: 34.0m	METHOD: Hand auger	HOLE FINISHED: 09/06/2025
DATUM: NZVD2016		DRILLED BY: SCZH
		LOGGED BY: SCZH
		CHECKED: RXSW

GEOLOGICAL		METHOD OBSERVATIONS										ENGINEERING DESCRIPTION													
STRATIGRAPHY / ENG GEOLOGICAL UNIT / ADDITIONAL OBSERVATIONS		WATER	CORE RECOVERY (%)	METHOD	SCALA PENETROMETER (Blows/100mm)										TESTS	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	WEATHERING CLASSIFICATION	MOISTURE CLASSIFICATION	CONSISTENCY / DENSITY CLASSIFICATION	ESTIMATED SOIL STRENGTH ( $S_u$ , kPa)	DESCRIPTION	
					0	1	2	3	4	5	6	7	8	9											
Topsoil																						0.00m: Clayey SILT, some organic; dark brown. Soft, wet, medium to high plasticity. [TOPSOIL].			
Residual East Coast Bays Formation		09/06/2025	100	HA																		0.05m: Silty CLAY; yellowish brown mottled light grey. Stiff, moist, high plasticity. [RESIDUAL ECBF].			
																					1.20m: SILT, trace clay; yellowish mottled grey. Very stiff, wet to saturated, non-plastic to low plasticity.				
																					1.60m: Colour becomes grey				
																					1.90m: SILT, trace clay; yellowish mottled grey. Hard, wet to saturated, non-plastic to low plasticity.				
																					3m: Refusal				

# HAND AUGER PHOTOS

BOREHOLE No.: **HA03**  
 Hole Location: 63 Rukutai Street  
 SHEET: 1 OF 1

PROJECT: The Point Development		LOCATION: 110-160 Rukutai Street	JOB No.: 1098049.0000
CO-ORDINATES: (NZTM2000)	5920070 mN 1762723 mE	DRILL TYPE: 50mm hand auger METHOD: Hand auger	HOLE STARTED: 09/06/2025 HOLE FINISHED: 09/06/2025 DRILLED BY: SCZH LOGGED BY: SCZH CHECKED: RXSW
R.L.:	34.0m		
DATUM:	NZVD2016		



0.00-3.00m



# HAND AUGER LOG

HOLE Id: **HA04**

**Hole Location:** 82 Aotea Street

SHEET: 1 OF 1

PROJECT: The Point Development				LOCATION: 110-160 Rukatai Street				JOB No.: 1098049.0000							
CO-ORDINATES:		5920141 mN (NZTM2000) 1762939 mE		DRILL TYPE: 50mm hand auger				HOLE STARTED: 10/06/2025							
R.L.:		16.7m		METHOD: Hand auger				HOLE FINISHED: 10/06/2025							
DATUM:		NZVD2016						DRILLED BY: SCZH		LOGGED BY: SCZH					
										CHECKED: RXSW					
GEOLOGICAL		METHOD OBSERVATIONS						ENGINEERING DESCRIPTION							
STRATIGRAPHY / ENG GEOLOGICAL UNIT / ADDITIONAL OBSERVATIONS		WATER	CORE RECOVERY (%)	METHOD	SCALA PENETROMETER (Blows/100mm)	TESTS	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	WEATHERING CLASSIFICATION	MOISTURE CLASSIFICATION	CONSISTENCY / DENSITY CLASSIFICATION	ESTIMATED SOIL SHEAR STRENGTH (kPa)	DESCRIPTION
					0 1 2 3 4 5 6 7 8 9										
Fill						● 152/71 kPa			0.5			M	St- Vst		0.00m: Gravelly SILT, minor clay; greyish brown. Stiff to very stiff, moist, low plasticity. [FILL].
						● 146/56 kPa		16	1.0				Vst		0.55m: Silty CLAY; brownish orange mottled dark brown. Very stiff, moist, high plasticity.
Residual East Coast Bays Formation						● 137/54 kPa			1.5				St- Vst		1.10m: Silty CLAY; brown mottled light grey. Stiff to very stiff, moist, high plasticity. [Residual ECBF].
						● 92/27 kPa		15	2.0			W			1.80m: SILT, some sand, minor clay; grey mottled light brown. Stiff to very stiff, wet, low plasticity.
						● 86/30 kPa			2.5						
						● 89/6 kPa			3.0						
						● 137/45 kPa			3.5						
East Coast Bays Formation						● >208 kPa		14	4.0			W-S	H		2.50m: SILT, minor sand; grey. Hard, wet to saturated, dilatant rapid. Sand, fine. [CW ECBF].
						● >208 kPa			4.5						
						● UTP			5.0						
						● UTP		13	5.5						
									6.0						
									6.5						
									7.0						
									7.5						
									8.0						
									8.5						
									9.0						
									9.5						
									10.0						
									10.5						
									11.0						
									11.5						
									12.0						
									12.5						
									13.0						
									13.5						
									14.0						
									14.5						
									15.0						
									15.5						
									16.0						
									16.5						
									17.0						
									17.5						
									18.0						
									18.5						
									19.0						
									19.5						
									20.0						
									20.5						
									21.0						
									21.5						
									22.0						
									22.5						
									23.0						
									23.5						
									24.0						
									24.5						
									25.0						
									25.5						
									26.0						
									26.5						
									27.0						
									27.5						
									28.0						
									28.5						
									29.0						
									29.5						
									30.0						
									30.5						
									31.0						
									31.5						
									32.0						
									32.5						
									33.0						
									33.5						
									34.0						
									34.5						
									35.0						
									35.5						
									36.0						
									36.5						
									37.0						
									37.5						
									38.0						
									38.5						
									39.0						
									39.5						
									40.0						
									40.5						
									41.0						
									41.5						
									42.0						
									42.5						
									43.0						
									43.5						
									44.0						
									44.5						
									45.0						
									45.5						
									46.0						
									46.5						
									47.0						
									47.5						
									48.0						
									48.5						
									49.0						
									49.5						
									50.0						
									50.5						
									51.0						
									51.5						
									52.0						
									52.5						
									53.0						
									53.5						
									54.0						
									54.5						
									55.0						
									55.5						
									56.0						
									56.5						
									57.0						
									57.5						
									58.0						
									58.5						
									59.0						
									59.5						
									60.0						
									60.5						
									61.0						
									61.5						
									62.0						
									62.5						
									63.0						
									63.5						
									64.0						
									64.5						
									65.0						
									65.5						
									66.0						
									66.5						
									67.0						
									67.5						
									68.0						
									68.5						
									69.0						
									69.5						
									70.0						
									70.5						
									71.0						
									71.5						
									72.0						
									72.5						
									73.0						
									73.5						
									74.0						
									74.5						
									75.0						
									75.5						
									76.0						
									76.5						
									77.0						
									77.5						
									78.0						
									78.5						
									79.0						
									79.5						

# HAND AUGER PHOTOS

PROJECT: The Point Development		LOCATION: 110-160 Rukutai Street	JOB No.: 1098049.0000
CO-ORDINATES: (NZTM2000)	5920141 mN 1762939 mE	DRILL TYPE: 50mm hand auger	HOLE STARTED: 10/06/2025
R.L.:	16.7m	METHOD: Hand auger	HOLE FINISHED: 10/06/2025
DATUM:	NZVD2016		DRILLED BY: SCZH
			LOGGED BY: SCZH
			CHECKED: RXSW




0.00-3.80m

## **Appendix C      Groundwater Monitoring**

---






## **Appendix D      Conceptual basement retention sequence**

---







## **Appendix E      Draft Monitoring & Contingency Plan**

---



# The Point Development

## Groundwater and Settlement Monitoring Contingency Plan (GSMCP)

### Prepared for

Generus Living Group Limited

### Prepared by

Tonkin & Taylor Ltd

### Date

August 2025

### Job Number

1098049.0000 v3



**Together we create and  
sustain a better world**

[www.tonkintaylor.co.nz](http://www.tonkintaylor.co.nz)

Document control

Title: The Point Development					
Date	Version	Description	Prepared by:	Reviewed by:	Authorised by:
11 July 2025	1	Draft for Client Review	S. Zhang	R. Wilkinson	
14 August 2025	2	Draft v2 for Client Review	S. Zhang	M. Thomas	
27 August 2025	3	Draft v3 for RC Application	S. Zhang	R. Wilkinson	A. Langbein

Distribution:

Generus Living Group Limited

1 PDF copy

Tonkin & Taylor Ltd (FILE)

1 PDF copy



# Table of contents

## Definitions

<b>1</b>	<b>Introduction</b>	<b>1</b>
1.1	Project description	1
1.2	Nearby potentially affected structure and services	2
1.2.1	Structures	2
1.2.2	Services	2
1.3	Reporting requirements	3
1.3.1	Allocation of monitoring and reporting tasks	3
1.3.2	General notification timeframes	4
1.3.3	Monitoring records/reporting	4
<b>2</b>	<b>Monitoring</b>	<b>4</b>
2.1	General	4
2.2	Pre-condition surveys	5
2.2.1	Service condition surveys	5
2.2.2	Building condition surveys	5
2.2.3	Construction phase monitoring	6
2.2.4	Condition survey intervals	6
2.3	Ground and building deformation	6
2.3.1	General	6
2.3.2	Settlement monitoring intervals	6
2.3.3	Ground trigger levels	7
2.4	Summary of monitoring frequency requirements	8
<b>3</b>	<b>Reporting of monitoring records</b>	<b>9</b>
3.1	Baseline readings	9
3.2	Reporting intervals and requirements	9
<b>4</b>	<b>Alert and Alarm trigger level reponse procedures</b>	<b>9</b>
4.1	Response procedure if the alert levels are exceeded	9
4.2	Response procedure if the alarm levels are exceeded	10
<b>5</b>	<b>Contingency</b>	<b>10</b>
5.1	General	10
5.2	Ground and building deformation contingency measures	10
<b>6</b>	<b>Applicability</b>	<b>11</b>

## Appendix A            Monitoring Summary

## Definitions

<b>AC</b>	Means the Auckland Council (Team Leader, Water Allocation, NRSI) or nominated AC staff acting on the Team Leader's behalf
<b>Bulk Excavation</b>	Includes all excavation that affects groundwater, excluding minor enabling works and pilling
<b>Commencement of Excavation</b>	Means commencement of Bulk Excavation or excavation to create perimeter walls
<b>Commencement of Dewatering</b>	Means commencement of Bulk Excavation and/or the commencement of the taking or diversion of groundwater, other than for initial state monitoring purposes
<b>Completion of Excavation</b>	When all bulk excavation has been completed and all foundation/footing excavations within 10 m of the retaining wall or excavation batter have been completed
<b>Completion of Dewatering</b>	Means, in the case of a tanked building or structure construction, the stage when all the external base slab and walls are essentially watertight, the structures internal support mechanisms, including ground floor have been completed, any temporary retention removed, and no further groundwater is being taken for the construction on the perimeter retention system.  Means, in the case of a drained building or structure, the stage the structures external and internal support mechanisms, including ground floors have been completed, the permanent drainage systems are in place, and no further groundwater is being taken for the construction of the perimeter retention system.
<b>Completion of Construction</b>	Means when the code compliance Certificate (CCC) is issued by Auckland Council
<b>Damage</b>	Includes Aesthetic, Serviceability and Stability damage categories in accordance with building damage classification after Burland 1995 and Mair <i>et. al.</i> 1996
<b>Alert Level</b>	Monitoring reaches a level close to, or equal to the design value, which is above the level where damage could occur, and requires review to assess the future trend
<b>Alarm Level</b>	Is the deformation limit set at a threshold which has the potential to cause damage to buildings, structures and services, and requires immediate action including the cessation of activities that may influence ground deformation and at which the Consent Holder shall implement the relevant procedure described in this GSMCP
<b>The Team Leader</b>	Team Leader, Centre Monitoring, Auckland Council (AC), or nominated AC staff acting on The Team Leader's behalf
<b>Services</b>	Includes fibre optic cables, sanitary drainage, stormwater drainage, gas and water mains, power and telephone installations, road infrastructure assets such as footpaths, kerbs, catch-pits, pavements and street furniture
<b>SQEP</b>	Means Suitably Qualified Engineering Professional (Tonkin & Taylor)
<b>SQES</b>	Means Suitably Qualified Engineering Surveyor
<b>GSMCP</b>	Means Groundwater and Settlement Monitoring and Contingency Plan

# 1 Introduction

Tonkin & Taylor Ltd (T+T) have been engaged by Generus Living Group Ltd (Generus) to prepare a draft Groundwater and Settlement Monitoring and Contingency Plan (GSMCP) to support the Resource Consent application for the proposed development of the retirement village referred to as 'The Point Mission Bay' (TPMB).

Monitoring of the excavation works and surroundings will be undertaken to assess effects on ground and structures adjacent to the site. Monitoring plans are shown in Appendix A.

This GSMCP serves to establish a set of project controls to monitor ground settlement, and to address potential geotechnical effects related to the project works. The GSMCP also provides contingency and mitigation measures that may be applied should monitoring results indicate ground settlement are approaching or likely to exceed established alert and alarm limits.

This GSMCP is applicable for the excavation based on the T+T Geotechnical Assessment Report<sup>1</sup>.

## 1.1 Project description

The proposed development involves the construction of 5 buildings across the site ranging in height between 5 to 7 stories, which includes partial basement levels of 1 to 2 stories that daylight from the sloping ground across the site that falls from west to east. A shared basement is proposed between Buildings 2, 3 & 4. The area between the buildings is to be used for recreation and hard and soft landscaping.

In accordance with the preliminary development plans provided<sup>2</sup>, the basement levels across the buildings are summarised below:

- Building 1: RL 16.50 m
- Building 2: RL 23.4 m to 28.3 m
- Building 3: RL 28.3 m to RL 31.75
- Building 4: RL 31.75 m
- Building 5: RL 35.20 m

Our assessment has allowed for bulk excavation up to 1.0 m below the finished floor levels to account for the floor slab and subsoil drainage construction. On this basis, the temporary retained heights of up to approximately 8.75 m are required to support the proposed excavation.

<sup>1</sup> T+T (August 2025), The Point Development – Geotechnical Assessment Report, v3. T+T Ref: 1094098.0000.

<sup>2</sup> Warren & Mahoney (22 August 2025). Architectural Design Report Prepared for Generus Living Group, Rev A. Job No. 10476.






Figure 1.1: Current development site and surrounds, with locations of potentially affected structures

## 1.2 Nearby potentially affected structure and services

### 1.2.1 Structures

The structures shown in Figure 1.1 and listed in Table 1.1 have been identified as “potentially affected structures”. The degree of risk to these structures as summarised below based on the assessment of effects presented in the T+T Geotechnical Assessment Report<sup>1</sup> for this site.

Table 1.1: Potentially affected structures

Structure	Direction (N,S,E,W)	Approximate distance from excavation (m)	Risk
217 Kupe Street	W	17.5	Negligible
104 Rukutai Street	S	18.0	Negligible
119 Rukutai Street		10.0	Negligible
119B Rukutai Street		16.0	Negligible
86 Aotea Street		14.5	Negligible

### 1.2.2 Services

Potentially affected services for the purposes of monitoring were assessed using public utility services identified in the online Auckland Council GIS database<sup>3</sup>. A plan extracted from the GIS online tool is shown in Figure 1.2. A summary of the identified affected services is given in Table 1.2.

<sup>3</sup> <https://geomapspublic.aucklandcouncil.govt.nz>

The Geotechnical Assessment Report for the site concluded that the likely effect of the proposed development for identified services was negligible to moderate.

**Table 1.2: Potentially affected services**

Service ID	Street	Service type	Material	Diameter (mm)	Direction (N,S,E,W)	Approximate distance from excavation (m)
2000609020	Michael Joseph Savage Memorial Park	Stormwater	Concrete	450	N	0
2000403490	Michael Joseph Savage Memorial Park	Stormwater	Concrete	375	E	0
300135283, 3000135314, and 2000154512	Aotea Street	Stormwater	Concrete	225	S	6.0
2000158462, and 2000616277	Rukutai Street	Stormwater	Concrete	300	S	2.5
2601731, 2496144, and 2493377	Rukutai Street	Wastewater	VC	150	S	7.5



Figure 1.2: Auckland Council public underground services (potentially affected serviced are highlighted in bold dashed line)

## 1.3 Reporting requirements

### 1.3.1 Allocation of monitoring and reporting tasks

The completion of the Groundwater and Settlement Monitoring and Contingency Plan detailed herein shall be the overall responsibility of the consent holder. The following allocation of monitoring and reporting tasks is assumed to enable successful plan completion.

Monitoring item	Install / baseline	Regular monitoring	Individual monitoring round reporting to T+T	Bi-monthly reporting to AC
Service condition surveys	Principal contractor	Principal contractor	Principal contractor	N/A
Structural condition surveys	Principal contractor / SQEP	Principal contractor	Principal contractor	T+T
Buildings and ground deformation pin survey	Principal contractor / SQES	Principal contractor / SQES	Principal contractor / SQES	T+T

### 1.3.2 General notification timeframes

The Team Leader shall be advised by the Principal Contractor of the following project milestones:

Project milestone	Notification requirement
Commencement of Excavation	10 working days prior
Commencement of Dewatering	10 working days prior

### 1.3.3 Monitoring records/reporting

Survey data collected during the course of the project shall be forwarded to T+T within three working days of that data being collected.

Monitoring results will be collated by T+T and compared with the specified trigger levels. These records will be held by T+T and will be available for inspection as required.

During construction, reporting of the monitoring results will be forwarded to AC at two-monthly intervals. Each report shall include the following:

- Monitoring records presented on a timeline plot.
- Comparison of monitoring data with the adopted trigger levels.
- Previous results set out with an explanation of any trends.
- A construction progress summary.
- Any other information relevant to the reporting period (i.e. exceedance of trigger levels and contingency measures being undertaken).

At the completion of the perimeter retention system construction, monitoring will continue for the timeframes required by the consent (or at such time that stable measurements are demonstrated, and written approval to cease monitoring is granted from AC).

In the event of any exceedance of the trigger levels, the relevant monitoring and reporting procedure will be implemented in accordance with Section 3 of the plan.

At the completion of the works a summary completion report will be prepared.

## 2 Monitoring

### 2.1 General

Monitoring of the excavation works and surroundings shall be undertaken to ensure that the ground and groundwater conditions are consistent with the design analyses and that the response of the structures is within design tolerances.



The monitoring requirements, including location of monitoring points, frequency of monitoring, action trigger levels, response procedures and reporting requirements, are detailed in the following sections. Survey monitoring locations are shown in the Construction Monitoring Instrumentation Plan in Appendix A.

The proposed construction phase monitoring to assess the effects on ground surrounding the site and of the services and structures identified above shall include:

- Pre and post-retention system construction, condition surveys of the potentially affected structures and services identified in Table 1.1 and Table 1.2 above.
- Regular visual external survey of the surrounding ground, pavement, associated street infrastructure and structures during construction to identify any deterioration of pre-construction baseline conditions.
- Precise levelling survey of the ground and buildings surrounding the site. The marks shall be set as low as practicable on the building on elements in direct connection with the foundation level (i.e. columns or perimeter footings).
- Precise levelling survey of pavement line levels surrounding the site.

## 2.2 Pre-condition surveys

### 2.2.1 Service condition surveys

Prior to the Commencement of Dewatering and following Completion of Dewatering (and within 6 months of completion of the retention system construction), a condition survey of potentially affected buried services (refer to Table 2.1) shall be undertaken in consultation with the relevant service provider.

Suitable condition surveys are expected to comprise CCTV survey for stormwater and wastewater services.

A condition survey is not required where written evidence is provided to the Council that the owner of that service has confirmed they do not require a condition survey.

**Table 2.1: List of neighbouring underground services requiring condition surveys**

Service ID	Direction (N,S,E,W)	Internal Survey	Settlement Pins (Yes/No)
2000609020	N	✓	Yes
2000403490	E	✓	Yes
300135283, 3000135314, and 2000154512	S	✓	Yes
2000158462, and 2000616277	S	✓	Yes

### 2.2.2 Building condition surveys

In accordance with the T+T Geotechnical Assessment Report<sup>1</sup>, estimated settlement across all potentially affected adjacent structures is less than 5 mm. On this basis, no building condition survey is considered to be required for the proposed basement excavation.

### 2.2.3 Construction phase monitoring

An external visual inspection undertaken by the Principal Contractor at regular intervals shall monitor any new damage or deterioration of any pre-existing damage for the following:

- The ground within 10 m of the excavation.

A photographic record of the surveys is to be maintained, including the time, date and any observations for each inspection. This record is to be maintained on site and forwarded to T+T typically monthly, but within one day if any deterioration or cracking is observed.

### 2.2.4 Condition survey intervals

A visual inspection of the surrounding ground and buildings listed above shall be carried out at the following intervals:

<b>Pre-commencement of dewatering</b>	Pre-construction survey as detailed in Section 2.2.1 and 2.2.2.
<b>From commencement of dewatering to completion of dewatering</b>	Fortnightly external visual inspections as detailed in Section 2.2.3.
<b>After completion of dewatering</b>	Post-construction survey within six months of completion of construction as detailed in Section 2.2.1 and 2.2.2.

At the reasonable request of the Council, an additional survey on any building shall be carried out for the purpose of checking for damage and for following up on a report of damage to that building.

## 2.3 Ground and building deformation

### 2.3.1 General

Ground and building deformation monitoring marks shall be established on the pavements and buildings surrounding the excavation area at the locations shown in Appendix A.

The marks shall be set as low as practicable on the building on elements in direct connection with the foundation level (i.e. columns or perimeter footings).

Survey measurements shall be accurate to  $\pm 2$  mm.

### 2.3.2 Settlement monitoring intervals

Surveys shall be carried out at the following intervals:

<b>Pre-commencement of dewatering</b>	At least two baseline surveys are required to establish baseline readings.
<b>Commencement of dewatering to completion of excavation</b>	Fortnightly
<b>Completion of excavation to completion of dewatering</b>	Fortnightly
<b>After the completion of dewatering</b>	Monthly for six months or until such a time following the completion of dewatering that stable measurements are demonstrated, and written approval is granted from the Council.

Subject to the Team Leader's approval, monitoring may be reduced in frequency, subject to demonstration of consistent results below the alert/alarm levels.

### 2.3.3 Ground trigger levels

Monitoring data is to be compared with the design assumptions and baseline readings. Alert and Alarm Levels at which actions are required to be undertaken are summarised in Table 2.2. If the alert or alarm levels in Table 2.2 are reached, the actions outlined in Section 4 shall be carried out.

**Table 2.2: Ground deformation mark trigger levels**

Settlement mark ID	Description	Settlement alert level (mm)	Settlement alarm level (mm)	Differential settlement alert level	Differential settlement alarm level
GS1 to G4	North ground monitoring points	15	25	1:450 between two ground monitoring marks	1:550 between two ground monitoring marks
GS5 to G12	South ground monitoring points	10	20		



2.4 Summary of monitoring frequency requirements

Monitoring Item	Monitoring Points	Alert Level (mm)	Alarm Level (mm)	Monitoring Frequencies <sup>2</sup>			Reporting Frequency
				Pre-Commencement of dewatering / Baseline	From Commencement of Dewatering/Excavation	After Completion of Dewatering/Excavation	
Differential Ground Surface Settlement <sup>1</sup>	GS1 to GS12	1:450 between two ground monitoring marks	1:550 between two ground monitoring marks	At least two baseline surveys for all deformation points to a horizontal and vertical accuracy of $\pm$ 2 mm.	Fortnightly to Completion of Excavation.	Monthly for six months or until such a time following the completion of dewatering that stable measurements are demonstrated, and written approval for monitoring termination is granted from the Council.	Results of the monitoring programme to be reported to Council at two monthly intervals during the monitoring period.
Total Ground Surface Settlement <sup>1</sup>	GS1 to GS4	15	25		Fortnightly following Completion of Excavation.		
	GS5 to G12	10	20				
Services condition survey	Refer Table 2.1	N/A	N/A	Pre-construction condition survey prior to commencement of perimeter retaining walls construction or commencement of dewatering.	Fortnightly external visual inspections.	Post-construction condition survey within 6 months of the Completion of Dewatering.	
					N/A		

Notes:

- 1
- Deformation stations shall be surveyed to a horizontal and vertical accuracy of + 2 mm (precise survey techniques).
- 2
- Subject to the Team Leader’s approval, monitoring may be reduced in frequency, subject to demonstration of consistent results.

### **3 Reporting of monitoring records**

#### **3.1 Baseline readings**

Baseline readings for ground and building deformation shall be established and baselined before any construction is commenced, including piling.

These baseline readings shall be compiled and submitted to the Council for certification prior to the commencement of excavation.

#### **3.2 Reporting intervals and requirements**

All monitoring records as detailed in this report shall be compiled and submitted to the Council at two monthly intervals from the commencement of construction, until six months after the completion of excavation (or at such time following the completion of excavation that stable measurements are demonstrated, and written approval for cessation of monitoring is granted from the Council), or completion of the retention system construction as appropriate.

As a minimum each report shall include the following:

- 1 Monitoring records presented in a tabulated format as well as on a timeline plot;
- 2 Comparison of monitoring data with trigger levels and the assumed design models;
- 3 Previous results set out with an explanation of any trends;
- 4 A construction progress summary; and
- 5 Any other information relevant to the reporting period (i.e. exceedance of trigger levels and contingency measures being undertaken).

### **4 Alert and Alarm trigger level response procedures**

#### **4.1 Response procedure if the alert levels are exceeded**

If any of the monitoring alert trigger levels are reached, then one or more of the contingency options described in Section 5 of this plan should be carried out together with:

- 1 Notify the Project Manager.
- 2 Notify the Council, in writing within one working day of the trigger level being exceeded, with details of any actions being undertaken.
- 3 Survey all monitoring marks within a 25 m radius of the affected monitoring mark(s) to confirm the extent of deformation and exceedance of the Alert Trigger.
- 4 Ensure the data is reviewed, and advice provided, by a SQEP on the need for mitigation measures or other actions necessary to avoid further deformation. Where mitigation measures or other actions are recommended those measures shall be implemented.
- 5 Submit a written report, prepared by the SQEP responsible for overseeing the monitoring, to the Team Leader Central Monitoring within five working days of Alert Level exceedance. The report shall provide an analysis of all monitoring data relating to the exceedance, actions taken to date to address the issue, recommendations for additional monitoring (i.e. the need for increased frequency or repeat condition survey(s) of building or structures) and recommendations for future remedial actions necessary to prevent Alarm Levels being exceeded.
- 6 Measure and record all Monitoring Stations within 25 metres of the location of any Alert Level exceedance every three days until such time the written report referred to above has been submitted to the Team Leader Central Monitoring.

- 7 Once approved, the recommendations shall be implemented.

## 4.2 Response procedure if the alarm levels are exceeded

If the monitoring alarm trigger levels are reached for any ground or building deformation then the following shall be carried out in addition to the actions outlined in Section 5:

- 1 Immediately halt construction activity, including excavation, dewatering or any other works that may result in increased deformation, unless halting the activity is considered by a SQEP to be likely to be more harmful (in terms of effects on the environment) than continuing to carry out the activity.
- 2 Notify the Team Leader (AC), within 24 hours of the alarm level exceedance being detected and provide details of the measurements taken.
- 3 Undertake a condition survey (this could comprise either a detailed condition survey or an external visual inspection at the discretion of the SQEP responsible for overseeing the monitoring) by a SQEP or suitably qualified building surveyor (SQBS) of any building or structure located adjacent to any Monitoring Station where the Alarm Level has been exceeded.
- 4 Take advice from the author of the Alert Level exceedance report (if there was one) or another SQEP on actions required to avoid remedy or mitigate adverse effects on ground, buildings or structures that may occur as a result of the exceedance.
- 5 Submit a written report, prepared by the SQEP responsible for overseeing the monitoring, for certification by the Team Leader Compliance Monitoring NW1, on the results of the condition survey(s), the mitigation measures implemented and any remedial works and/or agreements with affected parties within five working days of recommencement of works.
- 6 Not resume construction activities (or any associated activities), halted in accordance with paragraph (1) above, until any mitigation measures (recommended in accordance with paragraphs (4) or (5) above) have been implemented, to the satisfaction of a SQEP.

## 5 Contingency

### 5.1 General

If any of the monitoring trigger levels are exceeded, the general response will be as detailed in Section 4. Specific actions will be selected depending on the exact nature of the problem. Possible contingency actions are detailed in the following sections.

### 5.2 Ground and building deformation contingency measures

In the event of ground or building deformation exceeding the monitoring trigger levels, one or more of the following actions shall be taken:

- Check public safety is maintained.
- Discussions on the situation with the property/service owner that may be affected.
- Monitor the rate of settlement (assuming that other steps have been undertaken to address the cause).
- Consider options to mitigate further settlement if recommended by the SQEP, which may involve:
  - Install a berm or temporary prop in front of the retaining wall or excavation
- Accept and reinstate resultant damage.



## 6 Applicability

This report has been prepared for the exclusive use of our client Generus Living Group Limited, with respect to the particular brief given to us and it may not be relied upon in other contexts or for any other purpose, or by any person other than our client, without our prior written agreement.

We understand and agree that our client will submit this report as part of an application for resource consent under the Fast-track Approvals Act 2024 and that an Expert Panel as the consenting authority will use this report for the purpose of assessing that application.

Tonkin & Taylor Ltd  
Environmental and Engineering Consultants

Report prepared by:

Report reviewed by:

.....  
Scott Zhang  
Geotechnical Engineer

.....  
Ric Wilkinson  
Senior Geotechnical Engineer

Authorised for Tonkin & Taylor Ltd by:

.....  
Andrew Langbein  
Project Director

27-Aug-25  
\\ttgroup.local\corporate\aukland\projects\1098049\workingmaterial\3. report\the point\gsmcp\draft gscmp (bentley - gr - ae  
comments - 12.08.25).docx

## Appendix A      Monitoring Summary

---

- Construction monitoring instrumentation plan

DRAFT









## **Appendix F      Proposed Consent Conditions**

---

## **Proposed Conditions of Consent – Water Permit**

### **Abbreviations and definitions:**

The following abbreviations and definitions apply to these consent conditions.

<b>Alarm Level</b>	Means specific levels at which actions are required as described in the relevant conditions.
<b>Alert Level</b>	Means specific levels at which actions are required as described in the relevant conditions.
<b>Bulk Excavation</b>	Includes all excavation that affects groundwater excluding minor enabling works and piling less than 1.5m in diameter.
<b>Commencement of Dewatering</b>	Means commencement of Bulk Excavation and/or the commencement of the taking or diversion of groundwater, other than for initial state monitoring purposes.
<b>Completion of Dewatering</b>	Means, in the case of a drained building or structure, the stage when the structure's external and internal support mechanisms, including basement floors, have been completed, the permanent drainage system(s) are in place, and no further groundwater is being taken for the construction of the basement.
<b>Completion of Construction</b>	Means when the Code Compliance Certificate (CCC) is issued by Council.
<b>Commencement of Excavation</b>	Means commencement of Bulk Excavation or excavation to create perimeter walls.
<b>Commencement of Excavation</b>	Means commencement of Bulk Excavation or excavation to create perimeter walls.
<b>Completion of Excavation</b>	Means the stage when all Bulk Excavation and all foundation/footing excavations within ten (10) metres of the perimeter building retaining walls has been completed.
<b>Condition Survey</b>	Means an External Visual Inspection or a detailed Condition Survey (as defined in the relevant conditions).



<b>Damage</b>	Includes Aesthetic, Serviceability and Stability Damage, but does not include Negligible Damage, as described in Table 1 below.
<b>External Visual Inspection</b>	A Condition Survey undertaken for the purpose of detecting any new external Damage or deterioration of existing external Damage. Includes as a minimum a visual inspection of the exterior and a dated photographic record of all observable exterior Damage.
<b>Monitoring Station</b>	Means any monitoring instrument including a ground or building deformation station, inclinometer, groundwater monitoring bore, retaining wall deflection station, or other monitoring device required by this consent.
<b>Seasonal Low Groundwater Level</b>	Means the annual lowest groundwater level – which typically occurs in summer.
<b>Services</b>	Include fibre optic cables, sanitary drainage, stormwater drainage, gas and water mains, power and telephone installations and infrastructure, road infrastructure assets such as footpaths, kerbs, catch-pits, pavements and street furniture.
<b>SQBS</b>	Means Suitably Qualified Building Surveyor.

Table 1: Building Damage Classification Category of Damage			
Category of Damage	Normal Degree of Severity	Description of Typical Damage (Building Damage Classification after Burland (1995), and Mair et al (1996))	General Category (after Burland)
0	Negligible	Hairline cracks	Aesthetic Damage
1	Very Slight	Fine cracks easily treated during normal redecoration. Perhaps isolated slight fracture in building. Cracks in exterior visible upon close inspection. Typical crack widths up to 1mm.	
2	Slight	Cracks easily filled. Redecoration probably required. Several slight fractures inside building. Exterior cracks visible, some repainting may be required for weathertightness. Doors and windows may stick slightly. Typically, crack widths up to 5mm.	

3	Moderate	Cracks may require cutting out and patching. Recurrent cracks can be masked by suitable linings. Brick pointing and possible replacement of a small amount of exterior brickwork may be required. Doors and windows sticking. Utility services may be interrupted. Weather tightness often impaired. Typical crack widths are 5mm to 15mm or several >3mm.	Serviceability Damage
4	Severe	Extensive repair involving removal and replacement of walls especially over doors and windows. Window and door frames distorted. Floor slopes noticeably. Walls lean or bulge noticeably. Some loss of bearing in beams. Utility services disrupted. Typical crack widths are 15mm to 25mm but also depends on the number of cracks.	
5	Very Severe	Major repair required involving partial or complete reconstruction. Beams lose bearing, walls lean badly and require shoring. Windows broken by distortion. Danger of instability. Typical crack widths are greater than 25mm but depend on the number of cracks.	Stability Damage
Note: In the table above, the column headed "Description of Typical Damage" applies to masonry buildings only and the column headed "General Category" applies to all buildings			

#### **Duration of consent**

1. The take (dewatering) and groundwater diversion consent [WATXXXXXXXXX] expires thirty-five (35) years from the date of commencement, unless it has lapsed, been surrendered, or been cancelled at an earlier date pursuant to the RMA.

#### **Notice of Commencement of Dewatering**

2. The consent holder must notify the Council in writing at least ten (10) working days prior to the date of the Commencement of Construction Phase Dewatering.

#### **Design and Construction of Basement and Retaining Walls**

3. The design and construction of the basement and retaining walls must be undertaken in accordance with the specifications contained in the report titled: "Geotechnical Assessment Report – The Point Mission Bay", prepared by Tonkin & Taylor, dated October 2025. The consent holder must provide verification in writing from an SQEP that the recommendations of this report have been implemented on the Site. This must be provided no later than ten (10) working days after completion of basement construction.

## Damage Avoidance

4. All excavation, dewatering systems, retaining structures, basements and works associated with the diversion or taking of groundwater, must be designed, constructed and maintained so as to avoid damage to land, buildings, structures and services on the site and adjacent properties, outside that considered as part of the application process unless otherwise agreed in writing with the asset owner.

## Alert and Alarm Levels

5. The activity must not cause any settlement or movement greater than the Alarm Level thresholds specified in **Schedule A** below. Alert and Alarm Levels are triggered when the following Alert and Alarm Trigger thresholds are exceeded:

### Schedule A: Alarm and Alert Levels

Movement (Note 1)		Trigger Thresholds (+/-)	
		Alarm	Alert
a)	Differential vertical settlement between any two Ground Surface Settlement Monitoring Stations (the <b>Differential Ground Surface Settlement Alarm or Alert Level</b> ):		
	GS01 to GS12	1:550	1:450
b)	Total vertical settlement between the pre-excavation baseline level at any Ground Surface Settlement Monitoring Station (the <b>Total Ground Surface Settlement Alarm or Alert Level</b> ):		
	GS01 to GS04	15mm	25mm
	GS05 to GS12	10mm	20mm
Note	(1)	The locations of the Monitoring Stations listed in Schedule A are shown on the Proposed Construction Monitoring Instrumentation Plan included in Appendix A of the GSCMP referenced in <b>Attachment 1</b> .	

These levels may be amended subject to approval by the Council as part of the GSMCP certification process and recommendations from a SQEP, but only to the extent that avoidance of Damage to building, structures and Services can still be achieved.

**Advice note:** *There are conditions below that must be complied with when the Alert and Alarm Level triggers are exceeded. These include actions that must be taken immediately including seeking the advice of a SQEP.*

## Alert Level Actions

6. In the event of any Alert Level from **Schedule A (Condition 5)** being exceeded, the consent holder must:
  - (a) Notify the Council within twenty-four hours (24) of the exceedance.
  - (b) Re-measure all Monitoring Stations within twenty (20) metres of the affected monitoring location(s) to confirm the extent of apparent movement.



- (c) Ensure the data is reviewed, and advice provided, by a SQEP on the need for mitigation measures or other actions necessary to avoid further deformation. Where mitigation measures or other actions are recommended those measures must be implemented.
- (d) Submit a written report, prepared by the SQEP responsible for overseeing the monitoring, to the Council within five (5) working days of Alert Level exceedance. The report must provide an analysis of all monitoring data relating to the exceedance, actions taken to date to address the issue, recommendations for additional monitoring (i.e. the need for increased frequency or repeat Condition Survey(s)) and recommendations for future remedial actions necessary to prevent Alarm Levels being exceeded.
- (e) Measure and record all Monitoring Stations within twenty (20) metres of the location of any Alert Level exceedance every two (2) working days until such time the written report referred to above has been submitted to the Council.

### **Alarm Level Actions**

7. In the event of any Alarm Level from **Schedule A (Condition 5)** being exceeded, the consent holder must:
  - (a) Immediately halt construction activity relevant to the location of the Alarm Level exceedance, including excavation, dewatering, or any other works that may result in increased deformation, unless halting the activity is considered by a SQEP to be likely to be more harmful (in terms of effects on the environment) than continuing to carry out the activity.
  - (b) Notify the Council within twenty-four (24) hours of the Alarm Level exceedance being detected and provide details of the measurements taken.
  - (c) Take advice from the author of the Alert Level exceedance report (if there was one) on actions required to avoid, remedy or mitigate adverse effects on ground, buildings or structures that may occur as a result of the exceedance.
  - (d) Not resume construction activities (or any associated activities), halted in accordance with paragraph (a) above, until any mitigation measures have been implemented to the satisfaction of a SQEP.
  - (e) Submit a written report, prepared by the SQEP responsible for overseeing the monitoring on the mitigation measures implemented, and any remedial works and/or agreements with affected parties within five (5) working days of recommencement of works.

### **Groundwater Settlement Monitoring and Contingency Plan (GSMCP)**

8. At least ten (10) working days prior to the intended Commencement of Dewatering, a final GSMCP prepared by SQEP, must be submitted to the Council for certification. Any amendment of the GSMCP must also be submitted to the Council for certification. The submitted information must be generally in accordance with the draft GSMCP prepared by Tonkin + Taylor.

The overall objective of the GSMCP is to set out the practices and procedures to be adopted to ensure compliance with the consent conditions. To achieve this objective, the final GSMCP must include, at a minimum, the following information:

- (a) A monitoring location plan showing the location and type of all Monitoring Stations.
  - (b) Final completed **Schedule B** (as per the conditions below) for the ground surface monitoring programme (including any proposed changes to the monitoring frequency) as required by the conditions below.
  - (c) All monitoring data and the identification of services susceptible to damage required by the conditions below.
  - (d) A bar chart or a schedule, showing the timing and frequency of Condition Surveys, External Visual Inspections, and all other monitoring required by this consent, and a sample report template for the two (2)-monthly monitoring required by **Condition 14**.
  - (e) All Alert and Alarm Level triggers (including reasons if changes to such are proposed, for example as a result of recommendations in the Services Condition Surveys (required by **Condition 10**) or data obtained from pre-dewatering monitoring).
  - (f) Details of the contingency actions to be implemented if Alert or Alarm Levels are exceeded.
9. All construction, dewatering, monitoring and contingency actions must be carried out in accordance with the certified GSCMP. No Bulk Excavation (that may affect groundwater levels) or other dewatering activities must commence until the GSMCP is certified in writing by the Council.

#### **Services Condition Surveys**

10. The consent holder must engage a SQEP to undertake pre-condition and post-condition surveys for the following underground services:
- (a) Service ID 2000609020 (Stormwater 450 dia. Conc);
  - (b) Service ID 2000403490 (Stormwater 375 dia. Conc);
  - (c) Service ID 300135283, 3000135314 and 2000154512 (Stormwater 225 dia. Conc)
  - (d) Service ID 2000158462 and 2000616277 (Wastewater 150 dia. VC)
11. The Condition Survey required by **Condition 10** must include the following:
- (a) Type of services.
  - (b) Existing levels of damage.
  - (c) Susceptibility of structure to further movement.
  - (d) Photographic evidence of items (b), (c) and (d) via CCTV Survey.
  - (e) A review and the suitability of the proposed Alarm and density of building deformation stations.

A reasonable attempt must be made to contact the service owner to carry out surveys and if access is not made available, the reasons must be recorded.

A copy of the pre-condition and post condition surveys must be provided to the Council within twenty (20) working days following completing the survey.

**Advice note:** *This condition does not apply to any Service where written evidence is provided to the Council that the owner of that Service has confirmed they do not require a condition survey.*

### **External Visual Inspections during Construction Phase Dewatering**

12. External Visual Inspections of the surrounding ground within 10m of the basement excavation must be undertaken for the purpose of detecting any new external Damage or deterioration of existing external Damage. Inspections must be carried out fortnightly from the Commencement to Completion of Dewatering. A photographic record must be kept, including time and date, of each inspection and all observations made during the inspection, and must be of a quality that is fit for purpose.

The results of the External Visual Inspections and an assessment of the results must be reviewed by the SQEP responsible for overseeing the monitoring and must be included in the bimonthly monitoring report required by **Condition 16** for the relevant monitoring period.

**Advice note:** *This condition does not apply to any land, building or structure where written evidence is provided to the Council confirming that the owner of the land, building or structure does not require visual inspections to be carried out.*

### **Completion of Dewatering - Services Condition Surveys**

13. Between six (6) and twelve (12) months after the Completion of Dewatering, a detailed Condition Survey of all previously surveyed Services referenced in **Condition 10** must be undertaken by a SQEP and a written report must be prepared. The report must be prepared and/or reviewed by the SQEP responsible for overseeing the monitoring and submitted to the Council, within 20 working days of completion of the Condition Survey.

The Condition Survey report must make specific comment on those matters identified in the Condition Surveys required by **Condition 10**. It must also identify any new Damage that has occurred since the condition surveys were undertaken and must provide an assessment of the likely cause of any such Damage.

**Advice note:** *This condition does not apply to any building, structure or Service where written evidence is provided to the Council confirming that the owner of that building, structure, or Service does not require a condition survey to be undertaken.*

### **Ground Surface Deformation Monitoring**

14. Ground Surface Deformation Monitoring Stations must be established and maintained in the locations shown on the monitoring location plan in the certified GSMCP, as required in accordance with **Condition 8(a)**.

The Monitoring Stations must be monitored at the frequency set out in **Schedule B** below. The purpose of the Monitoring Stations is to record any vertical or horizontal (including differential) movement. Benchmark positions must be established no less than twenty (20) metres away from the excavated area.

The monitoring frequency may be changed through amendment to the GSMCP.

Schedule B: Monitoring frequency		
Monitoring period	Monitoring station and type	
	GS01 to GS12	Services Condition Survey
Pre-Commencement of Dewatering/Baseline	At least two (2) baseline surveys for all deformation points to a horizontal and vertical accuracy of +2mm.	Pre-construction Condition Survey prior to commencement of perimeter retaining walls construction or commencement of dewatering.
From Commencement of Dewatering/Excavation	Fortnightly to Completion of Excavation. Fortnightly following Completion of Excavation.	Fortnightly external visual inspections.
After Completion of Dewatering/Excavation	Monthly for six (6) months or until such a time following the completion of dewatering that stable measurements are demonstrated, and written approval for monitoring termination is granted from the Council.	Post-construction Condition Survey within six (6) months of the Completion of Dewatering.

### Contingency Actions

15. If the consent holder becomes aware of any Damage to buildings, structures or Services potentially caused wholly, or in part, by the exercise of this consent, the consent holder must:
  - (a) Notify the Council and the asset owner within two (2) working days of the consent holder becoming aware of the Damage.
  - (b) Provide a report prepared by a SQEP (engaged by the consent holder at their cost) that describes the Damage, identifies the cause of the Damage, identifies methods to remedy and/or mitigate the Damage that has been caused, identifies the potential for further Damage to occur, and describes actions that will be taken to avoid further Damage.
  - (c) Provide a copy of the report, prepared under (b) above, to the Council and the asset owner within ten (10) working days of notification under (a) above.
  - (d) Where the report provided by the SQEP in accordance with (b) above identifies the cause of the Damage to be activities authorised by this consent, the consent holder must offer to and, if accepted by the asset owner, rectify the Damage at the consent holder's cost, as soon as practicable, in consultation with the asset owner.



**Advice note:** *It is anticipated the consent holder will seek the permission of the damaged asset owner to access the property and asset to enable the inspection/investigation. It is understood that if access is denied the report will be of limited extent.*

#### **Reporting of Monitoring Data**

16. At two (2) monthly intervals, until the Completion of Dewatering, and at six (6) monthly intervals until twelve (12) months following Completion of Dewatering, a report containing all monitoring data required by conditions of this consent must be submitted to the Council. This report must include a construction progress timeline, the monitoring data recorded in that period, and a comparison of that data with previously recorded data and with the Alert and Alarm Levels for each Monitoring Station.

#### **Notice of Completion**

17. The Council must be advised in writing within ten (10) working days of when Bulk Excavation and Completion of Dewatering has been completed.

#### **Groundwater Maintenance Program**

18. Within twelve (12) months of Completion of Dewatering, the Council must be provided with a maintenance program for any permanent groundwater drainage system used to manage groundwater levels.

**Advice note:** *The consent holder is advised that the discharge of pumped groundwater to a stormwater system or waterbody will need to comply with any other regulations, bylaws or discharge rules that may apply.*

