

## WAIHI NORTH PROJECT - CONDITIONS FOR THE WAIKATO REGIONAL COUNCIL CONSENTS

### CONTENTS

|                                                                                |           |
|--------------------------------------------------------------------------------|-----------|
| <b>GENERAL CONDITIONS WHICH APPLY TO ALL WAIKATO REGIONAL COUNCIL CONSENTS</b> | <b>2</b>  |
| Exercise of Consents                                                           | 2         |
| Erosion and Sediment Control                                                   | 2         |
| Receiving Environment Standards                                                | 4         |
| Aquatic Ecology                                                                | 6         |
| Planting Areas                                                                 | 7         |
| Replacement of Water Supplies                                                  | 9         |
| Waihi Area Water Quality Management Plan                                       | 9         |
| Consent Review                                                                 | 10        |
| <b>RESOURCE CONSENTS WHICH APPLY TO ACTIVITIES UNDERTAKEN IN ALL AREAS</b>     | <b>12</b> |
| Air Discharge                                                                  | 13        |
| Soil disturbance and vegetation clearance                                      | 19        |
| Drilling below the water table                                                 | 20        |
| Groundwater Takes                                                              | 22        |
| <b>UNDERGROUND ACTIVITIES IN AREAS 1, 2, 3 and 5</b>                           | <b>23</b> |
| <b>AREA SPECIFIC CONSENTS</b>                                                  | <b>37</b> |
| AREA 1 SPECIFIC CONSENTS                                                       | 38        |
| AREA 2 SPECIFIC CONSENTS                                                       | 44        |
| AREA 5 SPECIFIC CONSENTS                                                       | 67        |
| AREA 6 SPECIFIC CONSENTS                                                       | 113       |
| AREA 7 SPECIFIC CONSENTS                                                       | 137       |

## GENERAL CONDITIONS WHICH APPLY TO ALL WAIKATO REGIONAL COUNCIL CONSENTS

### EXERCISE OF CONSENTS

|    |                                                                                                                                                                                                              |
|----|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| G1 | No later than 20 working days prior to the first exercise of any consent, the Consent Holder must advise the Waikato Regional Council in writing of the date upon which the consent will first be exercised. |
|----|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

### EROSION AND SEDIMENT CONTROL

|     |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
|-----|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| G2  | Conditions G3 – G17 apply to land disturbance and works within watercourses in Areas 2, 5, 6 and 7, where the area is not subject to permanent stormwater management infrastructure. They do not apply to land disturbance in areas which are isolated from waterbodies and adjacent land using permanent diversion drains, silt ponds, collection ponds and / or other permanent mine water management infrastructure.                                                                                                                                                                                                                            |
| G3  | Where works are undertaken within any watercourse in Areas 2, 5, 6 and 7, where the area is not subject to permanent stormwater management infrastructure, the Consent Holder must establish and maintain erosion and sediment control measures that are:<br><br>a. Consistent with Waikato Regional Council Technical Report No. 2009/02 Erosion and Sediment Control Guidelines for Soil Disturbing Activities, January 2009 ( <b>TR2009/02</b> ) or any subsequent version of those guidelines (in which case the latter version prevails).; and<br><br>b. In accordance with Erosion and Sediment Control Assessment Report by Southern Skies. |
| G4  | To minimise erosion, the Consent Holder must ensure, to the greatest extent practicable, that all clean water run-off from stabilised surfaces including catchment areas up gradient of the site is diverted away from the exposed areas via a stabilised system.                                                                                                                                                                                                                                                                                                                                                                                  |
| G5  | The Consent Holder must ensure that all run-off from areas where soil disturbance has occurred is treated by sediment retention structures prior to discharge, in accordance with any Site Specific Erosion and Sediment Control Plan (SSESCP) required by Condition G13. These structures are to be fully operational before soil disturbance in the relevant Area commences.                                                                                                                                                                                                                                                                     |
| G6  | The works authorised by this consent must not cause increases in upstream or down stream flows which cause flooding on adjacent land.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |
| G7  | All earthmoving machinery, and ancillary equipment must be operated in a manner which ensures spillages of fuel, oil and similar contaminants are prevented to the greatest extent practicable. Refuelling and lubrication activities must be carried out a distance from any water body, ephemeral water body, or overland flow path, that is sufficient to ensure that any spillage can be contained and not enter surface water.                                                                                                                                                                                                                |
| G7a | The storage of nitrogen-based explosives must be at a distance from any water body, ephemeral water body or overland flow path, that is sufficient to ensure that any spillage can be contained and not enter surface water. Any permanent storage facility for nitrogen-based explosives must prevent any loss of nitrogenous compounds to groundwater.                                                                                                                                                                                                                                                                                           |
| G8  | The Consent Holder must ensure that all mobile and non-fixed plant, equipment and machinery used for surface activities in Area 1 is cleaned prior to being transported to the Area to ensure that                                                                                                                                                                                                                                                                                                                                                                                                                                                 |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|     |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |
|-----|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|     | all seed and plant matter has been removed. Cleaning must be undertaken and documented in accordance with the document titled ' <i>KEEP IT CLEAN - best practice guide #A16</i> ' produced by National Pest Control Agencies, ISBN 978-1-877474-54-5, June 2013 or any subsequent version of the guide (in which case the latter version prevails).                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |
| G9  | All disturbed or cut vegetation, soil or debris must be placed in a position where it will not enter, nor cause erosion of, any water body.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |
| G10 | <ol style="list-style-type: none"> <li>Where chemical treatment forms part of the proposed erosion and sediment control measures, the Consent Holder must submit to the WRC a Chemical Treatment Plan for written certification under Condition C5, Schedule One no later than 30 working days prior to commencement of the works concerned.</li> <li>Certification is required to verify that the Chemical Treatment Plan: <ol style="list-style-type: none"> <li>Has been prepared in accordance with the draft Chemical Treatment Plan included as Appendix A of the Southern Skies Erosion and Sediment Control Assessment Report;</li> <li>Includes actions, methods, monitoring programmes and trigger levels as appropriate to meet the objectives in Condition G11; and</li> <li>Satisfies the requirements set out in Condition G12.</li> </ol> </li> </ol>                          |
| G11 | <p>The objectives of the Chemical Treatment Plan are to:</p> <ol style="list-style-type: none"> <li>Identify the circumstances where chemical treatment is necessary to enhance the efficacy of sediment retention ponds and decanting earth bunds; and</li> <li>Confirm details of the chemical treatment system.</li> </ol>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |
| G12 | <p>The Chemical Treatment Plan must as a minimum, include:</p> <ol style="list-style-type: none"> <li>An analysis of site soil reactivity to flocculants;</li> <li>Design details of the flocculation system, including within which sediment retention ponds and decanting earth bunds flocculants will be used;</li> <li>Monitoring (including pH and any other testing procedures) and maintenance (including post-storm) requirements, including a record keeping system;</li> <li>Details of optimum flocculant dosage (including assumptions); and</li> <li>Contact details of the person responsible for the operation and maintenance of the flocculation treatment system and the organisational structure to which this person shall report.</li> </ol>                                                                                                                             |
| G13 | <ol style="list-style-type: none"> <li>The Consent Holder must submit a SSESCP for works in each Area specified in Condition G2 for written certification under Condition C5, Schedule One no later than 30 working days prior to commencement of activities in the respective Area.</li> <li>Certification is required to verify that the SSESCP for each Area: <ol style="list-style-type: none"> <li>Has been prepared by a suitably qualified and experienced person in accordance with the draft Site Specific Erosion and Sediment Control Plan included as Appendix C of the Southern Skies Erosion and Sediment Control Assessment Report; and</li> <li>Satisfies the requirements set out in Condition G14.</li> </ol> </li> </ol> <p><i>Advice Note: Site Specific Erosion and Sediment Control Plans may be submitted for each Area separately or multiple Areas combined.</i></p> |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|     |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |
|-----|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| G14 | <p>Each SSESCP must include, as a minimum:</p> <ol style="list-style-type: none"> <li>A description of the construction activities to be undertaken;</li> <li>The specific erosion and sediment control measures to be implemented to achieve the conditions of this consent, including their location, dimensions and capacity;</li> <li>Supporting calculations and design drawings;</li> <li>Catchment boundaries and contour information;</li> <li>Location(s) of stabilised entranceway(s);</li> <li>Details of temporary and permanent stabilisation; and</li> <li>The construction methodology for any stream works within the relevant SSESCP works area.</li> </ol> |
| G15 | <p>The Consent Holder must ensure that all erosion and sediment control structures are inspected to identify any maintenance requirements, as follows:</p> <ol style="list-style-type: none"> <li>On a weekly basis; and</li> <li>During the period commencing 24 hours before any forecast rainfall event of 25 mm over the subsequent 24 hours; and</li> <li>As soon as practicable following any rainfall event exceeding 25 mm over 24 hours.</li> </ol>                                                                                                                                                                                                                 |
| G16 | <ol style="list-style-type: none"> <li>The Consent Holder must maintain records detailing: <ol style="list-style-type: none"> <li>The date, time and results of the inspection undertaken in accordance with Condition G15; and</li> <li>The erosion and sediment controls that required maintenance; and</li> <li>The date and time when the maintenance was completed.</li> </ol> </li> <li>These records must be provided to the Waikato Regional Council within 72 hours of a written request to do so.</li> </ol>                                                                                                                                                       |
| G17 | <p>Erosion and sediment control measures must only be removed:</p> <ol style="list-style-type: none"> <li>Once the corresponding catchment area has been permanently stabilised; or</li> <li>When in accordance with a certified SSESCP.</li> </ol>                                                                                                                                                                                                                                                                                                                                                                                                                          |

## RECEIVING ENVIRONMENT STANDARDS

G18

The discharges authorised by these consents and any associated seepage, in combination with all other discharges authorised for the Consent Holder’s mining activities must not exceed the limits set out in Table 1.

| Table 1: Receiving Water Quality Standards for the Ohinemuri River and its Tributaries |                                                                                                                                                                             |                                                                                                                                                                             |
|----------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Parameter                                                                              | Receiving Water Concentration                                                                                                                                               |                                                                                                                                                                             |
| g/m <sup>3</sup> unless otherwise stated                                               | Hardness 20 g/m <sup>3</sup> CaCO <sub>3</sub>                                                                                                                              | Hardness 100 g/m <sup>3</sup> CaCO <sub>3</sub>                                                                                                                             |
| pH                                                                                     | 6.0 to 9.0                                                                                                                                                                  | 6.0 to 9.0                                                                                                                                                                  |
| Suspended solids                                                                       | For upstream concentrations of less than or equal to 100 g/m <sup>3</sup> the increase must be no greater than 10 g/m <sup>3</sup> . For upstream concentrations of greater | For upstream concentrations of less than or equal to 100 g/m <sup>3</sup> the increase must be no greater than 10 g/m <sup>3</sup> . For upstream concentrations of greater |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|                                                                     | than 100 g/m <sup>3</sup> the increase must be no greater than 10% | than 100 g/m <sup>3</sup> the increase must be no greater than 10% |
|---------------------------------------------------------------------|--------------------------------------------------------------------|--------------------------------------------------------------------|
| Cyanide (CN <sub>WAD</sub> ) <sup>(1)</sup> – in Areas 5 and 7 only | 0.093                                                              | 0.093                                                              |
| Iron                                                                | 1.0                                                                | 1.0                                                                |
| Manganese                                                           | 2.0                                                                | 2.0                                                                |
| Copper                                                              | 0.003                                                              | 0.011                                                              |
| Nickel                                                              | 0.040                                                              | 0.160                                                              |
| Zinc                                                                | 0.027                                                              | 0.100                                                              |
| Silver <sup>1</sup>                                                 | 0.00025                                                            | 0.0028                                                             |
| Total Ammonia                                                       | Refer Table 3                                                      | Refer Table 3                                                      |
| Antimony                                                            | 0.030                                                              | 0.030                                                              |
| Arsenic                                                             | 0.190                                                              | 0.190                                                              |
| Selenium                                                            | 0.27                                                               | 0.27                                                               |
| Mercury                                                             | 0.000012                                                           | 0.000012                                                           |
| Cadmium                                                             | 0.0003                                                             | 0.001                                                              |
| Chromium (VI)                                                       | 0.010                                                              | 0.010                                                              |
| Lead                                                                | 0.0004                                                             | 0.0025                                                             |

### Advice Notes:

- 1) Site specific criteria derived using US EPA (1985) methodology.
- 2) Monitoring of metals must be based on the soluble test method, defined as the concentration of dissolved metals measured in that fraction which passes through a 0.45 µm filter except for mercury (Hg) which must be based on acid soluble concentrations determined on unfiltered samples.
- 3) Current analytical procedures for mercury have a practical quantification limit (“PQL”) of 0.0005 ppm. This PQL is acceptable for the purposes of reporting mercury concentrations. The reporting ‘limit’ for mercury concentrations must be reviewed annually by the Consent Holder and must be adjusted in line with improvements in analytical technology.

| Table 2 – Criteria for Total Ammonia (g/m <sup>3</sup> ) |      |      |      |      |      |      |      |
|----------------------------------------------------------|------|------|------|------|------|------|------|
| Temp (°C)                                                | 0    | 5    | 10   | 15   | 20   | 25   | 30   |
| pH                                                       |      |      |      |      |      |      |      |
| 6.50                                                     | 3.0  | 2.8  | 2.7  | 2.5  | 2.5  | 2.5  | 2.4  |
| 6.75                                                     | 3.0  | 2.8  | 2.7  | 2.6  | 2.5  | 2.5  | 2.5  |
| 7.00                                                     | 3.0  | 2.8  | 2.7  | 2.6  | 2.5  | 2.5  | 2.5  |
| 7.25                                                     | 3.0  | 2.8  | 2.7  | 2.6  | 2.5  | 2.5  | 2.5  |
| 7.50                                                     | 3.0  | 2.8  | 2.7  | 2.6  | 2.5  | 2.5  | 2.5  |
| 7.75                                                     | 2.8  | 2.6  | 2.5  | 2.4  | 2.3  | 2.3  | 2.4  |
| 8.00                                                     | 1.82 | 1.70 | 1.62 | 1.57 | 1.55 | 1.55 | 1.59 |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|                                                                                   |      |       |       |       |       |      |      |      |
|-----------------------------------------------------------------------------------|------|-------|-------|-------|-------|------|------|------|
|                                                                                   | 8.25 | 1.03  | 0.97  | 0.93  | 0.90  | 0.90 | 0.91 | 0.94 |
|                                                                                   | 8.50 | 0.58  | 0.55  | 0.53  | 0.53  | 0.53 | 0.55 | 0.58 |
|                                                                                   | 8.75 | 0.34  | 0.32  | 0.31  | 0.31  | 0.32 | 0.35 | 0.38 |
|                                                                                   | 9.00 | 0.195 | 0.189 | 0.189 | 0.195 | 0.21 | 0.23 | 0.27 |
| <i>Advice Note: To convert the values to mg/l as nitrogen, multiply by 0.822.</i> |      |       |       |       |       |      |      |      |

## AQUATIC ECOLOGY

|                               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |
|-------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|                               | <i>Advice Note: Aquatic ecology is subject to the Aquatic Fauna Salvage and Relocation Plans included in the WUG and Waihi Area Ecology and Landscape Management Plans Condition C5 of Schedule One</i>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |
| <i>Aquatic Ecology Offset</i> |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |
| G19                           | <p>The Consent Holder must undertake the following ecological offset works:</p> <ol style="list-style-type: none"> <li>Riparian restoration of, and the exclusion of stock from, 1,995 m of stream length of Tributaries 1 and 3 at the Willows Road site as shown in the Ecology and Landscape Management Plan Waihi Area (ELMP-WA) referred to in Condition C5 of Schedule One;</li> <li>Restoration of, and the exclusion of stock from, at least six spring and gully headwaters (at least 80 m in length in total) within the headwaters of Tributary 3 at the Willows Road site as shown in the ELMP-WA referred to in Condition C5 of Schedule One;</li> <li>Developing 2,765 metres of new stream channel with the ecological functionality shown in Appendix 1: Indicative Stream Channel Diversion Design of the Freshwater Fisheries Dispensation for the areas shown in the ELMP-WA referred to in Condition C5 of Schedule One; and</li> <li>Riparian restoration of 7,646 metres of stream length shown in the ELMP-WA referred to in Condition C5 of Schedule One, including the new stream channel required by (c) above, over an average width of 20 m (which can be spread across one or both banks).</li> </ol> <p><i>Advice Note: Collectively these areas are referred to as the Aquatic Ecology Offset Areas.</i></p> |
| <i>Diversion Design</i>       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |
| G20                           | <p>Stream diversion and enhancement measures must be consistent with Type 1, Type 2 or Type 3 diversions shown in the Stream Diversion and Development Plan provided within the ELMP-WA referred to in Condition C5 of Schedule One, and incorporate the following design elements:</p> <ol style="list-style-type: none"> <li>Stream diversions are to convey clean water, or surface water treated to remove silt (i.e., uncontaminated by construction or operational activities);</li> <li>The design of the diversion channels must create a range of stable microhabitats for fish and invertebrates, including stable pool habitats and gravel and cobble habitat, sufficient to achieve a level of stream function equivalent to that predicted through the mitigation calculations set out in the Boffa Miskell Freshwater Ecological Assessment;</li> <li>The diversion channel around TSF3 and the NRS must allow the passage of migrating eels and other native fish with climbing abilities;</li> <li>Riparian vegetation should extend to at least 10 m either side (where this occurs on land owned by the Consent Holder) of the channel and must include low-growing species with</li> </ol>                                                                                                                               |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |
|--|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|  | <p>overhanging cover in accordance with the Stream Enhancement Riparian Planting Plan provided within the ELMP-WA;</p> <p>e. Diversions should be constructed prior to the reclamation of the original channel;</p> <p>f. Where a diversion is required but it is not possible to replicate the existing habitat value (such as the upper reaches of the Ruahorehore Stream Tributary diversion channel) or where construction is taking place, then a clean water cut off drain must be created;</p> <p>g. The diversion around TSF3 must include provision for a 1.2 ha wetland to the east of the TSF3.</p> |
|--|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

### PLANTING AREAS

|                                                                                                                                                                       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <p><i>Advice Note: Planting is subject to the Residual Effects Offset Plan and Planting Plan included in the Waihi Area Ecology and Landscape Management Plan</i></p> |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
| G21                                                                                                                                                                   | <p>Subject to Condition G22, the Consent Holder must undertake the planting identified in <b>Figures A and B in Attachment 1</b> and the Table in <b>Attachment 2</b>.</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |
| G22                                                                                                                                                                   | <p>Should there be a delay in the completion of planting reflected in the timeframe set out in the ELMP due to:</p> <p>a. The availability of suitable seedlings; or</p> <p>b. Natural conditions resulting in poor seed production, or poor seed condition, or otherwise adversely affecting seedling propagation for indigenous plant species;</p> <p>the Consent Holder must provide the Waikato Regional Council with an amended timeframe within which pioneer and enrichment planting must occur. This timeframe must not exceed four planting seasons. The Consent Holder must complete the planting as soon as reasonably possible within the agreed timeframe and must inform the Waikato Regional Council when planting is complete.</p> |
| G23                                                                                                                                                                   | <p>Where ecological benefits can be obtained from excluding stock or carrying out riparian planting ahead of stream diversion work occurring, the Consent Holder must identify these measures and must demonstrate to the Waikato Regional Council how these measures can be implemented ahead of the diversion work, without later being compromised by that work. Any such early works must be implemented no later than the planting season that precedes the diversion work being commenced, as far as is practicable.</p>                                                                                                                                                                                                                     |
| G24                                                                                                                                                                   | <p>All planting required to be undertaken under Condition G21 must:</p> <p>a. Use plants which are ecosourced from the Coromandel or Bay of Plenty Ecological Region; and</p> <p>b. Use seed collected locally and germinated and raised at a New Zealand Plant Producers Incorporated (NZPPI)-accredited nursery or from a suitable alternative community-based nursery.</p>                                                                                                                                                                                                                                                                                                                                                                      |
| G25                                                                                                                                                                   | <p>1. All planting required to be undertaken under Condition G21 must be regularly maintained, including regular releasing of plants from weeds and replacement of plants that do not survive. Any species that consistently fails must be replaced with an alternative similar species listed as suitable for that purpose in the ELMP.</p>                                                                                                                                                                                                                                                                                                                                                                                                       |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|                              |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |
|------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|                              | <p>2. Maintenance must continue until at least 70 percent stream canopy shade success is achieved, except where this planting is carried out adjacent to the Ruahorehore Stream and the Ohinemuri River, in which case the required shade success requirement will be determined by an ecological assessment of canopy health to the satisfaction of the Waikato Regional Council.</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |
| <i>Access and Protection</i> |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |
| G26                          | <p>1. Except as provided for in Condition G27, stream diversions or loss of stream extent in Areas 5, 6 and 7 must not occur until the Waikato Regional Council has been provided with written confirmation that the Consent Holder has entered into legal agreements and/or holds other authorisations necessary to allow entry onto land to carry out, continue and maintain all Aquatic Offset measures required by Condition G19.</p> <p>2. The written confirmation must describe any specific legal arrangements and the land to which they apply, being land purchase, agreement providing for covenanting or similar registered title instruments that have been entered into to provide the planted and retired areas to be retained in perpetuity.</p> <p>3. Conditions G26.1 and G26.2 only apply to privately owned land and do not apply to land owned or administered by the Department of Conservation or any other public agency.</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |
| G27                          | <p>In the event that, despite best endeavours:</p> <p>1 The Consent Holder is unable to secure for any given area(s) the legal agreements and/or other authorisations specified in Condition G26: or</p> <p>2 A planting area identified in Condition G21 proves to be non-viable for any other reasons:</p> <p>a. The Consent Holder must identify alternative area(s) for riparian planting which have been assessed by a suitably qualified and experienced ecologist (the Ecologist) to be of equal or greater ecological value to the area(s) for which access could not be secured; and</p> <p>b. The Consent Holder must provide a written report to the Waikato Regional Council which sets out details of the replacement area(s), including;</p> <p>i. the ownership and legal title of the land;</p> <p>ii. the existing ecological condition;</p> <p>iii. the proposed enhancement works; and</p> <p>iv. a statement from the Ecologist demonstrating that the ecological values of the Aquatic Offset of the replacement area(s) are of equal or greater ecological value to the area(s) for which access could not be secured; and</p> <p>c. Stream diversions or loss of stream extent in Areas 5, 6 and 7 must not commence until the Waikato Regional Council has agreed in writing that the ecological values of the Aquatic Offset of the replacement area(s) are of equal or greater ecological value to the area(s) for which access could not be secured; and</p> <p>d. Condition G21 applies to the new area(s) as if they were those they are intended to replace.</p> |

## Appendix B4: Conditions for the Waikato Regional Council Consents

### REPLACEMENT OF WATER SUPPLIES

|     |                                                                                                                                                                                                                                                                                                                                                                                                        |
|-----|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| G28 | If the Waikato Regional Council determines that activities authorised by this consent are adversely affecting any lawfully established stock, domestic or other water supplies, the Consent Holder must, at its own cost, provide an alternative equivalent water supply, to the satisfaction of Waikato Regional Council, within 12 hours of being directed to do so by the Waikato Regional Council. |
|-----|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

### WAIHI AREA WATER QUALITY MANAGEMENT PLAN

|     |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |
|-----|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| G29 | <ol style="list-style-type: none"><li>1. The Consent Holder must submit a Waihi Area Water Quality Management Plan for written certification under Condition C5 of Schedule One no later than 30 working days prior to commencement of activities in any of Areas 2,3,5,6 and 7.</li><li>2. Certification is required to verify that the Waihi Area Water Quality Management Plan:<ol style="list-style-type: none"><li>a. Includes actions, methods, monitoring programmes and trigger levels as appropriate to meet the objective in Condition G30; and</li><li>b. Satisfies the requirements in Condition G31</li></ol></li></ol> <p><i>Advice Note: The Waihi Area Water Quality Management Plan may be merged with the existing water management plan for Waihi operations</i></p>                                                                                                                                                                                                                                                                                                                                |
| G30 | <p>The objective of the Waihi Area Water Quality Management Plan is to identify all sources of discharges to water in Areas 2,3,5,6 and 7 and set out:</p> <ol style="list-style-type: none"><li>a. The actions and methods required to minimise and mitigate adverse effects on the receiving water, water users, and aquatic biota;</li><li>b. The monitoring programmes and trigger levels required to ensure the best practicable options are being utilised to minimise and mitigate adverse effects on the receiving water, water users, or aquatic biota; and</li><li>c. To describe how the Waikato Regional Council is able to determine that the activity is being undertaken in a manner which appropriately avoids or remedies any more than minor effects on the receiving water, water users, or aquatic biota.</li></ol>                                                                                                                                                                                                                                                                                |
| G31 | <p>The Waihi Area Water Quality Management Plan must include, as a minimum:</p> <ol style="list-style-type: none"><li>a. A description of the water management system to be implemented to meet the requirements of Condition G30, with emphasis on management of stormwater and water requiring treatment in the Water Treatment Plant;</li><li>b. A description of measures to be adopted to meet the conditions of AUTH144654.05, AUTH144654.09, AUTH144654.12, AUTH144654.19, AUTH144654.20, AUTH144654.23, AUTH144654.32, AUTH144654.33, AUTH144654.41, AUTH144654.44, AUTH144654.51, AUTH144654.55, and to ensure that any impacts on receiving waters are minimised;</li><li>c. A contingency plan describing how any unauthorised discharges will be managed so as to remedy or mitigate potential adverse effects on water; and</li><li>d. A monitoring programme designed to define site discharge quality and receiving water quality, and to assess the effects of discharges on the receiving waters, including compliance with Condition G18. The monitoring programme must address monitoring</li></ol> |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|     |                                                                                                                                                                                                                                                                                                                                                                         |
|-----|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|     | methods, parameters, site locations, and calibration and maintenance of monitoring equipment.                                                                                                                                                                                                                                                                           |
| G32 | <ol style="list-style-type: none"> <li>1. The Waihi Area Water Quality Management Plan must be reviewed at least annually by the Consent Holder to ascertain whether any amendments are required in order to ensure ongoing compliance with Condition G30.</li> <li>2. Any required amendments must be made in accordance with Condition C8 of Schedule One.</li> </ol> |

### WAIHI DRINKING WATER SUPPLY

|     |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |
|-----|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| G33 | In the event of any system failure in Area 2 that could result in adverse effects on the quality of water at the Hauraki District Council water supply extraction points (identified in the Hauraki District Council water permits), no later than 24 hours after the occurrence of the system failure the Consent Holder must notify the Hauraki District Council (as the consent holder) and Waikato Regional Council (as the consent authority) that a system failure has occurred. |
|-----|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

### CONSENT REVIEW

|     |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
|-----|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| G34 | <ol style="list-style-type: none"> <li>1. Pursuant to sections 128(1)(a)(i) and (iii) of the Resource Management Act 1991, the Waikato Regional Council may, within one month of the second anniversary of the commencement of this consent and every 24 months thereafter, or on receipt of any of the reports required by this consent, review the conditions of these consents for the following purposes: <ol style="list-style-type: none"> <li>a. To review the effectiveness of the conditions of this consent in avoiding, remedying or mitigating any adverse effects on the environment that may arise from the exercise of this consent, and if necessary to avoid, remedy or mitigate such effects by way of further or amended conditions. In deciding to undertake a review and where further or amended conditions are deemed necessary, the Waikato Regional Council must have regard to all of the information contained in the reports required under the conditions of this consent; or</li> <li>b. To address any adverse effects on the environment which have arisen as a result of the exercise of this consent that were not anticipated at the time of commencement of the consent; or</li> <li>c. To review the adequacy of, and necessity for, any of the monitoring programmes, management plans or strategies that are part of the conditions of this consent.</li> </ol> </li> <li>2. Any review under this condition must, in addition to the matters set out in the Resource Management Act 1991, also recognise and provide for the purpose of the Fast-track Approvals Act 2024.</li> <li>3. In undertaking any review of conditions that are cross-referred to in the: <ol style="list-style-type: none"> <li>a. Wharekirauponga Access Arrangement;</li> <li>b. Favona Access Arrangement;</li> <li>c. Northern Area Concession; or</li> <li>d. Willows Area Concession</li> </ol> </li> </ol> |
|-----|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

**Appendix B4: Conditions for the Waikato Regional Council Consents**

|  |                                                                                                                                                                                                                                                  |
|--|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|  | <p>the Waikato Regional Council will invite the Department of Conservation to comment on the proposed wording of any amended conditions and take into account any comments received when finalising the wording of those amended conditions.</p> |
|--|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

**RESOURCE CONSENTS WHICH APPLY TO ACTIVITIES UNDERTAKEN IN  
ALL AREAS**

## Appendix B4: Conditions for the Waikato Regional Council Consents

### AIR DISCHARGE

|                                        |                                                                                                       |
|----------------------------------------|-------------------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                       | AUTH144654.01.01                                                                                      |
| CONSENT TYPE AND ACTIVITIES AUTHORISED | RMA S15 To discharge contaminants to air from all activities associated with the Waihi North Project. |
| LOCATION                               | All Areas                                                                                             |
| TERM                                   | 35 years                                                                                              |
| LAPSE PERIOD                           | 10 years                                                                                              |

|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |
|---------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|         | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |
| ALL.A.1 | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent.                                                                                                                                                                                                                                                                                                                                                                                                   |
|         | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |
| ALL.A.2 | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                                                                                                                                                                                                                                                                                                                                                                                                                                 |
|         | <b>General Requirements</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |
| ALL.A.3 | There must be no particulate matter or (including odour) in any discharge to air that gives rise to objectionable adverse effects (as defined in Section 6.4 of the Waikato Regional Plan) at or beyond the boundary of the subject property shown as Area's 1, 2, 3, 5, 6 and 7 of Attachment 1 (Waihi North Project Areas) in Schedule 1.                                                                                                                                                                                                                                                                                          |
| ALL.A.4 | Condition ALL.A.3 does not apply to any property or site that is: <ul style="list-style-type: none"> <li>a. Owned by the Consent Holder or a related company and exclusively occupied by the Consent Holder or leased and exclusively occupied by the Consent Holder; or</li> <li>b. Owned by a third party which is subject to either a registered covenant or a written agreement (a copy of which is provided to the Waikato Regional Council) whereby air quality effects on the property caused by activities authorised under this consent are not to be taken into account for monitoring and compliance purposes.</li> </ul> |
| ALL.A.5 | If any non-compliance with the conditions of this consent occurs, the Consent Holder must notify the Waikato Regional Council as soon as practicable and no later than 5 working days after the Consent Holder becomes aware that the event has occurred.                                                                                                                                                                                                                                                                                                                                                                            |
| ALL.A.6 | The Consent Holder must provide a written report to the Waikato Regional Council within five days of being notified by the Waikato Regional Council that a discharge to air has resulted in an objectionable effect at or beyond the boundary of land that is under the control of the Consent Holder. The report must specify: <ul style="list-style-type: none"> <li>a. The cause or likely cause of the event and any factors that influenced its severity;</li> </ul>                                                                                                                                                            |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
|----------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|          | <p>b. The nature and timing of any measures implemented by the Consent Holder to avoid, remedy or mitigate any adverse effects; and</p> <p>c. The steps proposed to be taken in future to prevent recurrence of similar events.</p>                                                                                                                                                                                                                |
| ALL.A.7  | The Consent Holder must implement the measures set out in Condition ALL.A.6 c, and any additional measures required by the Waikato Regional Council, to the satisfaction of the Waikato Regional Council.                                                                                                                                                                                                                                          |
| ALL.A.8  | Vehicle wheel washing facilities must be provided at the entrances to the mine related work sites from public roads. The wheel washing facilities must be well maintained and must be used by all soiled vehicles exiting the site, to minimise the tracking of particulate matter off-site.                                                                                                                                                       |
| ALL.A.9  | Access roads to the mine related work sites (excluding internal access roads) must be bitumen sealed (or to an equivalent standard approved by Waikato Regional Council). Sealing must take place as soon as practicable upon exercise of this consent and/or as part of any access road construction that is required. Sealed surfaces must be kept as clean and free of accumulations of dust as practicable.                                    |
| ALL.A.10 | All embankments, batters and other bare surfaces created through earthworks must be managed to minimise particulate emissions and be revegetated as soon as reasonably practicable.                                                                                                                                                                                                                                                                |
| ALL.A.11 | Stockpiles must be managed to minimise particulate emissions. Methods may include but are not limited to: covering, grassing, sheltering from prevailing winds, or wetting down.                                                                                                                                                                                                                                                                   |
| ALL.A.12 | Exposed yard surfaces and roadways must be kept damp as necessary to minimise particulate discharges to air, including during non-work hours.                                                                                                                                                                                                                                                                                                      |
| ALL.A.13 | No chemical dust suppressants or additives may be used without prior written approval from the Waikato Regional Council.                                                                                                                                                                                                                                                                                                                           |
|          | <b>Processing Plant - Air Discharge</b>                                                                                                                                                                                                                                                                                                                                                                                                            |
| ALL.A.14 | The Consent Holder must not process ore from the Gladstone Open Pit until a mercury retort oven has been installed and commissioned for use in the Processing Plant.                                                                                                                                                                                                                                                                               |
| ALL.A.15 | The Consent Holder must not operate any part of the gold recovery process (from electrowinning to carbon regeneration) without the associated emission control equipment being fully operational and functioning correctly.                                                                                                                                                                                                                        |
| ALL.A.16 | <ol style="list-style-type: none"> <li>1. The discharges to air from the electrowinning circuit must occur via a stack of at least 8 m above local ground level.</li> <li>2. The discharges to air from the oven and furnace must occur via a stack of at least 8.5 m above local ground level.</li> <li>3. The discharges to air from the carbon regeneration area must occur via a stack of at least 12.5 m above local ground level.</li> </ol> |
| ALL.A.17 | The Consent Holder must not process more than 2.25 million tonnes of ore at the Processing Plant in any 12 month period. No more than 0.611 million tonnes of the ore processed in any 12 month period is to be derived from the Gladstone Open Pit.                                                                                                                                                                                               |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |
|----------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| ALL.A.18 | <ol style="list-style-type: none"> <li>1. The combined mercury mass emitted from the sources listed in Condition ALL.A.16 over a 12 month period must be included in the annual monitoring report required by Condition ALL.A.26.</li> <li>2. If the combined mercury mass of the emitted mercury rate exceeds 131.4 kilograms for the year, the Consent Holder must specify within the annual monitoring report the actions that will be taken to reduce site mercury emissions and the timeframes within which these actions will be implemented.</li> </ol> <p><i>Advice Note: The annual mass mercury emission rate will be calculated from the operation information required by Condition ALL.A. 19, and the emission testing required by Condition ALL.A.21.</i></p>                                                                                                                                                                                                                                                                 |
|          | <b>Monitoring Processing Plant Air Discharge</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |
| ALL.A.19 | <ol style="list-style-type: none"> <li>1. For each type of ore processed by the Processing Plant, the Consent Holder must maintain a record of the following: <ol style="list-style-type: none"> <li>a. The amount of each ore type processed per year;</li> <li>b. The number of hours per year that each of the following emission sources are operated for each ore type: <ol style="list-style-type: none"> <li>i. The electrowinning circuit;</li> <li>ii. The oven and furnace; and</li> <li>iii. The carbon regeneration area.</li> </ol> </li> </ol> </li> <li>2. The findings of the records must be included in the annual monitoring report required by Condition ALL.A.26.</li> </ol>                                                                                                                                                                                                                                                                                                                                           |
| ALL.A.20 | A representative sample of any ore derived from the Gladstone Open Pit which is being processed in the Processing Plant must be collected at least once per month and sent to an IANZ accredited laboratory for analysis for mercury content as a percent by weight.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |
| ALL.A.21 | <ol style="list-style-type: none"> <li>1. Emission testing of the discharges from the sources listed in Condition ALL.A.16 must be conducted: <ol style="list-style-type: none"> <li>a. Twice per year for the first five years following commencement of this consent and then annually thereafter; and</li> <li>b. Within one month of the Consent Holder commencing processing ore from any new source, including the Gladstone Open Pit and Wharekirauponga Underground Mine;</li> </ol> </li> <li>2. The emission testing must be undertaken in accordance with USEPA Method 29 or an equivalent method approved by the Waikato Regional Council.</li> <li>3. The emission testing must be carried out by a suitably qualified professional with appropriate independent accreditation for the methods required for testing.</li> <li>4. The air contaminants included in the testing must, as a minimum, include: <ol style="list-style-type: none"> <li>a. mercury;</li> <li>b. arsenic;</li> <li>c. cadmium;</li> </ol> </li> </ol> |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |
|----------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|          | <ul style="list-style-type: none"> <li>d. chromium;</li> <li>e. nickel; and</li> <li>f. lead.</li> </ul> <p>5. The mercury content of the ore being processed at the time of testing must be recorded.</p> <p>6. The findings of the emission testing must be included in the annual monitoring report required by Condition ALL.A.26, with the mass discharge and discharge concentration of each contaminant reported. The discharge concentration results must be corrected to 0°C, 101.325 kPa and a dry gas basis.</p> <p>7. The testing of emission from the processing of different ore must be sufficient to enable an annual mass mercury emission rate to be calculated.</p>                                                                                                                                                        |
|          | <b>Air Quality Management Plan</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |
| ALL.A.22 | <p>1. Other than Area 3, for each Area described in Condition C1(i) of Schedule One the Consent Holder must submit an Air Quality Management Plan for written certification under Condition C5 of Schedule One no later than 30 working days prior to the commencement of activities in the respective Area.</p> <p>2. Certification is required to verify that the Air Quality Management Plan:</p> <ul style="list-style-type: none"> <li>a. Includes actions, methods, monitoring programmes and trigger levels as appropriate to meet the objectives in Condition ALL.A.23; and</li> <li>b. Satisfies the requirements in Condition ALL.A.24.</li> </ul> <p><i>Advice note: Air Quality Management Plans may be submitted for each Area separately or multiple Areas combined.</i></p>                                                    |
| ALL.A.23 | <p>The objectives of the Air Quality Management Plan are to identify all sources of discharges to air and set out:</p> <ul style="list-style-type: none"> <li>a. The measures required to mitigate dust emissions from all operations;</li> <li>b. Management of point and non-point source air emissions required to protect human health and the environment;</li> <li>c. Measures required to ensure that emissions are within Workplace Exposure Standards and are not objectionable or offensive;</li> <li>d. Protocols to monitor areas of community concern, respond to complaints and non-compliances and to communicate mitigation undertaken; and</li> <li>e. Best practicable options to minimise and mitigate adverse effects of discharges to air.</li> </ul>                                                                    |
| ALL.A.24 | <p>The Air Quality Management Plan must include, as a minimum:</p> <ul style="list-style-type: none"> <li>a. Details of the site operation and maintenance practices to be implemented to meet the requirements of Condition ALL.A.23 and to ensure that emissions from stockpiles, unsealed roadways, the Processing Plant, rock stacks and tailings storage facilities are minimised to the greatest extent practicable;</li> <li>b. An ambient air monitoring programme for deposited particulate matter (<b>DP</b>), total suspended particulate (<b>TSP</b>), particulate matter smaller than ten microns (<b>PM<sub>10</sub></b>) and particle size distribution studies (including silica content) including the type of particulate and meteorology monitoring instruments to be used, their installation, calibration and</li> </ul> |

## Appendix B4: Conditions for the Waikato Regional Council Consents

- maintenance and reference to the relevant Australia and New Zealand Standards for meteorological and particulate monitoring.
- c. With reference to the TSP and PM<sub>10</sub> require monitoring specified under this condition to be undertaken using a nephelometer instrument, or alternative instrument subject to approval by the Waikato Regional Council, to be used with a heated inlet to minimise the interface from humidity, configured to record concentrations in µg/m<sup>3</sup>;
  - d. Monitoring of windspeed, and TSP within 200m of sensitive receptors, and associated use of the trigger levels set out in Table ALL.A.24.T1 to determine the circumstances where additional dust control measures, or if required, the cessation of work, is necessary to ensure Condition ALL.A.3 is satisfied;
  - e. A process for investigating any exceedance of the trigger levels, reporting on the reason for the exceedance, and identifying and implementing corrective actions to prevent a repeat occurrence, where possible;
  - f. Procedures for revegetation of batters at the mine site, Tailings Storage Facility embankments, stockpiles and other bare surface areas as appropriate;
  - g. Details of the key personnel responsible for ensuring that site operations are carried out in accordance with the Air Quality Management Plan;
  - h. A process for investigating and reporting on any complaints about dust levels; and
  - i. Details of the site operation and maintenance practices to be implemented, particularly in relation to the stockpiles, haul roads, and access roads, to keep dust emissions to a minimum.

**Table ALL.A.24.T1: Trigger Levels and Actions**

| Item                                                                                                                              | Trigger                                                                                                                                        | Action                                                                                                                                                                                           |
|-----------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| TSP Alert                                                                                                                         | TSP concentration (1-hour average) exceeds 170 µg/m <sup>3</sup> .                                                                             | Dust sources and dust control measures within 200 m of sensitive receptors will be reviewed and additional dust control methods shall be implemented if necessary, as detailed in the site AQMP. |
| TSP Alarm                                                                                                                         | TSP concentration (1-hour average) exceeds 200 µg/m <sup>3</sup><br><br>Or<br>TSP concentration (24-hour average) exceeds 60 µg/m <sup>3</sup> | Contributing dust generating activities will cease within 200 m of sensitive receptors except for dust control activities as detailed in the AQMP.                                               |
| Wind Speed Alert<br>(applicable to activities within the Gladstone Open Pit (Area 5) only, and does not apply during rain events) | Rolling hourly average wind speeds exceed 5 m/s and winds are blowing towards sensitive receptors.                                             | Dust sources and dust control measures within 200 m of sensitive receptors will be reviewed and additional dust control methods shall be implemented if necessary, as detailed in the site AQMP. |
| Wind Speed Alarm<br>(applicable to activities within the Gladstone                                                                | Rolling hourly average wind speeds exceed 7.5 m/s and winds are blowing towards sensitive receptors.                                           | Contributing dust-generating activities will cease within 200 m of sensitive receptors except for dust control activities as detailed in the site AQMP.                                          |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |
|----------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|          | Open Pit (Area 5) only, and does not apply during rain events)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |
|          | <b>Monitoring</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |
| ALL.A.25 | The Consent Holder must undertake monitoring in accordance with the certified Air Quality Management Plan.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |
| ALL.A.26 | <ol style="list-style-type: none"> <li>The Consent Holder must submit an annual Air Quality Monitoring Report to the Waikato Regional Council. The Air Quality Monitoring Report must, as a minimum include: <ol style="list-style-type: none"> <li>A summary of the results of the monitoring required by this consent;</li> <li>Any environmentally important trends arising from the monitoring programme;</li> <li>Compliance with all conditions;</li> <li>Any reasons for non-compliance or difficulties in achieving compliance with the conditions of this resource consent; and</li> <li>Any works that have been undertaken to improve environmental performance or that are proposed to be undertaken in the up-coming year to improve environmental performance in relation to the activities included in this consent.</li> </ol> </li> <li>The report must be provided in a format acceptable to the Waikato Regional Council.</li> </ol>                                                                                                                                                                                                                          |
|          | <b>Complaints</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |
| ALL.A.27 | <ol style="list-style-type: none"> <li>If any complaints are received by the Consent Holder regarding dust, odour or other airborne contaminants that could reasonably be attributed to the Consent Holder's activities under these consents the Consent Holder must record the following details in a complaint log: <ol style="list-style-type: none"> <li>The date, time and details of the complaint;</li> <li>The name and address of complainant (if available);</li> <li>The location from which the complaint arose;</li> <li>The wind direction at the time of complaint;</li> <li>The likely cause of the complaint and any factors that influenced its severity;</li> <li>Any corrective action taken by the Consent Holder in response to the complaint, including timing of that corrective action; and</li> <li>Action taken or proposed as a result of the complaint including the steps to be taken in future to prevent recurrence of similar events.</li> </ol> </li> <li>The complaint log must be made available to the Waikato Regional Council on request and a copy must be submitted to the Waikato Regional Council at six monthly intervals</li> </ol> |

## Appendix B4: Conditions for the Waikato Regional Council Consents

### SOIL DISTURBANCE AND VEGETATION CLEARANCE

|                                           |                                                                                              |
|-------------------------------------------|----------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                          | AUTH144654.02.01                                                                             |
| CONSENT TYPE AND<br>ACTIVITIES AUTHORISED | RMA S9 To undertake soil disturbance and vegetation clearance in a<br>high-risk erosion area |
| LOCATION                                  | All Areas                                                                                    |
| TERM                                      | 35 years                                                                                     |
| LAPSE PERIOD                              | 10 years                                                                                     |

|         |                                                                                                                                                                                                                                    |
|---------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|         | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                          |
| ALL.B.1 | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent. |
|         | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                      |
| ALL.B.2 | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                               |

## Appendix B4: Conditions for the Waikato Regional Council Consents

### DRILLING BELOW THE WATER TABLE

|                                           |                                                                                                                                                                           |
|-------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                          | AUTH144654.03.01                                                                                                                                                          |
| CONSENT TYPE AND<br>ACTIVITIES AUTHORISED | RMA S9 / S15 To drill holes below the water table for mineral exploration, geotechnical investigation, water quality monitoring and to establish and operate piezometers. |
| LOCATION                                  | All Areas                                                                                                                                                                 |
| TERM                                      | 35 years                                                                                                                                                                  |
| LAPSE PERIOD                              | 10 years                                                                                                                                                                  |

|         |                                                                                                                                                                                                                                                                                                                  |
|---------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|         | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                                                                                                        |
| ALL.C.1 | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent.                                                                               |
|         | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                                                                                                    |
| ALL.C.2 | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                                                                                                             |
|         | <b>General Requirements</b>                                                                                                                                                                                                                                                                                      |
| ALL.C.3 | The Waikato Regional Council must be notified in writing at least two weeks in advance of the installation of each bore, standpipe, piezometer, and groundwater monitoring bore.                                                                                                                                 |
| ALL.C.4 | The bore must be constructed and maintained so that it will not cause cross contamination between hydraulic units (aquifers) in any water (including groundwater and geothermal water).                                                                                                                          |
| ALL.C.5 | <ol style="list-style-type: none"> <li>1. All openings to the bore must be sealed or screened to prevent the entry of foreign matter or contaminants.</li> <li>2. The ground immediately surrounding the top of the bore casing must be sealed and graded to drain surface water away from the bore.</li> </ol>  |
| ALL.C.6 | Upon completion of the bore, any wastes introduced to the bore during drilling and construction must be removed.                                                                                                                                                                                                 |
| ALL.C.7 | If artesian conditions are encountered, a conductor casing must be grout sealed to ensure control of potential flowing artesian groundwater and to prevent instability of the ground at the bore head. Bore head completion must be such that groundwater leakage under flowing artesian pressures is prevented. |
| ALL.C.8 | Discharge of wastewater from bore installation into or onto the ground is permitted provided that only non-hazardous and non-toxic drilling fluids and/or foams are used as approved by Waikato                                                                                                                  |

#### Appendix B4: Conditions for the Waikato Regional Council Consents

|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |
|----------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|          | Regional Council. Drilling must be undertaken in such a manner that there is no discharge of grease or oil, and wastewater does not directly enter surface water.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |
| ALL.C.9  | Bores that are no longer operational must be decommissioned to prevent contamination.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |
| ALL.C.10 | <p>The Consent Holder must submit to the Waikato Regional Council (within one month of an agreed anniversary date) an annual report which contains:</p> <ul style="list-style-type: none"><li>a. a log for each bore drilled during that calendar year. Each log must show:<ul style="list-style-type: none"><li>i. the location of the bore</li><li>ii. date of completion</li><li>iii. duration of drilling</li><li>iv. depth and diameter of the bore</li><li>v. the method of drilling</li><li>vi. full construction details</li><li>vii. the subsurface geology</li><li>viii. development information</li><li>ix. installed instrumentation (pumps, loggers, flow meters, etc.)</li></ul></li><li>b. A list of any decommissioned bores, including their logs.</li></ul> |

## Appendix B4: Conditions for the Waikato Regional Council Consents

### GROUNDWATER TAKES

|                                           |                                                                                                                                                   |
|-------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                          | AUTH144654.04.01                                                                                                                                  |
| CONSENT TYPE AND<br>ACTIVITIES AUTHORISED | RMA S14 To take groundwater for the purpose of servicing drilling activities relating to exploration, monitoring and geotechnical investigations. |
| LOCATION                                  | All Areas                                                                                                                                         |
| TERM                                      | 35 years                                                                                                                                          |
| LAPSE PERIOD                              | 10 years                                                                                                                                          |

|         |                                                                                                                                                                                                                                    |
|---------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|         | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                          |
| ALL.D.1 | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent. |
|         | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                      |
| ALL.D.2 | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                               |
|         | <b>Limits</b>                                                                                                                                                                                                                      |
| ALL.D.3 | The rate of abstraction from any individual bore used to service drilling activities must not exceed 3 litres / second.                                                                                                            |
| ALL.D.4 | Abstraction to service drilling activities must not occur from more than 4 bores in the same catchment at any given time.                                                                                                          |

**UNDERGROUND ACTIVITIES IN AREAS 1, 2, 3 AND 5**

## Appendix B4: Conditions for the Waikato Regional Council Consents

|                                        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |
|----------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                       | AUTH144654.05.01                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |
| CONSENT TYPE AND ACTIVITIES AUTHORISED | <p>RMA S9 To drill below the water table to establish underground tunnels, access portals and mines using a drill and blast technique. (UG.1)</p> <p>RMA S14 To take and divert groundwater intercepted during tunnelling and stoping activities. (UG.2)</p> <p>RMA S14 To take groundwater for surface water contingency mitigation purposes. (UG.3)</p> <p>RMA S15 To discharge contaminants to land and groundwater associated with the underground storage, use and backfilling of rock containing potential acid forming material and hydrocarbons. (UG.4)</p> <p>RMA S15 To discharge contaminants to land and groundwater when sealing drill holes and underground workings. (UG.5)</p> <p>RMA S15 To discharge groundwater to streams and wetlands for surface water contingency mitigation purposes. (UG.6)</p> |
| LOCATION                               | Areas 1, 2, 3, and 5                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |
| TERM                                   | 35 years                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |
| LAPSE PERIOD                           | 10 years                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |

|      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |
|------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|      | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                                                                                                                                                                                                                                                                                                                                               |
| UG.1 | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent.                                                                                                                                                                                                                                                                                                                      |
|      | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                           |
| UG.2 | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                                                                                                                                                                                                                                                                                                                                                    |
|      | <b>Definitions</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |
| UG.3 | <p>For the purposes of this consent:</p> <p>a. <b>Access Tunnels</b> means:</p> <ul style="list-style-type: none"> <li>i. The Wharekirauponga Access Tunnel which connects the Waihi Surface Facilities Area to the WUG Dual Tunnel and Willows Access Tunnel;</li> <li>ii. The WUG Dual Tunnel and related development which connect the WUG mining activities to the Wharekirauponga Access Tunnel; and</li> <li>iii. The Willows Access Tunnel which connects the Willows Surface Facilities Area with the Wharekirauponga Access Tunnel.</li> </ul> |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |
|------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|      | <p>b. Condition C.1.g of Schedule One does not apply and <b>Mining Activities</b> means:</p> <ol style="list-style-type: none"> <li>Ore drive development along the EG Vein System; and</li> <li>Stoping Activities (being the extraction of ore via drill and blast methods from level-to-level drill holes greater than 15 m).</li> </ol> <p>c. For groundwater management purposes, <b>EG Vein System</b> means any orebody associated structures that will be mined or hydraulically connected to mined structures, which have the potential to cause effects on shallow groundwater.</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |
|      | <b>Pre-Mining Activities Groundwater Management</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |
| UG.4 | <p>The Consent Holder must control groundwater ingress into all tunnels and ventilation shafts not including those that are Mining Activities by:</p> <ol style="list-style-type: none"> <li>Conducting drilling and investigative work sufficiently in advance of the tunnel faces within the Access Tunnels to assess geotechnical and hydrogeological conditions and evaluate where and what type of grouting or alternative mitigation measures may be required to manage any groundwater effects;</li> <li>Having available, when and where required, the equipment and suitably qualified and experienced personnel to conduct appropriate monitoring, carry out necessary mitigation, test the efficacy of measures employed and if required, implement alternative mitigation required within the Access Tunnels; and</li> <li>Ensuring that grouting or alternative methods to control groundwater ingress within the Access Tunnels and ventilation shafts are adapted where necessary to address any deviations from expected conditions and to avoid measurable effects on shallow groundwater which may adversely affect any surface water body.</li> </ol>                                                                                                                |
| UG.5 | <ol style="list-style-type: none"> <li>Subject to (b), at quarterly intervals during the construction of the Access Tunnels the Consent Holder must provide to the Waikato Regional Council, the Department of Conservation, and Expert Groundwater Management Panel required by Condition UG.30, a report (<b>Quarterly Access Tunnel Report</b>) which: <ol style="list-style-type: none"> <li>Describes the location, depth and excavated volume (m<sup>3</sup>) of the tunnels;</li> <li>Describes the total volume of water pumped to and from the tunnels;</li> <li>Identifies the lengths of the tunnels that, due to the encountered geotechnical and hydrogeological conditions, required grouting or alternative methods of mitigation to control the ingress of groundwater, and a description of the grouting or alternative mitigation that was undertaken; and</li> <li>Includes analysis of the effectiveness of the grouting or alternative mitigation over the previous three-month period and any proposed amendments as to how the Consent Holder will implement the requirements of Condition UG.4.</li> </ol> </li> <li>The first Quarterly Access Tunnel Report must be provided no later than four months after Access Tunnel construction commences.</li> </ol> |
|      | <b>Baseline Data Collection Ahead of Mining Activities</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |
| UG.6 | <ol style="list-style-type: none"> <li>The Consent Holder must undertake not less than two years of baseline data collection prior to the commencement of mining activities at the Wharekirauponga Underground Mine. The purpose of the baseline data collection is to confirm key hydrological and hydrogeological statistics (including seasonal variations where appropriate) of the hydrological and hydrogeological systems in the Wharekirauponga Catchment in such a way as to enable actual and potential material changes to those systems as a result of mining activities authorised by</li> </ol>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|                                          | <p>this consent to be identified through monitoring and addressed through management responses by the Consent Holder.</p> <p>2. The baseline data collection must include ecological condition of the wetlands listed in Table UG.13.T, as outlined in Condition UG.10.</p> <p>3. The baseline data collection must be undertaken in accordance with the Wharekirauponga Underground Mine Water Management Plan referred to in Condition C5 of Schedule One.</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                                          |                                      |       |                  |       |                  |               |                  |                |                  |              |                  |
|------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------|--------------------------------------|-------|------------------|-------|------------------|---------------|------------------|----------------|------------------|--------------|------------------|
|                                          | <b>Compliance Limits – Natural State Water Bodies and Natural Inland Wetlands Potentially Affected by Mining Activities</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                                          |                                      |       |                  |       |                  |               |                  |                |                  |              |                  |
| UG.7                                     | Other than for flows associated with the warm spring located nominally at NZTM E1850258, N5868719, and the EG vein discharge point the mining activities authorised by this consent must not cause the natural flows of any surface water body identified as a Natural State Water Body in the Waikato Regional Plan and identified as being potentially affected by mining activities in the Wharekirauponga Hydrology Modelling report prepared by GHD Limited (WAI-985-000-REP-LC-0063) dated January 2025 to fall below the relevant Respond Trigger Levels set out in Condition UG.10.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                                          |                                      |       |                  |       |                  |               |                  |                |                  |              |                  |
|                                          | <b>Natural State Water Bodies</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |                                          |                                      |       |                  |       |                  |               |                  |                |                  |              |                  |
| UG.8                                     | <p>1. To ensure compliance with Condition UG.7 during mining activities, and in accordance with the Wharekirauponga Underground Mine Water Management Plan referred to in Condition C5 of Schedule One, the Consent Holder must implement a monitoring programme which is capable of identifying when any reductions in the natural flows of Natural State Water Bodies are occurring as a result of the mining activities authorised by this consent.</p> <p>2. As a minimum the monitoring programme must:</p> <ol style="list-style-type: none"> <li>Measure and record the daily volume of water pumped from the underground mine (in accordance with Condition UG.39);</li> <li>Provide data on the dewatering effects on groundwater at different levels (shallow and deep) in the vicinity of the Wharekirauponga Underground Mine;</li> <li>Measure and record daily rainfall data specific to the catchments above the Wharekirauponga Underground Mine; and</li> <li>Provide data on the stream flow of Natural State Water Bodies and water levels within Natural Inland Wetlands above and in the vicinity of the Wharekirauponga Underground Mine, and at control sites in similar nearby catchments that will not be affected by mining activities, as set out in Condition UG.9.</li> </ol> |                                          |                                      |       |                  |       |                  |               |                  |                |                  |              |                  |
| UG.9                                     | <p>The monitoring programme required by Condition UG.8 must be implemented at the locations listed in Table UG.9.T below, unless otherwise agreed in writing by the Waikato Regional Council.</p> <p><b>Table UG.9.T</b></p> <table border="1"> <thead> <tr> <th>Natural State Water Body Monitoring Site</th><th>Map Reference NZTM2000 (Approximate)</th></tr> </thead> <tbody> <tr> <td>WKP01</td><td>1851376, 5871977</td></tr> <tr> <td>WKP03</td><td>1850400, 5868874</td></tr> <tr> <td>T-Stream West</td><td>1849598, 5868439</td></tr> <tr> <td>Edmonds Stream</td><td>1849983, 5868181</td></tr> <tr> <td>Adams Stream</td><td>1850384, 5868980</td></tr> </tbody> </table>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | Natural State Water Body Monitoring Site | Map Reference NZTM2000 (Approximate) | WKP01 | 1851376, 5871977 | WKP03 | 1850400, 5868874 | T-Stream West | 1849598, 5868439 | Edmonds Stream | 1849983, 5868181 | Adams Stream | 1850384, 5868980 |
| Natural State Water Body Monitoring Site | Map Reference NZTM2000 (Approximate)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |                                          |                                      |       |                  |       |                  |               |                  |                |                  |              |                  |
| WKP01                                    | 1851376, 5871977                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                                          |                                      |       |                  |       |                  |               |                  |                |                  |              |                  |
| WKP03                                    | 1850400, 5868874                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                                          |                                      |       |                  |       |                  |               |                  |                |                  |              |                  |
| T-Stream West                            | 1849598, 5868439                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                                          |                                      |       |                  |       |                  |               |                  |                |                  |              |                  |
| Edmonds Stream                           | 1849983, 5868181                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                                          |                                      |       |                  |       |                  |               |                  |                |                  |              |                  |
| Adams Stream                             | 1850384, 5868980                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                                          |                                      |       |                  |       |                  |               |                  |                |                  |              |                  |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |                   |  |
|-------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------|--|
|       | Thompson Stream                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | 1851165, 5869253  |  |
|       | LS1 (Control Site)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | 1851389, 5872531  |  |
|       | LS6 (Control Site)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | 1850462, 5870689  |  |
|       | WS2 (Control Site)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | 1854081, 5868827  |  |
|       | WHK2 (Control Site)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | 18498320, 5865641 |  |
| UG.10 | <div>1. At all times during mining activities, the Consent Holder must compare the monitored stream flow and rainfall conditions required by Condition UG.8 against the Alert Trigger Levels identified in Table UG.10.T below.</div> <div><i>Advice Note: The Alert Trigger Levels in Table UG.10.T reflect the modelled mean annual low flow for each of the listed Natural State Water Bodies and represents a rolling 7-day mean flow. <b>Attachment 1</b> details and defines the composition / function of the derivation of the Alert Trigger Level.</i></div> <div><i>If monitoring identifies that the flow in a Natural State Water Body is less than the Alert Trigger Level for that Natural State Water Body as set out in Table UG.10.T, this signifies that the Natural State Water Body has been in a state of low flow for a 7-day period, however it does not imply that the flow in the Natural State Water Body has been affected by the mining activities authorised by this consent. (Advice note ends)</i></div> <div>2. If a flow of less than the Alert Trigger Level for a Natural State Water Body in Table UG.10.T is recorded, the Consent Holder must undertake daily reviews of the flows at each of the listed Natural State Water Body locations set out in Table UG.9 until the flows are no longer less than the Alert Trigger Level, and:</div> <div><div>a. Check and verify the stream flow data, rainfall data and groundwater level data from piezometers near to these sites for the period leading up to the trigger event for accuracy and consistencies;</div><div>b. Check and verify the stream flow data and groundwater level data at the identified control sites, or at similar suitable locations, for evidence of similar or trending flow patterns and / or alignment with the expected rainfall / flow trends, and potential climatic drivers of the observed data; and</div><div>c. Provide a summary report of the Alert Trigger Level occurrences in a report required by Condition UG.26.</div></div> <div>3. If monitoring identifies that the flow in those Natural State Water Body locations identified in Table UG.9.T is less than the Respond Trigger Level for that Natural State Water Body calculated in accordance with Table UG.10.T, the Consent Holder must immediately cease any upstream surface water abstraction and commission a suitably qualified and experienced professional approved by the Waikato Regional Council to investigate the cause of the Respond Trigger Level exceedance, and provide a report which summarises the findings of that investigation as set out in Condition UG.27. If the investigation finds that mining activities have caused the Respond Trigger Level to be breached, the Consent Holder must implement mitigation measures in accordance with the Wharekirauponga Underground Mine Water Management Plan referred to in Condition C5 of Schedule One, and as detailed in the Trigger Action Response specified in Condition UG.19(c).</div> |                   |  |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|                                                 | <table><tr><th colspan="3">Table UG.10.T: Alert and Respond Trigger Levels</th></tr><tr><th>Natural State Water Body</th><th>Alert Trigger Level, m<sup>3</sup>/day<br/>(based off a rolling 7-day mean flow)</th><th>Respond Trigger Level, m<sup>3</sup>/day<br/>(R<sub>30</sub> = the rolling 30-day mean rainfall in mm)</th></tr><tr><td>WKP01</td><td>10,200</td><td>2213 x R<sub>30</sub> + 4285</td></tr><tr><td>WKP03</td><td>4,800</td><td>1106 x R<sub>30</sub> + 1864</td></tr><tr><td>T-Stream West</td><td>2,700</td><td>626 x R<sub>30</sub> + 919</td></tr><tr><td>Edmonds Stream</td><td>2,200</td><td>447 x R<sub>30</sub> + 930</td></tr><tr><td>Thompson Stream</td><td>1,600</td><td>299 x R<sub>30</sub> + 856</td></tr><tr><td>Adams Stream</td><td>1,000</td><td>145 x R<sub>30</sub> + 577</td></tr></table> <p><i>Advice Note: References to Natural State Water Body Alert and Respond Trigger Levels throughout the Waihi North Project – Conditions for the Waikato Regional Council are those set out in Table UG.10.T, unless the Alert and Respond Trigger Levels in Table UG.10.T have been adjusted via the provisions of Condition UG.29.</i></p>                                                                                                                                                                                                                                                                                                                                                   | Table UG.10.T: Alert and Respond Trigger Levels                                                          |  |  | Natural State Water Body | Alert Trigger Level, m <sup>3</sup> /day<br>(based off a rolling 7-day mean flow) | Respond Trigger Level, m <sup>3</sup> /day<br>(R <sub>30</sub> = the rolling 30-day mean rainfall in mm) | WKP01 | 10,200 | 2213 x R <sub>30</sub> + 4285 | WKP03 | 4,800 | 1106 x R <sub>30</sub> + 1864 | T-Stream West | 2,700 | 626 x R <sub>30</sub> + 919 | Edmonds Stream | 2,200 | 447 x R <sub>30</sub> + 930 | Thompson Stream | 1,600 | 299 x R <sub>30</sub> + 856 | Adams Stream | 1,000 | 145 x R <sub>30</sub> + 577 |
|-------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------|--|--|--------------------------|-----------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------|-------|--------|-------------------------------|-------|-------|-------------------------------|---------------|-------|-----------------------------|----------------|-------|-----------------------------|-----------------|-------|-----------------------------|--------------|-------|-----------------------------|
| Table UG.10.T: Alert and Respond Trigger Levels |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |                                                                                                          |  |  |                          |                                                                                   |                                                                                                          |       |        |                               |       |       |                               |               |       |                             |                |       |                             |                 |       |                             |              |       |                             |
| Natural State Water Body                        | Alert Trigger Level, m <sup>3</sup> /day<br>(based off a rolling 7-day mean flow)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | Respond Trigger Level, m <sup>3</sup> /day<br>(R <sub>30</sub> = the rolling 30-day mean rainfall in mm) |  |  |                          |                                                                                   |                                                                                                          |       |        |                               |       |       |                               |               |       |                             |                |       |                             |                 |       |                             |              |       |                             |
| WKP01                                           | 10,200                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | 2213 x R <sub>30</sub> + 4285                                                                            |  |  |                          |                                                                                   |                                                                                                          |       |        |                               |       |       |                               |               |       |                             |                |       |                             |                 |       |                             |              |       |                             |
| WKP03                                           | 4,800                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 1106 x R <sub>30</sub> + 1864                                                                            |  |  |                          |                                                                                   |                                                                                                          |       |        |                               |       |       |                               |               |       |                             |                |       |                             |                 |       |                             |              |       |                             |
| T-Stream West                                   | 2,700                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 626 x R <sub>30</sub> + 919                                                                              |  |  |                          |                                                                                   |                                                                                                          |       |        |                               |       |       |                               |               |       |                             |                |       |                             |                 |       |                             |              |       |                             |
| Edmonds Stream                                  | 2,200                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 447 x R <sub>30</sub> + 930                                                                              |  |  |                          |                                                                                   |                                                                                                          |       |        |                               |       |       |                               |               |       |                             |                |       |                             |                 |       |                             |              |       |                             |
| Thompson Stream                                 | 1,600                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 299 x R <sub>30</sub> + 856                                                                              |  |  |                          |                                                                                   |                                                                                                          |       |        |                               |       |       |                               |               |       |                             |                |       |                             |                 |       |                             |              |       |                             |
| Adams Stream                                    | 1,000                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 145 x R <sub>30</sub> + 577                                                                              |  |  |                          |                                                                                   |                                                                                                          |       |        |                               |       |       |                               |               |       |                             |                |       |                             |                 |       |                             |              |       |                             |
| UG.11                                           | In circumstances where a Respond Trigger Level has not been exceeded, but investigations undertaken in response to an Alert Trigger level required by Condition UG.14 demonstrate that mining activities are giving rise to unanticipated effects on flows within the Natural State Water Bodies identified in Table UG.10.T, the Consent Holder must commission a suitably qualified and experienced professional approved by the Waikato Regional Council to investigate the cause of the Alert Trigger Level exceedance and provide a report which summarises the findings of that investigation as set out in Condition UG.27. If the investigation finds that mining activities have caused the Respond Trigger Level to be breached, the Consent Holder must implement mitigation measures in accordance with the Wharekirauponga Underground Mine Water Management Plan, and as detailed in the Trigger Action Response specified in Condition UG.19(c).                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |                                                                                                          |  |  |                          |                                                                                   |                                                                                                          |       |        |                               |       |       |                               |               |       |                             |                |       |                             |                 |       |                             |              |       |                             |
|                                                 | <b>Natural Inland Wetlands</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |                                                                                                          |  |  |                          |                                                                                   |                                                                                                          |       |        |                               |       |       |                               |               |       |                             |                |       |                             |                 |       |                             |              |       |                             |
| UG.12                                           | <div><div>1.</div><div>In accordance with the Wharekirauponga Underground Mine Water Management Plan referred to in Condition C5 of Schedule One the Consent Holder must develop and implement a wetland monitoring programme for the Natural Inland Wetlands identified in Table UG.13.T in Condition UG.13 which is capable of identifying when any reductions in the natural water levels of those wetlands occur as a result of the mining activities authorised by this consent, and any consequential adverse ecological impacts.</div></div> <div><div>2.</div><div>As a minimum the monitoring programme must include the monitoring methods specified in Condition UG.8, and it must:<div><div>a.</div><div>Measure and record the water levels in Natural Inland Wetlands that are potentially affected by mining activities and at a wetland control site in a similar nearby catchment that will not be affected by mining activities (as per Condition UG.13); and</div></div><div><div>b.</div><div>Measure and record (through visual inspection) characteristics associated with water levels in Natural Inland Wetlands that are potentially affected by mining activities (as per Condition UG.13). These must include:<div><div>i.</div><div>Signs of composition shifts towards dryland plant species measured using national wetland delineation protocols for Dominance and Prevalence from representative vegetation plots within each wetland listed in Table UG.13.T; and</div></div></div></div></div></div> |                                                                                                          |  |  |                          |                                                                                   |                                                                                                          |       |        |                               |       |       |                               |               |       |                             |                |       |                             |                 |       |                             |              |       |                             |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|                            | <p>ii. Increase in % cover of invasive non-native Facultative, Facultative Upland or Upland plant species, including pampas and blackberry.</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |                        |                                      |            |                  |            |                  |            |                  |            |                  |            |                  |         |                  |         |                  |         |                  |          |                  |                            |                                                                                                                             |
|----------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------|--------------------------------------|------------|------------------|------------|------------------|------------|------------------|------------|------------------|------------|------------------|---------|------------------|---------|------------------|---------|------------------|----------|------------------|----------------------------|-----------------------------------------------------------------------------------------------------------------------------|
| UG.13                      | <p>The monitoring programme required by Condition UG.12 must be implemented at the locations listed in Table UG.13.T below.</p> <p><b>Table UG.13.T: Monitoring Locations</b></p> <table> <tr> <th>Natural Inland Wetland</th><th>Map Reference NZTM2000 (Approximate)</th></tr> <tr> <td>Edmonds 16</td><td>1849962, 5867471</td></tr> <tr> <td>Edmonds 17</td><td>1849822, 5867407</td></tr> <tr> <td>Edmonds 18</td><td>1849887, 5867447</td></tr> <tr> <td>Edmonds 20</td><td>1849779, 5867359</td></tr> <tr> <td>Edmonds 22</td><td>1849708, 5867243</td></tr> <tr> <td>Adams 3</td><td>1850260, 5869204</td></tr> <tr> <td>Adams 4</td><td>1850028, 5869249</td></tr> <tr> <td>Adams 9</td><td>1849853, 5869173</td></tr> <tr> <td>Adams 10</td><td>1849859, 5869131</td></tr> <tr> <td>Waiharakeke (Control Site)</td><td>1848909, 5864926<br/><i>Or an alternative control location that is determined to be appropriate, as approved by the WRC.</i></td></tr> </table>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Natural Inland Wetland | Map Reference NZTM2000 (Approximate) | Edmonds 16 | 1849962, 5867471 | Edmonds 17 | 1849822, 5867407 | Edmonds 18 | 1849887, 5867447 | Edmonds 20 | 1849779, 5867359 | Edmonds 22 | 1849708, 5867243 | Adams 3 | 1850260, 5869204 | Adams 4 | 1850028, 5869249 | Adams 9 | 1849853, 5869173 | Adams 10 | 1849859, 5869131 | Waiharakeke (Control Site) | 1848909, 5864926<br><i>Or an alternative control location that is determined to be appropriate, as approved by the WRC.</i> |
| Natural Inland Wetland     | Map Reference NZTM2000 (Approximate)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |                        |                                      |            |                  |            |                  |            |                  |            |                  |            |                  |         |                  |         |                  |         |                  |          |                  |                            |                                                                                                                             |
| Edmonds 16                 | 1849962, 5867471                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                        |                                      |            |                  |            |                  |            |                  |            |                  |            |                  |         |                  |         |                  |         |                  |          |                  |                            |                                                                                                                             |
| Edmonds 17                 | 1849822, 5867407                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                        |                                      |            |                  |            |                  |            |                  |            |                  |            |                  |         |                  |         |                  |         |                  |          |                  |                            |                                                                                                                             |
| Edmonds 18                 | 1849887, 5867447                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                        |                                      |            |                  |            |                  |            |                  |            |                  |            |                  |         |                  |         |                  |         |                  |          |                  |                            |                                                                                                                             |
| Edmonds 20                 | 1849779, 5867359                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                        |                                      |            |                  |            |                  |            |                  |            |                  |            |                  |         |                  |         |                  |         |                  |          |                  |                            |                                                                                                                             |
| Edmonds 22                 | 1849708, 5867243                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                        |                                      |            |                  |            |                  |            |                  |            |                  |            |                  |         |                  |         |                  |         |                  |          |                  |                            |                                                                                                                             |
| Adams 3                    | 1850260, 5869204                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                        |                                      |            |                  |            |                  |            |                  |            |                  |            |                  |         |                  |         |                  |         |                  |          |                  |                            |                                                                                                                             |
| Adams 4                    | 1850028, 5869249                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                        |                                      |            |                  |            |                  |            |                  |            |                  |            |                  |         |                  |         |                  |         |                  |          |                  |                            |                                                                                                                             |
| Adams 9                    | 1849853, 5869173                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                        |                                      |            |                  |            |                  |            |                  |            |                  |            |                  |         |                  |         |                  |         |                  |          |                  |                            |                                                                                                                             |
| Adams 10                   | 1849859, 5869131                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                        |                                      |            |                  |            |                  |            |                  |            |                  |            |                  |         |                  |         |                  |         |                  |          |                  |                            |                                                                                                                             |
| Waiharakeke (Control Site) | 1848909, 5864926<br><i>Or an alternative control location that is determined to be appropriate, as approved by the WRC.</i>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |                        |                                      |            |                  |            |                  |            |                  |            |                  |            |                  |         |                  |         |                  |         |                  |          |                  |                            |                                                                                                                             |
| UG.14                      | <ol style="list-style-type: none"> <li>If an Alert Trigger Level in Condition UG.10 has been exceeded at any of the Table UG.10.T Natural State Water Bodies, the Consent Holder must: <ol style="list-style-type: none"> <li>Check and verify the water level monitoring data and groundwater level data from piezometers within and near the Natural Inland Wetland sites listed in U.13.T. for the period leading up to the trigger event for accuracy and consistency;</li> <li>Check and verify the water level monitoring data at the identified Natural Inland Wetland control site, or at similar suitable locations, for evidence of similar or trending water level patterns and / or alignment with the expected rainfall / water level trends, and potential climatic drivers of the observed data;</li> <li>Undertake a visual inspection of the listed Natural Inland Wetlands potentially affected by mining activities to assess the water level of those wetlands and in the adjacent groundwater; and</li> <li>Include a summary report of the Alert Trigger Level exceedances, in the report required by Condition UG.26.</li> </ol> </li> <li>If a Respond Trigger Level in Condition UG.10 has been exceeded at any of the Table UG.10.T Natural State Water Bodies, the Consent Holder must assess the water levels both within and adjacent to the wetlands to determine whether any changes, or differences of water level within any pair of piezometers, indicate a potential dewatering effect. If changes beyond the expected natural variation are found, the Consent Holder must commission a suitably qualified and experienced professional approved by the Waikato Regional Council to investigate the matter, and prepare a report as set out in Condition UG.27. If the investigation finds it to be necessary, the Consent Holder must implement appropriate mitigation measures in accordance with the Wharekirauponga Underground Mine Water Management Plan, and as detailed in the Trigger Action Response Plan (as per Condition UG.19(b)).</li> </ol> |                        |                                      |            |                  |            |                  |            |                  |            |                  |            |                  |         |                  |         |                  |         |                  |          |                  |                            |                                                                                                                             |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |
|--------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|        | <i>Advice Note: If the suitably qualified and experienced professional investigating changes beyond the expected natural variation of wetland water levels requires assistance from other experts, they may seek such assistance (including from members of the Expert Groundwater Panel).</i>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |
| UG.15  | <p>In the event that an assessment undertaken pursuant to Condition UG.11 or Condition UG.14 concludes that supplementation or reinjection of water to a Natural State Water Bodies or Natural Inland Wetlands from groundwater is required, the Consent Holder must advise the Waikato Regional Council and the Department of Conservation no later than 5 working days of the recharge commencing of:</p> <ul style="list-style-type: none"> <li>a. The location of groundwater bore(s) and discharge point(s); and</li> <li>b. The expected commencement date and duration of the abstraction and discharge;</li> </ul>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |
| UG.16  | The consent holder shall ensure that the effects of any discharge of groundwater for mitigation purposes does not adversely affect the aquatic life of the receiving environment.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |
| UG.17  | <p>Prior to any discharge of groundwater into a Natural Inland Wetland for mitigation purposes a representative sample of the groundwater must be collected and analysed for temperature, turbidity, pH, electrical conductivity, hardness, sulphate, copper, iron, manganese and zinc.</p> <p><i>Advice Note: This sampling is required to confirm the groundwater quality in that bore can be discharged for recharge purposes in a manner which will comply with Condition UG.16.</i></p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |
| UG.18  | Discharge of groundwater for Natural Inland Wetland effect mitigation purposes must not occur unless the groundwater analysis undertaken pursuant to Condition UG.17 demonstrates that the discharge will comply with Condition UG.16.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
|        | <b>Waiharakeke Stream Monitoring</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |
| UG.18A | The Consent Holder must ensure the Wharekirauponga Underground Mine Water Management Plan includes the monitoring of surface flows in the Waiharakeke Stream at locations where flows in that Stream may potentially be affected by groundwater discharging into the Wharekirauponga dual access tunnel                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |
|        | <b>Mine Related Groundwater Management and Monitoring</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |
| UG.19  | <p>From the commencement of mining activities authorised by this consent the Consent Holder must control groundwater ingress into the area being mined in a manner that ensures compliance with the limits set out within Condition UG.7 by, as a minimum:</p> <ul style="list-style-type: none"> <li>a. Installing monitoring instruments and undertaking hydraulic testing in groundwater zones potentially affected by mining activities in advance of mining occurring (including use of instruments installed prior to or as part of work required by the Wharekirauponga Underground Mine Water Management Plan).</li> <li>b. Once confirmed, the location of the monitoring instruments is to be incorporated into the Wharekirauponga Underground Mine Water Management Plan, along with rationale as to why these locations are being utilised;</li> <li>c. Adhering to the Trigger Action Response measures set out in the Wharekirauponga Underground Mine Water Management Plan referred to in Condition C5 of Schedule One during mining activities so that methods of mitigation to control effects on Natural State Water Bodies and/or Natural Inland Wetlands are suitably adapted to address any deviations from the expected natural parameters of the Natural State Water Bodies and/or Natural Inland Wetlands which have been identified as being potentially affected by mining activities, where, having regard to the Alert or Respond Trigger Levels set out in Table UG.10.T, those deviations have</li> </ul> |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |
|--------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|        | <p>the potential to give rise to more than minor adverse changes in the flow regimes and/or water levels of Natural State Water Bodies and/or Natural Inland Wetlands which are inconsistent with achieving Condition UG.7; and</p> <p>d. Having available, when and where required, the equipment and suitably qualified and experienced personnel to conduct appropriate monitoring, carry out necessary mitigation, test efficacy of measures employed and if required implement alternative mitigation measures.</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |
|        | <b>Wharekirauponga Underground Mine Water Management Plan</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |
| UG.20A | The Consent Holder must prepare and submit a Wharekirauponga Underground Mine Water Management Plan (WUMWMP) to the Waikato Regional Council for written certification under Condition C5 of Schedule One.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |
| UG.20  | The Consent Holder must implement the certified WUMWMP, subject to any amendments that may be made under Condition C7 of Schedule One.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |
| UG.21  | <p>The WUMWMP and any amendments to it must be prepared by a suitably qualified and experienced professional and must achieve the following objectives:</p> <ul style="list-style-type: none"> <li>a. Ensure protection of the Natural State Water Bodies and Natural Inland Wetlands from dewatering activities associated with mining activities;</li> <li>b. Describe how the Consent Holder will undertake dewatering activities in accordance with the principles in Condition UG.19; and</li> <li>c. Describe how the Waikato Regional Council and the Department of Conservation are able to determine that the activity is being undertaken in a manner which appropriately avoids or remedies any measurable reductions in the expected natural flows within the Natural State Water Bodies and/or natural water levels within the Natural Inland Wetlands which have been identified as being potentially affected by mining activities.</li> </ul>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |
| UG.22  | <p>The WUMWMP and any amendments to it must include the following:</p> <ul style="list-style-type: none"> <li>a. Identification of the baseline data to be collected;</li> <li>b. A detailed strategy, describing how mining activities and associated groundwater management will be undertaken to achieve the following outcomes: <ul style="list-style-type: none"> <li>i. To ensure protection of the Natural State Water Bodies and Natural Inland Wetlands from dewatering activities associated with mining activities;</li> <li>ii. To describe how the Consent Holder will undertake dewatering activities in accordance with the principles in Condition UG.19; and</li> <li>iii. To describe how the Waikato Regional Council and the Department of Conservation are able to determine that the activity is being undertaken in a manner which appropriately avoids or remedies any measurable reductions in the expected natural flows within the Natural State Water Bodies and/or the Natural Inland Wetlands which have been identified as being potentially affected by mining activities.</li> </ul> </li> <li>c. Monitoring that is required to be undertaken for the period when any dewatering activities are occurring within the mine to enable timely assessment of stream flows within Natural State Water Bodies against the surface flow levels set in Condition UG.10, Table UG.10.T, including rainfall, surface water flows and groundwater levels;</li> <li>ca. Monitoring that is required to be undertaken within a zone defined by a distance of 70 m either side of the alignment of the overlying Waiharakeke Stream invert to assess the effectiveness of grouting and potential for direct connection with the stream.</li> </ul> |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |
|-------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|       | <p>cb. If after a period of 12 months of monitoring the collected groundwater inflows to the dual access tunnels within a zone defined by a distance of 70 m either side of the alignment of the overlying Waiharakeke Stream are in general accordance with rock mass groundwater inflows from elsewhere within the dual tunnels then the monitoring required under Condition UG.22.ca may be discontinued.</p> <p>d. Monitoring that is required to be undertaken for the period when any dewatering activities are occurring within the mine to enable timely assessment of wetland water levels against the surface flow levels set in accordance with Condition UG.10, including rainfall, surface water flows and groundwater levels and pressure; and</p> <p>e. Identification of potential adaptive management and mitigation measures to be implemented in circumstances where dewatering activities result in flows/levels reaching the Respond Trigger Levels for Natural State Water Bodies in Condition UG.10.</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |
| UG.23 | Prior to submitting the Wharekirauponga Underground Mine Water Management Plan or any amendments to it to the Waikato Regional Council and the Department of Conservation, the Plan or amendments must be provided to the Expert Groundwater Management Panel for review and comment in accordance with Conditions UG.31 – UG.37.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |
| UG.24 | [this condition is intentionally blank]                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |
|       | <b>Reporting</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |
| UG.25 | <p>1. Within three months of the commencement of mining activities (which are not tunnelling or monitoring and data collection activities), and every three months thereafter the Consent Holder must provide to the Waikato Regional Council, the Department of Conservation, and Expert Groundwater Management Panel a report (<b>Quarterly Report</b>) which includes:</p> <ul style="list-style-type: none"> <li>a. A description of the monitoring instruments installed, and pre-development hydraulic testing undertaken;</li> <li>b. A summary of all collected surface water flow and wetland water level data;</li> <li>c. A description of any new mining activities, including their location, depth and volume;</li> <li>d. A description of any dewatering that has occurred, including the method of dewatering and the daily flow rates, volume and chemistry of the water;</li> <li>e. A description of any grouting or alternative migration undertaken to control the ingress of groundwater;</li> <li>f. Any other methods of addressing dewatering as part of the Trigger Action Response Plan.</li> <li>g. An analysis of the effectiveness of the grouting or other mitigation over the previous reporting period and any proposed amendments which should be made to the Wharekirauponga Underground Mine Water Management Plan and in turn to the groundwater management practices implemented by the Consent Holder.</li> </ul> <p><i>Advice Note. At the request of the Consent Holder, the Waikato Regional Council may agree in writing to a less frequent reporting obligation than specified in (a). When considering a less frequent reporting obligation the Waikato Regional Council will generally take advice from the Expert Groundwater Management Panel.</i></p> |
| UG.26 | <p>At least once every 12 months following the commencement of mining activities (which are not tunnelling or monitoring and data collection activities), the Consent Holder must provide to the Waikato Regional Council, the Department of Conservation, and Expert Groundwater Management Panel an Annual Groundwater and Surface Water Monitoring Report which includes:</p> <ul style="list-style-type: none"> <li>a. Data from all monitoring undertaken during the previous year;</li> </ul>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |
|-------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|       | <ul style="list-style-type: none"> <li>b. Identification of any effects or trends resulting from mine dewatering activities in the flow regimes of Natural State Water Bodies and/or water levels within Natural Inland Wetlands which are potentially affected by mining activities;</li> <li>c. Interpretation and analysis of any change in surface flows or wetland water levels during the previous year, and any mitigation actions taken in response to those changes;</li> <li>d. A summary of compliance and / or non-compliance with resource consent conditions; and</li> <li>e. A summary of any works that have been, or are proposed to be, undertaken to improve environmental performance in relation to activities authorised by this consent.</li> </ul>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |
|       | <b>Mine Compliance Monitoring and Reporting</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |
| UG.27 | In the event that a Respond Trigger Level is exceeded for Natural State Waterways and/or Natural Inland Wetlands the Consent Holder must provide to the Waikato Regional Council, the Department of Conservation, and the Expert Groundwater Panel a report ("Compliance Report") outlining the nature of the exceedance and, if the investigation required by either Condition UG.10 or Condition UG.14 finds it to be necessary, the remedial and / or mitigation measures that were applied to in response.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |
| UG.28 | The report required by Condition UG.27 must be provided to the Waikato Regional Council, the Department of Conservation, and the Expert Groundwater Management Panel within 40 working days of the Respond Trigger Level being exceeded.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |
|       | <b>Natural State Water Body and Natural Inland Wetland Compliance Trigger Level Adjustment</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |
| UG.29 | <ol style="list-style-type: none"> <li>1. If the monitoring required by Conditions UG.8 and UG.9 determines that the Alert Trigger Levels and / or Respond Trigger Levels set out in Condition UG.10 are not appropriate in order to assess a departure from the expected natural operating range of the Natural State Water Bodies or Natural Inland Wetlands, the Consent Holder must engage a suitably qualified and experienced expert to prepare a Compliance Trigger Level Adjustment Report. This report must set out any proposed adjustments to the Condition UG.10 Alert Trigger Levels or Respond Trigger Levels. The reasoning for the proposed adjustments must be outlined and the suitably qualified and experienced expert must confirm that the change in these trigger levels is valid and reflects the observed natural flow levels of the Natural State Water Bodies.</li> <li>2. The Compliance Trigger Level Adjustment Report must be submitted to the Waikato Regional Council for written certification. Prior to submitting the report to the Waikato Regional Council for certification purposes, it must be provided to the Expert Groundwater Management Panel for review and comment in accordance with Conditions UG.30 – UG.38.</li> <li>3. Once the Compliance Trigger Level Adjustment Report has been certified by the Waikato Regional Council, the Natural State Water Body Alert Trigger Levels and / or Respond Trigger Levels set out in Condition UG.10 may be changed through a RMA section 127 application.</li> <li>4. The Compliance Trigger Level Adjustment Report may be reviewed and updated at any time by the Consent Holder. Any updates to the trigger levels set out in Condition UG.10 must not be implemented until the updated Compliance Trigger Level Adjustment Report has been reviewed and commented upon by the Expert Groundwater Management Panel and subsequently re-certified by the Consent Authority.</li> </ol> |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|       | <b>Expert Groundwater Management Panel</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |
|-------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| UG.30 | Prior to commencing work on the access tunnels, the Consent Holder must engage, at its cost, an Expert Groundwater Management Panel.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
| UG.31 | <p>The role of the Expert Groundwater Management Panel is to review and provide advice and recommendations to Waikato Regional Council, the Department of Conservation, and the Consent Holder on the adequacy and appropriateness of the following:</p> <ol style="list-style-type: none"> <li>Proposed mitigation measures to be applied in circumstances where the Consent Holder is required to respond to an exceedance of an Alert or a Respond Trigger Level set out in Table UG.10.T;</li> <li>Quarterly Access Tunnel Reports required by Condition UG.5;</li> <li>Any review of the Wharekirauponga Underground Mine Water Management Plan under Conditions C.7 of Schedule One and UG.20A to UG.23, prior to its provision to Council for written certification;</li> <li>Quarterly Report required by Condition UG.25;</li> <li>The Annual Groundwater and Surface Water Monitoring Report required by Condition UG.26;</li> <li>Any Compliance Report required by Condition UG.27: and</li> <li>Any adjustments recommended to Alert Trigger Levels and / or Respond Trigger Levels under Condition UG.29.</li> </ol>                                                      |
| UG.32 | The Consent Holder must address any recommendations from the Expert Groundwater Management Panel in finalising any changes to the Wharekirauponga Underground Mine Water Management Plan and any other document referred to in Condition UG.31 that is submitted to the Waikato Regional Council and the Consent Holder must identify any recommendations made by the Expert Groundwater Management Panel that have not been adopted and the reasons for this.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |
| UG.33 | <ol style="list-style-type: none"> <li>The Expert Groundwater Management Panel must comprise of a member or members who have expertise and technical specialty which has been demonstrated in at least one of the following fields: <ol style="list-style-type: none"> <li>Mātauranga Māori;</li> <li>Hydrology;</li> <li>Hydrogeology, including demonstratable experience in assessment of surface water-groundwater interactions;</li> <li>Geotechnical engineering;</li> <li>The use of grouting techniques to manage groundwater inflows; and</li> <li>Underground mining.</li> </ol> </li> <li>The Consent Holder must invite the Iwi Advisory Group established in accordance with the requirements of Condition C9 of Schedule One to nominate representative(s) to provide the Mātauranga Māori expertise identified in a.</li> <li>There may be any number of individuals on the Expert Groundwater Management Panel, however to ensure the Panel is fulfilling the purposes of Condition UG.31, the Panel may engage / call on suitably qualified and experienced experts with expertise and speciality in the fields set out in (a) above as and when necessary.</li> </ol> |
| UG.34 | The members of the Expert Groundwater Management Panel, and their defined field(s) of expertise, must be approved by the Waikato Regional Council prior to appointment to the Panel.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |
|-------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| UG.35 | <ol style="list-style-type: none"> <li>1. In the instance that the Waikato Regional Council considers that a member of the Expert Groundwater Management Panel is not fulfilling their role in accordance with Condition UG.31, the Waikato Regional Council can terminate that member's position on the Panel.</li> <li>2. In the instance that such termination results in the Expert Groundwater Management Panel having no members, a new Panel member must be appointed in accordance with Condition UG.30.</li> </ol>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |
| UG.36 | The Expert Groundwater Management Panel may co-opt other specialist members to assist in any of its functions for specified tasks and periods, subject to the prior approval of the Waikato Regional Council.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |
| UG.37 | The Consent Holder must provide the Expert Groundwater Management Panel with all records, plans and designs that the Panel requests, and must afford the Panel reasonable access to mining activities as is necessary and consistent with health and safety procedures.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |
| UG.38 | <ol style="list-style-type: none"> <li>1. If there is disagreement between the Consent Holder and the Expert Groundwater Management Panel about a Panel recommendation, in the first instance the Consent Holder must invite the Expert Groundwater Management Panel and Waikato Regional Council to a collaborative workshop to determine a process of resolution.</li> <li>2. If a resolution cannot be agreed within 10 working days, the matter shall be referred to an independent appropriately qualified expert, acceptable to both the Consent Holder and the Expert Groundwater Management Panel ('Expert'), setting out the details of the matter to be referred for determination and the reasons the parties do not agree.</li> <li>3. The Expert shall, as soon as possible, issue a recommendation on the matter. Within five working days of receipt of the recommendation from the expert the Waikato Regional Council must advise the Consent Holder on whether the recommendation of the Expert Groundwater Management Panel which was in dispute shall be implemented or an alternative course of action may be taken.</li> </ol> |
|       | <b>Telemetry / Flow Metering</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |
| UG.39 | <ol style="list-style-type: none"> <li>1. The Consent Holder must record the quantity of water taken from underground on a cumulative basis. This data must be telemetered to the Waikato Regional Council.</li> <li>2. The telemetry system must be compatible with Waikato Regional Council telemetry system standards and data protocols and be provided in continuous 15 minute values of net take volume in units of cubic metres.</li> <li>3. The data must be reported once daily to the Waikato Regional Council via the telemetry system and there must be 96 values per day.</li> </ol>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
| UG.40 | <ol style="list-style-type: none"> <li>1. Prior to the first exercise of this consent and upon request of the Waikato Regional Council, the Consent Holder must undertake an assessment of the accuracy of the water measuring system(s). Each system must have a reliable calibration to water flow and must be maintained to an accuracy of +/- 5%.</li> <li>2. The assessment must be undertaken by an independent, qualified person and evidence documenting the assessment shall be forwarded to the Waikato Regional Council within one month of the assessment occurring.</li> </ol>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |
|       | <b>Consent Review</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |
| UG.41 | <ol style="list-style-type: none"> <li>1. Pursuant to Section 128(1)(a)(i) and (iii) of the Resource Management Act, the Waikato Regional Council may, 12 months from the commencement of this consent and annually thereafter, or on receipt of any of the reports required by the conditions of this consent, review any or all of the conditions of these consents for the following purposes: <ol style="list-style-type: none"> <li>a. To review the effectiveness of the conditions of this consent to avoid, remedy or mitigate the effects of dewatering within the access and development tunnels and during mining</li> </ol> </li> </ol>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |
|--|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|  | <p>activities on the expected natural flows of the Natural State Water Bodies and/or the natural water levels in Natural Inland Wetlands which have been identified as being potentially affected by tunnelling and mining activities, where those effects are likely to give rise to measurable adverse changes in these flows / levels, and if necessary to avoid, remedy or mitigate such effects by way of further or amended conditions; or</p> <p>b. To address any matter relating to the recommendations of the Expert Groundwater Management Panel required by the conditions of this consent.</p> <p><i>Advice Notes: Any review under this condition must, in addition to the matters set out in the Resource Management Act 1991, also recognise and provide for the purpose of the Fast Approvals Track Act 2024.</i></p> <p><i>In deciding to undertake a review and where further or amended conditions are deemed necessary, the Waikato Regional Council will generally have regard to all of the information contained in the reports required under the conditions of this consent.</i></p> |
|--|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

**AREA SPECIFIC CONSENTS**

## Appendix B4: Conditions for the Waikato Regional Council Consents

### AREA 1 SPECIFIC CONSENTS

|                                        |                                                                                 |
|----------------------------------------|---------------------------------------------------------------------------------|
| RESOURCE CONSENT                       | AUTH144654.06.01                                                                |
| CONSENT TYPE AND ACTIVITIES AUTHORISED | RMA S14 To take surface water from streams and wetlands for monitoring purposes |
| LOCATION                               | Area 1                                                                          |
| TERM                                   | 35 years                                                                        |
| LAPSE PERIOD                           | 10 years                                                                        |

|         |                                                                                                                                                                                                                                    |
|---------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|         | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                          |
| SC1.A.1 | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent. |
|         | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                      |
| SC1.A.2 | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                               |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|                                        |                                                                                      |
|----------------------------------------|--------------------------------------------------------------------------------------|
| RESOURCE CONSENT                       | AUTH144654.07.01                                                                     |
| CONSENT TYPE AND ACTIVITIES AUTHORISED | RMA S14 To divert surface water in diversion channels around ventilation shaft sites |
| LOCATION                               | Area 1                                                                               |
| TERM                                   | 35 years                                                                             |
| LAPSE PERIOD                           | 10 years                                                                             |

|         |                                                                                                                                                                                                                                    |
|---------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|         | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                          |
| SC1.B.1 | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent. |
|         | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                      |
| SC1.B.2 | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                               |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|                                        |                                                |
|----------------------------------------|------------------------------------------------|
| RESOURCE CONSENT                       | AUTH144654.08.01                               |
| CONSENT TYPE AND ACTIVITIES AUTHORISED | RMA S14 To take groundwater for pumping tests. |
| LOCATION                               | Area 1                                         |
| TERM                                   | 35 years                                       |
| LAPSE PERIOD                           | 10 years                                       |

|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |
|----------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|          | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |
| SC1.C.1. | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |
|          | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |
| SC1.C.2. | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |
|          | <b>Limits</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |
| SC1.C.3. | The maximum instantaneous rate of take from any pumping test must not exceed 10 litres per second.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |
|          | <b>Telemetry</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |
| SC1.C.4. | <ol style="list-style-type: none"> <li>1. The consent holder must record the quantity of water taken from each pumping test at the point of take on a cumulative basis.</li> <li>2. This data must be telemetered to the Waikato Regional Council.</li> <li>3. The telemetry system must be compatible with Waikato Regional Council telemetry system standards and data protocols and be provided in continuous 15 minute values of net take volume in units of cubic metres.</li> <li>4. The data must be reported once daily to the Waikato Regional Council via the telemetry system and there must be 96 values per daily report. When no water is being taken the data must specify the net take volume as zero.</li> </ol> |
|          | <b>Accuracy of the Water Measuring Systems</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
| SC1.C.5. | Prior to the first exercise of this consent and upon request of the Waikato Regional Council, the consent holder must undertake an assessment of the accuracy of the water measuring system(s). Each system must have a reliable calibration to water flow and must be maintained to an accuracy of +/- 5%. The assessment must be undertaken by an independent, qualified person and evidence documenting the assessment shall be forwarded to the Waikato Regional Council within one month of the assessment occurring.                                                                                                                                                                                                        |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|                                        |                                                                                                                      |
|----------------------------------------|----------------------------------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                       | AUTH144654.09.01                                                                                                     |
| CONSENT TYPE AND ACTIVITIES AUTHORISED | RMA S15 To discharge groundwater potentially containing contaminants to the main stem of the Wharekirauponga Stream. |
| LOCATION                               | Area 1                                                                                                               |
| TERM                                   | 35 years                                                                                                             |
| LAPSE PERIOD                           | 10 years                                                                                                             |

|           |                                                                                                                                                                                                                                                                                                                                                                                                                   |
|-----------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|           | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                                                                                                                                                                                                         |
| SC1.D.1.  | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent.                                                                                                                                                                                |
|           | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                                                                                                                                                                                                     |
| SC1.D.2.  | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                                                                                                                                                                                                              |
|           | <b>General</b>                                                                                                                                                                                                                                                                                                                                                                                                    |
| SC1.D.3.  | This consent only authorises discharges from pumping test activities                                                                                                                                                                                                                                                                                                                                              |
| SC1.D.4.  | At least 10 working days prior to the commencement of the discharge from each pumping test, the consent holder shall advise the Waikato Regional Council in writing of: <ul style="list-style-type: none"> <li>a. The location of the bore and the discharge point; and</li> <li>b. The expected duration of the pumping test.</li> </ul>                                                                         |
| SC1.D.5.  | The discharges from the pumping tests must be to the main stem of the Wharekirauponga Stream only.                                                                                                                                                                                                                                                                                                                |
| SC1.D.6.  | The maximum instantaneous rate of any discharge must not exceed 10 litres per second.                                                                                                                                                                                                                                                                                                                             |
| SC1.D.7.  | The duration of any pump test must not exceed 30 days.                                                                                                                                                                                                                                                                                                                                                            |
| SC1.D.8.  | The consent holder must ensure that the effects of this discharge do not cause harm to the aquatic life of the Wharekirauponga Stream.                                                                                                                                                                                                                                                                            |
| SC1.D.9.  | The turbidity of the discharged water must not exceed 25 NTU.                                                                                                                                                                                                                                                                                                                                                     |
| SC1.D.10. | <ol style="list-style-type: none"> <li>1. The following limits must not be exceeded within the Wharekirauponga Stream immediately downstream of the zone of reasonable mixing as a result of the exercise of this consent.</li> <li>2. When determining compliance with this condition the zone of reasonable mixing shall comprise of the area of the stream bounded by the point of discharge on the</li> </ol> |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|                                                                                                                                                                                                                                                                                           | <p>Wharekirauponga Stream and the lesser of 100 metres downstream of the discharge point or a distance of 7 times the average width of the stream (measured at median flow) in the reach to 100 metres downstream of the discharge point.</p> <p><b>Table 1: Receiving Environment Limits</b></p> <table><tr><th>Parameter</th><th>Limit (mg/l)</th></tr><tr><td>Dissolved copper</td><td>0.003</td></tr><tr><td>Dissolved iron</td><td>1.0</td></tr><tr><td>Dissolved manganese</td><td>0.1</td></tr><tr><td>Dissolved zinc</td><td>0.05</td></tr><tr><td>pH</td><td>6-9</td></tr></table>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | Parameter                                                           | Limit (mg/l) | Dissolved copper | 0.003                                          | Dissolved iron | 1.0       | Dissolved manganese                                                            | 0.1                                                      | Dissolved zinc           | 0.05 | pH                                                                                                                                                                                                                                                                                        | 6-9       |                                                                     |                                                                                                                                                                                                               |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------|--------------|------------------|------------------------------------------------|----------------|-----------|--------------------------------------------------------------------------------|----------------------------------------------------------|--------------------------|------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------|---------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Parameter                                                                                                                                                                                                                                                                                 | Limit (mg/l)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                                                                     |              |                  |                                                |                |           |                                                                                |                                                          |                          |      |                                                                                                                                                                                                                                                                                           |           |                                                                     |                                                                                                                                                                                                               |
| Dissolved copper                                                                                                                                                                                                                                                                          | 0.003                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |                                                                     |              |                  |                                                |                |           |                                                                                |                                                          |                          |      |                                                                                                                                                                                                                                                                                           |           |                                                                     |                                                                                                                                                                                                               |
| Dissolved iron                                                                                                                                                                                                                                                                            | 1.0                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |                                                                     |              |                  |                                                |                |           |                                                                                |                                                          |                          |      |                                                                                                                                                                                                                                                                                           |           |                                                                     |                                                                                                                                                                                                               |
| Dissolved manganese                                                                                                                                                                                                                                                                       | 0.1                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |                                                                     |              |                  |                                                |                |           |                                                                                |                                                          |                          |      |                                                                                                                                                                                                                                                                                           |           |                                                                     |                                                                                                                                                                                                               |
| Dissolved zinc                                                                                                                                                                                                                                                                            | 0.05                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |                                                                     |              |                  |                                                |                |           |                                                                                |                                                          |                          |      |                                                                                                                                                                                                                                                                                           |           |                                                                     |                                                                                                                                                                                                               |
| pH                                                                                                                                                                                                                                                                                        | 6-9                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |                                                                     |              |                  |                                                |                |           |                                                                                |                                                          |                          |      |                                                                                                                                                                                                                                                                                           |           |                                                                     |                                                                                                                                                                                                               |
| SC1.D.11.                                                                                                                                                                                                                                                                                 | <p>Prior to the discharge of water from a pumping test a representative sample of the groundwater from that bore must be collected and analysed for pH, conductivity, hardness, sulphate, copper, iron, manganese and zinc.</p> <p><i>Advice Note: This sampling is required to confirm the groundwater quality in that bore can be discharged in a manner which will comply with Conditions SC1.D.8 – SD1.D.10, and to identify the minimum in-stream flow rate required for assimilation of the discharge within the specified limits.</i></p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |                                                                     |              |                  |                                                |                |           |                                                                                |                                                          |                          |      |                                                                                                                                                                                                                                                                                           |           |                                                                     |                                                                                                                                                                                                               |
| SC1.D.12.                                                                                                                                                                                                                                                                                 | <p>Results of the groundwater analysis and minimum flow rate assessment must be notified in writing to Waikato Regional Council prior to any discharge taking place.</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |                                                                     |              |                  |                                                |                |           |                                                                                |                                                          |                          |      |                                                                                                                                                                                                                                                                                           |           |                                                                     |                                                                                                                                                                                                               |
| SC1.D.13.                                                                                                                                                                                                                                                                                 | <p>The discharge from a pump test must not occur unless the groundwater analysis and minimum flow rate assessment demonstrate that the discharge will comply with Conditions SC1.D.8 – SD1.D.10.</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |                                                                     |              |                  |                                                |                |           |                                                                                |                                                          |                          |      |                                                                                                                                                                                                                                                                                           |           |                                                                     |                                                                                                                                                                                                               |
| SC1.D.14.                                                                                                                                                                                                                                                                                 | <p>Unless otherwise agreed in writing by the Waikato Regional Council the consent holder must undertake the following programme of monitoring for any discharge authorised by this consent:</p> <p><b>Table 2: Discharge Monitoring Parameters</b></p> <table><tr><th>Frequency</th><th>Site</th><th>Parameter</th></tr><tr><td rowspan="3">Continuously whilst the discharge is occurring</td><td>Discharge</td><td>Turbidity</td></tr><tr><td>Wharekirauponga Stream at existing flow gauging locations WKP1, WKP2 and WKP3.</td><td>Flow by level pressure transducers during the discharge.</td></tr><tr><td>Pumping test bore collar</td><td>Flow</td></tr><tr><td rowspan="2">Daily sampling comprising:<ul style="list-style-type: none"><li>At least one sample event before each pump test discharge commences;</li><li>A sample event on Day 1 and 3 of each pump test discharge;</li><li>A sample event on Day 8, 13, 18, 23 and 28 if the pump test is</li></ul></td><td>Discharge</td><td rowspan="2">pH, conductivity, hardness, sulphate, copper, iron, manganese, zinc</td></tr><tr><td>Wharekirauponga Stream:<ul style="list-style-type: none"><li>1. immediately downstream of the zone of reasonable mixing; and</li><li>2. immediately upstream of point of discharge (control point)</li></ul></td></tr></table> | Frequency                                                           | Site         | Parameter        | Continuously whilst the discharge is occurring | Discharge      | Turbidity | Wharekirauponga Stream at existing flow gauging locations WKP1, WKP2 and WKP3. | Flow by level pressure transducers during the discharge. | Pumping test bore collar | Flow | Daily sampling comprising: <ul style="list-style-type: none"><li>At least one sample event before each pump test discharge commences;</li><li>A sample event on Day 1 and 3 of each pump test discharge;</li><li>A sample event on Day 8, 13, 18, 23 and 28 if the pump test is</li></ul> | Discharge | pH, conductivity, hardness, sulphate, copper, iron, manganese, zinc | Wharekirauponga Stream: <ul style="list-style-type: none"><li>1. immediately downstream of the zone of reasonable mixing; and</li><li>2. immediately upstream of point of discharge (control point)</li></ul> |
| Frequency                                                                                                                                                                                                                                                                                 | Site                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | Parameter                                                           |              |                  |                                                |                |           |                                                                                |                                                          |                          |      |                                                                                                                                                                                                                                                                                           |           |                                                                     |                                                                                                                                                                                                               |
| Continuously whilst the discharge is occurring                                                                                                                                                                                                                                            | Discharge                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | Turbidity                                                           |              |                  |                                                |                |           |                                                                                |                                                          |                          |      |                                                                                                                                                                                                                                                                                           |           |                                                                     |                                                                                                                                                                                                               |
|                                                                                                                                                                                                                                                                                           | Wharekirauponga Stream at existing flow gauging locations WKP1, WKP2 and WKP3.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Flow by level pressure transducers during the discharge.            |              |                  |                                                |                |           |                                                                                |                                                          |                          |      |                                                                                                                                                                                                                                                                                           |           |                                                                     |                                                                                                                                                                                                               |
|                                                                                                                                                                                                                                                                                           | Pumping test bore collar                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Flow                                                                |              |                  |                                                |                |           |                                                                                |                                                          |                          |      |                                                                                                                                                                                                                                                                                           |           |                                                                     |                                                                                                                                                                                                               |
| Daily sampling comprising: <ul style="list-style-type: none"><li>At least one sample event before each pump test discharge commences;</li><li>A sample event on Day 1 and 3 of each pump test discharge;</li><li>A sample event on Day 8, 13, 18, 23 and 28 if the pump test is</li></ul> | Discharge                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | pH, conductivity, hardness, sulphate, copper, iron, manganese, zinc |              |                  |                                                |                |           |                                                                                |                                                          |                          |      |                                                                                                                                                                                                                                                                                           |           |                                                                     |                                                                                                                                                                                                               |
|                                                                                                                                                                                                                                                                                           | Wharekirauponga Stream: <ul style="list-style-type: none"><li>1. immediately downstream of the zone of reasonable mixing; and</li><li>2. immediately upstream of point of discharge (control point)</li></ul>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |                                                                     |              |                  |                                                |                |           |                                                                                |                                                          |                          |      |                                                                                                                                                                                                                                                                                           |           |                                                                     |                                                                                                                                                                                                               |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |  |  |
|-----------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|--|
|           | <p>continuing on those days; and</p> <ul style="list-style-type: none"> <li>• A sample event within at least 1 day after each pump test ceases.</li> </ul>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |  |  |
| SC1.D.15. | <ol style="list-style-type: none"> <li>1. All water quality sampling and analysis under this consent must be undertaken using Standard Methods for the Examination of Water and Wastewater (19th Edition, or any updated version), APHA, AWWA and WEF, unless otherwise agreed in writing by Waikato Regional Council. Analyses must be undertaken at an appropriately qualified laboratory.</li> <li>2. All other measuring, testing, recording and analytical methods as may be required from time to time pursuant to the requirements of this consent shall be to the satisfaction of the Waikato Regional Council.</li> </ol>                                                                                                                                                                        |  |  |
| SC1.D.16. | <ol style="list-style-type: none"> <li>1. Following the cessation of the discharge of each pumping test the consent holder must provide the Waikato Regional Council a report which: <ol style="list-style-type: none"> <li>a. Contains the results of all water monitoring undertaken in accordance with Conditions SC1.D.11 and SC1.D.14; and</li> <li>b. Assesses compliance with Conditions SC1.D.5 - SC1.D.10.</li> </ol> </li> <li>2. The final water monitoring sample(s) as required under Condition SC1.D.14 shall be dispatched for analysis as soon as reasonably practicable following cessation of the discharge and the complete report shall be provided to Waikato Regional Council within 10 working days of the receipt by the consent holder of the final analysis results.</li> </ol> |  |  |

## **Appendix B4: Conditions for the Waikato Regional Council Consents**

### **AREA 2 SPECIFIC CONSENTS**

**[WILLOWS PORTAL AND WILLOWS SURFACE FACILITIES AREA]**

## Appendix B4: Conditions for the Waikato Regional Council Consents

|                                        |                                                                                                                                                                                                     |
|----------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                       | AUTH144654.10.01                                                                                                                                                                                    |
| CONSENT TYPE AND ACTIVITIES AUTHORISED | RMA S13 To disturb and reclaim the bed of unnamed tributaries of the Mataura Stream associated with establishing clean and dirty water drains for mining and erosion and sediment control purposes. |
| LOCATION                               | Area 2                                                                                                                                                                                              |
| TERM                                   | 35 years                                                                                                                                                                                            |
| LAPSE PERIOD                           | 10 years                                                                                                                                                                                            |

|         |                                                                                                                                                                                                                                    |
|---------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|         | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                          |
| SC2.A.1 | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent. |
|         | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                      |
| SC2.A.2 | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                               |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|                                        |                                                                                                                     |
|----------------------------------------|---------------------------------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                       | AUTH144654.11.01                                                                                                    |
| CONSENT TYPE AND ACTIVITIES AUTHORISED | RMA S14 To dam and divert water for erosion and sediment control purposes using clean water and dirty water drains. |
| LOCATION                               | Area 2                                                                                                              |
| TERM                                   | 35 years                                                                                                            |
| LAPSE PERIOD                           | 10 years                                                                                                            |

|         |                                                                                                                                                                                                                                    |
|---------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|         | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                          |
| SC2.B.1 | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent. |
|         | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                      |
| SC2.B.2 | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent                                |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|                                        |                                                                                                                                                                                                 |
|----------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                       | AUTH144654.12.01                                                                                                                                                                                |
| CONSENT TYPE AND ACTIVITIES AUTHORISED | RMA S15 To discharge sediment laden water to land within temporary sediment retention ponds and decanting earth bunds and to discharge water from those devices to surface water via spillways. |
| LOCATION                               | Area 2                                                                                                                                                                                          |
| TERM                                   | 35 years                                                                                                                                                                                        |
| LAPSE PERIOD                           | 10 years                                                                                                                                                                                        |

|         |                                                                                                                                                                                                                                    |
|---------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|         | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                          |
| SC2.C.1 | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent. |
|         | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                      |
| SC2.C.2 | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                               |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|                                        |                                                                                                                                                                                                                                                                                                                    |
|----------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                       | AUTH144654.13.01                                                                                                                                                                                                                                                                                                   |
| CONSENT TYPE AND ACTIVITIES AUTHORISED | RMA S13 To disturb the bed of unnamed tributaries of the Mataura Stream associated with the establishment of diversion drains and formalised overland flow paths to divert natural runoff and unnamed tributaries of the Mataura Stream around developed areas to downstream water bodies and overland flow paths. |
| LOCATION                               | Area 2                                                                                                                                                                                                                                                                                                             |
| TERM                                   | 35 years                                                                                                                                                                                                                                                                                                           |
| LAPSE PERIOD                           | 10 years                                                                                                                                                                                                                                                                                                           |

|         |                                                                                                                                                                                                                                    |
|---------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|         | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                          |
| SC2.D.1 | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent. |
|         | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                      |
| SC2.D.2 | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                               |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|                                        |                                                                                                                                                                                     |
|----------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                       | AUTH144654.14.01                                                                                                                                                                    |
| CONSENT TYPE AND ACTIVITIES AUTHORISED | RMA S14 To dam and divert water within unnamed tributaries of the Mataura Stream and from natural runoff around developed areas to downstream water bodies and overland flow paths. |
| LOCATION                               | Area 2                                                                                                                                                                              |
| TERM                                   | 35 years                                                                                                                                                                            |
| LAPSE PERIOD                           | 10 years                                                                                                                                                                            |

|          |                                                                                                                                                                                                                                                                                                                                  |
|----------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|          | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                                                                                                                        |
| SC2.E.1. | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent.                                                                                               |
|          | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                                                                                                                    |
| SC2.E.2. | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                                                                                                                             |
|          | <b>Other Matters</b>                                                                                                                                                                                                                                                                                                             |
| SC2.E.3. | The Consent Holder must divert clean runoff away from downstream developed areas using clean water diversion drains and formalised overland flow paths in accordance with Waikato stormwater management guideline (TR2020/07, May 2020), or any subsequent version of the guideline (in which case the latter version prevails). |
| SC2.E.4. | All diversion drains and formalised overland flow paths must be designed and maintained to manage a 10% Annual Exceedance Probability (AEP) flood event.                                                                                                                                                                         |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |
|-------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                          | AUTH144654.15.01                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |
| CONSENT TYPE AND ACTIVITIES<br>AUTHORISED | <p>RMA S13 To disturb and reclaim the bed of an unnamed tributary of the Mataura Stream to establish the Willows Rock Stack.</p> <p>RMA S15 To discharge PAF and NAF rock and overburden on to land at the Willows Rock Stack and associated Mine Access Road.</p> <p>RMA S14 To dam and divert runoff, intercepted groundwater and seepage from the Willows Rock Stack, Willows Portal, Mine Access Road and WRS Toe Seepage Pond to the Willows Collection Pond.</p> <p>RMA S13 To disturb the bed and place a dam structure in the bed of an unnamed tributary of the Mataura Stream to establish the WRS Toe Seepage Pond.</p> <p>RMA S14 To dam water in an unnamed tributary of the Mataura Stream associated with the construction and operation of the WRS Toe Seepage Pond.</p> |
| LOCATION                                  | Area 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |
| TERM                                      | 35 years                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |
| LAPSE PERIOD                              | 10 years                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |

|          |                                                                                                                                                                                                                                    |
|----------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|          | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                          |
| SC2.F.1. | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent. |
|          | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                      |
| SC2.F.2. | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                               |
|          | <b>Design and Construction</b>                                                                                                                                                                                                     |
| SC2.F.3. | The Willows Rock Stack must be wholly located within the footprint shown on “Map 1 – Willows Rock Stack” as shown in as <b>Attachment 1</b> to this consent.                                                                       |
| SC2.F.4. | The Willows Rock Stack must be constructed in accordance with the following documents included in Part B of the application documents:                                                                                             |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |
|------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|            | <p>a. “Oceana Gold (New Zealand) Limited Waihi North Project; Willows Rock Stack and Surface Facilities Technical Report, Submitted by Engineering Geology Limited” (<b>the EGL Design Report</b>); and</p> <p>b. Waihi North Project Geochemical Assessment, Geochemistry of Tailings and Overburden, Treatment and Mitigation, submitted by AECOM New Zealand Limited.</p>                                                                                                                  |
| SC2.F.5.   | Clean water drains designed to accommodate, as a minimum, 10% Annual Exceedance Probability (AEP) storm flow must be installed and maintained around the footprint of the Willows Rock Stack, WRS Toe Seepage Pond and Mine Access Road to divert clean surface runoff and any groundwater that is intercepted within the footprint of those activities.                                                                                                                                      |
| SC2.F.6.   | Diversion drains must be designed, installed and maintained to collect runoff from the Willows Rock Stack, WRS Toe Seepage Pond and Mine Access Road and divert it to the Willows Collection Pond.                                                                                                                                                                                                                                                                                            |
| SC2.F.7.   | <p>Prior to deposition of rock or overburden, the footprint of the Willows Rock Stack must be stripped of topsoil, subsoil and other weak material, which is to be stockpiled for rehabilitation purposes.</p> <p><i>Advice Note: Characterisation of in-situ material, other than topsoil and subsoils, should be undertaken prior to the removal of materials to inform management requirements.</i></p>                                                                                    |
| SC2.F.8.   | The shear key specified in the EGL WRS Design Report must be earth lined with non-acid forming material with a permeability no greater than $1 \times 10^{-8} \text{m/s}$ .                                                                                                                                                                                                                                                                                                                   |
| SC2.F.9.   | A rockfill underdrainage system must be installed and maintained in the gully beneath Willows Rock Stack to collect contaminated seepage from waste rock and minimise the release of seepage to ground and convey it to the Willows Collection Pond. The drainage layer must be designed and constructed to prevent the ingress of oxygen into the rock stack.                                                                                                                                |
| SC2.F.10.  | The underdrain system required by Condition SC2.F.9 must be designed and installed to minimise air ingress into the stockpile, and to ensure that the toe of the Willows Rock Stack remains saturated.                                                                                                                                                                                                                                                                                        |
| SC2.F.11.  | Oxygen traps (goose necks or a similar approved technique) must be added to the underdrain system required by Condition SC2.F.9 to minimise oxygen ingress into the stockpile and associated oxidation and acid generation.                                                                                                                                                                                                                                                                   |
| SC2.F.12.  | The Consent Holder must ensure that the WRS Toe embankment is constructed from, or lined with, materials which provide for secure long term control of seepage and runoff, and which have no acid forming potential.                                                                                                                                                                                                                                                                          |
| SC2.F.13.  | <p>1 The Consent Holder must supply the following documentation to the Waikato Regional Council prior to commencement of the construction works authorised by this consent:</p> <ul style="list-style-type: none"> <li>a. Detailed Design Report</li> <li>b. Specification</li> <li>c. Drawings</li> <li>d. Construction Monitoring Inspection Schedule</li> </ul> <p>2 All subsequent amendments to the design must be supplied to the Waikato Regional Council prior to implementation.</p> |
| SC2.F.13.A | All detailed design reporting must include seismic design analyses in accordance with National Seismic Hazard Model (2022).                                                                                                                                                                                                                                                                                                                                                                   |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |
|-----------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| SC2.F.14. | All construction works must be implemented under the supervision of appropriately qualified and experienced persons.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |
| SC2.F.15. | <ol style="list-style-type: none"> <li>1 On completion of the initial foundations, underdrainage system, and surface water drainage system construction works, and prior to the commissioning of any subsequent stages, the Consent Holder must supply written confirmation to the Waikato Regional Council and the Peer Review Panel that the foundations, underdrainage system, and surface water drainage system works of the relevant stage have been constructed in accordance with the requirement in Condition SC2.F.12.</li> <li>2 Thereafter, the facility must be inspected by an appropriately qualified and experienced person or persons with recognised experience in the design of rock storage facilities (the Designer) on an annual basis, and a written report on the inspection provided to Waikato Regional Council and copied to the Peer Review Panel within one month of completion of the inspection.</li> </ol> |
| SC2.F.16. | The Consent Holder must not place any potentially acid forming material in any area of the Willows Rock Stack or Mine Access Road until the report required by Condition SC2.F.15 has been submitted to the Waikato Regional Council in respect of that area, acknowledging that the Willows Rock Stack and its foundations may be developed in stages.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |
|           | <b>Monitoring</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |
| SC2.F.17. | <ol style="list-style-type: none"> <li>1. The Consent Holder must install groundwater quality monitoring bores to detect seepage bypassing the underdrainage system, and to determine the representative groundwater quality for shallow and deeper groundwater around the perimeter of land owned by the Consent Holder.</li> <li>2. Groundwater quality monitoring bores must be installed between the Willows Rock Stack and the Mataura Stream (to the north, east and southeast of Willows Rock Stack).</li> <li>3. The locations and specifications of the bores shall be to the satisfaction of the Waikato Regional Council.</li> </ol>                                                                                                                                                                                                                                                                                           |
| SC2.F.18. | <ol style="list-style-type: none"> <li>1. The Consent Holder must undertake baseline monitoring of groundwater monitoring bores at least monthly over a twelve month period, prior to the placing of PAF material within the Willows Rock Stack. Groundwater monitoring is to be undertaken using the methodology provided in the Willows Rock Stack Monitoring and Management Plan required by Condition SC2.F.23 and monitoring shall include the measurement of the parameters annexed as <b>Attachment 2</b> to this consent.</li> <li>2. The results of baseline monitoring must be forwarded to Waikato Regional Council at quarterly intervals.</li> </ol>                                                                                                                                                                                                                                                                         |
| SC2.F.19. | <ol style="list-style-type: none"> <li>1. The Consent Holder must calculate trigger levels for the parameters annexed as <b>Attachment 2</b> to this consent for down gradient bores based on the trends observed in the baseline monitoring data required by Condition SC2.F.18 at levels which will provide early warning of potential changes of groundwater quality as a result of the activities authorised by this consent.</li> <li>2. All trigger levels must be set at the 95<sup>th</sup> percentile confidence limit.</li> </ol>                                                                                                                                                                                                                                                                                                                                                                                               |
| SC2.F.20. | <ol style="list-style-type: none"> <li>1. At any time following completion of baseline monitoring, if monitoring results within the monitoring bores exceeds the relevant trigger level for that bore over two consecutive readings, then the Consent Holder must: <ol style="list-style-type: none"> <li>a. Characterise and assess the source of the change; and</li> </ol> </li> </ol>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |
|-----------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|           | <p>b. Take all necessary measures to ensure that General Condition G18 is complied with.</p> <p>2. The trigger and actions taken must be reported to the Waikato Regional Council immediately upon completion.</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |
| SC2.F.21. | <p>1. Ongoing monitoring must be undertaken at the locations and using the methodology outlined in <b>the Willows Rock Stack Monitoring and Management Plan</b> required by Condition SC2.F.23, with monitoring to include the measurement of all parameters annexed as <b>Attachment 2</b> to this consent.</p> <p>2. Monitoring results must be provided to the Waikato Regional Council and copied to the Peer Review Panel as part of annual reporting as required under Condition SC2.F.27.</p>                                                                                                                                                                                                                                                                                                                                                                                         |
| SC2.F.22. | <p>The Consent Holder must classify waste rock in a manner to be set out in the Willows Rock Stack Monitoring and Management Plan required by Condition SC2.F.23 and as a minimum includes:</p> <ol style="list-style-type: none"> <li>Definitions used to characterise waste rock embankments in terms of acid base accounting;</li> <li>Criteria used for classifying waste rock;</li> <li>An assessment protocol for classifying waste rock;</li> <li>Waste rock sampling requirements during construction and rehabilitation of the Willows Rock Stack; and</li> <li>Requirements for limestone addition for any potentially acid forming rock placed within stockpiles.</li> </ol>                                                                                                                                                                                                      |
|           | <b>Willows Rock Stack Monitoring and Management Plan</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |
| SC2.F.23. | <p>1. No later than 30 working days prior to the first discharge of rock or overburden on to land at the Willows Rock Stack, the Consent Holder must submit a Willows Rock Stack Monitoring and Management Plan for written certification under Condition C5 of Schedule One.</p> <p>2. Certification is required to verify that the Willows Rock Stack Monitoring and Management Plan:</p> <ol style="list-style-type: none"> <li>Includes actions, methods, monitoring programmes, and trigger levels as appropriate to meet the objectives in Condition SC2.F.24; and</li> <li>Satisfies the requirements in Condition SC2.F.25.</li> </ol> <p>3. The Willows Rock Stack Monitoring and Management Plan need not be a standalone document, and the Consent Holder may, at its discretion, include it as part of any other management plan required by the conditions of this consent.</p> |
| SC2.F.24. | <p>The objectives of the Willows Rock Stack Monitoring and Management Plan are to set out details of:</p> <ol style="list-style-type: none"> <li>The monitoring that will be undertaken to ensure that the Willows Rock Stack does not adversely affect land, ground and surface water resources; and</li> <li>The contingency measures necessary to ensure the conditions of this consent are achieved.</li> </ol>                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |
| SC2.F.25. | <p>1. The Willows Rock Stack Monitoring and Management Plan must include, as a minimum:</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
|-----------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|           | <ol style="list-style-type: none"> <li>a. A Risk Management Plan, as defined in the Australian/New Zealand Standards for Risk Management (AS/NZS 4360:1999) or any subsequent replacement standard. The purposes of the Risk Management Plan must be to: <ol style="list-style-type: none"> <li>i. Identify and assess the operational risks relating to the Willows Rock Stack;</li> <li>ii. Develop an appropriate monitoring programme; and</li> <li>iii. Set out the actions to be taken in the event that monitoring in accordance with ii above indicates a material increase in the risks identified in i.</li> </ol> </li> <li>b. The details of the monitoring bores to be established in accordance with Condition SC2.F.17 to detect seepage bypassing the underdrainage system, and to determine the representative groundwater quality for shallow and deeper groundwater around the perimeter of land downstream of the Willows Rock Stack owned by the Consent Holder;</li> <li>c. Details of the monitoring to be undertaken in accordance with Condition SC2.F.18, and the trigger levels set in accordance with Condition SC2.F.19;</li> <li>d. A contingency plan to be actioned in the event a trigger level is exceeded over two consecutive readings, and which is sufficient to assess the source of the change, and to determine what, if any, measures should be implemented to ensure that General Condition G18 is complied with;</li> <li>e. Details of the waste rock classification process to be used in accordance with Condition SC2.F.22; and</li> <li>f. Details of monitoring measures that will be adopted to validate design criteria and confirm that oxygen is excluded beyond 8m of the edge of the Rock Stack.</li> </ol> <ol style="list-style-type: none"> <li>2. In detailing the monitoring programmes the Consent Holder must provide information on the monitoring methods proposed, the monitoring locations, parameters to be monitored, and the calibration and maintenance of monitoring equipment.</li> </ol> |
|           | <i>Review of the Willows Rock Stack Monitoring and Management Plan</i>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |
| SC2.F.26. | <ol style="list-style-type: none"> <li>1. The Willows Rock Stack Monitoring and Management Plan must be reviewed at least annually by the Consent Holder to ascertain whether any amendments are required in order to ensure ongoing compliance with Condition SC.2.F.24 and Condition SC2.F.25.</li> <li>2. Any required amendments must be made in accordance with Condition C8 of Schedule One.</li> </ol>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |
|           | <b>Willows Rock Stack Monitoring Report</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |
| SC2.F.27. | <ol style="list-style-type: none"> <li>1. The Consent Holder must submit an annual Willows Rock Stack Monitoring report to the Waikato Regional Council. The report must, as a minimum include: <ol style="list-style-type: none"> <li>a. The data from monitoring undertaken during the previous year;</li> <li>b. Identification of any environmentally important trends associated with the above monitoring;</li> <li>c. Interpretation and analysis of any change in groundwater chemistry over the previous year, predictions of any future changes in groundwater and identification of contingency actions, if any, are proposed in response to these predictions;</li> <li>d. Any contingency actions that may have been taken during the year;</li> </ol> </li> </ol>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |
|-----------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|           | <ul style="list-style-type: none"> <li>e. Comment on compliance with all conditions and any reasons for non-compliance or difficulty in achieving conformance with the conditions of this consent;</li> <li>f. A summary and analysis of any complaints relevant to this consent, from the complaint log; and</li> <li>g. Any works that have been undertaken to improve environmental performance or that are proposed to be undertaken in the forthcoming year to improve environmental performance in relation to activities permitted by this consent.</li> </ul> <p>2. The report must be forwarded in a format acceptable to the Waikato Regional Council.</p> <p>3. The report shall also be provided to the Peer Review Panel for their consideration in an advisory capacity only with regard to the progression of works.</p> <p>4. The Willows Rock Stack Monitoring Report need not be a standalone document and the Consent Holder may, at its discretion, include it as part of any other monitoring report required by the conditions of this consent.</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
|           | <b>Technical Review</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |
| SC2.F.28. | <p>1. The design and construction of all works covered by this consent must be reviewed by an appropriately qualified and experienced person or persons.</p> <p>2. The person or persons must be instructed to report in writing to the Waikato Regional Council at least at the following times:</p> <ul style="list-style-type: none"> <li>a. prior to commencement of construction of Willows Rock Stack;</li> <li>b. at all critical stages during the ongoing design and construction of Willows Rock Stack but not less than annually;</li> <li>c. on the completion of the Willows Rock Stack;</li> <li>d. following any significant design changes; and</li> <li>e. prior to commencement of approved post closure discharge to the Ohinemuri River from the Willows Rock Stack collection pond,</li> </ul> <p>3. The person or persons must be instructed to address at least the following matters:</p> <ul style="list-style-type: none"> <li>a. progress against the Annual Work Programme;</li> <li>b. site preparation including hydrogeological issues and geotechnical issues;</li> <li>c. foundation design and use of on-site material;</li> <li>d. foundation design and construction;</li> <li>e. all underdrainage systems;</li> <li>f. stockpile management;</li> <li>g. monitoring; and</li> <li>h. rehabilitation and closure plans associated with the Willows Rock Stack.</li> </ul> <p>4. The reports required by this condition must also be provided to the Peer Review Panel for their consideration in an advisory capacity only with regard to the progression of works.</p> |
|           | <b>Mataura Wetland</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |
| SC2.F.29. | Prior to any work authorised by this consent that may affect flows that sustain the Mataura Wetland, the Consent Holder must prepare a Mataura Wetland Restoration and Monitoring                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |
|-----------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|           | <p>Plan for written certification under Condition C5 of Schedule One by the Waikato Regional Council. This plan must include:</p> <ol style="list-style-type: none"> <li>A baseline description of the existing Mataura Wetland, and confirmation of the hydrological conditions that sustain its ecological values and the expected restored state;</li> <li>A map delineating the extent of the Mataura Wetland including any buffer area proposed; and</li> <li>A proposed monitoring and reporting framework, including the results of the monitoring and any remedial works undertaken to address adverse effects on hydrology.</li> </ol>                                                                                                                                                                                                                                                                                                                                     |
| SC2.F.30. | <ol style="list-style-type: none"> <li>At five yearly intervals following the written certification of the Mataura Wetland Restoration and Monitoring Plan referred to in Condition SC2.F.29, the Consent Holder must monitor the condition of the Mataura Wetland vegetation and the hydrological conditions that sustain it.</li> <li>Where there have been changes in the existing wetland flora or soil moisture levels such that the ecological value or extent of the wetland has been adversely affected the Consent Holder must: <ol style="list-style-type: none"> <li>Characterise and assess the source of the change; and</li> <li>Take all necessary measures to ensure that the ecological health and extent of the Mataura Wetland is restored to at least preconstruction baseline conditions.</li> </ol> </li> <li>The results of this monitoring and any actions taken to ensure compliance with (b) must be provided to the Waikato Regional Council.</li> </ol> |
| SC2.F.31. | <ol style="list-style-type: none"> <li>No construction or disturbance works may occur within the area identified as the Mataura Wetland.</li> <li>Subject to obtaining landowner approval, the Consent Holder must restore the Mataura Wetland including by stock fencing, weed and pest control and ecologically appropriate planting.</li> </ol>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|                                        |                                                                                                                                                                                                                 |
|----------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                       | AUTH144654.16.01                                                                                                                                                                                                |
| CONSENT TYPE AND ACTIVITIES AUTHORISED | RMA S13 To disturb the bed of the Mataura Stream and unnamed tributaries of the Mataura Stream to accommodate spillway structures and piped discharges from sediment retention ponds and decanting earth bunds. |
| LOCATION                               | Area 2                                                                                                                                                                                                          |
| TERM                                   | 35 years                                                                                                                                                                                                        |
| LAPSE PERIOD                           | 10 years                                                                                                                                                                                                        |

|         |                                                                                                                                                                                                                                    |
|---------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|         | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                          |
| SC2.G.1 | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent. |
|         | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                      |
| SC2.G.2 | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                               |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|                                        |                                                                             |
|----------------------------------------|-----------------------------------------------------------------------------|
| RESOURCE CONSENT                       | AUTH144654.17.01                                                            |
| CONSENT TYPE AND ACTIVITIES AUTHORISED | RMA S13 To place and use culverts within the Willows Surface Facility Area. |
| LOCATION                               | Area 2                                                                      |
| TERM                                   | 35 years                                                                    |
| LAPSE PERIOD                           | 10 years                                                                    |

|          |                                                                                                                                                                                                                                                                                                                                |
|----------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|          | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                                                                                                                      |
| SC2.H.1. | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent.                                                                                             |
|          | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                                                                                                                  |
| SC2.H.2. | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent                                                                                                                            |
|          | <b>Culvert Design</b>                                                                                                                                                                                                                                                                                                          |
| SC2.H.3. | All new culverts must be constructed and operated to convey the runoff resulting from at least a 5% Annual Exceedance Probability (AEP), 24-hour duration, design storm.                                                                                                                                                       |
| SC2.H.4. | Fish passage must be provided where temporary works on diversions and culverts have a duration exceeding 7 days.                                                                                                                                                                                                               |
| SC2.H.5. | Fish passage for fish species must be provided through culverts in accordance with the <i>New Zealand Fish Passage Guidelines for Structures up to 4 metres</i> (2018) or any subsequent version of the guidelines (in which case the latter version prevails).                                                                |
| SC2.H.6. | The Consent Holder must ensure that the area of disturbance during placement/construction of all culverts is kept to a practical minimum.                                                                                                                                                                                      |
| SC2.H.7. | Within 20 working days following completion of each culvert, the Consent Holder must provide the Waikato Regional Council with the information required under Regulations 62(3) and 63(3) of the Resource Management (National Environmental Standards for Freshwater) Regulations 2020 (NESF).                                |
|          | <b>Monitoring and Maintenance</b>                                                                                                                                                                                                                                                                                              |
| SC2.H.8. | Following the completion of construction of any new culvert where Condition SC2.H.4 applies, upstream and downstream fish passage through any culvert is to be maintained and monitored in accordance with Regulation 69 of the Resource Management (National Environmental Standards for Freshwater) Regulations 2020 (NESF). |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|                                        |                                                                                                                          |
|----------------------------------------|--------------------------------------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                       | AUTH144654.18.01                                                                                                         |
| CONSENT TYPE AND ACTIVITIES AUTHORISED | RMA S15 To discharge non-acid forming overburden, including soil and sediment, on to land in stockpiles and earth bunds. |
| LOCATION                               | Area 2                                                                                                                   |
| TERM                                   | 35 years                                                                                                                 |
| LAPSE PERIOD                           | 10 years                                                                                                                 |

|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |
|---------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|         | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |
| SC2.I.1 | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |
|         | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |
| SC2.I.2 | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |
|         | <b>General Requirements</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |
| SC2.I.3 | Preparation of stockpile sites for the temporary storage of non-acid forming waste rock, soil and sediment removed from ponds and drains prior to the placement of material must include: <ul style="list-style-type: none"> <li>a. Stripping and stockpiling of topsoil and subsoils for later use in site rehabilitation;</li> <li>b. Construction of clean water diversion drains around the site to divert and discharge clean surface run-off and intercepted groundwater in accordance with consents AUTH144654.14 ; and</li> <li>c. Construction of diversion drains around the site perimeter to divert stockpile run-off to sediment detention ponds for sediment reduction prior to discharge.</li> </ul> |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|                                        |                                                                                                                                                      |
|----------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                       | AUTH144654.19.01                                                                                                                                     |
| CONSENT TYPE AND ACTIVITIES AUTHORISED | RMA S14 To dam water within the Willows Collection Pond.<br>S15 To discharge water to surface water from the Willows Collection Pond via a spillway. |
| LOCATION                               | Area 2                                                                                                                                               |
| TERM                                   | 35 years                                                                                                                                             |
| LAPSE PERIOD                           | 10 years                                                                                                                                             |

|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |
|----------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|          | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |
| SC2.J.1. | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |
|          | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |
| SC2.J.2. | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |
|          | <b>Design and Construction</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
| SC2.J.3. | The Willows Collection Pond must be constructed and operated to contain, as a minimum, the run-off generated from within its catchment during a 24-hour duration rainfall event with an Annual Exceedance Probability (AEP) of 10%, taking into account a combination of both storage volume and pumping rate.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
| SC2.J.4. | Subject to Condition SC2.J.5, for 24-hour duration rainfall events with an AEP greater than 10%, all stormwater reporting to the Willows Collection Pond must be pumped to the Water Treatment Plant at the Waihi Surface Facilities Area for treatment.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |
| SC2.J.5. | <p>If the Consent Holder can demonstrate that the quality of water entering the Willows Collection Pond:</p> <ul style="list-style-type: none"> <li>a. Meets or is better than the receiving water criteria defined in Condition G18;</li> <li>b. Is capable of remaining so on a continuous basis; and,</li> <li>c. In combination with all other discharges authorised for this site, does not cause a significant adverse environmental effect on the receiving groundwater and surface water, or on users of these resources, or, in the case of surface water, aquatic biota,</li> </ul> <p>then the Consent Holder may, if approved by the Waikato Regional Council in writing, discharge directly from the pond, provided that:</p> <ul style="list-style-type: none"> <li>d. The Consent Holder continuously monitor pH and turbidity in the pond; and</li> <li>e. For rainfall events with an AEP greater than 50%, discharges from the pond:</li> </ul> |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|                                                                                                                                       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |                                                                           |    |              |           |               |                                                                                                                                       |
|---------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------|----|--------------|-----------|---------------|---------------------------------------------------------------------------------------------------------------------------------------|
|                                                                                                                                       | <div><div>i. have turbidity of no greater than 110 NTU and</div><div>ii. have a pH within the range of 6.0-9.0 pH units.</div></div>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |                                                                           |    |              |           |               |                                                                                                                                       |
| SC2.J.6.                                                                                                                              | The Willows Collection Pond must be provided with a spillway that will safely route a 1% AEP flood.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |                                                                           |    |              |           |               |                                                                                                                                       |
| SC2.J.7.                                                                                                                              | <div>The Consent Holder must ensure that the Willows Collection Pond is:</div> <div><div>a. Constructed from materials which provide for secure long term containment; and</div><div>b. Constructed using materials which have no acid forming potential; and</div><div>c. Either lined with 1.5mm HDPE (or other similar synthetic liner approved by the Waikato Regional Council) to a height of 1.5m from the base, and with a 0.5m protective cover layer.</div></div>                                                                                                                                                                                                                                                                                                       |                                                                           |    |              |           |               |                                                                                                                                       |
| SC2.J.8.                                                                                                                              | The Willows Collection Pond design must be submitted to the Waikato Regional Council for written certification prior to commencement of the construction works authorised by this consent.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |                                                                           |    |              |           |               |                                                                                                                                       |
| SC2.J.9.                                                                                                                              | The Willows Collection Pond and associated works must be designed and implemented under the supervision of appropriately qualified and experienced persons.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |                                                                           |    |              |           |               |                                                                                                                                       |
| SC2.J.10.                                                                                                                             | <div><div>1. Routine maintenance and desilting of the Willows Collection Pond must only occur during periods of projected fine weather.</div><div>2. All silt removed must be disposed of to a tailings storage facility.</div></div>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |                                                                           |    |              |           |               |                                                                                                                                       |
| SC2.J.11.                                                                                                                             | No chemicals or additives may be used in the Willows Collection Pond or the discharge from the pond without the prior written approval of the Waikato Regional Council.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |                                                                           |    |              |           |               |                                                                                                                                       |
|                                                                                                                                       | <div>Discharges and Monitoring</div>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |                                                                           |    |              |           |               |                                                                                                                                       |
| SC2.J.12.                                                                                                                             | <div>Except where Condition SC2.J.5 applies, the Consent Holder must monitor the discharge from the Willows Collection Pond every day during any overflow event in accordance with Table SC2.J.12.T:</div> <table><tr><td>Table SC2.J.12.T – Willows Collection Pond Overflow Monitoring Parameters</td></tr><tr><td>pH</td></tr><tr><td>Conductivity</td></tr><tr><td>Turbidity</td></tr><tr><td>Total ammonia</td></tr><tr><td>Trace elements (iron, manganese, copper, nickel, zinc, silver, antimony, arsenic, selenium, cadmium, chromium (iv), lead and mercury.</td></tr></table> <div><div>Table Note:</div><div>The Willows Collection Pond overflow monitoring programme for metals is for ‘acid-soluble’ concentrations determined on unfiltered samples.</div></div> | Table SC2.J.12.T – Willows Collection Pond Overflow Monitoring Parameters | pH | Conductivity | Turbidity | Total ammonia | Trace elements (iron, manganese, copper, nickel, zinc, silver, antimony, arsenic, selenium, cadmium, chromium (iv), lead and mercury. |
| Table SC2.J.12.T – Willows Collection Pond Overflow Monitoring Parameters                                                             |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |                                                                           |    |              |           |               |                                                                                                                                       |
| pH                                                                                                                                    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |                                                                           |    |              |           |               |                                                                                                                                       |
| Conductivity                                                                                                                          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |                                                                           |    |              |           |               |                                                                                                                                       |
| Turbidity                                                                                                                             |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |                                                                           |    |              |           |               |                                                                                                                                       |
| Total ammonia                                                                                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |                                                                           |    |              |           |               |                                                                                                                                       |
| Trace elements (iron, manganese, copper, nickel, zinc, silver, antimony, arsenic, selenium, cadmium, chromium (iv), lead and mercury. |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |                                                                           |    |              |           |               |                                                                                                                                       |
| SC2.J.13.                                                                                                                             | Results of the monitoring undertaken in accordance with Condition SC2.J.12 must be forwarded to the Waikato Regional Council every three months.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |                                                                           |    |              |           |               |                                                                                                                                       |
| SC2.J.14.                                                                                                                             | <div><div>1. All water quality sampling and analysis must be undertaken using Standard Methods for the Examination of Water and Wastewater (19th Edition 1995, or updates), APHA, AWWA and</div></div>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                                                                           |    |              |           |               |                                                                                                                                       |

**Appendix B4: Conditions for the Waikato Regional Council Consents**

|  |                                                                                                                                                                                                                                                                                                                                                                               |
|--|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|  | <p>WEF, unless otherwise agreed in writing by the Waikato Regional Council. Analyses must be undertaken at an appropriately certified laboratory.</p> <p>2. All other measuring, testing, recording and analytical methods as may be required from time to time pursuant to the requirements of this consent must be to the satisfaction of the Waikato Regional Council.</p> |
|--|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

## Appendix B4: Conditions for the Waikato Regional Council Consents

|                                           |                                                                                                                              |
|-------------------------------------------|------------------------------------------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                          | AUTH144654.20.01                                                                                                             |
| CONSENT TYPE AND<br>ACTIVITIES AUTHORISED | RMA S15 To discharge water to land within the Willows Surface Facilities Area Silt Pond and to surface water via a spillway. |
| LOCATION                                  | Area 2                                                                                                                       |
| TERM                                      | 35 years                                                                                                                     |
| LAPSE PERIOD                              | 10 years                                                                                                                     |

|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |
|----------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|          | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |
| SC2.K.1. | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent.                                                                                                                                                                                                                                                                                                                                                                                                                                                         |
|          | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |
| SC2.K.2. | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |
|          | <b>Design Requirements</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |
| SC2.K.3. | The Willows Surface Facilities Area Silt Pond must be designed and constructed to have a minimum live storage capacity equivalent to the volume of run-off generated during a 50% Annual Exceedance Probability (AEP), 2-hour duration, design storm. This pond must be regularly maintained so as to retain its design live storage capacity.                                                                                                                                                                                                                                                                                                                                             |
|          | <b>Discharge Quality</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |
| SC2.K.4. | No chemicals or additives may be used in the Willows Surface Facilities Area Silt Pond without the prior written approval of the Waikato Regional Council.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |
| SC2.K.5. | <ol style="list-style-type: none"> <li>Unless otherwise agreed by the Waikato Regional Council in writing, the contributing catchments to the Willows Surface Facilities Area Silt Pond must not contain contaminated or potentially acid-forming soil or rock.</li> <li>For the purpose of this condition, the definition of “non-acid-forming” is defined as: <ol style="list-style-type: none"> <li>NAGpH &gt; 4.5; and,</li> <li>NPR &gt; 1,</li> </ol> <p>where NAGpH is the pH of the solution produced from a Net Acid Generation test, NPR is Net Potential Ratio (=ANC/MPA), ANC is total Acid Neutralising Capacity, and MPA is total Maximum Potential Acidity.</p> </li> </ol> |

#### Appendix B4: Conditions for the Waikato Regional Council Consents

|          |                                                                                                                                                                                                                                                                                                                                                                                                           |
|----------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| SC2.K.6. | <p>For rainfall events with an AEP greater than 50%, the Willows Surface Facilities Area Silt Pond discharges must:</p> <ol style="list-style-type: none"><li>Contain no oil or grease;</li><li>Have a suspended solids concentration no greater than 100 g/m<sup>3</sup> and / or turbidity concentration no greater than 110 NTU; and</li><li>Have a pH within the range of 6.0-9.0 pH units.</li></ol> |
| SC2.K.7. | <ol style="list-style-type: none"><li>The Consent Holder must monitor pH and turbidity in the Willows Surface Facilities Area Silt Pond discharge not less than once per calendar month.</li><li>The results of the monitoring must be forwarded on a quarterly basis to Waikato Regional Council.</li></ol>                                                                                              |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|                                        |                                                                                 |
|----------------------------------------|---------------------------------------------------------------------------------|
| RESOURCE CONSENT                       | AUTH144654.21.01                                                                |
| CONSENT TYPE AND ACTIVITIES AUTHORISED | RMA S15 To discharge domestic sewage to land via a new effluent disposal field. |
| LOCATION                               | Area 2                                                                          |
| TERM                                   | 35 years                                                                        |
| LAPSE PERIOD                           | 10 years                                                                        |

|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |
|----------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|          | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                                                                                                                                                                                                                                                                                                                                   |
| SC2.L.1. | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent.                                                                                                                                                                                                                                                                                                          |
|          | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                                                                                                                                                                                                                                                                                                                               |
| SC2.L.2. | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent                                                                                                                                                                                                                                                                                                                                         |
|          | <b>Standards</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |
| SC2.L.3. | The maximum volume of treated wastewater discharged must not exceed 25 cubic metres per day as measured over any rolling 24-hour period.                                                                                                                                                                                                                                                                                                                                                                                                    |
| SC2.L.4. | Treated wastewater discharged onto the ground must not exceed a loading rate of 20 millimetres per day or the absorptive capacity of the soils, whichever is the lesser.                                                                                                                                                                                                                                                                                                                                                                    |
| SC2.L.5. | <ol style="list-style-type: none"> <li>1. The Consent Holder must ensure that a reserve wastewater disposal area of not less than one hundred percent (100%) of the duty disposal area is available all times.</li> <li>2. The Consent Holder must ensure that no permanent hard surface (for example concrete) is placed over the reserve disposal area.</li> </ol>                                                                                                                                                                        |
| SC2.L.6. | <p>The Consent Holder must ensure that:</p> <ol style="list-style-type: none"> <li>a. The design of the disposal system achieves a vertical separation distance of at least 600 millimetres of unsaturated soil between the bottom of the disposal system and the groundwater during the wettest months of the year immediately following a 200% Annual Exceedance Probability (AEP) rain event; and</li> <li>b. The operation of the disposal system is undertaken in a way that ensures the design standard in a. is achieved.</li> </ol> |
| SC2.L.7. | There must be no breakout (uncontrolled discharge) of wastewater from any part of the wastewater treatment system or the disposal area that results in visible ponding of the wastewater on the ground surface and/or an overland discharge of wastewater.                                                                                                                                                                                                                                                                                  |

**Appendix B4: Conditions for the Waikato Regional Council Consents**

|           |                                                                                                                                                                                                                                                                            |
|-----------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| SC2.L.8.  | Surface water and stormwater runoff must be directed away from the wastewater treatment and disposal area.                                                                                                                                                                 |
| SC2.L.9.  | The wastewater treatment system must be maintained in a watertight condition to prevent the ingress of stormwater or groundwater into the system.                                                                                                                          |
| SC2.L.10. | <p>The Consent Holder must:</p> <ul style="list-style-type: none"><li>a. Plant and maintain the disposal area with appropriate high evapotranspiration plant species or grass; and</li><li>b. Clearly signpost the treatment plant and wastewater disposal area.</li></ul> |
| SC2.L.11. | The Consent Holder must ensure that the wastewater treatment and disposal system is appropriately operated and maintained at all times.                                                                                                                                    |
| SC2.L.12. | Within one month of commissioning the new wastewater treatment system, the Consent Holder must provide the Waikato Regional Council with a copy of the As-Built Plans for the system. and confirm in writing the date the system was commissioned.                         |
| SC2.L.13. | The Consent Holder must maintain a record of all maintenance and desludging undertaken on the wastewater treatment and disposal system. These records must be compiled by 30 June each year and be made available to the Waikato Regional Council on request.              |

## **Appendix B4: Conditions for the Waikato Regional Council Consents**

### **AREA 5 SPECIFIC CONSENTS**

## Appendix B4: Conditions for the Waikato Regional Council Consents

|                                           |                                                                                                                                                                                           |
|-------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                          | AUTH144654.22.01                                                                                                                                                                          |
| CONSENT TYPE AND<br>ACTIVITIES AUTHORISED | RMA S13 To disturb the bed of unnamed tributaries of the Ohinemuri River to accommodate spillway structures and piped discharges from sediment retention ponds and decanting earth bunds. |
| LOCATION                                  | Area 5                                                                                                                                                                                    |
| TERM                                      | 35 years                                                                                                                                                                                  |
| LAPSE PERIOD                              | 10 years                                                                                                                                                                                  |

|          |                                                                                                                                                                                                                                    |
|----------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|          | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                          |
| SC5.A.1. | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent. |
|          | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                      |
| SC5.A.2. | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                               |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|                                        |                                                                                                                                          |
|----------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                       | AUTH144654.23.01                                                                                                                         |
| CONSENT TYPE AND ACTIVITIES AUTHORISED | RMA S15 To discharge overflow water from sediment retention ponds and decanted from earth bunds to land and surface water via spillways. |
| LOCATION                               | Area 5                                                                                                                                   |
| TERM                                   | 35 years                                                                                                                                 |
| LAPSE PERIOD                           | 10 years                                                                                                                                 |

|         |                                                                                                                                                                                                                                    |
|---------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|         | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                          |
| SC5.B.1 | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent. |
|         | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                      |
| SC5.B.2 | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent                                |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|                                        |                                                                                                                                           |
|----------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                       | AUTH144654.24.01                                                                                                                          |
| CONSENT TYPE AND ACTIVITIES AUTHORISED | RMA S15 To discharge non-acid forming overburden and topsoil on to land in stockpiles and earth bunds adjacent to the Gladstone Open Pit. |
| LOCATION                               | Area 5                                                                                                                                    |
| TERM                                   | 35 years                                                                                                                                  |
| LAPSE PERIOD                           | 10 years                                                                                                                                  |

|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |
|---------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|         | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |
| SC5.C.1 | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent.                                                                                                                                                                                                                                                                                                                                                                                                                                       |
|         | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |
| SC5.C.2 | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |
|         | <b>Stockpile Management</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |
| SC5.C.3 | Preparation of stockpile sites for the temporary storage of non-acid forming waste rock and soil prior to the placement of material must include: <ul style="list-style-type: none"> <li>a. Stripping and stockpiling of topsoil and subsoils for later use in site rehabilitation.</li> <li>b. Construction of clean water diversion drains around the site to divert and discharge clean surface run-off and intercepted groundwater in accordance with consent AUTH144654.34.01.</li> <li>c. Construction of diversion drains around the site perimeter to divert stockpile run-off to sediment retention ponds for sediment reduction prior to discharge.</li> </ul> |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|                                        |                                                                                                                            |
|----------------------------------------|----------------------------------------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                       | AUTH144654.25.01                                                                                                           |
| CONSENT TYPE AND ACTIVITIES AUTHORISED | RMA S13 To disturb and reclaim the bed of an unnamed tributary of the Ohinemuri River to establish the Gladstone Open Pit. |
| LOCATION                               | Area 5                                                                                                                     |
| TERM                                   | 35 years                                                                                                                   |
| LAPSE PERIOD                           | 10 years                                                                                                                   |

|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |
|---------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|         | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |
| SC5.D.1 | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |
|         | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
| SC5.D.2 | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |
|         | <b>Design</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
| SC5.D.3 | The Gladstone Open Pit must be wholly located within the footprint shown on “Map 1 – Gladstone Open Pit Area” shown on <b>Attachment 1</b> to this consent                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |
|         | <b>Gladstone Wetland</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |
| SC5.D.4 | <ol style="list-style-type: none"> <li>1. Prior to any disturbance or reclamation authorised by this consent the Consent Holder must undertake baseline monitoring of the Gladstone Wetland vegetation and confirm the hydrological conditions that sustain this wetland.</li> <li>2. The results of this monitoring must be reported to the Waikato Regional Council.</li> </ol>                                                                                                                                                                                                                                                                                                                                                                                                |
| SC5.D.5 | <ol style="list-style-type: none"> <li>1. At five yearly intervals after the commencement of activities authorised by this consent, the Consent Holder must monitor the condition of the Gladstone Wetland vegetation and the hydrological conditions that sustain it.</li> <li>2. Where there have been changes in the existing wetland flora or soil moisture levels such that the ecological value or extent of the wetland has been adversely affected, the Consent Holder must: <ol style="list-style-type: none"> <li>a. Characterise and assess the source of the change; and</li> <li>b. Take all necessary measures to ensure that the ecological health and extent of the Gladstone Wetland is restored to preconstruction baseline conditions.</li> </ol> </li> </ol> |

**Appendix B4: Conditions for the Waikato Regional Council Consents**

|  |                                                                                                                                          |
|--|------------------------------------------------------------------------------------------------------------------------------------------|
|  | 3. The results of this monitoring and any actions taken to ensure compliance with 2(b) must be provided to the Waikato Regional Council. |
|--|------------------------------------------------------------------------------------------------------------------------------------------|

**Appendix B4: Conditions for the Waikato Regional Council Consents**

**Attachment 1 – Gladstone Open Pit Footprint**

## Appendix B4: Conditions for the Waikato Regional Council Consents

|                                           |                                                                                                                                                                                                                                          |
|-------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                          | AUTH144654.26.01                                                                                                                                                                                                                         |
| CONSENT TYPE AND<br>ACTIVITIES AUTHORISED | <p>RMA S9 To drill drain holes in the wall of the Gladstone Open Pit to depressurise the pit wall.</p> <p>RMA S14 To take water to dewater the Gladstone Open Pit using pit wall drain holes and divert to the Water Treatment Plant</p> |
| LOCATION                                  | Area 5                                                                                                                                                                                                                                   |
| TERM                                      | 35 years                                                                                                                                                                                                                                 |
| LAPSE PERIOD                              | 10 years                                                                                                                                                                                                                                 |

|         |                                                                                                                                                                                                                                    |
|---------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|         | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                          |
| SC5.E.1 | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent. |
|         | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                      |
| SC5.E.2 | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                               |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|                                           |                                                                                                                                              |
|-------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                          | AUTH144654.27.01                                                                                                                             |
| CONSENT TYPE AND<br>ACTIVITIES AUTHORISED | RMA S14 To divert and take surface water collected in the base of the Gladstone Open Pit and divert this water to the Water Treatment Plant. |
| LOCATION                                  | Area 5                                                                                                                                       |
| TERM                                      | 35 years                                                                                                                                     |
| LAPSE PERIOD                              | 10 years                                                                                                                                     |

|         |                                                                                                                                                                                                                                    |
|---------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|         | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                          |
| SC5.F.1 | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent. |
|         | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                      |
| SC5.F.2 | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent                                |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|                                        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |
|----------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                       | AUTH144654.28.01                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |
| CONSENT TYPE AND ACTIVITIES AUTHORISED | <p>RMA S15 To discharge overburden to land within Gladstone Open Pit to create the Gladstone Open Pit Tailings Storage Facility.</p> <p>RMA S15 To discharge contaminants to land associated with the discharge of tailings into the Gladstone Open Pit Tailings Storage Facility.</p> <p>RMA S14 To dam water in the Gladstone Open Pit Tailings Storage Facility.</p> <p>RMA S14 To take groundwater from the Gladstone Open Pit Tailings Storage Facility and divert this water to the Water Treatment Plant or Processing Plant using underdrainage and decanting collection systems.</p> |
| LOCATION                               | Area 5                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |
| TERM                                   | 35 years                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |
| LAPSE PERIOD                           | 10 years                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |

|          |                                                                                                                                                                                                                                                              |
|----------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|          | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                                                    |
| SC5.G.1. | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent.                           |
|          | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                                                |
| SC5.G.2. | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent                                                          |
|          | <b>Design and Construction</b>                                                                                                                                                                                                                               |
| SC5.G.3. | The Gladstone Open Pit Tailings Storage Facility (“GOPTSF”) must be wholly located within the footprint shown on <b>Attachment 1</b> to this consent.                                                                                                        |
| SC5.G.4. | The GOPTSF must be constructed in accordance with the design document <i>Oceana Gold (New Zealand) Limited –Gladstone Pit TSF Design Report</i> , GHD.                                                                                                       |
| SC5.G.5. | The Consent Holder must ensure that the entire footprint of the GOPTSF tailing impoundment is underlain by a low permeability geosynthetic liner which provides for secure long term containment of tailings.                                                |
| SC5.G.6. | 1. The Consent Holder must ensure that any potentially acid forming (PAF) material stored outside the footprint of the GOPTSF, and which is intended for disposal into GOPTSF, is stored on a pad constructed in accordance with the following requirements: |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
|-----------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|           | <ol style="list-style-type: none"> <li>a. The pad must be constructed from or lined with at least 600 mm of natural, non-acid forming materials with a permeability of no greater than <math>1 \times 10^{-8}</math> m/s.</li> <li>b. The pad must be constructed to direct any seepage to a point from where it can be monitored, and if necessary, directed to the Water Treatment Plant for treatment prior to discharge.</li> <li>c. Any proposed monitoring locations must be agreed in writing with the Waikato Regional Council. The monitoring may form part of any monitoring programme already undertaken at the Site.</li> </ol> <p>2. If monitoring indicates the presence of sulphate in the groundwater, then monitoring of the surface water down-gradient of the storage pad must be undertaken and meet the limits specified in G18 with respect to baseline sulphate levels.</p> |
| SC5.G.7.  | The Consent Holder must install an underdrainage system beneath the GOPTSF impoundment liner to collect contaminated seepage and groundwater.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |
| SC5.G.8.  | The Consent Holder must ensure that this underdrainage system is in place prior to the discharge of tailings to GOPTSF.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |
| SC5.G.9.  | <ol style="list-style-type: none"> <li>1. Until basal lining of the GOPTSF is complete, the Consent Holder must ensure that the pH of a slurry of the surface of any exposed PAF rock (after liming) comprising one part solids (less than 4 mm size fraction) to two parts deionised water, remains greater than or equal to pH 5.5.</li> <li>2. Unless Waikato Regional Council agrees in writing to an alternative sampling programme, samples of a slurry of the surface of any exposed PAF rock (after liming) must be collected on a grid pattern of not more than 50 m and, within 1 week of placement of any PAF rock, and thereafter at intervals not exceeding 4 weeks.</li> <li>3. The procedure for collecting and analysing the samples must be as described in the GOPTSF Monitoring and Management Plan.</li> </ol>                                                                 |
| SC5.G.10. | The Consent Holder must collect all underdrainage flow from the tailings storage facility and divert it to the Water Treatment Plant for treatment or for use in the Processing Plant.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |
| SC5.G.11. | <ol style="list-style-type: none"> <li>1. A minimum freeboard of 4 metres must be maintained between the pit crest and all material in the tailings pond (i.e. solid and liquid).</li> <li>2. The water level in the tailings pond must be maintained at a level that is sufficient to impound the surface run-off arising from the Probable Maximum Precipitation (PMP) event without overtopping, plus a 1.0 metre freeboard.</li> <li>3. Following rainfall or any event that reduces the freeboard below 1.0 metres, the water level in the tailings pond must be drawn down as soon as practicable to restore the 1.0 metre minimum freeboard.</li> </ol>                                                                                                                                                                                                                                     |
| SC5.G.12. | <ol style="list-style-type: none"> <li>1. The Consent Holder must supply the following documentation to the Waikato Regional Council and Peer Review Panel prior to commencement of the GOPTSF construction works: <ol style="list-style-type: none"> <li>a. Detailed Design Report prepared by a suitably qualified and experienced person or persons</li> </ol> </li> </ol>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |
|------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|            | <p>b. Construction Drawings prepared by a suitably qualified and experienced person or persons</p> <p>2. All subsequent amendments to the design must be supplied to the Waikato Regional Council prior to implementation and following peer review by an appropriately qualified and experienced person or persons.</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |
| SC5.G.12.A | All detailed design reporting shall include seismic design analyses in accordance with National Seismic Hazard Model (2022).                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |
| SC5.G.13.  | <p>1. The Consent Holder must retain a person or persons with recognised qualifications and experience in the design of tailings storage facilities (the Designer).</p> <p>2. All aspects of the design of the GOPTSF must be undertaken under the supervision of the Designer, who must provide to Waikato Regional Council in conjunction with the documentation required by Condition SC5.G.12, written confirmation that all aspects of the GOPTSF have been designed in accordance with accepted engineering best practise, and to ensure the effective control of acid and metalliferous drainage and the containment of tailings.</p> <p><i>Advice Note: Acid and metalliferous drainage includes acidic drainage from materials classified as PAF and drainage from materials classified as waste with potential for trace element leaching as defined in the Waste Classification Management protocol in the GOPTSF Monitoring and Management Plan.</i></p> |
| SC5.G.14.  | All GOPTSF construction works must be implemented under the supervision of appropriately qualified and experienced persons.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |
| SC5.G.15.  | <p>1 On completion of the GOPTSF construction works, and prior to the first discharge of tailings into the impoundment, the Consent Holder must supply to the Waikato Regional Council and Peer Review Panel:</p> <p>a. A full set of as-built plans; and</p> <p>b. Written confirmation that the GOPTSF works have been constructed in accordance with the design submitted under Condition SC5.G.12.</p> <p>2 Thereafter, the GOPTSF must be inspected by a registered engineer on an annual basis, and a written report on the inspection provided to Waikato Regional Council and copied to the Peer Review Panel within one month of completion of the inspection.</p>                                                                                                                                                                                                                                                                                          |
| SC5.G.16.  | The Consent Holder must maintain the structural integrity of the GOPTSF works associated with the exercise of these consents and of any erosion control and energy dissipation works which become necessary as a consequence of the exercise of these consents.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |
|            | <b>Monitoring</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
| SC5.G.17.  | <p>1. The Consent Holder must measure and record the volume of storage provided by the available GOPTSF freeboard at quarterly intervals.</p> <p>2. This information must be made available to Waikato Regional Council on request.</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |
| SC5.G.18.  | <p>1. At monthly intervals the Consent Holder must collect a sample of tailings being discharged to the tailings pond and determine its acid neutralising capacity (ANC), maximum potential acidity (MPA), and net acid generation (NAG) capacity.</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |
|-----------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|           | <ol style="list-style-type: none"> <li>The date the sample is collected and the ANC, MPA and NAG results must be reported to the Waikato Regional Council annually.</li> </ol>                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |
| SC5.G.19. | <ol style="list-style-type: none"> <li>The Consent Holder must install groundwater quality monitoring bores to detect seepage bypassing the underdrainage system, and to determine the representative groundwater quality for shallow and deeper groundwater around the perimeter of land owned by the Consent Holder.</li> <li>Groundwater quality monitoring bores must be installed between the GOPTSF and the Ohinemuri River (around the full perimeter of the GOPTSF).</li> <li>The locations and specifications of the bores must be to the satisfaction of the Waikato Regional Council.</li> </ol>                                               |
| SC5.G.20. | <ol style="list-style-type: none"> <li>The Consent Holder must undertake baseline monitoring of groundwater monitoring bores at least monthly over a twelve month period, prior to the discharge of tailings or PAF material within the GOPTSF.</li> <li>Groundwater monitoring must be undertaken using the methodology provided in the GOPTSF Monitoring and Management Plan required by Condition SC5.G.25 and monitoring shall include the measurement of all parameters annexed as <b>Attachment 2</b> to this consent.</li> <li>The results of baseline monitoring must be forwarded to Waikato Regional Council at quarterly intervals.</li> </ol> |
| SC5.G.21. | <ol style="list-style-type: none"> <li>The Consent Holder must calculate trigger levels for the parameters annexed as <b>Attachment 2</b> to this consent for down gradient bores based on the trends observed in the baseline monitoring data required by Condition SC5.G.20 at levels which will provide early warning of potential changes of groundwater quality as a result of the activities authorised by this consent.</li> <li>All trigger levels must be set at the 95<sup>th</sup> percentile confidence limit.</li> </ol>                                                                                                                     |
| SC5.G.22. | <ol style="list-style-type: none"> <li>If at any time following completion of baseline monitoring, the monitoring results within the monitoring bores exceed the relevant trigger levels for that bore over two consecutive readings then the Consent Holder must: <ol style="list-style-type: none"> <li>Characterise and assess the source of the change; and</li> <li>Take all necessary measures to ensure that General Condition G18 is complied with.</li> </ol> </li> <li>The trigger level exceedance and measures taken must be reported to the Waikato Regional Council immediately on completion.</li> </ol>                                   |
| SC5.G.23. | <ol style="list-style-type: none"> <li>Ongoing monitoring must be undertaken at the locations and using the methodology outlined in the GOPTSF Monitoring and Management Plan required by Condition SC5.G.25, with monitoring to include the measurement of all parameters annexed as <b>Attachment 2</b> to this consent.</li> <li>Monitoring results must be provided to Waikato Regional Council and copied to the Peer Review Panel as part of annual reporting as required under Condition SC5.G.29.</li> </ol>                                                                                                                                      |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |
|-----------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| SC5.G.24. | <p>The Consent Holder must classify waste rock in a manner to be set out in the GOPTSF Monitoring and Management Plan required by Condition SC5.G.25 and as a minimum includes:</p> <ol style="list-style-type: none"> <li>Definitions used to characterise waste rock embankments in terms of acid base accounting;</li> <li>Criteria used for classifying waste rock;</li> <li>An assessment protocol for classifying waste rock;</li> <li>Waste rock sampling requirements for the Gladstone Open Pit and the Gladstone Open Pit Tailings Storage Facility; and</li> <li>Requirements for limestone addition for any potentially acid forming rock placed within stockpiles.</li> </ol>                                                                                                                                                                   |
|           | <b>GOPTSF Monitoring and Management Plan</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |
| SC5.G.25. | <ol style="list-style-type: none"> <li>No later than 30 working days prior to the commencement of construction of the GOPTSF, the Consent Holder must submit a GOPTSF Monitoring and Management Plan for written certification under Condition C5 of Schedule One.</li> <li>Certification is required to verify that the GOPTSF Monitoring and Management Plan: <ol style="list-style-type: none"> <li>Includes actions, methods, monitoring programmes and trigger levels as appropriate to meet the objectives in Condition SC5.G.26; and</li> <li>Satisfies the requirements in Condition SC5.G.27.</li> </ol> </li> <li>The GOPTSF Monitoring and Management Plan need not be a standalone document and the Consent Holder may, at its discretion, include it as part of any other management plan required by the conditions of this consent</li> </ol> |
| SC5.G.26. | <p>The objectives of the GOPTSF Monitoring and Management Plan are to set out details of:</p> <ol style="list-style-type: none"> <li>The monitoring that will be undertaken to ensure that the GOPTSF does not adversely affect land, ground and groundwater resources;</li> <li>The trigger levels determined in accordance with Condition SC5.G.21; and</li> <li>The contingency measures that will be implemented in response to any exceedance of a trigger level, in order to prevent any reoccurrence of an exceedance and to ensure compliance with the conditions of this consent.</li> </ol>                                                                                                                                                                                                                                                        |
| SC5.G.27. | <ol style="list-style-type: none"> <li>The GOPTSF Monitoring and Management Plan must be prepared in accordance with the Australian/New Zealand Standards for Risk Management (AS/NZS 4360:1999) or any subsequent replacement standard, and must, as a minimum: <ol style="list-style-type: none"> <li>Identify and assess the operational risks relating to the GOPTSF;</li> <li>Set out details of an appropriate monitoring programme; and</li> <li>Set out the actions to be taken in the event that monitoring in accordance with b above indicates a material increase in the risks identified in a above.</li> <li>Include a structural integrity surveillance and monitoring programme for the GOPTSF;</li> </ol> </li> </ol>                                                                                                                       |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |
|-----------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|           | <ul style="list-style-type: none"> <li>e. Include a description of the monitoring systems and the measures to be adopted to ensure compliance with General Condition G18, including: <ul style="list-style-type: none"> <li>i. The details of the monitoring bores to be established in accordance with Condition SC5.G.19;</li> <li>ii. Details of monitoring in both shallow and deep aquifer systems to be undertaken in accordance with Condition SC5.G.23;</li> <li>iii. The trigger levels set in accordance with Condition SC5.G.21 and the contingency measures required by Condition SC5.G.26.c; and</li> <li>iv. The measurement and monitoring of the liner system integrity (by measuring drainage quality and flow from all underdrainage and surface collection systems) in order to verify the "as built" structure is achieving design performance.</li> </ul> </li> <li>f. Include details of the waste rock classification to be used in accordance with Condition SC5.G.24.</li> </ul> <p>2. In detailing the GOPTSF monitoring programmes the Consent Holder must provide information on the monitoring methods proposed, the monitoring locations, parameters to be monitored, and the required calibration and maintenance of monitoring equipment.</p> |
|           | <i>Review of the GOPTSF Monitoring and Management Plan</i>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
| SC5.G.28. | <ul style="list-style-type: none"> <li>1. The GOPTSF Monitoring and Management Plan must be reviewed at least annually by the Consent Holder to ascertain whether any amendments are required in order to ensure ongoing compliance with Condition SC5.G.26 and Condition SC5.G.27.</li> <li>2. Any required amendments must be made in accordance with Condition C8 of Schedule One.</li> </ul>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |
|           | <b>GOPTSF Monitoring Report</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |
| SC5.G.29. | <ul style="list-style-type: none"> <li>1. The Consent Holder must submit an annual GOPTSF Monitoring Report to the Waikato Regional Council. The report must, as a minimum include: <ul style="list-style-type: none"> <li>a. The volume of all contaminated material disposed of within the GOPTSF, including brine and hydrocarbons;</li> <li>b. The data from monitoring undertaken during the previous year;</li> <li>c. Identification of any environmentally important trends associated with the above monitoring;</li> <li>d. Interpretation and analysis of any change in groundwater chemistry over the previous year and predictions of any future changes in groundwater or surface water chemistry, and identification of what contingency actions, if any, it proposes to take in response to these predictions;</li> <li>e. Any contingency actions that may have been taken during the previous year;</li> <li>f. Commentary on compliance with all conditions and any reasons for non-compliance or difficulty in achieving conformance with the conditions of this consent;</li> <li>g. A summary and analysis of complaints relevant to this consent, from the complaint log (refer to Schedule One); and</li> </ul> </li> </ul>                           |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |
|-----------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|           | <p>h. Any works that have been undertaken to improve environmental performance or that are proposed to be undertaken in the forthcoming year to improve environmental performance in relation to activities permitted by this consent.</p> <p>3. The report must be forwarded in a format acceptable to the Waikato Regional Council.</p> <p>4. The GOPTSF Monitoring Report need not be a standalone document and the Consent Holder may, at its discretion, include it as part of any other monitoring report required by the conditions of this consent.</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |
|           | <b>Technical Review</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |
| SC5.G.30. | <p>1. The Consent Holder must provide the design and proposed construction methodology of all GOPTSF works authorised by this consent to an appropriately qualified and experienced person or persons.</p> <p>2. The person or persons must be instructed by the Consent Holder to report in writing to the Waikato Regional Council at least at the following times:</p> <ul style="list-style-type: none"> <li>a. Prior to commencement of construction of GOPTSF;</li> <li>b. At all critical stages during the ongoing design and construction of GOPTSF, but not less than annually;</li> <li>c. On the completion of GOPTSF; and</li> <li>d. Following any significant design changes;</li> </ul> <p>and must be instructed to address at least the following matters:</p> <ul style="list-style-type: none"> <li>e. Progress against the Annual Work Programme;</li> <li>f. Site preparation including hydrogeological issues and geotechnical issues;</li> <li>g. Foundation and liner design;</li> <li>h. All underdrainage systems;</li> <li>i. Tailings impoundment management;</li> <li>j. Monitoring; and</li> <li>k. Rehabilitation and closure plans.</li> </ul> <p>3. The reports required by this condition must also be provided to the Peer Review Panel for their consideration in an advisory capacity only with regard to the progression of works.</p> |

**Appendix B4: Conditions for the Waikato Regional Council Consents**

**Attachment 1 Gladstone Open Pit Tailings Storage Facility Area Footprint**

## Appendix B4: Conditions for the Waikato Regional Council Consents

|                                        |                                                                                                                                                                                                                                  |
|----------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                       | AUTH144654.29.01                                                                                                                                                                                                                 |
| CONSENT TYPE AND ACTIVITIES AUTHORISED | <p>RMA S15 To discharge overburden to land to backfill the Gladstone Open Pit Tailings Storage Facility for rehabilitation.</p> <p>RMA S14 To divert water upon capping of the Gladstone Open Pit Tailings Storage Facility.</p> |
| LOCATION                               | Area 5                                                                                                                                                                                                                           |
| TERM                                   | 35 years                                                                                                                                                                                                                         |
| LAPSE PERIOD                           | 10 years                                                                                                                                                                                                                         |

|          |                                                                                                                                                                                                                                                                                                                    |
|----------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|          | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                                                                                                          |
| SC5.H.1. | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent.                                                                                 |
|          | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                                                                                                      |
| SC5.H.2. | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                                                                                                               |
|          | <b>Closure</b>                                                                                                                                                                                                                                                                                                     |
| SC5.H.3. | On completion of tailings deposition, the Gladstone Open Pit Tailings Storage Facility must be capped with a layer of low permeability NAF weathered rockfill, with a minimum thickness of 1.0 metre, and any exposed PAF material above outlets or spillways or in the north wall of the pit must also be capped. |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|                                        |                                                                                                                                                                                                                      |
|----------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                       | AUTH144654.30.01                                                                                                                                                                                                     |
| CONSENT TYPE AND ACTIVITIES AUTHORISED | RMA S15 To carry out earthworks, trenching and other activities in watercourses necessary for the construction of a pipeline corridor and the laying of pipes from the WTP to the Ohinemuri River outfall structures |
| LOCATION                               | Area 5                                                                                                                                                                                                               |
| TERM                                   | 35 years                                                                                                                                                                                                             |
| LAPSE PERIOD                           | 10 years                                                                                                                                                                                                             |



|          |                                                                                                                                                                                                                                    |
|----------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|          | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                          |
| SC5.I.1. | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent. |
|          | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                      |
| SC5.I.2. | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                               |

## Appendix B4: Conditions for the Waikato Regional Council Consents

|                                        |                                                                                                                               |
|----------------------------------------|-------------------------------------------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                       | AUTH144654.31.01                                                                                                              |
| CONSENT TYPE AND ACTIVITIES AUTHORISED | RMA S13 To disturb the bed and place outfall structures for the discharge of treated water in the bed of the Ohinemuri River. |
| LOCATION                               | Area 5                                                                                                                        |
| TERM                                   | 35 years                                                                                                                      |
| LAPSE PERIOD                           | 10 years                                                                                                                      |

|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |
|----------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|          | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |
| SC5.J.1. | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |
|          | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |
| SC5.J.2. | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |
|          | <b>Other Conditions</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |
| SC5.J.3. | <p>The outfall structures must be constructed in general accordance with the design annexed as <b>Attachment 1</b> to this consent. All outfall structures must include diffusers that are designed and installed:</p> <ul style="list-style-type: none"> <li>a. In accordance with best practice to ensure rapid dispersion and dilution of the discharges;</li> <li>b. In a manner that ensures the passage of migratory aquatic fauna; and</li> <li>c. So that complete mixing of the discharge authorised by AUTH144654.32 is achieved within: <ul style="list-style-type: none"> <li>i. 500 m of the upstream discharge point (E1), and</li> <li>ii. 250 m of the downstream discharge point (E2).</li> </ul> </li> </ul> |
| SC5.J.4. | All construction works must be implemented under the supervision of appropriately qualified and experienced persons.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |
| SC5.J.5. | The site must be left tidy following the placement of the structure and all equipment and surplus construction materials removed from the river.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |
| SC5.J.6. | The structures must remain in place and be maintained in a structurally sound condition at all times.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |

**Attachment 1 Outfall Design**



**RESOURCE CONSENT**  
**NOT FOR CONSTRUCTION**

|                                                                                                                                                                                                                                                                                           |  |  |  |                                                                                                                                          |                                                                                                                                                                                                                                              |                                                                                                        |                                                       |                                                     |                                                                 |                                                |                                              |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|--|--|------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------|-------------------------------------------------------|-----------------------------------------------------|-----------------------------------------------------------------|------------------------------------------------|----------------------------------------------|
| <div> <div>DO NOT SCALE FOR SET OUT DIMENSIONS</div> <div> <div> <div>10 FOR CONSENT</div> <div>Revision</div> </div> <div> <div>JB</div> <div>LS</div> <div>PR</div> <div>25.03.22</div> </div> <div> <div>By</div> <div>CHK</div> <div>Typed</div> <div>Draw</div> </div> </div> </div> |  |  |  | <div> <div>Original</div> <div>Drawn by: P. JOHNSON</div> <div>NTS</div> <div>15.03.22</div> <div>Approved For Construction</div> </div> | <div> <div>Design</div> <div>Checked by: C. SPENCER</div> <div>15.03.22</div> <div>Drawn by: C. SPENCER</div> <div>15.03.22</div> <div>Checked by: H. KERR</div> <div>25.03.22</div> <div>Drawn by: H. KERR</div> <div>25.03.22</div> </div> | <div> <div>Project</div> <div>WAIHI NORTH WATER TREATMENT PLANT OUTFALL DISCHARGE UPGRADE</div> </div> | <div> <div>Client</div> <div>OCEANA GOLD</div> </div> | <div> <div>Discipline</div> <div>CIVIL</div> </div> | <div> <div>Project No.</div> <div>2210983-203-SK21</div> </div> | <div> <div>Sheet No.</div> <div>2</div> </div> | <div> <div>Scale</div> <div>1:1</div> </div> |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|--|--|------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------|-------------------------------------------------------|-----------------------------------------------------|-----------------------------------------------------------------|------------------------------------------------|----------------------------------------------|

## Conditions for the Waikato Regional Council Consents

|                                        |                                                                                             |
|----------------------------------------|---------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                       | AUTH144654.32.01                                                                            |
| CONSENT TYPE AND ACTIVITIES AUTHORISED | RMA S15 To discharge treated water from the Water Treatment Plant into the Ohinemuri River. |
| LOCATION                               | Area 5                                                                                      |
| TERM                                   | 35 years                                                                                    |
| LAPSE PERIOD                           | 10 years                                                                                    |

|                        | <b>Discharge Rate and Method</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                    |                    |                    |                    |                    |                    |                        |            |            |           |            |            |                |         |         |        |         |         |                    |     |     |     |     |     |
|------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------|--------------------|--------------------|--------------------|--------------------|--------------------|------------------------|------------|------------|-----------|------------|------------|----------------|---------|---------|--------|---------|---------|--------------------|-----|-----|-----|-----|-----|
| SC5.K.1.               | The maximum combined daily discharge volumes from all discharge sites must not exceed those shown in Table SC5.K.4.T.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                    |                    |                    |                    |                    |                    |                        |            |            |           |            |            |                |         |         |        |         |         |                    |     |     |     |     |     |
| SC5.K.2.               | The maximum combined rate of discharge from all discharge sites must not exceed that shown in Table SC5.K.4.T.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |                    |                    |                    |                    |                    |                    |                        |            |            |           |            |            |                |         |         |        |         |         |                    |     |     |     |     |     |
| SC5.K.3.               | The rate of discharge at point E1 must not exceed the percentage of the instantaneous river flow (F) shown in Table SC5.K.4.T.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |                    |                    |                    |                    |                    |                    |                        |            |            |           |            |            |                |         |         |        |         |         |                    |     |     |     |     |     |
| SC5.K.4.               | <p>For the combined discharge from points E1 and E2, the rate of discharge must not exceed the percentage of the instantaneous river flow at discharge point E2, minus the discharge volume from point E1, (ie <math>E1+E2 \leq (Q-E1) F</math>), as shown in Table SC5.K.4.T, where:</p> <ul style="list-style-type: none"><li>- E1 = rate of discharge at point E1;</li><li>- E2 = rate of discharge at point E2; and</li><li>- Q= river flow at E2.</li></ul> <p><b>Table SC5.K.4.T – Discharge Criteria for Operating Regimes</b></p> <table><tr><th>Criteria</th><th>Operating Regime A</th><th>Operating Regime B</th><th>Operating Regime C</th><th>Operating Regime D</th><th>Operating Regime E</th></tr><tr><td>Daily Discharge Volume</td><td>20,000m³/d</td><td>26,000m³/d</td><td>5,200m³/d</td><td>26,000m³/d</td><td>52,000m³/d</td></tr><tr><td>Discharge Rate</td><td>235 L/s</td><td>301 L/s</td><td>60 L/s</td><td>301 L/s</td><td>602 L/s</td></tr><tr><td>% of river flow, F</td><td>15%</td><td>20%</td><td>10%</td><td>40%</td><td>60%</td></tr></table> | Criteria           | Operating Regime A | Operating Regime B | Operating Regime C | Operating Regime D | Operating Regime E | Daily Discharge Volume | 20,000m³/d | 26,000m³/d | 5,200m³/d | 26,000m³/d | 52,000m³/d | Discharge Rate | 235 L/s | 301 L/s | 60 L/s | 301 L/s | 602 L/s | % of river flow, F | 15% | 20% | 10% | 40% | 60% |
| Criteria               | Operating Regime A                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | Operating Regime B | Operating Regime C | Operating Regime D | Operating Regime E |                    |                    |                        |            |            |           |            |            |                |         |         |        |         |         |                    |     |     |     |     |     |
| Daily Discharge Volume | 20,000m³/d                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | 26,000m³/d         | 5,200m³/d          | 26,000m³/d         | 52,000m³/d         |                    |                    |                        |            |            |           |            |            |                |         |         |        |         |         |                    |     |     |     |     |     |
| Discharge Rate         | 235 L/s                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | 301 L/s            | 60 L/s             | 301 L/s            | 602 L/s            |                    |                    |                        |            |            |           |            |            |                |         |         |        |         |         |                    |     |     |     |     |     |
| % of river flow, F     | 15%                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | 20%                | 10%                | 40%                | 60%                |                    |                    |                        |            |            |           |            |            |                |         |         |        |         |         |                    |     |     |     |     |     |
| SC5.K.5.               | The Consent Holder must establish and maintain river gauging facilities, for the purpose of determining the river flow at the points of discharge, to the satisfaction of Waikato Regional Council.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |                    |                    |                    |                    |                    |                    |                        |            |            |           |            |            |                |         |         |        |         |         |                    |     |     |     |     |     |
| SC5.K.6.               | The treated water discharge to the Ohinemuri River must be undertaken via multi-port diffusers and ensure rapid dispersion and dilution of the discharges in accordance with best practice, to the satisfaction of the Waikato Regional Council.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                    |                    |                    |                    |                    |                    |                        |            |            |           |            |            |                |         |         |        |         |         |                    |     |     |     |     |     |
| SC5.K.7.               | The diffusers must be installed at a location and in a manner that ensures initial mixing does not prevent the passage of migratory aquatic fauna.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |                    |                    |                    |                    |                    |                    |                        |            |            |           |            |            |                |         |         |        |         |         |                    |     |     |     |     |     |

## Conditions for the Waikato Regional Council Consents

|          |                                                                                                                                                                                                                                                         |
|----------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| SC5.K.8. | The diffusers must be designed and installed so that complete mixing is achieved within:<br><ul style="list-style-type: none"><li>a. 500 m of the upstream discharge point (E1), and</li><li>b. 250 m of the downstream discharge point (E2).</li></ul> |
|          | <b>Discharge Limits and Receiving Environment Standards</b>                                                                                                                                                                                             |
| SC5.K.9. | The treated water discharge must comply with the limits specified in Tables SC5.K.9.T1, SC5.K.9.T2, and SC5.K.9.T3 at all times.                                                                                                                        |

Table SC5.K.9.T1: WTP Discharge Compliance Limits

| Parameter                     | Treated Water Concentration (g/m <sup>3</sup> unless otherwise stated) |                        |                                  |                        |                                  |                        |                                  |                        |                                  |                        |
|-------------------------------|------------------------------------------------------------------------|------------------------|----------------------------------|------------------------|----------------------------------|------------------------|----------------------------------|------------------------|----------------------------------|------------------------|
|                               | Operating Regime A                                                     |                        | Operating Regime B               |                        | Operating Regime C               |                        | Operating Regime D               |                        | Operating Regime E               |                        |
|                               | Normal Compliance <sup>(1)</sup>                                       | Maximum <sup>(1)</sup> | Normal Compliance <sup>(1)</sup> | Maximum <sup>(1)</sup> | Normal Compliance <sup>(1)</sup> | Maximum <sup>(1)</sup> | Normal Compliance <sup>(1)</sup> | Maximum <sup>(1)</sup> | Normal Compliance <sup>(1)</sup> | Maximum <sup>(1)</sup> |
| <b>pH</b>                     | 6.0-9.5                                                                |                        | 6.0-9.5                          |                        | 6.0-9.5                          |                        | 6.0-9.5                          |                        | 6.0-9.5                          |                        |
| <b>Temperature</b>            | <3°C rise                                                              | <3°C rise              | <3°C rise                        | <3°C rise              | <3°C rise                        | <3°C rise              | <3°C rise                        | <3°C rise              | <3°C rise                        | <3°C rise              |
| <b>Total Suspended Solids</b> | 10                                                                     | 50                     | 8                                | 40                     | 5                                | 10                     | 8                                | 40                     | 8                                | 40                     |
| <b>Cyanide (WAD)</b>          | 0.25                                                                   | 0.71                   | 0.2                              | 0.56                   | 0.36                             | 1.02                   | 0.11                             | 0.32                   | 0.09                             | 0.25                   |
| <b>Iron</b>                   | 1.0                                                                    | 6.7                    | 0.8                              | 5.0                    | 0.1                              | 0.3                    | 0.5                              | 3.1                    | 0.4                              | 2.4                    |
| <b>Manganese</b>              | 1.0                                                                    | 1.3                    | 0.8                              | 1.0                    | 0.1                              | 0.4                    | 0.5                              | 0.6                    | 0.4                              | 0.5                    |
| <b>Copper</b>                 | 0.07 <sup>(2)</sup>                                                    | 0.13 <sup>(2)</sup>    | 0.055 <sup>(3)</sup>             | 0.10 <sup>(3)</sup>    | 0.031 <sup>(4a)</sup>            | 0.054 <sup>(4a)</sup>  | 0.033 <sup>(4a)</sup>            | 0.06 <sup>(4a)</sup>   | 0.025 <sup>(4b)</sup>            | 0.05 <sup>(4b)</sup>   |
| <b>Nickel</b>                 |                                                                        | 1.2 <sup>(2)</sup>     |                                  | 0.94 <sup>(3)</sup>    |                                  | 0.64 <sup>(4a)</sup>   |                                  | 0.55 <sup>(4a)</sup>   |                                  | 0.42 <sup>(4b)</sup>   |
| <b>Zinc</b>                   |                                                                        | 0.8 <sup>(2)</sup>     |                                  | 0.61 <sup>(3)</sup>    |                                  | 0.38 <sup>(4a)</sup>   |                                  | 0.36 <sup>(4a)</sup>   |                                  | 0.27 <sup>(4b)</sup>   |
| <b>Ammonia</b>                | Refer Table SC5.K.9.T3                                                 |                        | Refer Table SC5.K.9.T3           |                        | Refer Table SC5.K.9.T3           |                        | Refer Table SC5.K.9.T3           |                        | Refer Table SC5.K.9.T3           |                        |
| <b>Silver</b>                 | 0.02 <sup>(2)</sup>                                                    | 0.03 <sup>(2)</sup>    | 0.017 <sup>(3)</sup>             | 0.024 <sup>(3)</sup>   | 0.005 <sup>(4a)</sup>            | 0.005 <sup>(4a)</sup>  | 0.01 <sup>(4a)</sup>             | 0.014 <sup>(4a)</sup>  | 0.007 <sup>(4b)</sup>            | 0.011 <sup>(4b)</sup>  |
| <b>Antimony</b>               |                                                                        | 0.23                   | 0.1 <sup>(5)</sup>               | 0.18                   | 0.07 <sup>(5)</sup>              | 0.33                   | 0.06 <sup>(5)</sup>              | 0.10                   | 0.05                             | 0.08                   |
| <b>Arsenic</b>                |                                                                        | 1.45                   |                                  | 1.14                   |                                  | 0.02                   |                                  | 0.66                   |                                  | 0.51                   |
| <b>Selenium</b>               | 0.15                                                                   | 0.27                   | 0.12 <sup>(5)</sup>              | 0.2 <sup>(5)</sup>     | 0.22 <sup>(5)</sup>              | 0.38 <sup>(5)</sup>    | 0.07 <sup>(5)</sup>              | 0.12 <sup>(5)</sup>    | 0.05 <sup>(5)</sup>              | 0.09 <sup>(5)</sup>    |
| <b>Mercury</b>                |                                                                        | 0.0005 <sup>(6)</sup>  |                                  | 0.0005 <sup>(6)</sup>  |                                  | 0.0005 <sup>(6)</sup>  |                                  | 0.0005 <sup>(6)</sup>  |                                  | 0.0005 <sup>(6)</sup>  |
| <b>Cadmium</b>                |                                                                        | 0.008 <sup>(2)</sup>   |                                  | 0.007 <sup>(3)</sup>   |                                  | 0.004 <sup>(4a)</sup>  |                                  | 0.004 <sup>(4a)</sup>  |                                  | 0.003 <sup>(4b)</sup>  |

| Parameter           | Treated Water Concentration (g/m <sup>3</sup> unless otherwise stated) |                        |                                  |                        |                                  |                        |                                  |                        |                                  |                        |
|---------------------|------------------------------------------------------------------------|------------------------|----------------------------------|------------------------|----------------------------------|------------------------|----------------------------------|------------------------|----------------------------------|------------------------|
|                     | Operating Regime A                                                     |                        | Operating Regime B               |                        | Operating Regime C               |                        | Operating Regime D               |                        | Operating Regime E               |                        |
|                     | Normal Compliance <sup>(1)</sup>                                       | Maximum <sup>(1)</sup> | Normal Compliance <sup>(1)</sup> | Maximum <sup>(1)</sup> | Normal Compliance <sup>(1)</sup> | Maximum <sup>(1)</sup> | Normal Compliance <sup>(1)</sup> | Maximum <sup>(1)</sup> | Normal Compliance <sup>(1)</sup> | Maximum <sup>(1)</sup> |
| Chromium (VI)       |                                                                        | 0.08                   |                                  | 0.06                   |                                  | 0.05 <sup>(6)</sup>    |                                  | 0.04                   |                                  | 0.03                   |
| Lead                |                                                                        | 0.02 <sup>(2)</sup>    |                                  | 0.018 <sup>(3)</sup>   |                                  | 0.006 <sup>(4a)</sup>  |                                  | 0.011 <sup>(4a)</sup>  |                                  | 0.008 <sup>(4b)</sup>  |
| Hardness Assumption | 670                                                                    |                        | 530                              |                        | 200 <sup>(4)</sup>               |                        | 315                              |                        | 243                              |                        |

## Conditions for the Waikato Regional Council Consents

|  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |
|--|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|  | <p><b>Table SC5.K.9.T1 Notes:</b></p> <p>(1) “Normal Compliance” values to be met 97% of time based on all analyses taken during a quarterly period when the WTP is discharging. “Maximum” values are not to be exceeded in any single analysis.</p> <p>(2) Operating Regime A – For hardness related metals, the compliance values in Table 1 assume a hardness in the WTP discharge of 670 g/m<sup>3</sup> as CaCO<sub>3</sub> prior to dilution in the Ohinemuri River. This equates to an in-river hardness of about 100 g/m<sup>3</sup> as CaCO<sub>3</sub> following mixing. Refer to Table SC5.K.9.T2 for the compliance levels at differing hardness concentrations.</p> <p>(3) Operating Regime B – For hardness related metals, the compliance values in Table SC5.K.9.T1 assume a hardness in the RO only discharge of zero and 530 g/m<sup>3</sup> CaCO<sub>3</sub> prior to dilution in the Ohinemuri River. This equates to an in-river hardness of about 100 g/m<sup>3</sup> as CaCO<sub>3</sub> following mixing. Refer to Table 2 for the compliance levels at differing hardness concentrations.</p> <p>(4) Operating Regime C – Prior to discharge of RO permeate, hardness must be added to achieve a minimum hardness of 200 g/m<sup>3</sup> as CaCO<sub>3</sub> to ensure in-river compliance for hardness-related metals. Refer to Table SC5.K.9.T2 for the compliance levels at differing hardness concentrations.</p> <p>(4a) Operating Regime D – For hardness related metals, the compliance values in Table SC5.K.9.T1 assume a hardness in the WTP discharge of 315 g/m<sup>3</sup> as CaCO<sub>3</sub> prior to dilution in the Ohinemuri River. This equates to an in-river hardness of about 100 g/m<sup>3</sup> as CaCO<sub>3</sub> following mixing. Refer to Table SC5.K.9.T2 for the compliance levels at differing hardness concentrations.</p> <p>(4b) Operating Regime E – For hardness related metals, the compliance values in Table SC5.K.9.T1 assume a hardness in the WTP discharge of 243 g/m<sup>3</sup> as CaCO<sub>3</sub> prior to dilution in the Ohinemuri River. This equates to an in-river hardness of about 100 g/m<sup>3</sup> as CaCO<sub>3</sub> following mixing. Refer to Table SC5.K.9.T2 for the compliance levels at differing hardness concentrations.</p> <p>(5) Values are trigger limits, not compliance limits. In the event that the trigger limits are exceeded, the Consent Holder must inform the Waikato Regional Council as soon as practicable and prepare a report, to the satisfaction of the council, to demonstrate that continued discharges at concentrations exceeding the trigger limits will have no more than minor effects on the Ohinemuri River. This report must be provided to the Waikato Regional Council within two months of the Consent Holder becoming aware of the trigger exceedance.</p> <p>(6) Current analytical procedures for mercury have a practical quantification limit (PQL) of 0.0005 g/m<sup>3</sup>, and for chromium (VI) have a PQL of 0.05 g/m<sup>3</sup>. The reporting 'limit' for mercury and chromium concentrations must be reviewed annually by the Consent Holder and must be adjusted in line with improvements in analytical technology.</p> <p>(7) Discharge limits for metals are for ‘acid-soluble’ concentration, determined on unfiltered samples.</p> <p><b>Table SC5.K.9.T2: Calculation of Compliance Levels for Hardness Related Criteria</b></p> $\text{Maximum Allowable Concentration} = \frac{(1+Z \times (Y-X))}{Z}$ <p>Where:</p> $Y = (\exp \{m [\ln H'] + b\}) \times 10^{-3} \times C, \text{ and}$ $H' = \frac{(Z \times \text{WTP Discharge Hardness}) + 14}{(1+Z)}$ <p>Z=0.15 for Operating Regime A</p> |
|--|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

## Conditions for the Waikato Regional Council Consents

Z=0.2 for Operating Regime B  
 Z=0.1 for Operating Regime C  
 Z=0.4 for Operating Regime D  
 Z=0.6 for Operating Regime E

using the following constants:

| Parameter      | Compliance            |                       | Maximum <sup>(1)</sup> |        | X <sup>(2)</sup> | C                           |
|----------------|-----------------------|-----------------------|------------------------|--------|------------------|-----------------------------|
|                | m                     | B                     | m                      | b      |                  |                             |
| <b>Copper</b>  | 0.8545 <sup>(3)</sup> | -1.465 <sup>(3)</sup> | 0.9422                 | -1.464 | 0.001            | 0.85 or 1.10 <sup>(4)</sup> |
| <b>Nickel</b>  | n/a                   | n/a                   | 0.846                  | 1.1645 | 0.0006           | 1.0                         |
| <b>Zinc</b>    | n/a                   | n/a                   | 0.8473                 | 0.7614 | 0.0047           | 1.0                         |
| <b>Silver</b>  | 1.51 <sup>(5)</sup>   | -9.72 <sup>(5)</sup>  | 1.72                   | -6.52  | 0.00005          | 45.2 or 1.0 <sup>(6)</sup>  |
| <b>Cadmium</b> | n/a                   | n/a                   | 0.7852                 | -3.49  | 0.0001           | 1.0                         |
| <b>Lead</b>    | n/a                   | n/a                   | 1.273                  | -4.705 | 0.0002           | 1.0                         |

Table SC5.K.9.T2 Notes:

- (1) From USEPA acute criteria (copper and silver) or chronic criteria (nickel, zinc, cadmium and lead) for aquatic biota.
- (2) Mean receiving water quality as measured at Station OH3.
- (3) From USEPA chronic criteria for aquatic biota.
- (4) Constant to convert calculation for copper = 0.85 (Compliance value) or = 1.0 (Maximum value).
- (5) From site specific criteria, calculated using USEPA (1985) methodology.
- (6) Constant to convert calculation for silver =  $10^{3/22.1}$  (Compliance value) or = 1.0 (Maximum value).

## Conditions for the Waikato Regional Council Consents

Table SC5.K.9.T3: Compliance Criteria for Total Ammonia

|                   | Normal Compliance, (g/m <sup>3</sup> as total ammonia) |       |       |       |       |       |       | Maximum, (g/m <sup>3</sup> as total ammonia) |        |        |        |        |        |        |
|-------------------|--------------------------------------------------------|-------|-------|-------|-------|-------|-------|----------------------------------------------|--------|--------|--------|--------|--------|--------|
| Temperature, (°C) | 0                                                      | 6     | 10    | 15    | 20    | 25    | 30    | 0                                            | 6      | 10     | 15     | 20     | 25     | 30     |
| pH                | Regime A                                               |       |       |       |       |       |       |                                              |        |        |        |        |        |        |
| 6.50              | 23.00                                                  | 21.46 | 20.70 | 19.17 | 19.17 | 19.17 | 18.40 | 268.31                                       | 252.98 | 237.65 | 229.98 | 222.31 | 222.31 | 222.31 |
| 6.75              | 23.00                                                  | 21.46 | 20.70 | 19.93 | 19.17 | 19.17 | 19.17 | 245.31                                       | 229.98 | 214.65 | 206.98 | 206.98 | 199.32 | 199.32 |
| 7.00              | 23.00                                                  | 21.46 | 20.70 | 19.93 | 19.17 | 19.17 | 19.17 | 214.65                                       | 199.32 | 191.65 | 183.98 | 176.32 | 176.32 | 176.32 |
| 7.25              | 23.00                                                  | 21.46 | 20.70 | 19.93 | 19.17 | 19.17 | 19.17 | 133.39                                       | 168.65 | 153.32 | 151.02 | 147.19 | 145.65 | 145.65 |
| 7.50              | 23.00                                                  | 21.46 | 20.70 | 19.93 | 19.17 | 19.17 | 19.17 | 133.39                                       | 124.96 | 118.82 | 114.22 | 111.92 | 111.16 | 111.16 |
| 7.75              | 21.46                                                  | 19.93 | 19.17 | 18.40 | 17.63 | 17.63 | 18.40 | 93.53                                        | 87.39  | 83.56  | 80.49  | 78.96  | 78.19  | 78.96  |
| 8.00              | 13.95                                                  | 13.03 | 12.42 | 12.04 | 12.65 | 11.88 | 12.19 | 61.33                                        | 57.50  | 54.43  | 52.90  | 52.13  | 52.13  | 53.66  |
| 8.25              | 7.90                                                   | 7.44  | 7.13  | 6.90  | 6.90  | 6.98  | 7.21  | 34.50                                        | 32.20  | 31.43  | 30.66  | 29.90  | 30.66  | 31.43  |
| 8.50              | 4.45                                                   | 4.22  | 4.06  | 4.06  | 4.06  | 4.22  | 4.45  | 19.93                                        | 18.40  | 17.63  | 17.63  | 17.63  | 18.40  | 19.93  |
| 8.75              | 2.61                                                   | 2.45  | 2.38  | 2.38  | 2.45  | 2.68  | 2.91  | 11.27                                        | 10.73  | 10.50  | 10.58  | 10.89  | 11.65  | 12.65  |
| 9.00              | 1.49                                                   | 1.45  | 1.45  | 1.49  | 1.61  | 1.76  | 2.07  | 6.59                                         | 6.36   | 6.36   | 6.59   | 6.98   | 7.74   | 8.89   |
| pH                | Regime B                                               |       |       |       |       |       |       |                                              |        |        |        |        |        |        |
| 6.50              | 18.00                                                  | 16.79 | 16.20 | 15.00 | 15.00 | 15.00 | 14.40 | 209.98                                       | 197.98 | 185.99 | 179.98 | 173.98 | 173.98 | 173.98 |
| 6.75              | 18.00                                                  | 16.79 | 16.20 | 15.60 | 15.00 | 15.00 | 15.00 | 191.98                                       | 179.98 | 167.99 | 161.98 | 161.98 | 155.99 | 155.99 |

# Conditions for the Waikato Regional Council Consents

|                   | Normal Compliance, (g/m <sup>3</sup> as total ammonia) |       |       |       |       |       |       | Maximum, (g/m <sup>3</sup> as total ammonia) |        |        |        |        |        |        |
|-------------------|--------------------------------------------------------|-------|-------|-------|-------|-------|-------|----------------------------------------------|--------|--------|--------|--------|--------|--------|
| Temperature, (°C) | 0                                                      | 6     | 10    | 15    | 20    | 25    | 30    | 0                                            | 6      | 10     | 15     | 20     | 25     | 30     |
| 7.00              | 18.00                                                  | 16.79 | 16.20 | 15.60 | 15.00 | 15.00 | 15.00 | 167.99                                       | 155.99 | 149.99 | 143.98 | 137.99 | 137.99 | 137.99 |
| 7.25              | 18.00                                                  | 16.79 | 16.20 | 15.60 | 15.00 | 15.00 | 15.00 | 104.39                                       | 131.99 | 119.99 | 118.19 | 115.19 | 113.99 | 113.99 |
| 7.50              | 18.00                                                  | 16.79 | 16.20 | 15.60 | 15.00 | 15.00 | 15.00 | 104.39                                       | 97.79  | 92.99  | 89.39  | 87.59  | 86.99  | 86.99  |
| 7.75              | 16.79                                                  | 15.60 | 15.00 | 14.40 | 13.80 | 13.80 | 14.40 | 73.20                                        | 68.39  | 65.39  | 62.99  | 61.79  | 61.19  | 61.79  |
| 8.00              | 10.92                                                  | 10.20 | 9.72  | 9.42  | 9.90  | 9.30  | 9.54  | 48.00                                        | 45.00  | 42.60  | 41.40  | 40.80  | 40.80  | 41.99  |
| 8.25              | 6.18                                                   | 5.82  | 5.58  | 5.40  | 5.40  | 5.46  | 5.64  | 27.00                                        | 25.20  | 24.60  | 23.99  | 23.40  | 23.99  | 24.60  |
| 8.50              | 3.48                                                   | 3.30  | 3.18  | 3.18  | 3.18  | 3.30  | 3.48  | 15.60                                        | 14.40  | 13.80  | 13.80  | 13.80  | 14.40  | 15.60  |
| 8.75              | 2.04                                                   | 1.92  | 1.86  | 1.86  | 1.92  | 2.10  | 2.28  | 8.82                                         | 8.40   | 8.22   | 8.28   | 8.52   | 9.12   | 9.90   |
| 9.00              | 1.17                                                   | 1.13  | 1.13  | 1.17  | 1.26  | 1.38  | 1.62  | 5.16                                         | 4.98   | 4.98   | 5.16   | 5.46   | 6.06   | 6.96   |
| pH                | Regime C                                               |       |       |       |       |       |       |                                              |        |        |        |        |        |        |
| 6.50              | 33.00                                                  | 30.79 | 29.70 | 27.50 | 27.50 | 27.50 | 26.40 | 384.97                                       | 362.97 | 340.98 | 329.97 | 318.97 | 318.97 | 318.97 |
| 6.75              | 33.00                                                  | 30.79 | 29.70 | 28.60 | 27.50 | 27.50 | 27.50 | 351.97                                       | 329.97 | 307.98 | 296.97 | 296.97 | 285.98 | 285.98 |
| 7.00              | 33.00                                                  | 30.79 | 29.70 | 28.60 | 27.50 | 27.50 | 27.50 | 307.98                                       | 285.98 | 274.98 | 263.97 | 252.98 | 252.98 | 252.98 |
| 7.25              | 33.00                                                  | 30.79 | 29.70 | 28.60 | 27.50 | 27.50 | 27.50 | 191.39                                       | 241.98 | 219.98 | 216.68 | 211.19 | 208.98 | 208.98 |
| 7.50              | 33.00                                                  | 30.79 | 29.70 | 28.60 | 27.50 | 27.50 | 27.50 | 191.39                                       | 179.29 | 170.48 | 163.88 | 160.58 | 159.49 | 159.49 |
| 7.75              | 30.79                                                  | 28.60 | 27.50 | 26.40 | 25.30 | 25.30 | 26.40 | 134.20                                       | 125.39 | 119.89 | 115.49 | 113.29 | 112.19 | 113.29 |

# Conditions for the Waikato Regional Council Consents

|                   | Normal Compliance, (g/m <sup>3</sup> as total ammonia) |       |       |       |       |       |       | Maximum, (g/m <sup>3</sup> as total ammonia) |        |        |        |        |        |        |
|-------------------|--------------------------------------------------------|-------|-------|-------|-------|-------|-------|----------------------------------------------|--------|--------|--------|--------|--------|--------|
| Temperature, (°C) | 0                                                      | 6     | 10    | 15    | 20    | 25    | 30    | 0                                            | 6      | 10     | 15     | 20     | 25     | 30     |
| 8.00              | 20.02                                                  | 18.70 | 17.82 | 17.27 | 18.15 | 17.05 | 17.49 | 88.00                                        | 82.50  | 78.10  | 75.90  | 74.80  | 74.80  | 76.99  |
| 8.25              | 11.33                                                  | 10.67 | 10.23 | 9.90  | 9.90  | 10.01 | 10.34 | 49.50                                        | 46.20  | 45.10  | 43.99  | 42.90  | 43.99  | 45.10  |
| 8.50              | 6.38                                                   | 6.05  | 5.83  | 5.83  | 5.83  | 6.05  | 6.38  | 28.60                                        | 26.40  | 25.30  | 25.30  | 25.30  | 26.40  | 28.60  |
| 8.75              | 3.74                                                   | 3.52  | 3.41  | 3.41  | 3.52  | 3.85  | 4.18  | 16.17                                        | 15.40  | 15.07  | 15.18  | 15.62  | 16.72  | 18.15  |
| 9.00              | 2.14                                                   | 2.08  | 2.08  | 2.14  | 2.31  | 2.53  | 2.97  | 9.46                                         | 9.13   | 9.13   | 9.46   | 10.01  | 11.11  | 12.76  |
| pH                | Regime D                                               |       |       |       |       |       |       |                                              |        |        |        |        |        |        |
| 6.50              | 10.50                                                  | 9.80  | 9.45  | 8.75  | 8.75  | 8.75  | 8.40  | 122.49                                       | 115.49 | 108.49 | 104.99 | 101.49 | 101.49 | 101.49 |
| 6.75              | 10.50                                                  | 9.80  | 9.45  | 9.10  | 8.75  | 8.75  | 8.75  | 111.99                                       | 104.99 | 97.99  | 94.49  | 94.49  | 90.99  | 90.99  |
| 7.00              | 10.50                                                  | 9.80  | 9.45  | 9.10  | 8.75  | 8.75  | 8.75  | 97.99                                        | 90.99  | 87.49  | 83.99  | 80.49  | 80.49  | 80.49  |
| 7.25              | 10.50                                                  | 9.80  | 9.45  | 9.10  | 8.75  | 8.75  | 8.75  | 60.90                                        | 76.99  | 69.99  | 68.94  | 67.20  | 66.49  | 66.49  |
| 7.50              | 10.50                                                  | 9.80  | 9.45  | 9.10  | 8.75  | 8.75  | 8.75  | 60.90                                        | 57.05  | 54.24  | 52.14  | 51.09  | 50.75  | 50.75  |
| 7.75              | 9.80                                                   | 9.10  | 8.75  | 8.40  | 8.05  | 8.05  | 8.40  | 42.70                                        | 39.90  | 38.15  | 36.75  | 36.05  | 35.70  | 36.05  |
| 8.00              | 6.37                                                   | 5.95  | 5.67  | 5.50  | 5.78  | 5.42  | 5.57  | 28.00                                        | 26.25  | 24.85  | 24.15  | 23.80  | 23.80  | 24.50  |
| 8.25              | 3.61                                                   | 3.40  | 3.26  | 3.15  | 3.15  | 3.19  | 3.29  | 15.75                                        | 14.70  | 14.35  | 14.00  | 13.65  | 14.00  | 14.35  |
| 8.50              | 2.03                                                   | 1.93  | 1.85  | 1.85  | 1.85  | 1.93  | 2.03  | 9.10                                         | 8.40   | 8.05   | 8.05   | 8.05   | 8.40   | 9.10   |
| 8.75              | 1.19                                                   | 1.12  | 1.09  | 1.09  | 1.12  | 1.22  | 1.33  | 5.15                                         | 4.90   | 4.79   | 4.83   | 4.97   | 5.32   | 5.78   |

# Conditions for the Waikato Regional Council Consents

|                   | Normal Compliance, (g/m <sup>3</sup> as total ammonia) |      |      |      |      |      |      | Maximum, (g/m <sup>3</sup> as total ammonia) |       |       |       |       |       |       |
|-------------------|--------------------------------------------------------|------|------|------|------|------|------|----------------------------------------------|-------|-------|-------|-------|-------|-------|
| Temperature, (°C) | 0                                                      | 6    | 10   | 15   | 20   | 25   | 30   | 0                                            | 6     | 10    | 15    | 20    | 25    | 30    |
| 9.00              | 0.68                                                   | 0.66 | 0.66 | 0.68 | 0.74 | 0.80 | 0.95 | 3.01                                         | 2.90  | 2.90  | 3.01  | 3.19  | 3.53  | 4.06  |
| pH                | Regime E                                               |      |      |      |      |      |      |                                              |       |       |       |       |       |       |
| 6.5               | 8                                                      | 7.47 | 7.2  | 6.67 | 6.67 | 6.67 | 6.4  | 93.33                                        | 87.99 | 83.04 | 79.99 | 77.33 | 77.33 | 77.33 |
| 6.75              | 8                                                      | 7.47 | 7.2  | 6.93 | 6.67 | 6.67 | 6.67 | 85.33                                        | 79.99 | 74.66 | 71.99 | 71.99 | 69.33 | 69.33 |
| 7                 | 8                                                      | 7.47 | 7.2  | 6.93 | 6.67 | 6.67 | 6.67 | 74.66                                        | 69.33 | 66.66 | 63.99 | 61.33 | 61.33 | 61.33 |
| 7.25              | 8                                                      | 7.47 | 7.2  | 6.93 | 6.67 | 6.67 | 6.67 | 46.4                                         | 58.66 | 53.33 | 52.53 | 51.2  | 50.66 | 50.66 |
| 7.5               | 8                                                      | 7.47 | 7.2  | 6.93 | 6.67 | 6.67 | 6.67 | 46.4                                         | 43.47 | 41.33 | 39.73 | 38.93 | 38.67 | 38.67 |
| 7.75              | 7.47                                                   | 6.93 | 6.67 | 6.4  | 6.13 | 6.13 | 6.4  | 32.53                                        | 30.4  | 29.07 | 28    | 27.47 | 27.2  | 27.47 |
| 8                 | 4.85                                                   | 4.53 | 4.32 | 4.19 | 4.13 | 4.13 | 4.24 | 21.33                                        | 20    | 18.93 | 18.4  | 18.13 | 18.13 | 18.67 |
| 8.25              | 2.75                                                   | 2.59 | 2.48 | 2.4  | 2.4  | 2.43 | 2.51 | 12                                           | 11.2  | 10.93 | 10.67 | 10.4  | 10.67 | 10.93 |
| 8.5               | 1.55                                                   | 1.47 | 1.41 | 1.41 | 1.41 | 1.47 | 1.55 | 6.93                                         | 6.4   | 6.13  | 6.13  | 6.13  | 6.4   | 6.93  |
| 8.75              | 0.91                                                   | 0.85 | 0.83 | 0.83 | 0.85 | 0.93 | 1.01 | 3.92                                         | 3.73  | 3.65  | 3.68  | 3.79  | 4.05  | 4.4   |
| 9                 | 0.52                                                   | 0.5  | 0.5  | 0.52 | 0.56 | 0.61 | 0.72 | 2.29                                         | 2.21  | 2.21  | 2.29  | 2.43  | 2.69  | 3.09  |

## Conditions for the Waikato Regional Council Consents

|               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |  |                                                          |         |     |
|---------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|----------------------------------------------------------|---------|-----|
| SC5.K.10.     | <p>1. The Consent Holder must manage the selenium concentration in the discharge to ensure that the following fish flesh triggers are not exceeded as a result of the discharge:</p> <table border="1" data-bbox="387 320 1331 427"> <tr> <td></td><td>Whole body fish flesh trigger limits, mg/kg (dry weight)</td></tr> <tr> <td>Bullies</td><td>8.4</td></tr> </table> <p>2. Compliance with this condition must be assessed by the monitoring regime described in Condition SC5.K.13, Table SC5.K.13.T5. In the event of an exceedance of the fish flesh trigger limit, the Consent Holder must:</p> <ol style="list-style-type: none"> <li>Advise Waikato Regional Council within 48 hours of receipt of the results, and</li> <li>Reduce the selenium concentration in the discharge to 0.04 g/m<sup>3</sup> for Regime A, 0.03 g/m<sup>3</sup> for Regime B, 0.05 g/m<sup>3</sup> for Regime C, 0.02 g/m<sup>3</sup> for Regime D and 0.02 g/m<sup>3</sup> for Regime E unless otherwise agreed with Waikato Regional Council in writing.</li> </ol> <p>3. Within 10 working days of advising Waikato Regional Council of an exceedance of the fish flesh trigger limit, the Consent Holder must submit a report to Waikato Regional Council that summarises:</p> <ol style="list-style-type: none"> <li>Selenium concentrations in the treated water and receiving water and the results of any additional selenium monitoring required by this consent over the previous three months or as otherwise agreed with Waikato Regional Council;</li> <li>Any operational events during the same period that might be related to the exceedance; and</li> <li>Any recommended actions as a result of the exceedance and the reported and assessed selenium concentrations.</li> </ol> <p>4. The recommended actions must be implemented following consultation with and the approval of Waikato Regional Council.</p> <p>5. Following the implementation of requirements SC5.K.10 (1) – (3), the Consent Holder may revert to normal operating limits (as per Table SC5.K.9.T1 – WTP Discharge Compliance Limits) with the written approval of the Waikato Regional Council.</p> |  | Whole body fish flesh trigger limits, mg/kg (dry weight) | Bullies | 8.4 |
|               | Whole body fish flesh trigger limits, mg/kg (dry weight)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |  |                                                          |         |     |
| Bullies       | 8.4                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |  |                                                          |         |     |
| SC5.K.10<br>B | <p>1. If after a period of three years from the commencement of this resource consent the monitoring required by Condition SC5.K.10 has not identified any exceedance of the identified fish flesh triggers for Bullies, the Consent Holder may consult with the Waikato Regional Council to determine if there is a need for this monitoring to continue.</p> <p>2. If it is agreed by the Waikato Regional Council that the monitoring requirements of Condition SC5.K.10 are no longer required, the Consent Holder may cease this monitoring.</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |  |                                                          |         |     |
| SC5.K.11.     | <p>Except as provided for by Condition SC5.K.13, Table SC5.K.13.T5 and Condition SCK.12, the Consent Holder must not sample and analyse eels unless otherwise agreed with Waikato Regional Council in writing.</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |  |                                                          |         |     |

## Conditions for the Waikato Regional Council Consents

|               | <b>Monitoring</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |                                                                                                                                                                                                                                                                                             |                  |                                                              |              |                                                          |                                                                                                   |                              |                                                  |                                                                     |                                                              |               |                                                                                                      |         |                                                                                                           |                                                                                                                                                                                                                                                                                             |        |               |        |
|---------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------|--------------------------------------------------------------|--------------|----------------------------------------------------------|---------------------------------------------------------------------------------------------------|------------------------------|--------------------------------------------------|---------------------------------------------------------------------|--------------------------------------------------------------|---------------|------------------------------------------------------------------------------------------------------|---------|-----------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|---------------|--------|
| SC5.K.12.     | <div>1. Unless otherwise agreed in writing by Waikato Regional Council, the Consent Holder must undertake the monitoring set out in Table SC5.K.12.4.</div> <div><b>Table SC5.K.12.4: WTP Discharge Monitoring</b></div> <table><tr><th>Frequency</th><th>Site</th><th>Parameters</th></tr><tr><td>Continuously</td><td>WTP Discharge<br/><br/>Frendrups<br/><br/>Torrens (Ruddocks)</td><td>Flow (at both discharge sites), turbidity, conductivity, pH, temperature<br/><br/>Flow, temperature</td></tr><tr><td>Daily</td><td>WTP Discharge</td><td>Cyanide, copper, iron, manganese, suspended solids, ammonia, silver</td></tr><tr><td>Weekly</td><td>WTP discharge</td><td>Nickel, zinc, arsenic, mercury, cadmium, chromium (VI), lead, hardness, sulphate, Selenium, Antimony</td></tr><tr><td>Monthly</td><td>Ohinemuri River (at location OH5 for discharges at point E1, and location OH6 for discharges at point E2)</td><td>pH, suspended solids, cyanide (CNWAD) iron, manganese, copper, nickel, zinc, silver, total ammonia, antimony, arsenic, selenium, mercury, cadmium, chromium (VI), lead, hardness, sulphate; nitrate, nitrite-nitrate, TKN, Total nitrogen, total phosphorus, dissolved reactive phosphorus.</td></tr><tr><td>Annual</td><td>WTP Discharge</td><td>Cobalt</td></tr></table> <div><p><i>Note:</i></p><p><i>The WTP discharge monitoring programme for metals are for 'acid-soluble' concentrates determined on unfiltered samples.</i></p><div>2. Monitoring of selenium and antimony in the Ohinemuri River must be based on the soluble test method, defined as the concentration of dissolved metal measured in that fraction which passes through a 0.45µm filter.</div></div> | Frequency                                                                                                                                                                                                                                                                                   | Site             | Parameters                                                   | Continuously | WTP Discharge<br><br>Frendrups<br><br>Torrens (Ruddocks) | Flow (at both discharge sites), turbidity, conductivity, pH, temperature<br><br>Flow, temperature | Daily                        | WTP Discharge                                    | Cyanide, copper, iron, manganese, suspended solids, ammonia, silver | Weekly                                                       | WTP discharge | Nickel, zinc, arsenic, mercury, cadmium, chromium (VI), lead, hardness, sulphate, Selenium, Antimony | Monthly | Ohinemuri River (at location OH5 for discharges at point E1, and location OH6 for discharges at point E2) | pH, suspended solids, cyanide (CNWAD) iron, manganese, copper, nickel, zinc, silver, total ammonia, antimony, arsenic, selenium, mercury, cadmium, chromium (VI), lead, hardness, sulphate; nitrate, nitrite-nitrate, TKN, Total nitrogen, total phosphorus, dissolved reactive phosphorus. | Annual | WTP Discharge | Cobalt |
| Frequency     | Site                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Parameters                                                                                                                                                                                                                                                                                  |                  |                                                              |              |                                                          |                                                                                                   |                              |                                                  |                                                                     |                                                              |               |                                                                                                      |         |                                                                                                           |                                                                                                                                                                                                                                                                                             |        |               |        |
| Continuously  | WTP Discharge<br><br>Frendrups<br><br>Torrens (Ruddocks)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | Flow (at both discharge sites), turbidity, conductivity, pH, temperature<br><br>Flow, temperature                                                                                                                                                                                           |                  |                                                              |              |                                                          |                                                                                                   |                              |                                                  |                                                                     |                                                              |               |                                                                                                      |         |                                                                                                           |                                                                                                                                                                                                                                                                                             |        |               |        |
| Daily         | WTP Discharge                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | Cyanide, copper, iron, manganese, suspended solids, ammonia, silver                                                                                                                                                                                                                         |                  |                                                              |              |                                                          |                                                                                                   |                              |                                                  |                                                                     |                                                              |               |                                                                                                      |         |                                                                                                           |                                                                                                                                                                                                                                                                                             |        |               |        |
| Weekly        | WTP discharge                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | Nickel, zinc, arsenic, mercury, cadmium, chromium (VI), lead, hardness, sulphate, Selenium, Antimony                                                                                                                                                                                        |                  |                                                              |              |                                                          |                                                                                                   |                              |                                                  |                                                                     |                                                              |               |                                                                                                      |         |                                                                                                           |                                                                                                                                                                                                                                                                                             |        |               |        |
| Monthly       | Ohinemuri River (at location OH5 for discharges at point E1, and location OH6 for discharges at point E2)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | pH, suspended solids, cyanide (CNWAD) iron, manganese, copper, nickel, zinc, silver, total ammonia, antimony, arsenic, selenium, mercury, cadmium, chromium (VI), lead, hardness, sulphate; nitrate, nitrite-nitrate, TKN, Total nitrogen, total phosphorus, dissolved reactive phosphorus. |                  |                                                              |              |                                                          |                                                                                                   |                              |                                                  |                                                                     |                                                              |               |                                                                                                      |         |                                                                                                           |                                                                                                                                                                                                                                                                                             |        |               |        |
| Annual        | WTP Discharge                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | Cobalt                                                                                                                                                                                                                                                                                      |                  |                                                              |              |                                                          |                                                                                                   |                              |                                                  |                                                                     |                                                              |               |                                                                                                      |         |                                                                                                           |                                                                                                                                                                                                                                                                                             |        |               |        |
| SC5.K.13.     | <div>1. Unless otherwise agreed with Waikato Regional Council, the Consent Holder must undertake the monitoring set out in Table SC5.K.13.T5.</div> <div><b>Table SC5.K.13.T5: Biological, Sediment and River Water Quality Monitoring</b></div> <table><tr><th>Aquatic biota</th><th>Frequency</th><th>Sites</th><th>Methods</th><th>Parameters</th></tr><tr><td>Fish</td><td>Late summer<br/><br/>(Feb-Mar)</td><td>OC2, OH5, RU1, OH1, OH6, a site on Mataura, (M1)</td><td>Electric fishing</td><td>Species numbers<br/><br/>Species abundance<br/><br/>Fish lengths</td></tr></table>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Aquatic biota                                                                                                                                                                                                                                                                               | Frequency        | Sites                                                        | Methods      | Parameters                                               | Fish                                                                                              | Late summer<br><br>(Feb-Mar) | OC2, OH5, RU1, OH1, OH6, a site on Mataura, (M1) | Electric fishing                                                    | Species numbers<br><br>Species abundance<br><br>Fish lengths |               |                                                                                                      |         |                                                                                                           |                                                                                                                                                                                                                                                                                             |        |               |        |
| Aquatic biota | Frequency                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Sites                                                                                                                                                                                                                                                                                       | Methods          | Parameters                                                   |              |                                                          |                                                                                                   |                              |                                                  |                                                                     |                                                              |               |                                                                                                      |         |                                                                                                           |                                                                                                                                                                                                                                                                                             |        |               |        |
| Fish          | Late summer<br><br>(Feb-Mar)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | OC2, OH5, RU1, OH1, OH6, a site on Mataura, (M1)                                                                                                                                                                                                                                            | Electric fishing | Species numbers<br><br>Species abundance<br><br>Fish lengths |              |                                                          |                                                                                                   |                              |                                                  |                                                                     |                                                              |               |                                                                                                      |         |                                                                                                           |                                                                                                                                                                                                                                                                                             |        |               |        |

## Conditions for the Waikato Regional Council Consents

|           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |                                                  |                           |                                                                                                                       |                                                                                      |
|-----------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------|---------------------------|-----------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------|
|           | Macro-Invertebrates                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Spring<br>(Oct-Dec)<br><br>Autumn<br>(Mar-May)   | OH3, OH5 RU1,<br>OH1, OH6 | Surber sampling                                                                                                       | Taxa richness<br><br>Total abundance<br><br>Key taxa<br>abundance                    |
|           | Periphyton                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | Spring<br>(Oct-Dec)<br><br>Autumn<br>(Mar-May)   | OH3, OH5 RU1,<br>OH1, OH6 | Rock scrape<br>sampling                                                                                               | Chla, AFDW, taxa<br>richness                                                         |
|           | Water<br>Quality                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | Spring<br>(Oct-Dec)<br><br>Autumn<br>(Mar-May)   | OH3, OH5 RU1,<br>OH1, OH6 | Spot Sampling                                                                                                         | All parameters<br>listed in<br>Condition<br>SC5.K.9, Table 1,<br>and NO <sub>3</sub> |
|           | Sediment                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | Spring<br>(Oct- Dec)<br><br>Autumn<br>(Mar- May) | OH3, OH5 RU1,<br>OH1, OH6 | Sediment Coring                                                                                                       | Metals listed in<br>Condition<br>SC5.K.9, Table 1                                    |
|           | Fish (bullies)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Once during<br>summer (January<br>to March)      | OC2, OH6                  | Analysed in<br>accordance with<br>appropriate<br>USEPA<br>procedures as<br>agreed with<br>Waikato Regional<br>Council | Composite whole<br>body selenium<br>concentration<br>(dry weight)                    |
|           | Periphyton<br>and<br>macrophyte                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Autumn (Mar-<br>May)                             | OC2, OH6                  | Analysed in<br>accordance with<br>appropriate<br>USEPA<br>procedures as<br>agreed with<br>Waikato Regional<br>Council | Total Selenium<br>(both wet weight<br>and dry weight)                                |
|           | 2. The results of sampling undertaken to determine selenium concentration in fish, periphyton and macrophyte must be submitted to the Waikato Regional Council within one month of the sampling event.                                                                                                                                                                                                                                                                                                        |                                                  |                           |                                                                                                                       |                                                                                      |
| SC5.K.14. | <p>1. Following the completion of two seasonal monitoring events (e.g. spring to spring), if a statistically significant difference (at the 95<sup>th</sup> confidence level) has occurred between sites the Consent Holder must immediately undertake further macroinvertebrate biota and abundance monitoring.</p> <p>2. Should this further monitoring determine that a statistically significant difference has persisted, the Consent Holder must inform the Waikato Regional Council immediately on</p> |                                                  |                           |                                                                                                                       |                                                                                      |

## Conditions for the Waikato Regional Council Consents

|           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |
|-----------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|           | <p>receipt of the results and determine any mitigation measures that need to be implemented to ensure that significant effects are remedied or mitigated.</p> <p>3. In this condition 'significant' is defined as follows:</p> <ol style="list-style-type: none"> <li>A significant difference in macroinvertebrate biota will be deemed to have occurred following a statistically significant change at test sites OH5 and OH6 of 30% above the natural variation recorded at the control sites OH3 and OH1; and</li> <li>A significant difference in total macroinvertebrate abundance will be deemed to have occurred following a statistically significant change at test sites OH5 and OH6 of 50% above the natural variation recorded at the control sites OH3 and OH1.</li> </ol> <p><i>Note: River monitoring sites are illustrated in <b>Attachment 1</b> to this consent</i></p> |
|           | <b>Temperature</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |
| SC5.K.15. | During the period 1 November to 30 April each year the discharge must not cause the temperature of the Ohinemuri River between monitoring sites OH3 and OH5, or OH1 and OH6 to increase more than 3.0 degrees Celsius.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |
| SC5.K.16. | <ol style="list-style-type: none"> <li>During the period 1 November to 30 April each year the Consent Holder must record water temperature continuously at sites OH3, OH5, OH1 and OH6. Data must be retrieved and checked for compliance every 7 days.</li> <li>The determination of compliance with Condition SC5.K.15 must be assessed on a daily basis as being the difference between the Cox-Rutherford Index, being the average of the daily mean and the maximum temperature for each site, or another method to the satisfaction of the Waikato Regional Council.</li> </ol> <p><i><u>Advice Note:</u> Continuously means recording temperature at least every 15 minutes for the extent of the required period.</i></p>                                                                                                                                                           |
|           | <b>Annual Summer Low Flow Monitoring</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
| SC5.K.17. | <ol style="list-style-type: none"> <li>The Consent Holder must undertake an annual low flow stream study (<b>the Study</b>) between February to April when the discharge is operating and following a period of stable dry weather and when no significant rainfall is forecast.</li> <li>The Study must commence within 12 months of this consent first being exercised and continue for four consecutive summers.</li> </ol>                                                                                                                                                                                                                                                                                                                                                                                                                                                              |
| SC5.K.18. | <ol style="list-style-type: none"> <li>The Study must be undertaken over a period of seven days in each summer at three locations close to sites OH3, OH5 and OH6.</li> <li>The study must account for any influence the discharge from TSF2 may be having at OH3 and the influence that flows from the Ruahorehore Stream have on OH6.</li> </ol>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |
| SC5.K.19. | <ol style="list-style-type: none"> <li>The Study must as a minimum include:</li> </ol>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |

## Conditions for the Waikato Regional Council Consents

|           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
|-----------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|           | <ul style="list-style-type: none"> <li>a. Continuous diurnal monitoring for temperature for the seven-day period, including monitoring in the Ruahorehore Stream due to the influence of its flows on the Ohinemuri River at OH6; and</li> <li>b. Periphyton, macrophyte, macroinvertebrate community and physical habitat assessments at sites OH3, OH5 and OH6 including monitoring in the Ruahorehore Stream due to the influence of its flows on the Ohinemuri River at OH6.</li> </ul> <p>2. The monitoring and assessment methods necessary to implement the Study must be formulated by a suitably qualified and experienced scientist to the satisfaction of the Waikato Regional Council.</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |
| SC5.K.20. | <p>By 30 June in each year that the Study is undertaken the Consent Holder must provide a report to the Waikato Regional Council prepared by a suitably qualified and experienced scientist that summarises the data collected by the Study.</p> <p><i>Note: The report of the low flow stream study may be combined with any similar reports required under other resource consents held by the consent holder which authorise mining in the Waihi area.</i></p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |
| SC5.K.21. | <p>By 30 June of year following the completion of the fourth year of the Study required by Condition SC5.K.17, the Consent Holder must provide a report to the Waikato Regional Council prepared by a suitably qualified and experienced scientist that:</p> <ul style="list-style-type: none"> <li>a. Summarises the findings of the low flow assessments;</li> <li>b. Provides an assessment of what temperature changes occur in the Ohinemuri River;</li> <li>c. Provides an assessment of any effects changes in water temperature upstream and downstream of the treated water discharge authorised by this consent have on the aquatic ecological values of the Ohinemuri River;</li> <li>d. Provides an assessment of the contribution of the treated water discharge (if any) to changes measured in temperature levels upstream and downstream of the discharge; and</li> <li>e. Provides recommendations on whether any changes to the operation of the Wastewater Treatment Plant are needed in respect of its contribution to instream temperature to safeguard the life supporting capacity of the Ohinemuri River. Such changes may include the need for an alteration to the discharge regime where the results of the study determine that there are adverse effects on ecological values occurring as a result of temperature changes that accrue from the discharge.</li> </ul> |
| SC5.K.22. | <p>All biological monitoring sampling and analysis must have regard to:</p> <ul style="list-style-type: none"> <li>a. Consistent quantitative estimates of the aquatic biota;</li> <li>b. Consistent laboratory and sorting/counting protocols;</li> <li>c. Consistent taxonomic resolution of aquatic biota;</li> </ul> <p>and must be undertaken to the satisfaction of the Waikato Regional Council.</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |

## Conditions for the Waikato Regional Council Consents

|           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |
|-----------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| SC5.K.23. | <ol style="list-style-type: none"> <li>1. All water quality and sediment sampling and analysis must be undertaken using Standard Methods for the Examination of Water and Wastewater (19th Edition 1995, or updates), APHA, AWWA and WEF, unless otherwise agreed in writing by Waikato Regional Council.</li> <li>2. All other measuring, testing, recording and analytical methods as may be required from time to time pursuant to the requirements of this consent must be to the satisfaction of the Waikato Regional Council.</li> </ol>                                                                                                                                                                                                                                                                                                                                                    |
| SC5.K.24. | <ol style="list-style-type: none"> <li>1. A report detailing the results of all monitoring specified in Condition SC5.K.12 and Condition SC5.K.13 must be submitted to Waikato Regional Council by 30 July each year.</li> <li>2. Should a more appropriate set of standards or guidelines be developed, then those may be substituted as the comparison guidelines by mutual written agreement between Waikato Regional Council and the Consent Holder.</li> </ol>                                                                                                                                                                                                                                                                                                                                                                                                                               |
|           | <b>Consent Review</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |
| SC5.K.25. | <p>In addition to the matters listed in Condition G34, the Waikato Regional Council may serve notice in accordance with Sections 128 and 129 of the Act, within 12 months of receiving the report required by Condition SC5.K.24 of its intention to review the conditions of this consent for the purposes of:</p> <ol style="list-style-type: none"> <li>a. Amending the discharge limits (Conditions SC5.K.9 and SC5.K.10) and receiving environment standards (Condition G18) to reflect the objectives and limits set in the Regional Plan;</li> <li>b. Providing for any investigations necessary to identify Plant improvements required to achieve any revised discharge limits and receiving environment standards; and</li> <li>c. Updating other conditions as necessary to reflect any changes to the discharge limits, receiving environment standards and/or timeframes.</li> </ol> |

## Conditions for the Waikato Regional Council Consents

|                                        |                                                                                                                                                                                                                                                                  |
|----------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                       | AUTH144654.33.01                                                                                                                                                                                                                                                 |
| CONSENT TYPE AND ACTIVITIES AUTHORISED | <p>RMA S13 To place a structure in the bed of an undefined waterbody.</p> <p>RMA S14 To dam water within the Water Treatment Plant Collection Pond.</p> <p>RMA S15 To discharge water from the Water Treatment Plant Collection Pond to the Ohinemuri River.</p> |
| LOCATION                               | Area 5                                                                                                                                                                                                                                                           |
| TERM                                   | 35 years                                                                                                                                                                                                                                                         |
| LAPSE PERIOD                           | 10 years                                                                                                                                                                                                                                                         |

|          |                                                                                                                                                                                                                                                                                                                                   |
|----------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|          | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                                                                                                                         |
| SC5.L.1. | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent.                                                                                                |
|          | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                                                                                                                     |
| SC5.L.2. | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                                                                                                                              |
|          | <b>Maintenance Requirements</b>                                                                                                                                                                                                                                                                                                   |
| SC5.L.3. | The Consent Holder must maintain the structural integrity of the works associated with the exercise of these consents and of any erosion control and energy dissipation works which become necessary as a consequence of the exercise of this consent.                                                                            |
|          | <b>Design Requirements</b>                                                                                                                                                                                                                                                                                                        |
| SC5.L.4. | The Water Treatment Plant Collection Pond must be constructed and operated to have a minimum water storage capacity sufficient to contain the run-off generated during a 10% Annual Exceedance Probability (AEP), 72-hour duration design storm event, taking into account a combination of both storage volume and pumping rate. |
|          | <b>Operational Requirements</b>                                                                                                                                                                                                                                                                                                   |
| SC5.L.5. | For rainfall events with an AEP greater than 10%, all stormwater reporting to the Collection Pond must be pumped to the Water Treatment Plant for treatment.                                                                                                                                                                      |
| SC5.L.6. | The Water Treatment Plant Collection Pond must be constructed from materials which provide for secure long term containment and which:                                                                                                                                                                                            |

## Conditions for the Waikato Regional Council Consents

|          |                                                                                                                                                                                                                   |
|----------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|          | <p>a. Has no acid forming potential; and</p> <p>b. Is lined with 1.5 mm HDPE with a 0.5 m protective cover layer (or other liner approved by the Waikato Regional Council) to a height of 1.5m from the base.</p> |
| SC5.L.7. | Routine maintenance and desilting of the Water Treatment Plant Collection Pond must only occur during periods of projected fine weather. All silt removed must be disposed of to a tailings storage facility.     |
| SC5.L.8. | No chemicals or additives must be used in the Water Treatment Plant Collection Pond or the discharge from those ponds without the prior written approval of the Waikato Regional Council.                         |

## Conditions for the Waikato Regional Council Consents

|                                        |                                                                                 |
|----------------------------------------|---------------------------------------------------------------------------------|
| RESOURCE CONSENT                       | AUTH144654.34.01                                                                |
| CONSENT TYPE AND ACTIVITIES AUTHORISED | RMA S14 To dam and divert natural water around the Waihi Surface Facility Area. |
| LOCATION                               | Area 5                                                                          |
| TERM                                   | 35 years                                                                        |
| LAPSE PERIOD                           | 10 years                                                                        |

|          |                                                                                                                                                                                                                                               |
|----------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|          | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                                     |
| SC5.M.1. | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent.            |
|          | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                                 |
| SC5.M.2. | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                                          |
|          | <b>Design and Construction Requirements</b>                                                                                                                                                                                                   |
| SC5.M.3. | The diversion channel must be designed to convey a 10% Annual Exceedance Probability (“AEP”) flood event.                                                                                                                                     |
| SC5.M.4. | All construction works must be implemented under the supervision of appropriately qualified and experienced persons.                                                                                                                          |
| SC5.M.5. | The Consent Holder must ensure that the area of disturbance during construction of the diversion works is kept to a minimum.                                                                                                                  |
| SC5.M.6. | The Consent Holder must advise Waikato Regional Council in writing in advance of the proposed construction of each of the diversion channels, and must provide plans of the proposed works, and advise proposed start times for construction. |
| SC5.M.7. | Within 20 working days following completion of each diversion, the Consent Holder must provide Waikato Regional Council with as-built plans of the completed works.                                                                           |

## Conditions for the Waikato Regional Council Consents

|                                        |                                                                                                                                      |
|----------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                       | AUTH144654.35.01                                                                                                                     |
| CONSENT TYPE AND ACTIVITIES AUTHORISED | RMA S14 To dam and divert site stormwater to the contingency ponds and WTP collection pond within the Waihi Surface Facilities Area. |
| LOCATION                               | Area 5                                                                                                                               |
| TERM                                   | 35 years                                                                                                                             |
| LAPSE PERIOD                           | 10 years                                                                                                                             |

|          |                                                                                                                                                                                                                                                             |
|----------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|          | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                                                   |
| SC5.N.1. | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent.                          |
|          | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                                               |
| SC5.N.2. | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                                                        |
|          | <b>Design and Construction Requirements</b>                                                                                                                                                                                                                 |
| SC5.N.3. | Any earthworks or structures installed for the diversion and discharge of stormwater must be designed to manage a 10% Annual Exceedance Probability (AEP) flood event and pass a 1% AEP flood event. Secondary flow paths must be away from the stockpiles. |
| SC5.N.4. | All construction works must be implemented under the supervision of appropriately qualified and experienced persons.                                                                                                                                        |
| SC5.N.5. | The Consent Holder must ensure that the area of disturbance during construction of the diversion works is kept to a minimum.                                                                                                                                |
| SC5.N.6. | The Consent Holder must advise Waikato Regional Council in writing in advance of the proposed construction of each of the diversion channels, and must provide plans of the proposed works, and advise proposed start times for construction.               |
| SC5.N.7. | Within 20 working days following completion of each diversion, the Consent Holder must provide Waikato Regional Council with as-built plans of the completed works.                                                                                         |

## Conditions for the Waikato Regional Council Consents

|                                        |                                                                                                            |
|----------------------------------------|------------------------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                       | AUTH144654.36.01                                                                                           |
| CONSENT TYPE AND ACTIVITIES AUTHORISED | RMA S15 To discharge overburden and ore on to land in stockpiles within the Waihi Surface Facilities Area. |
| LOCATION                               | Area 5                                                                                                     |
| TERM                                   | 35 years                                                                                                   |
| LAPSE PERIOD                           | 10 years                                                                                                   |

|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |
|----------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|          | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |
| SC5.O.1. | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent.                                                                                                                                                                                                                                                                                                                                                                                                                                                   |
|          | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |
| SC5.O.2. | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |
|          | <b>Non-Acid Forming Material Stockpiles</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |
| SC5.O.3. | Preparation of stockpile sites for the temporary storage of non-acid forming (NAF) waste rock and soil prior to the placement of material must include: <ul style="list-style-type: none"> <li>a. Stripping and stockpiling of topsoil and subsoils for later use in site rehabilitation.</li> <li>b. Construction of clean water diversion drains around the site to divert and discharge clean surface run-off and intercepted groundwater in accordance with consent AUTH144654.34 .</li> <li>c. Construction of diversion drains around the site perimeter to divert stockpile run-off to silt ponds for sediment reduction prior to discharge.</li> </ul>                       |
|          | <b>Potentially Acid Forming Material Stockpiles</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |
| SC5.O.4. | 1. Stockpiling of ore or any potentially acid forming (PAF) waste rock must occur only at sites specifically prepared for that purpose. Any area to be used for this purpose must be constructed from or lined with at least 600mm of natural or non acid forming materials with a permeability of no greater than $1 \times 10^{-8}$ m/s, or alternatively a synthetic liner with equivalent or better performance, approved by the Waikato Regional Council. In situ soils may be used for this purpose if the Consent Holder can demonstrate to the Waikato Regional Council's satisfaction that the protection provided is equivalent to the liner specification detailed above. |

## Conditions for the Waikato Regional Council Consents

|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |
|----------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|          | <p>2. In addition to the provisions of Condition SC5.O.3(a) and SC5.O.3(b), PAF stockpile site preparation must include:</p> <ul style="list-style-type: none"> <li>a. Grading of the proposed stockpile site and construction of stockpile drains around the site perimeter to divert stockpile run-off and leachate to a collection pond or ponds (from which collected water can be pumped to the Water Treatment Plant prior to discharge to the Ohinemuri River); and</li> <li>b. Placement of selected, coarse waste rock as the initial layer on the low-permeability layer of the stockpile footprint to act as a leachate drainage layer. The perimeter of this drainage layer must be designed and constructed to prevent the ingress of oxygen into the stockpile;</li> <li>c. If an alternative synthetic liner is used in preference to an earth liner, the synthetic liner must be covered with a protection layer consisting of soil that is placed and compacted to a minimum thickness of 400mm.</li> </ul>                                                                                                               |
| SC5.O.5. | Drains constructed for the purposes of conveying run-off and leachate from the PAF stockpile(s) to the collection pond(s) and the Water Treatment Plant must be adequately sized and lined by a method agreed to by the Waikato Regional Council and detailed in the Water Management Plan prepared pursuant to Conditions G29-G32 of Schedule Two – General Conditions.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |
| SC5.O.6. | <p>The Consent Holder must ensure that the collection pond(s) referred to in Condition SC5.O.4.2.a is designed and constructed from materials that provide secure long term containment including:</p> <ul style="list-style-type: none"> <li>a. A low-permeability liner forming the base and sides of the pond(s) that achieve the same or better standard to that required of the PAF stockpile liner as detailed in Condition SC5.O.4, or alternatively a synthetic liner with equivalent or better performance, approved by the Waikato Regional Council;</li> <li>b. A minimum water storage capacity equivalent to the volume of run-off generated from within its catchment during a 10% Annual Exceedance Probability (AEP), 72-hour duration, design storm, taking into account a combination of both storage volume and pumping rate;</li> <li>c. A pump system capable of pumping all stormwater reporting to the collection pond during rainfall events less than or equal to the above design storm to the Water Treatment Plant for treatment; and</li> <li>d. A spillway that will safely route a 1% AEP flood.</li> </ul> |
|          | <b>Monitoring</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |
| SC5.O.7. | The Consent Holder must maintain groundwater quality monitoring bores to detect seepage bypassing the PAF stockpile site underdrainage system, and to determine the representative groundwater quality for shallow groundwater around the perimeter of land owned by the Consent Holder.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |
| SC5.O.8. | The Consent Holder must undertake monitoring of the parameters annexed as <b>Attachment 1</b> to this consent in the bores maintained in accordance with Condition SC5.O.7 in order to establish trends in the monitoring bores. Monitoring must continue throughout the term of these                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |

## Conditions for the Waikato Regional Council Consents

|           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |
|-----------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|           | consents. The results of that monitoring must be forwarded to Waikato Regional Council quarterly.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |
| SC5.O.9.  | The Consent Holder must calculate trigger levels for the parameters annexed as <b>Attachment 1</b> to this consent for down gradient bores based on the trends observed in the monitoring data at levels which will provide early warning indicator of potential changes of groundwater quality as a result of the activities authorised by this consent.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |
| SC5.O.10. | <ol style="list-style-type: none"> <li>At any time if monitoring results within the monitoring bores exceed the relevant trigger level for that bore over two consecutive readings then the Consent Holder must: <ol style="list-style-type: none"> <li>Characterise and assess the source of the exceedance; and</li> <li>Take all necessary measures to ensure that General Condition G18 is complied with.</li> </ol> </li> <li>The trigger level exceedance and measures taken must be reported to the Waikato Regional Council immediately upon completion.</li> </ol>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |
| SC5.O.11. | <ol style="list-style-type: none"> <li>Ongoing monitoring must be undertaken at the locations and using the methodology outlined in the Area 5 Rock Storage Monitoring and Management Plan required by Condition SC5.O.12, with monitoring to include the measurement of all parameters annexed as <b>Attachment 1</b> to this consent.</li> <li>Monitoring results must be provided to the Waikato Regional Council and copied to the Peer Review Panel as part of annual reporting as required under Condition SC5.O.15.</li> </ol>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |
|           | <b>Area 5 Rock Storage Monitoring and Management Plan</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |
| SC5.O.12. | <ol style="list-style-type: none"> <li>No later than 30 working days prior to the deposition of ore or any potentially acid forming (PAF) waste rock at any Rock Storage Area, the Consent Holder must submit an Area 5 Rock Storage Monitoring and Management Plan for written certification under Condition C5 of Schedule One:</li> <li>Certification is required to verify that the Area 5 Rock Storage Monitoring and Management Plan: <ol style="list-style-type: none"> <li>Includes actions, methods, monitoring programmes and trigger levels as appropriate to meet the objectives in Condition SC5.O.13; and</li> <li>Satisfies the requirements in Condition SC5.O.14.</li> </ol> </li> <li>The Area 5 Rock Storage Monitoring and Management Plan need not be a standalone document, and the Consent Holder may, at its discretion, include it as part of any other management plan required by the conditions of this consent.</li> </ol> <p><i>Advice Note: The Area 5 Rock Storage Monitoring and Management Plan is applicable to rock storage provisions relating to the activities covered by this consent only, and does not apply to any of the Consent Holder's existing rock storage provisions which happen to be located within the boundaries of Area 5.</i></p> |
| SC5.O.13. | The objectives of the Area 5 Rock Storage Monitoring and Management Plan are to set out the details of:                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |

## Conditions for the Waikato Regional Council Consents

|           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |
|-----------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|           | <ol style="list-style-type: none"> <li>a. The monitoring that will be undertaken to ensure that the Waihi Surface Facilities Area Rock Storage does not adversely affect land, ground and groundwater; and</li> <li>b. The contingency measures necessary to ensure the conditions of this consent are achieved.</li> </ol>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
| SC5.O.14. | <ol style="list-style-type: none"> <li>1. The Area 5 Rock Storage Monitoring and Management Plan must include, as a minimum: <ol style="list-style-type: none"> <li>a. The details of the monitoring bores installed in accordance with Condition SC5.O.7;</li> <li>b. Details of monitoring to be undertaken in accordance with Condition SC5.O.8;</li> <li>c. The trigger levels set in accordance with Condition SC5.O.9;</li> <li>d. A contingency plan to be actioned in the event a trigger level is exceeded over two consecutive readings, and which is sufficient to assess the source of the exceedance, and to determine what, if any, mitigation measures should be implemented to ensure that General Condition G18 is complied with;</li> <li>e. Details of the waste rock classification to be used.</li> </ol> </li> <li>2. In detailing the monitoring programmes the Consent Holder must provide information on the monitoring methods proposed, the monitoring locations, parameters to be monitored, and the required calibration and maintenance of monitoring equipment.</li> </ol>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |
|           | <b>Area 5 Rock Storage Monitoring Report</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |
| SC5.O.15. | <ol style="list-style-type: none"> <li>1. The Consent Holder must submit an annual Area 5 Rock Storage Monitoring report to the Waikato Regional Council. The report must, as a minimum include: <ol style="list-style-type: none"> <li>a. The data from monitoring undertaken during the previous year;</li> <li>b. Identification of any environmentally important trends associated with the above monitoring;</li> <li>c. Interpretation and analysis of any change in groundwater chemistry over the previous year and predictions of any future changes in groundwater chemistry and what contingency actions, if any, it proposes to take in response to these predictions;</li> <li>d. Any contingency actions that may have been taken during the previous year;</li> <li>e. Commentary on compliance with all conditions and any reasons for non-compliance or difficulty in achieving conformance with the conditions of this consent;</li> <li>f. A summary and analysis of complaints relevant to this consent, from the complaint log (refer Schedule One); and</li> <li>g. Any works that have been undertaken to improve environmental performance or that are proposed to be undertaken in the forthcoming year to improve environmental performance in relation to activities permitted by this consent.</li> </ol> </li> <li>2. The report must be forwarded in a format acceptable to the Waikato Regional Council.</li> <li>3. The Waihi Surface Facilities Area Rock Storage Monitoring Report need not be a standalone document and the Consent Holder may, at its discretion, include it as part of any other monitoring report required by the conditions of this consent.</li> </ol> |

## **Conditions for the Waikato Regional Council Consents**

### **AREA 6 SPECIFIC CONSENTS**

## Conditions for the Waikato Regional Council Consents

|                                           |                                                                   |
|-------------------------------------------|-------------------------------------------------------------------|
| RESOURCE CONSENT                          | AUTH144654.37.01                                                  |
| CONSENT TYPE AND<br>ACTIVITIES AUTHORISED | RMA S14 To take groundwater for construction dewatering purposes. |
| LOCATION                                  | Area 6                                                            |
| TERM                                      | 35 years                                                          |
| LAPSE PERIOD                              | 10 years                                                          |

|         |                                                                                                                                                                                                                                    |
|---------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|         | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                          |
| SC6.A.1 | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent. |
|         | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                      |
| SC6.A.2 | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                               |

## Conditions for the Waikato Regional Council Consents

|                                        |                                                                                                                                                                                                                                            |
|----------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                       | AUTH144654.38.01                                                                                                                                                                                                                           |
| CONSENT TYPE AND ACTIVITIES AUTHORISED | RMA S13 To disturb and reclaim the bed of TB1 Stream and unnamed tributaries of TB1 Stream associated with establishing diversion drains, and for placing sediment retention ponds and culverts for erosion and sediment control purposes. |
| LOCATION                               | Area 6                                                                                                                                                                                                                                     |
| TERM                                   | 35 years                                                                                                                                                                                                                                   |
| LAPSE PERIOD                           | 10 years                                                                                                                                                                                                                                   |

|         |                                                                                                                                                                                                                                    |
|---------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|         | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                          |
| SC6.B.1 | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent. |
|         | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                      |
| SC6.B.2 | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                               |

## Conditions for the Waikato Regional Council Consents

|                                           |                                                                                                                                  |
|-------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                          | AUTH144654.39.01                                                                                                                 |
| CONSENT TYPE AND<br>ACTIVITIES AUTHORISED | RMA S14 To dam and divert water for erosion and sediment control purposes using clean water and dirty water drains and culverts. |
| LOCATION                                  | Area 6                                                                                                                           |
| TERM                                      | 35 years                                                                                                                         |
| LAPSE PERIOD                              | 10 years                                                                                                                         |

|         |                                                                                                                                                                                                                                    |
|---------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|         | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                          |
| SC6.C.1 | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent. |
|         | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                      |
| SC6.C.2 | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                               |

## Conditions for the Waikato Regional Council Consents

|                                           |                                                                                                                                                                                                                                            |
|-------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                          | AUTH144654.40.01                                                                                                                                                                                                                           |
| CONSENT TYPE AND<br>ACTIVITIES AUTHORISED | <p>RMA S9 To drill drain holes in the wall of the Western Borrow Area to depressurise the pit wall.</p> <p>RMA S14 To take water to dewater the Western Borrow Area using pit wall drain holes and divert to sediment collection ponds</p> |
| LOCATION                                  | Area 6                                                                                                                                                                                                                                     |
| TERM                                      | 35 years                                                                                                                                                                                                                                   |
| LAPSE PERIOD                              | 10 years                                                                                                                                                                                                                                   |

|         |                                                                                                                                                                                                                                    |
|---------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|         | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                          |
| SC6.D.1 | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent. |
|         | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                      |
| SC6.D.2 | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                               |

## Conditions for the Waikato Regional Council Consents

|                                           |                                                                                                                                         |
|-------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                          | AUTH144654.41.01                                                                                                                        |
| CONSENT TYPE AND<br>ACTIVITIES AUTHORISED | RMA S15 To discharge water to land within the sediment retention ponds<br>and decanting earth bunds and to surface water via spillways. |
| LOCATION                                  | Area 6                                                                                                                                  |
| TERM                                      | 35 years                                                                                                                                |
| LAPSE PERIOD                              | 10 years                                                                                                                                |

|         |                                                                                                                                                                                                                                    |
|---------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|         | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                          |
| SC6.E.1 | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent. |
|         | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                      |
| SC6.E.2 | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                               |

## Conditions for the Waikato Regional Council Consents

|                                        |                                                                                                                                                                                                                                                                                                                                          |
|----------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                       | AUTH144654.42.01                                                                                                                                                                                                                                                                                                                         |
| CONSENT TYPE AND ACTIVITIES AUTHORISED | <p>RMA S13 To disturb, reclaim and introduce plants in, on or over the bed of TB1 Stream to install the Northern Uphill Diversion Drain.</p> <p>RMA S14 To dam and divert TB1 Stream and natural surface runoff around disturbed areas, via the Northern Uphill Diversion Drain, and to discharge that diverted water to TB1 Stream.</p> |
| LOCATION                               | Area 6                                                                                                                                                                                                                                                                                                                                   |
| TERM                                   | 35 years                                                                                                                                                                                                                                                                                                                                 |
| LAPSE PERIOD                           | 10 years                                                                                                                                                                                                                                                                                                                                 |

|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |
|---------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|         | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                                                                                                                                                                                                                                                                     |
| SC6.F.1 | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent.                                                                                                                                                                                                                                            |
|         | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                                                                                                                                                                                                                                                                 |
| SC6.F.2 | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                                                                                                                                                                                                                                                                          |
|         | <b>Design and Construction Requirements</b>                                                                                                                                                                                                                                                                                                                                                                                                                                   |
| SC6.F.3 | The Northern Uphill Diversion Drain must be constructed in accordance with the design outlined in the document titled “ <i>OceanaGold (New Zealand) Limited –Waihi North Project -Tailings Storage and Rock Disposal Volume 4 –Northern Rock StackRL173-Proposed Rock Disposal Facility – Technical Report</i> ’ included in Part B of the application documents.                                                                                                             |
| SC6.F.4 | <p>Diversion drains and associated works must:</p> <ol style="list-style-type: none"> <li>For sections of the diversion drains which are only required during construction, be constructed and operated to convey the run-off resulting from a 10% Annual Exceedance Probability; and</li> <li>For sections of the diversion drains that are to be permanent, be constructed and operated to convey the run-off resulting from a 1% Annual Exceedance Probability.</li> </ol> |
| SC6.F.5 | All construction works must be implemented under the supervision of appropriately qualified and experienced persons.                                                                                                                                                                                                                                                                                                                                                          |

## Conditions for the Waikato Regional Council Consents

|         |                                                                                                                                                                                                                                             |
|---------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| SC6.F.6 | The Consent Holder must advise Waikato Regional Council in writing in advance of the proposed construction of each of the diversion drains, and must provide plans of the proposed works, and advise proposed start times for construction. |
| SC6.F.7 | Within 20 working days following completion of each diversion, the Consent Holder must provide Waikato Regional Council with as-built plans of the completed works.                                                                         |

## Conditions for the Waikato Regional Council Consents

|                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |
|-------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                          | AUTH144654.43.01                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |
| CONSENT TYPE AND<br>ACTIVITIES AUTHORISED | <p>RMA S13 To reclaim the bed of TB1 Stream and unnamed tributaries of TB1 Stream in association with the establishment of the Western Borrow Area, Northern Rock Stack, and adjacent haul roads, perimeter roads and perimeter drains.</p> <p>RMA S15 To discharge contaminants to land associated with the storage and use of overburden (including potentially acid forming material).</p> <p>RMA S15 To discharge contaminants from seepage water from the Northern Rock Stack to ground</p> <p>RMA S14 To divert intercepted groundwater and underdrain seepage water to the Water Treatment Plant using a subsurface drainage system, leachate drainage system and perimeter ring system of sumps and pipes.</p> <p>RMA S14 To divert runoff from within the Northern Rock Stack footprint to the Northern Rock Stack Collection Pond, and from there, to the Water Treatment Plant.</p> |
| LOCATION                                  | Area 6                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |
| TERM                                      | 35 years                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |
| LAPSE PERIOD                              | 10 years                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |

|         |                                                                                                                                                                                                                                    |
|---------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|         | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                          |
| SC6.G.1 | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent. |
|         | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                      |
| SC6.G.2 | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                               |
|         | <b>Design Requirements</b>                                                                                                                                                                                                         |
| SC6.G.3 | The Northern Rock Stack, including the Western Borrow Area, must be wholly located within the footprint shown in the figure annexed as <b>Attachment 1</b> to this consent.                                                        |
| SC6.G.4 | The Northern Rock Stack stockpile crest must not exceed a height of 173 metres RL (Mine Datum less 1000 metres).                                                                                                                   |

## Conditions for the Waikato Regional Council Consents

|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |
|----------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| SC6.G.5  | The Western Borrow Area floor level must not be below 113 metres RL (Mine Datum less 1000 metres).                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |
| SC6.G.6  | The Northern Rock Stack must be constructed in accordance with the design outlined in the document titled “ <i>OceanaGold (New Zealand) Limited –Waihi North Project -Tailings Storage and Rock Disposal Volume 4 –Northern Rock StackRL173-Proposed Rock Disposal Facility– Technical Report</i> ” included in Part B of the application documents.                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |
| SC6.G.7  | <ol style="list-style-type: none"> <li>The Consent Holder must ensure the entire footprint of the Northern Rock Stack is underlain by a low permeability liner which provides for secure long-term containment and which: <ol style="list-style-type: none"> <li>Has no acid forming potential;</li> <li>Has a permeability no greater than <math>1 \times 10^{-8}</math> m/s; and</li> <li>If constructed of natural materials, has a minimum thickness of 750 mm, or, if constructed wholly or partly from synthetic materials provide protection against damage or penetration of the liner during construction and operation.</li> </ol> </li> <li>The Consent Holder must line all leachate drains with a 3 m wide 1.5 mm HDPE (or other similar synthetic liner approved by the Waikato Regional Council).</li> </ol> |
| SC6.G.8  | <p>The Consent Holder must ensure all perimeter drains are constructed from materials which provide for secure long-term containment and which:</p> <ol style="list-style-type: none"> <li>Have no acid forming potential; and</li> <li>Are lined with 1.5 mm HDPE (or other similar synthetic liner approved by the Waikato Regional Council) to a height of 0.3 m from the base, and with a 0.5 m protective cover layer.</li> </ol>                                                                                                                                                                                                                                                                                                                                                                                      |
| SC6.G.9  | <ol style="list-style-type: none"> <li>The Consent Holder must ensure that any potentially acid forming (PAF) material stored outside the footprint of the Northern Rock Stack, and which is intended for disposal into the Northern Rock Stack, is only stored on a pad that is constructed from, or lined with, at least 600 mm of natural, non-acid forming materials with a permeability of no greater than <math>1 \times 10^{-8}</math> m/s.</li> <li>The pads must be constructed to direct any seepage to a point from where it can be monitored, and, if necessary, directed to the Water Treatment Plant for treatment prior to discharge.</li> </ol>                                                                                                                                                             |
| SC6.G.10 | The Consent Holder must install an underdrainage system beneath the Northern Rock Stack to collect contaminated seepage from any stockpiled PAF material.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |
| SC6.G.11 | The Consent Holder must ensure that this underdrainage system is in place prior to the placement of any PAF material in the Northern Rock Stack.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |
| SC6.G.12 | <ol style="list-style-type: none"> <li>Until final capping is complete, the Consent Holder must ensure that the pH of a slurry of one part solid (less than 4 mm size fraction) to two parts deionised water, on the surface of any exposed PAF rock (after liming) remains greater than or equal to pH 5.5.</li> <li>Unless Waikato Regional Council agrees to an alternative sampling programme in writing, slurry samples must be collected on a grid pattern of not more than 50 metres and, where</li> </ol>                                                                                                                                                                                                                                                                                                           |

## Conditions for the Waikato Regional Council Consents

|                |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |
|----------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|                | <p>practical, within 1 week of placement of any PAF rock and then at intervals not exceeding 4 weeks.</p> <p><i>Advice Note: This test is designed to manage the potential for acid generation and sulphate release from waste rock. The procedure for collecting and analysing the samples must be as described in the Northern Rock Stack Monitoring and Management Plan.</i></p>                                                                                                                                                                                                                                                                                             |
| SC6.G.13       | The Consent Holder must collect all underdrainage flow from the Northern Rock Stack and divert it to the Water Treatment Plant for treatment or for use in the Processing Plant.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |
| SC6.G.14       | The Consent Holder must provide the Peer Review Panel with all records, plans, designs, monitoring reports and any other information they request to assist with their advisory role and must provide the Panel full access to the site at all reasonable times.                                                                                                                                                                                                                                                                                                                                                                                                                |
| SC6.G.15       | <ol style="list-style-type: none"> <li>1. All aspects of the design of the Northern Rock Stack must be supervised by an appropriately qualified and experienced person or persons (the Designer).</li> <li>2. Prior to the placement of any PAF rock in the Northern Rock Stack, the Consent Holder must provide to Waikato Regional Council written confirmation from the Designer that all aspects of the foundations, low permeability liner, underdrainage system, and surface water drainage system have been investigated and designed in accordance with accepted engineering best practise, and be effective in controlling acid and metalliferous drainage.</li> </ol> |
| SC6.G.16       | <ol style="list-style-type: none"> <li>1 The Consent Holder must supply the following documentation to the Waikato Regional Council prior to commencement of the Northern Rock Stack construction works: <ol style="list-style-type: none"> <li>a. Detailed Design Report</li> <li>c. Design Drawings</li> <li>d. Construction Monitoring Inspection Schedule</li> </ol> </li> <li>2 All subsequent amendments to the design must be supplied to the Waikato Regional Council prior to implementation and following peer review by an appropriately qualified and experienced person or persons.</li> </ol>                                                                     |
| SC6.G.16.<br>A | All detailed design reporting must include seismic design analyses in accordance with National Seismic Hazard Model (2022).                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |
| SC6.G.17       | <ol style="list-style-type: none"> <li>1. All construction works associated with the Northern Rock Stack must be implemented under the supervision of appropriately qualified and experienced persons.</li> <li>2. The Consent Holder must supply to Waikato Regional Council a full set of as-built plans for the foundations, low permeability liner, underdrainage system, and surface water drainage system of the rock stack development.</li> </ol>                                                                                                                                                                                                                       |
| SC6.G.18       | The Consent Holder must maintain the structural integrity of the works associated with the exercise of these consents and of any erosion control and energy dissipation works that become necessary as a consequence of the exercise of these consents.                                                                                                                                                                                                                                                                                                                                                                                                                         |

## Conditions for the Waikato Regional Council Consents

|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |
|----------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| SC6.G.19 | <ol style="list-style-type: none"> <li>1 On completion of the foundations, low permeability liner, underdrainage system, and surface water drainage system construction works the Consent Holder must supply written confirmation to the Waikato Regional Council and the Peer Review Panel that the foundations, low permeability liner, underdrainage system, and surface water drainage system works of the relevant stage have been constructed in accordance with the design referred to in Condition SC6.G.16.</li> <li>2 Thereafter, the facility must be inspected by an appropriately qualified and experienced person on an annual basis, and a written report on the inspection provided to Waikato Regional Council and copied to the Peer Review Panel within one month of completion of the inspection.</li> </ol>               |
|          | <b>Monitoring</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |
| SC6.G.20 | <ol style="list-style-type: none"> <li>1. Throughout the period of mining the Consent Holder must establish and maintain an inventory of sources and estimated volumes of available inert material. This inventory is to be updated at six monthly intervals and balanced against estimated future demand for inert material. The inventory must be available upon request to Waikato Regional Council and the Peer Review Panel.</li> <li>2. In the event a shortfall of inert material occurs or is identified in advance, the Consent Holder must prepare and implement contingency measures to ensure that the control of geochemically active materials is maintained.</li> <li>3. A summary of the inventory and details of any measures which have needed to be taken must be reported annually to Waikato Regional Council.</li> </ol> |
| SC6.G.21 | <ol style="list-style-type: none"> <li>1. The Consent Holder must install groundwater quality monitoring bores to detect seepage escaping the underdrainage system, and to determine the representative groundwater quality for shallow and deeper groundwater around the perimeter of land downstream of the Northern Rock Stack owned by the Consent Holder. This is to include installation of groundwater quality monitoring bores between the Northern Rock Stack and the Ohinemuri River (to the northwest and west of the Northern Rock Stack).</li> <li>2. The locations and specifications of the bores shall be to the satisfaction of the Waikato Regional Council.</li> </ol>                                                                                                                                                      |
| SC6.G.22 | <ol style="list-style-type: none"> <li>1. The Consent Holder must undertake baseline monitoring of groundwater monitoring bores at least monthly over a twelve month period, prior to the placing of PAF material within the Northern Rock Stack.</li> <li>2. Groundwater monitoring is to be undertaken using the methodology provided in the Northern Rock Stack Monitoring and Management Plan required by Condition SC6.G.27, and monitoring shall include the measurement of all parameters annexed as <b>Attachment 2</b> to this consent.</li> <li>3. The results of baseline monitoring must be forwarded to Waikato Regional Council at quarterly intervals.</li> </ol>                                                                                                                                                               |
| SC6.G.23 | The Consent Holder must calculate trigger levels for the parameters annexed as <b>Attachment 2</b> to this consent for down gradient bores based on the trends observed in the baseline monitoring                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |

## Conditions for the Waikato Regional Council Consents

|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |
|----------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|          | data required by Condition SC6.G.22 at levels which will provide an early warning of potential changes of groundwater quality as a result of the activities authorised by this consent. All trigger levels must be set at the 95 <sup>th</sup> percentile confidence limit.                                                                                                                                                                                                                                                                                                                                                                                                                                 |
| SC6.G.24 | <ol style="list-style-type: none"> <li>1. At any time following completion of baseline monitoring, if monitoring results within the monitoring bores exceed the relevant trigger level for that bore over two consecutive readings, then the Consent Holder must: <ol style="list-style-type: none"> <li>a. Characterise and assess the source of the exceedance ; and</li> <li>b. Take all necessary measures to ensure that General Condition G18 is complied with.</li> </ol> </li> <li>2. The trigger and actions taken must be reported to the Waikato Regional Council immediately on completion.</li> </ol>                                                                                          |
| SC6.G.25 | <ol style="list-style-type: none"> <li>1. Ongoing monitoring must be undertaken at the locations and using the methodology outlined in the Northern Rock Stack Monitoring and Management Plan required by Condition SC6.G.27, with monitoring to include the measurement of all parameters annexed as <b>Attachment 2</b> to this consent.</li> <li>2. Monitoring results must be provided to the Waikato Regional Council and copied to the Peer Review Panel as part of annual reporting as required under Condition SC6.G.33.</li> </ol>                                                                                                                                                                 |
| SC6.G.26 | <p>The Consent Holder must classify waste rock in a manner to be set out in the Northern Rock Stack Monitoring and Management Plan required by Condition SC6.G.27 that, as a minimum, includes:</p> <ol style="list-style-type: none"> <li>a. Definitions used to characterise waste rock embankments in terms of acid base accounting;</li> <li>b. Criteria used for classifying waste rock;</li> <li>c. An assessment protocol for classifying waste rock;</li> <li>d. Waste rock sampling requirements during construction and rehabilitation of the Northern Rock Stack; and</li> <li>e. Requirements for limestone addition for any potentially acid forming rock placed within stockpiles.</li> </ol> |
|          | <b>Northern Rock Stack Monitoring and Management Plan</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |
| SC6.G.27 | <ol style="list-style-type: none"> <li>1. No later than 30 working days prior to the commencement of works to establish the Northern Rock Stack, the Consent Holder must submit to the Waikato Regional Council a Northern Rock Stack Monitoring and Management Plan for written certification under Condition C5 of Schedule One that : <ol style="list-style-type: none"> <li>a. Includes performance measures, triggers, actions, methods and monitoring programmes designed to achieve the objective in Condition SC6.G.28; and</li> <li>b. Satisfies the requirements in Condition SC6.G.29.</li> </ol> </li> </ol>                                                                                    |

## Conditions for the Waikato Regional Council Consents

|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |
|----------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|          | <p>2. The Northern Rock Stack Monitoring and Management Plan need not be a standalone document, and the Consent Holder may at its discretion include it as part of any other management plan required by the conditions of this consent.</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |
| SC6.G.28 | <p>The objective of the Northern Rock Stack Monitoring and Management Plan is to set out the details of:</p> <ul style="list-style-type: none"> <li>a. The monitoring that will be undertaken to ensure that the Northern Rock Stack does not adversely affect land, ground and groundwater resources; and</li> <li>b. The contingency measures necessary to ensure the conditions of this consent are achieved.</li> </ul>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
| SC6.G.29 | <p>1. The Northern Rock Stack Monitoring and Management Plan must include, as a minimum:</p> <ul style="list-style-type: none"> <li>a. A Risk Management Plan, as defined in the Australian/New Zealand Standards for Risk Management (AS/NZS 4360:1999) or any subsequent replacement standard that: <ul style="list-style-type: none"> <li>i. Identifies and assesses the operational risks relating to Northern Rock Stack;</li> <li>ii. Develops an appropriate monitoring programme; and</li> <li>iii. Sets out the actions to be taken in the event that monitoring in accordance with ii above indicates a material increase in the risks identified in i above.</li> </ul> </li> <li>b. A structural integrity monitoring programme for the embankment of Northern Rock Stack;</li> <li>c. Monitoring systems and the measures to be adopted to ensure compliance with General Condition G18, including: <ul style="list-style-type: none"> <li>i. The details of the monitoring bores to be established in accordance with Condition SC6.G.21;</li> <li>ii. Details of the monitoring in accordance with Condition SC6.G.22;</li> <li>iii. The trigger levels set in accordance with Condition SC6.G.23;</li> <li>iv. The measurement and monitoring of the liner and cover system integrity (by measuring drainage quality and flow from all underdrainage and surface collection systems) in order to verify the "as built" structure is achieving predicted design performance objectives; and</li> </ul> </li> <li>d. Details of the waste rock classification to be used in accordance with Condition SC6.C.26.</li> <li>e. Details of monitoring measures that will be adopted to validate design criteria and confirm that oxygen is excluded beyond 8m of the edge of the Rock Stack.</li> </ul> <p>2. In detailing the monitoring programmes the Consent Holder must provide information on the monitoring methods proposed, the monitoring locations, parameters to be monitored, and the required calibration and maintenance of monitoring equipment.</p> |
| SC6.G.30 | <p>Construction works must not commence until the Consent Holder has received written certification from the Waikato Regional Council of the Northern Rock Stack Monitoring and Management Plan.</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |

## Conditions for the Waikato Regional Council Consents

|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |
|----------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| SC6.G.31 | <ol style="list-style-type: none"> <li>1. The Northern Rock Stack Monitoring and Management Plan must be reviewed and updated (as necessary) by the Consent Holder at least annually.</li> <li>2. Any updated version of the Northern Rock Stack Monitoring and Management Plan must not be implemented until the updated Northern Rock Stack Monitoring and Management Plan has been recertified by the Waikato Regional Council.</li> </ol>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |
| SC6.G.32 | The Consent Holder must implement the certified Northern Rock Stack Monitoring and Management Plan.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |
|          | <b>Northern Rock Stack Monitoring Report</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |
| SC6.G.33 | <ol style="list-style-type: none"> <li>1. The Consent Holder must submit an annual Northern Rock Stack Monitoring Report to the Waikato Regional Council. The report must, as a minimum, contain: <ol style="list-style-type: none"> <li>a. The data from monitoring undertaken during the previous year;</li> <li>b. Identification of any environmentally important trends associated with the above monitoring;</li> <li>c. Interpretation and analysis of any change in groundwater chemistry over the previous year and predictions of any future changes in groundwater chemistry and identification of what contingency actions, if any, are proposed to be taken in response to these predictions;</li> <li>d. Any contingency actions that may have been taken during the year;</li> <li>e. Comment on compliance with all conditions of this consent and any reasons for non-compliance or difficulty in achieving conformance with the conditions of this consent;</li> <li>f. A summary and analysis of complaints relevant to this consent, from the complaint log (refer Schedule One); and</li> <li>g. Any works that have been undertaken to improve environmental performance or that are proposed to be undertaken in the forthcoming year to improve environmental performance in relation to activities permitted by this consent.</li> </ol> </li> <li>2. The report must be forwarded in a format acceptable to the Waikato Regional Council.</li> <li>3. The Northern Rock Stack Monitoring Report need not be a standalone document, and the Consent Holder may, at its discretion, include it as part of any other monitoring report required by the conditions of this consent.</li> </ol> |
|          | <b>Technical Review</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |
| SC6.G.34 | <ol style="list-style-type: none"> <li>1. The design and construction of all works covered by this consent must be peer reviewed by an appropriately qualified and experienced person or persons.</li> <li>2. The person or persons must be instructed by the Consent Holder to report in writing to the Waikato Regional Council at least at the following times: <ol style="list-style-type: none"> <li>a. prior to commencement of construction of Northern Rock Stack;</li> </ol> </li> </ol>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |

## Conditions for the Waikato Regional Council Consents

|  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |
|--|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|  | <ul style="list-style-type: none"><li>b. at all critical stages during the ongoing design and construction of Northern Rock Stack but not less than annually;</li><li>c. on the completion of the Northern Rock Stack;</li><li>d. following any significant design changes; and</li><li>e. prior to commencement of approved post closure discharge to the Ohinemuri River from the Northern Rock Stack collection pond,</li></ul> <p>3. The person or persons must be instructed by the Consent Holder to address at least the following matters:</p> <ul style="list-style-type: none"><li>a. progress against the Annual Work Programme;</li><li>b. site preparation including hydrogeological issues and geotechnical issues;</li><li>c. foundation design and use of on-site material;</li><li>d. foundation design and construction;</li><li>e. all underdrainage systems;</li><li>f. stockpile management;</li><li>g. monitoring; and</li><li>h. rehabilitation and closure plans associated with the Northern Rock Stack.</li></ul> <p>4. The reports required by this condition must also be provided to the Peer Review Panel for their consideration in an advisory capacity only with regard to the progression of works.</p> |
|--|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

## Conditions for the Waikato Regional Council Consents

|                                        |                                                                                                                                                                                                                                                                                                                                                           |
|----------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                       | AUTH144654.44.01                                                                                                                                                                                                                                                                                                                                          |
| CONSENT TYPE AND ACTIVITIES AUTHORISED | <p>RMA S14 To dam water within the Northern Rock Stack Collection Pond</p> <p>RMA S13 To erect an overflow spillway from the Northern Rock Stack Collection Pond in, on and over the bed of a tributary of TB1 Stream</p> <p>RMA S15 To discharge water to surface water from the Northern Rock Stack Collection Pond spillway to the Ohinemuri River</p> |
| LOCATION                               | Area 6                                                                                                                                                                                                                                                                                                                                                    |
| TERM                                   | 35 years                                                                                                                                                                                                                                                                                                                                                  |
| LAPSE PERIOD                           | 10 years                                                                                                                                                                                                                                                                                                                                                  |

|         |                                                                                                                                                                                                                                                                                                                                                                      |
|---------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|         | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                                                                                                                                                            |
| SC6.H.1 | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent.                                                                                                                                   |
|         | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                                                                                                                                                        |
| SC6.H.2 | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                                                                                                                                                                 |
|         | <b>Design and Construction</b>                                                                                                                                                                                                                                                                                                                                       |
| SC6.H.3 | The Northern Rock Stack Collection Pond must be constructed in accordance with the design outlined in the document titled “ <i>OceanaGold (New Zealand) Limited –Waihi North Project - Tailings Storage and Rock Disposal Volume 4 –Northern Rock StackRL173-Proposed Rock Disposal Facility–Technical Report</i> ” included in Part B of the application documents. |
| SC6.H.4 | The capacity of Northern Rock Stack Collection Pond must be constructed and operated to contain the run-off generated from within its catchment during a 72-hour duration rainfall event with an Annual Exceedance Probability (AEP) of less than 10%, taking into account a combination of both storage volume and pumping rate.                                    |
| SC6.H.5 | Except as provided for by Condition SC6.H.6 for 72 hour duration rainfall events with an AEP greater than 10%, all stormwater reporting to the Northern Rock Stack Collection Pond must be pumped to the Water Treatment Plant for treatment.                                                                                                                        |
| SC6.H.6 | If the Consent Holder can demonstrate that the quality of water entering the Northern Rock Stack Collection Pond:                                                                                                                                                                                                                                                    |

## Conditions for the Waikato Regional Council Consents

|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |
|----------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|          | <p>a. Meets or is better than the receiving water criteria defined in Condition G18;</p> <p>b. Is capable of remaining so on an ongoing basis; and,</p> <p>c. In combination with all other discharges authorised for this site, does not cause a significant adverse effect on the receiving groundwater and surface water, or on users of these resources, or, in the case of surface water, aquatic biota,</p> <p>then the Consent Holder may, if approved by the Waikato Regional Council in writing discharge directly from the pond, provided that:</p> <p>d. The Consent Holder continuously monitors pH and turbidity in the pond; and</p> <p>e. For rainfall events with an AEP greater than 50%, discharges from the pond</p> <p>i. have a turbidity of no greater than 110 NTU; and</p> <p>ii. has a pH within the range of 6.0-9.0 pH units.</p> |
| SC6.H.7  | The Northern Rock Stack Collection Pond must be provided with a spillway that will safely route a 1% AEP flood.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |
| SC6.H.8  | <p>The Consent Holder must ensure that the Northern Rock Stack Collection Pond is:</p> <p>a. Constructed from materials which provide for secure long term containment; and</p> <p>b. Constructed using materials which have no acid forming potential; and</p> <p>c. Lined with 1.5mm HDPE with a 0.5m protective cover layer (or other similar synthetic liner approved by the Waikato Regional Council) to a height of 1.5m from the base, and with a 0.5m protective layer cover.</p>                                                                                                                                                                                                                                                                                                                                                                    |
| SC6.H.9  | All construction works must be implemented under the supervision of appropriately qualified and experienced persons.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |
| SC6.H.10 | The Consent Holder must maintain the structural integrity of the works associated with the exercise of these consents and of any erosion control and energy dissipation works which become necessary as a consequence of the exercise of these consents.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |
| SC6.H.11 | <p>1 On completion of the construction works the Consent Holder must supply written confirmation to the Waikato Regional Council and the Peer Review Panel stating that the Northern Rock Stack Collection Pond has been constructed in accordance with the design parameters referred to in Condition SC6.H.8.</p> <p>2 Thereafter, the facility must be inspected by a registered engineer on an annual basis, and a written report on the inspection provided to the Waikato Regional Council and copied to the Peer Review Panel within one month of completion of the inspection.</p>                                                                                                                                                                                                                                                                   |
| SC6.H.12 | Routine maintenance and desilting of the Northern Rock Stack Collection Pond must only occur during periods of projected fine weather. All silt removed must be disposed of to a tailings storage facility.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |
| SC6.H.13 | No chemicals or additives may be used in the Northern Rock Stack Collection Pond or the discharge from the pond without the prior written approval of the Waikato Regional Council.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |

## Conditions for the Waikato Regional Council Consents

|                                                                                                                                        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |                                                                                               |    |              |                  |               |                                                                                                                                        |
|----------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------|----|--------------|------------------|---------------|----------------------------------------------------------------------------------------------------------------------------------------|
|                                                                                                                                        | <b>Discharges and Monitoring</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                                                                                               |    |              |                  |               |                                                                                                                                        |
| SC6.H.14                                                                                                                               | <p>Except where Condition SC6.H.6(e) applies the Consent Holder must monitor the discharge from the Northern Rock Stack Collection Pond every day during any overflow event in accordance with Table SC6.H.14.T1:</p> <table><tr><td><b>Table SC6.H.14.T1 – Northern Rock Stack Collection Pond Overflow Monitoring Parameters</b></td></tr><tr><td>pH</td></tr><tr><td>Conductivity</td></tr><tr><td>Suspended solids</td></tr><tr><td>Total ammonia</td></tr><tr><td>Trace elements, (iron, manganese, copper, nickel, zinc, silver, antimony, arsenic, selenium, cadmium, chromium (iv), lead and mercury.</td></tr></table> <p><i>Table Note:</i></p> <p><i>The Northern Rock Stack Collection Pond overflow monitoring programme for metals is for ‘acid-soluble’ concentrations determined on unfiltered samples.</i></p> | <b>Table SC6.H.14.T1 – Northern Rock Stack Collection Pond Overflow Monitoring Parameters</b> | pH | Conductivity | Suspended solids | Total ammonia | Trace elements, (iron, manganese, copper, nickel, zinc, silver, antimony, arsenic, selenium, cadmium, chromium (iv), lead and mercury. |
| <b>Table SC6.H.14.T1 – Northern Rock Stack Collection Pond Overflow Monitoring Parameters</b>                                          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |                                                                                               |    |              |                  |               |                                                                                                                                        |
| pH                                                                                                                                     |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |                                                                                               |    |              |                  |               |                                                                                                                                        |
| Conductivity                                                                                                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |                                                                                               |    |              |                  |               |                                                                                                                                        |
| Suspended solids                                                                                                                       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |                                                                                               |    |              |                  |               |                                                                                                                                        |
| Total ammonia                                                                                                                          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |                                                                                               |    |              |                  |               |                                                                                                                                        |
| Trace elements, (iron, manganese, copper, nickel, zinc, silver, antimony, arsenic, selenium, cadmium, chromium (iv), lead and mercury. |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |                                                                                               |    |              |                  |               |                                                                                                                                        |
| SC6.H.15                                                                                                                               | Results of the monitoring undertaken in accordance with Condition SC6.H.14 must be forwarded to Waikato Regional Council quarterly.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |                                                                                               |    |              |                  |               |                                                                                                                                        |
| SC6.H.16                                                                                                                               | All water quality sampling and analysis must be undertaken using Standard Methods for the Examination of Water and Wastewater (19th Edition 1995, or updates), APHA, AWWA and WEF, unless otherwise agreed in writing by Waikato Regional Council. Analyses must be undertaken at an appropriately qualified laboratory. All other measuring, testing, recording and analytical methods as may be required from time to time pursuant to the requirements of this consent must be to the satisfaction of the Waikato Regional Council.                                                                                                                                                                                                                                                                                          |                                                                                               |    |              |                  |               |                                                                                                                                        |

## Conditions for the Waikato Regional Council Consents

|                                        |                                                                                                     |
|----------------------------------------|-----------------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                       | AUTH144654.45.01                                                                                    |
| CONSENT TYPE AND ACTIVITIES AUTHORISED | RMA S13 To alter and use existing culverts to enable widening of the access track across TB1 Stream |
|                                        | RMA S13 To place and use new culverts                                                               |
| LOCATION                               | Area 6                                                                                              |
| TERM                                   | 35 years                                                                                            |
| LAPSE PERIOD                           | 10 years                                                                                            |

|         |                                                                                                                                                                                                                                                                                                   |
|---------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|         | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                                                                                         |
| SC6.I.1 | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent.                                                                |
|         | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                                                                                     |
| SC6.I.2 | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                                                                                              |
|         | <b>Culvert Design</b>                                                                                                                                                                                                                                                                             |
| SC6.I.3 | All new culverts must be constructed and operated to convey the runoff resulting from at least a 5% Annual Exceedance Probability (AEP), 24-hour duration, design storm.                                                                                                                          |
| SC6.I.4 | Fish passage must be provided where temporary works on diversions and culverts have a duration exceeding 7 days.                                                                                                                                                                                  |
| SC6.I.5 | All culvert construction works must be implemented under the supervision of appropriately qualified and experienced persons.                                                                                                                                                                      |
| SC6.I.6 | The Consent Holder must ensure that the area of disturbance during placement/construction of all culverts is kept to a practical minimum.                                                                                                                                                         |
| SC6.I.7 | Within 20 working days following completion of each culvert, the Consent Holder must provide the Waikato Regional Council with the information required under Regulations 62(3) and 63(3) of the Resource Management (National Environmental Standards for Freshwater) Regulations 2020 (“NESF”). |

## Conditions for the Waikato Regional Council Consents

|                                        |                                                                   |
|----------------------------------------|-------------------------------------------------------------------|
| RESOURCE CONSENT                       | AUTH144654.46.01                                                  |
| CONSENT TYPE AND ACTIVITIES AUTHORISED | RMA S15 To discharge overburden and ore on to land in stockpiles. |
| LOCATION                               | Area 6                                                            |
| TERM                                   | 35 years                                                          |
| LAPSE PERIOD                           | 10 years                                                          |

|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |
|----------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|          | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
| SC6.J.1. | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |
|          | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |
| SC6.J.2. | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |
|          | <b>Non-Acid Forming Material Stockpiles</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |
| SC6.J.3. | Preparation of stockpile sites for the temporary storage of non-acid forming (NAF) waste rock and soil prior to the placement of material must include: <ul style="list-style-type: none"> <li>a. Stripping and stockpiling of topsoil and subsoils for later use in site rehabilitation.</li> <li>b. Construction of clean water diversion drains around the site to divert and discharge clean surface run-off and intercepted groundwater.</li> <li>c. Construction of diversion drains around the site perimeter to divert stockpile run-off to silt ponds for sediment reduction prior to discharge.</li> </ul>                                                                                                                                                                                                         |
|          | <b>Potentially Acid Forming Material Stockpiles</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |
| SC6.J.4. | <ol style="list-style-type: none"> <li>1. Stockpiling of ore or any potentially acid forming (PAF) waste rock must occur only at sites specifically prepared for that purpose and must be constructed from or lined with at least 600mm of natural or non acid forming materials with a permeability of no greater than <math>1 \times 10^{-8}</math> m/s, or alternatively a synthetic liner with equivalent or better performance, approved by the Waikato Regional Council. In situ soils may be used for this purpose if the Consent Holder can demonstrate to the Waikato Regional Council's satisfaction that the protection provided is equivalent to the liner specification detailed above.</li> <li>2. In addition to the provisions of Condition SC6.J.3, PAF stockpile site preparation must include:</li> </ol> |

## Conditions for the Waikato Regional Council Consents

|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |
|----------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|          | <ul style="list-style-type: none"> <li>a. Grading of the proposed stockpile site and construction of stockpile drains around the site perimeter to divert stockpile run-off and leachate to a collection pond or ponds (from which collected water can be pumped to the Water Treatment Plant prior to discharge to the Ohinemuri River);</li> <li>b. Placement of selected, coarse waste rock as the initial layer on the low-permeability layer of the stockpile footprint to act as a leachate drainage layer. The perimeter of this drainage layer must be designed and constructed to prevent the ingress of oxygen into the stockpile; and</li> <li>c. If an alternative synthetic liner is used in preference to an earth liner, the synthetic liner must be covered with a protection layer consisting of soil that is placed and compacted to a minimum thickness of 400mm.</li> </ul>                                                                                                                                                                                                                              |
| SC6.J.5. | Drains constructed to convey run-off and leachate from the PAF stockpile(s) to the collection pond(s) and the Water Treatment Plant must be adequately sized and lined by a method agreed to by the Waikato Regional Council and detailed in the Water Management Plan prepared pursuant to Conditions G29 – G32.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |
| SC6.J.6. | <p>The Consent Holder must ensure that the collection pond(s) referred to in Condition SC6.J.4.2.a is designed and constructed from materials that provide secure long term containment including:</p> <ul style="list-style-type: none"> <li>a. A low-permeability liner forming the base and sides of the pond(s) that achieve the same or better standard to that required of the PAF stockpile liner as detailed in Condition SC6.J.4, or alternative liner with equivalent or better performance, approved by the Waikato Regional Council;</li> <li>b. A minimum water storage capacity equivalent to the volume of run-off generated from within its catchment during a 10% Annual Exceedance Probability (AEP), 72-hour duration, design storm, taking into account a combination of both storage volume and pumping rate;</li> <li>c. A pump system capable of pumping all stormwater reporting to the collection pond during rainfall events less than or equal to the above design storm to the water treatment plant for treatment; and</li> <li>d. A spillway that will safely route a 1% AEP flood.</li> </ul> |
|          | <b>Monitoring</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |
| SC6.J.7. | <p>The Consent Holder must maintain groundwater quality monitoring bores to detect any seepage bypassing the underdrainage system, and to determine the representative groundwater quality for shallow groundwater around the perimeter of land owned by the Consent Holder.</p> <p><i>Advice Note: All groundwater monitoring in these bores must be based on the soluble test method, defined as the concentration of dissolved metals measured in that fraction which passes through a 0.45 µm filter.</i></p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |
| SC6.J.8. | <ol style="list-style-type: none"> <li>1. The Consent Holder must undertake monitoring of the parameters annexed as <b>Attachment 1</b> to this consent in the bores maintained in accordance with Condition SC.J.7 in order to establish trends in the monitoring bores.</li> <li>2. Monitoring must continue throughout the term of these consents and the results of that monitoring must be forwarded to Waikato Regional Council at quarterly intervals.</li> </ol>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |

## Conditions for the Waikato Regional Council Consents

|           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |
|-----------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| SC6.J.9.  | The Consent Holder must set trigger levels for the parameters annexed as <b>Attachment 1</b> to this consent for down gradient bores based on the trends observed in the monitoring data at levels which will provide early warning indicator of potential changes of groundwater quality as a result of the activities authorised by this consent.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |
| SC6.J.10. | <ol style="list-style-type: none"> <li>1. If at any time monitoring results within the monitoring bores exceed the relevant trigger level for that bore over two consecutive readings then the Consent Holder must: <ol style="list-style-type: none"> <li>a. Characterise and assess the source of the exceedance; and</li> <li>b. Take all necessary measures to ensure that General Condition G18 is complied with.</li> </ol> </li> <li>2. The trigger level exceedance and measures taken must be detailed in the annual report to the Waikato Regional Council.</li> </ol>                                                                                                                                                                                                                                                                                                                                                                                                                                         |
|           | <b>Area 6 Stockpile Monitoring and Management Plan</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |
| SC6.J.11. | <ol style="list-style-type: none"> <li>1. The Consent Holder must submit an Area 6 Stockpile Monitoring and Management Plan for written certification under Condition C5 of Schedule One.</li> <li>2. Certification is required to verify that the Area 6 Stockpile Monitoring and Management Plan: <ol style="list-style-type: none"> <li>a. Includes actions, methods, monitoring programmes and trigger levels as appropriate to meet the objectives in Condition SC6.J.12; and</li> <li>b. Satisfies the requirements in Condition SC6.J.13.</li> </ol> </li> <li>3. The Area 6 Stockpile Monitoring and Management Plan need not be a standalone document, and the Consent Holder may, at its discretion, include it as part of any other management plan required by the conditions of this consent.</li> </ol>                                                                                                                                                                                                    |
| SC6.J.12. | <p>The objectives of the Area 6 Stockpile Monitoring and Management Plan are to set out the details of:</p> <ol style="list-style-type: none"> <li>a. The monitoring that will be undertaken to ensure that Area 6 stockpiles do not adversely affect land, ground and groundwater; and</li> <li>b. The contingency measures necessary to ensure the conditions of this consent are achieved.</li> </ol>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |
| SC6.J.13. | <ol style="list-style-type: none"> <li>1. The Area 6 Stockpile Monitoring and Management Plan must include, as a minimum: <ol style="list-style-type: none"> <li>a. The details of the monitoring bores installed in accordance with Condition SC6.J.7;</li> <li>b. Details of monitoring in accordance with Condition SC6.J.8;</li> <li>c. The trigger levels set in accordance with Condition SC6.J.9; and</li> <li>d. A contingency plan to be actioned in the event a trigger level is exceeded over two consecutive readings, and which is sufficient to assess the source of the exceedance, and to determine what, if any, mitigation measures should be implemented to ensure that General Condition G18 is complied with.</li> </ol> </li> <li>2. In detailing the monitoring programmes the Consent Holder must provide information on the monitoring methods proposed, the monitoring locations, parameters to be monitored, and the required calibration and maintenance of monitoring equipment.</li> </ol> |

## Conditions for the Waikato Regional Council Consents

|           | <b>Area 6 Stockpile Monitoring Report</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |
|-----------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| SC6.J.14. | <ol style="list-style-type: none"> <li>1. The Consent Holder must submit an annual Area 6 Stockpile Monitoring Report to the Waikato Regional Council. The report must, as a minimum include: <ol style="list-style-type: none"> <li>a. The data from monitoring undertaken during the previous year;</li> <li>b. Identification of any environmentally important trends associated with the above monitoring;</li> <li>c. Interpretation and analysis of any change in groundwater chemistry over the previous year and predictions of any future changes in groundwater chemistry and what contingency actions, if any, it proposes to take in response to these predictions;</li> <li>d. Any contingency actions that may have been taken during the previous year;</li> <li>e. Commentary on compliance with all conditions and any reasons for non-compliance or difficulty in achieving conformance with the conditions of this consent;</li> <li>f. A summary and analysis of complaints relevant to this consent, from the complaint log (refer Schedule One); and</li> <li>g. Any works that have been undertaken to improve environmental performance or that are proposed to be undertaken in the forthcoming year to improve environmental performance in relation to activities permitted by this consent.</li> </ol> </li> <li>2. The report must be forwarded in a format acceptable to the Waikato Regional Council.</li> <li>3. The Area 6 Stockpile Monitoring Report need not be a standalone document and the Consent Holder may, at its discretion, include it as part of any other monitoring report required by the conditions of this consent.</li> </ol> |

## **Conditions for the Waikato Regional Council Consents**

### **AREA 7 SPECIFIC CONSENTS**

#### **[TAILINGS STORAGE FACILITY 3]**

## Conditions for the Waikato Regional Council Consents

|                                           |                                                                   |
|-------------------------------------------|-------------------------------------------------------------------|
| RESOURCE CONSENT                          | AUTH144654.47.01                                                  |
| CONSENT TYPE AND<br>ACTIVITIES AUTHORISED | RMA S14 To take groundwater for construction dewatering purposes. |
| LOCATION                                  | Area 7                                                            |
| TERM                                      | 35 years                                                          |
| LAPSE PERIOD                              | 10 years                                                          |

|         |                                                                                                                                                                                                                                    |
|---------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|         | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                          |
| SC7.A.1 | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent. |
|         | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                      |
| SC7.A.2 | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                               |

## Conditions for the Waikato Regional Council Consents

|                                           |                                                                                                                                                                                          |
|-------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                          | AUTH144654.48.01                                                                                                                                                                         |
| CONSENT TYPE AND<br>ACTIVITIES AUTHORISED | RMA S13 To disturb and reclaim the bed of unnamed tributaries of Ruahorehore Stream associated with establishing clean and dirty water drains for erosion and sediment control purposes. |
| LOCATION                                  | Area 7                                                                                                                                                                                   |
| TERM                                      | 35 years                                                                                                                                                                                 |
| LAPSE PERIOD                              | 10 years                                                                                                                                                                                 |

|         |                                                                                                                                                                                                                                    |
|---------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|         | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                          |
| SC7.B.1 | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent. |
|         | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                      |
| SC7.B.2 | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                               |

## Conditions for the Waikato Regional Council Consents

|                                           |                                                                                                                            |
|-------------------------------------------|----------------------------------------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                          | AUTH144654.49.01                                                                                                           |
| CONSENT TYPE AND<br>ACTIVITIES AUTHORISED | RMA S14 To dam and divert water for erosion and sediment control purposes using clean water drains and dirty water drains. |
| LOCATION                                  | Area 7                                                                                                                     |
| TERM                                      | 35 years                                                                                                                   |
| LAPSE PERIOD                              | 10 years                                                                                                                   |

|         |                                                                                                                                                                                                                                    |
|---------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|         | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                          |
| SC7.C.1 | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent. |
|         | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                      |
| SC7.C.2 | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                               |

## Conditions for the Waikato Regional Council Consents

|                                           |                                                                                                                                                                                                                                                                         |
|-------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                          | AUTH144654.50.01                                                                                                                                                                                                                                                        |
| CONSENT TYPE AND<br>ACTIVITIES AUTHORISED | <p>RMA S9 To drill drain holes in the walls of the Central and Eastern Borrow Areas to depressurise the pit walls.</p> <p>RMA S14 To take water to dewater the Central and Eastern Borrow Areas using pit wall drain holes and divert to sediment collection ponds.</p> |
| LOCATION                                  | Area 7                                                                                                                                                                                                                                                                  |
| TERM                                      | 35 years                                                                                                                                                                                                                                                                |
| LAPSE PERIOD                              | 10 years                                                                                                                                                                                                                                                                |

|         |                                                                                                                                                                                                                                    |
|---------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|         | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                          |
| SC7.D.1 | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent. |
|         | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                      |
| SC7.D.2 | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                               |

## Conditions for the Waikato Regional Council Consents

|                                        |                                                                                                                                  |
|----------------------------------------|----------------------------------------------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                       | AUTH144654.51.01                                                                                                                 |
| CONSENT TYPE AND ACTIVITIES AUTHORISED | RMA S15 To discharge water to land within sediment retention ponds and decanting earth bunds and to surface water via spillways. |
| LOCATION                               | Area 7                                                                                                                           |
| TERM                                   | 35 years                                                                                                                         |
| LAPSE PERIOD                           | 10 years                                                                                                                         |

|         |                                                                                                                                                                                                                                    |
|---------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|         | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                          |
| SC7.E.1 | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent. |
|         | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                      |
| SC7.E.2 | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                               |

## Conditions for the Waikato Regional Council Consents

|                                        |                                                                                                                                                                                                                                                                                                                                                                          |
|----------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                       | AUTH144654.52.01                                                                                                                                                                                                                                                                                                                                                         |
| CONSENT TYPE AND ACTIVITIES AUTHORISED | <p>RMA S13 To disturb, reclaim and introduce plants in, on or over the bed of unnamed tributaries of the Ruahorehore Stream to install the Southern Uphill Diversion Drain.</p> <p>RMA S14 To dam and divert water within unnamed tributaries of the Ruahorehore Stream, and natural surface runoff, around disturbed areas, via the Southern Uphill Diversion Drain</p> |
| LOCATION                               | Area 7                                                                                                                                                                                                                                                                                                                                                                   |
| TERM                                   | 35 years                                                                                                                                                                                                                                                                                                                                                                 |
| LAPSE PERIOD                           | 10 years                                                                                                                                                                                                                                                                                                                                                                 |

|         |                                                                                                                                                                                                                                                                                                                                                                      |
|---------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|         | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                                                                                                                                                            |
| SC7.F.1 | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent.                                                                                                                                   |
|         | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                                                                                                                                                        |
| SC7.F.2 | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                                                                                                                                                                 |
|         | <b>Design and Construction Requirements</b>                                                                                                                                                                                                                                                                                                                          |
| SC7.F.3 | The Southern Uphill Diversion Drain must be constructed in accordance with the design outlined in the document titled “ <i>Oceana Gold (New Zealand) Limited –Waihi Operation, New Zealand– Tailings Storage and Rock Disposal Volume 3 –Proposed Tailings Storage Facility Storage 3 RL155 –Technical Report</i> ’ included in Part B of the application documents. |
| SC7.F.4 | Diversion drains and associated works must be constructed and operated to convey the run-off resulting from a 1% Annual Exceedance Probability.                                                                                                                                                                                                                      |
| SC7.F.5 | All construction works must be implemented under the supervision of appropriately qualified and experienced persons.                                                                                                                                                                                                                                                 |
| SC7.F.6 | The Consent Holder must advise Waikato Regional Council in writing in advance of the proposed construction of each of the diversion drains, and must provide plans of the proposed works, and advise proposed start times for construction.                                                                                                                          |
| SC7.F.7 | Within 20 working days following completion of each diversion, the Consent Holder must provide Waikato Regional Council with as-built plans of the completed works.                                                                                                                                                                                                  |

## Conditions for the Waikato Regional Council Consents

|                                           |                                                                                                                                                        |
|-------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                          | AUTH144654.53.01                                                                                                                                       |
| CONSENT TYPE AND<br>ACTIVITIES AUTHORISED | RMA S13 To disturb and reclaim the bed of unnamed tributaries of the Ruahorehore Stream within the footprint of TSF3 and Collection Ponds (S6 and S7). |
| LOCATION                                  | Area 7                                                                                                                                                 |
| TERM                                      | 35 years                                                                                                                                               |
| LAPSE PERIOD                              | 10 years                                                                                                                                               |

|         |                                                                                                                                                                                                                                    |
|---------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|         | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                          |
| SC7.G.1 | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent. |
|         | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                      |
| SC7.G.2 | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                               |

## Conditions for the Waikato Regional Council Consents

|                                        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |
|----------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                       | AUTH144654.54.01                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |
| CONSENT TYPE AND ACTIVITIES AUTHORISED | <p>RMA S14 To dam water in TSF3.</p> <p>RMA S14 To dam and divert runoff from within the TSF3 footprint to Collection Pond S7.</p> <p>RMA S14 To divert intercepted groundwater and subsurface drainage from TSF3 activities to treatment.</p> <p>RMA S15 To discharge overburden to land to construct, operate and rehabilitate TSF3 and the associated haul road and Collection Ponds.</p> <p>RMA S15 To discharge tailings into TSF3.</p> <p>RMA S15 To discharge seepage from TSF3 into the ground.</p> |
| LOCATION                               | Area 7                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |
| TERM                                   | 35 years                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
| LAPSE PERIOD                           | 10 years                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |

|         |                                                                                                                                                                                                                                    |
|---------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|         | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                          |
| SC7.H.1 | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent. |
|         | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                      |
| SC7.H.2 | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                               |
|         | <b>Design and Construction</b>                                                                                                                                                                                                     |
| SC7.H.3 | Tailings Storage Facility 3 including the Eastern and Central Borrow Areas must be wholly located within the footprint shown in the figure annexed as <b>Attachment 1</b> to this consent.                                         |
| SC7.H.4 | The TSF3 embankment crest must not exceed an elevation of 155 metres RL (Mine Datum less 1000 metres).                                                                                                                             |
| SC7.H.5 | The floor level of the Central and Eastern borrow areas must not be below 125 metres RL (Mine Datum less 1000 metres).                                                                                                             |

## Conditions for the Waikato Regional Council Consents

|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |
|----------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| SC7.H.6  | TSF3 must be constructed in accordance with the design outlined in the document titled <i>“Oceana Gold (New Zealand) Limited –Waihi Operation, New Zealand–Tailings Storage and Rock Disposal Volume 3 –Proposed Tailings Storage Facility 3 RL155 –Technical Report”</i> included in Part B of the application documents.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |
| SC7.H.7  | <ol style="list-style-type: none"> <li>The Consent Holder must ensure the entire footprint of the TSF3 embankment and tailing impoundment is underlain by a low permeability liner which provides for secure long term containment and which: <ol style="list-style-type: none"> <li>Has no acid forming potential;</li> <li>Has a permeability of no greater than <math>1 \times 10^{-8}</math> m/s; and,</li> <li>If constructed of natural materials, has a minimum thickness of 750 mm beneath the embankment and 600 mm beneath the impoundment, or, if constructed wholly or partly from synthetic materials the design must provide for protection against damage or penetration of the liner during construction and operation.</li> </ol> </li> <li>In addition, the Consent Holder must line all leachate drains with a 3 m wide 1.5 mm HDPE (or other similar synthetic liner approved by the Waikato Regional Council).</li> </ol>                                                                                                         |
| SC7.H.8  | <p>The Consent Holder must ensure all perimeter drains are constructed from materials which provide for secure long term containment and which:</p> <ol style="list-style-type: none"> <li>Have no acid forming potential; and</li> <li>Are lined with 1.5 mm HDPE (or other similar synthetic liner approved by the Waikato Regional Council) to a height of 0.3 m from the base, and with a 0.5 m protective cover layer.</li> </ol>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |
| SC7.H.9  | <ol style="list-style-type: none"> <li>The Consent Holder must ensure that any potentially acid forming (PAF) material stored outside the footprint of TSF3 embankment, and which is intended for disposal into TSF3 embankment, is only stored on a pad constructed in accordance with the requirements set out below.</li> <li>Any such pad must be constructed from or lined with at least 600 mm of natural, non-acid forming materials with a permeability of no greater than <math>1 \times 10^{-8}</math> m/s. The pads must be constructed to direct any seepage so that it reports to a point from where it can be monitored, and if necessary, directed to the Water Treatment Plant for treatment prior to discharge.</li> <li>Monitoring of the groundwater down-gradient of any such storage pad must be undertaken. That monitoring may form part of any monitoring programme already undertaken at the Site.</li> <li>The locations of any monitoring locations must be agreed in writing with the Waikato Regional Council.</li> </ol> |
| SC7.H.10 | The Consent Holder must install an underdrainage system beneath the TSF3 embankment and impoundment liner to collect contaminated seepage and groundwater.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |

## Conditions for the Waikato Regional Council Consents

|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |
|----------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| SC7.H.11 | The Consent Holder must ensure that this underdrainage system is in place prior to the discharge of tailings to TSF3.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
| SC7.H.12 | <ol style="list-style-type: none"> <li>1. Until final capping is complete, the Consent Holder must ensure that the pH of a slurry of one part solid (less than 4 mm size fraction) to two parts deionised water, of the surface of any exposed PAF rock (after liming) remains greater than or equal to pH 5.5.</li> <li>2. Unless Waikato Regional Council agrees to an alternative sampling programme in writing, slurry samples must be collected on a grid pattern of not more than 50 m and, where practical, within 1 week of placement of any PAF rock and then at intervals not exceeding 4 weeks.</li> <li>3. The procedure for collecting and analysing the samples must be as described in the TSF3 Monitoring and Management Plan.</li> </ol> <p><i>Advice Note. This sampling is designed to help determine the potential for acid generation and sulphate release from waste rock.</i></p> |
| SC7.H.13 | The Consent Holder must, unless otherwise authorised in writing by Waikato Regional Council, collect all underdrainage flow from the tailings storage facility and divert it to the Water Treatment Plant for treatment or for use in the Processing Plant.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |
| SC7.H.14 | <ol style="list-style-type: none"> <li>1. The embankment structure must incorporate a minimum freeboard above all material in the tailings pond (i.e. solid and liquid). This level must be sufficient to impound the surface run-off arising from the Probable Maximum Precipitation (PMP) event without overtopping, plus a 1.0 metre freeboard.</li> <li>2. Following rainfall or any event that reduces the freeboard below the minimum requirement, the water level must be drawn down as soon as practicable to restore the full freeboard.</li> </ol>                                                                                                                                                                                                                                                                                                                                             |
| SC7.H.15 | The Consent Holder must provide the Peer Review Panel with all records, plans, designs, and any other information they request to assist with their advisory role, and must afford the Panel full access to the site at all reasonable times.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |
| SC7.H.16 | <ol style="list-style-type: none"> <li>1. The Consent Holder must retain a person or persons with recognised qualifications and experience in the design of tailings storage facilities (the Designer).</li> <li>2. All aspects of the design of this facility must be undertaken under the supervision of the Designer, who must prior to the first discharge of tailings to this impoundment and prior to commissioning of subsequent embankment stages, provide to Waikato Regional Council written confirmation that all aspects of this structure have been designed in accordance with accepted engineering best practise, and to ensure the effective control of acid and metalliferous drainage and the containment of tailings.</li> </ol>                                                                                                                                                      |
| SC7.H.17 | <ol style="list-style-type: none"> <li>1 The Consent Holder must supply at least the following documentation to the Waikato Regional Council prior to commencement of TSF3 construction works: <ol style="list-style-type: none"> <li>a. Detailed Design Report</li> <li>c. Design Drawings</li> <li>d. Construction Monitoring Inspection Schedule</li> </ol> </li> </ol>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |

## Conditions for the Waikato Regional Council Consents

|            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |
|------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|            | 2 All subsequent amendments to the design must be supplied to the Waikato Regional Council prior to implementation and following peer review by an appropriately qualified and experienced person or persons.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |
| SC7.H.17.A | All detailed design reporting shall include seismic design analyses in accordance with National Seismic Hazard Model (2022).                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |
| SC7.H.17.B | <ol style="list-style-type: none"> <li>The Detailed Design Report required under Condition SC7.H.17.A must: <ol style="list-style-type: none"> <li>evaluate the respective positive and adverse environmental effects of a wet capping method and a dry capping method; and</li> <li>recommend a preferred capping method that minimises adverse effects and maximises positive effects.</li> </ol> </li> <li>The Consent Holder must implement the recommended preferred capping method.</li> </ol>                                                                                                                                                                                                                                                                                                                                                       |
| SC7.H.18   | <ol style="list-style-type: none"> <li>All construction works must be implemented under the supervision of appropriately qualified and experienced persons.</li> <li>The Consent Holder must supply to the Waikato Regional Council a full set of as-built plans for each completed stage of the TSF3 development.</li> </ol>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |
| SC7.H.19   | The Consent Holder must maintain the structural integrity of the works associated with the exercise of these consents and of any erosion control and energy dissipation works which become necessary as a consequence of the exercise of these consents.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |
| SC7.H.20   | <ol style="list-style-type: none"> <li>On completion of the initial embankment structure construction works and each subsequent stage (i.e. immediately prior to the first discharge of tailings into the impoundment) and prior to commissioning of subsequent embankment stages, the Consent Holder must supply written confirmation to the Waikato Regional Council and the Peer Review Panel stating that the embankment structure and associated works of the relevant stage have been constructed in accordance with the design referred to in Condition SC7.I.17.</li> <li>Thereafter, the facility must be inspected by a registered engineer on an annual basis, and a written report on the inspection provided to the Waikato Regional Council and copied to the Peer Review Panel within one month of completion of the inspection.</li> </ol> |
|            | <b>Monitoring</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |
| SC7.H.21   | The Consent Holder must measure and record the volume of storage provided by the available freeboard behind the embankment structure at quarterly intervals. This information must be made available to Waikato Regional Council on request.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |
| SC7.H.22   | <ol style="list-style-type: none"> <li>Throughout the period of mining the Consent Holder must establish and maintain an inventory of sources and estimated volumes of available inert material. This inventory is to be updated at six monthly intervals and balanced against estimated future demand for inert material. This inventory must be available upon request by Waikato Regional Council and the Peer Review Panel.</li> </ol>                                                                                                                                                                                                                                                                                                                                                                                                                 |

## Conditions for the Waikato Regional Council Consents

|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |
|----------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|          | <ol style="list-style-type: none"> <li>In the event a shortfall of inert material occurs or is identified in advance, the Consent Holder must prepare and implement contingency measures to ensure that proper control of geochemically active materials is maintained.</li> <li>A summary of the inventory and details of any measures which have needed to be taken must be reported annually to Waikato Regional Council.</li> </ol>                                                                                                                                                                                                  |
| SC7.H.23 | The Consent Holder must collect a sample of tailings being discharged to the tailings pond and must determine its acid neutralising capacity (ANC), maximum potential acidity (MPA), and net acid generation (NAG) capacity at monthly intervals. The date the sample is collected and the ANC, MPA and NAG results must be reported to the Waikato Regional Council annually.                                                                                                                                                                                                                                                           |
| SC7.H.24 | <ol style="list-style-type: none"> <li>The Consent Holder must install groundwater quality monitoring bores to detect seepage bypassing the underdrainage system, and to determine the representative groundwater quality for shallow and deeper groundwater around the perimeter of land downstream from TSF3 owned by the Consent Holder. This is to include installation of groundwater quality monitoring bores between the TSF3 and the Ruahorehore Stream (to the south and southeast of the TSF3).</li> <li>The locations and specifications of the bores must be to the satisfaction of the Waikato Regional Council.</li> </ol> |
| SC7.H.25 | <ol style="list-style-type: none"> <li>The Consent Holder must undertake baseline monitoring of groundwater monitoring bores at least monthly over a twelve month period, prior to the discharge of tailings or PAF material within TSF3.</li> <li>Groundwater monitoring is to be undertaken using the methodology provided in the TSF3 Monitoring and Management Plan required by SC7.H.30 and monitoring must include the measurement of all parameters annexed as <b>Attachment 2</b> to this consent.</li> <li>The results of baseline monitoring must be forwarded to Waikato Regional Council at quarterly intervals.</li> </ol>  |
| SC7.H.26 | The Consent Holder must calculate trigger levels for the parameters annexed as <b>Attachment 2</b> to this consent for down gradient bores based on the trends observed in the baseline monitoring data required by Condition SC7.H.25 at levels which will provide early warning of potential changes of groundwater quality as a result of the activities authorised by this consent. All trigger levels must be set at the 95 <sup>th</sup> percentile confidence limit.                                                                                                                                                              |
| SC7.H.27 | <ol style="list-style-type: none"> <li>At any time following completion of baseline monitoring, if monitoring results within the monitoring bores exceed the relevant trigger level for that bore over two consecutive readings then the Consent Holder must: <ol style="list-style-type: none"> <li>Characterise and assess the source of the exceedance; and</li> <li>Take all necessary measures to ensure that General Condition G18 is complied with.</li> </ol> </li> <li>The trigger and measures taken must be reported to the Waikato Regional Council immediately on completion.</li> </ol>                                    |
| SC7.H.28 | <ol style="list-style-type: none"> <li>Ongoing monitoring must be undertaken at the locations and using the methodology outlined in the TSF3 Monitoring and Management Plan required by SC7.H.30, with</li> </ol>                                                                                                                                                                                                                                                                                                                                                                                                                        |

## Conditions for the Waikato Regional Council Consents

|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |
|----------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|          | <p>monitoring to include the measurement of all parameters annexed as <b>Attachment 2</b> to this consent.</p> <p>2. Monitoring results must be provided to the Waikato Regional Council and copied to the Peer Review Panel as part of annual reporting as required under SC7.H.34.</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |
| SC7.H.29 | <p>1. The Consent Holder must identify how waste rock produced within Tailings Storage Facility 3 will be classified. The classification process must as a minimum include:</p> <ol style="list-style-type: none"> <li>Definitions used to characterise waste rock embankments in terms of acid base accounting;</li> <li>Criteria used for classifying waste rock;</li> <li>An assessment protocol for classifying waste rock;</li> <li>Waste rock sampling requirements for Tailings Storage Facility 3;</li> <li>Waste rock sampling requirements during construction and rehabilitation of Tailings Storage Facility 3; and</li> <li>Requirements for limestone addition for any potentially acid forming rock placed within stockpiles.</li> </ol> <p>2. The classification process is to be provided in the TSF3 Monitoring and Management Plan required by Condition SC6.H.30.</p> |
|          | <b>TSF3 Monitoring and Management Plan</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |
| SC7.H.30 | <p>1. No later than 30 working days prior to the commencement of works to establish TSF3, the Consent Holder must submit a TSF3 Monitoring and Management Plan for written certification under Condition C5 of Schedule One.</p> <p>2. Certification is required to verify that the TSF3 Monitoring and Management Plan:</p> <ol style="list-style-type: none"> <li>Includes actions, methods, monitoring programmes and trigger levels as appropriate to meet the objectives in Condition SC7.H.31; and</li> <li>Satisfies the requirements in Condition SC7.H.32.</li> </ol> <p>3. The TSF3 Monitoring and Management Plan need not be a standalone document, and the Consent Holder may, at its discretion, include it as part of any other management plan required by the conditions of this consent.</p>                                                                            |
| SC7.H.31 | <p>The objectives of the TSF3 Monitoring and Management Plan are to set out details of:</p> <ol style="list-style-type: none"> <li>The monitoring that will be undertaken to ensure that the TSF3 does not adversely affect land, ground and groundwater resources; and</li> <li>The contingency measures necessary to ensure the conditions of this consent are achieved.</li> </ol>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |
| SC7.H.32 | <p>1. The TSF3 Monitoring and Management Plan must include, as a minimum:</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |

## Conditions for the Waikato Regional Council Consents

|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |
|----------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|          | <ul style="list-style-type: none"> <li>a. A Risk Management Plan for TSF3 which is in accordance with the Australian/New Zealand Standards for Risk Management (AS/NZS 4360:1999) or any subsequent replacement standard that: <ul style="list-style-type: none"> <li>i. Identifies and assesses the operational risks relating to TSF3,</li> <li>ii. Develops an appropriate monitoring programme; and</li> <li>iii. Sets out the actions to be taken in the event that monitoring in accordance with ii above indicates a material increase in the risks identified in i above.</li> </ul> </li> <li>b. A structural integrity surveillance and monitoring programme for the embankment of TSF3 which conforms with the requirements of the current New Zealand Dam Safety Guidelines.</li> <li>c. A description of the tailings storage facility monitoring systems and the measures to be adopted to ensure compliance with General Condition G18, including: <ul style="list-style-type: none"> <li>i. The details of the monitoring bores to be established in accordance with Condition SC7.H.24;</li> <li>ii. Details of the monitoring to be undertaken in accordance with Condition SC7.H.25;</li> <li>iii. The trigger levels set in accordance with Condition SC7.H.26 and the contingency measures required by Condition SC7.H.31;</li> </ul> </li> <li>d. The measurement and monitoring of the liner and cover system integrity (by measuring drainage quality and flow from all underdrainage and surface collection systems) in order to verify the "as built" structure is achieving predicted design performance objectives.</li> <li>e. Details of the waste rock classification process in accordance with Condition SC7.H.29.</li> </ul> <p>2. In detailing the monitoring programmes the Consent Holder must provide information on the monitoring methods proposed, the monitoring locations, parameters to be monitored, and the required calibration and maintenance of monitoring equipment.</p> |
|          | <i>Review of the TSF3 Monitoring and Management Plan</i>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
| SC7.H.33 | <ul style="list-style-type: none"> <li>1. The TSF3 Monitoring and Management Plan must be reviewed at least annually by the Consent Holder to ascertain whether any amendments are required in order to ensure ongoing compliance with Condition SC7.H.31 and Condition SC7.H.32.</li> <li>2. Any required amendments must be made in accordance with Condition C8 of Schedule One.</li> </ul>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |
|          | <b>TSF3 Monitoring Report</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |
| SC7.H.34 | <ul style="list-style-type: none"> <li>1. The Consent Holder must submit an annual TSF3 Monitoring Report to the Waikato Regional Council. The report must, as a minimum include:</li> </ul>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |

## Conditions for the Waikato Regional Council Consents

|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |
|----------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|          | <ol style="list-style-type: none"> <li>a. The volume of all contaminated material disposed of within TSF3, including brine and hydrocarbons;</li> <li>b. The data from monitoring undertaken during the previous year.</li> <li>c. Identification of any environmentally important trends associated with the above monitoring.</li> <li>d. Interpretation and analysis of any change in groundwater chemistry over the previous year and predictions of any future changes in groundwater or surface water chemistry to identify what contingency actions, if any, it proposes to take in response to these predictions.</li> <li>e. Any contingency actions that may have been taken during the previous year.</li> <li>f. Comment on compliance with all conditions and any reasons for non-compliance or difficulty in achieving conformance with the conditions of this consent.</li> <li>g. A summary and analysis of complaints relevant to this consent, from the complaint log (refer Schedule One).</li> <li>h. Any works that have been undertaken to improve environmental performance or that are proposed to be undertaken in the forthcoming year to improve environmental performance in relation to activities permitted by this consent.</li> </ol> <ol style="list-style-type: none"> <li>2. The report must be forwarded in a format acceptable to the Waikato Regional Council.</li> <li>3. The TSF3 Monitoring Report need not be a standalone document and the Consent Holder may, at its discretion, include it as part of any other monitoring report required by the conditions of this consent.</li> </ol> |
|          | <b>Technical Review</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |
| SC7.H.35 | <ol style="list-style-type: none"> <li>1. The design and construction of all works covered by this consent must be reviewed by an appropriately qualified and experienced person or persons.</li> <li>2. The Consent Holder must instruct the person or persons to report in writing to the Waikato Regional Council at least at the following times: <ol style="list-style-type: none"> <li>a. Prior to commencement of construction of TSF3;</li> <li>b. At all critical stages during the ongoing design and construction of TSF3 but not less than annually;</li> <li>c. On the completion of TSF3;</li> <li>d. Following any significant design changes; and</li> <li>e. Prior to commencement of approved post closure discharge to the Ruahorehore Stream from the tailings pond;</li> </ol> </li> <li>3. The Consent Holder must instruct the person or persons to address at least the following matters: <ol style="list-style-type: none"> <li>a. progress against the Annual Work Programme,</li> </ol> </li> </ol>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |

## Conditions for the Waikato Regional Council Consents

|  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |
|--|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|  | <ul style="list-style-type: none"><li>b. site preparation including hydrogeological issues and geotechnical issues,</li><li>c. foundation design and use of on-site material,</li><li>d. embankment design and construction,</li><li>e. all underdrainage systems,</li><li>f. tailings impoundment management,</li><li>g. monitoring, and</li><li>h. rehabilitation and closure plans associated with the embankment and tailings pond.</li></ul> <p>3. The reports required by this condition shall also be provided to the Peer Review Panel for their consideration in an advisory capacity only with regard to the progression of works.</p> |
|--|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

## Conditions for the Waikato Regional Council Consents

|                                        |                                                                                                                                                                                                                                    |
|----------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                       | AUTH144654.55.01                                                                                                                                                                                                                   |
| CONSENT TYPE AND ACTIVITIES AUTHORISED | <p>RMA S13 To erect overflow spillways from Collection Ponds S6 and S7 in, on and over the bed of the Ruahorehore Stream.</p> <p>RMA S15 To discharge water to surface water from Collection Ponds (S6 and S7) via a spillway.</p> |
| LOCATION                               | Area 7                                                                                                                                                                                                                             |
| TERM                                   | 35 years                                                                                                                                                                                                                           |
| LAPSE PERIOD                           | 10 years                                                                                                                                                                                                                           |

|         |                                                                                                                                                                                                                                                                                                                  |
|---------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|         | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                                                                                                        |
| SC7.I.1 | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent.                                                                               |
|         | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                                                                                                    |
| SC7.I.2 | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                                                                                                             |
|         | <b>Design and Construction</b>                                                                                                                                                                                                                                                                                   |
| SC7.I.3 | The Consent Holder must maintain the structural integrity of the works associated with the exercise of this consent and of any erosion control and energy dissipation works which become necessary as a consequence of the exercise of this consent.                                                             |
| SC7.I.4 | The capacity of Collection Ponds (S6 and S7) must be constructed and designed to contain the run-off generated from within its catchment during a 24-hour duration rainfall event with an Annual Exceedance Probability (AEP) of 10%, taking into account a combination of both storage volume and pumping rate. |
| SC7.I.5 | Subject to Condition SC7.I.6 for 24-hour duration rainfall events with an AEP greater than 10%, all stormwater reporting to the Collection Ponds (S6 and 7) must be pumped to the Water Treatment Plant for treatment.                                                                                           |
| SC7.I.6 | <p>If the Consent Holder can demonstrate that the quality of water entering Collection Pond 6 or 7:</p> <ol style="list-style-type: none"> <li>Meets or is better than the receiving water criteria defined in Condition G18;</li> <li>Is capable of remaining so on a continuous basis; and,</li> </ol>         |

## Conditions for the Waikato Regional Council Consents

|                                                                                | <p>c In combination with all other discharges authorised for this site, does not cause a significant adverse effect on the receiving ground water and surface water, or on users of these resources, or, in the case of surface water, aquatic biota,</p> <p>then the Consent Holder may, if approved by the Waikato Regional Council in writing discharge directly from the pond, provided that</p> <p>d. The Consent Holder continuously monitors pH and turbidity in the pond; and</p> <p>e. For rainfall events with an AEP greater than 50%, the Consent Holder may direct discharges from the pond provided the continuous monitoring shows the water:</p> <p>i. has a turbidity concentration of no greater than 100 NTU; and</p> <p>ii. has a pH within the range of 6.0-9.0 pH units.</p> |                                                                                                                                                                                                                                                                                                                                                                 |                                                                                |    |              |                  |               |
|--------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------|----|--------------|------------------|---------------|
| SC7.I.7                                                                        | The Collection Ponds (S6 and S7) must be provided with a spillway to Ruahorehore Stream that that will safely route a 1% AEP flood.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                                                                                                                                                                                                                                                                                                                                                                 |                                                                                |    |              |                  |               |
| SC7.I.8                                                                        | The Consent Holder must ensure that Collection Ponds (S6 and S7) are:                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | <p>a. Constructed from materials which provide for secure long term containment; and</p> <p>b. Constructed using materials which have no acid forming potential; and</p> <p>c. Lined with 1.5mm HDPE (or other similar synthetic liner approved by the Waikato Regional Council) to a height of 1.5m from the base, and with a 0.5m protective cover layer.</p> |                                                                                |    |              |                  |               |
| SC7.I.9                                                                        | The design for Collection Ponds (S6 and S7) is to be submitted to the Waikato Regional Council for written certification no later than 30 working days prior to construction commencing.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                                                                                                                                                                                                                                                                                                                                                                 |                                                                                |    |              |                  |               |
| SC7.I.10                                                                       | Collection Ponds (S6 and S7) and associated works must be designed and implemented under the supervision of appropriately qualified and experienced persons.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |                                                                                                                                                                                                                                                                                                                                                                 |                                                                                |    |              |                  |               |
| SC7.I.11                                                                       | Routine maintenance and desilting of Collection Ponds (S6 and S7) must only occur during periods of projected fine weather. All removed silt must be disposed of to a tailings storage facility.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |                                                                                                                                                                                                                                                                                                                                                                 |                                                                                |    |              |                  |               |
| SC7.I.12                                                                       | No chemicals or additives may be used in Collection Ponds (S6 and S7) or the discharge from the ponds without the prior written approval of the Waikato Regional Council.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |                                                                                                                                                                                                                                                                                                                                                                 |                                                                                |    |              |                  |               |
|                                                                                | <b>Discharges and Monitoring</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |                                                                                                                                                                                                                                                                                                                                                                 |                                                                                |    |              |                  |               |
| SC7.I.13                                                                       | Except where Condition SC7.I.6(e) applies the Consent Holder must monitor the discharge from Collection Ponds (S6 and S7) every day during any overflow event in accordance with Table SC7.I.1.T1:                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |                                                                                                                                                                                                                                                                                                                                                                 |                                                                                |    |              |                  |               |
|                                                                                | <table><tr><th>Table SC7.I.1.T1 – Collection Ponds (S6 and S7) Overflow Monitoring Parameters</th></tr><tr><td>pH</td></tr><tr><td>Conductivity</td></tr><tr><td>Suspended solids</td></tr><tr><td>Cyanide (WAD)</td></tr></table>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |                                                                                                                                                                                                                                                                                                                                                                 | Table SC7.I.1.T1 – Collection Ponds (S6 and S7) Overflow Monitoring Parameters | pH | Conductivity | Suspended solids | Cyanide (WAD) |
| Table SC7.I.1.T1 – Collection Ponds (S6 and S7) Overflow Monitoring Parameters |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |                                                                                                                                                                                                                                                                                                                                                                 |                                                                                |    |              |                  |               |
| pH                                                                             |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |                                                                                                                                                                                                                                                                                                                                                                 |                                                                                |    |              |                  |               |
| Conductivity                                                                   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |                                                                                                                                                                                                                                                                                                                                                                 |                                                                                |    |              |                  |               |
| Suspended solids                                                               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |                                                                                                                                                                                                                                                                                                                                                                 |                                                                                |    |              |                  |               |
| Cyanide (WAD)                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |                                                                                                                                                                                                                                                                                                                                                                 |                                                                                |    |              |                  |               |

## Conditions for the Waikato Regional Council Consents

|                                                                                                                                      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |               |                                                                                                                                      |
|--------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------|--------------------------------------------------------------------------------------------------------------------------------------|
|                                                                                                                                      | <table><tr><td>Total ammonia</td></tr><tr><td>Trace elements(iron, manganese, copper, nickel, zinc, silver, antimony, arsenic, selenium, cadmium, chromium (iv), lead and mercury.</td></tr></table> <p><i>Table Note:</i></p> <p><i>The Collection Ponds (S6 and S7) overflow monitoring programme for metals is for ‘acid-soluble’ concentrations determined on unfiltered samples.</i></p>                                                                                                                                                                                                        | Total ammonia | Trace elements(iron, manganese, copper, nickel, zinc, silver, antimony, arsenic, selenium, cadmium, chromium (iv), lead and mercury. |
| Total ammonia                                                                                                                        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |               |                                                                                                                                      |
| Trace elements(iron, manganese, copper, nickel, zinc, silver, antimony, arsenic, selenium, cadmium, chromium (iv), lead and mercury. |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |               |                                                                                                                                      |
| SC7.I.14                                                                                                                             | Results of the monitoring undertaken in accordance with Condition SC7.I.13 must be forwarded to Waikato Regional Council quarterly.                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |               |                                                                                                                                      |
| SC7.I.15                                                                                                                             | <ol style="list-style-type: none"><li>1. All water quality sampling and analysis must be undertaken using Standard Methods for the Examination of Water and Wastewater (19th Edition 1995, or updates), APHA, AWWA and WEF, unless otherwise agreed in writing by Waikato Regional Council. Analyses must be undertaken at an appropriately certified laboratory.</li><li>2. All other measuring, testing, recording and analytical methods as may be required from time to time pursuant to the requirements of this consent must be to the satisfaction of the Waikato Regional Council.</li></ol> |               |                                                                                                                                      |

## Conditions for the Waikato Regional Council Consents

|                                        |                                                                                                                                                                                                                                                                                                      |
|----------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| RESOURCE CONSENT                       | AUTH144654.56.01                                                                                                                                                                                                                                                                                     |
| CONSENT TYPE AND ACTIVITIES AUTHORISED | <p>RMA S13 To disturb, reclaim and introduce plants in, on or over the bed of Ruahorehore Stream associated with a diversion of that stream around the Collection Pond S6 and S7 Buttress</p> <p>RMA S14 To dam and divert the Ruahorehore Stream around the Collection Pond S6 and S7 Buttress.</p> |
| LOCATION                               | Area 7                                                                                                                                                                                                                                                                                               |
| TERM                                   | 35 years                                                                                                                                                                                                                                                                                             |
| LAPSE PERIOD                           | 10 years                                                                                                                                                                                                                                                                                             |

|         |                                                                                                                                                                                                                                    |
|---------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|         | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                          |
| SC7.J.1 | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent. |
|         | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                      |
| SC7.J.2 | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                               |

## Conditions for the Waikato Regional Council Consents

|                                        |                                                                                  |
|----------------------------------------|----------------------------------------------------------------------------------|
| RESOURCE CONSENT                       | AUTH144654.57.01                                                                 |
| CONSENT TYPE AND ACTIVITIES AUTHORISED | RMA S15 To discharge overburden and topsoil to land in the TSF3 Soil Stockpiles. |
| LOCATION                               | Area 7                                                                           |
| TERM                                   | 35 years                                                                         |
| LAPSE PERIOD                           | 10 years                                                                         |

|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |
|---------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|         | <b>Schedule One – Common Conditions Which Apply to All Waikato Regional Council and Hauraki District Council Consents</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |
| SC7.K.1 | The Consent Holder must comply with the common conditions between the Hauraki District Council and the Waikato Regional Council in Schedule One to the extent relevant to the management of activities authorised by this consent.                                                                                                                                                                                                                                                                                                                                                                                                    |
|         | <b>Schedule Two – General Conditions Which Apply to All Waikato Regional Council Consents</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |
| SC7.K.2 | The Consent Holder must comply with the general conditions in Schedule Two which apply to all Waikato Regional Council consents to the extent relevant to the activities authorised by this consent.                                                                                                                                                                                                                                                                                                                                                                                                                                  |
|         | <b>Stockpile Management</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |
| SC7.K.3 | Stockpiling of ore or potentially acid forming rock must occur only at the sites specifically prepared for that purpose.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |
| SC7.K.4 | Preparation of stockpile sites for the temporary storage of soil prior to the placement of material must include: <ul style="list-style-type: none"> <li>a. Stripping and stockpiling of topsoil and subsoils for later use in site rehabilitation.</li> <li>b. Construction of clean water diversion drains around the site to divert and discharge clean surface run-off and intercepted groundwater in accordance with consent AUTH144654.52.</li> <li>c. Construction of diversion drains around the site perimeter to divert stockpile run-off to sediment retention ponds for sediment reduction prior to discharge.</li> </ul> |