

APPENDIX E – Insight Engineering Contaminated Land Report



Remediation Action Plan for the Parkburn Quarry at 922 Luggate- Cromwell Road (SH6), Cromwell

Prepared for: Fulton Hogan Land
Development

Date: 16/07/2026

Our Reference Number: 24019_RAP

Report prepared by: Claude Midgley
MSc, CEnvP

Reviewed by: Jana Kruyshaar
CMEngNZ

Record of Distribution

Sent to	Date	Report Status	No. of Copies
Daniel Thorne (Town Planning Group)	11/04/2026	Draft for Comment	1 Electronic
Melanie Foote (Town Planning Group)	19/06/2026	Final	1 Electronic
Melanie Foote (Town Planning Group)	16/07/2026	Updated Final	1 Electronic

Record of Report Version

Date	Version Number
11/04/2026	24019_RAP
19/06/2026	24019_RAP
16/07/2026	24019_RAP

Table of Contents

1	Introduction	5
1.1	Background	5
1.2	Purpose	5
1.3	Objectives	5
2	Site Description	5
2.1	Contaminants of Concern	6
2.2	Contaminant Distribution	7
2.3	Volume of Contaminated Soil	7
3	Assessment of Remedial Options	8
4	Discussion	10
5	Remediation Methodology	11
5.1	Introduction	11
5.2	Description of Remedial Works	11
5.3	Site Establishment	12
5.3.1	Procedures	12
5.3.2	Site Supervision	12
5.3.3	Health and Safety	13
5.4	Validation of Works	13
5.4.1	Selection of Remedial Goals	13
5.4.2	Validation Methodology	14
5.5	Timescales	14
5.6	Post Remediation	14
6	Assessment of Environmental Effects	14
6.1	Introduction	14
6.2	Dust Control	15
6.3	Noise	16
6.4	Stormwater Control	16
6.5	Site Access	16
6.6	Decontamination	16
6.7	Unforeseen Conditions / Circumstances	17
7	Reporting	17
8	Statutory considerations	17
8.1	Introduction	17
8.2	Central Otago District Plan and the National Environmental Standard for Assessing and Managing Contaminants in Soil to Protect Human Health	18

Remediation Action Plan for the Parkburn Quarry at 922 Luggate-Cromwell Road (SH6), Cromwell

8.3	Regional Policy Statement for Otago.....	19
8.3.1	Overview.....	19
8.3.2	Assessment of Relevant Objectives and Policies	19
8.4	Regional Plan: Waste for Otago	20
8.4.1	Overview.....	20
8.4.2	Assessment of Relevant Objectives and Policies	20
8.4.3	Assessment of rule applicability	21
8.5	Summary of Statutory Considerations	21
9	References.....	21
10	Limitations	22

Tables

Table 1: Site Description

Table 2: Assessment of Remedial Methods for Impacted Soil

Table 3: Potential effects of remediation works and proposed mitigation measures.

1 Introduction

1.1 Background

JKCM Limited, trading as Insight Engineering (IE), was contracted by Fulton Hogan Land Development to prepare this Remediation Action Plan (RAP), including an assessment of available remedial options, for the property (herein referred to as 'the site', refer to Appendix 1) at 922 Luggate-Cromwell Road, Cromwell.

Potentially contaminated areas were identified by e3scientific Limited (e3) during completion of a preliminary environmental site investigation (PSI) in 2021¹. Contamination impacts were then confirmed by IE during completion of a preliminary and detailed environmental site investigation (PSI/DSI) in 2026². Although some information is summarised in this RAP, it is recommended that this document is read in conjunction with the PSI¹ and PSI/DSI² for completeness (Appendix 2).

Figure 1 indicates the location of the subdivision and Figure 2 highlights the impacted areas / remediation areas.

1.2 Purpose

This purpose of this document is to assess and conclude on the suitability of various options available to remediate the impacted portions of the site, in accordance with the MfE *Contaminated Land Management Guideline No. 1: Reporting on Contaminated Sites in New Zealand*³ (CLMG#1) and Resource Management (National Environmental Standard for Assessing and Managing Contaminants in Soil to Protect Human Health) Regulations⁴ (herein referred to as the NES-CS) and then to provide procedures to enable implementation of the recommended remedial strategy / strategies.

1.3 Objectives

The RAP has the following specific objectives:

- Review past site investigation report(s) to assess contaminant distribution;
- Produce a report identifying the possible remedial options available, the method of risk reduction associated with each option, and the estimated positive and negative aspects associated with each remedial method;
- Recommend one, or several, methods that could adequately reduce the risk to human health at the site; and
- Provide procedures required to complete the remedial work in a safe and sustainable manner.

The limitations of this document are outlined in Section 10.

2 Site Description

The site information is summarised in Table 1.

Table 1: Summary of Site Information and Description

Location	922 Luggate-Cromwell Road (SH6), Cromwell
Legal Description	Part Sections 62-63 Block IV Wakefield Survey District, Part Section 63 Block IV Wakefield Survey District, Section 1 Survey Office Plan 365897, Section 4 Survey Office Plan 557380 and

Remediation Action Plan for the Parkburn Quarry at
922 Luggate-Cromwell Road (SH6), Cromwell

Table 1 (cont.): Summary of Site Information and Description

Legal Description (cont.)	Sections 64-65 Block IV Wakefield Survey District.
Property Owner	Fulton Hogan Limited
Former Site Use	A large proportion of the property is used for gravel quarrying purposes. Other isolated parts of the site are used for administration (offices), a concrete plant, an asphalt plant, a glass recycling area, equipment storage areas and for storage of a large stockpile of imported "cleanfill". The remainder of the site is not used.
Proposed Site Uses	Residential, commercial and recreation areas are proposed.
Property Area	Approximately 118 ha
Territorial Authorities	Central Otago District Council Otago Regional Council
Zoning	80.1 ha of Low Density Residential Zone, 10.1 ha of Medium Density Residential Zone, 4.7 ha of Business Resource Area 3, 2.3 ha of Industrial Resource Area 2, and 22.3 ha of Industrial Resource Area 3
Geology	The GNS New Zealand Geology Webmap⁵ indicates that the site contains two geological units: The majority of the site is located within Late Pleistocene outwash deposits of Albert Town Advance, described as "<i>Unweathered to slightly weathered, loose, sandy to silty, well rounded gravel usually on large outwash plains</i>". A small area located near to the northern boundary is underlain by Holocene fan deposits, broadly described as "<i>Loose, commonly angular, boulders, gravel, sand, and silt forming alluvial fans; grades into scree (upslope) and valley alluvium</i>".
Hydrogeology	Information provided in support of Private Plan Change 21, prepared by e3Scientific¹, confirms that the site is located within the Pisa Groundwater Management Zone. Groundwater flows from the Holocene river deposits, west of the site, through the highly permeable Late Pleistocene river deposits, comprised of sandy gravel or sandy cobbles and gravel, underlying the site. Groundwater ultimately reaches Lake Dunstan, east of the site. ORC data⁶ indicates that several water bores are located at and around the site. Groundwater depths in those wells ranged between 10.6 m below ground level (bgl) and 16.47 m bgl.


2.1 Contaminants of Concern

e3 identified¹ petroleum hydrocarbons, heavy metals and possible persistent pesticides as contaminants of concern in various isolated parts of the site.

2.2 Contaminant Distribution

Contamination impacts are primarily located within the north eastern portion of the site, in the vicinity of the asphalt plant, the concrete block manufacturing facility, equipment storage areas / yards and the cleanfill stockpile.

Additionally, isolated areas of potential impact were identified by e3 within the quarry area in the central and southern portions of the site.



The map above courtesy of e3 (Appendix 2) shows the areas within which contaminants are located. The locations of specific hazardous activities within the north eastern portion of the site are outlined in Figure 2.

2.3 Volume of Contaminated Soil

Cleanfill Stockpile

Due to the variability of the material observed by e3¹ and IE², a small percentage the 'cleanfill' stockpile is conservatively considered to contain contaminants at concentrations marginally exceeding the relevant SCSs.

As the process of separating impacted material from non-contaminated material is considered to be extremely laborious, the entire stockpile must be treated as if it contains contaminants at concentrations excluding the residential SCSs. The stockpile volume has been estimated at approximately 180,000 m³.

Asphalt plant

The volume of impacted material cannot be quantified until the plant and other operations on site have ceased. It is conservatively estimated that up to 100 m³ could be impacted with various petroleum hydrocarbon products in the vicinity of the asphalt plant.

Fuel storage areas

Above-ground fuel storage activities generally result in negligible surface impacts from drips during refilling of machinery. However, underground fuel storage tanks and associated pipework can result in more significant impacts. Those impacts will only become apparent when removing the fuel tank(s).

It is conservatively anticipated that the volume of impacted soil associated with fuel storage areas could total up to 50 m³.

Other areas

The contractors' yards, used for storing machinery and treated timber poles, are conservatively estimated to contain up to 100 m³ of impacted material.

The former orchard area is considered unlikely to contain significant concentrations of persistent pesticides, due to the significant length of time since they could have been applied to the site. However, if present, the conservative estimate for the volume of impacted material is 70 m², based on impacts within the upper 100 mm across an area of approximately 700 m².

3 Assessment of Remedial Options

The following section identifies potential remedial options that are considered suitable for remediating soil contaminated with heavy metals, petroleum hydrocarbons and persistent pesticides that have been successfully conducted at field scale level and that have been documented at contaminated site case studies both nationally and internationally.

Table 2 provides a brief description of the remedial method and an assessment of whether this method is applicable to this site given its setting, proposed land use, contaminant volume, and distribution across the site and throughout the soil profile, as well as the required timeframe to complete the work.

Table 2: Assessment of Remedial Methods for Impacted Soil.

Remedial method	Description	Applicable and feasible at the site?
Electrokinetics	Electrokinetics is the application of low intensity current between electrodes placed in the soil (in-situ or ex-situ) to mobilise the contaminants towards the polarised electrodes thereby concentrating them and allowing their subsequent removal in a smaller volume of soil ⁷ .	Not considered applicable or financially viable at the site given the nature of the majority of the contamination on site, which is not considered to be particularly mobile in soil.
Phytoremediation	Involves the planting of certain grasses and trees which uptake the contaminants from the soil root zone into above ground plant tissue. Plants are removed after a sufficient period and disposed of at an appropriate facility ⁷ .	Not considered applicable or feasible at the site given the length of time taken to remediate the site compared with the available timeframe to enable residential development.

Remediation Action Plan for the Parkburn Quarry at
922 Luggate-Cromwell Road (SH6), Cromwell

Table 2 (cont.): Assessment of Remedial Methods for Impacted Soil.

Solidification/ stabilisation	Solidification refers to a process that involves binding contaminated soil with a reagent such as lime or cement, thereby changing its physical properties by increasing the strength, decreasing its permeability and encapsulating the contaminants to form a solid material⁸. The stabilisation process refers to a chemical reaction that reduces the leachability of contaminated soil, immobilising the waste and reducing its solubility; thus making the soil less harmful or less mobile. Solidification/stabilisation treatment typically involves mixing a binding agent into the contaminated soil. These techniques are done either <i>in-situ</i>, by injecting the binder agent into the contaminated media, or <i>ex-situ</i> by excavating the materials and machine mixing them with the agent.	Remediation technique is considered applicable to the site, especially the material within the cleanfill stockpile, but the process requires specialised equipment to enable uniform mixing of the impacted material and the binding agent. The approach is therefore not considered to be economically viable.
Soil washing	This method would typically involve physical and chemical separation of the majority of the contaminants into a smaller volume which is then disposed of or treated further. The washed or processed soil is then returned to the site. Physical separation typically involves standard mineral processing equipment to remove the finer particles which are likely to contain the majority of the contaminants. Chemical washing involves transferring the contaminants from the soil into solution which is subsequently treated⁹.	Given the time and associated costs to design and set up the soil washing process, this remedial approach is considered not a financially viable option. This option would also produce other waste streams (liquid reagents) that would require further treatment/disposal.
'Do nothing' approach	Continue with the residential development without undertaking any prior remedial activities.	Not considered applicable given the restrictions of the NES-CS which prohibit the residential use of sites that contain contaminants at concentrations that exceed the SCSs. Furthermore, earthworks are required for geotechnical purposes and the opportunity to re-work the impacted material therefore exists.
Offsite disposal	This involves the physical excavation of the contaminated soil and offsite disposal at an appropriate waste disposal facility.	Considered applicable, but given the total volume of impacted material to be removed the cost of disposal is considered a significantly limiting factor. However, off-site disposal is considered likely to be selected as the remedial option for the most significantly impacted material on site e.g. bituminous residue, or significant petroleum hydrocarbon impacts.

**Remediation Action Plan for the Parkburn Quarry at
922 Luggate-Cromwell Road (SH6), Cromwell**

Table 2 (cont.): Assessment of Remedial Methods for Impacted Soil.

Containment / Encapsulation	This remedial approach would involve excavating the impacted soil identified at the site and placing within a containment cell. A suitable containment cell for the site could be positioned at significant depth, such as greater than 2 m below finished ground level, within the north eastern portion of the site.	Considered applicable given the abundance of available containment space in that part of the site. The 'cleanfill' stockpile is required to be moved to enable excavation of the underlying pea gravels which are not geotechnically suitable for use as engineered fill. Therefore, the opportunity to screen the 'cleanfill' stockpile and remove large inclusions will be incorporated into the remediation works. The screened 'cleanfill' can then be placed back into the area where pea gravels were excavated from. Once all 'cleanfill' material has been placed and compacted, back-filling to the finished design levels can continue, using clean material from other parts of the property. Once buried, the 'cleanfill' would not interact with the environment to a measurable degree.
Capping	This remedial method involves capping the site with a sufficient thickness of clean soil.	The geotechnical constraints of the underlying pea gravel layer means that excavation of the pea gravel beneath the 'cleanfill' stockpile is required to enable the construction of 'good ground', therefore the site cannot be capped in its current state. However, the containment / encapsulation approach is proposed to be supplemented by capping the 'cleanfill' with at least 2 m of clean material from other parts of the property.

Of the available options, on-site containment / encapsulation of the impacted material, supplemented by capping with at least 2 m of clean material, is considered to be the most effective way to eliminate risks to human, environmental and ecological health for the vast majority of the contaminated material at the site.

Significantly contaminated material, such as petroleum hydrocarbon-impacted soil, will be disposed of off-site at an appropriate facility such as Victoria Flat landfill in Gibbston, or the Taiko Landfill near Timaru.

4 Discussion

Excavation, screening and re-placement of the 'cleanfill' stockpile can be easily achieved during the bulk site earthworks phase. Excavation of the 'cleanfill' stockpile is required regardless of which remediation method is selected, because the underlying pea gravels must be removed prior to back-filling with competent material for geotechnical purposes.

Off site disposal will be reserved for the most significantly contaminated material due to the unsustainability of disposing of contaminated material at landfills intended for household refuse and industrial waste.

The encapsulation approach does result in minor risks to worker health or the wider environment, but only during the earthworks phase. Therefore, implementation of the approach should be under a remediation action plan (RAP) and environmental management plan (EMP) detailing the health and safety, environmental and regulatory considerations.

5 Remediation Methodology

5.1 Introduction

IE has developed the following methodology to complete the remediation of the impacts identified by e3¹.

5.2 Description of Remedial Works

The extent of the proposed remedial work is limited to the areas highlighted in Figure 3.

The remedial works will be undertaken in the following order:

- A site meeting will be held with the individuals responsible for physical works, to ensure that the methodology and requirements of this RAP have been communicated and understood;
- Physical works will be completed by the designated remediation contractor and periodically observed by IE staff;

The potential risks associated with the chosen remedial method to be employed at this site are considered negligible. However, to ensure that there are no adverse environmental effects beyond the immediate vicinity of the remediation areas, the earthwork activities shall be undertaken in accordance with the protocols outlined in this RAP, as well as under a robust EMP to ensure stormwater, sediment and dust are controlled to the maximum possible extents.

Potential risks associated with contaminants identified on site relate to dermal contact, ingestion and inhalation of soil particles (dust). These risks will be kept to a minimum through the use of controlling site access, dust mitigation measures, and the control of stormwater. Information relating to minimising such risks is outlined in Section 6.0.

This RAP should not be used as a standalone document but should supplement the earthwork operators own health and safety protocols for their employees and contractors.

While some tasks may overlap during the remediation, the following outline indicates the proposed sequencing of works:

- Site establishment and kick-off meeting;
- Excavation and stockpiling of impacted material from the areas identified by e3¹;
- Confirmation of the significance of contamination impacts in material from the asphalt plant, fuel storage locations and former orchard area through laboratory testing;
- Screening of the 'cleanfill' material to remove large inclusions;

Remediation Action Plan for the Parkburn Quarry at 922 Luggate-Cromwell Road (SH6), Cromwell

- Re-placement and compaction of the 'cleanfill' and marginally impacted material from other parts of the site, once the underlying pea gravels have been excavated from the north eastern corner of the site;
- Capping the 'cleanfill' material with at least 2 m of clean compacted material from other parts of the site;
- Off-site disposal of the significantly impacted material (if any) from other parts of the site; and
- Production of a Works Completion Report, to summarise the remediation activities undertaken for each area identified by e3¹.

These works are described in further detail in the following sections.

It should be noted that stormwater from the north eastern portion of the site, where the marginally impacted material will be encapsulated beneath compacted cleanfill, will be diverted via a reticulated system to discharge into the main stormwater collection system further south west of the encapsulated material. The potential for infiltration of stormwater through the >2 m thick compacted cleanfill, to be able to reach the marginally impacted layer, is considered to be *de minimis*.

Generation of leachate from the marginally impacted layer is likely to be minimal even without the > 2 m layer of compacted cleanfill and a reticulated stormwater collection system due to the fact that contaminant concentrations are expected to be at, or below, background concentrations in the majority of the marginally impacted material. However, to make the greatest practical effort to eliminate leachate from the marginally impacted material, the additional influences of the compacted cleanfill layer and the reticulated stormwater collection system have been included to demonstrate the commitment to ensuring the protection of the surrounding environment.

5.3 Site Establishment

5.3.1 Procedures

Prior to the remedial works commencing at the site, the remediation supervisor will outline all relevant Health and Safety requirements to personnel working on site during the remediation works. Such requirements will be documented within a detailed Health and Safety Plan (HASP) which will be kept in the site file. In general, the following procedures will be adhered to, to ensure that the health and safety, and environmental measures are achieved:

- Personal safety equipment and procedures associated with the contaminants will be explained to the individuals responsible for physical works;
- The identification and marking out of the proposed remediation areas by the remediation supervisor prior to commencement of the remediation program. 'Clean' and 'dirty' areas will be identified.

5.3.2 Site Supervision

To provide control and validation of the proposed remedial works it is recommended that a designated, suitably trained site supervisor is present to oversee the works on a part-time basis. The site supervisor would address field changes as necessary should unanticipated conditions arise.

Prior to earthworks activities commencing, all employees and contractors associated with the remedial work shall also be briefed by the individuals responsible for physical works with respect to any potential hazards on the site relevant to their role.

5.3.3 Health and Safety

This RAP identifies potential hazards associated with the presence of contaminants in site soils and recommends procedures to mitigate these risks. Risks associated with elevated concentrations of petroleum hydrocarbons, heavy metals and persistent pesticides relate to dermal contact, ingestion and to inhalation of impacted soil particles during earthwork activities.

Prior to the commencement of the remediation works a HASP will be prepared for the proposed activities. All site personnel will be required to review this document. At the start of each day, a brief “tool box” meeting shall be held to review the HASP and the proposed work for the day, discuss potential perceived health and safety risks as well as environmental management procedures and communicate these issues to the remediation team.

To prevent the unintended transfer of any contamination off site, or to other areas within site boundaries, and to minimise exposure to site remediation workers the following risk mitigation measures will be followed:

- To minimise exposure to airborne dust, the excavator and truck driver shall keep cab windows closed and use air conditioning when excavating and loading soil during remediation earthworks;
- Contractors working outside shall wear a half face disposable mask or filter type particulate respirator, if dust is generated during completion of remedial works; and
- Eating, drinking, smoking, use of mobile phones and applying cosmetics / sunscreen should only occur outside of the remediation areas and after face and hands have been thoroughly washed with potable water.

5.4 Validation of Works

The extents of the encapsulation / containment cell will be professionally surveyed as part of the site development works. The relative levels and extents of the base, sides and top of the compacted layer of impacted material will be recorded. Furthermore, the survey data for the finished ground level above the encapsulated material will be recorded to confirm the thickness of the capping layer.

5.4.1 Selection of Remedial Goals

The remedial goals are proposed to make the site suitable for residential use⁴.

Given the fact that marginally impacted material will be encapsulated deep below the finished site surface, no laboratory testing of that material is considered necessary. Instead, periodic XRF scans will be undertaken to assess whether any heavy metals are present at concentrations that could be considered significant.

Furthermore, laboratory testing of material from areas used for asphalt production or fuel storage will be undertaken to quantify the significance of the impacts (if present).

For this site, significant contamination impacts are conservatively set at twice the applicable criteria for the protection of human health (such as SCSs, or equivalent) on residential land.

If any contaminants are identified to be present at concentrations exceeding the remedial goals, the material will be diverted away from the containment cell and will be disposed of off-site at an appropriately licensed facility.

5.4.2 Validation Methodology

IE will supervise the excavation and off-site disposal of material from significantly contaminated areas, where impacts are visually obvious, such as the areas covered with a bituminous product near to the asphalt plant and south east of the 'cleanfill' stockpile.

Material surrounding the obviously contaminated areas, where petroleum hydrocarbons are present, will be screened on site using a photoionization detector (PID). If the vapour concentration exceeds 100 ppm, samples will be collected for laboratory analysis to confirm whether the material is suitable to be retained on site within the containment cell, or whether off-site disposal is required. If the vapour concentrations are below 100 ppm, no further excavation will be undertaken unless required for geotechnical purposes. Any excess spoil from those areas, with vapour concentrations below 100 ppm, will be placed into the containment cell prior to the cell being capped with clean material.

If any material is required to be excavated from the former orchard area, it will be placed and compacted into the containment cell. Samples will be collected from the soil remaining in the former orchard area, after excavation works have been completed, for laboratory testing of persistent pesticide concentrations. If pesticides are found at concentrations above the laboratory limits of detection, additional excavation will be undertaken until the remaining soil does not contain detectable concentrations of persistent pesticides.

5.5 Timescales

It is expected that site development earthworks could continue for up to 10 years.

IE understands that the site development will be undertaken in a staged approach, with the north eastern portion of the site being developed last of all. That provides abundant time to ensure that the remediation works are completed well before bulk earthworks commence in that part of the site.

The remedial works are expected to take up to two years, for the excavation, screening, re-placement and compaction of the 'cleanfill' stockpile. Remediation of the remaining areas could be completed within 3 months at any time during the site development process.

A Works Completion Report will be presented to CODC within three months following completion of all remediation earthworks.

5.6 Post Remediation

Other than areas of currently unknown sources of contamination, surface soil remaining at the site will not exceed criteria designed to be protective of human health during normal residential use.

It is not expected that disturbance of the compacted 'cleanfill' material within the containment cell would require disturbance in the future. However, if excavation depths reach that material it is recommended that a Contaminated Site Management Plan be prepared to control those works.

6 Assessment of Environmental Effects

6.1 Introduction

This section of the RAP details the potential environmental effects that could occur from conducting the remediation outlined previously. Table 3 summarises the potential effects associated with the proposed remedial works and the management measures that are recommended to mitigate these. Remedial construction works will be managed to mitigate potential adverse effects during and after operations.

**Remediation Action Plan for the Parkburn Quarry at
922 Luggate-Cromwell Road (SH6), Cromwell**

Table 3: Potential effects of remediation works and proposed mitigation measures.

Potential Effects	Receptor	Mitigation Measures
The potential for dust generation is high during the stockpiling and placement of soil on site.	Site workers and members of the public on neighbouring properties are the primary receptors.	When wind speed is high enough to cause visible dust, the site surface and excavations will be dampened to suppress dust generation. Stockpiles of soil will be covered or stabilised with dust suppressant spray, as necessary.
Excavator and truck noise will be generated during the remedial activities.	None, because surrounding residential properties are located over 800 m from the activities.	All work will be conducted during regular daytime business hours.
Contaminated surface water, stormwater and sediment discharge from site during rainfall events.	Neighbouring properties and Lake Dunstan / <i>Te Wairere</i> .	All works will be completed under a robust EMP to ensure that surface water, stormwater and sediment are controlled appropriately.
Exposure to impacted materials (direct contact with contaminated soil).	Site personnel.	Control site access, no public access to be allowed. Instruction on site rules and site induction to site workers. Appropriate dust suppression. Good hygiene practices (hand washing, no smoking). Use of appropriate PPE. Suitable decontamination procedures.

6.2 Dust Control

The inhalation of contaminated dust on site during earthworks is considered to be a hazard to earthwork contractors and staff present within the site.

The following activities may generate dust during the remedial works:

- Excavation of contaminated material.
- Placement of fill onto the containment cell.

It is recommended that the following control methods are implemented to ensure that dust levels generated by earthwork activities are kept to a minimum:

- Any material temporarily stockpiled should be covered as soon as possible.
- Avoid working or standing in areas down-wind of earthwork activities.
- Limit drop heights from excavator buckets.

Remediation Action Plan for the Parkburn Quarry at 922 Luggate-Cromwell Road (SH6), Cromwell

- Keep windows / doors on excavators and trucks closed when parked in the earthworks area.
- Apply water by a cart or sprinkler prior to commencement of works. The site shall be regularly damped down to reduce any airborne dust. This should prevent visible dust emissions beyond the site boundary.

Weather reports will be checked at the beginning of each day and if high wind speeds are expected the above mitigation measures will be prepared. When wind speed exceeds such a level that dust is noted to be airborne, operations shall cease. The site health and safety officer or site foreman will be responsible for ensuring that the dust mitigation measures are implemented when necessary.

Site practices to reduce worker exposure to contaminated dust should also include the designation of exclusion zones, such as the excavation area(s), where the provision and use of particulate dust masks is required. Such controls should be outlined within the contractors HASP.

6.3 Noise

The following protocols will be employed to ensure that noise levels are kept to acceptable standards:

- Earthwork activities will be restricted to the hours of 7:00 am to 6:00 pm Monday to Friday and 7:30 am to 5:30 on Saturdays. No work shall be permitted on Sundays or Public Holidays.
- These remedial works will be required to comply with the New Zealand Standard NZS 6803: 1999 "Acoustics – Construction Noise"¹⁰.

6.4 Stormwater Control

Where applicable, the site surface will be graded to divert stormwater away from site boundaries.

Any temporary stockpiled soil will not be placed adjacent to drainage areas and will not contain contaminated soils. Runoff from the stockpiles will be mitigated by covering stockpiles with tarpaulins, or other sediment management methods specified in the EMP.

6.5 Site Access

The remediation contractor will use appropriate means to ensure that members of the public are not able to enter the site during completion of remedial works. This may be through the use of fences, barrier tape, signs and / or personal observation and communication.

6.6 Decontamination

No decontamination of equipment is expected to be required upon completion of the remedial works within the containment cell.

Decontamination of equipment used to excavate petroleum hydrocarbon-impacted soil will be undertaken by rinsing excavator buckets with water in a way that the wash water is contained within the bed of the truck used to dispose of the material off-site.

If bitumen remains attached to the excavator bucket(s) or truck bed(s), those parts of the machines will be scrubbed using degreaser to dissolve the bitumen. The waste liquid will then be placed into the next load of contaminated material being disposed of off-site. Liquid from the final rise will be collected in an appropriate receptacle for off-site disposal, such as an empty 44 gallon drum that can be sealed for transport.

6.7 Unforeseen Conditions / Circumstances

Other potentially hazardous conditions which have not been identified may exist at the site, including discovery of additional contamination during remedial works. In the event of any unforeseen circumstances the remediation supervisor should be consulted. Assessment of the contamination will be determined using the remediation supervisors judgement and knowledge of industry best practise.

7 Reporting

At the completion of the remediation and validation works a Works Completion Report will be prepared outlining the remediation works undertaken and presenting the laboratory results of the soils tested during the remedial works.

8 Statutory considerations

8.1 Introduction

The Resource Management Act 1991 (RMA), and associated statutory planning documents, establish the framework for the management of all activities that utilise New Zealand's natural and physical resources. The remediation of the site is assessed against the requirements of these documents in the following sections of the RAP.

In relation to the proposed remediation, the relevant statutory documents are:

- Resource Management Act 1991 (RMA)¹¹.
- Central Otago District Plan and the National Environmental Standard for Assessing and Managing Contaminants in Soil to Protect Human Health (NES-CS)³.
- Regional Policy Statement for Otago 1998 (RPS)¹².
- Regional Plan: Waste for Otago 2022 (Waste Plan)¹³.

Part 2 of the RMA outlines the purpose and principles of the RMA. Section 5 states:

- “(1) The purpose of this Act is to promote the sustainable management of natural and physical resources.*
- (2) In this Act, “sustainable management” means managing the use, development, and protection of natural and physical resources in a way, or at a rate, which enables people and communities to provide for their social, economic, and cultural wellbeing and for their health and safety while –*
- (a) Sustaining the potential of natural and physical resources (excluding minerals) to meet the reasonably foreseeable needs of future generations; and*
 - (b) Safeguarding the life-supporting capacity of air, water, soil, and ecosystems; and*
 - (c) Avoiding, remedying, or mitigating any adverse effects of activities on the environment.”*

The proposed remediation of the site is intended to ensure that the site can be used for residential purposes. The ability to use the land resource safely, into the future, means that people and communities can provide for their social, economic and cultural well-being. In relation to the land, water and air resources of the area, the proposed remediation approach will ensure that, except for a relatively small volume of soil impacted with petroleum hydrocarbons, valuable landfill space (land)

Remediation Action Plan for the Parkburn Quarry at 922 Luggate-Cromwell Road (SH6), Cromwell

will not be taken up by impacted material, the generation of dust and sediment discharge will be managed to minimise or eliminate the potential adverse effects on air and surrounding land / water.

Section 6 sets out the matters of national importance which shall be recognised and provided for while Section 7 identifies matters for which regard shall be had under the RMA. There are no section 6 matters which are considered to be of relevance to this proposal. However, the following section 7 matters are considered to be relevant:

“(b) the efficient use and development of natural and physical resources:

(c) the maintenance and enhancement of amenity values:

(f) maintenance and enhancement of the quality of the environment”

The proposed remediation method, as detailed in this RAP, will enable the efficient use of the land into the future, in so doing achieving the intent of Section 7(b)).

In addition, the management measures incorporated into the proposed remediation approach will ensure that the land, air and water resources of the area will not be adversely affected during the remediation process and into the future. This ensures that the quality of the surrounding environment is enhanced (section 7(f)), which in turn provides for enhancement of amenity values in the area (section 7(c)).

Section 8 of the RMA requires specific regard to be had to the principles of the Treaty of Waitangi (Te Tiriti o Waitangi).

Lake Dunstan / Te Wairere is of significant cultural importance to mana whenua. Lake Dunstan / Te Wairere is a Statutory Acknowledgement Area and formally recognises the deep cultural, spiritual, historical, and traditional association of Ngāi Tahu with the lake and surrounding section of the Clutha River.

Given the above assessment, the proposed remediation approach, as outlined in this RAP, will promote the sustainable management of natural and physical resources and is therefore consistent with Part 2 of the RMA.

8.2 Central Otago District Plan and the National Environmental Standard for Assessing and Managing Contaminants in Soil to Protect Human Health

Land contamination is dealt with under the Central Otago District Plan through the implementation of the National Environmental Standard for Assessing and Managing Contaminants in Soil to Protect Human Health (NES-CS). All local territorial authorities (district and city councils) are required to give effect to and enforce the requirements of the NES-CS.

The NES-CS⁴ came into effect on 1 January 2012. The objective of the NES-CS is to ensure that land affected by contaminants in soil is appropriately identified and assessed at the time of being developed and if necessary remediated, or the contaminants contained, to make the land safe for human use.

Regulation 5 sets out the land and the activities to which the NES-CS applies. The NES-CS applies if it is on land described under Regulation 5(7), and if the activity proposed is described in any of subclauses (2) to (6) of Regulation 5.

Regulation 5(7), applies to any land on which an activity or industry described in the current edition of the Hazardous Activities and Industries List (HAIL) is being undertaken, is suspected to have been, or

has been undertaken. Activities undertaken at the site are included on the HAIL (refer to the site investigation reports^{1,2}). Therefore, Regulation 5(7) applies.

The activities described in subclauses (2) to (6) of Regulation 5 include subdivision, land-use change, significant earthworks, soil sampling or removing fuel storage systems. The remedial approach involves disturbing the soil of the piece of land for a particular purpose, therefore the NES-CS applies to this activity.

The proposed remediation of the site does not meet the requirements of Regulation 8(3) and the remedial work can therefore not be undertaken as a Permitted Activity. The activity is not Controlled, being that it does not meet Regulations 9(1)(b) and 9(3)(b). As a result, the activity would, under normal circumstances, require consent under the NES-CS for a restricted discretionary activity pursuant to Regulations 10(1) and 10(2). However, given the fact that certain areas of contamination impact cannot be assessed while the site is operational, the activity would need to be undertaken as a Discretionary Activity pursuant to Regulation 11.

8.3 Regional Policy Statement for Otago

8.3.1 Overview

The RPS¹² became operative on 1 October 1998. Since becoming operative changes were notified in May 2015 and a decision was made in October 2016. Changes to the RPS went through an appeals process and a partially operative RPS was issued in 2019, including the changes resulting from the appeals process.

The RPS 1998 is now deemed to be only partially operative and the provisions of Chapter 13 – Wastes and Hazardous Substances in this version of the document have been fully revoked. Accordingly, for the purposes of this assessment, it is the provisions of the Partially Operative RPS 2019 in Part B Chapter 4, that address contaminated land that are relevant to the consideration of this proposal.

The RPS provides an overview of the resource management issues within the Otago region. It then developments a policy framework (i.e., objectives and policies), and associated methods for delivering on that policy, aimed at achieving integrated management of the region's natural and physical resources. Regional Plans, including the Waste Plan, and district plans cannot be inconsistent with the RPS.

8.3.2 Assessment of Relevant Objectives and Policies

Part B Chapter 4 of the Partially Operative RPS addresses issues, and develops an associated policy framework, in relation to 'hazardous substances, contaminated land and waste materials'. This includes contaminated sites. Therefore, the policy framework of relevance to the proposed remediation, as outlined in Section 13 of the RPS, is:

- To minimise the risks, to people and the environment, arising from existing contaminated sites (Objective 13.4.4).
- To address the adverse effects from past waste disposal, including identified contaminated sites, by remedying and mitigating any adverse effects arising from such sites (Policy 13.5.7).

The proposed remediation approach, as outlined in this RAP, has been developed to minimise the future risks to people and the environment. This is to be achieved by encapsulating and capping the contaminated soil within a portion the property that is unlikely to be disturbed in the future. In so doing, the removal of impacted fill from the site is eliminated. On this basis, the proposed remediation approach is consistent with the relevant policy framework of the Partially Operative RPS.

8.4 Regional Plan: Waste for Otago

8.4.1 Overview

The Waste Plan¹³ became operative on 9 July 2022.

The Waste Plan seeks to provide for the integrated management of waste (solid, liquid and gaseous) through the implementation of a waste strategy which addresses all stages of the waste life cycle.

Chapter 4 of the Waste Plan covers Waste Minimisation to enable the most efficient use of resources and energy.

Chapter 5 of the Waste Plan covers Contaminated Sites, and includes the discharge of hazardous substances or wastes onto or into land or water, and the issues associated with remedying or mitigating the adverse effects of those contaminant discharges. Therefore, Chapter 5 is of relevance to the proposed remediation of the site.

Chapter 7 of the Waste Plan covers Landfills, which includes the disposal of solid wastes onto or into land. As the remediation method eliminates the requirement to dispose of impacted material at a landfill, Chapter 7 is also of relevance to the proposed remediation.

8.4.2 Assessment of Relevant Objectives and Policies

The policy framework within Chapters 4 and 5 of relevance are:

- To encourage, support and facilitate integrated waste management by minimising the effects on the environment by reducing the quantity and / or toxicity of material entering the waste stream; reusing materials, recycling materials, where practicable, that cannot be reused; recovering resources from materials in the waste stream and disposing of the residual waste in an environmentally safe manner (Objective 4.4.2).
- To avoid, remedy or mitigate any adverse effects of contaminated sites (Objective 5.3.1).
- To avoid further site contamination. (Objective 5.3.2).
- To contain and remediate contaminated sites, to the extent that is practicable, and having regard to the land's future use (Policy 5.4.3).
- To apply the Australia and New Zealand Conservation Council's "Guidelines for the Assessment and Management of Contaminated Sites" (January 1992) to determine, for a particular contaminated site, the most appropriate course of action (Policy 5.4.4).

The proposed remediation of the site has been designed utilising the current relevant guidelines (i.e., guidelines that have superseded those specified in Policy 5.4.4 above), to ensure that the land can be utilised in a manner consistent with its proposed future use (i.e. residential land use). This means that the adverse effects of contamination at site will be avoided, remedied and mitigated as a result of the proposed remediation.

Given the above assessment, the proposed remediation approach is consistent with objectives 4.4.2, 5.3.1, 5.3.2 and policies 5.4.3 and 5.4.4 of the Waste Plan.

The policy framework within Chapter 7 – Landfills, is mostly relevant to typical landfills, and not the proposed remediation activity. However Objective 7.3.1 (*to avoid, remedy or mitigate the adverse environmental effects arising from the discharge of contaminants at and from landfills*) is of relevance to the remediation method, as disposal of the vast majority of impacted spoil is actively avoided by the on-site containment and encapsulation strategy. The potential negative effects that could occur, if

impacted spoil was disposed of at a landfill, are therefore eliminated to the maximum practicable extent.

8.4.3 Assessment of rule applicability

The Waste Plan contains only one rule (Rule 5.6.1) covering activities in and around contaminated land as follows:

“5.6.1 Hazardous wastes at contaminated sites (discretionary activity).

- 1. The disturbance of land; or*
- 2. The discharge of hazardous waste into water; or*
- 3. The discharge of hazardous waste onto or into land in circumstances that may result in that hazardous waste (or any other hazardous waste emanating as a result of natural processes from that hazardous waste) entering water; or*
- 4. The deposit of any hazardous waste, in , on or under land; or*
- 5. The discharge of hazardous waste into air at or from a contaminated site; is a discretionary activity.”*

The excavation, containment and encapsulation of the impacted soil requires the disturbance of land and a discharge of hazardous waste to land (within the containment / encapsulation area). As such, resource consent would be required for the proposed remediation pursuant to Rule 5.6.1.

The rules covering the discharges of waste onto or into land are contained in Section 7.6 of the Waste Plan and these will be applicable to the operator of the receptor site where some waste will be disposed of.

8.5 Summary of Statutory Considerations

Remediation of the site by excavation and on-site capping of arsenic impacted near surface soils, as well as off-site disposal of soil impacted with cadmium and zinc, as outlined in this RAP, is consistent with the requirements of Part 2 of the RMA¹¹ and the policy framework of the relevant statutory plans (i.e., the RPS¹², the Waste Plan¹³).

Resource Consent is required from the ORC, according to Rule 5.6.1., as the remediation method results in a disturbance of land containing hazardous waste at a contaminated site¹³. Resource Consent is also required from CODC, under NES-CS Regulation 8(3)⁴, to disturb soil on a site where hazardous activities or industries have occurred.

9 References

1. e3scientific Limited 2021: Parkburn Quarry Preliminary Site Investigation. Report reference #21085
2. Insight Engineering 2026: Preliminary and Detailed Environmental Investigation at 922 Luggate-Cromwell Road (SH6), Cromwell. Report reference 24019_3
3. Ministry for the Environment 2011: Contaminated Land Management Guidelines No.1: Reporting on Contaminated Sites in New Zealand.
4. Ministry for the Environment 2012: Users' Guide National Environmental Standard for Assessing and Managing Contaminants in Soil to Protect Human Health.
5. GNS Webmap Institute of Geological and Nuclear Sciences 2013: 1:250,000 Geology. Viewed at: <http://data.gns.cri.nz/geology/>

**Remediation Action Plan for the Parkburn Quarry at
922 Luggate-Cromwell Road (SH6), Cromwell**

6. Otago Regional Council 2025: Otago Regional Council Resource Consent Database. Viewed at: <https://maps.orc.govt.nz/OtagoMaps/>
7. US Environmental Protection Agency 1997: Recent Developments for In Situ Treatment of Metal Contaminated Soils. USEPA Contract Number: 68-W5-0055.
8. US Environmental Protection Agency 2009: Technology Performance Review: Selecting and Using Solidification / Stabilization Treatment for Site Remediation.
9. Contaminated Land: Applications in Real Environments 2007: Understanding Soil Washing, Technical bulletin TB13.
10. Standards New Zealand 1999: NZS 6803:1999 Acoustics – Construction Noise.
11. Ministry for the Environment 1991: Resource Management Act.
12. Otago Regional Council 1998: Regional Policy Statement for Otago.
13. Otago Regional Council 2022: Regional Plan: Waste for Otago.

10 Limitations

- i. We have prepared this report in accordance with the brief as provided. This report has been prepared for the use of our client, Fulton Hogan Land Development, their professional advisers and the relevant Territorial Authorities in relation to the specified project brief described in this report. No liability is accepted for the use of any part of the report for any other purpose or by any other person or entity.
- ii. The recommendations in this report are based on the ground conditions indicated from published sources, site assessments and subsurface investigations described in this report based on accepted normal methods of site investigations. Only a limited amount of information has been collected to meet the specific financial and technical requirements of the client's brief and this report does not purport to completely describe all the site characteristics and properties. The nature and continuity of the ground between test locations has been inferred using experience and judgement and it should be appreciated that actual conditions could vary from the assumed model.
- iii. Subsurface conditions relevant to construction works should be assessed by contractors who can make their own interpretation of the factual data provided. They should perform any additional tests as necessary for their own purposes.
- iv. This Limitation should be read in conjunction with the IPENZ/ACENZ Standard Terms of Engagement.
- v. This ROA is not to be reproduced either wholly or in part without our prior written permission.

We trust that this information meets your current requirements. Please do not hesitate to contact the undersigned on 021 556 549 if you require any further information. The author is a Certified Environmental Practitioner (CEnvP) under the Environment Institute of Australia and New Zealand (EIANZ) accreditation system.

Remediation Action Plan for the Parkburn Quarry at
922 Luggate-Cromwell Road (SH6), Cromwell

Prepared by




Claude Midgley, CEnvP
Principal Environmental Scientist



Appendix 1

Figures



Description	Site Location Plan	Figure Number	1
Project	Preliminary and Detailed Site Investigation 922 Luggate-Cromwell Road, Cromwell	Date	Jun-26
Client	Fulton Hogan Land Development Limited c/- Tim James Limited	Drawn by	CM
Project Number	24019_RAP	Approved by	JK





Description	Sample Location Plan and HAIL Areas	Figure Number	2
Project	Preliminary and Detailed Site Investigation 922 Luggate-Cromwell Road, Cromwell	Date	Jun-26
Client	Fulton Hogan Land Development Limited c/- Tim James Limited	Drawn by	CM
Project Number	24019_RAP	Approved by	JK



Appendix 2

Insight Engineering Preliminary and Detailed Site Investigation Report



Preliminary and Detailed Environmental Investigation at 922 Luggate-Cromwell Road (SH6), Cromwell

Prepared for: Fulton Hogan Land
Development

Date: 16/07/2026

Our Reference Number: 24019_3

Report prepared by: Claude Midgley
CEnvP, MSc.

Authorised by: Jana Kruyshaar
CMEngNZ, CPEng

Record of Distribution

Sent to	Date	Report Status	No. of Copies
Daniel Thorne (Town Planning Group)	11/04/2026	Draft for comment	1 (electronic)
Melanie Foote (Town Planning Group)	19/06/2026	Final	1 (electronic)
Melanie Foote (Town Planning Group)	16/07/2026	Updated Final	1 (electronic)

Contents

List of Tables	4
List of Appendices	4
1 Introduction and Scope of Report	5
2 Objectives of the Investigation	5
2.1 Approach	5
2.1.1 Review of Site Information	5
2.1.2 Intrusive Investigation	6
3 Site Description	7
3.1 Current Site Conditions	9
3.2 e3scientific Preliminary Site Investigation	10
3.3 ORC Property Database	13
3.4 CODC NES Records Search	14
3.5 Review of Historical Maps and Aerial Photographs	15
3.6 Summary of Identified Hazardous Activities and Industries	19
4 Intrusive Investigation	20
4.1 Data Quality Objectives	20
4.2 Methodology	20
4.2.1 Quality Assurance / Quality Control	20
4.3 Investigation Criteria	21
4.3.1 Soil Criteria	21
4.4 Results	21
4.4.1 Soil Encountered	21
4.4.2 Laboratory Test Results	22
5 Discussion	24
6 Conceptual Site Model	24
7 Conclusions	25
8 Recommendations	26
9 References	26
10 Limitations	27

List of Tables

Table 1:	Site Information
Table 2:	Site Setting
Table 3:	Current Site Conditions
Table 4:	Historical Maps and Aerial Photographs
Table 5:	Laboratory Results Compared with Human Health Criteria, Ecological Health Criteria and Background Concentrations
Table 6:	Conceptual Site Model

List of Appendices

Appendix 1:	Figures
Appendix 2:	Proposed Subdivision Plan
Appendix 3:	Site Photographs
Appendix 4:	e3scientific PSI Report
Appendix 5:	CODC NES Records Search
Appendix 6:	Laboratory Results and Chain of Custody Documentation

1 Introduction and Scope of Report

JKCM Ltd, trading as Insight Engineering (IE), was requested to undertake a preliminary and detailed environmental site investigation (PSI and DSI) at the northern portion of 922 Luggate-Cromwell Road, Cromwell (herein referred to as 'the site'). IE understands that the report will form part of an application for subdivision and use of the land for urban development via the Fast Track Approvals Act 2024 process.

The Parkburn Development Project (herein referred to as 'the Project') involves the staged subdivision and development of land at 922 Luggate-Cromwell Road (State Highway 6), Cromwell, located approximately 8 kilometres north of the Cromwell township and adjoining Lake Dunstan / Te Wairere.

The property includes part of the existing Parkburn Quarry. The Project provides for the establishment of a mixed-use urban development, including quarry rehabilitation, residential development, supporting commercial and community activities, open space, and associated infrastructure. Works are also proposed within the State Highway 6 (SH6) road reserve.

Figure 1 (under Appendix 1) indicates the location of the Project and the relevant portion of that property that was investigated as part of this report (herein referred to as 'the site').

Private Plan Change 21, approved in 2025, provides for future residential development over the majority of the Project. As part of that rezoning, the land in the northern portion of the Project (the site) was zoned for industrial land use. The proposed subdivision and development plans have since evolved and it is now proposed to undertake residential development at the site.

The purpose of this investigation was to assess the suitability of the site for residential subdivision, development and use, from the perspective of the Resource Management (*National Environmental Standard for Assessing and Managing Contaminants in Soil to Protect Human Health*) Regulations¹ (herein referred to as the NES-CS). This investigation was undertaken in general accordance with the Ministry for the Environment (MfE) *Contaminated Land Management Guidelines No. 1: Reporting on Contaminated Sites in New Zealand*².

Potential risks to ecological receptors were assessed according to the criteria provided in the *Determination and use of background concentrations of trace elements in soil in Otago and Southland*³.

2 Objectives of the Investigation

The objective was to determine if potentially contaminating historical activities pose an unacceptable risk to human health, or the health of ecological and environmental receptors, during and post site development.

2.1 Approach

IE completed the following scope of work to satisfy the investigation objectives:

2.1.1 Review of Site Information

Several sources were contacted for information relating to the past and present uses of the site and to identify any other environmental issues which may be on record. This consisted of:

- Review an existing PSI report⁴ prepared by e3scientific as part of the 2022 Private Plan Change application, which was approved in 2025;

Preliminary and Detailed Environmental Investigation

922 Luggate-Cromwell Road (SH6), Cromwell

- Undertaking a site walkover to describe current site conditions and assess whether any visual or olfactory evidence of contamination is present at the site;
- Review of publicly available data describing the local geology and hydrogeology;
- Review of the Otago Regional Council Selected Land Use Sites (SLUS) database to identify property specific records of hazardous activities or industries at the site and in the surrounding area;
- Reviewing the CODC NES Records Search statement to determine whether any records of contamination at the site are held in their database; and
- Reviewing publicly available historical aerial photographs and maps of the site and surrounding area.

2.1.2 Intrusive Investigation

The following scope of work was undertaken upon completion of the review of site information:

- Collect 8 soil samples from 8 locations within the cleanfill stockpile;
- Visual and olfactory inspection of soil samples in the field;
- Submit 8 soil samples to Hill Labs for analysis of either a suite of common heavy metals (As, Cd, Cr, Cu, Pu, Ni and Zn) or a suite of common heavy metals and mercury;
- Assess laboratory results for the soil samples against the adopted human health criteria for residential land use, as well as commercial / industrial land use, which serves as surrogate values for land development / excavation activities / future maintenance of underground services;
- Assess laboratory results for the soil samples against the expected naturally occurring concentrations, as well as the adopted ecological health criteria for residential land use; and
- Present a combined PSI and DSI report outlining the suitability of the site for land development earthworks and ongoing maintenance of underground services, as well as the post-development residential land use.

Site information is summarised in Table 1.

Table 1: Site Information

Location	922 Luggate-Cromwell Road (SH6), Cromwell
Legal Description	PT Secs 62 and 63 BLK IV WAKEFIELD SD and Sec 1 SO 365897
Property Ownership	Fulton Hogan Limited
Current Site Use	Parts of the site are used for administration (offices), a concrete plant, an asphalt plant, a glass recycling area, equipment storage areas and a large stockpile of imported "cleanfill". The remainder of the site is not used.
Proposed Site Use	Residential
Site Area	Approximately 24.280 ha (242,800 m ²) refer to Appendix 1
Territorial Authorities	Central Otago District Council (CODC) Otago Regional Council (ORC)
Zoning	Industrial Area

3 Site Description

The site is located on the western side of Lake Dunstan / *Te Wairere* and is approximately 8 km north of Cromwell. Lake Dunstan / *Te Wairere* is of significant cultural importance to mana whenua. Lake Dunstan / *Te Wairere* is a Statutory Acknowledgement Area and formally recognises the deep cultural, spiritual, historical, and traditional association of Ngāi Tahu with the lake and surrounding section of the Clutha River.

The site is bound by horticultural (viticulture) and rural residential land towards the west (beyond SH6) and industrial land (quarry and contractors' yards) to the north. The land south of the site contains areas used for quarrying gravel, which was operational at the time of writing, as well as previously undisturbed, disused land vegetated with turf.

The quarry activities do not currently extend into the subject site and are limited to areas to the north and south of the site. However, the quarry areas are accessed by tracks extending through the site and it is understood that quarrying activities were historically undertaken within the site boundaries.

The Park Burn creek flows through the site in a roughly NW to SE direction. It discharges into Lake Dunstan in the area directly south east of the site.

The site also contains offices for the quarry operators (Fulton Hogan Limited), a concrete plant, an asphalt plant, a glass recycling area, equipment storage areas and a large stockpile of imported "cleanfill".

The remainder of the site can be referred to as a "greenfield" areas because no industrial activities have occurred in those parts of the site.

The site setting is summarised in Table 2.

Table 2: Site Setting

Nearest Surface Water & Use	The Park Burn creek flows through the site in a roughly NNW to SSE direction. It discharges into Lake Dunstan in the area directly south east of the site. Lake Dunstan / <i>Te Wairere</i> is used as a source of potable water as well as for recreational and irrigation purposes, as well as for electricity generation.
Geology	The GNS New Zealand Geology Webmap⁵ indicates that the site contains two geological units: The majority of the site is located within Late Pleistocene outwash deposits of Albert Town Advance, described as "<i>Unweathered to slightly weathered, loose, sandy to silty, well rounded gravel usually on large outwash plains</i>". The remainder of the site, located near to the northern boundary, is underlain by Holocene fan deposits, broadly described as "<i>Loose, commonly angular, boulders, gravel, sand, and silt forming alluvial fans; grades into scree (upslope) and valley alluvium</i>". According to a geotechnical investigation completed by Geotago⁵, including test pits excavated in the cleanfill stockpile and the south eastern corner of the site, the cleanfill stockpile consists of uncontrolled fill described as "<i>Sandy silty GRAVELS with cobbles and occasional extraneous materials (wood, plastic, concrete)</i>" overlying "<i>sandy silt with roots, rootlets and decaying plant matter</i>" over a 1 m thick layer of pea gravel.

Preliminary and Detailed Environmental Investigation
922 Luggate-Cromwell Road (SH6), Cromwell

Table 2 (cont.): Site Setting

Geology (cont.)	Material in the south eastern corner of the site was described as topsoil overlying pea gravel. Both test pits were terminated at approximately 2 m below surface, due to the pea gravel causing the sides of the test pits to collapse.
Hydrogeology	Information provided in support of Private Plan Change 21, prepared by e3Scientific⁴, confirms that the site is located within the Pisa Groundwater Management Zone. Groundwater flows from the Holocene river deposits, west of the site, through the highly permeable Late Pleistocene river deposits, comprised of sandy gravel or sandy cobbles and gravel, underlying the site. Groundwater ultimately reaches Lake Dunstan / <i>Te Wairere</i>, east of the site. ORC data⁶ indicates that several water bores are located at and around the site. Groundwater depths in those wells ranged between 10.6 m bgl and 16.47 m bgl.
Groundwater Abstractions ⁶	Three groundwater abstraction consents are active at, or within 250 m of the site: • Consent 2010.042.V1 was issued to HWR Property Limited to take and use groundwater from well number G41/0113 located approximately 1.5 km southeast of the intersection of the Luggate-Cromwell Road (State Highway 6) and Smiths' [sic] Way. The Consent was originally issued to Downer New Zealand Limited in April 2010 and was transferred to HWR Property Limited in August 2022. The Consent expires on 31 March 2030. • Consent RM14.064.01 was issued to Number 925 Water Company Limited to take and use ground water for the purpose of irrigation, stock water and domestic supply from a location approximately 2 kilometres north northeast of the intersection of Luggate-Cromwell Road (State Highway 6) and Pisa Moorings Road in May 2014. The Consent was transferred The Consent expires on 12 May 2044. • Consent RM17.106.01 was issued to Skeggs Group Limited to take and use groundwater for the purpose of vineyard irrigation and domestic supply from a location approximately 1965 metres north east of the intersection of the Luggate-Cromwell Road (State Highway 6) and Clark Road. The Consent was originally issued to Akarua Limited in May 2017 and was transferred to Skeggs Group Limited in June 2024. The Consent expires on 15 May 2052.
Discharge Consents ⁶	Three discharge to land consents, and four discharge to air consents are active at, or within 250 m of the site: • Consent 99664 was issued to Fulton Hogan Limited – Alexandra to discharge solid fill to land within an operating gravel quarry beside Lake Dunstan / <i>Te Wairere</i> at the location where the Parkburn flows into the Lake for the purpose of backfill at a quarry site. The consent was issued on an unknown date and it expires on 6 November 2026. • Consent 2004.600 was issued to Fulton Hogan Limited – Alexandra to discharge dust to air for the purpose of quarrying, crushing and screening aggregate. The consent was issued on an unknown date and it expires on 31 March 2041.

Table 2 (cont.): Site Setting

Discharge Consents (cont.) ⁶	Consent 2010.043.V1 was issued to HWR Property Limited to discharge water and contaminants to land for the purpose of gravel washing at a location approximately 1.5 km southeast of the intersection of the Luggate-Cromwell Road (State Highway 6) and Smiths' [sic] Way. The Consent was originally issued to Downer New Zealand Limited in April 2010 and was transferred to HWR Property Limited in July 2022 and reissued in August 2022. The Consent expires on 31 March 2030.
Discharge Consents (cont.) ⁶	- Consent RM15.050.01.V1 was issued to Downer New Zealand Limited to discharge contaminants to air for the purpose of an operating an asphalt plant from a location approximately 1.4 km south of the intersection of the Luggate-Cromwell Road (State Highway 6) and Smiths Way in April 2016. The discharge of total suspended particulate matter shall not exceed 50 milligrams per cubic metre of air. The Consent expires on 13 May 2050. - Consent RM15.108.02.V2 was issued to Fulton Hogan Limited to discharge silt, sediment and water to land for the purpose of aggregate washing, processing aggregate, asphalt and concrete, truck washing and dust suppression at the asphalt plant sediment ponds and soakage areas located within the eastern half of the site, as well as south of the south eastern portion of the site, in November 2015. The Consent expires on 13 November 2050. - Consent RM18.376.01.V2 was issued to Fulton Hogan Limited to discharge contaminants to air for the purpose of an operating an asphalt plant from a location approximately 1.6 km south of the intersection of the Luggate-Cromwell Road (State Highway 6) and Smiths Way in March 2019. The discharge of total suspended particulate matter must not exceed 50 milligrams per cubic metre of air and the discharge of arsenic, cadmium, chromium, lead, cobalt, manganese and nickel must not exceed 10 grams per hour (combined). The Consent expires on 6 March 2044. - Consent RM24.364.02 was issued to Southern Transport Company Limited to discharge contaminants to air for the purpose of operating a worm farm at 922A Luggate-Cromwell Road in July 2024. The Consent expires on 31 July 2039.

3.1 Current Site Conditions

Claude Midgley of IE completed a site walkover inspection on 6 November 2025. Observations made at that time are summarised in Table 3 and photographs are presented in Appendix 3.

Table 3: Current Site Conditions

Visible signs of contamination	Bitumen residue, engine oil stains and waste asphalt millings were observed in the eastern half of the site.
Surface water appearance	Water in the Park Burn creek was clear and free flowing, with no evidence of contamination impacts such as chemical odours, discolouration or hydrocarbon sheen.
Current surrounding land use	Horticultural, rural residential and industrial land surrounds the site.

Table 3 (cont.): Current Site Conditions

Local sensitive environments	The Park Burn creek, Lake Dunstan / <i>Te Wairere</i> and the associated riparian zones are considered sensitive environments.
Visible signs of plant stress	No significant signs of plant stress were noted.

3.2 e3scientific Preliminary Site Investigation

e3scientific produced a PSI report⁴ that was submitted as part of Private Plan Change 21 in 2022. Their scope of work included assessment of the site and the areas south of the site. The full report is included as Appendix 4, but this summary contains relevant information related only to the land within the current site boundaries.

Site History

Fulton Hogan acquired the lease for the site in December 1985, after Robert and Charles Perriam had leased the land for farming purposes earlier in 1985. Prior to that, the site was leased by several private individuals (unnamed) since Robert Davidson acquired the initial lease in 1894. Fulton Hogan obtained a mining license for the site and surrounding area towards the south by July 1987.

Regional Council information confirmed that an underground petroleum storage system (UPSS), associated with Z Energy, was removed and the removal was reported to ORC in 2015. The contamination investigation associated with the removal of the UPSS confirmed that the residual contamination was acceptable for commercial / industrial land use.

The report about the removal of the UPSS provides information related to the removal of a 10,000L underground kerosene storage tank and a 10,000L underground diesel storage tank, as well as the associated pipework from a single pit where the tanks had been positioned end to end, undertaken in October 2014. The results of laboratory analyses confirmed that residual petroleum hydrocarbon concentrations were below the human health criteria for commercial / industrial land use and for the protection of groundwater quality. A 7 m long section of pipeline and a fuel bowser within a building were not removed as part of the site works at that time. The former tanks were replaced with above-ground fuel storage tanks.

On-Site Observations

e3scientific completed a walkover assessment that included inspection of the general site conditions, including the condition of the buildings and the ground surface across the site. They noted visible signs of contamination such as stains associated with leaks or spills, odours, plant stress, areas of fill or stockpiled material / waste, ground disturbance, former building foundations, incineration areas, chemicals storage and discharges from those areas, as well as the locations of former buildings, processes or activities undertaken on site.

The site was found to contain three separate areas, referred to as the “*weighbridge and offices*”, “*industrial area*” and “*cleanfill and yards*”.

No evidence of hazardous substance use or storage was found in the “*weighbridge and offices*” area, but the “*industrial area*” was used for asphalt and concrete manufacturing activities. The following excerpts describe the specific findings associated with those activities:

“The Firth Concrete block manufacturing facility is located on the western end of the industrial area. The gravel yard was generally tidy and well kept. A 10,000 L diesel tank is located to the east of the manufacturing building. An open storage shed is located along the western boundary of this area. A small, waste oil ‘igloo’ was present to the south of the open shed. There was no staining around the waste oil tanks. Several empty drums of concrete retardant (Sika Retarder) were stored behind (west

Preliminary and Detailed Environmental Investigation
922 Luggate-Cromwell Road (SH6), Cromwell

of) the open shed. Hardfill, consisting of broken concrete tiles and blocks was deposited over the landscape bund, north of the factory.

East of the Firth Concrete block manufacturing facility, an open yard is used as a parking area by Fulton Hogan Transport. An above ground diesel tank (4) associated with the nearby asphalt plant, was removed from the site in September 2021. Evidence of disturbed ground beneath the removed tank, including some soil on a plastic sheet, was still present. There was no evidence of staining or odour in this area. Underground fuel lines, running to the asphalt plant are reportedly still present.

The asphalt plant itself is located down an embankment to the east of the parking area. The plant is comprised of aggregate feeder bins, bitumen storage tanks, mixing drum, conveyor belt feeding, asphalt storage silos, a bag house and an operations office. The asphalt plant can produce up to 120 tonnes per hour (tph) of asphalt but will typically run at a production rate of approximately 80 tph. Bitumen and kerosene are stored in a bunded above ground tank at the base of the terrace. Bitumen is also stored in a shed near the plant. The ORC resource consent specifies that the plant can be run on used oil; however, to date only diesel fuel has been used.

The Allied Concrete batching plant is located on the opposite side of the main access road from the transport yard. The batching plant appears to be located at the repurposed weighbridge, where diesel fuel storage was noted in plans with several of the building consent applications. Immediately south of the batching plant, there is a gravel yard which was used by a company to produce concrete panels for the construction of the Frankton Marina in 2018. These areas appeared generally tidy.

A truck wash is located on the south side of the main access road. Run-off from the truck wash flows down the side of the access road into an infiltration pond. This is one of the discharge points authorised by ORC consent RM15.108.02. There was no oily sheens or hydrocarbon odour associated with the run-off water or sediment at the truck wash."

The "cleanfill and yards" area, located on the eastern side of the creek, was described as a former quarry area that was repurposed for cleanfill disposal and for "outdoor yards used by JCL Asphalt Limited and several divisions of Fulton Hogan."

The following excerpts describe the specific findings associated with those activities:

"A new shed, which will be used for crushing and storage of recycled glass, has been constructed. This building was consented under RC210112. During the site inspection, drainage work was being completed, but storage and crushing of glass had not yet commenced.

Beyond the new glass processing shed, an excavation is used for disposal of surplus concrete. Further to the east, there are two active (1-2 m high) faces used for cleanfill disposal. A concrete bay just east of the weighbridge at the entrance to the site is used for drop-off of small loads of cleanfill by Fulton Hogan and their sub-contractors. This material is then relocated to the cleanfill face. Visible material was predominantly soil, rock, and gravel, with occasional loads of cured asphalt, and some scattered broken glass across the surface of the cleanfill. A separate area is used for disposal of hardfill, including concrete, tile, bricks, and cured asphalt, as well as soil, gravel and rock. Disposal of material at the cleanfill is authorised by ORC resource consent 99664.

A Cleanfill Management Plan prepared by Fulton Hogan outlines the procedures required to achieve environmental best practice. Visual inspections of the quality of the fill material coming to the site are completed to ensure the material is consistent with resource consent requirements. If a non-complying load is identified, the cleanfill operator is to isolate the load and advise the Quarry Manager immediately. Signage is in place at the entrance to the cleanfill, providing a clear description of acceptable materials. Material is not to be accepted from any Hazardous Activities and Industries List (HAIL) sites unless it has been suitably analysed.

Preliminary and Detailed Environmental Investigation
922 Luggate-Cromwell Road (SH6), Cromwell

A partially buried skip is used for temporary storage of waste from high pressure water cutting used during roading maintenance work. The skip is covered and sealed, with waste periodically taken to landfill when full. To the east of the hardfill disposal area, finished areas of the cleanfill have been capped with gravel for use as open yards for other divisions of Fulton Hogan, as well as JCL Asphalt.

At the JCL Asphalt yard, there is a moveable above ground diesel tank located in the corner of the container shelter (1). Some soil staining was also visible. In this area, there were also 4 x 1,000 L IBC of concrete additive (Sika Viscacrete), with some visible product on the ground below the IBCs. The Fulton Hogan civil engineering and construction yards were predominantly used for the storage of building supplies and equipment. There were two small steel explosive storage containers (2) used by the Fulton Hogan geotechnical team. There was also a stack of CCA treated telephone poles (3) in the construction yard. Otherwise, there was no evidence of hazardous substance storage or use in these areas, and surface gravels were free of staining.”

e3scientific used a portable X-Ray Fluorescent Spectrophotometer (XRF) to estimate the concentrations of heavy metals at 40 locations within the active faces of the cleanfill / hardfill disposal area. Additional scans were undertaken in a previously undisturbed part of the site, to compare the results from the fill with results representing natural ground conditions. The results indicated that one or more of the heavy metals concentrations in 14 of the 40 samples exceed the naturally occurring concentrations at the site, but 4 of those samples may have been included due to the precision level of the XRF. They concluded that “three samples exceeded the Manaaki Whenua Landcare Research (2015) predicted background concentration by more than 35%, indicating that there is a higher likelihood that contaminants in excess of the local natural background were present in these samples.”

A preliminary conceptual site model was developed, to provide an overview of the potential interactions between contaminants and sensitive receptors. The following excerpts describe the potential risks associated with the relevant identified sources of contamination:

“Concrete manufacture - Commercial concrete manufacture has taken place on site since 2005. Contaminants associated with concrete manufacture may affect soil pH and stormwater quality; however, risks to human health are generally not considered significant.

In addition to the contaminants listed in Table 4, small quantities of concrete retarding admixture are used within the concrete block manufacturing plant. The active ingredient in this product is tetrapotassium pyrophosphate. Tetrapotassium pyrophosphate is a common food additive, and not considered particularly toxic. The material safety data sheet (MSDS) does not list any special environmental protections required and does not identify the product as toxic to people.

A 10,000 L diesel tank and waste oil igloo are also known to be present within the concrete block manufacturing facility, and it is suspected diesel storage also occurred at the Allied Concrete batching plant in the past.

Asphalt manufacture - The asphalt manufacturing plant has operated on site since 1987. Asphalt manufacture involves the storage and handling of petroleum hydrocarbons including diesel, kerosene, and bitumen. Once manufactured and cured, asphalt is relatively stable, and unlikely to leach significant quantities of contaminants.

Fuel storage - Outside of the asphalt and concrete block plants, there are four known areas of relatively small-scale fuel storage. These include a diesel tank, waste oil storage, and generator at the quarry plant and diesel storage at the JCL asphalt yard.

Treated timber storage - A relatively small area within the Fulton Hogan construction yard has been used for storage of treated timber poles. Although this activity has only occurred recently, and

Preliminary and Detailed Environmental Investigation 922 Luggate-Cromwell Road (SH6), Cromwell

appears to be for relatively short duration, leaching of copper, chromium and arsenic from tanalised timber can impact soils directly under the poles. Although leaching from treated timber stacks can pose a risk to human health under residential land use, results from previous investigations suggest that exceedance of commercial/industrial soil contaminant standards is unlikely (Marlborough District Council, 2016).

Waste disposal to land - Backfilling of the north-eastern portion of the site with cleanfill has taken place since the 1980's.

This activity was consented by the Otago Regional Council in November 2000, and the cleanfill generally appears to be well managed. ORC compliance reports in 2009 and 2020 identified minor non-compliance associated with reporting, but both inspections found the site to be tidy with no evidence of unconsented fill types or adverse environmental effects. A cleanfill management plan for the Parkburn Quarry was prepared by Fulton Hogan in 2018. The management plan provides clear direction on consent and unconsented fill types and confirms that material from HAIL sites is not to be accepted without prior sampling.

Field readings of heavy metal concentrations with an X-Ray Fluorescent Spectrophotometer (XRF) indicates that heavy metal concentrations within most of the soil within the cleanfill surface and tipping faces are consistent natural background concentrations. A small number of readings returned results that indicate some contaminated fill material has been received."

The report provided the following conclusions related to contamination risks within the site boundaries:

"Within the future industrially zoned area, the identified HAIL activities include concrete manufacturing and batching, asphalt production, fuel storage, persistent pesticide use, treated timber storage, and disposal of cleanfill. We consider that it is highly unlikely that contaminants in soil associated with concrete manufacture, persistent pesticide use, and treated timber storage would pose a risk to human under the proposed commercial/industrial land use.

It is possible that contaminants associated with asphalt production, fuel storage and cleanfill disposal could result in soil contamination that could pose a risk to long term outdoor workers using the site in the future without appropriate investigation, remediation and/or management during development. The greatest risks are associated with hydrocarbon storage, particularly around any underground fuel storage infrastructure (e.g. fuel supply pipelines). Risks associated with the disposal of cleanfill appear relatively low; however, given the long history of filling, it is possible that localised areas of contaminated fill material may be present.

Given the on-going use of the site for these HAIL activities, it would be appropriate to complete additional investigation upon decommissioning of any potentially contaminating land uses. These investigations may also be better able to assess risks to human health as plans for the proposed development become more detailed."

It should be noted that e3scientific report includes assessment of the remainder of the Project area. Three other activities (fuel storage, bitumen storage and a generator) that could have resulted in contamination impacts were identified within the boundaries of the Project. Those areas could not be assessed as part of this report, due to the ongoing quarrying operations.

3.3 ORC Property Database

IE reviewed the ORC Hazardous Activities, Industries and Bore Search database⁷ on 5 November 2025. The search confirmed that the site is not recorded on the database.

Preliminary and Detailed Environmental Investigation

922 Luggate-Cromwell Road (SH6), Cromwell

The site contains the only record (HAIL.00359.01) in the database within approximately 1.75 km of the site boundaries.

HAIL.00359.01 is recorded in the eastern portion of the site as the “*Fulton Hogan Asphalt Plant Parkburn*”. The summary notes state “*Consented asphalt plant location. Z Energy tank removal report rec'd in 2015 confirmed residual contamination from diesel tank was acceptable.*”

The site is recorded as “*Partially Investigated*” for verified hazardous activities and industries list (HAIL)⁸ Category E2 activities (Asphalt or bitumen manufacture or bulk storage (excluding single-use sites used by a mobile asphalt plant)).

3.4 CODC NES Records Search

The CODC NES Records Search (Appendix 5) was prepared by Adam Vincent, Planning Officer – Consents, on 26 November 2025. The records search contained various records related to Building Consents and Resource Consents associated with the site.

The Resource Area is listed as Medium Density Residential Zone, Low Density Residential Zone, Industrial Resource Area (2), Industrial Resource Area (3), with the Industrial zoning being relevant to the site and the other zones relating to the remainder of the property towards the south.

The following Building Consents were issued for the site: Erect an office building at a quarry (1988), erect a bitumen storage shed (1990), relocate a storage building (1995), erect a new Portacom building (2004), erect all new buildings / platforms for a new industrial plant (2005), relocate a building onto site for staff facilities (2006), additions to an existing shed (2015), erect a new storage shed (2015), foundations and site works for relocated office / smoko room (2016), foundations and site works for relocated office (2018, 2019 and 2020), install a Smart Shelter container roof (2020), foundations, water supply, drainage and site works for unisex Portacom ablution block (2020), a new 20 mx 26 m storage shed (2021), foundations and site works for a relocated Portacom (2022), new foundations and construction of portal frame gantry (2022) and change in the location for the relocated Portacom (2022).

The following Resource Consents were issued for the site: Backfill against quarry pit faces with solid fill (2000), land use to build and operate a concrete block manufacturing plant (2005), land use to extract and convey sand aggregate from the upper terrace (2007), land use to establish Portacom offices (2019), change of conditions of a Resource Consent to allow establishment of two further Portacom (2020), land use to construct a shed to house a glass crushing plant (2021), land use to install 2 20,000L diesel fuel tanks to replace one diesel tank with was to be removed (2022), change of conditions of Consent to change a building location (2022) and change of conditions of a Consent to allow the installation of a Smart Shelter on site.

Council aerial photographs, dating back to 2006, confirmed that an asphalt plant and a concrete block plant was present in the eastern portion of the site. The outdoor storage of unknown materials was also confirmed to have occurred in the south eastern portion of the site.

The records search also confirmed that a preliminary environmental site investigation was undertaken at the site in support of Plan Change 23. Extracts of the e3scientific report⁴, showing the locations of areas where hazardous activities were undertaken, are included in the records search.

HAIL activities associated with Council's records are A17 (storage tanks or drums for fuel, chemicals or liquid waste), A18 (storage tanks or drums for fuel, chemicals or liquid waste), E2 (Asphalt or bitumen manufacture or bulk storage), E4 (commercial concrete manufacture or commercial cement storage), G4 (scrap yards) and G5 (waste disposal to land).

3.5 Review of Historical Maps and Aerial Photographs

Photographs in the Crown Collection⁹ and Google Earth¹⁰, as well as topomaps on the MapsPast¹¹ website, have been reviewed to obtain information on the past uses of the site. Aerial photographs taken between 1958 and 2024, as well as maps created between 1939 and 2019, have been reviewed.

Table 4 summarises the features visible in each image.

Table 4: Historical Maps and Aerial Photographs

1939 ¹¹	The site is part of a block of land that is split by two parallel lines representing a road in the north western corner. The road crosses through the site from just south of the north western corner to just east of the north western corner. The site is labelled with "9" and "148,1,17". An overland water flow path is marked with curved black lines from near to the centre of the northern site boundary, to the south eastern corner of the site. Two parallel dashed lines, representing a vehicle track, as well as a dashed line with a single dot between each dash, representing a walking track, are located along a south west / north east axis in the area beyond the eastern site boundary. Another smaller property is located beyond the eastern site boundary and the Clutha River / <i>Mata Au</i> is marked in blue at the eastern side of that property. No other significant features are visible on the map.
1949 ¹¹	No significant changes are visible at the site, or in the surrounding area, compared with the 1939 map.
1958 ⁹	In the surrounding land, dwellings and border dykes are visible on the neighbouring property towards the west. A track extends along the southern site boundary, from Luggate – Cromwell Road to a small orchard on the southern bank of the Park Burn creek located just beyond the south eastern portion of the site. Another dwelling is visible towards the south east of that area. The remainder of the surrounding area appears to be used for agriculture in the same way as the site, with flood irrigation supplying water to various areas via water races. No other significant features are visible at the site or in the surrounding area.
1964 ⁹	The majority of the site is visible, but the eastern edge of the site is not covered by this photograph. A few water races are visible in the western portion of the site, west of the Park Burn creek. The trees near to the centre of the site and in the eastern portion of the site have grown. A small rectangular object, surrounded by a roughly triangular portion of cleared land, is visible just west of the trees near to the centre of the site. In the surrounding land, linear features representing border dykes for flood irrigation purposes, arranged along a north east / south west orientation, are visible towards the north east and south west. A large stack of hay bales is visible south west of the stand of trees near to the centre of the site. No other significant changes are visible at the site, or in the surrounding area.
1968 ⁹	Apart from a stack of hay bales is visible on the western bank of the Park Burn creek in the eastern portion of the site, the site remains unchanged compared to the 1964 photograph. In the surrounding land, new border dykes are visible in the south western corner and the eastern portion of the neighbouring property towards the north. No other significant changes are visible at the site or in the surrounding area.
1976 ⁹	Apart from the stack of hay bales no longer being present in the eastern portion of the site, the site appears unchanged compared with the 1968 photograph.

Preliminary and Detailed Environmental Investigation
922 Luggate-Cromwell Road (SH6), Cromwell

Table 4 (cont.): Historical Maps and Aerial Photographs

1976 (cont.) ⁹	In the surrounding land, new border dykes have been constructed on the neighbouring property towards the north of the site. No other significant features are visible at the site or in the surrounding area.
1978 ⁹	No significant changes are apparent at the site, or in the surrounding land.
1979 ¹¹	Symbols indicating the presence of trees are visible on the eastern side of the Park Burn creek near to the northern site boundary. Symbols indicating the presence of embankments or terraces are visible in the eastern portion of the site. The creek crosses through the eastern portion of the site and extends past a neighbouring property towards the east, which is labelled "<i>Rahoy</i>". Two blue lines with arrows pointing southwards indicate the presence of water races that cross through the central portion of the site and terminate just beyond the southern site boundary. The Clutha / <i>Mata Au</i> is marked in blue further east of the eastern site boundary. In the surrounding land, a track is marked along the southern site boundary from Luggate – Cromwell Road to the area marked "<i>Rahoy</i>". Symbols indicating the presence of a shelter belt are visible along the south western boundary of the neighbouring property towards the north. Black squares, representing buildings, are marked in the south west and east of the neighbouring property towards the north, as well as on the neighbouring properties towards the west, south and east. No other significant features are visible at the site or in the surrounding area.
1982 ⁹	No significant changes are apparent at the site, or in the surrounding land.
1983 ⁹	No significant changes are apparent at the site or in the surrounding land.
1984 ⁹	With the exception of a new light-coloured, square-shaped object in the area west of the stand of trees near to the centre of the site, no significant changes are apparent at the site or in the surrounding land.
1989 ¹¹	No significant changes are apparent, compared with the 1979 map.
1999 ¹¹	A black circle is labelled "<i>Tank</i>" is visible in the area just south east of the eastern edge of the shelter belt marked along the north western site boundary. New water races that extend towards the south east and south are marked in the central portion of the site. Symbols indicating the presence of trees are visible in the central and eastern portions of the site. In the surrounding land, the black squares are no longer present on the neighbouring properties towards the north and south. The area east of the site now has alternating diagonal blue and white lines and the area is labelled "<i>Bed of proposed Lake Dunstan</i>". No other significant changes are apparent, compared with the 1989 map.
2001 ⁹	A large quarry has been established in the eastern half of the site. Two new buildings are visible in the western portion of the quarry area. A small dam is visible near to the north eastern corner of the site. In the surrounding land, the areas directly east and west of the Park Burn creek in the southern half of the neighbouring property towards the north have been quarried and the ground surface in those areas is grey. Another area has been stripped of topsoil directly east of the eastern quarry area and the stripped topsoil appears to have been stockpiled further east of that area. Stripped topsoil from the eastern quarry appears to have been stockpiled at the eastern side of the main excavated area in that part of that property. Lake Dunstan / <i>Te Wairere</i> is visible at the eastern edge of the site. The buildings that had been present in the area labelled "<i>Rahoy</i>" have been removed and that area is now part of Lake Dunstan / <i>Te Wairere</i>.

Preliminary and Detailed Environmental Investigation
922 Luggate-Cromwell Road (SH6), Cromwell

Table 4 (cont.): Historical Maps and Aerial Photographs

2001 (cont.) ⁹	A vineyard appears to have been established on the neighbouring property towards the west. No other significant changes are apparent at the site or in the surrounding area.
2003 ⁹	The quarry has been extended towards the south, beyond the south eastern site boundary. A new, larger dam is visible north east of the small dam in the north eastern corner of the site. Another dam is visible directly east of the large dam. In the surrounding land, quarried portions of the neighbouring property towards the north appear to cover the same footprints, with the exception of the eastern extent, which has extended towards the east in the area south east of the stockpile of stripped topsoil. Another relatively small area has been stripped of topsoil on the neighbouring property towards the south, in the area south west of the central portion of the site. No other significant changes are visible at the site or in the surrounding area.
2005 ¹⁰	Only the eastern quarter of the site is covered by this image. The original small dam is no longer visible in the north eastern corner of the site. Instead, the large dam appears to have been mostly filled in and only the south eastern corner remains. The dam directly east of that dam remains. In the surrounding area, the quarry has been extended towards the east in the area east of the stripped topsoil stockpile on the eastern side of the Park Burn creek on the neighbouring property towards the north. No other significant changes are visible at the site or in the surrounding area.
2007 ¹⁰	Two large new buildings have been constructed in the western portion of the quarry area. Another small rectangular building has been constructed further west, between a parking area and the road that extends from Luggate – Cromwell Road to the quarry area. The dams in the north eastern corner of that property are no longer visible. No other significant changes are visible at the site or in the surrounding area. In the surrounding land, a large new quarry has been established in the southern portion of the neighbouring property towards the south. On the neighbouring property towards the north, the eastern quarry area has been extended towards the east in the area east of the stripped topsoil stockpile. The western topsoil stockpile area on that property has been stripped of topsoil and developed with three buildings, consisting of a large rectangular building in the north western portion of that area, as well as a small rectangular building east of the large building and an L-shaped building half-way along the western boundary of the newly stripped area.
2009 ¹¹	The water races are no longer marked on the site. Three black squares are visible in the eastern half of the site and the tank is no longer labelled, but the circular symbol remains. A quarry is labelled in the eastern portion of the site and the outline, marked as a dashed black line, extends across the south eastern portion of the neighbouring property towards the north. A small dam is marked in the area between the quarry and Lake Dunstan / <i>Te Wairere</i> in the north eastern corner of the site. Lake Dunstan / <i>Te Wairere</i> is now labelled as “Lake Dunstan” directly east of the eastern site boundary. “Rahoy” is no longer labelled in the area south east of the site. Symbols indicating the presence of horticultural land are visible on the neighbouring properties towards the west of the site. No other significant changes are visible at the site or in the surrounding area compared with the 1999 map.

Preliminary and Detailed Environmental Investigation
922 Luggate-Cromwell Road (SH6), Cromwell

Table 4 (cont.): Historical Maps and Aerial Photographs

2011 to 2019 ¹⁰	New stockpiles of dark grey material are visible near to the western bank of the Park Burn creek near to the northern site boundary. A new road connects the site to the south western portion of the neighbouring property towards the north. Three new relatively small new buildings have been constructed in the area east of the new road. A large new light-coloured structure is constructed in the area south of the original buildings located on that property.
2011 to 2019 (cont.) ¹⁰	In the surrounding land, quarrying activities continue to extend towards the east, north and west in the southern portion of the neighbouring property towards the south. The new quarry eventually connects to the original quarry in the eastern portion of the site. Quarrying continues to extend towards the east on the neighbouring property towards the north and stripped topsoil from the new quarry areas is stockpiled along the north eastern boundary of that property. The western portion of the area south east of the Park Burn creek is slowly back-filled towards the east after 2015. Equipment and machines, as well as dark grey stockpiles of unknown material, are stored in the area west of the Park Burn creek. Additional buildings are constructed in the area west of the equipment storage area. No other significant changes are apparent at the site or in the surrounding area during this timeframe.
2019 ¹¹	A new track is marked in the western portion of the site and it extends from the existing track on site to the north western site boundary, where it continues towards the east. Another track extends southwards from the area near to the symbol representing a tank. Three additional black squares are marked in the central portion of the site. A new quarry area is visible on the neighbouring property towards the south. A black square is visible in the south western portion of the neighbouring property towards the north. No other significant changes are apparent compared with the 2009 map.
2021 to 2023 ¹⁰	Bulk fill placement is visible in the north eastern corner of the site. The light-coloured structure is removed and a new dark grey structure is constructed in the area north east of the original buildings on the site. Two additional new structures are constructed east of that building, on the eastern side of the Park Burn creek and west of the bulk filling activities. One new building is removed from the area between the Park Burn creek and the area being filled. The area directly west of the stand of trees located near to the centre of the site has been stripped of topsoil. In the surrounding land, the quarry in the southern western portion of the neighbouring property towards the south also becomes back-filled and vegetation is established over that area. The quarry on the neighbouring property towards the north is extended towards the north east and the western side of the quarry is slowly back-filled. No other significant changes are apparent at the site or in the surrounding land.
2024 ¹⁰	Bulk fill placement has continued in the north eastern corner of the site. In the surrounding land, quarrying activities continue to extend towards the north in the eastern portion of the neighbouring property towards the north, with topsoil still being stockpiled along the north eastern property boundary. A new area is stripped and developed with three new buildings in the south western corner of that property. No other significant changes are apparent at the site or in the surrounding land.

3.6 Summary of Identified Hazardous Activities and Industries

The following activities noted on the MfE Hazardous Activities and Industries List⁸ (HAIL) have been identified during review of the history of the site:

Category A2 – Chemical manufacture, formulation or bulk storage.

- This category is represented by the presence of waste oil tanks and bitumen storage tanks at the asphalt plant. The risks to human health from these sources are likely to be low, due to the chemicals being contained in tanks that did not show signs of leakage, except in the areas where bitumen residue was visible on the ground surface.

Category A17 – Storage tanks or drums for fuel, chemicals or liquid waste.

- This category is represented by the presence of above-ground fuel, kerosene, bitumen, waste oil, concrete additive and concrete retardant storage tanks or drums. The risks to human health are considered likely to be low, except in the areas where bitumen residue was visible on the ground surface.

Category A18 – Wood treatment or preservation including the commercial use of anti-sapstain chemicals during milling, or bulk storage of treated timber outside.

- This category is represented by the presence of stacks of treated timber telephone poles noted by e3scientific in the JCL Asphalt yard. The risks to human health from that area is considered likely to be significant from a residential land use perspective, due to the high toxicity of arsenic which leaches from the poles during rainfall events.

Category E2 – Asphalt or bitumen manufacture or bulk storage (excluding single-use sites used by a mobile asphalt plant).

- This category is represented by the presence of the asphalt plant which poses significant risks to human health in areas where bitumen residue is visible on the ground surface.

Category E4 – Commercial concrete manufacture or commercial cement storage.

- This category is represented by the presence of the concrete block manufacturing facility which is not considered likely to pose significant risks to human health.

Category G5 – Waste disposal to land.

- This category is represented by the “cleanfill” stockpile in the eastern portion of the site which consists of imported fill. Additionally, engine oil stains, waste asphalt and bitumen residue on the ground are considered to represent waste disposal to land. The risks to human health from engine oil, waste asphalt and bitumen residue in those areas are considered to be significant, but the risks to health from the “cleanfill” stockpile in the eastern part of the site are unknown.

Category F8 – Transport depots or yards including areas used for refuelling or the bulk storage of hazardous substances.

- This category is represented by the yards in the south eastern portion of the site. The risks to human health from oil stains and treated timber poles in those areas are considered to be significant.

According to Regulation 5 of the NES¹, the Regulations apply if a HAIL⁸ activity has been undertaken, or currently is being undertaken on the property.

4 Intrusive Investigation

Under the NES-CS¹, the soil disturbance required for the proposed residential development of the site, as well as the subdivision and change of land use required to enable the development, are considered to meet the definitions provided under Regulations 5(4) disturbing the soil of the piece of land, 5(5) subdividing land and 5(6) changing the use of a piece of land that has had a HAIL activity undertaken on it.

The Fast Track application does not require an exhaustive assessment of the extents of contamination impacts at the site, but rather a high-level assessment to identify activities that could have resulted in significant contamination impacts and conclusions related to the potential for the site to be made suitable for the proposed residential development and use.

Therefore, a limited detailed environmental investigation was undertaken to assess whether certain activities have resulted in unacceptable risks to human health. Where other activities have resulted in obvious contamination impacts that pose significant risks to human health, detailed assessment of the extents of those impacts are considered more appropriate to be undertaken when commercial / industrial activities at the site have concluded. This approach is consistent with the conclusions of the e3scientific PSI report⁴.

Therefore, eight discrete soil samples were collected from the cleanfill stockpile in the eastern portion of the site, where the significance of contamination impacts (if any) could not be confirmed by visual observation. The samples were submitted to Hill Labs for analysis of a suite of common heavy metals (As, Cd, Cr, Cu, Pu, Ni and Zn). One sample (CF8) was also tested for mercury, in addition to the suite of common heavy metals. Sample locations are displayed in Figure 2.

4.1 Data Quality Objectives

The data quality objectives (DQO) of this assessment were:

- To assess the presence and concentrations of contaminants in near surface and stockpiled soil; and
- To assess the risks to human health posed by contamination at the site.

4.2 Methodology

The following was undertaken during the soil sampling works:

- Samples were given individual names that corresponded to specific locations recorded on a site plan (refer to Figure 2);
- Visual and olfactory inspection of soil samples in the field;
- Collect 8 soil samples from 8 locations along the edge of the “cleanfill” stockpile. Samples were compressed directly into laboratory supplied containers using a new pair of nitrile gloves for each sample. Prior to sampling, the equipment (hand trowel) was decontaminated using a triple wash procedure with potable water, Decon 90 solution and deionised water;
- Placement of samples into a chilly bin and transportation, under standard IE chain of custody procedures, to Hill Labs; and
- Request that Hill Labs analyse the samples for a suite of common heavy metals (As, Cd, Cr, Cu, Pu, Ni and Zn), or a suite of common heavy metals and mercury.

4.2.1 Quality Assurance / Quality Control

The quality assurance / quality control (QA / QC) procedures employed during the works included:

- Standard sample registers and chain of custody records have been kept for all samples;
- The use of Hill Labs, accredited by International Accreditation New Zealand (IANZ), to conduct laboratory analyses; and
- During the site investigation every attempt was made to ensure that cross contamination did not occur through the use of the procedures outlined within this document.

4.3 Investigation Criteria

4.3.1 Soil Criteria

The investigation criteria referenced in this report have been selected from the NES-CS to assess risks to human health. Where a soil contaminant standard (SCS) was not available, the hierarchy detailed in the MfE *Contaminated Land Management Guidelines No. 2: Hierarchy and Application in New Zealand of Environmental Guideline Values*¹² was used to select applicable criteria.

Human Health

SCSs¹, or other appropriate criteria for residential land use and commercial / industrial use have been presented to assess the risks to human health during the disturbance of soil associated with construction works required as part of the site development, as well as to assess the health risks during residential activities.

Ambient Concentrations of Contaminants

The New Zealand Institute for Bioeconomy Science Limited produced a report³ for ORC and Environment Southland titled *Determination and use of background concentrations of trace elements in soil in Otago and Southland*.

The report provides new criteria that are proposed to be adopted as standardised background / ambient concentrations for Otago and Southland, because the current national database of predicted background concentrations is too variable and has resulted in an unnecessarily complex situation when determining whether soil can be reused at other sites.

Therefore, based on advice received from Joon van der Linde, Principal Compliance Specialist at ORC, laboratory results below the proposed '*risk-based background concentrations or soil re-use criteria for the management of contaminated land and soil relocation*' can be considered to qualify as 'cleanfill' according to the MfE definition¹³.

Ecological Health

Due to the standardisation of the background concentrations for heavy metals within Otago and Southland, criteria for the protection of ecological receptors (Eco-SVGs) are now standardised as well. For ease of use, the recently published report³ includes Eco-SVGs that were calculated using the new background criteria.

Laboratory results below the Eco-SVGs provided in the report³ are considered acceptable for the protection of ecological receptors at the site.

4.4 Results

4.4.1 Soil Encountered

Soil encountered in the "cleanfill" stockpile was extremely variable and included silty sandy gravel with bricks, metal, plastic, textile, waste asphalt and concrete inclusions. Compacted hardfill was present at the surface of the remainder of the potentially contaminated areas.

Preliminary and Detailed Environmental Investigation
922 Luggate-Cromwell Road (SH6), Cromwell

4.4.2 Laboratory Test Results

Table 5 compares soil contaminant concentrations in the samples with the adopted investigation criteria described in Section 4.3. The full analytical results are included in Appendix 6.

Table 5: Laboratory Results Compared with Human Health Criteria, Ecological Health Criteria and Background Concentrations

Analyte	Investigation Criteria				Investigation Results							
	Predicted Background Concentrations ^A	Ecological Soil Guideline ^A	Soil Contaminant Standards (SCSs) ^B		CF1	CF2	CF3	CF4	CF5	CF6	CF7	CF8
		Residential	Residential	Commercial / Industrial (Excavation Activities)								
Land Use												
Heavy Metals												
Arsenic	12	20	20	70	<u>32</u>	8	7	7	10	<u>13</u>	9	5
Cadmium	0.6	5	3	1,300	< 0.10	< 0.10	< 0.10	< 0.10	< 0.10	< 0.10	< 0.10	< 0.10
Chromium	120	200	460 ^C	6,300	6	8	12	7	15	5	12	8
Copper	80	95	>10,000	>10,000	17	16	14	12	13	18	17	9
Lead	150	290	210	3,300	16	10	11	14	23	15	21	13
Mercury	-	-	310	4,200	-	-	-	-	-	-	-	< 0.10
Nickel	30	200 ^D	400 ^F	6,000 ^F	11	10	12	8	13	9	14	7
Zinc	180	180	7,400 ^F	400,000 ^F	57	39	51	32	53	23	54	28

Notes:

All values in mg/kg. Only detected analytes are presented. Full laboratory certificates are included in Appendix 5.

Underlined text indicates concentration exceeds the background concentration³.

Italics text indicates that the concentration exceeds the Ecological SGV for Residential Land Use³.

Bold text indicates that the concentration exceeds the SCS for Residential land use¹.

Highlighted cell indicates that the concentration exceeds the SCS for Commercial / Industrial Land Use which serves a surrogate for excavation activities and maintenance of underground services¹.

- Indicates that the tests was not completed on the sample.

A The New Zealand Institute for Bioeconomy Limited: Determination and use of background concentrations of trace elements in soil in Otago and Southland².

B The National Environmental Standard for Assessing and Managing Contaminants in Soil to Protect Human Health¹.

C Criteria for Cr6 presented as criteria for Cr3 are non limiting¹.

D Australian National Environmental Protection Council (NEPC) National Environmental Protection (Assessment of Site Contamination) Measure Schedule B(1): Guideline on the investigation levels for soil and groundwater. Calculation: Added Contaminant Limited (ACL) for urban residential and public open space (CEC = 10) + background concentration¹⁴.

E Australian National Environmental Protection Council (NEPC) National Environmental Protection (Assessment of Site Contamination) Measure Schedule B(1): Guideline on the investigation levels for soil and groundwater¹⁴.

5 Discussion

The arsenic concentration in sample CF1, located at the north eastern side of the “cleanfill” stockpile, exceeds the SCS for residential land use, as well as the expected background concentration and the Eco-SVG for residential land.

None of the concentrations of contaminants measured in other samples from the “cleanfill” stockpile pose significant risks to human health or ecological receptors.

However, significant contamination impacts consisting of engine oil stains, soil beneath treated timber poles and spilled bitumen were visually confirmed at the site. Laboratory analysis of those impacts is not required, due to visual and olfactory confirmation of the significance of the impacts. The below-ground extents of those impacts can be ascertained during the site remediation process, when excavation and disposal of the impacted material is proposed to occur.

6 Conceptual Site Model

A contamination conceptual site model, presented in Table 6, consists of three primary components to allow the potential for risk to be determined. These are:

- Source of contamination;
- Pathway to allow the contamination to mobilise; and
- Sensitive receptors which may be impacted by the contamination.

Table 6: Conceptual Site Model

Source	Pathway	Receptor
Heavy metals (naturally occurring), Petroleum hydrocarbons, polycyclic aromatic hydrocarbons (PAHs), and bitumen.	Inhalation of dust Dermal absorption (direct contact) Ingestion of soil and / or produce grown in the soil Wind-blown dust; Sediment migration via stormwater; Leaching via stormwater infiltration.	Maintenance / Excavation workers Site workers Future residents and visitors Soil microbes; Soil invertebrates; Plants; Wildlife.
Acceptable risk to human health	Earthworks Associated with Land Development Yes: The contamination impacts that could pose significant risks to human health are located in well defined areas and can be easily remediated prior to, or as part of the bulk subdivision earthworks. Future Residential Land Use No: Contamination impacts that pose significant risks to human health are located within the site boundaries. Remediation is required prior to residential development in those areas.	

Table 6 (cont.): Conceptual Site Model

Acceptable risk to ecological health	Future Residential Land Use No: Contamination impacts that pose significant risks to ecological receptors are located in the eastern portion of the site
--------------------------------------	--

7 Conclusions

Site History

Information obtained as part of this investigation (refer to Section 3) indicates that the site was used for agricultural purposes, likely as grazing for livestock and / or production of hay prior to establishment of a quarry and associated contractors' yards during the late 1980s.

Evidence was found that HAIL activities (refer to Section 3.6) have occurred in certain parts of the site. Soil samples were therefore collected from areas where significant contamination impacts could not be confirmed by visual or olfactory assessment. Soil samples were not required in areas where visual and olfactory indicators of contamination impacts were obvious, including engine oil stains, stacked treated timber poles and spilled bitumen.

Intrusive Investigation

Eight soil samples were collected from the eastern and southern sides of the "cleanfill" stockpile (Figure 2), then dispatched to Hill Labs under standard chain of custody documentation. IE requested that Hill Labs analyse the samples for a suite of common heavy metals and mercury was added to the suite of analyses at one sample location (CF8).

The arsenic concentration in sample CF1, located at the north eastern side of the "cleanfill" stockpile, exceeds the SCS for residential land use, as well as the expected background concentration and the Eco-SVG for residential land.

None of the concentrations of contaminants measured in other samples from the "cleanfill" stockpile pose significant risks to human health or ecological receptors.

Significant Contamination Impacts

Visual and olfactory confirmation of significant contamination impacts in various parts of the eastern portion of the site are not considered suitable for residential use until the impacted areas have been remediated.

The impacted areas are likely to be remediated relatively easily and the success of the remediation works would be validated upon completion, through laboratory analysis of the soil remaining in those areas.

This investigation has therefore confirmed that contaminants in soil, within the parts of the proposed residential use areas, pose significant risks to human health, environmental health or ecological health until such time that remediation earthworks are completed and validated.

Non-HAIL areas

No evidence of HAIL activities was found in the western portion of the site. The non-HAIL area is delineated in Figure 2.

NES Applicability

Contamination impacts identified in isolated parts of the Project confirm that the soil contamination exceeds the applicable standard in Regulation 7. Therefore, the proposed activities of subdividing land, changing land use and disturbing soil do not qualify as Controlled Activities pursuant to Regulation 9¹.

Consent will be required under the NES-CS for Restricted Discretionary Activities (Regulation 10) or Discretionary Activities (Regulation 11), to enable the remediation of the impacted areas prior to the change of land use, subdivision and development of the site for residential purposes.

8 Recommendations

It is recommended that this report be read in conjunction with the e3scientific PSI included as Appendix 4.

Furthermore, it is recommended that the soil contamination aspects of the Fast Track application be approved, because contamination impacts at the site appear to be relatively isolated and should be easily remediated prior to, or during bulk subdivision earthworks occurring.

Finally, it is recommended that the Remediation Action Plan (RAP)¹⁵ provided as part of this application be accepted, to enable all parts of the Project to be made suitable for residential purposes.

These conclusions and recommendations are considered to be consistent with those presented by e3scientific⁴.

9 References

1. Ministry for the Environment 2012: Users' Guide National Environmental Standard for Assessing and Managing Contaminants in Soil to Protect Human Health
2. Ministry for the Environment 2021: Contaminated Land Management Guidelines No.1: Reporting on Contaminated Sites in New Zealand
3. The New Zealand Institute for Bioeconomy Limited 2025: Determination and use of background concentrations of trace elements in soil in Otago and Southland.
4. e3scientific Limited 2021: Parkburn Quarry Preliminary Site Investigation. Report reference #21085
5. GNS Webmap Institute of Geological and Nuclear Sciences 2013: 1:250,000 Geology. Viewed at: <http://data.gns.cri.nz/geology/>
6. Otago Regional Council 2025: Otago Regional Council Resource Consent Database. Viewed at: <http://data.orc.govt.nz/>
7. Otago Regional Council 2025: Mapping Resource Hazardous Activities, Industries and Bores Search. Viewed at: <https://maps.orc.govt.nz/portal/apps/MapSeries/index.html?appid=052ba04547d74dc4bf070e8d97fd6819>
8. Ministry for the Environment 2011: Ministry for the Environment Hazardous Activities and Industries List
9. Local Government Geospatial Alliance 2025: Retrolens - Historical Image Resource Project. Viewed at: <http://retrolens.nz>

Preliminary and Detailed Environmental Investigation
922 Luggate-Cromwell Road (SH6), Cromwell

10. Google Earth v7.3.6.10441. Mount Pisa, Central Otago, New Zealand. -44.960981°lon, 169.253345° lat, Eye alt 1.87 km. <http://www.earth.google.com>. [November 2025]
11. Mapspast 2025: Current and Historical Topographic Maps (Topomaps) of New Zealand. Viewed at: <http://www.mapspast.org.nz/>
12. Ministry for the Environment 2011: Contaminated Land Management Guidelines No.2 - Hierarchy and Application in New Zealand of Environmental Guideline Values.
13. Ministry for the Environment 2002: A Guide to the Management of Cleanfills.
14. Australian National Environmental Protection Council 2013: National Environmental Protection (Assessment of Site Contamination) Measure Schedule B(1): Guideline on the investigation levels for soil and groundwater.
15. Insight Engineering 2026: Remediation Action Plan for 922 Luggate-Cromwell Road (SH6), Cromwell. Reference #24019_RAP

10 Limitations

- i. We have prepared this report in accordance with the brief as provided. This report has been prepared for the use of our client, Fulton Hogan Land Development Ltd C/- Tim James Ltd, their professional advisers and the relevant Territorial Authorities in relation to the specified project brief described in this report. No liability is accepted for the use of any part of the report for any other purpose or by any other person or entity.
- ii. The recommendations in this report are based on the ground conditions indicated from published sources, site assessments and subsurface investigations described in this report based on accepted normal methods of site investigations. Only a limited amount of information has been collected to meet the specific financial and technical requirements of the client's brief and this report does not purport to completely describe all the site characteristics and properties. The nature and continuity of the ground between test locations has been inferred using experience and judgement and it should be appreciated that actual conditions could vary from the assumed model.
- iii. Subsurface conditions relevant to construction works should be assessed by contractors who can make their own interpretation of the factual data provided. They should perform any additional tests as necessary for their own purposes.
- iv. This Limitation should be read in conjunction with the IPENZ/ACENZ Standard Terms of Engagement.
- v. This report is not to be reproduced either wholly or in part without our prior written permission.

We trust that this information meets your current requirements. Please do not hesitate to contact the undersigned on 021 556 549 if you require any further information. The author is a Certified Environmental Practitioner (CEnvP) under the Environment Institute of Australia and New Zealand (EIANZ) accreditation system.

Preliminary and Detailed Environmental Investigation
922 Luggate-Cromwell Road (SH6), Cromwell

I, Claude Midgley of JKCM Limited, certify that this report meets the requirements of the Resource Management (National Environmental Standard for assessing and managing contaminants in soil to protect human health) Regulations (2011)¹, because it has been:

- Done by a suitably qualified and experienced practitioner (SQEP);
- Reported on in accordance with the current edition of Contaminated Land Management Guidelines No 1: Reporting on contaminated sites in New Zealand; and
- Certified by a SQEP.

Evidence of the qualifications and experience of the suitably qualified and experienced practitioner who has undertaken this investigation and certified this report is included in Appendix 7

Report prepared and certified by



Claude Midgley
CEnvP, MSc.
Principal Environmental Scientist



Appendix 1

Figures



Description	Site Location Plan	Figure Number	1	
Project	Preliminary and Detailed Site Investigation 922 Luggate-Cromwell Road, Cromwell	Date	Jun-26	
Client	Fulton Hogan Land Development Limited c/- Tim James Limited	Drawn by	CM	
Project Number	24019_3	Approved by	JK	



Description	Sample Location Plan	Figure Number	2
Project	Preliminary and Detailed Site Investigation 922 Luggate-Cromwell Road, Cromwell	Date	Jun-26
Client	Fulton Hogan Land Development Limited c/- Tim James Limited	Drawn by	CM
Project Number	24019_3	Approved by	JK



Appendix 2

Proposed Subdivision Plan

LEGEND

- ➊ Possible Primary School
- ➋ Neighbourhood Centre and Preschool
- ➌ Lakeside Park
- ➍ SH6 Landscape Buffer



Appendix 3

Site Photographs



Photo 1: Above-ground diesel storage tank at the asphalt plant.



Photo 2: No evidence of petroleum hydrocarbons in the bunded area.



Photo 3: Above-ground bitumen storage tank at the asphalt plant.



Photo 4: Bitument disposed to ground near the asphalt plant.



Photo 5: Waste bitumen disposed to ground south east of the cleanfill stockpile, facing west.



Photo 6: Waste bitumen disposed to ground south east of the cleanfill stockpile, facing south.

Description	Site Photographs	Photos	1 to 6	
Project	Preliminary and Detailed Site Investigation 922 Luggate-Cromwell Road, Cromwell	Date Taken	6/11/26	
Client	Fulton Hogan Land Development Limited c/- Tim James Limited	Taken by	CM	
Project Number	24019_2	Approved by	JK	



Photo 7: Southern face of the cleanfill stockpile at the eastern end, viewed from the east facing west.




Photo 8: Relatively small stockpile in the cleanfill area at the north eastern corner of the site, facing south west.



Photo 9: Eastern face of the cleanfill stockpile, viewed from the east facing north west.



Photo 10: Example of non-soil inclusions in the cleanfill stockpile.



Photo 11: Southern face of the cleanfill stockpile at the western end, facing east.




Photo 12: Surface of the cleanfill stockpile, facing north east.

Description	Site Photographs	Photos	7 to 12	
Project	Preliminary and Detailed Site Investigation 922 Luggate-Cromwell Road, Cromwell	Date Taken	6/11/26	
Client	Fulton Hogan Land Development Limited c/- Tim James Limited	Taken by	CM	
Project Number	24019_2	Approved by	JK	

Appendix 4

e3scientific PSI Report



**Parkburn Quarry
Preliminary Site
Investigation**

Fulton Hogan Limited

December 2021



Arrow Lane Arrowtown 9302

www.e3scientific.co.nz

**Parkburn Quarry
Preliminary Site Investigation**

Document Status

Version	Purpose of Document	Prepared By	Reviewer	Review Date
0.1	Draft for internal review	L. Salemink Waldren & S. Beardmore	G. Davis	20/10/21
0.2	Draft for client review	S. Beardmore	G. Davis	20/10/21
1.0	FINAL	S. Beardmore	G. Davis	6/12/21



TABLE OF CONTENTS

1	Introduction	6
1.1	Purpose	6
1.2	Proposed Development	6
1.3	Scope of Work	7
1.4	Limitations	8
2	Site Location and Description	10
2.1	Site Location	10
2.2	Topography	11
2.3	Geology	11
2.4	Hydrogeology	12
3	Site History	15
3.1	Historical Certificates of Title, Maps and Surveys	15
3.2	Historic Aerial Photography	15
3.3	District Council Information	17
3.4	Regional Council Information	20
3.5	Previous Investigation Reports	21
4	Site Inspection	22
4.1	Weighbridge and offices	24
4.2	Industrial Area	24
4.3	Cleanfill and Yards	26
	4.3.1 Cleanfill and Hardfill XRF Results	28
4.4	Quarry Area	29
4.5	Balance of the site	31
5	Summary of HAIL Activities	32
5.1	Identified HAIL Activities	32
5.2	Non-HAIL Areas	33
5.3	Integrity Assessment	35
6	Preliminary Conceptual Site Model	36
6.1	Sources	36
	6.1.1 Concrete manufacture	37
	6.1.2 Asphalt manufacture	37
	6.1.3 Fuel storage	38
	6.1.4 Persistent pesticide use	38
	6.1.5 Treated timber storage	38
	6.1.6 Waste disposal to land	38
6.2	Receptors and Pathways	39



6.3	Preliminary Risk Assessment	39
7	Activity Status under the NESCS	42
8	Summary and Conclusions	44
9	Report Certification	46
10	References	47

LIST OF FIGURES

Figure 1: Draft concept plans	7
Figure 2: Site Location (topographic)	10
Figure 3: Site location (aerial)	11
Figure 4: Registered bores within 1 km of the site	13
Figure 5: Site Layout	23
Figure 6: Weighbridge and offices	24
Figure 7: Industrial area activities	25
Figure 8: Cleanfill and yards area	27
Figure 9: Quarry layout	30
Figure 10: Approximate spatial extent of HAIL areas	35

LIST OF TABLES

Table 1: Summary of Site Location and Description	14
Table 2: Summary of Aerial Images and Maps	16
Table 3: Identified HAIL Activities	33
Table 4: HAIL activities and potential contaminants	36
Table 5: Preliminary conceptual site model	41

LIST OF APPENDICES

Appendix A: e3Scientific Limited Contaminated Land Experience
Appendix B: Historic Certificates of Title
Appendix C: Historic Aerials
Appendix D: Otago Regional Council Supporting Information
Appendix E: Site Photographs
Appendix F: XRF Screening Results



Executive Summary

Fulton Hogan Limited (FHL) operate Parkburn Quarry, immediately north of Pisa Moorings. The quarry was developed by FHL in the 1980s and has been in operation since this time. The quarry produces a range of aggregates, from sealing chip to construction and concrete aggregates. As the site is nearing the end of its operational lifespan, Fulton Hogan are seeking a plan change to rezone the site so that it can be redeveloped for a range of future land uses upon closure.

Currently, a range of activities associated with quarry operation take place on site, including asphalt production, concrete batching and block manufacture, disposal of cleanfill, and fuel storage. These activities are listed on the Ministry for the Environment's Hazardous Activities and Industries List (HAIL) and therefore any subdivision, change of use, or soil disturbance where these activities occur will be subject to the provisions of the National Environmental Standard for Assessing and Managing Contaminants in Soil to Protect Human Health (NESCSCS).

To assist Fulton Hogan in managing the risks associated with contaminants in soil, e3Scientific has undertaken a Preliminary Site Investigation (PSI) to identify the areas of potential contamination within the site, consider the risks to human health associated with the proposed development, consider the activity status of the future development under the NESCSCS, and assess the need for further investigation.

Based on the review of site history information and a site inspection, six discrete HAIL activities were identified. HAIL activities identified during this investigation include commercial concrete manufacture, asphalt manufacture, fuel storage, persistent pesticide use associated with the orchard, bulk storage of treated timber and waste disposal to land associated with the cleanfill. These HAIL activities are predominantly located in the industrial area on the northern portion of the property. Within the quarry itself, fuel and bitumen storage were the only HAIL activities identified.

Based on the proposed plan change and eventual development of the site, there is potential for workers and residents to be exposed to contaminants associated with the existing HAIL activities.



Within the future residential area, the identified HAIL activities include relatively small-scale hydrocarbon storage associated with the bitumen spray plant, a diesel tank and waste oil storage, and a diesel generator. It is possible that these activities could leave localised areas of hydrocarbon contamination. Although topsoil will need to be imported to this part of this site, there is a relatively low risk that inhalation of volatile contaminants would remain an open exposure pathway. Any topsoil imported to the site should be certified as meeting the appropriate human health and environmental criteria.

Within the future industrially zoned area, the identified HAIL activities include concrete manufacturing and batching, asphalt production, fuel storage, persistent pesticide use, treated timber storage, and disposal of cleanfill. We consider that it is highly unlikely that contaminants in soil associated with concrete manufacture, persistent pesticide use, and treated timber storage would pose a risk to human under the proposed commercial/industrial land use.

It is possible that contaminants associated with asphalt production, fuel storage and cleanfill disposal could result in soil contamination that could pose a risk to long term outdoor workers using the site in the future without appropriate investigation, remediation and/or management during development. The greatest risks are associated with hydrocarbon storage, particularly around any underground fuel storage infrastructure (e.g. fuel supply pipelines). Risks associated with the disposal of cleanfill appear relatively low; however, given the long history of filling, it is possible that localised areas of contaminated fill material may be present.

Given the on-going use of the site for these HAIL activities, it would be appropriate to complete additional investigation upon decommissioning of any potentially contaminating land uses. These investigations may also be better able to assess risks to human health as plans for the proposed development become more detailed.



1 Introduction

1.1 Purpose

Fulton Hogan Limited (FHL) operate Parkburn Quarry, immediately north of Pisa Moorings. The quarry was developed by FHL in the 1980s and has been in operation since this time. The quarry produces a range of aggregates, from sealing chip to construction and concrete aggregates. As the site is nearing the end of its operational lifespan, Fulton Hogan are seeking a plan change to rezone the site so that it can be redeveloped for a range of future land uses upon closure.

Currently, a range of activities associated with quarry operation take place on site, including asphalt production, concrete batching and block manufacture, disposal of cleanfill, and fuel storage. These activities are listed on the Ministry for the Environment's Hazardous Activities and Industries List (HAIL) and therefore any subdivision, change of use, or soil disturbance where these activities occur will be subject to the provisions of the National Environmental Standard for Assessing and Managing Contaminants in Soil to Protect Human Health (NESCS).

To assist Fulton Hogan in managing the risks associated with contaminants in soil, e3Scientific has undertaken a Preliminary Site Investigation (PSI) to identify the areas of potential contamination within the site, consider the risks to human health associated with the proposed development, consider the activity status of future development under the NESCS, and assess the need for further investigation.

1.2 Proposed Development

Fulton Hogan are proposing to rezone the quarry through a private plan change. Draft concept plans provided by Fulton Hogan indicate that the site could potentially accommodate a wide range of uses, including residential (standard and high density), commercial, retail commercial, childcare / education, green space, and industrial (Figure 1).





Figure 1: Draft concept plans

The residential areas will be located towards the south of the property, where the current quarry operations are located, adjacent to the existing Pisa Moorings development. The residential areas could be located around man-made waterways and inlets, as found in the southern area of Pisa Moorings. The commercial and industrial areas will be located towards the northern boundary of the site, where these types of activities currently take place.

As the developed areas of the quarry have been stripped, topsoil for residential areas will need to be imported, either from off-site or from stockpiles of soil stripped during quarry operations.

1.3 Scope of Work

The scope of work completed during the investigation included the following:

- Review of land use history from historic aerial photographs, certificates of title, Central Otago District Plan (CODC) property files, and information available from the Otago Regional Council (ORC).
- Completion of a site inspection and review of existing physical environment.



- Development of a conceptual site model identifying potential contaminant sources, the possible routes of exposure to contaminants that may be present in soils on the site, and critical receptors.
- Consideration of risks to human health, the need for any further investigation, and the status of the development under the National Environmental Standard for Assessing and Managing Contaminants in Soil to Protect Human Health (the NESCS).
- Preparation of a Preliminary Site Investigation report in accordance with the requirements of the Contaminated Land Management Guidelines (CLMG) No. 1: Reporting on Contaminated Sites in New Zealand (Ministry for the Environment, 2021).

e3Scientific's experience in the provision of contaminated land services is provided in Appendix A.

1.4 Limitations

The findings of this report are based on the Scope of Work outlined above. e3Scientific Limited (e3s) performed the services in a manner consistent with the normal level of care and expertise exercised by members of the environmental science profession. No warranties, express or implied, are made. Subject to the Scope of Work, e3s's assessment is limited strictly to identifying the risk to human health based on the historical activities on the site. The confidence in the findings is limited by the Scope of Work.

The results of this assessment are based upon site inspections conducted by e3s personnel, information from interviews with people who have knowledge of site conditions and information provided in previous reports. All conclusions and recommendations regarding the properties are the professional opinions of e3s personnel involved with the project, subject to the qualifications made above. While normal assessments of data reliability have been made, e3s assumes no responsibility or liability for errors in any data obtained from regulatory agencies, statements from sources outside e3s, or developments resulting from situations outside the scope of this project.

Observations and assessments of the site are relevant to the time of inspection and the scope of this assessment. Investigations were limited to the site



investigation area. e3Scientific notes that the continued operation of the site could result in contamination that may alter the status of the site under the NESCS.



2 Site Location and Description

2.1 Site Location

The area under investigation (the site) is located at 922 and 922A Luggate-Cromwell Road (SH6) (see Figures 2 and 3). The site is situated between Lake Dunstan and the state highway, approximately 8 km north of Cromwell.

The property to the immediate north of the site is owned by Downer EDI Limited, and accommodates a quarry, associated support buildings and infrastructure associated with civil construction and road maintenance. Beyond the Downer EDI quarry, the land is primarily agricultural (pastoral) with some rural residential use. The southern boundary backs onto the Pisa Moorings residential housing development. The land west of the site, opposite SH6, is used for a combination of lifestyle, grazing and viticulture. Lake Dunstan lies immediately to the east of the site. A public walkway/cycleway traverses the lakeside marginal strip along the lake edge. From the southern boundary, the site extends approximately 980 m to the north and covers an area of approximately 120 ha.

The central coordinates of the site are E: 1304358 N: 5014130 (NZTM)




Figure 2: Site Location (topographic)






Figure 3: Site location (aerial)

The site is zoned Rural in Central Otago District Council District Plan, and eastern portion of the site is subject to Scheduled Activity notation SA25A – ‘Gravel Pit Parkburn.’

2.2 Topography

Natural ground at the site slopes gently in a southward direction with an elevation 220 m above mean sea levels in the northwest corner to 199 m above mean sea level in the southeast corner. The local topography is highly influenced by the operation of the quarry, with active faces approximately 10 m high in the southern part of the site.

2.3 Geology

Based on the 1:250,000 Geological Map of New Zealand, the site is situated primarily on Late Pleistocene River deposits consisting of unweathered to slightly weathered, loose, sandy well-rounded gravel usually on the large outwash plains. There is a small section on the central northern boundary of the site that is situated on Holocene River deposits. These consist of loose commonly angular, boulders,



gravel, sand and silt forming alluvial fans; grades into scree (upslope) and valley alluvium (GNS Science, 2021).

2.4 Hydrogeology

The site overlies the Pisa Groundwater Management Zone. This zone is not identified in the current Regional Plan: Water or any of its schedules but has been identified in the draft/recommended aquifers on the ORC Water Allocation for Consultants webpage. The Groundwater Management Zone extends through the Late Pleistocene River deposits east of SH6 and Holocene river deposits that extend up the valleys of the foothills that run west of SH6. Groundwater beneath the site flows east through the alluvial terraces towards Lake Dunstan. The aquifer is unconfined with generally highly permeable sediments that are comprised of sandy gravel or sandy cobble gravel and is likely to be hydraulically connected to Lake Dunstan.

There are four bores on site, with reported depths to water ranging from 9.9 to 12.6 metres below ground level (mbgl). e3s examined the bore logs from nearby bores to assess the likely aquifer thickness and permeability. No basement rock was found in nearby bores; however, there was clay at the base of G41/0319 and clay-bound gravels at 30 mbgl in G41/0465 at 40 mbgl, which may function as the base of the aquifer. This indicates the saturated thickness of the aquifer may be 10-15 m.

There are 36 recorded bores within a 1km radius of the site's location (Figure 4). Of these bores, the primary usages are: 14 for Irrigation, 16 for domestic use, 3 for community supply, 2 for commercial/industrial, 1 for investigation, and 1 is unknown.






Figure 4: Registered bores within 1 km of the site

Lake Dunstan borders the site's eastern boundary. The lake is utilised for a wide range of water related pursuits including swimming, fishing and boating. To enable these pursuits, access is provided throughout the length of the Lake, including roads to the north and south of the Quarry. The Park Burn, and associated marginal strip, passes through the north-eastern corner of the site. Visible water races can be seen across the pastoral land in the north of the site. There are also several channels and ponds within the quarry site.



Table 1: Summary of Site Location and Description

Address	922 & 922A Luggate Cromwell road, Mount Pisa, 9393
Legal Descriptions	Section 64-65 Block IV Wakefield Survey District, Part Section 62-63 Block IV, Part Section 63 Block IV Wakefield survey District and Section 1 Survey Office Plan 365897.
Location	North of Pisa Moorings residential area, West of lake Dunstan, East of SH6 and approximately 1.5 km south of Smiths Way.
NZTM Coordinates	E: 1304358 N: 5014130 (NZTM)
Owners	Fulton Hogan Limited
Site area	120 ha
Surrounding Land Uses	North: Agricultural farming, commercial/industrial. East: Lake Dunstan South: Residential housing West: Viticulture
Regulatory Authorities	Regional Authority: Otago Regional Council Local Authority: Central Otago District Council
Zoning	Rural Resource Area
Topography	Sloping from south-east to the north-west corner, but heavily influenced by quarry operations
Geology	Late Pleistocene River deposits
Hydrogeology	Pisa Groundwater Management Zone
Nearest Surface water	Lake Dunstan directly to the east, Park Burn passing through the north-east corner and small water races running through the site.
Current Land Use	Industrial and commercial
Future Land Use	Residential, industrial, and commercial



3 Site History

3.1 Historical Certificates of Title, Maps and Surveys

Online available historical maps and images of the area available from the 1800's to present day were accessed via the National Library Cartographic Collection on 23 September 2021 and MapsPast.org.nz on 19 August 2021.

A perpetual lease for what is now Sections 62 and 63 was issued to Robert Davidson in 1894. The lease was transferred to a series of private owners (some of which are illegible on the scanned copy of the deed) in 1905, 1940, and 1947. In 1983, the eastern portion of the site was acquired by the Crown for electricity generation so that it could be inundated by Lake Dunstan. In 1985, the lease was transferred to Robert and Charles Perriam, farmers, and a new certificate of title (10B/738) was issued. In December 1985, the title was transferred to Fulton Hogan Limited, and a mining license commenced on 20 July 1987. In 2008, two sections were declared to be road and vested with Central Otago District Council, and an adjoining road was stopped and amalgamated with the adjoining land to create the current title (407414).

The land that is now Sections 64 and 65 was also appears to have been leased for agricultural use until it was transferred from the Perriams to Fulton Hogan Limited in 1985.

Historic surveys and certificates of title are provided in Appendix B.

3.2 Historic Aerial Photography

Aerial images sourced from retrolens.nz, the National Library, and from Google Earth Pro and Google maps street view have been reviewed. A summary of notable observations is presented in Table 2. Selected images are included in Appendix C.

The review of aerial photographs was completed using digital copies of the images, which provide higher resolution than those provided in the appendix.



Table 2: Summary of Aerial Images and Maps

Date	Source	Site Observations
07.03.1958	Retrolens	An unsealed driveway runs from SH6, approximately 150 m south of the northern site boundary, across the site, to a house, just beyond the eastern boundary of the site. A small orchard is visible between the driveway and the Park Burn. Most of this orchard lies outside of the site boundary to the east; however, approximately 1000 m ² is within the site. The remainder site is flood irrigated pasture, with several farm tracks and water races visible. The Clutha Mata-Au is approximately 450 m east of the site.
01.03.1975	Retrolens	An irrigation pond has been created south of the orchard visible in the previous image. Four rectangular shapes/structures are visible on the site, two located together within the central parcel and two separated on the southern parcel. The balance of the site continues to be used for flood irrigated pasture. Stacks of felled trees are visible in the central northern portion of the site.
14.11.1976	Retrolens	The majority of the site is similar to the previous image. The rectangular structures visible in the previous image have been removed, with no sign of soil disturbance, suggesting these were most likely bales of hay/feed. Felled trees can still be seen in the central northern section of the site.
20.02.1978	Retrolens	There are no significant changes from the previous image.
17.02.1983	Retrolens	There are no significant changes from the previous image.
19.02.2001	Retrolens	Lake Dunstan has been filled, up to the eastern site boundary. Gravel extraction in the northern portion of the site, on both sides of the Park Burn, has commenced. Two structures associated with present day asphalt plant are visible to the west of Park Burn. There is a small pond visible in the north-east corner of the site. The southern portion of the site remains largely unchanged.
27.02.2003	Retrolens	Quarrying extends further south along the eastern site boundary. The ponds in the north-eastern corner of the site are much larger. The southern portion of the site remains largely unchanged.



Table 2 (continued)

Date	Source	Site Observations
02.2007	Google Earth (c)	A second area of quarrying along the southern boundary, connected to the main driveway by two haul roads, is visible. The ponds in the north-east corner of the site have been filled, and series of small ponds can be seen in pits on the eastern side of the site. In the centre of the northern section, two additional buildings, parking area, and material storage associated with the concrete block manufacturing plant has been established. A gate house and weighbridge has been established near the entrance to the site from SH6. South of the site, Pisa Moorings has been established, with several house and roading infrastructure in place.
10.2011	Google Earth (c)	The layout of the site remains largely the same as the previous image. The quarry to the south has been extended further east and west. The series of ponds in the central/eastern portion of the site have extended further south, and these are in various stages of being filled, with discrete loads of material visible in three of the ponds. The banks of the Park Burn have more vegetation.
12.2015	Google Earth (c)	The overall layout of the site remains unchanged, and the progression of quarrying and filling has continued through the site.
11.2019	Google Earth (c)	The overall layout of the site remains unchanged, and the progression of quarrying and filling has continued through the site. Two more locations have been setup as work yards with infrastructure in place. Both are within the north-eastern section of the site.
06.2021	Fulton Hogan	A recent drone image shows the site in its current configuration. Again, the overall layout of the site remains unchanged, and the progression of quarrying and filling has continued through the site. South of the site, Pisa Moorings is fully developed.

3.3 District Council Information

e3s was provided resource consent and building consent documentation for the site from the Central Otago District Council.

The following information was found in the property file:



- A 1988 building permit (F037756) to erect an office building at the existing weighbridge.
- A 1990 building permit (H056122) to erect a relocated bitumen storage shed. Plans provided with the application show diesel storage at the weighbridge and asphalt plant, and kerosene near the bitumen shed. The weighbridge is located approximately 120 m southeast of the asphalt plant.
- A 1995 building consent application (BC950406) and associated processing information for the installation a shed at the asphalt plant. Plans provided with the application show diesel storage at the weighbridge and asphalt plant.
- A 2004 building consent application (BC040935) and associated processing information for the installation of a prefabricated Portacom building near a new weighbridge, approximately 250 m from the site entrance. The Portacom building was used as an office and washroom and included a single chamber septic tank and wastewater disposal field.
- 2005 building consent and resource consent applications (BC050850 RC050211) and associated processing information for the construction of concrete block processing facility, capable of producing a range of concrete products including masonry, paving stones, landscaping, and other associated building products. The facility is constructed from pre-cast concrete block building and includes a single chamber septic tank and wastewater disposal field. Information in the file also indicates that a 10,000 L diesel tank is used to provide fuel for a boiler, and cement is stored in silo adjacent to the main building. Wash water is channelled into a collection area and settling ponds, after which the water is to be recycled or directed to a soak pit.
- A 2006 building consent application (BC060538) to relocate a Portacom for staff facilities at the weighbridge.
- A 2007 resource consent application (RC070216) and associated processing information for a land use consent to extract and convey sand and gravel. The purpose of the consent was to allow extraction outside of the Scheduled Area provided in the district plan, and to convey these products to the existing processing plant.



- A 2015 building consent application (BC150440) to add an extension to the side of a shed to allow for the installation of a 40,000 L vertical bitumen tank. Plans for the consent show the layout of the asphalt plant, including diesel and kerosene tanks, loading bins, and bitumen spray release.
- A 2015 building consent application (BC150689) and associated processing information for a single pitch storage shed at the concrete block processing facility.
- A 2016 building consent application (BC160880) and associated processing information for the installation of a transportable office on piles near the weighbridge.
- A 2018 building consent application (BC180636) and associated processing information for the foundations and site works for a Portacom office near the weighbridge.
- A 2019 resource consent application (RC190341) and associated processing information to construct three additional relocatable offices/amenities buildings near the weighbridge. The consent was later amended (RC200046) to allow two further Portacom buildings to be established. There are three subsequent building consents (BC200395, BC190440, BC190726) associated with these structures.
- A 2020 resource consent application (RC210112) and associated processing information to build a commercial shed for a glass crushing plant. Power for the crushing plant is provided by a standalone generator. The fuel source for the generator is not described in the application. There is a subsequent building consent (BC210205) to install a recycled glass materials shed.
- A 2020 building consent application (BC200568) and associated processing information to install a Smart Shelter container roof.
- A 2020 building consent application (BC200771) and associated processing information for foundation and drainage works to install an ablution block. Wastewater is discharged to an existing septic tank.
- A 2021 resource consent application (RC210129) and associated processing information to install two 20,000 litre diesel fuel tanks to replace



one 30, 000 litre diesel fuel tank, located approximately 20 m WSW of the asphalt plant. The tank is noted to be scheduled to be removed mid-2021.

None of the Project Information Memoranda for the above consents identified the likely presence of any hazardous substances, and available plans did not specify the use of any asbestos containing materials (ACM). Supporting documentation from the district council is too large to append but can be provided upon request.

3.4 Regional Council Information

e3Scientific reviewed Otago Regional Council's Hazardous Activities and Industries List (HAIL) Register and consent information on 23 September 2021 and requested information on any Resource Management Act incidents or complaints related to the site.

Part of the site is currently recorded on the Otago Regional Council's HAIL database. This piece of land is registered as site number HAIL.00359.01, as verified HAIL site under the category E2: Asphalt or Bitumen Manufacture. The site is noted as a consented asphalt plant. An underground petroleum storage system (UPSS) removal report was received by the ORC from Z Energy in 2015. The investigation confirmed that residual contamination was acceptable for commercial/industrial land use. However, because of the on-going use as an asphalt plant and other areas of hazardous substance storage, this site is recorded with a contamination status of 'partially investigated.' The UPSS removal report is discussed further in section 3.5.

With regards to the balance of the site, the ORC notes that the database is continually under development and should not be regarded as a complete record of all properties in Otago. The absence of available information does not necessarily mean that the property is uncontaminated; rather no information exists on the database.

There are 25 resource consents associated with the site. Of these, thirteen are expired, five are surrendered, and six are current. Eight of the 25 consents are associated with construction of bores or groundwater takes, Seven are associated with discharges to air from an asphalt plant, six are associated with discharges of water, silt and/or sediment to land for processing aggregate, dust suppression, and truck washing, one is associated with a crossing over the Park



Burn, one is to discharge dust from the quarry operation, and one is to discharge solid fill to land for the purpose of backfilling the quarry.

The Otago Regional Council confirmed that there are four Resource Management Act incidents or complaints recorded for the site. Three of these are associated with dust. The fourth was a complaint regarding odour associated with stockpiles of broken glass.

Supporting documentation from the regional council is provided in Appendix D

3.5 Previous Investigation Reports

The only contaminated land investigation report available for the site is a 'Site Assessment for the Removal of an Underground Petroleum Storage System at the Fulton Hogan Asphalt Plant, Parkburn Quarry, 922 Luggate-Cromwell Road, Cromwell, Central Otago' prepared by Pattle Delamore Partners for Z Energy in 2015.

The report describes the results of soil benchmarking and Tier 1 risk assessment following the removal of a 10,000 L kerosene tank, 10,000 L diesel tank, and associated pipework in October 2014. The two tanks were located end to end in a single tank pit. All thirty samples collected from the tank pit, fuel pipelines and vent risers contained petroleum hydrocarbons below the relevant tier 1 soil acceptance criteria for commercial/industrial land use and for the protection of groundwater quality.

A dispenser within the bituminous emulsion manufacturing building and a 7 m section of pipeline were not removed at the time, and two new aboveground tanks replaced the removed UPSS.



4 Site Inspection

e3s staff conducted a site walkover on the 28th of September 2021. e3s staff were accompanied by Matt Goulding, Fulton Hogan's Central Quarries Operations Manager.

The site inspection was conducted in accordance with the Contaminated Land Management Guidelines No. 5: Site investigation and analysis of soils (revised 2021) (Ministry for the Environment, 2021).

Information gathered during site inspections included:

- General site condition, current use, local topography, and surrounding environmental setting.
- The condition of the buildings.
- The nature of the ground surface across the site.
- The location and condition of surface watercourses, drainage systems, and any groundwater wells.
- Visible signs of contamination or potential contamination, such as evidence of spills or leaks, surface staining, absent or stressed vegetation, and odours.
- Visible signs of areas of fill, stockpiled material, waste, ground disturbance, burnt areas, and former building foundations.
- The location of any chemical storage and transfer areas, bunding, waste storage areas, and discharges.
- The land use of neighbouring properties that have the potential to have an impact on the site or be affected by contamination from the site.
- The location of former buildings, processes or activities undertaken on the site.

The wider site layout is shown in Figure 55, and descriptions of the main parts of the site are provided in the following sections. Site photographs and observations are provided in Appendix E.






Figure 5: Site Layout



4.1 Weighbridge and offices

The weighbridge and site offices are located approximately 250 m from the SH6 entrance to the property.

There are five Portacom style buildings in addition to the weighbridge. All buildings appeared to be in good condition. The surface cover is predominantly hard stand, gravels, and landscaped areas (Figure 66).




Figure 6: Weighbridge and offices

There was no evidence of any hazardous substance use or storage in this area.

4.2 Industrial Area

Approximately 200 m east of the weighbridge, approximately 7.5 ha of land is used for industrial activity, predominantly related to asphalt and concrete manufacturing.

Activities in this area include: the Firth Concrete block manufacturing facility, the Fulton Hogan asphalt plant, the Allied Concrete batching plant, a yard formerly



used for producing pre-cast concrete panels for the Frankton Marina, a truck wash, and truck parking area (Figure 77).




Figure 7: Industrial area activities

The Firth Concrete block manufacturing facility is located on the western end of the industrial area. The gravel yard was generally tidy and well kept. A 10,000 L diesel tank is located to the east of the manufacturing building (1). An open storage shed is located along the western boundary of this area. A small, waste oil 'igloo' was present to the south of the open shed (2). There was no staining around the waste oil tanks. Several empty drums of concrete retardant (Sika Retarder) were stored behind (west of) the open shed. Hardfill, consisting of broken concrete tiles and blocks was deposited over the landscape bund, north of the factory (3).

East of the Firth Concrete block manufacturing facility, an open yard is used as a parking area by Fulton Hogan Transport. An above ground diesel tank (4) associated with the nearby asphalt plant, was removed from the site in September 2021. Evidence of disturbed ground beneath the removed tank, including some soil on a plastic sheet, was still present. There was no evidence of staining or odour in this area. Underground fuel lines, running to the asphalt plant are reportedly still present.



The asphalt plant itself is located down an embankment to the east of the parking area. The plant is comprised of aggregate feeder bins, bitumen storage tanks, mixing drum, conveyor belt feeding, asphalt storage silos, a bag house and an operations office. The asphalt plant can produce up to 120 tonnes per hour (tph) of asphalt but will typically run at a production rate of approximately 80 tph. Bitumen and kerosene are stored in a bunded above ground tank at the base of the terrace. Bitumen is also stored in a shed near the plant. The ORC resource consent specifies that the plant can be run on used oil; however, to date only diesel fuel has been used.

The Allied Concrete batching plant is located on the opposite side of the main access road from the transport yard. The batching plant appears to be located at the repurposed weighbridge, where diesel fuel storage was noted in plans with several of the building consent applications. Immediately south of the batching plant, there is a gravel yard which was used by a company to produce concrete panels for the construction of the Frankton Marina in 2018. These areas appeared generally tidy.

A truck wash is located on the south side of the main access road. Run-off from the truck wash flows down the side of the access road into an infiltration pond. This is one of the discharge points authorised by ORC consent RM15.108.02. There was no oily sheens or hydrocarbon odour associated with the run-off water or sediment at the truck wash.

4.3 Cleanfill and Yards

On the opposite side of the Park Burn, an area of past quarrying is now used for cleanfill disposal and for outdoor yards used by JCL Asphalt Limited and several divisions of Fulton Hogan (Figure 8).






Figure 8: Cleanfill and yards area

A new shed, which will be used for crushing and storage of recycled glass, has been constructed. This building was consented under RC210112. During the site inspection, drainage work was being completed, but storage and crushing of glass had not yet commenced.

Beyond the new glass processing shed, an excavation is used for disposal of surplus concrete. Further to the east, there are two active (1-2 m high) faces used for cleanfill disposal. A concrete bay just east of the weighbridge at the entrance to the site is used for drop-off of small loads of cleanfill by Fulton Hogan and their sub-contractors. This material is then relocated to the cleanfill face. Visible material was predominantly soil, rock, and gravel, with occasional loads of cured asphalt, and some scattered broken glass across the surface of the cleanfill. A separate area is used for disposal of hardfill, including concrete, tile, bricks, and cured asphalt, as well as soil, gravel and rock. Disposal of material at the cleanfill is authorised by ORC resource consent 99664.

A Cleanfill Management Plan prepared by Fulton Hogan outlines the procedures required to achieve environmental best practice. Visual inspections of the quality of the fill material coming to the site are completed to ensure the material is consistent with resource consent requirements. If a non-complying load is



identified, the cleanfill operator is to isolate the load and advise the Quarry Manager immediately. Signage is in place at the entrance to the cleanfill, providing a clear description of acceptable materials. Material is not to be accepted from any Hazardous Activities and Industries List (HAIL) sites unless it has been suitably analysed.

A partially buried skip is used for temporary storage of waste from high pressure water cutting used during roading maintenance work. The skip is covered and sealed, with waste periodically taken to landfill when full.

To the east of the hardfill disposal area, finished areas of the cleanfill have been capped with gravel for use as open yards for other divisions of Fulton Hogan, as well as JCL Asphalt.

At the JCL Asphalt yard, there is a moveable above ground diesel tank located in the corner of the container shelter (1). Some soil staining was also visible. In this area, there were also 4 x 1,000 L IBC of concrete additive (Sika Viscacrete), with some visible product on the ground below the IBCs. The Fulton Hogan civil engineering and construction yards were predominantly used for the storage of building supplies and equipment. There were two small steel explosive storage containers (2) used by the Fulton Hogan geotechnical team. There was also a stack of CCA treated telephone poles (3) in the construction yard. Otherwise, there was no evidence of hazardous substance storage or use in these areas, and surface gravels were free of staining.

4.3.1 Cleanfill and Hardfill XRF Results

An Olympus Vanta field portable X-Ray Fluorescent Spectrophotometer (XRF) was used to collect in-situ field readings of heavy metal concentrations at 40 locations within the active faces of the cleanfill and hardfill disposal area, and across the finished cleanfill surface. For comparison, 10 readings were also taken from undisturbed ground under the pine trees, north of the cleanfill area to provide an estimate of naturally occurring background concentrations. Although not as precise as laboratory analysis, use of an XRF enables a rapid screening-level assessment of soil contaminant concentrations. A table of XRF screening results is provided in Appendix F, and raw results exported from the instrument are available upon request.



XRF instrument checks were undertaken in accordance with e3Scientific's XRF standard operating procedure. These included checking the functionality of the XRF, performing an energy calibration and checking the calibration of the XRF with a certified reference material (NIST 2711a) and a silicon dioxide blank, monitoring analysis time, and ensuring the integrity and cleanliness of the XRF sampling window throughout the sampling.

To collect readings, samples were checked for large non-representative debris, e.g. large pebbles or roots, and these were removed from the sample prior to analysis with the XRF. Soil was gently tamped down to provide a uniform surface for the instrument window. One reading was taken from each location, using two beams, with analysis times of 30 seconds and 3 seconds.

All instrument blank readings returned results of 0.0 parts per million (ppm), with the exception of one zinc reading, which measured at 7.0 ppm. This reading may have been associated with dust within the instrument. Given the range of concentrations detected on site (53 to 385 ppm), this is not considered significant.

One or more heavy metals in 14 out of the 40 samples exceeded the background concentration established using the XRF; however, for 4 of these, the exceedance was by less than 35%, within the expected precision of the XRF. Three samples exceeded the Manaaki Whenua Landcare Research (2015) predicted background concentration by more than 35%, indicating that there is a higher likelihood that contaminants in excess of the local natural background were present in these samples.

4.4 Quarry Area

The active quarry occupies approximately 60 hectares over the southern half of the site. Extraction of sand and aggregate within the eastern two-thirds of the site is allowable under the Scheduled Activity designation in the district plan. Quarrying in the western third of the site is authorised by RC070216, which was issued in 2007. The current layout of the quarry is shown in Figure 99 below.






Figure 9: Quarry layout

Topsoil and overburden are stripped from the natural ground surface in advance of the active quarry faces (1). Within the consented quarry area, the extracted material is transported, using a conveyor belt system (2), to the crushing plant (3). Water is sprayed over aggregate as it passes through the plant on a screened conveyor. Debris and sediments are washed off the gravels, and wash water from the processing plant is discharged through a sludge channel to a series of silt ponds (4), which remove sediment from the water. No flocculants are used in this process. Water evaporates or infiltrates through gravels at the base of the ponds. After processing, the sorted material is stored at the site prior to dispatch.

Surplus pea gravel (4.5 to 8 mm gravels) from processing is used for reclamation within the quarry. These gravels are currently being used to form a 1V:3H batter along the southern face of the quarry (5). Topsoil stripped from the site is then placed over the pea gravels and grassed (6).

Roading chip produced at the processing plant is sprayed with a bitumen emulsion at a processing plant in the quarry (7). Bitumen is stored in a 30,000 L tank. The bitumen-coated chip is stored in separate stockpiles at the quarry.



North of the processing plant, there is a small fuel storage area, which includes a moveable double skinned diesel tank, and a bunded waste oil storage area (8). A storage area (9) near the shed is used for miscellaneous equipment and parts.

Mobile crushing (10) and screening (11) plants are used within the eastern portion of the quarry. These machines are periodically refuelled by a mobile diesel delivery service.

A small generator (12) with an in-built diesel tank is located within this part of the quarry. The diesel powers a generator used to supply power to pump for dust suppression. There was no evidence of soil staining or spills near the generator.

4.5 Balance of the site

The balance of the site is predominantly undeveloped pasture. The land is not currently grazed and there was no evidence of contaminating activities.

In the forested area to the west of the Firth Concrete plant, there was some old equipment and occasional surface litter, but not to the extent that soil contamination is likely.

The area occupied the orchard visible in the early aerial images was vacant land, and partially occupied by a bund. Topsoil from this area appeared to have been stripped in the past.



5 Summary of HAIL Activities

5.1 Identified HAIL Activities

The Ministry for the Environment's Hazardous Activities and Industries List (HAIL) is a compilation of activities and industries that have the potential to cause land contamination resulting from hazardous substance use, storage, or disposal. The HAIL is intended to identify most situations in New Zealand where use and storage of hazardous substances could cause, and in some cases have caused, land contamination.

Based on the review of site history information and a site inspection, several separate HAIL activities were identified. HAIL activities identified during this investigation include commercial concrete manufacture, asphalt manufacture, fuel storage, persistent pesticide use associated with the orchard, bulk storage of treated timber and waste disposal to land associated with the cleanfill. The identified HAIL activities are summarised in Table 3.



Table 3: Identified HAIL Activities

HAIL Activity	Dates	Comment	Likelihood
E4. Commercial concrete manufacture or commercial cement storage	2005 - present	Concrete block manufacturing facility	Certain
E2. Asphalt or bitumen manufacture or bulk storage (excluding single-use sites used by a mobile asphalt plant)	1987 - present	Asphalt plant	Certain
A17. Storage tanks or drums for fuel, chemicals or liquid waste	<1990-2004	Various fuel storage	Possible
A10. Persistent pesticide bulk storage or use including sport turfs, market gardens, orchards, glass houses or spray sheds	<1958~1985	1000 m ² of orchard	More likely than not
A18. Wood treatment or preservation including the commercial use of anti-sapstain chemicals during milling, or bulk storage of treated timber outside	~2020 - present	250 m ² of treated timber storage	Certain
G5. Waste disposal to land (excluding where biosolids have been used as soil conditioners)	1987 - present	Cleanfill	Likely

5.2 Non-HAIL Areas

Based on a review of site history information and observations on site, it is more likely than not those activities listed on the HAIL have *not* been undertaken on the site outside of those areas identified in section 5.1.

There is no evidence of HAIL activities having occurred through the balance of pastoral land through the site. There is no evidence of stock yards, sheep dips, woolsheds, farm landfills or other rural HAIL activities on the site in any historic aerial photographs.

It is likely that routine applications of superphosphate and DDT would have occurred during the period of low intensity productive use as farmland. These agrichemicals were commonly used to fertilise soil and control pests such as grass grub. e3Scientific has assessed Organochlorine Pesticides (such as DDT) and



cadmium (a contaminant associated with superphosphate) concentrations in soils throughout Otago and Southland. In all investigations, contaminants have only been encountered at elevated concentrations approaching NESCS soil contaminant standards in the vicinity of sheep dips, sheep footbaths, dusting yards and areas of historic agrichemical storage. It is highly unlikely the broadacre application of agrichemicals over the farm have occurred at a rate and intensity that would result in an accumulation of contaminants in concentrations that could present a risk to human health or the environment. As such, this activity is not considered a HAIL activity.

It is known that several on-site wastewater treatment and disposal systems have been used to treat domestic-type effluent from small offices and ablution blocks. These small-scale systems are considered as being of sufficient size or risk to be interpreted as HAIL sites under category HAIL category G6: *Waste recycling or waste or wastewater treatment*. Hazardous substances associated with wastewater effluent primarily come from commercial and industrial trade wastes that discharge to the sewer network. The primary risk to human health from domestic wastewater is associated with biological hazards, such as viruses and bacteria. These pathogens fall outside the scope of hazardous substance and contaminated land regulation but should be considered a matter for worker health and safety if excavation into the disposal fields were to be necessary.

Although mining industries are listed under HAIL Category E7, gravel extraction is explicitly excluded from this category, and the extraction and processing of aggregate at the Parkburn Quarry is not considered a HAIL activity.

Within the Fulton Hogan civil engineering yard, two small steel containers were used for storing explosives. Although HAIL Category C1 includes '*explosive or ordinance production, maintenance, dismantling, disposal, bulk storage or re-packaging,*' we do not consider the quantity stored to be considered of sufficient scale to be considered a HAIL activity.

Although waste recycling is listed under HAIL Category G6, we consider that the storage and crushing of glass should not be considered a HAIL activity, as it does not involve the storage, use or disposal of hazardous substances.

Prior to the development of the quarry, the only identified HAIL activity was the presence of a small (1,000 m²) orchard. Topsoil within the former orchard may have contained concentrations of organochlorine or heavy metal persistent



pesticides. Topsoil stripped from the site is typically used for reclamation and creating bunds on site, and it is possible that soil from the orchard has been reused or relocated on site. However, the volume of topsoil from this area, perhaps 200 m³, is relatively small compared to the volume of soil that has been stripped throughout life of the quarry, perhaps 150,000 m³. With incidental mixing of soils as they are stockpiled and moved around site prior to and during reclamation, we do not consider the reuse of topsoil to be a HAIL activity.

Outside the areas identified in Section 5.1, it is more likely than not that no activities or industries listed on the HAIL have occurred. The approximate spatial extents of HAIL and non-HAIL areas are shown in Figure 10.




Figure 10: Approximate spatial extent of HAIL areas

5.3 Integrity Assessment

Overall, the established site history spans a period of approximately 120 years. Information obtained from the historic certificates of title and maps, historic aerial images (with a maximum interval of 18 years between 1983 and 2001), local authorities, and a site walkover has provided a reasonable understanding of the site history.



6 Preliminary Conceptual Site Model

A conceptual site model (CSM) for assessing site contamination provides an overview of the interaction between contaminants on site and potential receptors. Also referred to as the pollutant linkage model, the conceptual site model consists of three components (source-pathway-receptor), which if linked, indicate a risk may be present.

The following section sets out a preliminary conceptual site model. This preliminary conceptual site model is based on the collated information including an understanding of the possible contaminant sources, the possible routes of exposure to contaminants that may be present in soils on the site, and critical receptors.

6.1 Sources

A summary of the hazardous activities that have occurred on the site and the contaminants that may be associated with these activities is presented in Table 4 and described in the following sections. The contaminant list in Table 4 is based on site-specific observations and Appendix C of the NESCS User's Guide (Ministry for the Environment, 2012).

Table 4: HAIL activities and potential contaminants

HAIL Activity	Locations	Potential Contaminants
Concrete manufacture	Firth Concrete Block Plant Allied Concrete Batching Plant Frankton Marina Concrete Plant	Cement, calcium hydroxide, alkalis, ammonia, additives
Asphalt manufacture	Fulton Hogan Asphalt Plant	Total petroleum hydrocarbons (TPH) Polycyclic Aromatic Hydrocarbons (PAH)
Fuel storage	Diesel generator, bitumen spray, diesel and waste oil storage	Total petroleum hydrocarbons (TPH) Polycyclic Aromatic Hydrocarbons (PAH)



Persistent pesticide use	Former orchard	Heavy metals Organochlorine Pesticides
Treated timber storage	Fulton Hogan construction yard	Copper, chromium, arsenic
Waste disposal to land	Cleanfill area	Heavy metals

6.1.1 Concrete manufacture

Commercial concrete manufacture has taken place on site since 2005. Contaminants associated with concrete manufacture may affect soil pH and stormwater quality; however, risks to human health are generally not considered significant.

In addition to the contaminants listed in Table 4, small quantities of concrete retarding admixture are used within the concrete block manufacturing plant. The active ingredient in this product is tetrapotassium pyrophosphate. Tetrapotassium pyrophosphate is a common food additive, and not considered particularly toxic. The material safety data sheet (MSDS) does not list any special environmental protections required and does not identify the product as toxic to people.

A 10,000 L diesel tank and waste oil igloo are also known to be present within the concrete block manufacturing facility, and it is suspected diesel storage also occurred at the Allied Concrete batching plant in the past.

6.1.2 Asphalt manufacture

The asphalt manufacturing plant has operated on site since 1987. Asphalt manufacture involves the storage and handling of petroleum hydrocarbons including diesel, kerosene, and bitumen. Once manufactured and cured, asphalt is relatively stable, and unlikely to leach significant quantities of contaminants.



6.1.3 Fuel storage

Outside of the asphalt and concrete block plants, there are four known areas of relatively small-scale fuel storage. These include a diesel tank, waste oil storage, and generator at the quarry plant and diesel storage at the JCL asphalt yard.

6.1.4 Persistent pesticide use

Approximately 1,000 m² of orchard was present on the site from at least 1958 until 1985. During this period, organochlorine and heavy metal pesticides are likely to have been used on site. These contaminants typically bind strongly to soils and are not readily leached through the soil profile.

Topsoils from within the footprint of the former orchard were stripped as part of quarry development, and it is unlikely that pesticide residues are still present within this area. As discussed in section 5.2, topsoil stripped from the site is typically used for reclamation or creating bunds on site, and it is possible that soil from the orchard has been reused or relocated on site. However, the volume of topsoil from this area, perhaps 200 m³, is relatively small compared to the volume of soil that has been stripped throughout life of the quarry, perhaps 150,000 m³. With incidental mixing of soils as they are stockpiled and moved around site prior to and during reclamation, it is unlikely that detectable concentrations of pesticides could be found on site.

6.1.5 Treated timber storage

A relatively small area within the Fulton Hogan construction yard has been used for storage of treated timber poles. Although this activity has only occurred recently, and appears to be for relatively short duration, leaching of copper, chromium and arsenic from tanalised timber can impact soils directly under the poles. Although leaching from treated timber stacks can pose a risk to human health under residential land use, results from previous investigations suggest that exceedance of commercial/industrial soil contaminant standards is unlikely (Marlborough District Council, 2016)

6.1.6 Waste disposal to land

Backfilling of the north-eastern portion of the site with cleanfill has taken place since the 1980's.



This activity was consented by the Otago Regional Council in November 2000, and the cleanfill generally appears to be well managed. ORC compliance reports in 2009 and 2020 identified minor non-compliance associated with reporting, but both inspections found the site to be tidy with no evidence of unconsented fill types or adverse environmental effects. A cleanfill management plan for the Parkburn Quarry was prepared by Fulton Hogan in 2018.

The management plan provides clear direction on consent and unconsented fill types and confirms that material from HAIL sites is not to be accepted without prior sampling.

Field readings of heavy metal concentrations with an X-Ray Fluorescent Spectrophotometer (XRF) indicates that heavy metal concentrations within most of the soil within the cleanfill surface and tipping faces are consistent natural background concentrations. A small number of readings returned results that indicate some contaminated fill material has been received.

6.2 Receptors and Pathways

Based on the proposed plan change and eventual development of the site, potential receptors will vary throughout the site. Because HAIL activities have been identified in areas proposed to be used for industrial and residential purposes, potential receptors will include:

- Construction workers involved in the development of the site.
- Outdoor workers in the industrial or commercially zoned areas.
- Adults and children living on the site in the residential and childcare areas.

Exposure pathways for contaminants to these potential receptors include:

- Incidental ingestion of contaminated soil.
- Inhalation of contaminants entrained in dust or volatile contaminants.
- Dermal absorption of contaminants.
- Consumption of produce grown in soils on site.

6.3 Preliminary Risk Assessment

A conceptual site model, based on the identified sources, pathways and receptors above is described in Table 5.



Based on the proposed plan change and eventual development of the site, there is potential for workers and residents to be exposed to contaminants associated with the existing HAIL activities.

Within the future residential area, the identified HAIL activities include relatively small-scale hydrocarbon storage associated with the bitumen spray plant, a diesel tank and waste oil storage, and a diesel generator. It is possible that these activities could leave localised areas of hydrocarbon contamination. Although topsoil will need to be imported to this part of this site, there is a relatively low risk that inhalation of volatile contaminants would remain an open exposure pathway. Any topsoil imported to the site should be certified as meeting the appropriate human health and environmental criteria.

Within the future industrially zoned area, the identified HAIL activities include concrete manufacturing and batching, asphalt production, fuel storage, persistent pesticide use, treated timber storage, and disposal of cleanfill. We consider that it is highly unlikely that contaminants in soil associated with concrete manufacture, persistent pesticide use, and treated timber storage would pose a risk to human under the proposed commercial/industrial land use.

It is possible that contaminants associated with asphalt production, fuel storage and cleanfill disposal could result in soil contamination that could pose a risk to long term outdoor workers using the site in the future without appropriate investigation, remediation and/or management during development. The greatest risks are associated with hydrocarbon storage, particularly around any underground fuel storage infrastructure (e.g. fuel supply pipelines). Risks associated with the disposal of cleanfill appear relatively low; however, given the long history of filling, it is possible that localised areas of contaminated fill material may be present.

Given the on-going use of the site for these HAIL activities, it would be appropriate to complete additional investigation upon decommissioning of any potentially contaminating land uses. These investigations may also be better able to assess risks to human health as plans for the proposed development become more detailed.



Table 5: Preliminary conceptual site model

Area	Source	Exposure Pathway	Possible Receptor	Pathway Linkage Assessment
Future Industrial Zoned Areas	Contaminants associated with asphalt manufacture, fuel storage and disposal of cleanfill	Ingestion of contaminated soil	Long term Outdoor workers and Construction workers involved in development of the site	Potentially complete – Site remains to be occupied and utilised by various commercial/industrial businesses.
		Dermal contact with contaminated soil and dust		
		Inhalation of volatile contaminants or contaminated dust		
Future residential zoned areas	Contaminants associated with hydrocarbon storage	Ingestion of contaminated soil	Residents	Incomplete – Residential development will require topsoil to be imported, either from off-site or from stockpiles of soil stripped during quarry operations. As such, direction exposure is unlikely.
		Dermal contact with contaminated soil and dust		
		Consumption of home grown produce		
		Inhalation of volatile contaminants or contaminated dust	Construction workers involved in development of the site	Potentially complete (volatile contaminants) – Inhalation of volatile contaminants may be a potentially complete pathway, even after topsoil has been imported.
		Ingestion of contaminated soil		
		Dermal contact with contaminated soil and dust		
		Inhalation of volatile contaminants or contaminated dust		Potentially complete – Construction workers involved in earthworks on site may be exposed to contaminants associated with fuel storage.



7 Activity Status under the NESCS

Preliminary investigation of the site has identified areas of HAIL activity on discrete pieces of land throughout the site. As such, the NESCS will apply to subdivision, change of use, and soil disturbance associated with the development of the site if the plan change is approved.

7.1 Subdivision and Land Use Change

Regulation 8(4) of the NESCS states that subdividing land or changing the use of a piece of land is a permitted activity while the following requirements are met:

- (a) A preliminary site investigation of the land or piece of land must exist
- (b) The report on the preliminary site investigation must state that it is highly unlikely that there will be a risk to human health if the activity is done to the piece of land.
- (c) The report must be accompanied by a relevant site plan to which the report is referenced.
- (d) The consent authority must have the report and the plan.

In this case, we do not consider that the requirements of Regulation 8(3) are currently fully met. We consider the proposed zoning associated with the plan change to be generally suitable; however, given the on-going use of the site for HAIL activities, it would be appropriate to complete additional investigation upon decommissioning of any potentially contaminating land uses. These investigations may also be better able to assess risks to human health as plans for the proposed development become more detailed.

7.2 Soil Disturbance and Removal

Regulation 8(3) states that disturbing the soil of the piece of land is a permitted activity while the following requirements are met:

- a) Controls to minimise the exposure of humans to mobilised contaminants must:
 - i) be in place when the activity begins.
 - ii) be effective while the activity is done.
 - iii) be effective until the soil is reinstated to an erosion-resistant state.
- b) The soil must be reinstated to an erosion-resistant state within 1 month after the serving of the purpose for which the activity was done.



- c) The volume of the disturbance of the soil of the piece of land must be no more than 25 m³ per 500 m².
- d) Soil must not be taken away in the course of the activity, except that,—
- e) For the purpose of laboratory analysis, any amount of soil may be taken away as samples.
- f) For all other purposes combined, a maximum of 5 m³ per 500 m² of soil may be taken away per year.
- g) Soil taken away in the course of the activity must be disposed of at a facility authorised to receive soil of that kind:
- h) The duration of the activity must be no longer than 2 months:
- i) The integrity of a structure designed to contain contaminated soil or other contaminated materials must not be compromised.

Based on disturbance over the entire area of HAIL activity (160,000 m²) a maximum of 8000 m³ could be disturbed in any one year, and 1600 m³ can be removed.

Any soil disturbance or removal within the identified HAIL areas that do not meet the permitted activity criteria outlined in Regulation 8(3) would be a discretionary activity under Regulation 11 unless a Detailed Site Investigation (DSI) to quantify contaminant concentrations is completed.



8 Summary and Conclusions

Fulton Hogan Limited (FHL) operate Parkburn Quarry, immediately north of Pisa Moorings. The quarry was developed by FHL in the 1980s and has been in operation since this time. The quarry produces a range of aggregates, from sealing chip to construction and concrete aggregates. As the site is nearing the end of its operational lifespan, Fulton Hogan are seeking a plan change to rezone the site so that, upon closure, it can be redeveloped for a range of future land uses, including residential (standard and high density), commercial, retail commercial, childcare / education, green space, and industrial.

To assist Fulton Hogan in managing the risks associated with contaminants in soil, e3Scientific has undertaken a Preliminary Site Investigation (PSI) to identify the areas of potential contamination within the site, consider the risks to human health associated with the proposed development, consider the activity status of the future development under the NESCS, and assess the need for further investigation.

Based on a detailed review of site history information, HAIL activities identified during this investigation include commercial concrete manufacture, asphalt manufacture, fuel storage, persistent pesticide use associated with the orchard, bulk storage of treated timber and waste disposal to land associated with the cleanfill.

We consider that it is highly unlikely that contaminants in soil associated with concrete manufacture, persistent pesticide use, and treated timber storage would pose a risk to human under the commercial/industrial land use proposed for these areas.

It is possible that contaminants associated with asphalt production, fuel storage and cleanfill disposal could result in soil contamination that could pose a risk to long term outdoor workers using the site in the future without appropriate investigation, remediation and/or management during development. The greatest risks are associated with hydrocarbon storage, particularly around any underground fuel storage infrastructure (e.g. fuel supply pipelines). Risks associated with the disposal of cleanfill appear relatively low; however, given the



long history of filling, it is possible that localised areas of contaminated fill material may be present.

Given the on-going use of the site for these HAIL activities, it would be appropriate to complete additional investigation upon decommissioning or closure of any potentially contaminating land uses. At that stage, we consider that it would be appropriate to develop a number of feasible strategies for remediation and/or site management if necessary.



9 Report Certification

I, Simon Beardmore of e3Scientific, certify that:

1. This preliminary site investigation meets the requirements of the Resource Management (National Environmental Standard for assessing and managing contaminants in soil to protect human health) Regulations 2011 because it has been:
 - a. done by a suitably qualified and experienced practitioner, and
 - b. reported on in accordance with the current edition of Contaminated land management guidelines No 1 – Reporting on contaminated sites in New Zealand, and
 - c. certified by a suitably qualified and experienced practitioner.

2. This preliminary site investigation does **not** conclude:
 - a. it is highly unlikely that there will be a risk to human health if the subdivision and/or land use change described in Section 1.2 is done to the piece of land.

Evidence of the qualifications and experience of the suitably qualified and experienced practitioner(s) who have done this investigation and have certified this report is included in Appendix A.



Signed and dated:06/12/21.....



10 References

- GNS Science. (n.d.). *New Zealand Geology Web Map*. Retrieved from <http://data.gns.cri.nz/geology/>
- Landcare Research Manaaki Whenua. (2015). *Background soil concentrations of selected trace elements and organic contaminants in New Zealand*. .
- Ministry for the Environment. (1999). *Guidelines for Assessing and Managing Petroleum Hydrocarbon Contaminated Sites in New Zealand Module 4- Tier 1 Soil Screening Criteria (revised 2011)*. Ministry for the Environment.
- Ministry for the Environment. (2003). *Contaminated Land Management Guidelines No. 2: Hierarchy and Application in New Zealand of Environmental Guideline Values*. .
- Ministry for the Environment. (2003a). *Contaminated Land Management Guidelines No. 1: Reporting on Contaminated Sites in New Zealand (revised 2011)*. Wellington: Ministry for the Environment.
- Ministry for the Environment. (2004). *Contaminated Land Management Guidelines No. 5: Site Investigation and Analysis of Soils (Revised 2011)*.
- Ministry for the Environment. (2004). *Module 2: Hazardous Waste Guidelines - Landfill Waste Acceptance Criteria and Landfill Classification*. Wellington: Ministry for the Environment.
- Ministry for the Environment. (2011). *Methodology for Deriving Standards for Contaminants in Soil to Protect Human Health*. Wellington: Ministry for the Environment.
- Ministry for the Environment. (2011). *Soil Contaminant Standards in the Methodology for Deriving Standards for Contaminants in Soil to Protect Human Health*. Ministry for the Environment.
- Ministry for the Environment. (2012). *Users' Guide: National Environmental Standard for Assessing and Managing Contaminants in Soil to Protect Human Health*. Wellington: Ministry for the Environment.
- NEPC. (1999). *National Environment Protection (Assessment of Site Contamination) Measure 1999*, amended 2013.
- US EPA. (2018). *Regional Screening Levels*. US Environmental Protection Agency.



Appendices

Appendix A:
e3Scientific Limited Contaminated Land Experience



Contaminated Land Services

e3Scientific Limited (e3Scientific) is a New Zealand owned and operated environmental science consultancy. Our team delivers technical, innovative science; practical solutions; and expert advice to assist our clients in the smart management of the environment.

e3Scientific provides a range contaminated land services, including:

- Due Diligence Investigations.
- Preliminary Site Investigations.
- Detailed Site Investigations.
- Soil and groundwater remedial advice and management.
- Peer review and regulator support.

Our Contaminated Land team has a sound understanding of New Zealand's regulatory environment with respect to the assessment and management of contaminated land and has been a major supplier of contaminated land services in Otago and Southland since 2012.

Simon Beardmore is the Technical Director of the Contaminated Land team at e3Scientific. Simon has over 12 years post graduate experience working as an Environmental Scientist, specialising in the investigation and management of contaminated land. Simon developed contaminated land management strategy and standard operating procedures at the Otago Regional Council and has completed and supervised the delivery of preliminary and detailed site investigations, and site remediation projects throughout Otago and Southland. Simon is responsible for technical oversight of projects and certifying contaminated land investigations as a suitably qualified and experienced practitioner. Simon is supported by Team Leader Fiona Rowley, Senior Environmental Scientists Carrie Pritchard, Jodi Halleux and Simon Bloomberg, and Environmental Scientist and Geospatial Specialist Jessie Lindsay.

The e3Scientific team has completed many Preliminary Site Investigations, Detailed Site Investigations and remedial projects across New Zealand and regularly provides peer review of site investigations for district and regional councils. Projects have involved investigations into the impact on soil quality associated with operational and historic timber treatment plants, fuel storage and distribution facilities, substations, sheep dips and yards, orchards, vineyards, agricultural activities, gasworks, service stations, and operational and closed landfills.





The following provides a summary of key contaminated land work e3Scientific is involved in or has completed:

- Hundreds of Preliminary Site Investigations and Detailed Site Investigations to support subdivision, landuse change and earthworks consent applications.
- Support Environment Southland's Selected Landuse Register including the identification of Hazardous Activities on properties across Southland and the registration of HAIL sites.
- Review of groundwater contamination associated with the former Invercargill gasworks site including the completion of a groundwater investigations and an environmental risk assessment to support a discharge consent application.
- Large scale remedial works of former timber treatment plants and sheep dips including the completion of detailed investigations to delineate the extent of contaminated soils, design of remedial action plans, project management of remedial works and completion of site validation and council close out reports.
- Investigations into an area of arsenic impacted soils in Frankton including the completion of detailed investigations to delineate the horizontal extent, consideration of the source of the arsenic, liaison with property owners and council.
- Project management of a bioavailability study of arsenic impacted soils in Gibbston Valley to support a Tier 2 risk assessment associated with a residential development.
- Oversight of the removal of multiple underground fuel storage systems for private residences, schools and oil and gas clients.

The e3Scientific team is committed to professional development, and employing new technologies in the prevention, assessment and remediation of contaminated land. e3Scientific is an active member of the Australasian Land & Groundwater Association and WasteMINZ.




Appendix B:
Historic Certificates of Title



RECORD OF TITLE
UNDER LAND TRANSFER ACT 2017
FREEHOLD
Search Copy




R.W. Muir
Registrar-General
of Land

Identifier **407414**
Land Registration District **Otago**
Date Issued 07 February 2008

Prior References
GN7705203.1 OT10B/738

Estate Fee Simple
Area 50.1065 hectares more or less
Legal Description Part Section 62-63 Block IV and Part
Section 63 Block IV Wakefield Survey
District and Section 1 Survey Office Plan
365897

Registered Owners
Fulton Hogan Limited

Interests


Subject to Section 8 Mining Act 1971(affects part formerly in CT OT10B/738)
Subject to Section 5 Coal Mines Act 1979(affects part formerly in CT OT10B/738)
5041663.1 Gazette Notice (2001/1044) declaring adjoining road (S.H.No. 6) to be limited access road - 11.5.2001 at 9:31 am
5057376.2 Notice pursuant to Section 91 Transit New Zealand Act 1989 - 10.7.2001 at 2:30 pm

Title Diagram ct 40741

Cpy - 01/01, Pgs - 001, 22/02/08, 09:06



DocID: 212144396



Total area: 50.1065 ha

For further dimensions see SO 365897 & SO 20808


CANCELLED

No. 10A / 748

Renewable Lease under the Land Act 1948

This Deed, made the 1st day of July 1982, between HER MAJESTY THE QUEEN (hereinafter referred to as "the Lessor"), of the one part, and CHARLES ROBERT REPPAS of Lowerm Farmer

(hereinafter referred to as "the Lessee"), of the other part WITNESSETH that, in consideration of the rent hereinafter reserved, and of the covenants, conditions, and agreements herein contained and implied, and on the part of the Lessee to be paid, observed, and performed, the Lessor doth hereby demise and lease unto the lessee, all that parcel of land containing by admeasurement 67.8380 hectares more or less, situated in the Land District of Otago, and being Sections 64 and 65 Block IV Wakefield Survey District



TOTAL AREA 67.8380 ha
SQ 20838

as the same is more particularly delineated with bold black lines on the plan hereon, together with the rights, easements, and appurtenances thereto belonging. TO HOLD the said premises intended to be hereby demised unto the Lessee for the term of 33 years, commencing on the 1st day of

July 1982 together with the period between the date of this lease and the aforesaid 1st day of

1982, YIELDING and paying therefor for the first 11 years of the said term unto the Department of Lands and Survey at Dunedin

the annual rent of \$792.00 calculated on a Rental Value of \$17600.00

payable without demand by equal half-yearly payments in advance on the 1st day of January and the 1st day of July in each and every year during the said period of 11 years, and for the next two successive periods of 11 years of the said term a rent determined in respect of each of those periods in the manner provided in section 132A of the Land Act 1948. AND also paying in respect of the improvements specified in the Schedule hereto the sum of \$

by a deposit of \$ (which has already been paid), together with interest thereon at the rate of per

centum per annum and thereafter by half yearly instalments of \$ on

the 30th day of June and the 31st day of December in each and every year subject to variation of the rate of interest and the amount of the half yearly

instalments in the manner hereinafter provided. The first such instalment shall be payable on the 31st day of December 1982.

Interest on the balance of the purchase money from the day of 1982 to the day of 1982 shall be payable on the said day of

AND it is hereby declared and agreed (1) That these presents are intended to take effect as a renewable lease of Farm land under section 63 of the Land Act 1948 and of any enactments passed in amendment or substitution thereof and the provisions of the said Act and of the regulations made thereunder applicable to such leases shall be binding in all respects upon the parties hereto in the same manner as if such provisions had been fully set out herein.

(2) That the Land Settlement Board, pursuant to its powers under section 170B of the Land Act 1948, reserves the right to review the rate of interest payable by the Lessee in the respect of the improvements specified in the Schedule hereto for the second and each ensuing period of 5 years of the term hereof, and the provisions of that section shall apply to any such review, and any necessary adjustments to the instalments payable.

Assistant
IN WITNESS whereof the Commissioner of Crown Lands for the said Land District, on behalf of the Lessor, has hereunto set his hand,
and these presents have also been signed by the said Lessee

10A 748
No. 1

Assistant
Signed by the said Commissioner, on behalf of the Lessor,
in the presence of—
Witness *W. Clump*
Occupation *C. L. K., Dept. Land & Survey*
Address *Dunedin*
Assistant Commissioner of Crown Lands

Signed by the above named Lessee in the presence of—
Witness: *[Signature]*
Occupation: *[Signature]*
Address: *[Signature]*
Lessee *E. R. Perriam*

Interests at date of Issue:

X20543 Irrigation Agreement under Part X1 of the
Public Works Act 1928 with Her Majesty the Queen
- 9.12.1958 at 2.40 pm.

X20544 Irrigation Agreement under Part X1 of the
Public Works Act 1928 with Her Majesty the Queen
- 9.12.1958 at 2.41 pm.

394308 Mortgage to Bank of New Zealand - 2.11.1972
at 11.09 am.

506155 Compensation Certificate pursuant to Section
17 of the Public Works Amendment Act 1948 - 1.11.1978
at 11.59 am.

[Signature]
A.L.R.

638087/2 Transfer to Robert Stanley
Perriam of Lowburn Farmer - 2.7.1985
at 10.37am

[Signature]
A.L.R.

638087/3 Mortgage to Charles Robert
Perriam - 2.7.1985 at 10.37am

[Signature]
A.L.R.

648690) Cancelled and new C.T. 10B/1452
13.12.1985) issued for the within land

[Signature]
A.L.R.

44572E-2,000/3/80 MK



DUPLICATE DESTROYED

11/13/1986


10.24 23.NOV.84 626107/13
PARTICULARS ENTERED IN REGISTER
LAND REGISTRY OTAGO
ASST. LAND REGISTRAR



COMPUTER FREEHOLD REGISTER UNDER LAND TRANSFER ACT 1952

Historical Search Copy




R.W. Muir
Registrar-General
of Land

Identifier

OT10B/738

Cancelled

Land Registration District **Otago**

Date Issued 26 August 1985

Prior References

OT115/31

Estate	Fee Simple
Area	50.2450 hectares more or less
Legal Description	Section 62-63 Block IV Wakefield Survey District

Original Proprietors

Fulton Hogan Limited

Interests

Subject to Section 8 Mining Act 1971

Subject to Section 5 Coal Mines Act 1979

Mining Licence embodied in register 9D/212 - 3.8.1987 at 9:08 am

5041663.1 Gazette Notice (2001/1044) declaring adjoining road (S.H.No. 6) to be limited access road - 11.5.2001 at 9:31 am

5057376.2 Notice pursuant to Section 91 Transit New Zealand Act 1989 - 10.7.2001 at 2:30 pm

5879308.1 Expiry of Mining Permit 684068 - 29.1.2004 at 9:00 am

7705203.1 Gazette Notice (2008 page 360) declaring Section 3 SO 365897(317m2) and Section 4 SO 365897 (6009m2) to be road and vested in the Central Otago District Council on 31.1.2008 and stopping the adjoining road (Section 1 SO 365897 -4940m2) and amalgamating it with the within land CT 407414 issued- 7.2.2008 at 9:00 am

CANCELLED

Reference:

Certificate No. 641455
P.R. Vol. 115 Folio 31
Transfer No.



REGISTER

No. 10B/738

CERTIFICATE OF TITLE UNDER LAND TRANSFER ACT

This Certificate dated the 26th day of August one thousand nine hundred and eighty five under the seal of the District Land Registrar of the Land Registration District of O T A G O being a Certificate in lieu of Grant, **WITNESSETH** that ROBERT STANLEY PERRIAM of Lowburn, Farmer

is seised of an estate in fee simple (subject to such reservations, restrictions, encumbrances, liens, and interests as are notified by memorial underwritten or endorsed hereon) in the land hereinafter described, delineated with bold black lines on the plan hereon, be the several admeasurements a little more or less, which said land was originally acquired by the abovenamed

as from the 17th day of December one thousand nine hundred and eighty four under Section 124A Land Act 1948 that is to say: All that parcel of land containing 50.2450 hectares more or less being Sections 62 and 63 Block IV WAKEFIELD DISTRICT

Interests at date of issue:

ASSISTANT LAND REGISTRAR

Subject to the reservations and conditions imposed by Section 8 Mining Act 1971 and Section 5 Coal Mines Act 1979


X20543 Irrigation Agreement under Part XI Public Works Act 1951 12.1958 at 2.40pm

649433 Transfer to Fulton Hogan Limited - 23.12.1985 at 1.43pm

X20544 Irrigation Agreement under Part XI Public Works Act 1951 9.12.1958 at 2.41pm

638087/3 Mortgage to Charles Robert Perriam - 2.7.1985 at 10.37am

684068 Mining Licence under the Mining Act 1971 affecting part of the within land in favour of Fulton Hogan Limited for a term of 21 years commencing on 20 July 1987 - 3.8.1987 at 9.08 am
See Volume 9D Folio 212



Scale 1:12500 S.O. 20808
Total Area: 50.2450ha


Measurements are Metric

Register copy for L. & D. 69, 71, 72



RECORD OF TITLE
UNDER LAND TRANSFER ACT 2017
FREEHOLD
Search Copy




R.W. Muir
Registrar-General
of Land

Identifier **OT10B/1452**

Land Registration District **Otago**

Date Issued 13 December 1985

Prior References

OT10A/748

Estate	Fee Simple
Area	67.8380 hectares more or less
Legal Description	Section 64-65 Block IV Wakefield Survey District

Registered Owners


Fulton Hogan Limited

Interests

Subject to Section 8 Mining Act 1971

Subject to Section 5 Coal Mines Act 1979

5041663.1 Gazette Notice (2001/1044) declaring adjoining road (S.H.No. 6) to be limited access road - 11.5.2001 at 9:31 am



Reference to the original
Image Quality due to Condition of Original

NEW ZEALAND.
CANCELLED

(Crown Lands Form No. 51)

Register-book.

Vol. 115 fol. 31

Application No.

115/31

Clay LAND DISTRICT.

LEASE IN PERPETUITY UNDER PART III. OF "THE LAND ACT, 1892," AND
SECTION 7 OF "THE MINING ACT AMENDMENT ACT (No. 2), 1893."

No. 829.

This Deed, made the 6th day of October, 1897, between Her Majesty the Queen (who with her heirs and successors is hereinafter termed "the Lessor"), of the one part, and Robert Davidson

of Lamburn Ferry in the Land District of Clay

Block IV Wakefield District

189 ac. 25 per.

EQUIVALENT METRIC

AREA IS 80.5957 ha
605706 31.4080 ha
49.1877 ha
611 832/4 50.2450 ha

in the Colony of New Zealand (hereinafter, with his executors, administrators, and permitted assigns, referred to as and included in the term "the Lessee"), of the other part, Edithnessly that, in consideration of the rent hereinafter reserved, and of the covenants, conditions, and agreements herein contained and implied and on the part of the Lessee to be paid, observed, and performed, the Lessor doth hereby demise and lease unto the Lessee All that piece or parcel of land, containing by admeasurement One hundred and Ninety nine (199) acres

roods and breaky five (25) perches, a little more or less, situated in the Land District of Clay aforesaid, and being Section numbered 9 and 16, Block IV Survey District of Wakefield, as the same is more particularly delineated and described in the plan drawn hereon, and therein

coloured red in outline; together with the rights, easements, and appurtenances to the same belonging:


To hold the said several premises intended to be hereby demised unto the Lessee for the term of nine hundred and ninety seven and a half years, commencing from the 1st day of January next

yielding and paying therefor unto the Receiver of Land Revenue for the said District of Clay the annual rent of Three pounds twelve shillings and eight pence

(£ 3 : 12 : 8), payable half-yearly in advance on the 1st day of January and 1st day of July in each and every year during the said term, free from all deductions whatsoever this being a

And it is hereby declared and agreed that these presents are intended to take effect as a lease in perpetuity under Part III. of "The Land Act, 1892"; and the provisions of that statute applicable to such leases, so far as the same apply to the term, estate, or interest hereby granted or created, and to the relations between the Lessor and Lessee from time to time, shall, subject to the provisions of section 7 of "The Mining Act Amendment Act (No. 2), 1893," be binding in all respects upon the parties hereto in the same manner as if such provisions had been fully set out herein: And it is hereby further declared that if any dispute or disagreement shall arise between the parties hereto touching the construction of these presents, or in anywise relating hereto, such dispute or disagreement shall be referred to arbitration in the manner set forth in section 79 of the said Act; and neither of the said parties shall take or cause to be taken any steps or proceedings to set aside or call in question any award or decision which may have been given upon any such reference as final:

In Witness whereof the Commissioner of Crown Lands for the Land District of Clay on behalf of the Lessor, hath hereunto set his hand, and these presents have been also executed by the said Lessee,



Scale: 30 chains to an inch.

Signed by the said Commissioner, on behalf of the said Lessor, in the presence of—

James de la Gorge
Wellington

Signed by the above-named

Robert Davidson

as Lessee, in the presence of—

James de la Gorge
Wellington

James de la Gorge

Robert Davidson

Transfer No. 40542 Robert Davidson to
 Lillian Macpherson of Lowburn Parkhouse
 entered 2nd September 1905 at 11.00

Transmission No. 12215 to Susan Hill of Auckland
 Road, Lowburn, Wairarapa entered 27th September 1905 at 10.00

Mortgage No. 54614 Susan Hill Macpherson to
 Robert Davidson Superintendent produced
 1905 at 10.00

Transmission No. 2692 to Ernest Jolly of Cromwell
 Merchant as Executor entered 20th June 1940
 at 11.30.00

Transfer No. 152214 Ernest Jolly to William Henry Perriam
 and Charles Robert Perriam of Auckland entered
 produced 1st November 1940 at 11.00

Mortgage No. 107136 William Henry Perriam and
 Charles Robert Perriam to the Bank of New Zealand
 produced 1st November 1940 at 12.00

Transfer No. 155697 William Henry Perriam
 and Charles Robert Perriam to the Bank of New Zealand
 entered 1947 at 11.00

220543 Imposition Agreement under Part 21 of the Public Works Act
 1928 between Her Majesty the Queen and Charles Robert
 Perriam entered 9th December 1958 at 2.40.00

220544 Imposition Agreement under Part 21 of the Public Works Act
 1928 between Her Majesty the Queen and Charles
 Robert Perriam entered 9th December 1958 at 2.40.00

344308 Mortgage to Bank of New Zealand -
 DISCHARGED
 2.11.1972 - at 10.09.00 am

THIS REPRODUCTION (ON A REDUCED SCALE)
 CERTIFIED TO BE A TRUE COPY OF THE
 ORIGINAL REGISTER FOR THE PURPOSES OF
 SECTION 215A LAND TRANSFER ACT 1952.

503342 Certificate of Charge under
 Section 280(1) Public Works Act
 1928 - 13.9.1978 at 4.42 pm

506156 Compensation Certificate pursuant to
 section 17 of the Public Works Amendment Act
 1948 - 1.11.1978 at 11.59 am

605706 Gazette Notice declaring parts of
 Sections 9 (1.95 ha, 2.42 ha, 4800 m²)
 and 16 (206580 ha) shown hatched black on
 the diagram hereon are acquired for the
 generation of electricity and shall vest
 in the Crown from and after the 27th day
 of October 1983 - 21.11.1983 at 10.56 am

The within land is now known as Sections
 62 (1.3250 ha) and 63 (48.92 ha) Block IV
 Wakefield S.D. - 20.3.1984 at 11.51 am
 See Re-appellation 611832/4

626107/1 Certificate of alteration with
 effect from 27.10.1984 reducing the
 rental value to \$118.94 and annual rent
 to \$4.76 - 23.11.1984 at 10.24 am.

638087/2 Transfer to Robert Stanley
 Perriam of Lowburn Farmer - 2.7.1985
 at 10.37am

638087/3 Mortgage to Charles Robert
 Perriam - 2.7.1985 at 10.37am

641455) Cancelled and new C.T.
 26.8.1985) 103/738 issued.

DISTRICT LAND
 REGISTRAR

CANCELLED

OTAGO
 NEW ZEALAND

DUPLICATE DESTROYED

9 19 1985

No. 829.
DATED 6th October 1897.

Her Majesty the Queen

Robert Davidson

Sup. Land District.

LEASE

Of Section 9 & 16, Block 11.


Wakefield Survey District.

Under "The Land Act, 1892."

Nine hundred and ninety-nine years from

1st January 1898.

Entered at 10 o'clock on the 24th day
of October 1897.



District Land Registrar.

SECTIONS 141 TO 147 OF "THE LAND ACT, 1892."

Compulsory Residence.

141. Residence on any land, not being land purchased for cash, selected under this Part of this Act shall be compulsory, and shall commence in bush-lands or on swamp-lands within four years, and in open or partly open land within one year, from the date of selection; and thereafter such residence shall be continuous—

(1.) On lands occupied with right of purchase, for six years on bush-lands or on swamp-lands, and for seven years on open or partly open land;

(2.) On lease-in-perpetuity lands, for a term of ten years.

But these conditions of residence shall not apply to any person who has acquired an interest in any lease or license under an intestacy or by virtue of a will.

142. The Board may dispense with residence if the lessee or licensee reside and continue to reside on lands contiguous to the lands held under lease or license. Lands shall be deemed to be contiguous to each other if only separated by a road or stream, or by such interval of space as the Board may determine in each case.

The Board may also dispense with residence for four years after the commencement of the term where residence is otherwise compulsory in cases where the lessee or licensee are youths or unmarried women living within the land district, and residing with their parents or near relatives.

In case of the death of either or both parents of a child or children, residence may be dispensed with until such child or one of such children respectively attain the age of seventeen years.

143. Personal residence may also be dispensed with by the Board in the cases hereinafter mentioned:—

(1.) Whenever any two persons, being licensees with right of purchase or leases in perpetuity, have lawfully intermarried at some period not sooner than twelve months after the issue of the last of such licenses or leases, such persons may reside on such one of the selections of land made by them as they may think fit.

(2.) Whenever any two persons, one of whom has become a selector of land with right of purchase or a lessee in perpetuity, and the other is an owner or occupier of freehold land, have lawfully intermarried at some period not sooner than twelve months from the issue of the license or lease held by such selector, such selector may reside on such freehold.

(3.) Residence on such selection or on such freehold, as may be the case, shall be deemed a compliance with the conditions of section one hundred and forty-one in respect of residence by such several persons.

(4.) The Board, however, shall have a discretionary power to dispense with personal residence on sufficient and satisfactory grounds being shown for non-residence.

Improvements.

144. Every selector of lands under this Part of this Act, whether for occupation with right of purchase or for lease in perpetuity, shall put on the land comprised in his license or lease, as the case may be, substantial improvements—

(a.) Within one year from the date of his license or lease, to a value equal to ten per centum of the price of the land;

(b.) Within two years from the date of his license or lease, to a value equal to another ten per centum of the price of the land;

(c.) And thereafter, but within six years from the date of his license or lease, to a value equal to another ten per centum of the price of the land;

And in addition thereto shall, within six years from the date of his license or lease, put substantial improvements of a permanent character on first-class land to the value of one pound for every acre of such land, and on second-class land to an amount equal to the net price of every acre of such land: Provided that in no case shall the additional improvements required on second-class land be more than ten shillings per acre.

And every selector shall be bound at any time when so required by the Board to make and sign a statutory declaration as to his fulfilment of the conditions of occupation and improvement of the land in his occupation up to the time of making the said declaration.


145. Any holder of bush-lands or swamp-lands on deferred payments under section one hundred and fourteen of "The Land Act, 1887," or in any special settlement under regulations made before the twenty-seventh day of February, one thousand eight hundred and ninety-one, under Part V. of such Act, and any holder of a perpetual lease of any land under section one hundred and forty-eight of such Act, shall be deemed to have complied with the requirements of section twenty-one of "The Land Act Amendment Act, 1887," if within six years from the date of his license or lease he has brought or shall bring into cultivation twice the amount of land required by the herein first above-mentioned sections or regulations respectively, and in addition thereto has put or shall put substantial improvements of a permanent character on the land in his occupation to the value of one pound for every acre of such land.

146. In the case of suburban lands the Board in its discretion may dispense with conditions as to improvements of special monetary value, where such substantial improvements have been effected as in the opinion of the Board are reasonable in the circumstances.

147. The Board, on compliance with the provisions of section eighty-three, or on their being satisfied by a statutory declaration that the transferee is unable or not in a position to make the improvements on the land required by this Act, may sanction a transfer, either by way of mortgage or otherwise, of land other than such land, or of any interest in such land, held under this Part of this Act, at any time after the first selection thereof, to any person not disqualified who shall make the declaration under the particular system under which the land is held, as given in the Schedules to this Act.



1939




0 500 1000 1500 m



 Site Boundary

1949



0

500

1000

1500 m



 Site Boundary

1979



Rahoy

80



1000

 Site Boundary

Cartography sourced from <http://mapspast.org.nz> which includes data licensed by LINZ for reuse under the CC-BY 3.0 license.

1989



0

500

1000

1500 m



 Site Boundary



 Site Boundary



 Site Boundary

Appendix C:
Historic Aerials

1958




0 400 800 1200 m



 Site Boundary

Aerial image sourced from <http://retrolens.nz> and licensed by LINZ for reuse under the CC-BY 3.0 license.

1975




0 400 800 1200 m




 Site Boundary

1976



0 400 800 1200 m



Aerial image sourced from <http://retrolens.nz> and licensed by LINZ for reuse under the CC-BY 3.0 license.

1978



0 400 800 1200 m



 Site Boundary

1983



0 400 800 1200 m



 Site Boundary

2001



0 400 800 1200 m



 Site Boundary

Aerial image sourced from <http://retrolens.nz> and licensed by LINZ for reuse under the CC-BY 3.0 license.

2003



 Site Boundary

Aerial image sourced from Google Earth Pro, Maxar technologies.

2007

Untitled Map

Write a description for your map.



800 m



0 400 800 1200 m

 Site Boundary

Aerial image sourced from Google Earth Pro, Maxar technologies.

2011



0 400 800 1200 m



 Site Boundary

Aerial image sourced from Google Earth Pro, Maxar technologies.

2015



0 400 800 1200 m



 Site Boundary

Aerial image sourced from Google Earth Pro, Maxar technologies.

2019



0 400 800 1200 m



 Site Boundary

Aerial image sourced from Google Earth Pro, Maxar technologies.

2021



 Site Boundary

Aerial image sourced from Fulton Hogan

Appendix D:
Otago Regional Council Supporting Information

From: [Contaminated Land](#)
To: [Simon Beardmore](#)
Subject: RE: Parkburn Quarry
Date: Friday, 10 September 2021 3:04:07 PM
Attachments: [image002.png](#)
[image001.png](#)
[image003.jpg](#)
[CURRENT - Annual Works Programme - Parkburn Quarry - Updated June 20.docx](#)

Hi Simon,

No problem, find attached the cleanfill's Annual Works Programme.

There are five incidents on file for Parkburn Quarry, these being:

- **IN17.0186** (01/04/2017) – Complaint about dust at Pisa Moorings as it was windy from the North. ORC contacted Fulton Hogan and informed them of the complaint and that they need to check their water system.
- **IN16.0790** (22/07/2016) – Complaint the quarry was stockpiling broken glass and glass bottles in the yard and there was a strong smell associated with it. Complainant was concerned it might cause something to leach into the lake.
- **IN16.0406** (07/04/2016) – Complaint about clouds of dust coming from the quarry on a windy day (wind coming from the north). The complainant informed ORC they couldn't see over the bund but felt that dust mitigation should always be employed when the weather conditions are windy.
- **IN15.1172** (30/11/2015) – Complaint about dust coming from the quarry and hours that the crushing plant should be working. The complainant informed ORC that the crushing plant has been operating all day up to 10:30pm and starting up again at 4:30am. Complainant was wanting to know whether there was a constraint on the crushing plant working hours.
- **IN08.0001** (12/07/2008) – Burn off by Works Infrastructure.

Let me know if you need any further information.

Have a great weekend.

Thanks,
Shannen



Shannen Barns
ENVIRONMENTAL OFFICER

shannen.barns@orc.govt.nz
www.orc.govt.nz

Important notice

This email contains information which is confidential and may be subject to legal privilege. If you are not the intended recipient, you must not peruse, use, disseminate, distribute or copy this email or attachments. If you have received this in error, please notify us immediately by return email or telephone (03 474-0827) and delete this email. The Otago Regional Council accepts no responsibility for changes made to this email or to any attachments following the original transmission from its offices. Thank you.

From: Simon Beardmore [REDACTED]
Sent: Thursday, 9 September 2021 4:07 p.m.
To: Contaminated Land <contaminated.land@orc.govt.nz>
Subject: RE: Parkburn Quarry

Awesome – thanks so much. Two hopefully quick additional queries:

Can you provide a copy of the cleanfill's annual work programme (A1418462)/

Can you check if there have been any RMA incidents recorded for the site?

Thanks again,

Simon Beardmore

From: Contaminated Land <contaminated.land@orc.govt.nz>
Sent: Thursday, 9 September 2021 11:01 AM
To: Simon Beardmore [REDACTED]
Subject: RE: Parkburn Quarry

Hi Simon,

Lastly, find attached the photos from the 2020 audit reports for 99664, 2004.600, RM15.108.01-.02 and RM18.376.01.V1.

As mentioned, if you require any specific PM information please get in touch.

Kind regards,
Shannen



Shannen Barns
ENVIRONMENTAL OFFICER

P 0800 474 082 | M 027 207 9404
shannen.barns@orc.govt.nz
www.orc.govt.nz

Important notice

This email contains information which is confidential and may be subject to legal privilege. If you are not the intended recipient, you

must not peruse, use, disseminate, distribute or copy this email or attachments. If you have received this in error, please notify us immediately by return email or telephone (03 474-0827) and delete this email. The Otago Regional Council accepts no responsibility for changes made to this email or to any attachments following the original transmission from its offices. Thank you.

From: Simon Beardmore [REDACTED]
Sent: Wednesday, 1 September 2021 10:11 a.m.
To: Contaminated Land <contaminated.land@orc.govt.nz>
Cc: Liam Salemink Waldren [REDACTED]
Subject: Parkburn Quarry

Good morning,

Hope you are doing well on this fine Level 3 morning.

We are preparing a preliminary site investigation for Fulton Hogan's Parkburn Quarry.

Would you be able to provide copies of information relating to HAIL.00359.01, including tank pull report and any correspondence

And consents information (application, recommending report, any performance monitoring results, and ORC audit reports) for:

- 99664
- 2004.600
- RM18.376.01.V1
- RM15.108.01-.02
- RM17.359.01 and .03

Thanks very much,



Simon Beardmore
Technical Director - Contaminated Land

d. [REDACTED] m. [REDACTED] w. e3scientific.co.nz



e3Scientific Limited Disclaimer - This message and accompanying data may contain information that is confidential or subject to legal privilege. No confidentiality or privilege is waived or lost by any error in transmission. If you are not the intended recipient you are notified that any use, dissemination, distribution or copying of this message or data is prohibited. If you received this email in error please contact the sender immediately and delete all copies of the message and attachments. We apologise for the inconvenience.

Well Number	Status	Type	Take Consent	Depth	Diameter	Depth To Water	Drill Date	Owner	Location	Driller	Drawdown	Pump Rate	Pump Duration	Use1	Use2	Screen From	Screen To	Bore Consent Number
G41/0465	Completed	Borehole		30.92	0.15	20.07	11/04/2016	Penturen Estates Limited	Luggate-Cromwell Road	McNeill	24.04	1512	150	Irrigation		27.92	30.92	RM16.015.01
G41/0459	Completed	Borehole		30.17	0.4	9.86	18/11/2015	Fulton Hogan Limited	Cromwell	McNeill	22.99	0	0	Commercial	Industrial	24.17	30.17	RM15.310.01
G41/0453	Completed	Borehole		22.8	0.15	12.6	12/08/2015		Cromwell	McNeill	0.35	717.12	120	Irrigation		21.3	22.8	RM15.167.01
G41/0489	Completed	Borehole		28.67	0.15	20.29	2/11/2017	Moonshine Cherries Limited	Adjacent to Luggate Cromwell Road approximately 1,380 metres West of Lake Dunstan	SouthDrill	0.21	0	138.24	Domestic		27.67	28.67	RM17.150
G41/0298				20	0.15	0	1/07/2003		Pisa North development adjacent to Lake Dunstan.		0	0	0	Community Supply		0	0	2003.571
G41/0293				10	0.125	0	5/01/2003		Adjacent to Lake Dunstan at Pisa Moorings, Lowburn		0	71.7	0	Domestic		80.2	81.3	2003.255
G41/0284	Completed	Borehole	RM13.445.01	31.33	0.15	15.45	3/08/2001	Opiki Cropping Ltd	Parkburn Rd, Lowburn-Luggate Rd	McNeill	3	1166.4	0	Irrigation		28.58	31.33	2002.524
G41/0275	Completed	Borehole		34.59	0.15	12.95	24/06/2002		Clarks Rd - Lowburn	McNeill	3.74	432	0	Irrigation		31.65	34.59	2002.339
G41/0267	Completed	Borehole	RM15.093.01	25.06	0.15	14.5	13/09/2002		Pisa Moorings	McNeill	2.35	1814	0	Domestic	Irrigation	22.36	25.06	2002.243
G41/0303	Completed	Borehole	RM17.138.01	25	0.3	0	10/01/2003	Pisa Village Development	approximately 475 metres east of State Highway 6,		0	2592	0	Domestic		81.68	82.5	2003.757
G41/0302	Completed	Borehole	RM17.138.01	25	0.03	0	10/01/2003	Pisa Village Development	approximately 475 metres east of State Highway 6,		0	2592	0	Domestic		29.75	30.45	2003.755
G41/0301	Completed	Borehole	RM15.108.01.V1	30	0.3	0	9/01/2003	Fulton Hogan Ltd	Adjacent State Highway 6, Mount Pisa		0	3456	0	Unknown		0	0	2003.718
G41/0356	Completed	Borehole		23.34	0.15	13	13/12/2007	Apple Bomb Trust	State Highway 6 Cromwell	McMillan	0.07	183	90	Domestic	Irrigation	21.84	23.34	2007.504
G41/0350	Completed	Borehole		29.92	0.15	13.23	26/09/2007	- Linita Trust	Smiths Way	McNeill	0.04	115.2	120	Domestic		0	0	2007.397
G41/0344	Completed	Borehole	RM11.237.01	27.63	0.3	12.97	16/09/2005		Lowburn Cromwell	McNeill	0.71	2764	240	Irrigation		0	0	2005.395
G41/0386	Completed	Borehole	RM16.002.01	27.88	0.125	20.92	22/12/2010	Penturen Estates Ltd	Cromwell Luggate Highway	McNeill	0.26	108	60	Domestic	Stockwater	26.88	27.88	RM10.418
G41/0378	Completed	Borehole	2009.478	19	0.2	3.76	3/02/2010	Pisa Moorings Utilities Society Inc.	Revival Lane and Ferry Lane, Cromwell	SouthDrill	6.05	1382.4	240	Domestic		16	19	2009.478
G41/0159				25	0.1	0	1/04/1997			McNeill	0	95	0	Domestic	Stockwater	0	0	97218
G41/0201				35	0.15	0	27/08/1999	GREENER CAPITAL LTD	SITE B - S SIDE PARK BURN ADJ (W SIDE) SH6	McNeill	0	0	0	Irrigation	Domestic	0	0	99331
G41/0199	Completed	Borehole	RM14.064.01	27.95	0.15	16.42	25/11/1999		Pisa Range Estate, Lowburn-Wanaka Rd	McNeill	2.05	1296	0	Domestic	Irrigation	26.66	27.95	99033
G41/0172	Completed	Borehole	RM17.254.01	28.66	0.15	15.42	12/07/1998		Chard Farm, Lowburn-Wanaka Rd	McNeill	1.67	1123.2	0	Domestic	Irrigation	26.57	28.66	97663
G41/0171			RM17.155.01	12	0.1	0		PISA MOORINGS LTD		McNeill	0	285.1	0	Irrigation		0	0	97607
G41/0227	Completed	Borehole		25	0.31	0	2/03/2001	S Hawker	behind #925 SH6		0	777.6	0	Irrigation		42.6	43.6	2001.162
G41/0226	Completed	Borehole		12.15	0.125	4.38	26/01/2001	Pisa Moorings Ltd c/- Begg I	Adjacent to Lake Dunstan - Cromwell	McNeill	0.02	112.32	0	Domestic		11.05	12.15	2001.064
G41/0215	Completed	Borehole	2000.549	28.44	0.15	15.47	5/05/2000		SH6	McNeill	4.74	1987.2	0	Irrigation		25.28	28.44	2000.094
G41/0205			RM19.253.01	52	0.15	0	27/08/1999		W OF SH 6 ADJ TO ROAD	McNeill	0	1728	0	Irrigation		0	0	99422
G41/0204	Completed	Borehole	2002.326.V1	25.44	0.15	13.44	12/08/1999		Clarks Road adjacent to SH6, Cromwell-Wanaka Rd - Lowburn	McNeill	3.16	777.6	0	Community Supply	Irrigation	23.8	25.44	99383
G41/0244	Completed	Borehole		31	0.15	18.82	5/10/2001		East of State Highway, north of Parkburn Creek. Wanaka Rd	McNeill	6.8	1900	0	Irrigation		27.9	31	2001.821
G41/0240	Completed	Borehole	2001.A47.V1	29.92	0.15	21	6/08/2001		North of Park Burn Creek, Cromwell - Wanaka Highway	McNeill	3.2	950.4	0	Domestic	Irrigation	28.32	29.92	2001.67
G41/0237	Completed	Borehole	2001.82	31.33	0.15	15.45	3/08/2001	Nemarosa Estate	SH6 Wanaka Rd	McNeill	3	1166.4	0	Irrigation		28.23	31.33	2001.525
G41/0102	Completed	Borehole		27.8	0.15	13.25	17/01/1996		Wanaka Rd - Lowburn	McNeill	0	182.4	0	Domestic		24.68	27.8	94552
G41/0004	Abandoned	Borehole		205	0	0	1/10/1978	NZ Geological Survey DL-23			0	0	0	Investigation		0	0	
G41/0132				30	0.1	0	10/07/1996			McNeill	0	121	0	Domestic		0	0	96358
G41/0126	Completed	Borehole		11.16	0.15	3.65	12/09/1995	Pisa Moorings Incorporated	Wanaka Rd - Wanaka	McNeill	2.3	1373.8	0	Community Supply		9.02	11.04	95705
G41/0125				10	0.8	0		BITUMIX LTD		McNeill	0	51.8	0	Irrigation		0	0	
G41/0115	Completed	Borehole		23.485	0.2	12.6	6/01/1994		Wanaka Rd - Cromwell	McNeill	1.2	976.3	0	Irrigation		20.6	23.45	93517
G41/0113	Completed	Borehole	2010.042.V1	24.9	0.2	16.74	10/08/1992	Downer EDi Works (was Bitumix)	#940 SH6	McNeill	0	2160	0	Commercial		0	0	

Easting	Northing	Consent Number	Consent Type	Consent Status	Consent Holder	Postal Address	Consent Expiry Date	Purpose
1304551	5014468	3978	Discharge to Air Permit	Expired	Fulton Hogan Limited	PO Box 277, Alexandra 9340	31/03/1993	To discharge to air from the operation of a mobile asphalt plant with main base at Parkburn, Cromwell
1304751	5014568	95546	General/Structure Land Use Consent	Expired	Fulton Hogan Limited	PO Box 277, Alexandra 9340	1/08/1996	To construct a crossing over the Parkburn Creek for the purpose of facilitating access to an industrial activity
1304551	5014468	4187	Discharge to Air Permit	Expired	Fulton Hogan Limited	PO Box 277, Alexandra 9340	1/04/1998	To discharge to air from the operation of a hot-mix asphalt plant at Parkburn, Cromwell
1304551	5014468	HD/1158/90	Discharge to Air Permit	Expired	Fulton Hogan Limited	PO Box 277, Alexandra 9340	1/04/1998	To discharge to air from the operation of a hot-mix asphalt plant at Parkburn, Cromwell (current consent no as at 15 September 1995 - No. 4187)
1304851	5014268	3353	Groundwater Take Permit	Expired	Fulton Hogan Limited	PO Box 277, Alexandra 9340	1/06/1998	To take 145,000 litres per hour from a bore for gravel washing at Parkburn, Cromwell
1304851	5014268	3353B	Discharge to Land Permit	Expired	Fulton Hogan Limited	PO Box 277, Alexandra 9340	1/06/1998	to discharge 145,000 litres per hour onto land
1304351	5013967	2003.718	Bore Construction Consent	Expired	Fulton Hogan Limited	PO Box 277, Alexandra 9340	4/09/2005	To construct a bore for the processing of roading aggregate for an unlimited term.
1304551	5014568	96273	Discharge to Air Permit	Expired	Bitumix Limited	1 Parry Street, Dunedin 9016	31/10/2006	To discharge to air contaminants produced when manufacturing up to 40 tonnes per hour of asphalt, including the products of diesel oil at the Bitumix Parkburn Quarry, Cromwell
1304551	5014267	98117	Discharge to Air Permit	Expired	Fulton Hogan Limited - Christchurch	PO Box 277, Alexandra 9340	30/04/2013	To discharge contaminants to air for the purpose of operating an asphalt plant. Location of activity: Parkburn quarry, SH 6, Cromwell
1304851	5014268	98127	Groundwater Take Permit	Expired	Fulton Hogan Limited	PO Box 277, Alexandra 9340	1/06/2018	To take 31,680,000 litres per month at a maximum rate of 144,000 litres per hour from a bore for the purpose of gravel washing, asphalt plant, mobile concrete plant, truck washing, domestic and irrigation - Parkburn Quarry.
1304551	5014267	98130	Discharge to Land Permit	Expired	Fulton Hogan Limited	PO Box 277, Alexandra 9340	1/06/2018	To discharge 23,760,000 litres per wash water per month at a maximum rate of 108,000 litres per hour, to land from settling ponds for the purpose of gravel, sand and crushed aggregate washing at Parkburn Quarry
1304551	5014267	98129	Groundwater Take Permit	Expired	Fulton Hogan Limited	PO Box 277, Alexandra 9340	1/06/2018	To take 23,760,000 litres of water per month at a maximum rate of 108,000 litres per hour, from open pits for the purpose of gravel, sand and crushed aggregate washing at Parkburn quarry
1304951	5014368	98128	Discharge to Land Permit	Expired	Fulton Hogan Limited	PO Box 277, Alexandra 9340	1/06/2018	To discharge up to 31,680,000 litres of quarry wash water per month at a maximum rate of 144,000 litres per hour, to land from settling ponds. See 98127 for groundwater take.
1305051	5014468	99664	Discharge to Land Permit	Current	Fulton Hogan Limited - Alexandra	PO Box 277, Alexandra 9340	6/11/2026	To discharge solid fill to land within an operating gravel quarry beside Lake Dunstan at the location where the Parkburn flows into the Lake for the purpose of backfill at a quarry site.
1304351	5013967	2003.719.V1	Groundwater Take Permit	Surrendered	Fulton Hogan Limited (Use for Consents)	Private Bag 1962, Fairfield, Dunedin 9054	10/09/2028	To take and use groundwater for the purpose of processing roading aggregate.
1304551	5014267	2004.6	Discharge to Air Permit	Current	Fulton Hogan Limited - Christchurch	PO Box 277, Alexandra 9340	31/03/2041	To discharge dust to air for the purpose of quarrying, crushing and screening aggregate.
1304756	5014503	RM18.376.01.V1	Discharge to Air Permit	Current	Fulton Hogan Limited - Alexandra	PO Box 277, Alexandra 9340	6/03/2044	To discharge contaminants to air for the purpose of operating an asphalt plant
1304756	5014503	RM12.385.01	Discharge to Air Permit	Surrendered	Fulton Hogan Limited - Alexandra	PO Box 277, Alexandra 9340	21/11/2047	To discharge contaminants to air for the purpose of operating an asphalt plant.
1304857	5014082	RM15.108.02.V1	Discharge to Land Permit	Current	Fulton Hogan Limited - Alexandra	PO Box 277, Alexandra 9340	1/11/2050	To discharge silt, sediment and water to land for the purpose of aggregate washing, processing aggregate, asphalt and concrete, truck washing and dust suppression.
1304286	5013958	RM15.108.01.V1	Groundwater Take Permit	Current	Fulton Hogan Limited - Alexandra	PO Box 277, Alexandra 9340	1/11/2050	To take and use groundwater for the purpose of processing aggregate, asphalt and concrete, truck washing, domestic use, irrigation and dust suppression.
1304784	5014492	RM17.359.01	Discharge to Land Permit	Surrendered	Fulton Hogan Limited (Use for Consents)	Private Bag 1962, Fairfield, Dunedin 9054	12/01/2053	To discharge water to land for the purpose of processing aggregate, asphalt and concrete, truck washing and dust suppression
1304855	5014046	RM17.359.03	Discharge to Land Permit	Surrendered	Fulton Hogan Limited (Use for Consents)	Private Bag 1962, Fairfield, Dunedin 9054	12/01/2053	To discharge water to land for the purpose of processing aggregate and dust suppression.
1304175	5013704	RM17.359.04	Groundwater Take Permit	Surrendered	Fulton Hogan Limited (Use for Consents)	Private Bag 1962, Fairfield, Dunedin 9054	12/01/2053	To take and use groundwater for the purpose of processing aggregate, irrigation and dust suppression
1304340	5013960	RM15.310.01	Bore Construction Consent	Current	Fulton Hogan Limited - Alexandra	PO Box 277, Alexandra 9340		To construct a bore for the purpose of accessing groundwater

Appendix E:
Site Photographs



Figure 1: Working face of quarry.



Figure 2: Stockpiled pea gravel for reclamation.



Figure 3: Reclaimed area at southern end of quarry.




Figure 4: Diesel generator with in-built fuel tank in quarry.



Figure 5: Mobile crusher within Schedule Activity portion of quarry.



Figure 6: Bitumen spray plant within quarry.



Figure 7: Fuel and waste oil storage within quarry.



Figure 8: Silt ponds for treatment and disposal of quarry plant wash water.



Figure 9: Asphalt plant



Figure 10: Bitumen storage at the asphalt plant.



Figure 11: Former diesel tank location.



Figure 12: Firth concrete block plant, with concrete silo (white) and diesel tank (yellow) in background.



Figure 13: Allied concrete batching plant.




Figure 14: Truck wash.



Figure 15: Signage at entrance to cleanfill.



Figure 16: Cleanfill face.



Figure 17: Road cutting waste storage.



Figure 18: Hardfill face.



Figure 19: New glass processing building.



Figure 20: JCL Asphalt yard, with diesel tank (white) at entrance to container shelter.



Figure 21: Two explosive storage containers (white) at Fulton Hogan yard.

Appendix F:
XRF Screening Results

Table 1: XRF background readings (ppm)

Sample ID	Depth (m)	Arsenic	Cadmium	Chromium	Copper	Lead	Nickel	Zinc
background 1	0.0-0.05	14	<LOD	<LOD	31	26	31	99
background 2	0.0-0.05	8	<LOD	<LOD	17	19	15	58
background 3	0.0-0.05	10	<LOD	<LOD	11	16	19	70
background 4	0.0-0.05	6	<LOD	<LOD	17	20	11	65
background 5	0.0-0.05	8	<LOD	<LOD	16	20	17	56
background 6	0.0-0.05	9	<LOD	<LOD	19	26	16	76
background 7	0.0-0.05	7	<LOD	<LOD	12	20	18	53
background 8	0.0-0.05	9	<LOD	<LOD	17	19	14	63
background 9	0.0-0.05	11	<LOD	<LOD	18	18	22	67
background 10	0.0-0.05	7	<LOD	75	19	19	16	70
Local Background Minimum		6	<LOD	<LOD	11	16	11	53
Local Background Maximum		15	<LOD	75	31	26	38	99
Predicted Background Concentration ¹		12	0.34	80	43	44	45	182

¹ 95 %ile predicted background concentration for Gravel (Manaaki Whenua Landcare Research, 2015)
 < Denotes concentration is below laboratory detection limits

Table 2: XRF Screening results (ppm)

Sample ID	Depth (m)	Arsenic	Cadmium	Chromium	Copper	Lead	Nickel	Zinc
cleanfill 01	0.0-0.05	13	<LOD	48	22	19	27	95
cleanfill 02	0.0-0.05	10	<LOD	<LOD	12	13	<LOD	62
cleanfill 03	0.0-0.05	9	<LOD	44	<LOD	19	18	62
cleanfill 04	0.0-0.05	7	<LOD	<LOD	11	12	<LOD	38
cleanfill 05	0.0-0.05	14	<LOD	83	21	15	19	62
cleanfill 06	0.0-0.05	11	<LOD	95	26	59	26	78
cleanfill 07	0.0-0.05	9	<LOD	55	22	58	14	63
cleanfill 08	0.0-0.05	10	<LOD	<LOD	8	12	<LOD	74
cleanfill 09	0.0-0.05	9	<LOD	52	12	10	15	41
cleanfill 10	0.0-0.05	16	<LOD	<LOD	25	21	26	54
cleanfill 11	0.0-0.05	10	<LOD	76	21	42	22	70
cleanfill 12	0.0-0.05	7	<LOD	75	<LOD	27	17	32
cleanfill 13	0.0-0.05	11	<LOD	124	22	38	19	55
cleanfill 14	0.0-0.05	5	<LOD	<LOD	<LOD	5	<LOD	64
cleanfill 15	0.0-0.05	7	<LOD	90	16	43	13	58
cleanfill 16	0.0-0.05	7	<LOD	70	14	43	23	52
cleanfill 17	0.0-0.05	13	<LOD	<LOD	22	19	16	50
cleanfill 18	0.0-0.05	9	<LOD	<LOD	14	18	<LOD	55
cleanfill 19	0.0-0.05	6	<LOD	98	14	8	17	51
cleanfill 20	0.0-0.05	18	<LOD	48	19	367	13	385
cleanfill 21	0.0-0.05	10	<LOD	43	13	11	<LOD	38
cleanfill 22	0.0-0.05	18	<LOD	<LOD	23	19	16	63
cleanfill 23	0.0-0.05	8	<LOD	40	14	12	12	49
cleanfill 24	0.0-0.05	8	<LOD	<LOD	17	21	14	45
cleanfill 25	0.0-0.05	10	<LOD	<LOD	13	14	14	60
cleanfill 26	0.0-0.05	11	<LOD	<LOD	11	16	11	59
cleanfill 27	0.0-0.05	10	<LOD	<LOD	16	21	12	36
cleanfill 28	0.0-0.05	12	<LOD	<LOD	16	22	14	40
cleanfill 29	0.0-0.05	11	<LOD	54	7	12	14	58
cleanfill 30	0.0-0.05	12	<LOD	<LOD	19	19	11	50
hardfill 31	0.0-0.05	9	<LOD	<LOD	14	22	14	61
hardfill 32	0.0-0.05	11	<LOD	<LOD	27	21	17	96
hardfill 33	0.0-0.05	11	<LOD	72	19	23	16	59
hardfill 34	0.0-0.05	10	<LOD	48	18	95	11	188
hardfill 35	0.0-0.05	16	<LOD	65	30	23	26	93
hardfill 36	0.0-0.05	14	<LOD	<LOD	20	22	18	57
hardfill 37	0.0-0.05	11	<LOD	<LOD	16	13	15	57
hardfill 38	0.0-0.05	10	<LOD	47	8	14	<LOD	45
hardfill 39	0.0-0.05	9	<LOD	<LOD	10	18	14	68
hardfill 40	0.0-0.05	7	<LOD	69	11	15	<LOD	51
Local Background Minimum ¹		6	<LOD	<LOD	11	16	11	53
Local Background Maximum ¹		15	<LOD	75	31	26	38	99
Predicted Background Concentration ⁵		12	0.34	80	43	44	45	182
¹ Based on 10 XRF readings from an undisturbed part of the site								
² 95 %ile predicted background concentration for Gravel (Manaaki Whenua Landcare Research, 2015)								
< Denotes concentration is below laboratory detection limits								
Orange shading denotes exceedance of local background maximum								

Appendix 5

CODC NES Records Search

NES RECORD SEARCH

Application

JKCM Limited	Number	NES250014
PO Box 456, Cromwell 9342	Application date	12/11/25
	Phone	
	Mobile	021556549
	Email	claud@insighteng.co.nz

Property

Valuation No.	2842114401
Location	922 Luggate-Cromwell Road (State Highway 6), Cromwell
Legal Description	Part Section 63 Block IV Wakefield SD
Area (hectares)	48.3192

Resource consents

Resource Area: Medium Density Residential Zone, Low Density Residential Zone, Industrial Resource Area (2), Industrial Resource Area (3)

Consents:

- 17/02/2023 RC 220339V1: Change conditions of RC220339 to allow for the installation of one 'smart shelter' on site
- Information provided with the application indicates the presence of an asphalt plant and concrete block manufacturing plant. Asphalt manufacture or bulk storage and commercial concrete manufacture are items E2 and E4 on the HAIL and may trigger NES-CS requirements.*
- Further, the application suggests that the site has been used for motor vehicle maintenance and repair (Associated with quarry operations). Motor vehicle workshops are Item F4 on the HAIL and may trigger NES-CS requirements if undertaken on the site.*
- Note: This application was cancelled and superseded by RC 220443.*
- 01/11/2022 RC 200046V1: Change of conditions to change building location
- Information provided with the application indicates the presence of an asphalt plant and concrete block manufacturing plant. Asphalt manufacture or bulk storage and commercial concrete manufacture are items E2 and E4 on the HAIL and may trigger NES-CS requirements.*
- 07/09/2022 RC 220268: Install three portacombs for temporary Aurora Energy depot
- Information provided with the application indicates the presence of a glass crushing plant. Waste recycling is item G6 on the HAIL and may trigger NES-CS requirements.*
- 16/08/2021 RC 210129: Land use consent to install two 20,000L diesel fuel tanks to replace one diesel tank which is to be removed
- Information provided with the application indicates the presence of fuel storage tanks, and an asphalt plant. Fuel storage and asphalt manufacture and bulk storage are items A17 and E2 on the HAIL and may trigger NES-CS requirements.*



Figure One: Extract from application for RC 210129 showing location of pre-existing and proposed fuel tanks.

- 09/06/2021 RC 210112: Land use consent to construct a shed to house a glass crushing plant
Information provided with the application indicates the presence of a glass crushing plant. Waste recycling is item G6 on the HAIL and may trigger NES-CS requirements.
- 24/04/2020 RC 200046: Change condition 1 of RC 190641 to allow establishment of two further portacoms
Information provided with the application indicates the presence of an asphalt plant and concrete block manufacturing plant. Asphalt manufacture or bulk storage and commercial concrete manufacture are items E2 and E4 on the HAIL and may trigger NES-CS requirements.
- 01/11/2019 RC 190341: Land use consent to establish portacom offices
Information provided with the application, indicates the presence of a concrete block manufacturing plant. Commercial concrete manufacture is item E4 on the HAIL and may trigger NES-CS requirements.
- 05/11/2007 RC 070216: Land use consent to extract and convey sand aggregate from the Upper Terrace
Information provided with the application, indicates the presence of a concrete block manufacturing plant. Commercial concrete manufacture is item E4 on the HAIL and may trigger NES-CS requirements.

01/09/2005 RC 050211: Land use consent to build and operate concrete block manufacturing plant
Information provided with the application indicates the presence of an asphalt plant and concrete block manufacturing plant. Asphalt manufacture or bulk storage and commercial concrete manufacture are items E2 and E4 on the HAIL and may trigger NES-CS requirements.




Figure Two: Extract from application showing location of concrete block plant.

19/06/2000 RC 990155: Backfill against quarry pit faces with solid fill
Information provided in support of this application indicates a bitumen storage area. Asphalt or bitumen manufacture or bulk storage is Item E2 on the HAIL and may trigger NES-CS requirements.
Note: This application was withdrawn before any decisions were made on it.

Building

Consents/Permits/Compliance Schedules:

13/10/22 BC 220462A: Change in Site Location for BC 220462
No information in relation to HAIL activities could be found on this record.

5/10/22 BC 220703: New foundations and construction of portal frame gantry
Information provided in support of this application indicates presence of diesel storage tanks and bitumen storage. Tanks for fuel and bitumen bulk storage are Items A17 and E2 on the HAIL respectively, and may trigger NES-CS requirements.





Figure Three: Extract from application showing location of diesel and bitumen tanks.

21/07/22	BC 220462: Foundations and site works for relocated Portacom <i>No information in relation to HAIL activities could be found on this record.</i>
18/05/21	BC 210205: New 20m x 16m storage shed <i>Information provided with the application indicates the presence of a glass crushing plant. Waste recycling is item G6 on the HAIL and may trigger NES-CS requirements.</i>
9/12/20	BC 200771: Foundations, water supply, drainage & site works for unisex portacom ablution block <i>No information in relation to HAIL activities could be found on this record.</i>
1/09/20	BC 200568: Install 1x Smart Shelter container roof <i>Information provided with the application indicates the presence of an asphalt plant. Asphalt manufacture or bulk storage is item E2 on the HAIL and may trigger NES-CS requirements.</i>
26/06/20	BC 200395: Foundations and site works for relocated office (portacom) <i>No information in relation to HAIL activities could be found on this record.</i>
27/09/19	BC 190726: Foundations & site works for relocated office (portacom) <i>No information in relation to HAIL activities could be found on this record.</i>
10/07/19	BC 190440: Foundations & site works for relocated office (portacom) <i>No information in relation to HAIL activities could be found on this record.</i>
12/11/18	BC 180636: Foundations & site works for relocated office (portacom) <i>No information in relation to HAIL activities could be found on this record.</i>

- 9/11/16 BC 160880: Foundations & site works for relocated office/smoko room
No information in relation to HAIL activities could be found on this record.
- 30/11/15 BC 150689: Erect a new storage shed
No information in relation to HAIL activities could be found on this record.
- 30/07/15 BC 150440: Additions to existing shed
Information provided in support of this application indicates the presence of bulk bitumen storage tanks and above ground fuel tanks. Asphalt or bitumen manufacture or bulk storage and fuel storage tanks are Items E2 and A17 on the HAIL respectively and may trigger NES-CS requirements.



HANLON & PARTNERS LTD CONSULTING STRUCTURAL & FIRE ENGINEERS 213 HIGH STREET, DUNEDIN Tel: (03) 479 2547 Fax: (03) 479 2547		Fulton Hogan Ltd. Main North Road, Oamaru Seismic Restraint for Bitumen Emulsion Tank	
DRAWN L. Hughes	JOB NO. 10486/s1		
DATE 24.01.06	ISSUED		



Figure Four: Extracts from application showing bitumen and fuel tanks

14/08/06 BC 060538: Relocate building onto site for staff facilities

No information in relation to HAIL activities could be found on this record.

7/12/05 BC 050850: Erect all new buildings/platforms for new industrial plant

Information provided with the application indicates the presence of a concrete block manufacturing plant. Commercial concrete manufacture is item E4 on the HAIL and may trigger NES-CS requirements.

25/11/04 BC 040935: Erect a new Portacom building

No information in relation to HAIL activities could be found on this record.

31/07/95 BC 950406: Relocate storage building

Information provided in support of this application indicates the presence of bulk bitumen storage tanks and above ground fuel tanks. Asphalt or bitumen manufacture or bulk storage and fuel storage tanks are Items E2 and A17 on the HAIL respectively and may trigger NES-CS requirements.




Figure Five: Extract from application showing bitumen storage and fuel tanks

21/12/1990 Building Permit H056122: Erect a Bitumen storage shed (relocated)

Information provided in support of this application indicates the presence of bulk bitumen storage tanks and above ground fuel tanks. Asphalt or bitumen manufacture or bulk storage and fuel storage tanks are Items E2 and A17 on the HAIL respectively and may trigger NES-CS requirements.

23/11/1988 Building Permit F037756: Erect office building at quarry

No information in relation to HAIL activities could be found on this record.

Preliminary Site Investigations and Detailed Site Investigations

A preliminary site investigation was undertaken for the site in support of Plan Change 23. The PSI identified the following HAIL activities as having occurred on different parts of the site.

Table 3: Identified HAIL Activities

HAIL Activity	Dates	Comment	Likelihood
E4. Commercial concrete manufacture or commercial cement storage	2005 - present	Concrete block manufacturing facility	Certain
E2. Asphalt or bitumen manufacture or bulk storage (excluding single-use sites used by a mobile asphalt plant)	1987 - present	Asphalt plant	Certain
A17. Storage tanks or drums for fuel, chemicals or liquid waste	<1990-2004	Various fuel storage	Possible
A10. Persistent pesticide bulk storage or use including sport turfs, market gardens, orchards, glass houses or spray sheds	<1958~1985	1000 m ² of orchard	More likely than not
A18. Wood treatment or preservation including the commercial use of anti-sapstain chemicals during milling, or bulk storage of treated timber outside	~2020 - present	250 m ² of treated timber storage	Certain
G5. Waste disposal to land (excluding where biosolids have been used as soil conditioners)	1987 - present	Cleanfill	Likely

The below figures are from the PSI, showing different activities on the site.




Figure Six: Extract from PSI showing activities in the industrial area of the site.



Figure Seven: Extract from PSI showing activities in the cleanfill and yards area of the site.

Further, the PSI notes that the following activities have occurred on the site, but did not consider them to constitute HAIL activities:

Several on-site wastewater treatment and disposal systems treating domestic-type effluent from offices and ablution blocks on the site

Gravel extraction – Exempted from HAIL under Item E7.

Explosives storage in two steel containers in the Fulton Hogan Yard area. This was not considered to be bulk storage in terms of Item C1 on the HAIL.

The storage and crushing of glass was not considered to constitute waste recycling under Item G6 as it does not involve the storage use or disposal of hazardous substances.

The below extract from the PSI indicates the areas considered likely to contain HAIL Activities:




Figure Eight: Extract from PSI showing areas considered likely to contain HAIL activities.

The PSI concluded that it was unlikely that contaminants in soil associated with concrete manufacture, persistent pesticide use, and treated timber storage would pose a risk to human under the commercial/industrial land use proposed for these areas as part of the plan change. It recommended that additional investigation upon decommissioning or closure of any potentially contaminating land uses, Given the on-going use of the site for many of these HAIL activities.

Aerial Photographs

Council's aerial photographs of the site date back to 2006. Aerial photographs indicate the presence of the following HAIL activities, which may trigger NES-CS requirements:

Asphalt Plant. Asphalt or bitumen manufacture or bulk storage is Item E2 on the HAIL.



Figure Nine: Aerial photo dated 2025 showing location of asphalt plant.



Figure 10: Aerial photograph dates 2006 showing the location of the asphalt plant.

Concrete Block Manufacturing Plant. Commercial concrete manufacture or commercial cement storage is Item E4 on the HAIL



Figure 11: Aerial photograph dated 2025 showing location of concrete block plant.

Outdoor storage of unknown materials. HAIL activities that can be associated with material storage can include storage tanks or drums for fuel, chemicals or liquid waste (Item A18), scrap yards (Item G4), or waste disposal to land (Item G5)



Figure 12: Aerial photograph dated 2025 showing material storage on the site.



Figure 13: Aerial photograph dated 2019 showing material storage on the site.

Other Land Features

No information in relation to the above could be found on Council's records.

Disclaimer: The Council does not hold records directly relating to activities on the Hazardous Activities and Industries List (HAIL). In the event some information is available it cannot be guaranteed as correct or complete and therefore may not satisfy your request. We therefore recommend you undertake further investigation to determine whether any HAIL activities exist on the site.

Prepared by

A handwritten signature in blue ink, appearing to read 'A. Vincent'.

Adam Vincent
Planning Officer - Consents
Date: 26 November 2025

Appendix 6

Laboratory Results and Chain of Custody Documentation

Certificate of Analysis

Page 1 of 2

Client:	Insight Engineering	Lab No:	4027551	SPV1
Contact:	Claude Midgley C/- Insight Engineering PO Box 456 Cromwell 9384	Date Received:	10-Nov-2025	
		Date Reported:	12-Nov-2025	
		Quote No:	137281	
		Order No:		
		Client Reference:	24019	
		Submitted By:	Claude Midgley	

Sample Type: Soil

Sample Name:	CF1	CF2	CF3	CF4	CF5
Lab Number:	4027551.1	4027551.2	4027551.3	4027551.4	4027551.5
Heavy Metals, Screen Level					
Total Recoverable Arsenic mg/kg dry wt	32	8	7	7	10
Total Recoverable Cadmium mg/kg dry wt	< 0.10	< 0.10	< 0.10	< 0.10	< 0.10
Total Recoverable Chromium mg/kg dry wt	6	8	12	7	15
Total Recoverable Copper mg/kg dry wt	17	16	14	12	13
Total Recoverable Lead mg/kg dry wt	15.6	10.4	11.4	14.3	23
Total Recoverable Nickel mg/kg dry wt	11	10	12	8	13
Total Recoverable Zinc mg/kg dry wt	57	39	51	32	53

Sample Name:	CF6	CF7	CF8
Lab Number:	4027551.6	4027551.7	4027551.8

Heavy Metals, Screen Level			
Total Recoverable Arsenic mg/kg dry wt	13	9	-
Total Recoverable Cadmium mg/kg dry wt	< 0.10	< 0.10	-
Total Recoverable Chromium mg/kg dry wt	5	12	-
Total Recoverable Copper mg/kg dry wt	18	17	-
Total Recoverable Lead mg/kg dry wt	15.4	21	-
Total Recoverable Nickel mg/kg dry wt	9	14	-
Total Recoverable Zinc mg/kg dry wt	23	54	-

Heavy Metals with Mercury, Screen Level			
Total Recoverable Arsenic mg/kg dry wt	-	-	5
Total Recoverable Cadmium mg/kg dry wt	-	-	< 0.10
Total Recoverable Chromium mg/kg dry wt	-	-	8
Total Recoverable Copper mg/kg dry wt	-	-	9
Total Recoverable Lead mg/kg dry wt	-	-	12.7
Total Recoverable Mercury mg/kg dry wt	-	-	< 0.10
Total Recoverable Nickel mg/kg dry wt	-	-	7
Total Recoverable Zinc mg/kg dry wt	-	-	28

Summary of Methods

The following table(s) give a brief description of the methods used to conduct the analyses for this job. The detection limits given below are those attainable in a relatively simple matrix. Detection limits may be higher for individual samples should insufficient sample be available, or if the matrix requires that dilutions be performed during analysis. A detection limit range indicates the lowest and highest detection limits in the associated suite of analytes. A full listing of compounds and detection limits are available from the laboratory upon request. Unless otherwise indicated, analyses were performed at Hill Labs, 28 Duke Street, Frankton, Hamilton 3204.

Sample Type: Soil

Test	Method Description	Default Detection Limit	Sample No
Environmental Solids Sample Drying*	Air dried at 35°C Used for sample preparation. May contain a residual moisture content of 2-5%. (Free water removed before analysis, non-soil objects such as sticks, leaves, grass and stones also removed).	-	1-8



This Laboratory is accredited by International Accreditation New Zealand (IANZ), which represents New Zealand in the International Laboratory Accreditation Cooperation (ILAC). Through the ILAC Mutual Recognition Arrangement (ILAC-MRA) this accreditation is internationally recognised. The tests reported herein have been performed in accordance with the terms of accreditation, with the exception of tests marked * or any comments and interpretations, which are not accredited.

Sample Type: Soil			
Test	Method Description	Default Detection Limit	Sample No
Heavy Metals, Screen Level	Dried sample, < 2mm fraction. Nitric/Hydrochloric acid digestion. Complies with NES Regulations. ICP-MS screen level, interference removal by Kinetic Energy Discrimination if required. US EPA 200.2 (modified), APHA 3125 B: Online Edition.	0.10 - 4 mg/kg dry wt	1-7
Heavy Metals with Mercury, Screen Level	Dried sample, < 2mm fraction. Nitric/Hydrochloric acid digestion. Complies with NES Regulations. ICP-MS screen level, interference removal by Kinetic Energy Discrimination if required. US EPA 200.2 (modified), APHA 3125 B: Online Edition.	0.10 - 4 mg/kg dry wt	8

These samples were collected by yourselves (or your agent) and analysed as received at the laboratory.

Testing was completed between 10-Nov-2025 and 12-Nov-2025. For completion dates of individual analyses please contact the laboratory.

Samples are held at the laboratory after reporting for a length of time based on the stability of the samples and analytes being tested (considering any preservation used), and the storage space available. Once the storage period is completed, the samples are discarded unless otherwise agreed with the customer. Extended storage times may incur additional charges.

This certificate of analysis must not be reproduced, except in full, without the written consent of the signatory.



Kim Harrison MSc
Client Services Manager - Environmental

ENVIRONMENTAL Analysis Request Form

CLIENT

Name **Insight Engineering** [229068]
PO Box 456
Cromwell 9342
 Phone: 021 556 549 Fax:
 Client Reference: 24019 (Project Code)
 Quote Number: 137281 Order No: (Cost Centre)

RESULTS TO

☐ Mail Client ☐ Mail Submitter

☐ Fax Results
☒ Email Results

claude@insighteng.co.nz

Additional Information

Hill Laboratories **402 7551**

R J Hill Laboratories Limited — accredited
 Accreditation NZ

Job No: Date Recv: 10-Nov-25 06:44

Received by: Nathaniel Sue

1 Clyde Street, Telephone
 Private Bag 3205, Facsimile:



3140275514

Hill Laboratories office use only.

Date In Job # No. of Samples

Submitted By **Claude Midgley** [228982]

Charge To: **Insight Engineering** [229068]

☒ C.O.C & coversheet to be scanned and emailed back

Chain of Custody Record

Delivered to **Hill Laboratories** Date & Time: 07/11/2025 15:00
 (Depatched by) Name: Claude Midgley
 Signature: *Claude Midgley*

Received at **Hill Laboratories** Date & Time:
 Name:
 Signature:

Condition ☐ Ambient Temp ☐ Chilled 22-8C

PRIORITY

☐ Normal (up to 10 days) ☒ High (approx 5 days) ☐ Urgent (MUST be pre-arranged)
 Results required by:

Sample types

GW Bore/well **TW** Trade waste **S** Saline water **ES** Soil/Solid **PI** Plant
SW Surface water **E** Effluent **O** Oil **Sed** Sediment **BM** Fish/shellfish/Biota
P Potable/DI **L** Leachate **SI** Sludge **BS** Biosolid **M** Misc (Specify)

Site ID	Sample type	Tests required	Comments
CF1	ES	HMsSoil	
CF2	ES	HMsSoil	
CF3	ES	HMsSoil	
CF4	ES	HMsSoil	
CF5	ES	HMsSoil	
CF6	ES	HMsSoil	
CF7	ES	HMsSoil	
CF8	ES	HMsSoil + Hg	

Appendix 7

Qualifications and Experience



Education

Master of Science 2004
Bachelor of Science Honours 2002
Bachelor of Science 2001

Additional Training

Environmental Impact Assessment (EIA) Project Management, The Centre for Science and Industrial Research (CSIR), Stellenbosch, South Africa
Project Management, University of Auckland School of Business, Auckland, New Zealand
RAB QSA Certified Environmental Management Systems (ISO14001) Implementation course, Andsam Training, Auckland, New Zealand
HSNO Advanced Training Course, Responsible Care New Zealand Inc. Christchurch, New Zealand
St John First Aid – Level Two Course (Unit Standard 26552 (V2), Christchurch, New Zealand
New Zealand Red Cross Comprehensive First Aid Course, Auckland, New Zealand
Operating a Four Wheel Drive Vehicle in an Off Road Environment, DECA Training, Auckland, New Zealand
Site Safe BUILDING CONSTRUCTION, CIVIL Passport and CONSULTANT Passport Auckland and Christchurch, New Zealand
OSHA 24 Hour HAZWOPER certified (certificate 121122264382), Safety Unlimited Inc, Simi Valley, California
Conduct asbestos assessment associated with removal (Course Code CPCCBC5014A), AlertForce, Australia
Field Portable Analytical Radiation Apparatus – Radiation Safety Course (Certificate of Training No 7772, March 2024, Evident Australia)
NZ Ministry of Health License to Use Ionising Radiation (License No. 31470, valid until 10 July 2027)

Claude Midgley

Principal Environmental Scientist

Claude is a Principal Environmental Scientist specialised in contaminated land and groundwater assessment since 2005.

He has diverse experience and capability in contamination assessment, gained through involvement in projects for oil and gas, mining, waste, council, industry and land development clients across New Zealand, as well as in Australia, The Federated States of Micronesia, The Republic of Palau and The Republic of the Marshall Islands.

Claude became a Certified Environmental Practitioner in 2013 and has maintained that certification by completing over 50 hours of continuing professional development, focussed entirely on contamination assessment, per year.

Claude has lived in Central Otago since 2016 and is passionate about promoting sustainable practices in land development. He has undertaken hundreds of contaminated site assessments, with highlights including:

- **The Christchurch-wide identification of hazardous activities and industries between the 1940s and the 2010s for Environment Canterbury;**
- **Physically surveying three Pacific Island nations to identify asbestos-containing building materials in each country for SPREP;**
- **Establishment of artificial wetlands to treat and reduce landfill leachate for the Otago Polytechnic;**
- **Groundwater and ground vapour assessment across the Wynyard Quarter in the Auckland waterfront for Auckland Regional Council.**
- **Groundwater monitoring at 15 closed landfills across Central Otago for Central Otago District Council.**

Since 2024, Claude has held a license to use ionising radiation which enables him to operate a portable X-ray Fluorescence analyser (XRF) to rapidly identify areas impacted with certain priority heavy metals.