
ATTACHMENT 3

Includes: Appendix I to Appendix O



Source Term Definition Report

Bendigo-Ophir Gold Project

5 August 2025

J-NZ0475-001-R-Rev2





Source Term Definition Report

Bendigo-Ophir Gold Project

Document Number: J-NZ0475-001-R-Rev2

Document Date: 5 August 2025

Prepared for:

Matakanui Gold Limited

15a Chardonnay Street, Cromwell, 9310

Prepared by:

Mine Waste Management Limited

5 Sir William Pickering Drive, Christchurch 8053, New Zealand

+64 3 242 0221

www.minewaste.com.au

REVISION	DATE	AUTHOR	RECORD OF REVIEW	
RevA	21/02/2025	QY/PW/EW	PW	
Rev0	09/06/2025	PW	PW	
Rev1	02/08/2025	PW/EW/LN	PW	
Rev2	04/08/2025	PW	PW	

Page ii www.minewaste.com.au

EXECUTIVE SUMMARY

Mine Waste Management Limited (MWM) has developed this report to define the source terms for the water and load balance model (WLBM) for the Bendigo-Ophir Gold Project (BOGP) for Matakanui Gold Limited (MGL) to provide a summary of inputs that will be used during the modelling process. The model is discussed in MWM (2025c).

Objectives of this Study

The objectives of this report are to:

- Define the sources of data used for developing the water quality source terms.
- Define the rationale applied in deriving the source terms.
- Propose what performance monitoring is required to ensure potential effects are understood in advance.

Findings

The materials associated with the BOGP will generate neutral metalliferous drainage and may have elevated potential constituents of concern (PCOC) such as arsenic (As), sulfate, (SO₄), and trace metals. Nitrogenous compounds are also likely to be elevated. Collectively this is identified as mine impacted waters (MIW).

Water quality source terms were developed from a variety of sources including analogue data sources, baseline studies at the BOGP, and laboratory derived data from environmental geochemistry testing. This report provides an explanation of how the source terms for modelling were developed for the WLBM.

Management

Water management during the Operational Phase of the BOGP will involve discharge of only episodic runoff from haul roads and ELF surfaces. All other MIW (e.g., landform seepage) will be collected, used, and stored on site. In the Active Closure / Post Closure Phase, MIW will be treated and discharged to the receiving environment. Two models have been developed, that are reported elsewhere (MWM, 2025c) to reflect these phases:

- Operational Phase Excel based models and calculations focussing on average annual water balance and runoff event discharge of MIW.
- Active Closure / Post Closure Phase GoldSim based models and calculations, focussing on the evolution of instream water quality over time as a result of discharge of treated MIW.

Detailed stage models for years 1-13 of the BOGP will be developed using GoldSim¹ prior to mining commencing (i.e., during the project pre-startup phase). This will provide an operational tool for MGL to effectively manage water during operations.

¹ <u>https://www.goldsim.com</u>

General Background

MGL is proposing to establish the BOGP, which comprises gold mining operations, processing operations, ancillary facilities and environmental mitigation measures on Bendigo and Ardgour Stations in the Dunstan Mountains of Central Otago. The project site is located approximately 20 km north of Cromwell and will have a maximum disturbance footprint of 550 hectares.

The total Mineral Resource Estimate for the BOGP using a 0.5 g/t cut-off for open pit and 1.5 g/t for underground is 34.3 Mt at 2.1 g/t for 2.34 M oz (MGL, 2025). The Bendigo-Ophir resources occur in four deposits: Come in Time (CIT), Rise and Shine (RAS), Srex (SRX), Srex East (SRE). The majority of identified mineral resources are located within the RAS deposit. Three primary geological units are recognised at site:

- RSSZ Rise and Shine Shear Zone
- TZ3 Lower Greenschist facies Textural Zone 3 rocks of the Otago Schist
- TZ4 Upper Greenschist facies Textural Zone 4 rocks of the Otago Schist

The resources will be mined by open pit methods at each deposit within the project site, with underground mining methods also proposed to be utilised at RAS to access the deeper gold deposits. The majority of the mining activities, ancillary facilities and associated infrastructure will be located in the Shepherds Valley with non-operational infrastructure located on the adjoining Ardgour Terrace. The BOGP also involves the taking of groundwater from the Bendigo Aquifer for use in mining-related activities and the realignment of Thomson Gorge Road via Ardgour Station.

There are numerous historic mine workings throughout the project area, which can impact baseline water quality. The archaeological survey completed by Lawrence et al. (2019) indicated 59 historic mine archaeological sites were identified within a 16 km² survey area. The majority of mine workings were pre-1900 mining activities and included the following key historic workings (Lawrence et al., 2019):

- Stamping batteries and processing areas.
- Underground mine adits.
- Mullock piles and tailings mounds.
- Sluicing areas.

These historical workings have affected the water quality in the area. For instance, arsenic is elevated in the Rise and Shine Creek, which is below these historic workings (MWM, 2025a).

Project Description

The proposed BOGP will include the following components:

- Open pits targeting the RAS, SRX, SRE, and CIT deposits.
- An underground mine targeting the RAS deposit.
- Three ex-pit engineered landforms (ELFs) Shepherds ELF, SRX ELF, and West ELF (WELF).

- Two in-pit landforms (backfill) CIT and SRE².
- Plant and processing area, where carbon-in-leach (CIL) extraction technologies will be used as part of the ore recovery process.
- A tailings storage facility (TSF) and TSF Embankment.
- Other ancillary support services / structures (e.g., roads, water management infrastructure, water treatment plants, etc).

Baseline Studies

The proposed BOGP water quality compliance limits (Ryder, 2025) are used as a screening tool to determine whether baseline water quality data are elevated. The assessment (MWM, 2025a) indicated that:

- Shepherds Creek is elevated in copper (Cu).
- Bendigo Creek is elevated in arsenic (As), cobalt (Co), Cu, and iron (Fe).
- <u>Groundwater</u> is elevated in As, Cu, Fe, zinc (Zn), and on occasion strontium (Sr) within the project area. Thallium (Tl) was elevated on one occasion (although this appears anomalous).

Geoenvironmental Hazards

All BOGP materials are classified as non-acid forming (NAF), with circum-neutral pH drainage expected from mine domains that contain the materials. However, neutral metalliferous drainage is likely to occur with elevated levels of arsenic (As), sulfate (SO₄), trace metal, and nitrogenous compounds.

The most significant AMD source hazard for waste rock relates to the TZ4 and RSSZ materials, some of which will be waste rock, and some will be processed (to extract gold) producing tailings.

Data for waste rock indicates that the TZ4 and RSSZ lithologies contain ~95.3% of arsenic and 21.9% of sulfur yet represents only 9.3% of the waste rock that will be disturbed. Hence, appropriate management of TZ4 and RSSZ materials to reduce sulfide mineral oxidation is a critical step to minimise deleterious effects, i.e., manage 9.3% of the waste rock well to mitigate 95.3% of the arsenic risk in the engineered landforms (ELFs) that will contain the waste rock.

The following potential constituents of concern (PCOC) are identified and are considered in this report:

- TZ3 materials are enriched As and cobalt (Co). Antimony (Sb) is possibly elevated.
- RZ4 and RSSZ materials are enriched in As, sulfur (S). Sb is possibly elevated.
- Geochemical testing indicates that BOGP materials could generate MIW that could be elevated in aluminium (AI), As, Co, copper (Cu), chromium (Cr), iron (Fe), and zinc (Zn).
- Process water quality data suggests that AI, As, Co, Cu, Cr, Fe, molybdenum (Mo), nickel (Ni), lead (Pb), Sb, strontium (Sr), Zn, cyanide (CN), and ammoniacal nitrogen (Amm-N) may be elevated. It is noted these data are limited.

² Note: SRE Pit is backfilled by the SRX ELF.

- Based on analogue data and general geoenvironmental hazards:
 - Nitrogenous compounds (nitrate and ammoniacal nitrogen) are expected due to the use on ammonium-nitrate based explosives and cyanide.
 - Sulfate is considered a PCOC based on sulfate being elevated at the Macraes Gold Mine, which is considered a suitable analogue site due to its similar sulfur content.

Water and Load Balance Model

A WLBM that contains water flow and quality data is required for the BOGP to understand potential deleterious effects on the receiving environment associated with these MIW (noting the management of TSS is covered by the sediment and erosion management plan: EGL (2025a)). The WLBM has been developed using the GoldSim modelling platform³. Key water quality inputs (source terms) need to be defined for the WLBM and this includes the following key model components:

- Baseline streams within the BOGP area
- Groundwater
- Engineered Landform (ELF) seepage
- Pit voids
- · Ore stockpile
- Tailings storage facility (TSF)
- Hardstand areas, ELF surfaces, and roads (e.g., mine impacted surfaces)
- Underground workings
- Rehabilitated surfaces

Derivation of Source Terms

Source terms were developed from a variety of sources including analogue data sources, baseline studies at the BOGP, and laboratory derived data from environmental geochemistry testing. This report provides an explanation of how the source terms for modelling were developed for the WLBM.

Source terms need to be validated through performance monitoring that should be ongoing through the operational and closure phases of the project.

-

³ <u>https://www.goldsim.com</u>

TABLE OF CONTENTS

1	Intro	oduction	1
	1.1	Background	1
	1.2	Project Description	1
	1.3	Mine Plan	3
	1.4	Objectives	3
	1.5	Source Term Components	4
	1.6	Modelling Approach	4
2	Proj	ect Area Description	5
	2.1	Introduction	5
	2.2	Surface Water	6
	2.3	Soils	7
	2.4	Geology	8
	2.4.	1 Regional Geology	8
	2.4.	2 Project Geology	9
	2.5	Geochemistry	9
3	Sou	rce Terms – Rainfall Water Quality	.11
	3.1	Data Source	. 11
	3.1.	1 Rainfall Water Quality Source Term	.11
	3.1.	2 Assumptions	. 11
4	Sou	rce Terms - Baseline Water Quality	. 12
	4.1	Surface Water Quality	. 12
	4.1.	1 Shepherds Creek Catchment Source Term	. 12
	4.1.	2 Bendigo Creek Catchment Source Term	. 13
	4.1.	3 Temperature Effects	. 14
	4.1.	4 Assumptions	. 15
	4.1.	5 Performance Monitoring	. 15
	4.2	Groundwater Quality	. 15
	4.2.	1 Groundwater Source Term	. 15
	4.2.	2 Assumptions	. 17
	4.2.	3 Performance Monitoring	. 17
5	Eng	ineered Landforms	
	5.1	Background	. 18
	5.2	Literature Review - Macraes	
	5.3	Source Terms	
	5.4	Assumptions	
	5.5	Performance Monitoring	
6		Voids	
	6.1	Literature Review – Pit Lakes	
	6.2	Literature Review – Pit Wall Runoff	24

	6.3	Des	cription	24
	6.3.	1	RAS Pit	24
	6.3.	2	SRX Pit	25
	6.3.	3	CIT Pit	25
	6.4	Sou	rce Terms	25
	6.4.	1	RAS and SRX Pit Wall Runoff	26
	6.4.	2	CIT Pit Backfill	27
	6.5	Ass	umptions	27
	6.6	Perf	formance Monitoring	27
7	RAS	S Un	derground Workings	28
	7.1	Lite	rature Review – Golden Point Adit – Macraes	28
	7.2	Low	er Bendigo Adit	29
	7.3	Und	lerground Working Source Term	31
	7.3.	1	RAS Underground – Operational Phase Source Term	31
	7.3.	2	RAS Underground – Closure Phase Source Term	31
	7.4	Ass	umptions	31
	7.5	Perf	formance Monitoring	32
8	Sou	rce 7	Terms – Mine Impacted Waters	33
	8.1	Imp	acted Run-off Water Quality	33
	8.2	Disc	cussion – Dust Suppression Water	34
	8.2.	1	Analysis – Dust Suppression Water	34
	8.3	Sou	rce Terms: Mine Impacted Surfaces and Rehab Surfaces	34
	8.4	Ass	umptions	36
	8.5	Perf	formance Monitoring	37
	8.6	Ore	Stockpile	37
9	Sou	rce 7	Terms – Tailings Storage Facility	38
	9.1	Bac	kground	38
	9.2	Lite	rature Review	38
	9.2.	1	Tailings Cyanide Concentrations	41
	9.2.	2	Geochemical Maturation of Seepage Waters	41
	9.2.	3	Literature Review Summary	44
	9.3	Pro	cess Water	44
	9.3.	1	Process Water Treatment	44
	9.3.	2	Metallurgical Test Data	44
	9.4	TSF	Seepage Source Term	46
	9.5	Ass	umptions	46
	9.6	Perf	formance Monitoring	47
10	S	ourc	e Terms - Treated Water	48
	10.1	Α	ctive Water Treatment	48
	10.2	Р	assive Water Treatment	48
11	С	losin	g	49

11.	1 V	Vater and Load Balance Model Summary	49
11.2	2 D	Perivation of Source Terms	49
11.3	3 V	Vater Balance Model	49
11.4	4 S	Summary	50
12	Refer	ences	51
13	Limita	itions	54
Apper	ndix A	Abbreviations	
Apper	ndix B	Mineralis Report	
Apper	ndix C	Limitations	

LIST OF TABLES

Table 1. BOGP Mine Plan	3
Table 2. Rainfall Quality Source Term Data	11
Table 3. Surface water quality source terms for Shepherds Creek.	12
Table 4. Surface water quality source terms for Bendigo Creek.	13
Table 5: Average seasonal water temperature at proposed compliance monitoring sites SC01 and RS03.	
Table 6. Water quality source terms for groundwater	16
Table 7. WRS silt pond seepage water quality from Macraes. From Golder (2011b)	18
Table 8. Pit Lake Water Quality – Frasers.	20
Table 9. Pit Lake Water Quality – Golden Bar Pit	20
Table 10. Pit Lake Water Quality – Golden Point Pit	21
Table 11. Pit Lake Water Quality – Innes Mills South	21
Table 12. Pit Lake Water Quality – Round Hill	22
Table 13. Frasers Pit wall runoff water quality	24
Table 14. RAS Pit Material Summary	24
Table 15. SRX Pit Material Summary.	25
Table 16. BOGP Pit Wall Runoff Source Term	26
Table 17. Golden Point Adit Water Quality. From Golder 2011c	29
Table 18. Groundwater source term for the RAS Underground based on LBA	30
Table 19. MIW – Macraes	33
Table 20. Source terms: Mine Impacted Surfaces and Rehabilitated Surfaces	35
Table 21: Macraes MTI average water quality between 1994 – 1999: decant water and the outflow chimney drain	_
Table 22: Representative water quality in November 1993, when the CTI and FTI were active	43
Table 23: Source Terms: Process water quality and tailings seepage water	45
LIST OF FIGURES	
Figure 1. Bendigo-Ophir Gold Project Infrastructure	6
Figure 2. Bendigo-Ophir Gold Project area and water quality monitoring sites	7
Figure 3. Arsenic concentration in soils in the study area	8
Figure 4. Golden Bar Pit Lake nitrate-N and ammoniacal-M concentrations and loads over time	23
Figure 5. Lake water residence time and nitrogen removal	
Figure 6. CIT Backfill	
Figure 7. Golden Point Adit water quality	28
Figure 8. Macraes Gold Mine TSF Decant Water Quality - Sulfate	39
Figure 9. Macraes Gold Mine TSF Decant Water Quality - Arsenic	40
Figure 10. Macraes Gold Mine TSF Decant Water Quality - Iron	40

Figure	11.	Cyanide -	WAD -	Macrae	s		41	
Figure	12: I	Macraes T	ailings s	eepage	water q	uality	42)

1 INTRODUCTION

Mine Waste Management Limited (MWM) has developed this report to define the source terms for the water and load balance model (WLBM) for the Bendigo-Ophir Gold Project (BOGP) for Matakanui Gold Limited (MGL) to provide a summary of inputs that will be used during the modelling process. The WLBM is discussed in MWM (2025c).

1.1 Background

MGL is proposing to establish the BOGP, which comprises a new gold mine, ancillary facilities and environmental mitigation measures on Bendigo and Ardgour Stations in the Dunstan Mountains of Central Otago. The project site is located approximately 20 km north of Cromwell and will have a maximum disturbance footprint of 550 hectares.

As part of the assessment of environmental effects, the BOGP requires the development of a WLBM that will simulate flow and key water quality parameters associated with mine impacted waters (MIW) to support water management and treatment planning/design and forecast water quality at downstream compliance monitoring sites.

A key component of developing a WLBM is the development of appropriate source terms to define the water quality of each model domain. Some of these source terms will share commonality between model components, others will be unique to the model domain. Clarity on how these terms are derived is important to support the modelling process.

1.2 Project Description

MGL is proposing to establish the BOGP, which comprises gold mining operations, processing operations, ancillary facilities and environmental mitigation measures on Bendigo and Ardgour Stations in the Dunstan Mountains of Central Otago. The project site is located approximately 20 km north of Cromwell and will have a maximum disturbance footprint of 550 hectares.

The total Mineral Resource Estimate for the BOGP using a 0.5 g/t cut-off for open pit and 1.5 g/t for underground is 34.3 Mt at 2.1 g/t for 2.34 M oz (MGL, 2025). The Bendigo-Ophir resources occur in four deposits: Come in Time (CIT), Rise and Shine (RAS), Srex (SRX), Srex East (SRE). The majority of identified mineral resources are located within the RAS deposit. Three primary geological units are recognised at site:

- RSSZ Rise and Shine Shear Zone
- TZ3 Lower Greenschist facies Textural Zone 3 rocks of the Otago Schist
- TZ4 Upper Greenschist facies Textural Zone 4 rocks of the Otago Schist

The resources will be mined by open pit methods at each deposit within the project site, with underground mining methods also proposed to be utilised at RAS to access the deeper gold deposits. The majority of the mining activities, ancillary facilities and associated infrastructure will be located in the Shepherds Valley – which includes a conventional carbon-in-leach (CIL) gold processing plant and water treatment plant, a tailing storage facility, three engineered landforms, internal haul roads, topsoil stockpiles, water pipelines, underground utilities and electrical supply - with non-operational infrastructure located on the adjoining Ardgour Terrace. The BOGP also involves the taking of

Page 1 MWM-S003-Rev2

groundwater from the Bendigo Aquifer for use in mining-related activities and the realignment of Thomson Gorge Road via Ardgour Station.

There are numerous historic mine workings throughout the project area, which can impact baseline water quality. The archaeological survey completed by Lawrence et al. (2019) indicated 59 historic mine archaeological sites were identified within a 16 km² survey area. The majority of mine workings were pre-1900 mining activities and included the following key historic workings (Lawrence et al., 2019):

- Stamping batteries and processing areas.
- Underground mine adits.
- Mullock piles and tailings mounds.
- Sluicing areas.

These historical workings have affected the water quality in the area. For instance, arsenic (As) is elevated in the Rise and Shine Creek, a tributary of Bendigo Creek, which is below these historic workings (MWM, 2025a).

The proposed BOGP will include the following components:

- Open pits targeting the RAS, SRX, SRE, and CIT deposits.
- An underground mine targeting the RAS deposit.
- Three ex-pit engineered landforms (ELFs) Shepherds ELF, SRX ELF, and West ELF (WELF).
- Two in-pit landforms (backfill) CIT and SRE⁴.
- Plant and processing area, where CIL extraction technologies will be used as part of the ore recovery process.
- A tailings storage facility (TSF) and TSF Embankment.
- Other ancillary support services / structures (e.g., roads, water management infrastructure, water treatment plants, etc).

Page 2 MWM-S003-Rev2

⁴ Note: SRE Pit is backfilled by the SRX ELF.

1.3 Mine Plan

The proposed mine plan is shown in Table 1 as a schedule of activities.

Table 1. BOGP Mine Plan

MONTH YEAR		MINING PHASE	DESCRIPTION OF PHASE		
		Pre-startup	Detailed design phase		
0 to 6	0 to 0.5	Startup	Pioneering / RAS Pre-Strip, Initial Jean Creek Silt Pond, earthworks at process plant.		
6 to 24	0.5 to 2	Project Development	Construction of process plant, TSF, Shepherds Creek Silt Pond, North Diversion Channel, Commissioning, mining RAS pre- strip (Pre-strip ends month 19).		
		Operations			
25 to 54	54 3 to 4.5 RAS pit mining on its own		Operations (Pit ore production in month 20. UG Development begins month 54)		
54 to 72	4.5 to 5	RAS pit with UG development	Operations (UG Ore production begins month 70 -)		
72 to 132	2 to 132 6 to 11 RAS pit plus RAS		Operations (UG Ore production months 70 to 150)		
		RAS Pit plus RAS UG plus CIT Pit	Operations (CIT Pit mined months 102 to 114)		
		RAS Pit plus RAS UG, plus CIT backfilled, plus Srex	Operations (Srex Pit mined months 145 onwards)		
120 - 160	10 to 13.3	RAS UG continues on its own with CIT and Srex open pit feeds	Operations (all mining halted month 160)		
		Closure			
160 - 372	11 to 31	Active Closure	All mining halted. Active closure of pits, TSF, and wider site, plus setup of active water treatment plant (option).		
372 -	31 onwards	Post-Closure	Passive treatment and maintenance		

TSF = Tailings Storage Facility; UG = Underground

1.4 Objectives

The purpose of this report is to define and present the relevant data that have been used to derive the key source terms to be used in the WLBM for the BOGP. The objectives of this report are to:

- Define the sources of data used for developing the water quality source terms.
- Define the rationale applied in deriving the source terms.
- Propose what performance monitoring is required to ensure potential effects are understood in advance.

Page 3 MWM-S003-Rev2

1.5 Source Term Components

Models that assess the effects on water quality generally require flow rates and water quality estimates. Source terms are created to represent the water quality of each component of the model. Source terms are derived from empirical site data and analogue data, which may be from the compilation of data (mean, 95th percentile, etc) or from geochemical relationships (e.g., sulfate versus potential constituents of concern (PCOC)). Source terms that require definition for BOGP include:

- The composition of rainfall water, for understanding its interaction with project materials.
- Baseline surface water quality.
- Groundwater inflow quality (e.g., to the RAS Pit void).
- ELF seepage.
- Process water quality associated with the tailings (assumed to be representative of TSF decant water quality).
- Pit water quality.
- TSF decant water.
- TSF seepage water quality.
- MIW quality associated with ELF runoff, haul roads, and hardstand areas.
- Underground workings (operational and closure).
- Rehabilitated surfaces.

1.6 Modelling Approach

Water management during the Operational Phase of the BOGP will involve discharge of only episodic runoff from haul roads and ELF surfaces. All other MIW (e.g., landform seepage) will be collected, used, and stored on site. In the Active Closure / Post Closure Phase, MIW will be treated and discharged to the receiving environment. Two models have been developed (MWM, 2025c) to reflect these phases:

- Operational Phase Excel based models and calculations focussing on average annual water balance and runoff event discharge of MIW.
- Active Closure / Post Closure Phase GoldSim based models and calculations, focussing on the evolution of instream water quality over time as a result of discharge of treated MIW.

Detailed stage models for years 1-13 of the BOGP (Table 1) will be developed using GoldSim⁵ prior to mining commencing (i.e., during the project pre-startup phase). This will provide an operational tool for MGL to effectively manage water during operations.

Page 4 MWM-S003-Rev2

⁵ https://www.goldsim.com

2 PROJECT AREA DESCRIPTION

The following section summarises the relevant background information for the BOGP.

2.1 Introduction

MGL is proposing to establish the BOGP, which comprises gold mining operations, processing operations, ancillary facilities and environmental mitigation measures on Bendigo and Ardgour Stations in the Dunstan Mountains of Central Otago. The project site is located approximately 20 km north of Cromwell and will have a maximum disturbance footprint of 550 hectares.

The total Mineral Resource Estimate for the BOGP using a 0.5 g/t cut-off for open pit and 1.5 g/t for underground is 34.3 Mt at 2.1 g/t for 2.34 M oz (MGL, 2025). The Bendigo-Ophir resources occur in four deposits: Come in Time (CIT), Rise and Shine (RAS), Srex (SRX), Srex East (SRE). The majority of identified mineral resources are located within the RAS deposit. Three primary geological units are recognised at site:

- RSSZ Rise and Shine Shear Zone
- TZ3 Lower Greenschist facies Textural Zone 3 rocks of the Otago Schist
- TZ4 Upper Greenschist facies Textural Zone 4 rocks of the Otago Schist

The resources will be mined by open pit methods at each deposit within the project site, with underground mining methods also proposed to be utilised at RAS to access the deeper gold deposits. The majority of the mining activities, ancillary facilities and associated infrastructure will be located in the Shepherds Valley – which includes a conventional carbon-in-leach (CIL) gold processing plant and water treatment plant, a tailing storage facility, three engineered landforms, internal haul roads, topsoil stockpiles, water pipelines, underground utilities and electrical supply - with non-operational infrastructure located on the adjoining Ardgour Terrace. The BOGP also involves the taking of groundwater from the Bendigo Aquifer for use in mining-related activities and the realignment of Thomson Gorge Road via Ardgour Station.

There are numerous historic mine workings throughout the project area, which can impact baseline water quality. The archaeological survey completed by Lawrence et al. (2019) indicated 59 historic mine archaeological sites were identified within a 16 km² survey area. The majority of mine workings were pre-1900 mining activities and included the following key historic workings (Lawrence et al., 2019):

- Stamping batteries and processing areas.
- Underground mine adits.
- Mullock piles and tailings mounds.
- Sluicing areas.

These historical workings have affected the water quality in the area. For instance, As is elevated in the Rise and Shine Creek, a tributary of Bendigo Creek, which is below these historic workings (MWM, 2025a).

The proposed BOGP will include the following components as shown in Figure 1:

Open pits targeting the RAS, SRX, SRE, and CIT deposits.

Page 5 MWM-S003-Rev2

- · An underground mine targeting the RAS deposit.
- Three ex-pit engineered landforms (ELFs) Shepherds ELF, SRX ELF, and West ELF (WELF).
- Two in-pit landforms (backfill) CIT and SRE⁶.
- Plant and processing area, where CIL extraction technologies will be used as part of the ore recovery process.
- A tailings storage facility (TSF) and TSF Embankment.
- Other ancillary support services / structures (e.g., roads, water management infrastructure, water treatment plants, etc).




Figure 1. Bendigo-Ophir Gold Project Infrastructure

2.2 Surface Water

The project area covers several catchments and sub-catchments (Figure 2), including:

• Shepherds Creek: This creek runs through the project area and runs intermittently towards the Lindis River. An irrigation water-take on Shepherds Creek (RM17.301.15) downstream of SC1 monitoring site takes all available surface water in normal flow conditions, which is supplied to an irrigation dam, so the creek does not flow past this point. There is potential for groundwater to flow past this point via a thin layer of alluvial gravels along the creek bed.

Page 6 MWM-S003-Rev2

⁶ Note: SRE Pit is backfilled by the SRX ELF.

- Jean Creek: This creek is an intermittent tributary to Shepherds Creek.
- Rise and Shine Creek: This creek reek joins Clearwater Creek south-east of the Come in Time Battery and flows into Bendigo Creek.
- Clearwater Creek: Flows into Bendigo Creek.
- Bendigo Creek: Several irrigation water-takes are in place on this creek (RM20.079.01 and RM20.079.02).




Figure 2. Bendigo-Ophir Gold Project area and water quality monitoring sites.

The proposed BOGP water quality compliance limits (Ryder, 2025) are used as a screening tool to determine whether baseline water quality data are elevated. The assessment (MWM, 2025a) indicated that:

- Shepherds Creek is elevated in copper (Cu).
- Bendigo Creek is elevated in arsenic (As), cobalt (Co), Cu, and iron (Fe).
- <u>Groundwater</u> is elevated in As, Cu, Fe, zinc (Zn), and on occasion strontium (Sr) within the project area. Thallium (Tl) was elevated on one occasion (although this appears anomalous).

Further details are provided in MWM (2025a).

2.3 Soils

MGL has conducted a soil study within the Rise and Shine Creek to map the distribution of As in the soils. This study utilised portable X-ray fluorescence (pXRF) and the results are presented in Figure 3.

Page 7 MWM-S003-Rev2

The average crustal abundance of As is approximately 1.5 ppm (AusIMM, 2011), while the As concentrations observed in the soil within the Rise and Shine Creek valley ranged from 20 - >500 ppm. These anomalous As concentrations are likely to be associated with mineralisation that created the gold deposit.

Further studies have been completed on these As-rich soils (GRM, 2025).




Figure 3. Arsenic concentration in soils in the study area.

Data source: Santana (2024) - GIS Shape Files

2.4 Geology

2.4.1 Regional Geology

The Dunstan Mountains are an uplifted block of the Otago Schist tilted to the northwest with remnants of a Cretaceous peneplain well preserved on its northern slopes. The Otago Schist is formed from sedimentary and minor intermediate volcanics and volcaniclastics of the Caples and Torlesse tectonostratigraphic terranes. Greenschist facies rocks of the Otago schist are sub-divided into four textural zones based on mineralogy and mineral textures. Peak metamorphic grades in the Otago Schist occurred during the Jurassic when the Zealandia micro continent formed the outboard subduction complex of the Gondwana continental margin.

The regional geology of the Central Otago goldfields surrounding the BOGP consists of chlorite and biotite schists. The Rise & Shine Shear Zone (RSSZ), a late metamorphic deformation zone (Cox et al., 2006), runs through the project area dipping at 20-30 degrees northeast. The RSSZ occurs only in the footwall Textural Zone 4 (TZ4) schist in close association with the Thomsons Gorge Fault, which cuts and truncates the RSSZ against the unmineralised TZ3 schist (Cox et al., 2006). There is no

Page 8 MWM-S003-Rev2

mineralisation associated with the Thomsons Gorge Fault itself, and Au mineralisation had ceased by the time of formation of the Thomsons Gorge Fault (c. 100 Ma) (Cox et al., 2006).

2.4.2 Project Geology

The project area contains four discrete mineral occurrences:

- Rise and Shine (RAS) deposit
- · Come in Time (CIT) deposit
- Srex (SRX) deposit
- Srex East (SRE) deposit

The main mineralisation at RAS is associated with silica-siderite/ankerite alteration with minor arsenopyrite sulfides associated with the gold. In some areas a cataclastite (brecciated) network of anastomosing, post-metamorphic quartz, occur with minor sulfide veins in a halo of the core mineralisation. Allibone (2023) also identified the presence of sphalerite ((Zn,Fe)S) and galena (PbS) at the BOGP.

Locally, a number of splay faults are interpreted coming off the main structure which give a sense of structural control. These are also mineralised and are traceable for 10s to 100s of metres. Gold occurs as free gold particles, typically up to 400 µm but with some coarser visible gold. A minor gold component occurs associated with the arsenopyrite grains, but it is typically not in solid solution, giving rise to the free milling and highly gravity recoverable components expressed by metallurgical testing.

2.5 Geochemistry

All BOGP materials are classified as non-acid forming, with circum-neutral pH drainage expected from mine domains that contain the materials. However, neutral metalliferous drainage is likely to occur with elevated levels of As, sulfate (SO₄), trace metal, and nitrogenous compounds.

The most significant AMD source hazard for waste rock relates to the TZ4 and RSSZ materials, some of which will be waste rock, and some will be processed (to extract gold) producing tailings.

Data for waste rock indicates that the TZ4 and RSSZ lithologies contain ~95.3% of arsenic and 21.9% of sulfur yet represents only 9.3% of the waste rock that will be disturbed. Hence, appropriate management of TZ4 and RSSZ materials to reduce sulfide mineral oxidation is a critical step to minimise deleterious effects, i.e., manage 9.3% of the waste rock well to mitigate 95.3% of the arsenic risk in the engineered landforms (ELFs) that will contain the waste rock.

The following potential constituents of concern (PCOC) are identified and are considered in this report:

- TZ3 materials are enriched As and cobalt (Co). Antimony (Sb) is possibly elevated.
- RZ4 and RSSZ materials are enriched in As, sulfur (S). Sb is possibly elevated.
- Geochemical testing indicates that BOGP materials could generate MIW that could be elevated
 in aluminium (Al), As, Co, copper (Cu), chromium (Cr), iron (Fe), and zinc (Zn).
- Process water quality data suggests that AI, As, Co, Cu, Cr, Fe, molybdenum (Mo), nickel (Ni), lead (Pb), Sb, strontium (Sr), Zn, cyanide (CN), and ammoniacal nitrogen (Amm-N) may be elevated. It is noted these data are limited.

Page 9 MWM-S003-Rev2

- Based on analogue data and general geoenvironmental hazards:
 - Nitrogenous compounds (nitrate and ammoniacal nitrogen) are expected due to the use on ammonium-nitrate based explosives and cyanide.
 - Sulfate is considered a PCOC based on sulfate being elevated at the Macraes Gold Mine, which is considered a suitable analogue site due to its similar sulfur content.

Further details are provided in MWM (2024b).

Page 10 MWM-S003-Rev2

3 SOURCE TERMS - RAINFALL WATER QUALITY

This section summarises the rainfall water quality data used for the project area.

3.1 Data Source

Rainfall water quality is required as an input to the WLBM (MWM, 2024c). Further climatic information is available in Rekker (2025).

3.1.1 Rainfall Water Quality Source Term

The source term for average rainfall water quality is obtained from Nichol et al. (1997) using the Lauder collection site, which includes rainfall water quality data from 1983 to 1994. The Lauder site is located to the west of BOGP with an annual rainfall of 530 mm/year (Nichol et al., 1997) and therefore presents a reasonable dataset for rainfall water quality.

The rainfall quality data is provided in Table 2. The rainfall is slightly acidic with a pH value of 5.2 and with a low alkalinity (0.8 mg/L as CaCO₃).

Table 2. Rainfall Quality Source Term Data

PARAMETERS	UNITS	VALUE	
рН	pH unit	5.2	
Acidity	mg/L as CaCO₃	2.28	
Alkalinity Total	mg/L as CaCO₃	0.81	
Са	mg/L	0.11	
CI	mg/L	0.31	
К	mg/L	0.88	
Mg	mg/L	0.09	
Na	mg/L	0.32	
NO ₃ -N	mg/L	0.06	
SO ₄	mg/L	0.18	

Source: Nichol et al., 1997: Table 5 (Lauder M8391) for the period 1983 – 1991 (monthly data).

These data are used as the source term for rainfall in the WLBM.

3.1.2 Assumptions

• It is assumed these data represent the reasonable concentrations of rainfall and that the average data provided are suitable.

Page 11 MWM-S003-Rev2

4 SOURCE TERMS - BASELINE WATER QUALITY

This section reviews baseline water quality for the BOGP area.

4.1 Surface Water Quality

Source terms for baseline water quality have been derived from surface water quality data from the Shepherds Creek and Bendigo Creek (e.g., Rise and Shine Creek) areas, with monitoring data covering multiple locations from 2022 to 2024. The complete presentation and analysis of data, including discussion of monitoring data limitations is provided in the baseline water quality report (MWM, 2025a).

4.1.1 Shepherds Creek Catchment Source Term

Surface water quality data for Shepherds Catchment are provided in Table 3. The following observations are provided:

- Concentrations of dissolved parameters are generally lower in the upper catchment (e.g., SC03 and JC01) and are likely to be unaffected by mineralisation, which could influence SC01.
- In the upper catchment, SC03 has a larger dataset, which provides more confidence in the data.
- Data lower than the limit of reporting (LOR) are presented in Table 3 in green text as half the LOR. For the source term they are treated as a value of 0 in the WLBM.
- Average data for SC03 (as shown in Figure 2) were selected as the source term for water quality in the WLBM for the Shepherds Creek Catchment and is assumed to be reflective of water quality in the catchment (as shown by yellow data in Table 3).

Table 3. Surface water quality source terms for Shepherds Creek.

	SC01	SC03	JC01
PARAMETERS	(n=25)	(n=21)	(n=6)
PARAMETERS	AVE	AVE	AVE
	(mg/L)	(mg/L)	(mg/L)
Alkalinity (mg CaCO ₃ /L)	216.0	136.2	246.3
pH (pH units)	8.11	7.88	8.30
EC (µS/cm)	488.9	319.1	498.0
Ca	60.8	40.9	53.3
CI	6.08	2.74	5.55
F	0.103	0.119	0.076
Mg	21.3	10.2	20.1
Na	20.3	36.2	59.0
К	2.01	1.43	1.98
TOC	2.08	2.01	4.40
Al	0.00454	0.00640	0.0070
As	0.00239	0.00079	0.00085
В	0.03304	0.0280	0.0337
Cd	0.00010	0.00011	0.00011
Со	0.00026	0.00029	0.00031
Cr	0.00056	0.00062	0.00060
Cu	0.00055	0.00055	0.00143

Page 12 MWM-S003-Rev2

	SC01	SC03	JC01
DADAMETERS	(n=25)	(n=21)	(n=6)
PARAMETERS	AVE	AVE	AVE
	(mg/L)	(mg/L)	(mg/L)
Fe	0.01135	0.0215	0.00750
Hg	0.00026	0.00030	0.00029
Mn	0.00265	0.00357	0.00104
Мо	0.00051	0.00044	0.00114
Ni	0.00035	0.00036	0.00039
Pb	0.00025	0.00029	0.00034
Sb	0.00053	0.00058	0.00073
Se	0.0025	0.0029	0.0028
Sr	0.947	0.675	0.718
TI	0.00023	0.00027	0.00026
U	0.0051	0.0022	0.006
V	0.0005	0.0005	0.0005
Zn	0.0017	0.0015	0.0025
Sulfate	40.5	14.4	18.5
Ammoniacal nitrogen	0.0103	0.0117	0.0075
Nitrate-N	0.083	0.139	0.062
TCN	0.0028	0.0032	0.0026

Note: Green data are 1/2 LOR and are included in the source term as '0'

4.1.2 Bendigo Creek Catchment Source Term

Surface water quality source terms for the Bendigo Creek Catchment are provided in Table 4. The following observations are provided:

- Water quality in the Rise and Shine Creek is generally poorer than the water quality in Shepherds Creek due to the historic mining activities and natural mineralisation (e.g., refer to MWM, 2025a).
- RS04 was selected (Figure 2) to represent water quality within the catchment upstream of the Rise and Shine historic mine workings (as shown by yellow data in Table 4). Average water quality data are provided Table 4.
- Data lower than the LOR are presented in Table 4 in green text as half the LOR. For the source term they are treated as a value of 0 in the WLBM.
- Average data for CC01 was selected (as shown by green data in Table 4) as the source term for water quality in the WLBM for the Clearwater Creek Catchment and is assumed to be reflective of water quality in the catchment.

Table 4. Surface water quality source terms for Bendigo Creek.

	RSA1	RS01	RS02	RS03	RS04	CC01
DADAMETERS	(n=25)	(n=26)	(n=26)	(n=25)	(n=14)	(n=16)
PARAMETERS	AVE	AVE	AVE	AVE	AVE	AVE
	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)
Alkalinity (mg CaCO₃/L	107.8	87.5	65.8	39.1	72.8	14.7
pH (pH units)	7.32	7.61	7.57	7.42	7.51	7.03

Page 13 MWM-S003-Rev2

	RSA1	RS01	RS02	RS03	RS04	CC01
	(n=25)	(n=26)	(n=26)	(n=25)	(n=14)	(n=16)
PARAMETERS	AVE	AVE	AVE	AVE	AVE	AVE
	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)
EC (µS/cm)	211.7	181.8	151.4	86.4	165.0	34.0
Ca	28.7	26.3	19.7	11.1	23.3	3.88
CI	2.55	2.38	2.07	1.33	1.96	0.794
F	0.096	0.086	0.082	0.057	0.059	0.055
Mg	5.22	4.82	3.61	1.99	3.74	0.844
Na	52.5	10.4	6.87	39.5	5.15	2.35
К	1.04	1.14	1.07	0.578	1.18	0.335
TOC	4.04	2.77	2.09	1.75	2.75	1.23
Al	0.00288	0.00421	0.00820	0.00756	0.00686	0.01231
As	0.0386	0.0193	0.0049	0.0085	0.001	0.0010
В	0.0188	0.0185	0.0185	0.0188	0.011	0.0175
Cd	0.00010	0.00010	0.00010	0.00010	0.00003	0.00009
Со	0.00053	0.00026	0.00025	0.00025	0.00013	0.00021
Cr	0.00058	0.00054	0.00054	0.00059	0.00026	0.00056
Cu	0.00185	0.00057	0.00063	0.00046	0.00083	0.00043
Fe	0.2048	0.0614	0.0245	0.0375	0.068	0.0293
Hg	0.00026	0.00026	0.00026	0.00026	0.00011	0.00024
Mn	0.1614	0.0211	0.0011	0.0095	0.006	0.0009
Мо	0.00034	0.00034	0.00033	0.00033	0.00022	0.00033
Ni	0.00049	0.00044	0.00041	0.00035	0.00049	0.00056
Pb	0.00025	0.00025	0.00025	0.00025	0.00008	0.00022
Sb	0.00050	0.00048	0.00048	0.00050	0.00017	0.00044
Se	0.0025	0.0024	0.0024	0.0025	0.0008	0.0022
Sr	0.381	0.358	0.266	0.136	0.315	0.042
TI	0.00023	0.00022	0.00022	0.00023	0.00005	0.00019
U	0.00025	0.00015	0.00026	0.00012	0.00030	0.00009
V	0.00050	0.00050	0.00050	0.00050	0.00050	0.00050
Zn	0.00466	0.00175	0.00204	0.00229	0.00142	0.00161
Sulfate	4.52	5.13	2.72	1.57	2.80	0.843
Ammoniacal nitrogen	0.0222	0.0098	0.0121	0.0092	0.013	0.0086
Nitrate-N	0.0153	0.0171	0.0308	0.0088	0.0033	0.0096
TCN	0.0028	0.0028	0.0028	0.0028	0.0013	0.0026

Note: Green data are 1/2 LOR and are included in the source term as '0'

Average data for RS04 (see Figure 2) was selected as the source term for water quality in the WLBM for the Rise and Shine Creek Catchment and is assumed to be reflective of water quality in the catchment.

4.1.3 Temperature Effects

The temperature of the streams at the proposed compliance monitoring sites (SC01 and RS03) were assessed to derive average summer and winter stream water temperature. These average data are used to modify toxicity for cyanide and sulfide (e.g., Ryder, 2025). These data are presented in Table 5

Page 14 MWM-S003-Rev2

The WLBM does not consider temperature effects given that cyanide is not modelled, and sulfide will be a function of passive treatment in the post closure phase when further empirical data will be available of understand effects.

Table 5: Average seasonal water temperature at proposed compliance monitoring sites SC01 and RS03.

SITE ID	SEASON	AVERAGE TEMPERATURE (°C)
DOGG	Summer (November – April)	10.7
RS03 -	Winter (May – October)	4.4
0004	Summer (November – April)	14.2
SC01 -	Winter (May – October)	7.2

Note: Calculated from data obtained over the period 2023-2025.

4.1.4 Assumptions

The following assumptions are presented for the source term for the baseline streams:

- It is assumed that the average water quality provides a reasonable dataset to create a source term for the project area for non-impacted catchments.
- It is assumed that water quality data upstream of mineralisation is suitable as the baseline water quality with the expectation that mineralised areas will be mined.

4.1.5 Performance Monitoring

The following performance monitoring is recommended for the baseline stream water quality:

- Ongoing monitoring of water monitoring sites SC01 and RS03 including continuous flow, EC, temperature, and pH; and monthly grab samples for water quality and compliance monitoring.
- Ongoing performance monitoring of RS01 for water quality effects associated with the project and historic mining activities / natural mineralisation.
- Ongoing performance monitoring of Clearwater Creek as a control site (monthly samples for water quality).
- Comparison of water quality data and trends against agreed BOGP water quality compliance limits as proposed by Ryder (2025).

4.2 Groundwater Quality

Groundwater is implicitly included within the WLBM through the use of baseline groundwater quality data for the BOGP. However, a source term is required for inflow to the pit voids.

4.2.1 Groundwater Source Term

The source terms for groundwater are provided in Table 6. The following observations are provided:

MDD015 (Figure 2) is located with the proposed RAS Pit shell. It also has the greatest number
of samples.

Page 15 MWM-S003-Rev2

- Water quality data suggests that As and Sr can be elevated in groundwater associated with the BOGP.
- Data lower than the LOR are presented in Table 4 in green text as half the LOR. For the source term they are treated as a value of 0 in the WLBM.
- Data for MDD015 (see Figure 2) was selected as the source term for groundwater quality (data shown in yellow in Table 6) and is assumed to be reflective of water quality in the catchment.

Table 6. Water quality source terms for groundwater.

	, ,	J	
	MDD015	MRC002	MDD302
PARAMETERS	(n=18)	(n=1)	(n=12)
	AVE	AVE	AVE
Alkalinity (mg CaCO ₃ /L	201.6	110.0	237.0
pH (pH units)	8.10	8.00	7.78
EC (µS/cm)	446.5	250.0	493.3
Са	38.9	14.8	63.3
CI	9.42	3.50	2.96
F	0.162	-	0.137
Mg	16.2	6.61	21.6
Na	43.6	27.0	7.98
K	1.44	1.88	1.42
TOC	0.300	-	0.500
Al	0.0061	0.0060	0.0038
As	0.024	0.011	0.052
В	0.0331	-	0.01
Cd	0.00008	0.0002	0.00002
Со	0.00019	0.0005	0.00001
Cr	0.0005	0.001	0.0002
Cu	0.0003	0.002	0.0002
Fe	0.0147	0.090	0.005
Hg	0.0002	0.0005	0.00008
Mn	0.0068	0.0034	0.0045
Мо	0.0004	0.0009	0.0003
Ni	0.0003	0.0005	0.0002
Pb	0.0002	0.0005	0.00005
Sb	0.0004	-	0.00018
Se	0.0018	-	0.0005
Sr	9.76	3.57	1.13
TI	0.0003	0.0005	0.00001
U	0.0010	-	0.004815
V	0.0005	0.0005	0.0005
Zn	0.0015	0.094	0.001
Sulfate	10.3	5.40	9.59
Ammoniacal nitrogen	0.109	-	0.050
Nitrate-N	0.0051	-	0.0033
TCN	0.0023	-	0.0011

Note: Green data are 1/2 LOR and are included in the source term as '0'. Data in mg/L unless stated outherwise.

Page 16 MWM-S003-Rev2

4.2.2 Assumptions

The following assumptions are presented for the source term for groundwater:

- It is assumed that the average water quality provides a reasonable dataset to create a source term for the project area.
- It is assumed the source term derived is appropriate for all pits within the proposed BOGP area.

4.2.3 Performance Monitoring

The following performance monitoring is recommended for the groundwater quality:

- Continue monitoring of groundwater for the project at MDD015 until mining commences to confirm baseline conditions.
- Commence monitoring of the Ardgour Aquifer groundwater quality once the monitoring bores (e.g., MWM101 – MWM 103: Figure 2) have been installed. These bores will be installed for compliance monitoring purposes, and a baseline is required to determine any effects.

Page 17 MWM-S003-Rev2

5 ENGINEERED LANDFORMS

This section discusses the source term for the engineered landform (ELF) seepage at the BOGP.

5.1 Background

During the operational phase of the BOGP, surface water from the surface of the Shepherds ELF will be directed to the Shepherds Silt Pond. Water sheeted off the ELF will be diluted by high rainfall events. The water will report to the Shepherds Silt Pond for sediment retention and will then be discharged to Shepherds Creek. EGL (2025b) note that the Shepherds Silt Pond will be a large dam with a decant tower. The silt pond will have a total capacity of around 100,000 m³ (some of which will be dead storage for sediment capture).

In closure, Shepherds ELF will be capped in brown rock and topsoils. Once vegetation establishes, the risk of sediment laden water is mitigated. Shepherds Silt Pond can then be decommissioned, although it may also be used for passive treatment during the active- and post-closure phases. The decision to use this sediment pond as a passive treatment system will be subject to further studies, completed during the operational phase of the BOGP.

5.2 Literature Review - Macraes

Analysis indicates that Macraes and the BOGP have similar sulfur content and similar geology (MWM, 2025b). Sulfur content is a key consideration as to whether an analogue site is suitable as this represents the potential source hazard for AMD. Analysis of total sulfur data for tailings and waste rock at Macraes is comparable to BOGP with average waste rock being ~ 0.13 wt% S at Macraes and ~ 0.094 wt% S at BOGP (MWM, 2024b). Hence, the source hazard for sulfate in waste rock is similar for both Macraes and BOGP and is therefore a suitable analogue site.

Data provided by Golder (2011b) for silt ponds, located at the toe of waste rock stacks (WRSs) at Macraes, indicates elevated sulfate in seepage waters (Table 7). Such data provides an indication of the risks to surface waters associated with this mine domain at the BOGP.

Table 7. WRS silt pond seepage water quality from Macraes. From Golder (2011b).

PARAMETER	DEEPDELL NORTH	DEEPDELL SOUTH	BATTERY CREEK	NORTHERN GULLY	FRASERS WEST (NBWR)	MURPHYS CREEK	BACK ROAD	AVERAGE
Arsenic	0.011	0.00001	0.00001	0.001	0.001	0.00001	0.00001	0.0016
Sulfate	38.6	15.4	1,200	2,300	1,500	1,320	2,200	1084
Cyanide _{WAD}	0.00001	0.00001	0.00001	0.013	0.00001	0.00001	0.00001	0.0016
Copper	0.001	0.00001	0.00001	0.003	0.001	0.001	0.002	0.0010
Iron	0.170	0.00001	0.00001	0.93	0.42	0.52	0.91	0.3734
Lead	0.001	0.00001	0.00001	0.00001	0.00001	0.00001	0.00001	0.0001
Sodium	16	10.8	36	57.7	26.2	33	56.4	29.81
Potassium	5.5	1.89	10	12	5.47	6.69	11.7	6.72
Calcium	68.5	40.2	290	434	199	250	425	215.5
Magnesium	14.5	7.7	200	360	165	204	352	164.7
Zinc	0.00001	0.00001	0.00001	0.032	0.015	0.018	0.032	0.012
Chloride	11.5	7.1	10	10.2	4.69	6.03	9.99	7.49

^{1. -} All values presented in units of mg/L

Page 18 MWM-S003-Rev2

The assessment by Golder in 2011 for Macraes did not consider the risks associated with nitrogenous compounds. Recent work in 2020 identified that nitrate can be elevated up to 10.5 mg/L in WRS seepage (OceanaGold, 2020).

Data presented in this section indicates that a number of PCOC could be elevated in WRS seepage including sulfate, nitrate, and zinc. Further details are provided in the ELF model report (MWM, 2025d) on PCOC and the potential risks for water quality from this mine domain.

5.3 Source Terms

Two source terms for the WLBM are required for the proposed engineered landforms at the BOGP including ELF surface run-off and ELF seepage. ELF surface run-off is assumed to have the source term for Mine Impacted Surfaces (Table 19). ELF seepage requires numerical modelling and is a function of the ELF average height (e.g., Navarro-Valdivia, et al., 2024). Further details of how the ELF seepage source terms were developed are provided in MWM (2025d). Modelling associated with the WLBM are discussed in MWM (2025c).

5.4 Assumptions

Assumptions relating to the source terms for ELF seepage are discussed in MWM (2025d).

5.5 Performance Monitoring

Performance monitoring is discussed in MWM (2025d).

Page 19 MWM-S003-Rev2

6 PIT VOIDS

Active pits are likely to be a significant source of contaminants due to the blasting and exposure of overburden that will generate a large reactive surface area.

6.1 Literature Review - Pit Lakes

Golder (2011c) identifies that PCOC can be elevated in pit lakes at Macraes with:

- Sulfate ranging from 24 3,000 mg/L.
- Arsenic ranging from <0.005 0.8 mg/L.
- Cyanide_{WAD} ranging from <0.005 0.87 mg/L, which indicates that process waters are discharged to some of these pits and this would also account for the elevated sulfate in some pit voids.

These data are shown in Table 8 to Table 12 and summarise the Macraes pit water quality from Frasers Pit, Golden Bar Pit, Golden Point Pit, Innes Mills South, and Round Hill Pit. It is reasonable to expect that pit lake water quality for RAS Pit at BOGP will be comparable to the larger pits at Macraes (e.g., Frasers Pit) once developed to maximum footprint and depth due to a similar lithologies and mineralisation style.

Table 8. Pit Lake Water Quality - Frasers.

PARAMETER	MINIMUM	MEAN	95 [™] PERCENTILE	MAXIMUM
pH (unitless)	7.2	8.1	8.8	9.8
Conductivity (mS/m)	320	760	1,100	1,200
Calcium	29	67	96	110
Chlorine	1.7	11	18	20
Magnesium	15	39	56	74
Potassium	2.8	7.8	16	16
Na	4.9	35	61	72
Sulfate	24	200	350	470
CN _{WAD}	<0.005	<0.013	0.018	0.15
Arsenic	<0.005	<0.18	0.42	0.80
Copper	<0.001	<0.003	0.010	0.022
Iron	<0.02	<0.17	0.60	1.2
Lead	<0.0010	<0.0010	0.0020	0.011

Source: Golder (2011d) - Appendix E.

Notes: All units in mg/L unless otherwise stated; and all data presented to two significant figures or less.

Table 9. Pit Lake Water Quality – Golden Bar Pit.

PARAMETER	MINIMUM	MEAN	95 [™] PERCENTILE	MAXIMUM
pH (unitless)	7.0	8.1	8.3	8.4
Conductivity (mS/m)	270	640	810	860
Calcium	26	70	86	100
Chloride	3.7	6.6	8.5	9.6

Page 20 MWM-S003-Rev2

PARAMETER	MINIMUM	MEAN	95 [™] PERCENTILE	MAXIMUM
Magnesium	14	32	46	48
Potassium	1.8	4.6	7.3	8.2
Sodium	8.2	13	17	18
Sulfate	50	160	260	290
Arsenic	0.07	0.36	0.60	0.72
Copper	<0.001	<0.006	0.024	0.074
Iron	<0.02	<0.067	0.16	0.16
Lead	<0.0001	<0.001	0.002	0.005

Source: Golder (2011d) - Appendix E.

Notes: All units in mg/L unless otherwise stated; and all data presented to two significant figures or less.

Table 10. Pit Lake Water Quality - Golden Point Pit.

PARAMETER	MINIMUM	MEAN	95 TH PERCENTILE	MAXIMUM
pH (unitless)	6.7	7.5	8.1	8.3
Conductivity (mS/m)	780	2,700	4,400	4,600
Calcium	110	370	550	560
Chloride	4.1	14	22	23
Magnesium	26	192	333	345
Potassium	2.4	17	31	54
Sodium	19	130	260	280
Sulfate	200	1,600	3,000	3,000
CN _{WAD}	<0.005	NA	NA	0.040
Arsenic	<0.005	<0.039	0.15	0.17
Iron	<0.04	<0.23	0.69	0.78
Lead ^A	<0.001	NA	NA	NA

Source: Golder (2011d) – Appendix E.

Notes: All units in mg/L unless stated; all data presented to two significant figures or less; NA = not applicable; CN_{WAD} was analysed five times, with all but one below detection limit of 0.005 g/m³

Table 11. Pit Lake Water Quality – Innes Mills South.

PARAMETER	MINIMUM	MEAN	95 [™] PERCENTILE	MAXIMUM
pH (unitless)	7.3	8	8.3	8.3
Conductivity (mS/m)	1,200	2,500	3,600	3,900
Calcium	130	310	430	470
Chloride	1.8	33	86	110
Magnesium	46	100	130	140
Potassium	9.4	31	49	55
Sodium	60	180	340	360
Sulfate	400	1,400	2,100	2,300
Cyanidewad	<0.005	<0.20	0.83	0.87
Arsenic	<0.005	<0.022	0.049	0.052
Copper	<0.001	<0.016	0.057	0.060

Page 21 MWM-S003-Rev2

^A lead was below the detection limit on each sampling occasion.

PARAMETER	MINIMUM	MEAN	95 [™] PERCENTILE	MAXIMUM
Iron	<0.050	<1.4	6.3	8.2
Lead ^{A,B}	<0.001	NA	NA	NA
Zinc ^C	<0.04	NA	NA	NA

Source: Golder (2011d) - Appendix E.

Notes: All units in mg/L unless stated; all data presented to two significant figures or less; NA = not applicable; A - Summary statistics were derived after excluding detection limits superseded by lower limits.

Table 12. Pit Lake Water Quality - Round Hill.

PARAMETER	MINIMUM	MEAN	95 TH PERCENTILE	MAXIMUM
pH (unitless)	7.3	7.8	8.2	8.3
Conductivity (mS/m)	560	840	1,100	1,100
Sulfate	58	200	350	370
CN _{WAD}	<0.005	<0.009	0.021	0.022
Arsenic	<0.002	<0.61	1.4	1.6
Copper ^A	<0.0005	NA	NA	NA
Iron	<0.040	<1.1	4.3	6.3
Lead ^A	<0.0002	NA	NA	NA
Zinc ^A	<0.005	NA	NA	NA

Source: Golder (2011d) - Appendix E.

Notes: All units in mg/L unless stated; all data presented to two significant figures or less; NA = not applicable.

As noted by Navarro-Valdivia et al. (2023) pit lakes can also be elevated in nitrogenous compounds due to the presence of blasting residues, with nitrate nitrogen concentrations peaking in the Golden Bar Pit Lake at 30 mg/L due to an initial nitrate load of 400 kg, yet steadily decreases at 20-30% per year due to biogeochemical processes (Figure 4). Similar processes are expected at BOGP within the final pit lakes. Such decreases in nitrogenous compounds are in agreement with literature (Figure 5).

Navarro-Valdivia et al. (2023) noted that the quantity of nitrogen as NH_4NO_3 was estimated to be 5.35 g/m² once the pit lake started to fill.

Page 22 MWM-S003-Rev2

^B - lead was below the detection limit on each sampling occasion; ^c - sampled on only one occasion.

^A copper, lead and zinc concentrations were below the respective detection limits on each sampling occasion.




Figure 4. Golden Bar Pit Lake nitrate-N and ammoniacal-M concentrations and loads over time. Source: Navarro-Valdivia et al. (2023)




Figure 5. Lake water residence time and nitrogen removal Source: Navarro-Valdivia et al. (2023) with data from Seitzinger et al. (2006).

Page 23 MWM-S003-Rev2

6.2 Literature Review - Pit Wall Runoff

Data provided by Golder (2011d) for Frasers pit runoff water quality is comparable to Frasers Pit water quality (95th percentile), which suggest wall runoff is a good indication of pit water quality prior to dilution by other inflows (e.g., MIW, process water, rainfall) and evaporation. Results indicate that sulfate can range from 12 – 390 mg/L with a mean sulfate of 160 mg/L.

Table 13. Frasers Pit wall runoff water quality.

PARAMETER	MINIMUM	MEAN	95 [™] PERCENTILE	MAXIMUM
pH (unitless)	7.6	8.2	8.4	8.5
Conductivity (mS/m)	400	640	970	1,100
Calcium	20	55	93	110
Chloride	2.9	13	20	27
Magnesium	7.8	37	78	88
Potassium	1.4	3.9	7.1	10
Sodium	4.6	33	59	63
Sulfate	12	160	320	390
Arsenic	<0.005	<0.093	0.36	0.48
Copper	<0.001	<0.0034	0.0082	0.041 ²
Iron	<0.040	9.1 ¹	21	220 ²
Lead	<0.001	<0.004	0.010	0.051 ²

Source: Golder (2011d) - Appendix F.

Notes: All units in mg/L unless otherwise stated; all results presented to two significant figures or less; Data measured at FR3 North Wall, Frasers East Wall, S452RL and W435RL.

6.3 Description

This section describes the three pits that will be constructed as part of the BOGP. No discussion is provided on SRE pit, due to its small size and for the fact it will be backfilled by SRX ELF that will dominate any effects on water quality from the area.

6.3.1 RAS Pit

The RAS Pit design is ~200 m deep, approximately 1,000 m long in a roughly north-south direction and approximately 900 m wide (MGL, 2024). Data are provided in Table 14.

Table 14. RAS Pit Material Summary.

PIT STAGE	TOTAL TONNES	ORE TONNES	ORE GRADE	WASTE TONNES
	(Mt)	(Mt)	(g/t)	(Mt)
Shell 32	187.2	11.6	2.49	175.6
Final Design	214.0	11.9	2.42	202.1
Variance	14%	3%	-3%	15%

Source: MGL, 2024

Page 24 MWM-S003-Rev2

¹ – This data point as presented as <9.1 mg/L. For this report, it is assumed that 9.1 is the mean, which appears reasonable based on the graphed information.

² – this datapoint is an outlier and appears erroneous from the graphed data in the Golder (2011d) report. All other data appear reasonable.

MWM-S003-Rev2

6.3.2 SRX Pit

The SRX Pit design is ~88 m deep, 650 m long and 210 m long (MGL, 2024). Data are provided in Table 15.

Table 15. SRX Pit Material Summary.

PIT STAGE	TOTAL TONNES	ORE TONNES	ORE GRADE	WASTE TONNES
	(Mt)	(Mt)	(g/t)	(Mt)
Shell 33	8.2	1.9	0.69	6.3
Final Design	7.3	1.4	0.68	5.9
Variance	-11%	-11%	9%	-11%

Source: MGL, 2024

6.3.3 CIT Pit

Waste rock (TZ3) will be placed as backfill in the CIT Pit to return the ground to its pre-mining topography (or similar). The CIT backfill is shown in Figure 6 and indicates that the long-term groundwater level will be equivalent to the spill point of 503 m. Waste rock will be constructed as an ELF to minimise long term risks to water quality. The volume of the CIT Pit has been estimated at ~923,000 m³ and this will include 700 kt ore, 475kt soil, 2,550 kt TZ3, and 850 kt TZ4 materials⁷.




Figure 6. CIT Backfill.

Source: Rekker and Dumont, 2025

6.4 Source Terms

Definition of pit lake water quality is required for the various pits proposed at BOGP including RAS, SRX and CIT. Modelling associated with the WLBM are discussed in MWM (2025c). Inputs to the pit lake models include:

- · Pit wall runoff.
- Rainfall.
- Groundwater inflow.
- Surface water.

The following sections define the derivation of source terms for pit wall runoff.

_

Page 25

⁷ Pers. comm. Rod Redden: email dated 12 February 2025.

6.4.1 RAS and SRX Pit Wall Runoff

Data for Frasers Pit and Pit wall runoff are presented in Table 16. Generally, the concentrations in the pit lake are higher than the pit wall runoff (as evidenced by an increase in conductivity). This suggests an increase in concentration due to evaporation. Data are presented for mean and 95th percentile data and source terms for the BOGP Pit Wall runoff are based on these terms. Other data, absent from the Frasers Pit dataset are derived from column leach test data (MWM, 2025f) and analogue datasets.

Table 16. BOGP Pit Wall Runoff Source Term.

		RS PIT LAKE ER QUALITY	RUNG	RS PIT WALL DFF WATER UALITY		WALL RUNOFF RCE TERM
PARAMETER	MEAN	95 TH PERCENTILE	MEAN	95 TH PERCENTILE	MEAN ⁴	95 TH PERCENTILE ⁵
Alkalinity (mg CaCO₃/L)					61.3	140.5
pH (pH units)	8.1	8.8	8.2	8.4	8.2	8.4
EC (µS/cm)	760	1,100	640	970	566 ⁶	1037 ⁶
Ca	67	96	55	93	55	93
CI	11	18	13	20	13	20
F					0.21	0.83
Mg	39	56	37	78	37	78
Na	35	61	33	59	33	59
K	7.8	16	3.9	7.1	3.9	7.1
TOC	-	-	-	-	-	-
Al					0.114	0.24
As	<0.18	0.42	<0.093	0.36	0.093	0.36
В					0.046 ³	0.104
Cd					0.0001	0.0001
Co					0.0005	0.001
Cr					0.0005	0.0005
Cu	<0.003	0.010	<0.0034	0.0082	0.0034	0.0082
Fe	<0.17	0.60	9.1 ¹	21	9.1	21
Mn					0.014	0.039
Мо					0.023	0.045
Ni					0.0009	0.003
Pb	<0.0010	0.0020	<0.004	0.010	0.004	0.010
Sb					0.027	0.14
Se					0.00025	0.00025
Sr					0.91	1.84
TI					0.00025	0.00025
U					0.0106 ⁶	0.0162 ⁶
V					0.0005	0.0005
Zn					0.002	0.007
Sulfate	200	350	160	320	160	320
Ammoniacal-N					10 ²	10 ²
Nitrate-N					30 ²	30 ²

Note: All units in mg/L unless otherwise stated; and all data presented to two significant figures or less.

Note: Green data are 1/2 LOR and are included in the source term as '0' for water modelling purposes.

Page 26 MWM-S003-Rev2

Source: Blue cells from Golder (2011d) - Appendix E.

Cyanide is not included as a source term for pit voids as it is assumed no tailings water and/or process water will be pumped to the pit.

- 1. This data point as presented as <9.1 mg/L by Golder (2011d). It is assumed for this report that 9.1 mg/L is the mean, which appears reasonable based on the graphed information in the Golder report.
- 2. From Navarro-Valdivia et al. (2023) see Figure 4.
- 3. A total of 21 of 30 TZ4 samples are <LOR.
- 4. Mean of all column leach test data (CLT) data for TZ3 and TZ4 (as of 17-2-25)
- 5. 95th percentile of all CLT data for TZ3 and TZ4 (as of 17-2-25).
- 6. where there is a relationship between sulfate and the constituent for the sulfate concentration of interest, then the average of the two relationships for TZ3 and TZ4 is used (based on the presented sulfate concentration).

6.4.2 CIT Pit Backfill

Water quality for the CIT Pit Backfill is discussed in MWM (2025d) where closure water quality is dominated by the materials above the long-term groundwater level.

6.5 Assumptions

The following assumptions are presented for the source term for groundwater:

- It is assumed the Frasers pit and pit wall runoff water quality dataset is a reasonable analogue for BOGP due to a similar lithologies and mineralisation style with both mean and 95th percentile data being available.
- It is assumed that the concentrations of nitrogenous compounds will be similar to the Golden
 Bar Pit Lake as a comparable analogue site (same lithologies, same mineralisation style, and
 the same explosives that generate the ammonium-nitrate source hazard) and that these will
 decrease at a rate of 20-30% per year due to biogeochemical processes.
- It is assumed that the use of mean and 95th percentile column leach test data provides a suitable conservative source term for other water quality parameters absent in the analogue data to understand AMD risks.

6.6 Performance Monitoring

The following performance monitoring is recommended for the RAS and SRX pit lakes:

- Once pit lakes have evolved, it is assumed that nitrogenous compounds will be at low concentrations due to biogeochemical processes. The pit lakes should be monitored for the decay of nitrogenous compounds to validate model assumptions.
- Pit sumps should be monitored to confirm water quality trends for PCOC.
- Pumping records and the quantity of water extraction from the pits for dust extraction should be recorded to validate contaminant load models and the water balance model.

Page 27 MWM-S003-Rev2

7 RAS UNDERGROUND WORKINGS

A review was undertaken of available data to determine a source term for the RAS underground workings, with the water quality and quantity being a function of groundwater flow through the underground workings and flow from the proposed RAS Pit Lake once it fills.

7.1 Literature Review - Golden Point Adit - Macraes

Data are publicly available for the Golden Point Adit, Macraes, from 1993 to 2007 when the frequency of sampling was increased to monthly water quality sampling due to the increase in flow rates from the adit in ~October 2006 (Golder, 2011d). As noted by Golder (2011d) the historic golden point underground workings intersect the Golden Point Pit, which explains the change in water quality from the 1990's to the 2000's. Pertinent available data are presented in Figure 7 and in Table 17.

Data indicates that there is a decrease in arsenic and iron concentrations across this time period, with the adit discharge being similar to the Golden Point Pit after the pit commenced draining through the workings (Table 10), although sulfate is slightly lower. Given the hydraulic connection of the adit to the pit void, only earlier data would be representative of adit seepage water quality (e.g., pre-2002) prior to the Golden Point Pit filling.

Analysis of these data (Figure 7; Table 17) suggests that adit seepage could have sulfate concentrations of ~120 mg/L; 4.1 mg/L arsenic; and 11 mg/L Fe (Table 17), which is higher than that observed at the Lower Bendigo Adit at the BOGP (Section 7.2 below). This needs consideration as part of the source term development for underground workings.




Figure 7. Golden Point Adit water quality

Source: Golder (2011d).

Page 28 MWM-S003-Rev2

MINIMUM MEAN PARAMETER 95TH PERCENTILE MAXIMUM pH (unitless) 6.8 7.2 7.6 7.7 Conductivity (mS/m) 830 3,200 3,900 4,400 480 610 620 Calcium 130 Chloride 10 13 17 18 Magnesium 28 220 300 320 Potassium 2.4 18 22 27 Sodium 18 100 160 190 Sulfate 120 1,800 2,500 2,600 0.0062 <0.001 < 0.0032 0.011 CN_{WAD} 0.014 0.23 1.1 4.1 Arsenic Copper^A <0.0010 <0.0016 0.0026 0.003 < 0.02 <0.65 4.5 11 Iron <0.0011 Lead < 0.0002 0.0032 0.010 ZincB < 0.005 NA NA 0.011

Table 17. Golden Point Adit Water Quality. From Golder 2011c.

Golder (2011c) Notes: All units in mg/L unless stated; all data presented to two significant figures or less. NA = not applicable.

7.2 Lower Bendigo Adit

Data are available from the MGL water quality database for the Lower Bendigo Adit (LBA), which have been reported in MWM (2025a). These data are presented in Table 18. Data indicates that moderate impacts to water quality are identified compared to groundwater data (Table 6) with COPC such as SO₄ and As being elevated.

Based on SO₄ data, results indicate that the water quality in the Bendigo adit is 4.3 times lower; and based on As data it is 3.9 times lower than the Golden Point Adit. The SO₄ ratio between the two datasets is used to derive an estimate of the source term for the RAS underground as shown in Table 18.

Column Leach Test (CLT) data was used to derive a source term for the proposed RAS Underground, where analogue data were not available, using the relationship with SO₄ to determine other water quality constituents. This analysis and the derivation of relationships for each constituent is described in MWM (2025f). Analysis indicated that concentrations are generally lower than those proposed using the ratio approach, although Al, B, Co, Cu, Mo, V, and ammoniacal N are higher (Table 18). The mean of all data (TZ3 and TZ4) was used to derive the source term for the RAS Underground (Table 18).

The following notes are provided for the data presented in Table 18:

- CLT EC (relationship data) provides a reasonable match to EC data for both the Bendigo Adit
 and the Golden Point Adit. This suggests similar geochemical reactions / ions in solution from
 scaling off SO₄.
- Alkalinity is comparable across the models, suggesting reasonable reliability.
- Calcium is low in the CLT relationship with sulfate.

Page 29 MWM-S003-Rev2

^A - summary statistics were derived after excluding detection limits superseded by lower limits.

^B - zinc was analysed twice and was below detection on one occasion.

Arsenic concentrations are elevated in both models, however the data from Golden Point Adit
of 4.1 is used even though this is a maximum (see Figure 7) to provide a conservative number
for modelling of potential effects.

Table 18. Groundwater source term for the RAS Underground based on LBA.

PARAMETERS	Lower Bendigo Adit (this study) (mg/L)	Golden Point Adit (Macraes) (mg/L)	RAS Underground (Ratio [x4.3]) (mg/L)	RAS Underground (CLT Relationship) (mg/L) ³	RAS Underground Source Term (mg/L)
Alkalinity (mg CaCO₃/L)	191.4		191.4 ¹	185.1 ⁵	191.4
pH (pH units)	8.06	6.8	6.8 ²	-	6.8
EC (µS/cm)	467.6	830	830 ²	448.1 ⁶	-
Са	53.1	130	130 ²	13.59	130
Cl	7.19	10	10 ²	2.04	10
F	0.292		1.27	0.21	1.27
Mg	15.4	28	28 ²	5.33	28
Na	19.9	18	18 ²	20.02	20.02
K	1.94		8.4	10.8	10.8
TOC	1.40				1.4
Al	0.00329		0.0143	0.114	0.114
As	1.0527	4.1	4.1	0.42	4.1
В	0.0175		0.076	0.046	0.046
Cd	0.00007		0.00030	0.0001	0.0003
Со	0.00016		0.00070	0.0005	0.0007
Cr	0.00043		0.00187	0.0007	0.00187
Cu	0.00029		0.00126	0.0005 7	0.00126
Fe	0.0452		0.19652	0.04	0.196
Mn	0.0233		0.10130	0.014	0.101
Мо	0.00107		0.00465	0.023	0.042
Ni	0.00028		0.00122	0.0005 7	0.00122
Pb	0.00016		0.00070	0.0005 7	0.00070
Sb	0.00030		0.00130	0.027	0.027
Se	0.0017		0.0074	0.0025	0.0074
Sr	0.468		2.03	0.91	2.03
TI	0.00012		0.00052	0.00025	0.00052
U	0.00211		0.009	0.0092 6	0.092
V	0.00050		0.002	0.0005 7	0.01
Zn	0.00137		0.0060	0.005 ⁷	0.006
Sulfate	27.6	120	120 ²	120	120
Ammoniacal-N	0.0061				0.0061
Nitrate-N	0.2141				0.2141

^{1.} Uses lower Bendigo Adit values

Page 30 MWM-S003-Rev2

^{2.} Uses Golden Point Adit data

^{3. &#}x27;r' indicates a relationship is used as explained in MWM (2025f)

^{4.} Mean of all column leach test data (CLT) data for TZ3 and TZ4 (as of 17-2-25) where red data are identified as a maximum and are applied to the source term for RAS underground.

^{5.} Based on TZ3 sulfate relationship data, which provided a dataset that comparable to other data from Lower Bendigo Adit

6. where there is a relationship between sulfate and the constituent for the sulfate concentration, then the average of the two relationships for TZ3 and TZ4 is used.

7. Multiple LOR provided by various labs. The highest LOR is presented.

Note: Green data are 1/2 LOR and are included in the source term as '0'

7.3 Underground Working Source Term

For the WLBM two source terms are required:

- During the operational phase of the BOGP, once the underground is established there will be seepage to the underground, which will be introduced into the mine water BOGP management system.
- During the closure phases of the project there will be seepage from the RAS underground portal that will be a combination of flow from groundwater and the RAS Pit void. It is assumed that the RAS Pit Void water quality will dominant the source term (as seen at Golden Point Adit).

7.3.1 RAS Underground – Operational Phase Source Term

The source term for the RAS Underground working during the operation phase of the project are provided in Table 18.

7.3.2 RAS Underground – Closure Phase Source Term

Water quality for seepage from the RAS Underground in the closure phases of the project utilises RAS Pit Lake water quality. As shown at Macraes, adit seepage at Golden Point Adit is dominated by pit lake water quality and the same process is expected at the BOGP once the crown pillar is removed and the pit lake is connected to the underground workings. Flow will be a function of pit lake seepage flow. This mixing is managed by the GoldSim model.

7.4 Assumptions

The following assumptions are presented for the source term for the underground workings:

- It is assumed the Macraes Golden Point Adit provides a reasonable example of the effects of the mineralisation (i.e., SO₄) on underground water quality and that the data are more reliable than the Lower Bendigo Adit that may not have intersected the RSSZ. Higher PCOC data are chosen to ensure that AMD risks are considered.
- It is assumed that mean PCOC derived from column leach testing is reasonable to develop a
 water quality source term for the RAS underground for those parameters that are missing from
 the analogue dataset and would account for subtle differences in mineralisation between BOGP
 and Macraes.
- The WLBM (MWM, 2024c) indicates that the seepage from the RAS underground working will discharge many decades after mining operations cease. It is expected that with such residence times that nitrogenous compounds are degraded by biogeochemical reactions (e.g., Navarro-Valdivia, et al., 2023) such that the nitrate nitrogen and ammoniacal nitrogen resembles the water quality shown in Table 18.

Page 31 MWM-S003-Rev2

It is assumed that there is no first flush of contaminants from the underground workings and
that the combined source terms (dominated by the pit water quality rather than water in the
deeper underground workings that is unlikely to move upwards) will be reasonable to
understand risks to the receiving environment and consider any appropriate management
options.

7.5 Performance Monitoring

The following performance monitoring is recommended for the Underground Workings water quality:

- Install a piezometer to confirm groundwater levels and provide guidance on when discharge from the RAS underground portal might occur (with comparison to RAS Pit Lake water levels)
- Monitor the underground workings seepage water quality prior to it discharging to validate management requirements.

Page 32 MWM-S003-Rev2

8 SOURCE TERMS – MINE IMPACTED WATERS

This section summarises the source terms used for general mining areas that will generate MIW.

8.1 Impacted Run-off Water Quality

A literature review of data available from Macraes was undertaken to provide empirical analogue data for MIW runoff. Golder (2011a) defines two surfaces as impacted and non-impacted where:

- Impacted surfaces include pits, ore processing areas, mine roads, unrehabilitated waste rock stacks (WRSs) and rehabilitated tailings surfaces.
- Non-impacted surfaces are those surfaces that are in a natural state but might be impacted by mine dust and the definition also include rehabilitated WRS.

The water quality associated with these surfaces is provided in Table 19 and was derived by Golder (2011c) from Frasers Pit runoff where 25th percentile data from Frasers Pit run off was used for non-impacted runoff and 50th percentile data was used for impacted runoff. For this report, we have refined the terminology to be rehabilitated WRS surfaces and mine impacted areas. Areas affected by dust would be considered mine impacted surfaces and further studies are required to define these areas and any effects (once the project is operational)

During consenting of Deepdell North Stage III Project these source terms were updated using recent empirical data (OceanaGold, 2020a; GHD, 2020) with GHD (2020) stating that these data were derived from water quality monitoring data provided by OceanaGold and represent mean values.

PARAMETER REHABILITATED WRS SURFACES MINE IMPACTED SURFACES OceanaGold Golder (2011a) Source Golder (2011a) OceanaGold (2020a)1 (2020a)1 Units mg/L mg/L mg/L mg/L 0.021 0.02 0.04 Arsenic 0.1 Sulfate 125 470 201 930 Cyanide 0.001 0.001 Copper 0.001 0.001 0.002 0.0012 Iron 0.05 0.14 0.135 0.032 Lead 0.0001 0.00019 0.001 0.0002 Zinc 0.005 0.001 0.005 0.001 Sodium 15 28 Potassium 3 4 Calcium 46 63 Magnesium 26 34 Chloride 6 13 Nitrate 0.4 0.094 0.012 0.012 Ammonia

Table 19. MIW - Macraes

Source: Golder (2011a) and OceanaGold (2020a)

Red Text is greater than the proposed consent limits for BOGP noting the Cu has no toxicity modifying factors applied.

1 – Derived by GHD (2020)

Page 33 MWM-S003-Rev2

Data are available for runoff from the Fraser Pit Wall (Table 13 and Table 16), which suggests a broad range in pit wall runoff water quality. For the purposes of this report, it is assumed that runoff from mine impacted surfaces is fairly represented by:

- TZ3 mine impacted surfaces is best represented by mean data (as shown in Table 20 below).
- TZ4/RSSZ mine impacted surfaces is best represented by 95th percentile data (as shown in Table 20 below).

However, the use of these source terms is complicated by the source of dust suppression water. Further consideration is given to whether these data are conservative and adequately reflect the potential risk to the receiving environment given these waters may discharge from site during the operational phase of the project.

8.2 Discussion – Dust Suppression Water

Water is required for dust suppression and this water can be sourced from the pit void and also groundwater bores. Dust suppression water will be applied to all haul roads, hardstands, and the operating surfaces of the engineered landforms. If the water for dust suppression is sourced from the RAS pit sump it could introduce contaminants to these surfaces from the pit water.

No management of MIW is proposed for haul roads and run-off from the ELF other than sediment management (and sediment sumps), with discharge of these waters off site during higher rainfall periods (EGL, 2025b). Hence dissolved constituents that remain in solution such as sulfate in the pit water might be elevated and affect the downstream receiving environment.

To address the potential effects of poorer water quality associated with the effects of dust suppression water derived from the pit sump, a numerical analysis was undertaken using sulfate as an indicator of effect.

8.2.1 Analysis – Dust Suppression Water

Table 19 indicates that the source terms for mine impacted surface runoff derived by Golder in 2011 and by GHD in 2020 are generally comparable except for a significant increase in sulfate from 2011 to 2020. It is unlikely that mine surfaces can generate such elevated sulfate without the ongoing addition (and evaporation) of MIW to these surfaces. For instance, pit wall runoff (which would include runoff from mineralised rock, ore zones, and waste rock has a sulfate concentration ranging from 12 – 390 mg/L; a mean of 160 mg/L; and a 95th percentile value of 320 mg/L. This is considerably lower than 930 mg/L proposed by GHD (2020). It is reasonable to assume that the elevated sulfate is related to ongoing dust control with mine water elevated in sulfate (e.g., from pit voids).

Based on flow rates into the RAS Pit of 7-14 L/s (Rekker and Dumont, 2025), and the assumption this mixes to generate the water quality observed at the Frasers Pit of (Table 8) this would result in 240 – 570 kg sulfate per day being applied to mine surfaces, which is likely to produce a comparable load to that observed at Macraes.

8.3 Source Terms: Mine Impacted Surfaces and Rehab Surfaces

The source terms are provided in Table 20. The following discussion is provided:

 Where mine surfaces do not use pit water elevated in sulfate for dust suppression, a source term derived from Frasers Pit Wall runoff is used. Data are provided for run-off from TZ3 and

Page 34 MWM-S003-Rev2

TZ4/RSSZ materials. To assess stability and transport at surface conditions the original source term for TZ4/RSSZ, which had elevated iron of 21 mg/L, was assessed with PHREEQC. It was seen that through precipitation iron, copper, aluminium and lead concentrations are likely to decrease. Adsorption ratios from Raven et al. (1998) show that the iron precipitate will be sufficient to reduce arsenic concentrations to <LOR.

- For mine impacted surfaces that have pit lake water applied (that is elevated in sulfate), the source term for these surfaces is based on data in Table 19 (e.g., a sulfate concentration of 930 mg/L).
- For rehabilitation surfaces, the source term for these surfaces is based on data in Table 19 (e.g., a sulfate concentration of 470 mg/L).
- OceanaGold (2020) report that impacted and rehabilitated surfaces have ammoniacal-N concentrations of 0.012 mg/L and nitrate-N concentrations of 0.094 mg/L and 0.4 mg/L respectively based on pit water quality of 0.9 mg/L ammonia and 10.5 mg/L nitrate. Nitrate concentrations within the RAS pit have been estimated at 30 mg/L nitrate-N, and 10 mg/L ammoniacal-N. These values are used as conservative datasets to derive a source term for mine impacted surfaces that use the pit sump for dust suppression.

Table 20. Source terms: Mine Impacted Surfaces and Rehabilitated Surfaces

PARAMETER	MINE IMPACTED SURFACES (BORE WATER DUST SUPPRESSION)		MINE IMPACTED SURFACES (DUST SUPPRESSION USING PIT SUMP WATER)	REHABILITATION SURFACES
	TZ3	TZ4/RSSZ	ALL SURFACES	BROWN ROCK
Alkalinity (mg CaCO₃/L)	61.3	140.5	140.5 ³	140.5 ³
pH (pH units)	8.2	8.4	8.4 ⁴	8.4 ⁴
EC (µS/cm)	566 ⁶	1,037 ⁶	3,738 ⁶	1,952 ⁶
Ca	55	90.4 ⁷	22.94 ³	15.68 ⁵
CI	13	20	17.7 ³	3.1 ⁵
F	0.21	0.83	1.14 ³	0.34 ⁵
Mg	37	76.4 ⁷	3.06 ³	1.95 ⁵
Na	33	59	94.2 ³	32.88 ⁵
K	3.9	7.1	13.64 ³	8.66 ⁵
TOC	-	-	-	2.01 8
Al	0.114	0.00016 ⁷	0.438 ³	0.155 ⁵
As	0.093	0.005 7	0.04	0.02
В	0.046	0.104	0.11 ³	0.064 ⁵
Cd	0.0001	0.0001	0.0001	0.0001
Со	0.0005	0.0005 7	0.0005	0.0005
Cr	0.0005	0.0005	0.0005	0.0005
Cu	0.0034	0.0005 7	0.0012	0.001
Fe	9.1 ¹	0.005 7	0.032	0.14
Mn	0.014	0.039	0.028 ³	0.0115 ⁵
Мо	0.023	0.045	0.285 ⁶	0.147 ⁶

Page 35 MWM-S003-Rev2

PARAMETER	MINE IMPACTED SURFACES (BORE WATER DUST SUPPRESSION)		MINE IMPACTED SURFACES (DUST SUPPRESSION USING PIT SUMP WATER)	REHABILITATION SURFACES
	TZ3	TZ4/RSSZ	ALL SURFACES	BROWN ROCK
Ni	0.0009	0.003	0.0005	0.0005
Pb	0.004	0.003 ⁷	0.0002	0.00019
Sb	0.027	0.14	0.155 ³	0.049 5
Se	0.00025	0.00025	0.00025	0.00025
Sr	0.91	1.84	1.77 ³	0.67 ⁵
TI	0.00025	0.00025	0.00025	0.00025
U	0.0106 ⁶	0.0162 ⁶	0.099 ⁶	0.053 ⁶
٧	0.0005	0.0005	0.0005	0.0005
Zn	0.002	0.007	0.001	0.001
Sulfate	160	320	930	470
Ammoniacal-N	0.012	0.012	10 ²	0.012
Nitrate-N	0.094	0.094	30 ²	0.4

Note: All units in mg/L unless otherwise stated; and all data presented to two significant figures or less.

Note: Green data are 1/2 LOR and are included in the source term as '0'

Source: Blue cells from Golder (2011d) – Appendix E. Source: Orange cells are from OceanaGold (2020a)

- 1. This data point as presented as <9.1 mg/L by Golder (2011d). It is assumed for this report that 9.1 mg/L is the mean, which appears reasonable based on the graphed information in the Golder report.
- 2. From Navarro-Valdivia et al. (2023) see Figure 4.
- 3. Uses 95th percentile data from Column Leach Tests
- 4. Uses 95th percentile data from the Frasers Pit wall runoff.
- 5. Mean of all column leach test data (CLT) data for TZ3 (as of 17-2-25)
- 6. Where there is a relationship between sulfate and the constituent for the sulfate concentration of interest, then the TZ3 relationship is used.
- 7. Reduced from original runoff source term due to likely precipitate formation and adsorption as per PHREEQC equilibrium phases modelling and Raven et al. 1998.
- 8. TOC defined from SC01 baseline water quality.

Note: Mine impacted surfaces are defined in Section 8.1 of this report.

8.4 Assumptions

The following assumptions are presented for the source term for mine impacted surfaces:

- It is assumed that mine impacted surfaces use mean (160 mg/L) and 95th percentile (320 mg/L) SO₄ data from Frasers Pit runoff (and other available parameters) for runoff from TZ3 and TZ4 materials respectively. This is considered conservative, as concentration will remain constant for higher flow events, when there is likely to be considerable dilution.
- Where pit sump water is used for dust suppression it is assumed there is the potential to
 accumulate salts that could generate poor water quality. This risk is likely to be lesser at the
 start of operations and higher once the pit is at maximum volume and water quality is poorest.
 It is assumed that the empirical data provided by GHD (2020) is representative of mine
 impacted surfaces that utilise pit sump water for dust suppression (e.g., 930 mg/L sulfate). This

Page 36 MWM-S003-Rev2

is considered conservative, as concentration will remain constant for higher flow events, when there is likely to be considerable dilution.

- It is assumed that that data from Macraes provides a reasonable estimate of runoff water quality from rehabilitated slopes (e.g., 470 mg/L sulfate) as this is based on empirical data from similar materials.
- It is assumed that the assumptions presented in Table 20 (footnotes) are reasonable in regards to the development of appropriate source terms to understand AMD risk and that the direct application of column leach test data (mean and 95th percentile) is conservative.

8.5 Performance Monitoring

The following performance monitoring is recommended for the water quality of mine impacted surfaces:

- Monitoring of water quality and flow rates of runoff from mine impacted surfaces such as haul roads and the ELF (e.g., monitoring of runoff within sediment sumps).
- Monitoring or water quality from rehabilitation surfaces (e.g., measurement of runoff water quality)

Mine impacted surfaces are released directly to the receiving environment. Hence, they represent a diffuse source of potentially poor water quality. Modelling (MWM, 2025c) suggests that there are some risks to the receiving environment, and it would be advantageous to develop a Trigger Action Response Plan (TARP) to manage this risk. One management option would be to use bore water for dust suppression rather than pit sump water.

8.6 Ore Stockpile

An ore stockpile area is proposed as part of the BOGP that will be used to blend low grade ore (LGO) and ore to supply the processing plant. The source term presented in Table 20 for mine impacted surfaces is considered appropriate if the effects require assessment. At closure the ore stockpile is removed and during operations any runoff water is returned to the process plant.

Page 37 MWM-S003-Rev2

9 SOURCE TERMS – TAILINGS STORAGE FACILITY

This section describes the process to derive source terms for the WLBM for MIW from the Shepherds TSF. Two source terms are required including:

- Decant water quality Influenced by chemical composition of the ore being processed, processing reagents, operational water management discharges to the TSF surface, recycling of process water, climatic effects including evaporation and dilution by rainfall, and geochemical processes.
- TSF seepage water quality Influenced by the decant water quality and geochemical processes occurring as decant water migrates through the tailings to report as seepage.

9.1 Background

The proposed Shepherds TSF will retain all tailings (other than those used for paste backfill) for the BOGP. Supernatant water will be managed on top of the tailings within the decant pond. During operations the TSF will operate as a zero-release facility with sufficient freeboard to manage both operational water and the inflow design flood without discharge (EGL, 2025b). Water on the TSF will be lost via evapotranspiration or be reused in the Process Plant.

EGL (2025b) note that during operation seepage collected in the TSF and ELF underdrainage will be collected in a HDPE lined sump and will be pumped back the TSF. The HDPE lined sump is proposed to be 4,500 m³ to allow time for reestablishment of the pumps if there is a breakdown. The Shepherds Creek Silt Pond is immediately downstream of the sump and allows a contingency option (in dry conditions) if the sump filled up. As an alternative option a gravity line could be run down to the Process Plant (Note: the need for this is considered a detailed operational decision (EGL, 2025b).

During the active- and post- closures stages, seepage from the TSF and ELF will continue to collect in the underdrainage and at the toe of the ELF. This will be either sent to a water treatment plant or passive treatment ponds before discharge to Shepherds Creek.

During the active- and post- closure stages, the TSF will be fully dry capped with brown rock, topsoil, and revegetated. On the northern side of the TSF a shallow amount of water will be allowed to pond on the dry capping to attenuate flood flows and form a wetland (if desired as a final closure landform). Runoff from the top of the closure dry capping will be clean and discharge through an outlet channel around the northern edge of the ELF into Shepherds Creek.

9.2 Literature Review

Publicly available water quality data for the Macraes was reviewed to provide an analogue dataset of TSF water quality for the TSF decant surface water and TSF seepage water quality. However, the processing of ore at Macraes post ~1999 is different to that proposed at BOGP. Since 1999 Macraes have introduced a pressure oxidation (POX) stage to the ore processing plant that oxidises all sulfide minerals to sulfate liberating the refractory gold. Hence pre-1999 data is of relevance as POX of ore is not proposed at the BOGP. The tailings were originally stored in separate impoundments until 1993, with the sulfate rich cyanidation tailings stored in the Concentrate Tailings Impoundment (CTI), and the other tailings stored in the Flotation Tailings Impoundment (FTI). From 1993 onwards these were combined and stored in the Mixed Tailings Impoundment (MTI).

Page 38 MWM-S003-Rev2

Hence it is anticipated that sulfate concentrations (including other contaminants associated with sulfides) in BOGP tailings water will be comparable to pre-POX water quality at Macraes. Hence, the most appropriate tailings water quality data at Macraes, as an analogue for BOGP is prior to 1999 when POX commenced. Prior to the introduction of POX sulfate concentrations were gradually increasing, but appear to have stabilized between 1994 – 1999 with an average concentration of 952 mg/L. The change in water quality following the introduction of POX is shown in Figure 8 with sulfate concentrations increasing to ~5,000 mg/L.




Figure 8. Macraes Gold Mine TSF Decant Water Quality - Sulfate Source: Golder (2011d) – Appendix B

Decant water quality shows a decrease in arsenic concentrations following the introduction of POX at Macraes from 0.1 - 450 mg/L (average 39 mg/L) to ~0.1 - 5 mg/L (Figure 9). Craw and Pope (2017) indicated that this decrease in dissolved As concentrations is due to greatly increased Fe-oxyhydroxide formation associated with the POX, which provides adsorption sites for As. Dissolved iron (Fe) concentrations in the decant water remained reasonably consistent until 2002 when concentrations increased (Figure 10).

Page 39 MWM-S003-Rev2





Figure 9. Macraes Gold Mine TSF Decant Water Quality - Arsenic






Figure 10. Macraes Gold Mine TSF Decant Water Quality - Iron

Source: Golder (2011d) – Appendix C

Page 40 MWM-S003-Rev2

9.2.1 Tailings Cyanide Concentrations

Cyanide may be elevated in the BOGP TSF due to its use in the gold recovery process (e.g., MACA, 2025). Golder (2011f) not a general decline in cyanide with time for the Macraes Project (Figure 11). Data presented by Golder (2011c) indicates that operational seepage water quality for the TSF's at Macraes (TTTSF, MTI, SPI) ranged from 0.022 – 0.051 mg/L and that TSF seepage water following closure would be 0.08 mg/L. Golder (2011a) note that tailings pore water seepage post closure would be 0.35 mg/L and that operationally TSF decant water was 0.47 mg/L.




Figure 11. Cyanide – WAD – Macraes

Source: Golder 2011d

9.2.2 Geochemical Maturation of Seepage Waters

Golder (2011a,c) note that the quality of the tailings pore water, as represented by TSF drain discharges differs from that of tailings decant water due to complex hydrogeochemical interactions, which includes precipitation and dissolution reactions, adsorption and desorption processes, hydraulic residence times of pore water in the TSF, and the redox environment within the TSF.

Craw and Pope (2017) presented the water quality in the MTI decant pond and the chimney drain, which collected water that had percolated through the tailing impoundment (Figure 12). The average concentrations in the pre-POX period (1994-1999) are presented in Table 21. This data was derived from manually extracting data from Craw and Pope (2017) published graphs with WebPlotDigitizer (Rohatji, 2011), which may have a small level of imprecision.

Page 41 MWM-S003-Rev2




Figure 12: Macraes Tailings seepage water quality

Source: Craw and Pope (2017). The blue and red dots were used for the analysis presented in this report (Table 21).

Table 21: Macraes MTI average water quality between 1994 – 1999: decant water and the outflowing chimney drain.

PARAMETER	MIXED TAILINGS IMPOUNDMENT DECANT (mg/L)	SUMP B CHIMNEY DRAIN (mg/L)	% CHANGE
Alkalinity	138.1	158.6	15%
As	8.6	1.9	-78%
Ca	98.3	69.1	-30%
CI	342.7	173.3	-49%
K	69.1	14.9	-78%
Mg	14.8	36.9	150%
Na	634.7	383.1	-40%
Sulfate	1,049.4	734.6	-30%
pH	8.3	6.3	

Note: pH is unitless.

Source: Craw and Pope (2017).

Page 42 MWM-S003-Rev2

Since the geology and processing procedure over this period was similar to what is proposed at BOGP, the derived water quality provides an indication of how the decant water quality at the BOGP may mature as it percolates through the TSF, where:

- pH decreased from an average of 8.3 to 6.3 through the MTI.
- Sulfate decreased by 30%, arsenic decreased by 78%, calcium decreased by 30%, potassium decreased by 78%, and sodium decreased by 40%.
- Alkalinity increased by 15% and magnesium concentrations increased by 150%.

Copper concentrations were not presented in Craw and Pope (2017) however they were discussed in Craw and Nelson (2000), which presented representative concentrations in the decant ponds and Sump B from when the CTI and FTI were active in 1993 (Table 22). In this period the tailings were split into different impoundments, which results in different water qualities due to the geochemical differences of the tailings. However, the trends between the difference in the average decant water quality to the average sump water quality were similar to the later data from the MTI.

Craw and Nelson (2000) indicate that the Sump B (seepage) water is made up of approximately half regional groundwater and half tailings seepage, with the two mixing beneath the tailings dam before reaching Sump B. Ca, Fe and Mg concentrations were seen to increase between the decant water and the sump water, while other analytes decreased in concentration, some by the approximate value expected amount given the groundwater dilution, and some by more, indicating other attenuation factors were occurring. Copper was seen to decrease from an average of 14.4 mg/L in the decant water to below the LOR to <0.01 mg/L, while arsenic was seen to decrease 98% from an average of 56.06 mg/L in the decant water to ~0.9 mg/L in sump B.

Golder (2011c) note that sulfate concentrations in the TSF decant water quality increased with time, which was assumed to be the result of ongoing recycling of decant water quality, evaporation, dilution, and changes to the process and water management methods over the 20 years of mining operations.

Table 22: Representative water quality in November 1993, when the CTI and FTI were active.

-						% CHANGE
	DEC	ANT		SUMP B	SUMP B	
	CTI DECANT	FTI DECANT	SUMP B CDE	SUMP B CDW	SUMP B SSF	
As (total)	110	2.1	1.1	1.3	<0.5	-98%¹
Cu	28.2	0.67	<0.01	<0.01	<0.01	-100% ¹
Fe (total)	8	1.31	4.97	4.96	11.8	56%
Na	915	394	172	188	96.8	-77%
K	52.9	60.1	8.14	8.09	6.26	-87%
Ca	31.8	33.4	55.1	45.6	85	90%
Mg	3.8	6.4	26.9	25.3	39.1	497%
Cl	787	323	141	154	67.6	-78%
HCO₃⁻	564	125	183	186	277	-37%
Sulfate	695	425	344	317	296	-43%
pН	9.8	8.4	6.4	6.5	6.2	-

All units are in mg/L other than pH, which is unitless.

Page 43 MWM-S003-Rev2

^{1. -} where readings were below the detection limit, half the detection limit was used for calculating the % change. Percent (%) change calculated from the average between the decant concentrations and the average of the Sump B measurements.

Source: Data from Craw and Nelson (2000) when the TSF was active (e.g., 1993).

9.2.3 Literature Review Summary

The following summary is provided:

- TSF water quality in the BOGP decant and seepage is expected to be comparable to pre-POX water quality at Macraes (pre-1999).
- Fe is expected to be elevated, with pre-POX water at Macraes showing average concentrations of 4.6 mg/L in decant water and 7.2 mg/L in outflowing sump water.
- Nitrate is expected to be elevated due to the use of nitrogenous compounds (e.g., ANFO, cyanide).
- Cu is expected to decrease through the TSF. Cu is added to the process water to facilitate the destruction of cyanide (MACA, 2025). Assessment of

9.3 Process Water

This section reviews the process water that will be the discharge water quality from the processing plant to the TSF. Further details on the ore processing plant are provided in MACA (2025). Mineralis (2025) provide additional discussion on the use of Cu to facilitate cyanide destruction (Appendix B).

9.3.1 Process Water Treatment

MGL (2024) state that an air/SO₂ circuit has been selected for cyanide destruction based on the relatively lower operating cost of these circuits, the less hazardous reagents required in comparison to Caros acid and the amenability shown in the testwork of the ore to this form of cyanide destruction. The circuit will reduce the weakly acid dissociable cyanide to less than 30 ppm at discharge of the TSF spigot. Current data indicates that cyanide may be elevated and MGL indicates this is being retested to confirm the cyanide destruction works. It is assumed that cyanide concentrations measured in the Macraes TSF (0.47 mg//L: Golder, 2011a) can be achieved at the BOGP and that the long-term seepage water quality post closure for Cyanidewad will be 0.35 mg/L as proposed for Macraes (Golder, 2011a).

Ferric chloride precipitation of solubilised arsenic as a ferric arsenate has been selected based on the amenability of the ore to this removal method, and the anticipated stability of the arsenate species generated (MGL, 2024). Test results indicate that as of <0.7 mg/L was achieved and that significant additional testwork is required for the arsenic removal step, including undertaking Toxicity Characteristic Leaching Procedure (TCLP) testing of solids generated in the arsenic removal process to determine the stability of the precipitate formed, and undertaking further testing to confirm the reproducibility of these results (MGL, 2024).

9.3.2 Metallurgical Test Data

This section discusses water quality data derived from metallurgical testing (MACA, 2025), which provides a source term for the expected process water. Metallurgical testing was coordinated by MACA, with final leachate analysis after detox and As removal providing an estimation of the expected water quality for the decant water in the TSF (Table 23).

Only one dataset is available for the process water quality (MACA, 2025), which introduces some uncertainty into the model. To account for this, the WLBM does not consider any improvement in water quality with time after closure to ensure MIW risks for water quality are identified and managed

Page 44 MWM-S003-Rev2

appropriately in the long term. For instance, Golder (2011e) note that at Macraes following closure of the TSF it is expected that a gradual change in seepage water quality will occur that reflects a change from process water to rainwater. Golder (2011) note the infiltrating rainwater will continue to leach PCOC but that concentrations will be lower. Data presented (Golder, 2011e) indicates that in the long term, TSF seepage water quality could change from 2,769 mg SO_4/L to 2,260 mg SO_4/L , i.e., a ~20% decrease.

Table 23: Source Terms: Process water quality and tailings seepage water.

PARAMETER	DETECTION LIMIT	PROCESS WATER QUALITY ¹	OPERATIONAL TSF DECANT QUALITY ²	CLOSURE TSF SEEPAGE WATER QUALITY ⁶
Alkalinity (mg/L as CaCO₃)	5	310	34.6	73.21
pH (pH units)	0.01	7.86	6.41	6.41
EC (µS/cm)	2	2,500	1,948	4,121
Са	0.5	140	140	297
Cl	1	380	380	804
F	0.1	0.913	0.913	1.93
Mg	0.5	19	47 ³	99
Na	0.5	400	400	847
K	0.5	24	24	50.8
TOC	-	-	-	-
Al	0.01	0.72	<0.01	<0.01
Ag	0.001	0.0034	0.0034	0.0068
As	0.001	0.12	0.97 ⁵	2.05
В	0.02	0.39	0.39	0.825
Cd	0.0001	0.0001	0.0001	0.0002
Со	0.001	0.025	0.025	0.053
Cr	0.001	0.0068	0.003	0.0055
Cu	0.001	1 ¹⁰	0.001	0.001 8
Fe	0.01	2.1	7.24 ⁴	15.3
Mn	0.001	0.28	0.28	0.59
Мо	0.001	0.12	0.066	0.14
Ni ⁹	0.001	0.32	0.32	0.678
Pb	0.001	0.013	0.013	0.0275
Sb	0.0001	0.085	0.085	0.18
Se	0.001	0.0014	0.0014	0.003
Sr	0.001	2.1	2.1	4.4
TI	0.001	0.001	0.001	0.001
U	0.001	0.013	0.013	0.028
V	0.001	0.0018	0.0018	0.004
Zn	0.001	0.014	0.014	0.0296
Cyanide - WAD	0.01	47	0.47 ⁷	0.35 7
Sulfate	1	450	450	954
Ammoniacal-N	0.005	2	2	2
Nitrate-N	0.005	<0.0050	0.005	0.005

Note: All units in mg/L unless otherwise stated.

Note: Green data are LOR and are included in the source term as '0'

Note: Red data are elevated compared to the unmodified surface water quality limits provided by Ryder (2025).

Page 45 MWM-S003-Rev2

If no data are provided these are identified by '- '.

1. - MACA (2025).

Source: Process water quality sourced from metallurgical testing - final liquor analysis from bulk leach, detox and As removal.

- 2. Seepage water results are from solution modelling with PHREEQC. This modelling gives an indication of changes expected due to the saturation and therefore precipitation of certain minerals as the water sits in the decant pond.
- 3. Evidence from the Macraes data indicates that this element had higher concentrations in the seepage water than the decant water. It has therefore been increased in by the same factor seen at Macraes.
- 4. The Fe concentration has been increased from the concentration modelled by PHREEQC to the average Fe concentration for seepage observed at Macraes (Table 22).
- 5. With Fe dissolving, it is assumed that some As may also be mobilised and the As concentration has been increased from the concentration modelled by PHREEQC (0.28 mg/L) to the average As concentration for seepage observed at Macraes (Table 22).
- 6. To account for the recycling of water, transfer of water from ELF seepage, evaporative concentration, etc the closure source term was multiplied using sulfate as the scaling factor to be comparable to the sulfate concentrations seen at Macraes pre-POX, i.e., 954 mg/L as shown in Figure 8.
- 7. Source: Golder (2011a) Table 14 for Macraes
- 8. Cu precipitation was simulated in PHREEQC to account for solubility limits reducing the process water concentration to <0.001 mg/L. A value of 0.001 mg/L is used as the source term to be conservative.
- 9. Ni is elevated compared to ANZG(2018) guidelines 90% trigger value of 0.013 mg/L
- 10. Process water quality data (MACA, 2025) indicate that Cu in process water was 75 mg/L. This has been adjusted to 1 mg/L based on advice by Mineralis (2025), which is provided in Appendix B.

9.4 TSF Seepage Source Term

As seen from the Macraes data presented by Craw and Nelson (2000) and Craw and Pope (2017), the decant water quality will change as seepage percolates through the tailings facility. The change in water quality is the result of a complex array of processes which can include precipitation of minerals, dilution with rainwater and groundwater, dissolution of minerals within the tailings, and adsorption of metals and metalloids to clays and iron oxyhydroxides.

PHREEQC geochemical modelling software (Parkhurst and Appelo, 2013) has been used as an initial indication of how the seepage water will evolve from the process water due to the precipitation of minerals from the solution. The resulting seepage water quality is presented in Table 23. This seepage water quality may be conservative as it does not take into account any dilution or adsorption of metals within the tailings. Where the Macraes data showed an increase of concentrations in the seepage compared to the decant, likely due to dissolution or weathering of minerals within the tailings, the indicated seepage concentrations have been manually increased by the same factor. For example, magnesium concentrations were 150% higher in seepage compared to decant concentrations, so the results from the metallurgical testing have been increased by 150% for the seepage water.

Some data has been manually adjusted to higher concentrations (As and Fe) to account for the sub-oxic conditions in the TSF using data from Macraes (Table 22) to provide a conservative value.

9.5 Assumptions

The following assumptions are provided for the source terms for the TSF:

• It is assumed that the TSF seepage water quality represents the long-term risk to water quality from this mine domain and that this is adequately represented by the source term developed from the Process Water quality.

Page 46 MWM-S003-Rev2

9.6 Performance Monitoring

The following performance monitoring is recommended:

- Validate the process water quality including the geochemistry of the tailings on a monthly basis to confirm water quality inputs to the WLBM and validate assumptions on the geoenvironmental hazards for the solids stream.
- Undertake monthly sampling of the TSF seepage for water quality to improve the source term for modelling of effects. This should also include continuous monitoring for EC, pH, and flow to improve the WLBM.

Page 47 MWM-S003-Rev2

10 SOURCE TERMS - TREATED WATER

This section summarises the treatment of water during the Active Closure Phase and the Post Closure Phase of the BOGP.

10.1 Active Water Treatment

During the Active Closure Phase of the BOGP it is proposed that MIW are treated by the active water treatment plant (WTP). Further details of this WTP are provided in MWM (2025g) and Process Flow (2025).

10.2 Passive Water Treatment

During the Post Closure Phase of the BOGP it is proposed that MIW are treated by the passive treatment system (PTS). Further details of the PTS are provided in MWM (2025g) including effluent water quality following treatment.

Page 48 MWM-S003-Rev2

11 CLOSING

MWM has developed this report to define the water quality source terms for the WLBM for the BOGP for MGL to provide a summary of inputs that will be used during the modelling process.

11.1 Water and Load Balance Model Summary

A WLBM, that contains water flow and quality data is required for the BOGP to understand potential deleterious effects on the receiving environment associated with these MIW (noting the management of TSS is covered by the sediment and erosion management plan: EGL (2025a)). The WLBM has been developed using the GoldSim modelling platform⁸ Key water quality inputs (source terms) are defined in this report, and this includes the following key model components:

- The composition of rainfall water, for understanding its interaction with project materials.
- Baseline surface water quality.
- Groundwater inflow quality (e.g., to the RAS Pit void).
- · ELF seepage.
- Process water quality associated with the tailings (assumed to be representative of TSF decant water quality).
- Pit water quality.
- TSF decant water.
- TSF seepage water quality.
- MIW quality associated with ELF runoff, haul roads, and hardstand areas.
- Underground workings (operational and closure).
- Rehabilitated surfaces.

11.2 Derivation of Source Terms

Source terms were developed from a variety of sources including analogue data sources, baseline studies at the BOGP, and laboratory derived data from environmental geochemistry testing. This report provides an explanation of how the source terms for modelling were developed for the WLBM.

11.3 Water Balance Model

Water management during the Operational Phase of the BOGP will involve discharge of only episodic runoff from haul roads and ELF surfaces. All other MIW (e.g., landform seepage) will be collected, used, and stored on site. In the Active Closure / Post Closure Phase, MIW will be treated and discharged to the receiving environment. Two models have been developed, that are reported elsewhere (MWM, 2025c) to reflect these phases:

 Operational Phase - Excel based models and calculations focussing on average annual water balance and runoff event discharge of MIW.

-

Page 49 MWM-S003-Rev2

⁸ https://www.goldsim.com

 Active Closure / Post Closure Phase - GoldSim based models and calculations, focussing on the evolution of instream water quality over time as a result of discharge of treated MIW.

EGL (2025b) note that the site shall maintain a water balance model representing the operational conditions on site. This should be regularly reviewed and calibrated as the site develops and be used to predict the closure situation. Detailed stage models for years 1-13 (Table 1) will be developed using GoldSim⁹ prior to mining commencing (i.e., during the project pre-startup phase). This will provide an operational tool for MGL to effectively manage water during operations.

During operation, for the site to operate without a water treatment plant the site needs to be in a net deficit water balance on average. Without a water treatment plant, the main mechanism for water loss is evapotranspiration from the tailings decant pond and dust suppression. There is water stored within the pores of the tailings. In a wet year, some water may accumulate in surplus on the TSF however in the following year the site should be able to return to normal operating conditions. If the site ends up in an accumulating surplus water balance then a water treatment plant will need to be installed as is proposed for closure. Preliminary analysis by MWM (2025c) indicates for the site to be in deficit the water pumped from pit and underground will need to be used for dust suppression on the ELF and runoff water from the catchment above the TSF will need to be diverted around the facility. Dust suppression in dry conditions is expected.

11.4 Summary

This report provides source terms that are used in the WLBM to understand potential effects for the proposed BCPC Project. It is recommended that:

- Source terms need to be validated through performance monitoring that should be ongoing through the operational and closure phases of the project.
- A detailed operational water balance model is required prior to mining commencing, which should be updated annually.
- Trigger Action Response Plans (TARPs) should be developed for BOGP. For instance, a TARP should be developed for water runoff from mine impacted surfaces that receive dust suppression water from the pit void.

Page 50 MWM-S003-Rev2

^{9 &}lt;u>https://www.goldsim.com</u>

12 REFERENCES

- ANZG, 2018. Australian and New Zealand guidelines for fresh and marine water quality. Australian and New Zealand Environment and Conservation Council, Agriculture and Resource Management Council of Australia and New Zealand.
- Allibone, A., 2023. Mineralisation at the Rise and Shine Gold deposit, Bendigo District. Presentation for the Australasian Institute of Mining and Metallurgy (AusIMM) 2023 New Zealand Branch Conference, August 2023, Christchurch, New Zealand. 19 pp. https://santanaminerals.com/investors/reports.
- AusIMM, 2011. Field Geologists' Manual Fifth Edition. Monograph 9. Published by the Australasian Institute of Mining and Metallurgy, 480 pp.
- Cox, L., MacKenzie, D. J., Craw, D., Norris, R. J., & Frew, R. (2006). Structure and geochemistry of the Rise & Shine Shear Zone mesothermal gold system, Otago Schist, New Zealand. New Zealand Journal of Geology and Geophysics, 49(4), 429-442
- Craw, D. and Nelson, M., 2000. Geochemical signatures of discharge waters, Macraes mine flotation tailings, east Otago, New Zealand. *New Zealand Journal of Marine and Freshwater Research*, *34*(4), pp.597-613.
- Craw, D. and Pope, J., 2017. Time-series monitoring of water-rock interactions in mine wastes, Macraes gold mine, New Zealand. New Zealand Journal of Geology and Geophysics, 60(3), pp.159-175.
- EGL, 2025a Sediment and Erosion Management Plan. Provided by Engineering geology for Matakanui Gold Limited.
- EGL, 2025b ELF / Water Management Plan. Provided by Engineering geology for Matakanui Gold Limited.
- GHD, 2020. Deepdell North Stage III Project Receiving Water Quality Analysis. GHD Report 125/02848 dated November 2019. https://www.orc.govt.nz/consents-and-compliance/current-notified-applications/oceana-gold-new-zealand-limited-rm20024/
- Golder, 2011a. Macraes Phase III Project Water Management Summary Report. Report by Golder Associates for OceanaGold. Report 0978110-562 R002 vE. Appendix 8 to the OceanaGold AEE. 56 pp. https://www.orc.govt.nz/consents-and-compliance/current-notified-applications/archived-applications/oceana-gold-new-zealand-limited-application-rm10351
- Golder, 2011b. Macraes Phase III Project Groundwater Contaminant Transport Assessment Deepdell Creek, North Branch Waikouaita River and Murphy's Creek Catchments. Report 0978110-562-R006 vD. Appendix 14 to the OceanaGold AEE. 93 pp. https://www.orc.govt.nz/consents-and-compliance/current-notified-applications/archived-applications/oceana-gold-new-zealand-limited-application-rm10351
- Golder, 2011c. Macraes Phase III Project Site Wide Surface Water Quality Model Appendix E Water Quality Input Data Sources. Appendix 10, 3 pp. https://www.orc.govt.nz/consents-and-compliance/current-notified-applications/archived-applications/oceana-gold-new-zealand-limited-application-rm10351

Page 51 MWM-S003-Rev2

- Golder, 2011d. Macraes Phase III Project Environmental Water Quality Data Summary Report. Report 0978110-562-R012vC, 124 pp. Appendix 15. https://www.orc.govt.nz/consents-and-compliance/current-notified-applications/archived-applications/oceana-gold-new-zealand-limited-application-rm10351
- Golder, 2011e. Macraes Phase III Project Top Tipperary Tailings Storage Facility Hydrogeological Assessment. 112 pp. Appendix 14 to the OceanaGold AEE. 93 pp. https://www.orc.govt.nz/consents-and-compliance/current-notified-applications/archived-applications/oceana-gold-new-zealand-limited-application-rm10351
- Geocontam Risk Management (GRM), 2025. Preliminary Site Investigation Bendigo-Ophir Gold Project. GRM Report J-G-NZ0005-001-R-Rev1.
- Lawrence M., Lewis J., Scrivener P., 2019. Bendigo-Ophir Project Dunstan Range 2018 LiDAR Area, Archaeological Survey Report: Site Assessment and Avoidance Strategy. New Zealand Heritage Properties Ltd, (NZHP). August 2019. 239pp.
- MACA, 2025. Bendigo Ophir Gold Project Pre-feasibility Study. Provided for Matakanui Gold Limited.
- Matakanui Gold Limited (MGL), 2024. Bendigo-Ophir Pre-Feasibility Study. 330 pp.
- Mineralis Consultants, 2025. Cyanide Detoc Discharge Copper Levels. Memorandum prepared by Mineralis Consultants Pty Ltd for Matakanui Gold Limited.
- MWM, 2025a. Baseline Water Quality Report Bendigo-Ophir Gold Project. Mine Waste Management report: J-NZ0233-006-R-Rev5
- MWM, 2024b. Factual Report: Geoenvironmental Hazards Bendigo-Ophir Gold Project. Mine Waste Management report: J-NZ0233-008-R-Rev2.
- MWM, 2025c. Water Load Balance Model Report Bendigo-Ophir Gold Project. Mine Waste Management report: J-NZ0233-016-Rev0.
- MWM, 2025d. Engineered Landform Water Quality Forecast Report Bendigo-Ophir Gold Project. Mine Waste Management report: J-NZ0457-002-R-Rev2.
- MWM, 2025f. Factual Report: Column Leach Test (Interim) Bendigo-Ophir Gold Project. Mine Waste Management report: J-NZ0233-015-R-Rev2.
- MWM, 2025g. Water Management /Treatment Strategy. Mine Waste Management report: J-NZ-0464-002-M-Rev0.
- Navarro-Valdivia, L., Weber, P.A., Tuck, J., Hillman, C., 2023. Natural Decay of ANFO-Derived Nitrate in Pit Lakes: Insights from the Golden Bar Pit Lake, Macraes Gold Mine, Otago, New Zealand. 2023. AuslMM New Zealand Branch Annual Conference. Available: https://www.ausimm.com/news-and-media/community-news/new-zealand-branch-2023-annual-conference-presentations--abstracts
- Navarro-Valdivia, L., Weber, P., Hillman, C., 2024. Forecasting Water Quality from Waste Rock Stacks

 A Relationship with Height. New Zealand Annual AuslMM Branch Conference, Wellington, 19

 21 August, 12 pp.

Page 52 MWM-S003-Rev2

- Nichol, S. E., Harvey, M. J., & Boyd, I. S. (1997). Ten years of rainfall chemistry in New Zealand. Clean Air: Journal of the Clean Air Society of Australia and New Zealand, 31(1), 30-37¹⁰.
- Oceana Gold (NZ) Ltd 2020. Deepdell North Stage III Project Assessment of Environmental Effects
 Part 1. Dated 29 January 2020, 252 pp. https://www.orc.govt.nz/consents-and-compliance/current-notified-applications/oceana-gold-new-zealand-limited-rm20024/
- Parkhurst, D. L., & Appelo, C. A. J., 2013. Description of input and examples for PHREEQC version 3—a computer program for speciation, batch-reaction, one-dimensional transport, and inverse geochemical calculations. US geological survey techniques and methods, 6(A43), 497.
- Process Flow Limited (Process Flow), 2025. BOGP Post Closure Active Water Treatment Plant (WTP) Order of Magnitude (Oom) Study. Report FL-2426-PRJ-RPT-00001 for Matakanui Gold Limited.
- Raven, K. P., Jain, A., & Loeppert, R. H. (1998). Arsenite and arsenate adsorption on ferrihydrite: kinetics, equilibrium, and adsorption envelopes. *Environmental science & technology*, 32(3), 344-349.
- Rekker, J., 2025. Rise & Shine Gold Project Surface Water & Catchment Existing Environment & Effects Assessment (Report Series No. Z24002BOG2-Rev0). Kōmanawa Solutions Ltd, Christchurch.
- Rekker, J. H., & Dumont, M. 2025. Rise & Shine Gold Project Groundwater Existing Environment & Effects Assessment. Kōmanawa Solutions Client Report No. Z24002BOG1. Kōmanawa Solutions Ltd, Christchurch.
- Rohatgi, A. 2011, WebPlotDigitizer, Version 5.2, https://automeris.io
- Ryder, G., 2025. Bendigo-Ophir Gold Project: Recommended water quality compliance limits for the Bendigo-Ophir Gold Project. Report for Matakanui Gold by Greg Ryder Consulting.
- Seitzinger, S., Harrison, J. A., Böhlke, J. K., Bouwman, A. F., Lowrance, R., Peterson, B. Tobias, C. & Drecht, G. V. (2006). Denitrification across landscapes and waterscapes: a synthesis. Ecological applications, 16(6), 2064-2090.

Harvey/publication/228515438 Ten years of rainfall chemistry in New Zealand/links/02bfe510ec610d5e1c000000/Ten-years-of-rainfall-chemistry-in-New-Zealand.pdf

Page 53 MWM-S003-Rev2

¹⁰ https://www.researchgate.net/profile/Mike-

13 **LIMITATIONS**

Attention is drawn to the document "Limitations", which is included in Appendix B of this report. The statements presented in this document are intended to provide advice on what the realistic expectations of this report should be, and to present recommendations on how to minimise the risks associated with this project. The document is not intended to reduce the level of responsibility accepted by Mine Waste Management, but rather to ensure that all parties who may rely on this report are aware of the responsibilities each assumes in doing so.

Page 54 MWM-S003-Rev2

APPENDIX A ABBREVIATIONS

ABBREVIATION	DEFINITION
AMD	Acid and metalliferous drainage
BOD	Biochemical oxygen demand
CIL	Carbon-in-leach
CIT	Come in Time
CLT	Column leach test
СТІ	Central tailings impoundment - Macraes
DGV	Default guideline value
DOC	Dissolved organic carbon
ELF	Engineered landform
FTI	Flotation tailings impoundment - Macraes
LOR	Limit of reporting
MAV	Maximum acceptable value
MEQ	Metal ecotox quotient
MGL	Matakanui Gold Limited
MIW	Mine impacted waters
Mt	Million tonnes
MTI	Mixed tailings impoundment – Macraes
MWM	Mine Waste Management Ltd
COPC	Constituents of potential concern
QA/QC	Quality assurance and quality control
PCOC	Potential contaminants of concern
POX	Pressure oxidation
pXRF	Portable x-ray fluorescence
RAS	Rise and Shine
RPD	Relative percent difference
RSSZ	Rise and Shine Shear Zone
SRX	Srex
SRE	Srex East
TSF	Tailings Storage Facility
TZ3	Textural zone 3 of the Otago Schist
TZ4	Textural zone 4 of the Otago Schist
UG	Underground

ABBREVIATION	DEFINITION
WAD	Weakly acid dissociable (Cyanide)
WELF	West ELF
WLBM	Water and load balance model
WRS	Waste rock stack

APPENDIX B MINERALIS REPORT



MEMORANDUM

Subject: Cyanide Detoc Discharge Copper Levels

Date: 7 July 2025

Attention: Mark Mitchell

From: Katie Barns

Background

Cyanide detoxification test work completed as part of the IMO test program (Santana Minerals Limited (SMI) Bendigo-Ophir Gold Project RAS & SRX Deposit Metallurgical Testwork Programs Project 6680 + 6749 February 2025) reported discharge solution copper levels up to 75mg/L. Subsequent water modelling has identified the high copper levels as an issue within the long term water balance and if discharged would require ongoing water treatment for a significant period of time following mine closure.

Full Cyanide Detox Circuit

The cyanide detoxification process proposed for the Bendigo Ophir Project is based on the INCO SO₂/AIR process shown in Figure 1.

Suphur Diozade

Ferric Otloride or Lane
(if required)

Tailings Starry
or Solution

Air Sparas

Air Sparas

Air Sparas

Figure 1: INCO Process Flowsheet

MINERALIS CONSULTANTS PTY LTD

ACN 613 294 885

An Agent of Mineralurgy Pty Ltd - ABN 58 094 603 166

PO Box 818, Toowong, QLD 4066, Australia T: +61 (0)7 3870 7024 | F: +61 (0)7 3870 7606

E: expertise@mineralis.com.au | W: www.mineralis.com.au



The basic chemistry of the INCO SO_2/AIR process is straight forward. In the primary reaction, weak acid dissociable cyanide (CN_{wad}), which includes free cyanide and weakly complexed metal cyanides, is oxidized to produce cyanate (OCN-) and sulphuric acid while releasing metals into solution. This reaction requires a small amount of copper in solution to serve as a catalyst which is usually added as copper sulphate. Acid produced in the oxidation reactions is neutralized with lime at a controlled pH of 8-9. The product of neutralization is calcium sulphate (gypsum). Iron cyanide, a strongly complexed metal cyanide, is normally the only other species of cyanide encountered in a typical mine effluent. Metals which are dissociated during the oxidation reactions (particularly copper), precipitate the iron cyanide as an insoluble salt. This precipitate is stable within a wide range of pH values. Excess metals in solution, including the spent copper catalyst, are precipitated as hydroxides. Stoichiometrically, the reactions require approximately 2.46 grams of SO_2 per gram of CN_{wad} to be oxidized although operating ranges are more typically 3.5-4.5 grams of SO_2 per gram of CN_{wad} . (Robbins 1996).

The reactions that occur in the INCO process are written in various forms but typically as

Reagents

$$SO_2 + O_2 + H_2O \rightarrow H_2SO_5$$
, Cu^{2+} catalyst

Reactions

$$SO_2 + O_2 + H_2O + CN-WAD \rightarrow CNO^- + H_2SO_4$$
 $Na_2S_2O_5 + 2O_2 + H_2O + 2CN^-WAD \rightarrow 2 CNO^- + 2NaHSO_4$
 $2Cu^{2+} + Fe(CN)_6^{4-} \rightarrow Cu_2Fe(CN)_6$
 $CNO^- + H^+ + H_2O \rightarrow CO_2 + NH_3$

The reaction is normally carried out at a pH of 8-9, with lime normally required for pH control. The lime (or other alkali) requirement to control pH depends on the choice of reactant (Na₂SO₃,SMBS,SO₂). The reaction rate is extremely fast and is limited by the transfer of oxygen. Typical reaction times to achieve the required oxygen mass transfer vary from about 30 min to 2 h. Iron complexed cyanides are reduced to the ferrous state and precipitated with copper, nickel or zinc as insoluble metal–iron–cyanide complexes. Residual metals liberated from the WAD cyanide complexes are precipitated as metal hydroxides.

Benchmarking Published Operating Data

Literature searches of publicly available data show that the levels of copper in solution in the discharge of a full INCO process is typically <1mg/L from a fully operating INCO circuit (Table 1). This compares well with the solution copper levels in the INCO discharge from Oceanagold's Macraes INCO circuit which typically sits at 0.1mg/L and concurs with the expectations of other industry professionals familiar with the operation of INCO circuits in other gold operations.



Table 1: INCO process operating data

Operation		detox descript	tox descript stream		e feed (mg/L)			effluent / INCO discharge (mg/L)			Reagents (g/gCN _T)		pH	
				min	CNT	Cu	Fe	CNT	Cu	Fe	Cu++	SO2	barren	treated
Campbell Red Lake	laboratory				890	55	80	1.6	0.4	0.4	0.11	2.2	9.5	9.5
Campbell Red Lake	laboratory				665	62	35	0.7	0.5	0.2	0.07	3.6	10.5	9.8
Scottie gold mines	commercial				450	35	1.5	0.1-2	1-10	< 0.5			9	8
McBean Mill	commercial				370	30	20	0.2	0.7	<0.2			11.5	9
Campbell red lake	laboratory		barren sltn	60	940	39	118	0.7	0.6	0.2	0.15	3	11.1	10
Equity	laboratory		CIP tails (30% sol)	30	195	42	25	0.4	1.1	0.2	0.25	3.8	10	8
Mount Skukum	laboratory		tailings (45% solids)	40	215	3	40	0.3	0.2	0.1	0.5	2.1	9.8	8
Lynn gold	laboratory		Pit water	20	13	1.5	0.1	0.6	0.4	0.1	0.4	4.8	8.7	9.9
Colosseum	laboratory		CIP tails (53% sol)	80	243	84	85	0.3	0.9	0.2	0	4.3	10.5	8
Kuntz	laboratory		electroplating rinse water	100	100	54	4.5	2.1	3.2	0.6		0.6		8.5
McBean	laboratory		barren sitn	90	404	35	26	0.3	0.5	<0.2	0	3.5	11.7	9
Skyline	laboratory		repulped talings	120	1124	455	73	1.5	2.7	0.1	0	4	10.4	8
Inco/ Golden Knight	laboratory		CIL Tailings	60	200	15	2.4	0.2	0.9	0.2	0.2	4.6	10.5	8
ERG	laboratory		pond water	40	155	88	6.5	0.1	0.3	<0.1	0	6.5	9	7.7
Westmin	laboratory		CIPtailings	120	278	24	13	0.3	8.0	0.1	0.07	5.3	10.7	8
Equity	commercial	1 stage	CIL Tailings		100	35	2	1-5	2-5	0	0.27	5.9	11	8
Mt Skukum	commercial	flotation cells	Repulp		100	5	15	0.9	1	0.2	0.25	4	11	8.2
McBean	commercial	1 stage	Barren		370	30	20	0.2	0.7	<0.2	0	4	11.5	9
Lynngold	commercial	2 stage	Pond		100	20	2	0.6	0.1	0.1	0.1	6	8.7	9.5
collosseum	commercial	1 stage	CIP Tailings		375	129	2.2	0.4	1.5	0.2	0.11	5.6	10.6	8.7
Ketza R*	commercial	1 stage*	CIP Tailings		150	8	<0.1	5	15	<0.1	0.3	6	9.8	8.4
Skyline	commercial	1 stage	Repulp		450	300	10	<0.1	2	0.3	0	6	10.5	8.1
Kuntz	commercial	multi	Rinse		150	90	2.8	0.2	1.2	<0.2	0	8	9.5	8.5
Ovacik	operation	3 stage	CIP Tailings		183				<1	<0.1	150	50	8-9	7
Detour Lake	NI43-101	2 stage	CILTailings	1.5				<5			0.14	5		

Source: Devuyst EA, Conard BR Hudson W, Commecial Operation of INCO's SO2/Air Cyanide Removal Process, Conference on Cyanide and the Environment, Arizona, Dec 1984, Devuyst EA, Conard BR Robins G, Vergunst R, INCO SO2/Air Cyanide Removal Process Update, World Gold '89 1999

IMO Test work

The IMO cyanide detoxification test work for Santana Minerals was completed in two test work rounds on tails generated from the master composite. Round 1 tails sample was generated without a gravity step and round 2 tails sample was generated with the inclusion of a gravity gold recovery step. The Round 1 detoxification test work was completed on a single batch sample while the round 2 work included a 1kg batch test followed by a 29kg bulk sample detoxification test.

The copper levels in test work detoxification discharge liquor were

Round 1 Batch test work: 0.84mg/L
 Round 2 Batch test work: 32mg/L
 Round 2 Bulk test work: 75mg/L

The elevated coper levels are not typical of a full INCO installation where copper (and other metal ions) in solution after the INCO reactor would be precipitated out as metal hydroxides and levels of less than 1mg/L would be expected in the system tails. While the full test work scope is not detailed in the IMO report it appears that the test work was a single stage test completed only to determine the amenability of the RAS CIL discharge to cyanide destruction via the INCO methodology. The single test does not appear to have an additional step to precipitate out metal ions including Cu²⁺ ions to copper hydroxide as would be typical in a commercial INCO installation. Although not explicitly this precipitation of metal ions does not appear to have been part of the test work scope.



Recommendations

While copper in solution assays of 1mg/L would be a reasonable starting point for water and tails modelling work the amenability of the full INCO process for <u>both</u> cyanide detoxification and subsequent metal ion precipitation of the Bendigo Ophir CIL discharge for should be tested and confirmed as part of the current ALS test work plan (Quote No: 32703).

References

Breuer, P, Jeffery C, Meakin R, FUNDAMENTAL INVESTIGATIONS OF THE SO2/AIR, PEROXIDE AND CARO'S ACID CYANIDE DESTRUCTION PROCESSES, Parker CRC for Integrated Hydrometallurgy Solutions CSIRO Minerals Down Under National Research Flagship CSIRO Process Science and Engineering Australia

Devuyst EA, Conard BR Hudson W, Commercial Operation of INCO's SO2/Air Cyanide Removal Process, Conference on Cyanide and the Environment, Arizona, Dec 1984,

Devuyst EA, Conard BR Robins G, Vergunst R, INCO SO2/Air Cyanide Removal Process Update, World Gold '89 1999

Robbins GH, Historical development of the INCO SO2/AIR cyanide destruction process, CIM Bulletin, Sept 1996



Original INCO licenses (1996)

Owne	er/Project	Location	Treatment	
1.	Scottie Gold Mine	British Columbia	Barren and slurry	
2.	Carolin Mines/Ladner Creek	British Columbia	Barren and slurry	
3.	Dupont Exploration/Baker Mine	British Columbia	Slurry	
4.	Placer Dome/Equity Silver	British Columbia	Slurry	
5.	Inco-Queenston/McBean Mine	Ontario	Barren	
6.	Lynngold Inc./MacLellan Mill	Manitoba	Pond water	
7.	Kuntz Electroplating	Ontario	Solution	
8.	Lac Minerals/Colosseum Mine	California	Slurry	
9.	Mount Skukum Gold Mining	Yukon	Slurry	
10.	Canamax/Ketza River	Yukon	Slurry/Pond water	
11.	Skyline Explorations/Johnny Mountain	British Columbia	Slurry	
12.	Placer Dome/Kiena	Quebec	Slurry	
13.	Giant Yellowknife/E.R.G. Resources	Ontario	Pond water	
14.	TVX-Golden Knight/Les Mines Casa Berardi	Quebec	Slurry/Pond Water	
15.	Precious Plate	Ontario	Solution	
16.	Citadel/Surluga Mine	Ontario	Barren	
17.	Superfinish	Ontario	Solution	
18.	Westmin/Premier Gold	British Columbia	Slurry	
19.	Minnova Inc./Lac Shortt	Ouebec	Pond Water	
20.	TVX/Mineral Hill Mine	Montana	Barren	
21.	N.A. Metals/Golden Bear Mine	British Columbia	Slurry	
22.	St. Andrew Goldfields/Stock Mine	Ontario	Pond water	
23.	Echo Bay/Kettle River	Washington State	Slurry	
24.	Sable Resources/Baker Mine	British Columbia	Barren	
25.	Muscocho/Mauntoban	Ouebec	Pond water	
26.	Barrick/East Malartic	Quebec	Slurry	
27.	Sunshine/Snow Caps	California	Heap rinse	
28.	Barrick/Mercur	Utah	Pond Water/Slurry	
29.	Echo Bay/McCoy-Cove	Nevada	Slurry	
30.	Royal Oak/Hope Brook	Newfoundland	Slurry	
31.	IBM	Quebec	Solution	
32.	ACNC/Grant Mine	Alaska	Mill Solution	
33.	Citigold/Ryan Lode	Alaska	Heap Solution	
34.	Homestake/Nickel Plate	British Columbia	Slurry	
35.	AJ Perron Gold/Kerr Mill	Ontario	Slurry	
36.	AMAX Gold/Hayden Hill	California	Slurry	
37.	Battle Mountain Gold/San Luis	Colorado	Slurry	
38.	Placer Dome/Campbell Mine	Ontario	Pond water	
39.	Newmont/Yanacocha	Peru	Heap solution	
40.	Macraes/Flat	New Zealand	Slurry	
40. 41.	Placer Dome/Detour	Ontario	Slurry	
41.		Mexico		
42. 43.	Peñoles/La Cienega Homestake/McLaughlin	California	Slurry Pond water	
44.	Devex/Gympie	Australia	Slurry	
45.	Battle Mountain Gold/Kori Kollo	Bolivia	Slurry	
46.	Eltin-Orion/Salsigne	France	Slurry	
47.	Kinross Gold/Q.R.	British Columbia	Slurry	
48.	Barrick/Bullfrog	Nevada	Slurry	
49.	TVX/New Britannia	Manitoba	Slurry	
50.	Dome Resources/Tolukuma	Papua, New Guinea	Slurry	



Disclaimer

This report is subject to the standard Mineralis Consultants Pty. Ltd. disclaimer as follows:

Mineralis Consultants Pty. Ltd. makes reasonable efforts to ensure an accurate understanding of client requirements. The information in this report is based on that understanding and Mineralis Consultants Pty. Ltd. strives to be accurate in its advice.

The opinions expressed in this report have been based on the information supplied to Mineralis Consultants by Santana Minerals Limited. Mineralis Consultants has exercised all due care in reviewing the supplied information. The accuracy of the results and conclusions from the review are reliant on the accuracy of the supplied data. Mineralis Consultants has relied on this information. Mineralis Consultants does not accept responsibility for any errors or omissions in the supplied information and does not accept any consequential liability arising from commercial decisions or actions resulting from them.

While reasonable care has been taken in the preparation of this report, this report and all information, assumptions, and recommendations herein are published, given, made, or expressed without any responsibility whatsoever on the part of Mineralis Consultants Pty. Ltd. whether arising by way of negligence, breach of contract, breach of statutory duty or otherwise.

No warranty or representation of accuracy or reliability in respect of the report/proposal is given by Mineralis Consultants Pty. Ltd. or its directors, employees, servants, agents, consultants, successors in title and assigns.

If liability is not, by law, capable of exclusion, then Mineralis Consultants Pty. Ltd. accepts liability to the minimum level set by that law.

This disclaimer shall apply to liability to any person whatsoever, irrespective of how such liability arises, whether by use of this report/proposal by that person or you or any other person or otherwise.

Mineralis Consultants Pty. Ltd. is not responsible in any way whatsoever for the error neglect or default of others upon whom it has placed reliance in the preparation of this report/proposal.

This report is for the exclusive use of Santana Minerals Limited. You shall indemnify Mineralis Consultants Pty. Ltd. Limited and its directors, employees, servants, agents, consultants, successors in title and assigns against any claim made against any or all of them by third parties arising out of the disclosure of the report/proposal, whether directly or indirectly, to a third party.

APPENDIX C LIMITATIONS

This Document has been provided by Mine Waste Management Ltd (MWM) subject to the following limitations:

This Document has been prepared for the particular purpose outlined in MWM's proposal and no responsibility is accepted for the use of this Document, in whole or in part, in other contexts or for any other purpose.

The scope and the period of MWM's services are as described in MWM's proposal, and are subject to restrictions and limitations. MWM did not perform a complete assessment of all possible conditions or circumstances that may exist at the site referenced in this Document. If a service is not expressly indicated, do not assume it has been provided. If a matter is not addressed, do not assume that any determination has been made by MWM in regards to it.

Conditions may exist which were undetectable given the limited nature of the enquiry MWM was retained to undertake with respect to the site. Variations in conditions may occur between investigatory locations, and there may be special conditions pertaining to the site which have not been revealed by the investigation and which have not therefore been taken into account in the Document. Accordingly, additional studies and actions may be required.

In addition, it is recognised that the passage of time affects the information and assessment provided in this Document. MWM's opinions are based upon information that existed at the time of the production of this Document. It is understood that the services provided allowed MWM to form no more than an opinion of the actual conditions of the site at the time the site was reviewed and cannot be used to assess the effect of any subsequent changes in the quality of the site, or its surroundings, or any laws or regulations.

Any assessments made in this Document are based on the conditions indicated from published sources and the investigation described. No warranty is included, either express or implied, that the actual conditions will conform exactly to the assessments contained in this Document.

Where data supplied by the client or other external sources, including previous site investigation data, have been used, it has been assumed that the information is correct unless otherwise stated. No responsibility is accepted by MWM for incomplete or inaccurate data supplied by others.

MWM may have retained subconsultants affiliated with MWM to provide services for the benefit of MWM. To the maximum extent allowed by law, the Client acknowledges and agrees it will not have any direct legal recourse to, and waives any claim, demand, or cause of action against, MWM's affiliated companies, and their employees, officers and directors.

This Document is provided for sole use by Matakanui Gold Limited and is confidential to it and its professional advisers. No responsibility whatsoever for the contents of this Document will be accepted to any person other than the Client. Any use which a third party makes of this Document, or any reliance on or decisions to be made based on it, is the responsibility of such third parties. MWM accepts no responsibility for damages, if any, suffered by any third party as a result of decisions made or actions based on this Document.

MWM acknowledges that this report will be relied on by a Panel appointed under the Fast Track Approvals Act 2024 and these disclaimers do not prevent that reliance







5 Sir William Pickering Drive, Burnside Christchurch 8053, New Zealand

T. +64 3 242 0221

E. admin@minewaste.com.au

MEMORANDUM

Recipient: Cheryl Low – Matakanui Gold Limited

From: Paul Weber – Mine Waste Management Limited

Date: 13 September 2025

Cc: Leo Navarro – Mine Waste Management Limited; Ryan Burgess – Hydro

Geochem Group Limited

Document Number: J-NZ0233-009-M-Rev3

Document Title: Engineered Landform Design Philosophy

Mine Waste Management Limited (MWM) has provided this engineered landform (ELF) design philosophy memorandum to Matakanui Gold Limited (MGL) for the management of waste rock associated with the proposed Bendigo-Ophir Gold Project (BOGP).

EXECUTIVE SUMMARY

Objectives of this Study

The objectives of this study are to:

- Summarise literature and provide industry proven methods for the design of engineered landforms for the storage of waste rock.
- Provide recommendations (design objectives) to prevent and minimise the potential risks associated with acid and metalliferous drainage (AMD) by the use of source control technologies.
- Provide preliminary recommendations (design objectives) on how waste rock could be managed within an ELF at the proposed BOGP.

Findings

Previous studies (e.g., MWM, 2025a,b,e) have indicated that a number of potential constituents of concern (PCOC) could be elevated at the BOGP including for instance, As, SO₄, Cu, Fe etc., which could have an effect on the downstream environment if not managed appropriately. One aspect of AMD management is source control to prevent sulfide mineral oxidation and the mobilisation of these oxidation products from landforms.

MGL has committed to proactive source control, using engineered landforms, which provides a foundation for sustainable waste rock management, aligning with INAP¹ (2024) principles for long-term environmental stewardship.

_

¹ International Network for Acid Prevention: https://www.inap.com.au/acid-drainage

Management

This report provides a design philosophy for the ELF to prevent the oxidation of sulfides and minimise the mobilisation of any oxidation products by water. Design objectives are incorporated into the ELF Management Plan (EGL, 2025a) and the Mine Impacted Water (MIW) Management Plan (MGL, 2025).

ELFs will use available industry proven methods (e.g., INAP, 2020, 2024) to minimise water and oxygen ingress and hence control the potential geochemical hazards at their source. The current proposed design objectives are explained in Table 1 and focus on minimising oxidation of sulfide minerals and mobilisation of oxidation products (e.g., water management).

Table 1. BOGP ELF Design Objectives

DESIGN FEATURE ATTRIBUTE			
Foundation Earthworks	 Clean water diversion to minimise water/rock interaction. Inert – low sulfur basal materials (3 m thick) to minimise PCOC mobilisation due to basal seepage from natural springs etc. Note: Low sulfur materials (<0.02 wt% S) have been identified in drill holes near the surface of the RAS² deposit to approximately 10-15 m depth and these materials should be used for this basal layer where practicable (MWM, 2025a). Basal underdrainage network to minimise water/rock interaction using the low sulfur (< 0.02 wt% S) materials where practicable. ELF toe bund (or similar) to prevent advective oxygen ingress. 		
Clean Water Management	 Clean water diversion to minimise water/rock interaction. ELF design to shed water as quickly as practicable. Compaction to shed water. 		
Materials Management	 Development of a material classification management process. Development of a material management process. Minimise time between blasting and placement. Maximise blasting opportunities to maximise grainsize of waste rock – e.g., reduce reactive surface area of higher risk materials (e.g., TZ4 / RSSZ³). 		
Lift Height	 Commence construction using a 4-6 m lift height. Confirm grainsize segregation does not occur for lift heights of 4-6 m via test pitting or tip head inspections. Maximise paddock dumping where possible. Undertake studies to confirm whether higher lifts can be used (e.g., >4-6 m) yet advective oxygen ingress is prevented and diffusion of oxygen is limited to 20 m horizontal depth into the ELF. Limit long term diffusive oxygen ingress to < 20 m horizontally and 15 m vertically. Confirm by performance monitoring. 		

Page 2 MWM-S004-Rev2

² Rise and Shine

³ Textural Zone 4 and Rise and Shine Shear Zone materials

DESIGN FEATURE	ATTRIBUTE
	 Validate oxygen flux rates (e.g., cover system trials) to confirm long term sulfide oxidation processes and geochemical model reliability.
Encapsulation	 Placement of RSSZ, TZ4, and high As TZ3 waste rock in the core of the ELF surrounded by lower risk TZ3 materials. Development of perimeter bund (advective oxygen barrier) and lower permeability running surfaces constructed from TZ3 materials.
Cover System	 0.2 m of topsoil/subsoil 0.3 m of moderately weathered mine rock (commonly referred to as 'Brown Rock') Develop a cover system to limit net percolation to <20% of annual rainfall and limit oxygen flux such that closure objectives can be achieved. Further work is required.
Progressive Rehabilitation	 Up-valley construction of the ELF where practicable, to provide immediate surfaces for rehabilitation (cover system installation). Placement of compacted brown rock, soils, and vegetation to reduce net percolation of rainfall.
Performance Monitoring	 Geochemical characterisation and quality assurance / quality control (QA/QC) Grainsize segregation and lift height Oxygen ingress depth Net percolation rates Seepage water quality and quantity

BACKGROUND

MGL is proposing to establish the BOGP, which comprises gold mining operations, processing operations, ancillary facilities and environmental mitigation measures on Bendigo and Ardgour Stations in the Dunstan Mountains of Central Otago. The project site is located approximately 20 km north of Cromwell and will have a maximum disturbance footprint of 550 hectares.

The total Mineral Resource Estimate for the BOGP using a 0.5 g/t cut-off for open pit and 1.5 g/t for underground is 34.3 Mt at 2.1 g/t for 2.34 M oz (MGL, 2025). The Bendigo-Ophir resources occur in four deposits: Come in Time (CIT), Rise and Shine (RAS), Srex (SRX), Srex East (SRE). The majority of identified mineral resources are located within the RAS deposit. Three primary geological units are recognised at site:

- RSSZ Rise and Shine Shear Zone
- TZ3 Lower Greenschist facies Textural Zone 3 rocks of the Otago Schist
- TZ4 Upper Greenschist facies Textural Zone 4 rocks of the Otago Schist

The resources will be mined by open pit methods at each deposit within the project site, with underground mining methods also proposed to be utilised at RAS to access the deeper gold deposits. The majority of the mining activities, ancillary facilities and associated infrastructure will be located in the Shepherds Valley with non-operational infrastructure located on the adjoining Ardgour Terrace. The BOGP also involves the taking of groundwater from the Bendigo Aquifer for use in mining-related activities and the realignment of Thomson Gorge Road via Ardgour Station.

Page 3 MWM-S004-Rev2

The following key mine facilities are proposed:

- Open pits targeting the RAS, SRX, SRE, and CIT deposits.
- An underground mine targeting the RAS deposit.
- Three ex-pit engineered landforms (ELFs) Shepherds ELF, SRX ELF, and West ELF (WELF).
- Two in-pit landforms (backfill) CIT and SRE⁴.
- Plant and processing area, where CIL extraction technologies will be used as part of the ore recovery process.
- A tailings storage facility (TSF) and TSF Embankment.
- Other ancillary support services / structures (e.g., roads, water management infrastructure, water treatment plants, etc).

These facilities will be placed in the catchment of Shepherds and Bendigo creeks (Figure 1).




Figure 1. Bendigo-Ophir Gold Project Infrastructure.

Source: MGL (2025).

OBJECTIVES

The objectives of this study are to:

Page 4 MWM-S004-Rev2

⁴ Note: SRE Pit is backfilled by the SRX ELF.

- Summarise literature and provide industry proven methods for the design of engineered landforms.
- Provide recommendations to prevent and minimise the potential risks associated with acid and metalliferous drainage (AMD) by the use of source control technologies.
- Provide preliminary recommendations on how waste rock could be managed within an ELF at the proposed BOGP.

GEOENVIRONMENTAL HAZARD CHARACTERISATION

The geoenvironmental hazards associated with the BOGP have been assessed (MWM, 2025a,b,e).

Studies indicate that the rocks associated with the project (TZ3, TZ4, and RSSZ) will not generate acid rock drainage with >350 samples tested by industry accepted acid base accounting (ABA) techniques (e.g., AMIRA, 2002). This is a function of the high acid neutralisation capacity (ANC) of the rocks associated with carbonate minerals (e.g., dolomite) and a low sulfide mineral content (e.g., arsenopyrite, pyrite) that can generate lesser acidity. The overall ABA assessment indicates that the rocks are classified as non-acid forming (NAF).

Rocks associated with the BOGP will generate neutral metalliferous drainage (NMD) elevated in PCOC such as As, Cu, Fe, SO₄ etc. Minimising sulfide mineral oxidation (e.g., arsenopyrite) and the mobilisation of oxidation products will minimise the potential effects to receiving waters.

Nitrogenous compounds such as nitrate are also expected to be elevated in seepage from blasted rock due to the use of ANFO, an ammonium-nitrate fuel oil explosive. This is not an uncommon issue in the mining industry.

It is expected that mining of the BOGP will affect waters within the project area and these effects will include:

- Neutral metalliferous drainage (NMD) with elevated sulfate and the other constituents of concern (see MWM, 2025b).
- Nitrate-rich drainage due to the use of ANFO.
- Cyanide using in mineral processing and gold recovery.

Collectively these waters are referred to as mine impacted water (MIW) to acknowledge the different contributions to poor water quality within the project area.

BOGP ENGINEERED LANDFORM - OVERVIEW

This section summarises the primary landforms for the storage of waste rock including the engineered landforms and backfill

Engineered Landform Summary: Shepherd ELF, West ELF, and SRX ELF

Overburden waste rock from the RAS deposit will be stored in the Shepherds ELF (Figure 2) and the West ELF (Figure 3) and the overburden from the SRX Pit will be stored in the SRX ELF (Figure 4).

Page 5 MWM-S004-Rev2

MGL (2024) note that an ELF with a total design capacity of 103.6 million loose cubic metres (LCM) has been designed for the Shepherds Creek catchment (Figure 2). The design quantity has a contingency of roughly 12% which would account for possible changes in the swell factor or the compaction ratio following further analysis on the actual site-specific parameters.

Waste landform sequencing has been undertaken based on the assumption that arsenic concentrations are higher in the ore host rock (TZ4 and RSSZ) and for precautionary reasons it is planned to be encapsulated and capped with lower arsenic waste rock (TZ3).

A base layer and encapsulating layer of inert material is typically required, with a core of non-inert material. For this reason, the ELF has a base layer of 3 metres of TZ3 material. Low sulfur materials (<0.02 wt% S) have been identified in drill holes near the surface of the RAS deposit to approximately 10-15 m depth (MWM, 2025a) and these materials should be used for this basal layer where practicable.

The TSF dam embankment will also consist of TZ3 material. MGL (2024) propose that a minimum 20 m thick capping layer of TZ3 materials will encapsulate the ELF and higher sulfur TZ4 and RSSZ waste rock.

Backfill

Waste rock (TZ3) will be placed as backfill in the CIT Pit to return the ground to its pre-mining topography (or similar). The CIT Backfill is shown in Figure 5 and indicates that the long-term groundwater level will be equivalent to the spill point of 503 m. Waste rock will be constructed as an ELF to minimise long term risks to water quality. The volume of the CIT Pit has been estimated at ~923,000 m³.

Page 6 MWM-S004-Rev2




Figure 2. Shepherds ELF.

Source: MGL (2024).




Figure 3. Conceptual (and schematic) water balance and material distribution for the WELF.

Page 7 MWM-S004-Rev2




Figure 4. SRX Pit and SRX ELF

Source: MGL (2024)




Figure 5. CIT Backfill.

Source: Rekker and Dumont, 2025

AMD MANAGEMENT APPROACH

This section describes the general approach to how AMD is managed.

Background

AMD needs to be managed to reduce health and safety risks for on-site staff and communities, reduce deleterious effects to the environment, and ensure that appropriate closure of the site is achieved at the end of mining activities. This requires six AMD management steps to be undertaken as a holistic approach to AMD management, which is based on international industry guidance (e.g., International Network for Acid Prevention (INAP), 2014; DFAT, 2016). The six AMD management steps include:

Page 8 MWM-S004-Rev2

- 1. Set Closure Goals
- 2. Predict
- 3. Prevent
- 4. Minimise
- 5. Control and Treat
- 6. Monitor Performance

These steps form the basis for any comprehensive AMD Management Plan, which is often supported by a risk assessment process and the development of site-specific operational controls to manage these risks and/or uncertainties. The AMD risk assessment process is based on data obtained from AMD prediction activities and determines the engineering control requirements for the project (e.g., prevention, minimisation, control and treat).

AMD Management Approach

This section provides a high-level summary of the six steps of AMD management.

Table 2. AMD Management Steps

	- · · · · · · · · · · · · · · · · · · ·	
AMD MANAGEMENT STEP	EXPLANATION	RELATED DOCUMENTS FOR THE BOGP
Set Closure Goals	 Closure goals are set in order to minimise legacy issues associated with potential AMD sources and any in-perpetuity uncontrolled AMD from mine domains containing AMD generating materials. These goals are revaluated throughout the mine life against performance monitoring results. 	 Closure objectives for water quality have been established (Ryder, 2025). Baseline Water Quality (MWM, 2025c).
Predict	 Prediction is critical to understanding the potential, severity, and longevity of AMD. Prediction is facilitated by geochemical analysis and interpretations. A key prediction objective is to estimate water quality generated by various materials and mine domains that have the potential to generate AMD. 	 Geoenvironmental Hazards Report (MWM, 2024a). Leach testing to determine PCOC (MWM, 2025b,e).
Prevent	 Prevention of sulfide mineral oxidation, where practicable, is a key management step for AMD. The prevention of AMD relates to reducing sulfide mineral oxidation as much as practicable by limiting the ingress of oxygen into a mine domain where it can oxidise sulfide minerals Prevention strategies are implemented during operations to manage a future risk. 	This memorandum.
Minimise	 Where prevention is not practicable, or has already occurred, the next management step involves minimising the contaminant load reporting to the receiving environment. This often involves progressive reclamation strategies focused on minimising ongoing sulfide oxidation (potential oxidation products) and the mobilization of oxidation products with net percolation through the waste rock. 	This memorandum.

Page 9 MWM-S004-Rev2

Control and Treat	 Although the objective is to prevent and minimise AMD, control and treat measures are an important step in managing the effects of AMD to the receiving environment. 	 Water Management / Treatment Study (MWM, 2024d). Process Flow (2025).
Monitor Performance	 Performance Monitoring should be conducted to regularly evaluate how AMD management techniques are performing openly and objectively against closure goals and success criteria (ICMM, 2019). 	MIW Management Plan (MGL, 2025).

SOURCE CONTROL

Prevention and minimisation of AMD can be considered engineering controls to manage the AMD source hazard. This section discusses source control technologies for the proposed engineered landforms that would contain waste rock at the BOGP.

Overview

Source control involves the prevention of sulfide mineral oxidation (where possible) and minimisation of contact water to reduce the mobilisation of oxidation products. Source control can be considered the a best practice approach to AMD management and reduces the risks of long-term AMD management by tempering the maximum potential AMD risk at closure that requires mitigation / management.

Generally waste rock dumps represent 60 - 80% of a site's AMD contaminant load (INAP, 2020) if the AMD source hazard is not managed appropriately. International case studies are available (e.g., Weber et al., 2017) to demonstrate the high proportion of AMD associated with waste rock domains. Hence there is a strong driver to incorporate waste rock into engineered landforms that address the key principles of AMD source control: Prevention and Minimisation.

Many examples of successful source control for engineered landforms are from New Zealand. INAP (2020) notes the following sites as examples:

- Cypress Coal Mine, Stockton.
- Stockton Coal Mine.
- Reddale Coal Mine.
- Escarpment Coal Mine.
- Waihi Gold Mine (Martha Mine).

Other New Zealand sites that have utilised engineered landforms include:

- Macraes Gold Mine (Coronation North Landform).
- Canterbury Coal Mine.

Prevention of Sulfide Mineral Oxidation

Waste rock that is end dumped in high lifts (>4-6 m in height) and the associated kinetic energy can result in grainsize segregation and the development of alternating coarse-textured and fine-textured bedding planes of poorly graded and well sorted material with high vertical airflow capacity (e.g., Fala et al., 2003; Wilson, 2008). This also results in an overall downward coarser grading providing higher airflow capacity deeper in the facility. In addition, the fall of rocks / cobbles from the end-tipped / dozer

Page 10 MWM-S004-Rev2

pushed material results in the development of a coarse basal layer with high lateral airflow capacity that provides oxygen ingress pathways into the core of the waste rock dump (WRD) as shown in Figure 6.

The dominant process for oxygen flux is by the advective and convective flow of oxygen (temperature differences, barometric pressure differences) along coarser waste rock layers that form within poorly constructed WRD. Work completed by Brown et al. (2014) has demonstrated that in a poorly constructed WRD, advection accounts for ~90% of oxygen ingress, and that diffusion of oxygen accounts for 10%.

Hence, a key control to prevent sulfide mineral oxidation and minimise the effects on seepage waters from WRD is to prevent the advective ingress of oxygen.




Figure 6. Advective air flow driven by grainsize segregation.

Source: Meiers (2020).

The flux of oxygen into a poorly constructed WRD is typically higher than the flux of oxygen into a tailings storage facility (TSF).

- Within a TSF the oxygen flux is driven by diffusion due to the chemical gradient (no oxygen at depth versus atmospheric oxygen concentrations at the surface).
- Within a WRD the oxygen flux is often driven by the advective flow of oxygen (temperature differences, barometric pressure differences, etc) along coarser waste rock layers that form within poorly constructed WRD.

The oxygen flux (as evidenced by oxidation products) is shown in Figure 7. Hence, for the BOGP, control of oxidation is focused on the ELF rather than the TSF.

Page 11 MWM-S004-Rev2



Figure 7. Diffusion of oxygen into a TSF as shown by Fe oxidation products, and advection pathways within a WRD as shown by oxidation at angle of response tipheads.

Source: Miller et al., 2003: ICARD 2003 ARD Prediction Short Course.

International research (INAP, 2020; 2024) has demonstrated that one of the most effective methods to minimise advective ingress of oxygen into WRDs is to minimise the height of the tiphead to <4 - 6 m and ensure that each lift has a compacted engineered surface, which reduces the size of the advective cell (both vertically and horizontally into the WRD; Figure 8 and Figure 9). Reducing oxygen ingress reduces sulfide mineral oxidation and hence the risks associated with AMD.

The establishment of multiple traffic compacted lifts also reduces the height of advective oxygen ingress to these cells. Further detailed design work is required to confirm that traffic air-entry layers can be achieved at BOGP, or whether additional materials / material management is required.




Figure 8. Conceptual gas transport regime in a WRD with no engineering controls.

Source: INAP (2024): Significant horizontal ingress along the basal chimney zone and significant vertical rise upwards along chimney zones.

Page 12 MWM-S004-Rev2




Figure 9. Conceptual gas transport regime into an ELF with trafficked air-entry disrupting running surfaces.

Source: INAP (2024): Limited oxygen ingress horizontally due to a lack of a basal rubble layer; limited vertical oxygen rise due to lower permeability running surfaces.

INAP (2024) note that an "Engineered Fill' approach "allows for the ability to more accurately model and predict O₂ ingress and the volume and quality of recoverable seepage requiring treatment over time" and that "this approach focuses on prevention, rather than a cure. This 'Engineered Fill' approach manages AMD "risks through implementation of source control, progressive reclamation, and cover systems, which allows for opportunities to move from active to passive water treatment over time thereby reducing asset liability, and likelihood of in-perpetuity management".

Figure 10 shows the impact of various grain-sized materials on the gas flux rate and acidity generation (i.e., sulfide mineral oxidation). Employing techniques like short lifts and paddock dumping effectively reduces oxygen ingress, leading to reduced sulfide mineral oxidation and, consequently, mitigating the potential risks associated with AMD.

Page 13 MWM-S004-Rev2




Figure 10. Grainsize segregation: high tipheads.

Source: Pearce et al (2016).

Water Management

Water flow through materials that contain sulfide oxidation products is the primary pathway for mobilisation of contaminants and the generation of AMD impacted waters. Diversion of run-on water and reducing infiltration of water into materials containing sulfide minerals, or sulfide mineral oxidation products, is a key management step for the management of AMD. Often this is site specific and is dependent on climate, topography, location of mine domains, etc.

ELF SOURCE CONTROL OPTIONS FOR THE BOGP

The following section reviews source control opportunities for the BOGP. Appropriate design objectives can then be integrated into the mine schedule and the ELF Basis of Design report (which will be developed prior to mining). Note: the guidance provided needs to be considered by a competent geotechnical engineer as being appropriate for geotechnical risks.

Foundation Earthworks

The following is recommended for the starter lift:

 Clean water upstream of the ELF could be piped through the facility as a management option during the operational phase of the mine to minimise water/rock interactions.

Page 14 MWM-S004-Rev2

- Basal lift materials are likely to be in contact with topographic surface level seeps. Such
 materials should be inert, low sulfur, low arsenic, TZ3 materials. MGL (2024) have indicated
 this will be 3 m thick. Low sulfur materials (<0.02 wt% S) have been identified in drill holes near
 the surface of the RAS deposit to approximately 10-15 m depth (MWM, 2025a) and should be
 used for this basal layer where practicable.
- Prior to construction of the first starter lift, ensure a drainage pathway (underdrain) is created so that any seepage from the ELF is directed to one location. For the BOGP, seepage is likely to collect on the natural stream/topographic floor. Engineering Geology Limited (EGL) have designed this underdrainage system for Shepherds ELF and SRX ELF (EGL, 2025b).
- Materials used for the underdrain should be inert, low sulfur, low arsenic, TZ3 materials. The
 low sulfur (<0.02 wt% S) materials near the RAS surface (MWM, 2024a) should be used as
 construction materials for the underdrains where practicable.
- The underdrain will be connected to a HDPE pipe that will take seepage water from the ELF to the Shepherds Sediment Pond.
- An ELF toe bund will be constructed within the ELF. This will act as a barrier to advective oxygen flow. Underdrain pipes will be placed through this ELF toe bund in a manner that prevents oxygen ingress. The design of this is discussed by EGL (2025b).
- An ELF Sediment Pond should be constructed at the base of the starter lift to capture seepage
 from the ELF. The design of the ELF Sediment Pond should consider repurposing as a passive
 treatment system for ELF seepage at mine closure. This should include suitable maintenance
 access for removing sediment accumulation and potentially decant structures.

Clean Water Management

Studies have indicated that the BOGP materials are elevated in sulfate (SO₄) minerals that can be mobilised by water (MWM, 2025e). This means water flow through these materials within the ELF will mobilise this contaminant load. The following is recommended for ELF water management:

- Diversion of clean run-on water from upslope areas away from the ELF.
- Design of the ELF (batter slopes and running surfaces) to shed water as quickly as possible.
- Where practicable, avoid ponding of water on waste rock (e.g., avoid sediment sumps on ELF surfaces).
- Compaction, to design specifications, of the ELF running surfaces during operations to shed
 water and minimise infiltration of rainwater thus reducing the volume of seepage water and
 extending the wetting up time period and onset to basal and toe seepage.
- Flattening out paddock dumped materials (ideally wheel rolled or compacted) to shed water before significant rainfall events.

Page 15 MWM-S004-Rev2

Materials Management

MGL (2024) state that waste rock disposal will be carried out by haul trucks approaching the Shepherds ELF from the west at various elevation levels. Track dozers will be used to push the material to form the batter slopes.

The following materials management processes need to be considered:

- Development of a materials schedule (and quantities) to ensure the correct materials are available and are placed in the correct location. This will be completed for the BOGP as part of the detailed design. This will include topsoil scheduling.
- Minimise the time between blasting and placement of mineralised waste, TZ4, RSSZ, high As
 TZ3 waste in the ELF. This will reduce the oxidation of sulfide materials.
- Manage the ore stockpiles as higher-risk mineralised waste, which is likely to contribute to poor water quality.
- Investigate blasting practices to increase particle size in TZ4 and RSSZ waste rock (to minimise mineral surface area exposure to oxygen (and AMD generation)). Conversely an assessment should be undertaken to look at decreasing the particle size of TZ3 materials for encapsulation purposes, although the risks of nitrogenous compounds and elevated SO₄ should also be considered for blasting to generate finer materials.
- TZ3 materials are weaker than the TZ4 materials with an UCS⁵ of ~20 MPa compared to TZ4 materials that ~ 70 MPa (EGL, 2025b). It is expected TZ3 will break down with trafficking to form a lower permeability surface compared to TZ4 materials. This may have benefits for limiting advective oxygen ingress within the proposed ELFs.
- Blasting of TZ4 / RSSZ materials may generate waste rock that has a greater proportion of clast supported materials compared to TZ3 materials, which is a higher risk for oxygen ingress (Table 3). This is another benefit for having the TZ4 /RSSZ placement zones towards the rear of the ELF.
- Develop a traffic management plan to ensure the running surfaces are thoroughly compacted to minimise vertical rise of oxygen by advective processes.

Lift Height

It is recommended that the construction process and the height of end-tips is designed to prevent grainsize segregation and minimise advective flux of oxygen. Research has shown that tipheads <4 – 6 m do not generate grainsize segregation (Fala et al., 2003; Wilson, 2008), which reduces the risk of advective oxygen flux. However, tiphead height will be specific to the project materials and further work is required to confirm that advective oxygen ingress is prevented. The following approach is proposed:

 Commence construction using a lift height of 4 - 6 m and confirm that no segregation of materials occurs at this height.

5

Page 16 MWM-S004-Rev2

⁵ Unconfined compressive strength

- Higher lift heights might be possible. Undertake studies to confirm whether higher lifts can be
 used (e.g., 4-6 m) yet advective oxygen ingress is prevented and diffusion of oxygen is limited
 to ~20 m horizontal depth into the ELF.
- Confirm that segregation does not occur for different materials at different tiphead heights (e.g., TZ3 versus TZ4). Table 3 provides a high-level summary for the clast supported vs matrix supported ELF due to segregation processes.
- Where practicable, paddock dumping should be undertaken.
- Undertake performance monitoring to confirm depth of oxygen ingress aligns with geochemical model estimates of 20 m (MWM, 2025f), which was used to support the design objectives for the ELF (MGL, 2024).

Table 3. Clast vs matrix supported ELF.

ELF MATRIX	PROPERTIES	COMMENTS				
Clast Supported	Greater porosity Greater air voids Lower density	End-tipping results in the separation of coarser and finer particles creating a material that tends to be clast supported with higher overall porosity				
Matrix Supported	Lower porosity Less air voids High density	Paddock dumping and low-lift heights prevents material segregation such that the coarser materials are supported by a matrix of miner materials leading to lower porosity.				

Encapsulation

The encapsulation of reactive sulfide-rich materials with low-risk materials is a proven source control technology to reduce sulfide mineral oxidation. The greater the thickness of low sulfide-bearing encapsulating material, the less oxygen diffusion from the atmosphere to the reactive materials (e.g., Figure 11), assuming that advective and convective airflow is minimised by material placement strategies.

Page 17 MWM-S004-Rev2




Figure 11. Acid generation rate (due to oxygen diffusion) as a function of cover thickness.

Source: Miller et al., 2010; ASGR = acid sulfate generation rate

For the BOGP the following encapsulation options should be undertaken:

- Placement of higher sulfur waste rock (TZ4, RSSZ) towards the back of each lift in a zone of limited airflow. As shown in Figure 9, this prevents higher-risk material from being within the zone of higher oxygen movement (e.g., the advective cell) near the front batter slopes of an ELF. The size of these zones and the number of individual zones will be a function of the materials schedule and 20 m is proposed as the set-back.
- Development of a perimeter bund of paddock dumped waste rock (lower sulfur TZ3 and or brown rock) at the start of each lift at the outer edge of the ELF. This can then be compacted as a toe barrier (~ 2 m high). Toe barriers have been proposed for other projects to limit oxygen ingress due to grainsize segregation (e.g., Figure 12). Further work is required to confirm the height and width of any advective toe barrier. This will be part of the detailed design.




Figure 12. Advective toe barrier.

Source: Meiers (2020).

Page 18 MWM-S004-Rev2

Cover System

A cover system can minimise the amount of oxygen and water flux into an ELF as well as providing a stable revegetation medium. A variety of systems are available including soil/rock covers, low permeability compacted clays barrier layers, capillary breaks, geosynthetic clay layers, and membrane technology such as polythene. A cover system should be considered one aspect of AMD management.

A cover system should be considered one aspect of AMD management. INAP (2017) notes that cover systems are designed to:

- Meet regulatory requirements
- Divert clean water and reduce the volume of impacted surface water managed on site
- Isolate chemically reactive waste material
- Limit upward movement of process-water constituents and oxidation products
- Limit influx of oxygen and oxidation of certain minerals
- Limit influx of meteoric water to limit oxidation of certain minerals, and limit leaching and dilution of oxidation products
- Control wind and water erosion of waste material as part of the overall landform stability
- Provide a growth medium as the "building blocks" for establishing vegetation and ecosystems.

Types of cover systems include (INAP, 2017):

- · Erosion-protection systems
- Store-and-release systems
- Enhanced store-and-release systems
- Barrier-type systems
- Cover systems with engineered layers
- Saturated soil or rock cover systems

MWM (2025g) has provided guidance on the expected net percolation rates (i.e., % of rainfall that will enter the mine facilities) for the ELFs at the BOGP, which has been estimated at 30 – 50%. Data from Macraes (MWM, 2024) suggest lower NP may be possible, in the region of 10 to 20% of annual rainfall. Cover system design elements such as thicker layers and/or lower permeability layers at the base of the cover system could be considered to achieve NP towards the lower range (e.g., NP of 20% of annual rainfall). Further work is required to demonstrate this is achievable at the BOGP.

This flow will mobilise stored contaminants within the mine domain. For the BOGP the following is recommended:

- Utilisation of existing soils and subsoils as the growing medium.
- Brown rock and lower sulfur TZ3 materials need to be assessed for their geotechnical benefits as a cover system material to limit oxygen/water ingress.

Page 19 MWM-S004-Rev2

• Further analysis is recommended as part of the ELF detailed design to understand the benefits of the cover system including a store and release system to reduce net percolation.

The long-term oxygen flux rate will determine the ongoing generation of PCOC from the ELFs. Hence, the cover system and ELF construction processes should also limit oxygen flux such that closure objectives can be achieved. Further work is required on confirm oxygen flux rates through cover system trials.

Progressive Rehabilitation

Progressive rehabilitation will be a key component of the ELF construction process. This will include:

- Grading down materials from the dump crest to the toe of the batter slope and compaction with a dozer.
- Spreading cover materials (e.g., brown rock, or inert finer grained lower sulfur TZ3 materials)
 to achieve the agreed design specification to limit oxygen ingress / water ingress.
- Topsoiling of the batter slope (or application of suitable brown rock), hydroseeding to control soil loss and the establishment of vegetation.

PERFORMANCE MONITORING

Performance monitoring is an important aspect of AMD management and should include leading and lagging performance monitoring programs to confirm design objectives are being achieved. Performance monitoring provides the data for trigger action response plans (TARPs) in case there is a variance from the expected case and further actions are required to minimise potential effects. Performance monitoring should be designed around demonstrating success criteria (primarily based on design objectives) are being achieved and that performance can be demonstrated openly and objectively. This report suggests that performance monitoring should include, for instance:

- Monitoring of water quality and quantity at the discharge of the ELF underdrain (e.g., Shepherds ELF, SRX ELF, West ELF, CIT backfill) to understand water quality effects and confirm net percolation rates.
- Monitoring of groundwater downgradient of ELF to confirm that basal seepage is not significant.
- Monitoring of oxygen flux into the ELF using oxygen probes and/or oxygen sensors to confirm the oxygen concentration and the depth of the oxidation is < 20 m (i.e., the design objectives)
- Installation of lysimeters soil monitoring (i.e., matric suction and water content sensors) to validate net percolation rates are acceptable (i.e., < 20%) and meet design expectations.

Construction QA/QC is also required during the construction of the ELF to ensure the facility has been constructed as per the basis of design. Construction QA/QC could include for instance:

- Geochemical characterisation of materials (pre-excavation and placement) for AMD risks and risks associated with nitrogenous compounds.
- Monitoring of tipheads to confirm that grainsize segregation is not occurring to ensure a matrix supported rock mass is achieved.

Page 20 MWM-S004-Rev2

Performance monitoring and TARPs are a key aspect of adaptive management.

HEALTH AND SAFETY CONSIDERATIONS

Construction methodologies involving small lift heights introduce several health and safety benefits during the construction/operational phases:

- Eliminating many risks related to working on and around tipheads with significant vertical drops.
- Substituting less stabled wheeled plant with highly stable tracked machines when working close to the tiphead.
- A reduction in the likelihood and consequence severity of geotechnical failures at tipheads due to restricted height.
- Lesser risk of differential settlement and areas requiring active control and management.
- Lesser reliance on catch berms to control larger rocks at the toe of the tiphead.
- A reduction in point source dust emissions through smaller drop heights leading to improved air quality for operators within the immediate vicinity and a reduction to the cumulative particulate load released to receiving environments.
- A general decrease in potential AMD effects and risks in the longer term.

SUMMARY

INAP (2020) notes that "direct and indirect measurements of acidity load from various site domains at more than 40 sites over the past 25 years have revealed that mined sulfidic waste rock typically contributes to the majority of the total acidity load (60 to 80%) from most mine sites, with a further 20 to 30% of acidity load associated with TSFs, and relatively minor contributions from other sources (e.g., underground mine void wall-rock, open cuts, heap leach facilities and other stockpiles)". Hence the greatest long term source hazard for AMD is waste rock rather than tailings. For the BOGP, acidity and low pH are not considered an issue due to the high carbonate content, however, the risks associated with sulfide oxidation products (i.e., neutral metalliferous drainage) remain, hence the risks remain applicable for waste rock storage facilities.

To address this risk, MGL has committed to proactive source control, using engineered landforms, which provides a foundation for sustainable waste rock management, aligning with INAP (2024) principles for long-term environmental stewardship.

Several optioneering studies were completed to determine the most appropriate location for the ELF (MWM, 2025h) with consideration given to minimisation of oxygen ingress and water ingress as components of the optioneering study. The upper Shepherds Creek catchment was chosen for the Shepherds ELF, which minimised exposed surface area. ELFs will use available industry proven methods and acceptable solutions (e.g., INAP, 2020, 2024) to minimise water and oxygen ingress.

CLOSING REMARKS

Please do not hesitate to contact Paul Weber at +64 3 242 0221 or paul.weber@minewaste.com.au should you wish to discuss this memorandum in greater detail.

Page 21 MWM-S004-Rev2

REFERENCES

- AMIRA, 2002. ARD Test Handbook Project P387A Prediction and Kinetic Control of Acid Mine Drainage. AMIRA International Limited. Melbourne, Australia.
- Brown, P. L., Logsdon, M. J., Vinton, B., Schofield, I., & Payne, K., 2014. Detailed characterisation of the waste rock dumps at the Kennecott Utah Copper Bingham Canyon Mine–Optionality for Closure. In Proceedings of the Eighth Australian Workshop on Acid and Metalliferous Drainage. Adelaide (pp. 1-12).
- DFAT, 2016. Leading Practice Sustainable Development Program for the Mining Industry Preventing Acid and Metalliferous Drainage. Department of Foreign Affairs and Trade, Commonwealth of Australia. Canberra, Australia. https://www.industry.gov.au/publications/leading-practice-handbooks-sustainable-mining/preventing-acid-and-metalliferous-drainage.
- EGL, 2025a. ELF Management Plan. Report prepared by Engineering Geology Limited for MGL.
- Engineering Geology Limited (EGL), 2025b. Bendigo-Ophir Gold Project Shepherds Tailings Storage Facility Technical Report. Prepared for Matakanui Gold Limited. Dated 15 July 2025.
- Fala, O., Aubertin, M., Molson, J., Bussière, B., Wilson, G.W., Chapuis, R., Martin, V., 2003. Numerical Modelling of Unsaturated Flow in Uniform and Heterogeneous Waste Rock Piles. In "Proceedings of the Sixth International Conference on Acid Rock Drainage", Cairns, Australia, 14-17 July (Eds. T Farrell and G Taylor), pp. 895 -902. Australian Institute of Mining and Metallurgy, Carlton, Victoria.
- ICMM, 2019. Integrated Mine Closure, Good practice Guide, 2nd edition, February.
- INAP, 2014. Global Acid Rock Drainage Guide (GARD Guide) Rev1 International Network for Acid Prevention. http://www.gardguide.com/images/5/5f/TheGlobalAcidRockDrainageGuide.pdf.
- INAP, 2017. Global Cover System Design Technical Guidance Document. International Network for Acid Prevention, November 2017, 220 pp.
- INAP, 2020. Rock Placement Strategies to Enhance Operational and Closure Performance of Mine Rock Stockpiles. Phase 1 Work Program Review, Assessment & Summary of Improved Construction Methods. Report prepared for the International Network for Acid Prevention (INAP) by Okane and Earth Systems. 105 pp.
- INAP, 2024. ARD/AMD Source Control for Mine Rock Stockpiles Phase 3. Report prepared for the International Network for Acid Prevention (INAP) by Okane. 53 pp: https://www.inap.com.au/wp-content/uploads/2024-6-Jun-27-1043-222-001-Source-Control-for-MRS-Ph-3-Rev-0.pdf.
- Miller, S.D., Stewart, W.S., Rusdinar, Y., Schumann, R.E., Ciccarelli, J.M., Li, J., Smart, R. St.C., 2010. Methods for estimation of long-term non-carbonate neutralisation of acid rock drainage. Science of the Total Environment 408 (2010) 2129–2135
- Meiers, G, 2020. A Case Study of the Influence of Shorter Tips in Mine Rock Storage on Internal Air Flow Capacity. BC-MEND Metal Leaching and Acid Rock Drainage Workshop. December 1 -3, 2020 Vancouver, British Columbia, Canada Zoom Conference.

Page 22 MWM-S004-Rev2

- MEND, 2009. Prediction Manual for Drainage Chemistry from Sulphidic Geologic Materials Report, MEND Report 1.20.1.
- MGL, 2024. Bendigo-Ophir Pre-Feasibility Study. Report prepared by Santana Minerals Limited, 330 pp.
- MGL, 2025. Mine Impacted Water Management Plan. Report prepared by Mine Waste Management for MGL.
- Mine Waste Management (MWM), 2024. BWWRS Geochem Model. MWM Report J-NZ0229-M-009-Rev0 for OceanaGold. Available: https://www.orc.govt.nz/media/vfpbccka/annexure-02-brwrs-geochemical-model-mwm.pdf
- MWM, 2025a. Factual Report: Geoenvironmental Hazards. Bendigo-Ophir Gold Project. Mine Waste Management Report No. J-NZ0233-008-R-Rev0 for Matakanui Gold Limited.
- MWM, 2025b. SPLP and SEM EDS Analysis. Mine Waste Management Memorandum J-NZ0233-014-M-Rev0.
- MWM, 2025c. Baseline Water Quality Report, Bendigo-Ophir Gold Project. Mine Waste Management Report J-NZ0233-006-R-Rev1 for Matakanui Gold Limited.
- MWM, 2025d. Water Management / Treatment Study. Mine Waste Management Memorandum J-NZ0464-002-M-Rev0 for Matakanui Gold Limited.
- MWM, 2025e. Factual Report: Column Leach Test, Bendigo-Ophir Gold Project. Mine Waste Management Report J-NZ0233-015-R-Rev0.
- MWM, 2025f. Engineered Landform Water Quality Forecast Model Report, Bendigo-Ophir Gold Project.

 Mine Waste Management Report J-NZ0457-002-R-Rev0 for Matakanui Gold Limited.
- MWM, 2025g. Net Percolation Assessment for the Proposed Bendigo-Ophir Gold Project Engineered Landforms. Mine Waste Management Report J-NZ0455-001-M-Rev4 for Matakanui Gold Limited.
- MWM, 2025h. ELF Options Assessment. Mine Waste Management Report J-NZ0457-001-M-Rev1 for Matakanui Gold Limited.
- Pearce, S., Baisley, A., O'kane, M., 2016. Quantitatively Assessing the Benefits of Managing Gas Entry into Waste Rock Dumps During Placement to Reduce Long-Term ML-ARD Risk. BC MEND ML/ARD Workshop 2016, https://bc-mlard.ca/workshop-proceedings/2016-workshop, 28 pp.
- Process Flow (2025). BOGP Post Closure Active Water Treatment Plant (WTP) Order of Magnitude (Oom) Study. Process Flow Report PFL-2426-PRJ-RPT-00001.
- Rekker, J. H., & Dumont, M. 2025. Rise & Shine Gold Project Groundwater Existing Environment & Effects Assessment. Kōmanawa Solutions Client Report No. Z24002BOG1. Kōmanawa Solutions Ltd, Christchurch.
- Ryder, G., 2025. Bendigo-Ophir Gold Project: Recommended water quality compliance limits for the Bendigo-Ophir Gold Project. Report for Matakanui Gold by Greg Ryder Consulting.

Page 23 MWM-S004-Rev2

- Weber, P.A., McKeown, M., Christensen, D., Mueller, S., O'Kane, M., Bird, B., 2017. Forecasting long term water quality after closure: Boliden Aitik Cu mine. New Zealand Annual AuslMM Branch Conference, Christchurch, 10 13 September, p 353 361.
- Wilson, G.W., 2008. Why are we still battling ARD. In "Proceedings of the Sixth Australian Workshop on Acid and Metalliferous Drainage", Burnie, Tasmania. 15-18 April 2008. (Eds LC Bell, BMD Barrie, B Baddock, and RW MacLean) pp. 101 112 (ACMER: Brisbane).

Page 24 MWM-S004-Rev2

APPENDIX K NET PERCOLATION ASSESSMENT



5 Sir William Pickering Drive, Burnside, Christchurch 8053, New Zealand

T. +64 3 242 0221

E. admin@minewaste.com.au

MEMORANDUM

Recipient: Cheryl Low – Environment Manager – Matakanui Gold Limited

From: Paul Weber – Principal Environmental Geochemist, Mine Waste

Management Limited

Date: 12 August 2025

Ryan Burgess – Hydro Geochem Group Limited

Greg Meiers – Mine Closure Management Limited

Document Number: J-NZ0455-001-M-Rev3

Document Title:Net Percolation Assessment for the Proposed Bendigo-Ophir Gold Project

Mine Waste Storage Facilities

Mine Waste Management Limited (MWM) has been engaged by Matakanui Gold Limited (MGL) to assess the net percolation (NP) (or water ingress) rates into mine waste storage facilities (MWSFs) at the Bendigo-Ophir Gold Project (BOGP). The estimated water ingress rates will be used to support an assessment of environmental effects for the BOGP and support the resource consent application under the Fast Track Act Application.

EXECUTIVE SUMMARY

Higher NP is typically associated with increased Acid and Metalliferous Drainage (AMD) load and will therefore be a key influence on AMD water collection and treatment requirements to meet closure objectives at the BOGP. The Water and Load Balance Model (WLBM) developed for the BOGP will use NP estimates provided in this assessment to understand the project risks associated with downstream water quality and treatment needs.

Objectives of this Study

- Estimate a range of potential water ingress rates into the proposed MWSFs to support an assessment of environmental effects for the BOGP.
- Make recommendations for forward works to advance cover system designs and increase confidence in expected performance.

Findings

- During operations, the uncovered ELF, with relatively coarse texture and higher permeability material will result in high NP, estimated to be in the region of 60 to 80 % of annual precipitation.
- The proposed cover system can be categorised as a water store-and-release cover system.
 The main driving factors are the climate and texture of the proposed cover materials. Landform and vegetation aspects are not expected to significantly influence NP.
- NP for the covered ELF and TSF is estimated to range between 30% and 50% of annual precipitation.

- Data from Macraes (MWM, 2024) suggest lower NP may be possible, in the region of 10 to 20% of annual rainfall, but further work is required to demonstrate this is achievable at the BOGP.
- Cover system design elements such as thicker layers and/or lower permeability layers at the base of the cover system could be considered to achieve NP towards the lower range (e.g., NP of 20% of annual rainfall).
- Modelling to understand potential effects of the BOGP uses 20% NP. Further work is required to validate this assumption and comprehensive cover trials are required in the first few years of operations.

Recommended Forward Works

Following development of the BOGP, it is recommended that cover system field trials, dedicated cover monitoring, and focused material characterisation be initiated following approvals to improve confidence in post-closure cover system performance.

Ultimately, the understanding gained from these studies will improve estimates of closure costs, (especially post-closure water collection and treatment requirements and longevity) and convey to external stakeholders a level of understanding of the site that demonstrates a commitment to successful closure.

ASSESSMENT SCOPE

The scope of this assessment was to develop a range of NP estimates for the following MWSFs and BOGP phases:

- Mine rock Engineered Landform (ELF) during operations.
- ELF post-closure with a cover system constructed over the surface.
- Tailings Storage Facility (TSF) post-closure with a cover system constructed over the surface.

The current BOGP mine plan includes three ELFs, Shepherds ELF, Western ELF and Srex (SRX) ELF. For the purposes of this assessment, it is assumed that they share similar characteristics that would influence NP, and thus it is proposed that a single range of estimated NP values is applicable for all ELFs. The TSF during operations was excluded from the scope as the water balance will largely be influenced by active tailings deposition / process water and water management practices.

The typical process followed in cover design is shown as a flow chart in Figure 1. The scope outlined in this assessment falls into the first two steps: (i) Site and Materials Characterisation and (ii) Conceptual Design, noting that the scope of this assessment is based on a cover system design provided by others (i.e., this document does not design the cover system, only assess potential performance of said design). The WLBM that will used the estimates of NP made in this assessment will allow for Impact Analysis to identify any noncompliance and/or unacceptable risk that may necessitate changes in the current cover system design.

Page 2 MWM-S004-Rev2




Figure 1: Typical cover design flow chart.

Source: MEND (2004).

CONCEPTUAL MODEL

This section describes key BOGP ELF material properties and aspects of the upper and lower boundary conditions used to estimate NP. ELF aspects are based on the Project Description (PD)¹ and discussions during a meeting² held with MGL and other subject matter experts.

For the purposes of this assessment, the term NP means infiltration of water that will migrate below the 'active zone' into the underlying mine waste material (see Figure 2). Within the near surface active zone, water can be subject to storage, transport, evaporation, or transpiration processes. Once NP has reached the mine waste, it could either be stored as moisture, report to groundwater, or emerge at the toe of the facility.

Page 3 MWM-S004-Rev2

¹ Bendigo-Ophir Gold Project Description, Version 2. Dated 30 July 2024.

² In person meeting held 19 September 2024.




Figure 2: Net percolation conceptual illustration.

Source: MEND (2004).

Proposed Cover System

During operations, mine rock will be exposed during active placement. According to the PD, the ELFs will be built bottom up in small lifts that are end tipped with a dozer push to reduce segregation.

At closure both the ELF and TSF will have the following proposed cover system, from the top down, installed over the respective mine waste material (EGL, 2025).

- 0.2 m of topsoil/subsoil.
- 0.3 m of moderately weathered mine rock (commonly known as 'Brown Rock').

Given the upper boundary climate condition with a potential evaporation (PE) to precipitation ratio of 0.75, the cover system will reduce NP through the process of water store-and-release, where a proportion of precipitation is stored within the cover profile and then subsequently released back to the atmosphere through evapotranspiration.

Climate

At the BOGP, three meteorological stations have been installed across the project area at varying elevations. Data has been collected since November 2022. The SRX meteorological station data was used to characterise the climate for this assessment since it is at an elevation closest to where the ELFs will be positioned on the landscape. Other stations are positioned at lower elevations so are likely to be less representative, particularly for precipitation. In addition, these lower elevation stations experienced measurement malfunctions for solar radiation over a number of months in 2023.

Page 4 MWM-S004-Rev2

Precipitation and PE are presented on a monthly basis in Figure 3. Precipitation was based on a synthetic rainfall record (Chater, 2024) developed for the Lake Clearview station (2006 to 2023, 17 years) and scaled to the SRX station elevation. Snowfall occurs anecdotally over winter (site meteorological stations do not measure snowfall or snowpack depth), but with mean monthly winter temperatures ranging between 2 to 5 °C, active ablation of the snowpack occurs. Overall, precipitation may be underestimated slightly, but unlikely enough to change the interpretation of climatic conditions relevant to this assessment.

PE was calculated with the Penman (1948) method, using site specific air temperature, relative humidity, wind speed, and solar radiation for the period available at the time of reporting (November 2022 through July 2025).

Calculating water surplus (Rainfall-PE)³ at different temporal scales provides an approximate indication of the climate's ability to remove water from a cover system through evapotranspiration processes (assuming negligible surface ponding or runoff). The cover systems with greater ability to store water would tend towards weekly to monthly scales and vice vera. Calculations for data between 22/11/2022 and 29/07/2025, were as follows:

- Monthly scale, 322 mm of water available for net percolation, or ~25% of rainfall that fell over this period (1,370 mm). 75% is returned to the atmosphere.
- Weekly scale, 582 mm of available for net percolation, or ~40% of rainfall. 60% is returned to the atmosphere.
- Daily scale, 1095 mm of available for net percolation, or 80% of rainfall. 20% is returned to the atmosphere.

The following observations are made based on the available climatic data:

- Based on the Köppen-Geiger classification, the climate can be characterised as temperate, without a dry season, and as having a warm summer (Cfb). Mean annual air temperature is 8 °C. Without a dry season, the process of water store-and-release will be muted over the winter where there is an observed decrease in PE.
- On an annual basis, precipitation (P) is approximately 510 mm while PE is approximately 815 mm. On average, the annual PE:P ratio is 1.6, and typically ranges between 1.3 and 2.0 over the 17-year rainfall record (PE was assumed constant given the lack of data).
- The climate is relatively dry, with a strong energy surplus (PE>P) present between September through March, and an energy deficit (PE<P) over the remainder of the year, most notably over winter.
- For cover systems that have a favourable ability to store water, 60 to 75% of infiltrating water could be removed through evapotranspiration (assuming negligible surface ponding or runoff).
 Conversely, cover systems that have a poorer water ability to store water (i.e., thin covers), 20 to 60% of soil water could be removed.

Page 5 MWM-S004-Rev2

³ Where PE>Rainfall, water surplus is set to zero.




Figure 3: Monthly precipitation and PE summary.

PE=Potential Evaporation. Bars show monthly averages while error bars show rainfall standard deviation over period of record.

Material Properties

Site-specific reclamation and waste material physical material properties are not available. Based on the nearby Macraes Mine, which has a similar climate (mean annual rainfall of approximately 600 mm) and similar geological setting, mine rock is expected to be relatively coarse textured, with a high surface infiltration rate and hence reduced potential for runoff generation.

In the absence of site-specific data, the following is assumed:

- Topsoil: When stripped, it is likely to be a mixture of topsoil and upper weathered bedrock horizon. Site visit observations suggest in-situ soil is well graded and loamy (Figure 4). For the purposes of this assessment the topsoil layer is assumed to be representative of a loamy sand material, with 20% fines and relatively moderate saturated permeability (k=10-5 m/s).
- Brown Rock: Mine rock overburden with a moderate degree of weathering, will be relatively coarse, well graded, with limited clay and silt sized particles (fines) (potentially less than 10%⁴) with and estimated saturated hydraulic conductivity of 1 x 10⁻⁴ m/s.

Page 6 MWM-S004-Rev2

⁴ Provided by E. Torvelainen of Engineering Geology Limited via email 11 November 2024.



Figure 4: Topsoil (in-situ) example.

Landform

The project layout and ELFs are shown Figure 5. The following landform relevant details are highlighted:

- The ELFs and TSF will be positioned in the valley bottoms of incised valleys.
- Post-closure, the ELFs are expected to have a relatively flat top surface with minor slope to direct any runoff generated to manage water. The batter slopes of the ELF landforms will be 3(H):1(V). All ELFs will have a mixture of north, south, east and west aspects.
- Post-closure, the TSF will be relatively flat, with minor slopes to direct any runoff generated to
 the north side to the clean water diversion drain which is ultimately conveyed past the
 Shepherds ELF back to the valley bottom downstream of the ELF toe.
- Post-closure, the ELFs will be sloped to convey any runoff that is generated off the landforms. The TSF drainage condition post-closure will be drained.

Page 7 MWM-S004-Rev2




Figure 5: BOGP layout showing the TSF, Shepherds ELF, Western ELF, and SRX ELF.

Source: MGL Project Description.

Vegetation

Post-closure vegetation established over the cover systems is anticipated to similar to the existing vegetation, notably a mixture of pasture and tussock. An example of this vegetation is shown in Figure 6.



Figure 6: Existing vegetation examples for the region.

Looking approximately east.

Page 8 MWM-S004-Rev2

ASSESSMENT FINDINGS

Exposed ELFs (Operations)

Although the BOGP climatic setting suggests that there is potential for PE to lower NP into exposed (or uncovered) ELFs, the likely coarse texture, inferred high permeability and limited water retention capacity of the mine rock, coupled with the upper climate boundary condition, suggests a relatively high expected NP. Williams (2008) collated and reviewed worldwide data on NP into waste rock dumps and found it ranges between 50 and >85% of annual rainfall.

The bottom-up ELF construction would produce running surfaces on each lift, but the permeability needed to start appreciably diverting runoff and reducing NP, would be challenging to achieve in a consistent manner given the anticipated physical properties of the mine rock.

On balance, NP for the exposed ELFs is expected to range between 60% to 80% of annual precipitation.

Rehabilitation Cover System for ELF and TSF (Post-Closure)

Industry guidance is useful to place the climatic setting into the context of expected performance for different types of cover systems. For a temperate climate and a water store-and-release cover system, INAP (2017) suggest NP performance can be expected to range between 15% to 50% of mean annual precipitation. An enhanced water store-and-release or barrier type system would likely be required to reduce NP below this range given the Köppen-Geiger Cfb climate classification.

The GARD Guide (INAP, 2014) define cover system type suitability based on climatic setting, as shown in Figure 7. Based on a PE:P ration of 1.7, ranging between 1.3 and 2 (shown in red on Figure 7), the GARD Guide (INAP, 2014) suggests that water store-and-release cover systems are targeted for climates with a PE:P of greater than 2 and as such a cover system that includes some form of infiltration control (e.g., enhanced store and release, low permeability barrier, etc.) would improve performance (i.e., lower NP).

Williams (2008) also compiled and reviewed worldwide data on NP performance for cover systems. For water store-and-release covers, the reported NP performance was approximately 15% or less. However, these types of systems were used in more arid sites in Australia and USA, and the cover systems were much thicker (2 m or more) than proposed for the BOGP, allowing for more water store-and-release prior to NP. For example, NP for a 2 m thick store-and-release system at the Mt. Whaleback Mine in Western Australia (with a stronger PE:P ratio of roughly 8) was reported to achieve a NP of 5% to 15 % of annual rainfall. Note the influence of material texture is not factored into this comparison given the lack of data. For example, thinner covers with finer texture material can perform better than thicker and coarser material. On balance, the lower BOGP PE:P ratio suggests higher rates of NP as compared to performance observed at more arid sites as reported by Williams (2008).

MWM (2024) estimated NP into the Frasers West Waste Rock Stack at Macraes Mine to be about 12% of annual rainfall.

Factors from the conceptual model influencing potential NP ranges are summarised in Table 1. Overall, based on currently available data, it is expected the proposed cover system, a relatively thin water store-and-release cover system with relatively permeable material, will achieve a NP performance in the range of 30 to 50 % of annual precipitation. Data from Macraes (i.e., MWM, 2024) suggest lower NP in the range of 10 to 20% of annual rainfall may be possible, but further work is required to

Page 9 MWM-S004-Rev2

demonstrate this is achievable (see the Recommendations section for further details). Cover system design elements such as thicker layers and/or lower permeability layers at the base of the cover system could be considered to achieve NP towards the lower range (e.g., NP of 20% of annual rainfall).




Figure 7: Climatic conditions to support water store-and-release cover systems.

Note: the red circle represents the long term annual average climatic conditions, while the bar show the typical annual variability.

Source: INAP (2014).

Page 10 MWM-S004-Rev2

Table 1: Estimated performance of a water store-and-release cover system.

PARAMETER	REMARK	NET PERCOLATION
Climate	 Temperate, without dry season, warm summer (Cfb). Gard Guide recommends barrier type cover system. The estimated performance based on INAP (2017) seems reasonable. 	20% to 50%
Materials	 Cover material to be moderately weathered coarse mine rock and topsoil with modest fines content, possible less than 20%, with limited clay minerals. Nominally thin cover profile with reduced water storage. This would support a NP towards the higher end of the range from climate alone. 	Lower NP estimate scaled upward based on materials to 30% to 50%
Landform	 Landform unlikely to have high degree of influence on NP due to anticipated relatively high surface permeability. Range unchanged from materials. Both the ELF and the TSF are largely flat or north facing, so likely have similar PE. ELF has steeper slopes while TSF is much flatter so runoff likely higher for ELF. Overall, ELF NP could be lower than that of the TSF but may not be substantially different if surface permeability is relatively high. Long-term lower boundary condition within the TSF not considered assessment. 	Landform not considered to change estimated NP range 30% to 50%
Vegetation	 Mixture of grassland and evergreen species. Vegetation will promote evapotranspiration during the growing season however this may be limited due to the relatively coarse textured cover material and low winter PE. Overall, vegetation is unlikely to greatly influence NP compared to other parameters. 	Vegetation considered to be healthy and not increase NP range 30% to 50%

CONCLUSIONS

Findings from the NP assessment for the uncovered and covered MWSFs are as follows:

- During operations, the uncovered ELF, with relatively coarse texture and higher permeability material will result in high NP, estimated to be in the region of 60 to 80 % of annual precipitation.
- The proposed cover system can be categorised as a water store-and-release cover system.
 Industry guidance (INAP, 2014, 2017) suggest it will not perform as well as infiltration control type systems due to the reduced atmospheric demand for water over the winter period.
- Post-closure, NP for the covered ELF and TSF is estimated to range between 30% and 50% of annual precipitation. The main driving factors are the climate and texture of the proposed cover materials. Landform and vegetation aspects are not expected to significantly influence NP.
- Data from Macraes (MWM, 2024) suggest lower NP may be possible, in the region of 10 to 20% of annual rainfall, but further work is required to demonstrate this is achievable at the BOGP. Cover system design elements such as thicker layers and/or lower permeability layers at the base of the cover system could be considered to achieve NP towards the lower range (e.g., NP of 20% of annual rainfall).

Page 11 MWM-S004-Rev2

 Given the ELFs have greater proportions of north facing slopes that will increase PE, and have steeper slope angles that would increase runoff, NP for the ELF could be lower than the TSF (valley bottom position and flat slopes). However, if surface permeabilities are relatively high as anticipated, the difference in NP may not be substantial.

RECOMMENDATIONS

If further studies indicate improved cover system performance is required, in terms of treatment requirements or downstream water quality, the following recommendations can be considered:

- Material textural properties are based on anecdotal evidence and could be finer texture than currently assumed. In general, finer textured materials would tend to improve NP performance (i.e., reduce estimated NP toward the lower end of ranges provided). As such, incorporation of site-specific particle size distribution data would refine the assessment.
- Numerical simulations are completed to better assess sensitivity to the upper and lower boundary condition and material properties on simulated performance. Modelling may be able to demonstrate more favourable performance (i.e., expected performance is closer to 30% of annual precipitation than 50%).
- Alternate cover system designs could be considered. For example, thicker cover layers, enhanced water store-and-release systems, or low permeability barrier type systems would improve expected performance.

Following development of BOGP it is recommended that cover system field trials, dedicated monitoring, and focused material characterisation be initiated following approvals to improve confidence in post-closure cover system performance and allow for detailed design (i.e., as shown in Figure 1).

Ultimately, the understanding gained from these studies will improve estimates of closure costs, (especially post-closure water collection and treatment requirements and longevity) and convey to external stakeholders a level of understanding of the site that demonstrates a commitment to successful closure.

CLOSING REMARKS

Please do not hesitate to contact Paul Weber at	10	
should you wish to discuss this memorandum in gre	eater detail.	

Page 12 MWM-S004-Rev2

REFERENCES

- Chater, M, 2024. Extension of synthetic rainfall time series, Bendigo Project. Dated August 2024.
- Engineering Geology Limited (EGL), 2025. Bendigo-Ophir Gold Project Shepherds Tailings Storage Facility Technical Report. Prepared for Matakanui Gold Limited. Dated 15 July 2025.
- International Network for Acid Prevention (INAP), 2014. Global Acid Rock Drainage (GARD) Guide. Dated October 2014. https://www.gardguide.com/index.php?title=Chapter 6. Accessed October 2024.
- International Network for Acid Prevention (INAP), 2017. Global Cover System Design Technical Guidance Document. Dated November 2017.
- MEND, 2004. Design, Construction and Performance Monitoring of Cover Systems for Waste Rock and Tailings. Volume 1. Dated July 2004.
- Mine Waste Management (MWM), 2024. BWWRS Geochem Model. MWM Report J-NZ0229-M-009-Rev0 for OceanaGold. Available: https://www.orc.govt.nz/media/vfpbccka/annexure-02-brwrs-geochemical-model-mwm.pdf
- Penman, H., 1948. Natural evaporation from open water, bare soil, and grass. Proceedings of the Royal Society of London, Series A: Mathematical and Physical Sciences, 193: 120-145.
- Williams, 2008. The Influence of Climate on Seepage from Mine Waste Storages During Deposition and Post-Closure. Mine Closure 2008 proceedings.

Page 13 MWM-S004-Rev2

APPENDIX L ENGINEERED LANDFORM WATER QUALITY FORECAST **REPORT**

Engineered Landform Water Quality Forecast Model Report

Bendigo-Ophir Gold Project

13 September 2025

J-NZ0457-002-R-Rev1





Engineered Landform Water Quality Forecast Report

Bendigo-Ophir Gold Project

Document Number: J-NZ0457-002-Rev1

Document Date: 13 September 2025

Prepared for:

Matakanui Gold Limited

15a Chardonnay Street, Cromwell, 9310

Prepared by:

Mine Waste Management Limited

5 Sir William Pickering Drive, Burnside, Christchurch 8053, New Zealand +64 3 242 0221

REVISION	DATE	AUTHOR RECORD OF REVIEW		
RevA	31-3-2025	LN	PW	
RevB	12-06-2025	LN	PW	
Rev0	05-08-2025	LN	PW	
Rev1	13-09-2025	LN	PW	

EXECUTIVE SUMMARY

Mine Waste Management Limited (MWM) has prepared this report on the geochemical modelling of the proposed engineered landforms (ELFs) at the Bendigo-Ophir Gold Project (BOGP) for Matakanui Gold Limited (MGL) to understand potential effects on water quality from these mine domains. The modelling supports proactive source control and provides a foundation for sustainable waste rock management, aligning with INAP ¹ (2024) principles for long-term environmental stewardship. Data are used in the water and load balance model (MWM, 2025b) to understand the effects on the receiving environment and provide improved management opportunities for ELF seepage.

Objectives of this Study

The purpose of this report is to present the geochemical modelling undertaken to estimate seepage water quality for the Shepherds ELF, SRX ELF, Come in Time (CIT) Backfill, West ELF, and Shepherds Creek (SCK) Fill during operations and during the active closure and post closure phases of the BOGP. The objectives of this report are as follows:

- Develop a conceptual geochemical model for each ELF.
- Estimate water quality seepage from the ELFs during operations and the active closure and post closure phases of the BOGP.
- Provide recommendations for management of ELF seepage based on model results.

Findings

MGL will place waste rock in ELFs to minimise long term risks associated with sulfide mineral oxidation and the release of potential constituents of concern (PCOC). Further details on the design philosophy for ELFs are provided in MWM (2025f)

The materials associated with the BOGP will generate neutral metalliferous drainage and may have elevated PCOC such as arsenic (As), sulfate, (SO₄), and trace metals. Nitrogenous compounds are also likely to be elevated. Collectively the waters are referred to as mine impacted waters (MIW).

If waste rock was managed by traditional waste rock stack construction methods that did not manage advective oxygen ingress along basal rubble zones created by high tipheads (>10 - 20 m in height) and grainsize segregation, then Shepherds WRS seepage water quality could be > 6,000 mg/L sulfate. By minimising oxygen ingress to the outer 20 m of the proposed ELFs, a significant reduction in sulfate (and other PCOC) are expected.

Modelling indicates that peak sulfate concentrations for the Shepherds ELF could be reduced by ~80% to approximately ~1,120 mg/L by using best practicable management methods for waste rock storage.

Management

This study has identified and recommends the following management opportunities that will minimise the long-term risks to water quality for waste rock storage at the BOGP:

¹ International Network for Acid Prevention: https://www.inap.com.au/acid-drainage

- Proceed with the proposed ELF design, ensuring low As TZ3 materials encapsulate high-sulfur materials (TZ4) to minimise oxygen ingress.
- Proceed with short lift heights at 5 m height and confirm that grainsize segregation is minimised and that oxygen is reduced to < 5% after 10-20 m horizontal distance into the ELF and that the oxygen profiles (from oxygen probe monitoring) demonstrate that oxygen ingress is diffusion controlled. Higher heights may be possible if advective oxygen ingress is prevented by engineering controls.
- Install cover systems to further mitigate risks as the final landform is created. Consider cover systems to minimise net percolation as this is a key driver of long term PCOC load.
- Establish a comprehensive monitoring program for water quality, oxidation rates, and cover system performance. Adapt management strategies based on observed trends and evolving conditions.
- Continue validating laboratory-to-field scaling factors using site-specific data, particularly for TZ3 and TZ4 materials, to refine long-term predictions.

General Background

MGL is proposing to establish the BOGP, which comprises a new gold mine, ancillary facilities and environmental mitigation measures on Bendigo and Ardgour Stations in the Dunstan Mountains of Central Otago. The project site is located approximately 20 km north of Cromwell and will have a maximum disturbance footprint of 550 hectares.

The total Mineral Resource Estimate for the BOGP using a 0.5 g/t cut-off for open pit and 1.5 g/t for underground is 34.3 Mt at 2.1 g/t for 2.34 M oz (MGL, 2025). The Bendigo-Ophir resources occur in four deposits: Come in Time (CIT), Rise and Shine (RAS), Srex (SRX), Srex East (SRE). The majority of identified mineral resources are located within the RAS deposit. Three primary geological units are recognised at site:

- RSSZ Rise and Shine Shear Zone
- TZ3 Lower Greenschist facies Textural Zone 3 rocks of the Otago Schist
- TZ4 Upper Greenschist facies Textural Zone 4 rocks of the Otago Schist

The resources will be mined by open pit methods at each deposit within the project site, with underground mining methods also proposed to be utilised at RAS to access the deeper gold deposits. The majority of the mining activities, ancillary facilities and associated infrastructure will be located in the Shepherds Valley – which includes a conventional carbon-in-leach (CIL) gold processing plant and water treatment plant, a tailing storage facility, three engineered landforms, internal haul roads, topsoil stockpiles, water pipelines, underground utilities and electrical supply - with non-operational infrastructure located on the adjoining Ardgour Terrace. The BOGP also involves the taking of groundwater from the Bendigo Aquifer for use in mining-related activities and the realignment of Thomson Gorge Road via Ardgour Station.

The proposed BOGP will include the following components:

Open pits targeting the RAS, SRX, SRE, and CIT deposits.

- · An underground mine targeting the RAS deposit.
- Three ex-pit engineered landforms (ELFs) Shepherds ELF, SRX ELF, and West ELF (WELF).
- Two in-pit landforms (backfill) CIT and SRE².
- Plant and processing area, where CIL extraction technologies will be used as part of the ore recovery process. This includes ~ 5 m of TZ3 fill and is referred to as SCK Fill.
- A tailings storage facility (TSF) and TSF Embankment.
- Other ancillary support services / structures (e.g., roads, water management infrastructure, water treatment plants, etc).

Mine Impacted Water

A geochemical model is required to understand the effect on the receiving environment of the MIW and forecast the water quality from the proposed ELFs, as traditional waste rock stacks (WRS) generally represent the greatest source of contaminants for any mining project (e.g., INAP, 2020).

Model Development

The following modelling methods were used:

<u>Data and Methodology:</u> The geochemical model risks were informed by data from acid-base accounting (ABA), total sulfur analysis, and chemical assay of waste rock samples, as well as AMIRA (2002) column leach test (CLT) data. The geochemical behaviour was modelled under three scenarios:

- 1. A traditional WRS with high lift heights and complete oxidation of materials: This model was used to calibrate the model water quality estimates to empirical datasets.
- 2. An ELF constructed with limited oxygen ingress 10 m horizontal oxidation shell.
- 3. An ELF constructed with limited oxygen ingress 20 m horizontal oxidation shell.

<u>Sulfur Reservoir Estimation:</u> Reactive fractions of waste rock within the WRS and ELF models were defined, using a non-reactive fraction of 0.9 to account for field-scale mineral accessibility ³. Sulfur reservoirs were split into stored oxidation products (SOP) and long-term sulfide sources that was based on CLT data.

<u>Oxidation and Release Rates:</u> Sulfate and metal release rates were calculated for the TZ3 and TZ4 lithological units from CLT data. CLT data showed that TZ4 was found to release sulfate at a rate six times higher than TZ3 due to its higher sulfur content and mineral reactivity.

<u>Time Lag to Peak Concentration:</u> A delay between waste rock placement and peak solute concentrations reporting as seepage from the structures is expected. Peak sulfate concentrations, a function of average ELF height, were determined for Shepherds ELF (~27 years), SRX ELF (~5 years),

² Note: SRE Pit is backfilled by the SRX ELF.

³ This non-reactive fraction is comparable to international literature (e.g., Linklater et al., 2017).

CIT ELF (~4 years), WELF (~10 years), and SCK Fill (~3 years) based on analogue data from Macraes (e.g., MWM, 2024a).

Adjustment Factors: To align lab results with analogue data from Macraes, a release rate adjustment factor of 0.8575 was applied to oxidising materials (i.e., 10% of the materials in the WRS). These adjustments allowed the model to simulate realistic peak sulfate concentrations for a traditional WRS (e.g., ~6,200 mg/L for Shepherds WRS).

<u>Mobilisation:</u> Oxidation products are driven by net percolation, which has been estimated at 20% of rainfall (MWM, 2025c).

Solubility Controls: PHREEQC geochemical modelling (Parkhurst and Appelo, 2003) was used to apply mineral solubility limits and simulate precipitation of secondary minerals. Assumptions included dolomite buffering and elevated CO₂ in porewaters (due to carbonate dissolution within the WRS / ELF).

Summary

The study indicates that:

- Water quality is expected to be circum-neutral pH with low acidity. This is due to the abundance of carbonate minerals and a low sulfide content.
- When the results for the two scenarios overlap (e.g., 10 m and 20 m oxidation zones), it indicates that the solutes originate from short-term release, where oxidation has no impact on the results, and therefore, results are the same.
- The first 50 years are strongly influenced by the short-term release of SOP. This is particularly evident for nitrate-nitrogen (NO₃-N), boron (B), cobalt (Co), and zinc (Zn), which are generally elevated and are associated with SOP (see Table 14). Reducing water ingress would reduce the rate that these PCOC are mobilised.
- Sulfate concentrations are > 500 mg/L for the Shepherds ELF, SRX ELF, and WELF. Sulfate concentrations are < 500 mg/L in the CIT backfill and the SCK Fill.
- Nitrate-N concentrations are > 2.4 mg/L in seepage from all waste rock disposal areas. Duration
 of elevated nitrate in seepage is expected to range from 25 100 years but may be shorter due
 to biogeochemical processes that would remove the nitrate.
- Results indicate that the following trace metals: Co, Mo, Mn, Se, Sb, Sr, U, and Zn, are generally over the respective water quality reference limits.
- Results indicate that Al, B, Cd, Cr, Cu, Hg, and Pb, are below the respective water quality reference limits in all cases. These PCOC are not considered an issue for this mine domain.
- Constant concentrations are assumed for As (0.2 mg/L) and Fe (7.6 mg/L) based on empirical
 data for sub-oxic conditions (e.g., Globe Progress Waste Rock Stack, Hayton et al., 2022).
 These concentrations are above the proposed water quality reference limit (Ryder, 2025) and
 will require management. The SCK Fill assumes full oxidation, which results in low Fe
 concentrations.

Conclusions

- ELF construction to limit oxygen ingress significantly improve water quality outcomes over traditional WRS by limiting oxygen ingress and reducing the oxidation of higher sulfur materials.
- Net percolation rates drive the mobilisation of soluble contaminants.
- This modelling supports proactive source control and provides a foundation for sustainable waste rock management, aligning with INAP (2024) principles for long-term environmental stewardship.

Performance Monitoring

- Confirm the sulfur content of materials placed in the ELF ensuring that lower sulfur TZ3
 materials are placed on the outside of the ELF. Testing should include shake-flask testing to
 validate the quantity of sulfate and nitrogenous compounds present in blasted rock.
- Confirm that oxygen ingress is excluded from the core of the ELF by the construction of oxygen
 probes into each lift during construction of the ELF.
- Confirm water quality for ELF seepage aligns with geochemical models including sulfate and nitrate. Update models where significant differences are observed.
- The geochemical model relies on laboratory data and analogue assumptions; field validation is required. The model requires updating once the CLT is complete as early data can bias results towards higher loads.
- If performance monitoring indicates unacceptable loads, then adaptive management options should be considered including additional source control actions (e.g., engineered cover systems), reducing oxidation depth to 10 m into the ELF, a longer period of active treatment and/or the development of passive treatment systems to manage the PCOC concentrations and loads.

TABLE OF CONTENTS

1	Ir	ntro	oduction	1
	1.1	I	Project Description	1
	1.2		Geology	2
	1	.2.1	1 Regional Geology	2
	1	.2.2	2 BOGP Geology	3
	1.3	I	Environmental Geochemistry	3
	1.4	(Climate	4
	1.5	ı	Rehabilitation	4
	1.6	ı	Report Objectives	4
2	L	iter	rature Review and Model Assumptions	6
	2.1	,	Analogue Site - Macraes	6
	2	2.1.1	1 Sulfur Content	6
	2	2.1.2	2 Waste Rock Stack Seepage	7
	2.2	ı	Macraes WRS Seepage Water Quality: Height Relationship	8
	2.3	(Concentration Versus Flow	9
	2.4	(Oxygen Ingress	11
	2	2.4.1	1 Waste Rock Stacks	11
	2	2.4.2	2 Engineered Landforms	11
	2	2.4.3	3 Model Development	12
		2.4	4.3.1 20 m Wide ELF Oxidation Zones (ELF – 20 m Model)	12
		2.4	4.3.2 10 m Wide ELF Oxidation Zones (ELF – 10 m Model)	12
	2.5	;	Scaling Factors	13
	2.6		Nitrogenous Compounds	14
	2	2.6.1	1 Literature Review	14
	2	2.6.2	2 Model Inputs	18
3	Е	LF	Conceptual Geochemical Model	19
	3.1	I	Engineered Landform Summary: RAS, SRX, and WELF	19
	3.2	ı	Backfill	21
	3.3	;	Shepherds Creek Fill Area	22
	3.4	(Cover System	22
	3.5		Water Soluble PCOC	
	3.6	(Oxygen Ingress	23
	3.7	(Conceptual Domain Models	23
	3	3.7.1	1 Shepherds ELF	24
	3	3.7.2	2 SRX ELF	25
	3	3.7.3	3 West ELF	26
	3	3.7.4	4 CIT Backfill	26
	3	3.7.5	5 SCK Fill	27
4	E	LF	Geochemical Modelling Process	29

	4.1	Data Sc	ources	. 29
	4.2	Modellir	ng Approach	. 29
	4.2.	1 Sce	enarios Definition	. 29
	4.2.	2 Sul	fur Reservoir Estimation	. 29
	4.2.	3 Rel	lease Rates	. 33
	4.2.	4 Tim	ne Lag to Peak Concentrations and Adjustments to Empirical Data	. 35
	4.2.	5 Adj	ustments to Match Empirical Data: Waste Rock Stack Height	. 37
	4.2.	6 Oth	ner Solute Release Calculations	. 38
	4.2.	7 Sol	ubility Controls (PHREEQC)	.40
	4.3	Summa	ry of Model Inputs and Other Considerations	.41
	4.4	Model L	imitations	.44
5	Mod	del Resu	Its and Analysis	.45
	5.1	Water C	Quality Reference Criteria	.45
	5.2	Genera	l Observations	.45
	5.3	Shephe	rds ELF	.46
	5.4	SRX EL	.F	. 50
	5.5	West El	LF	. 53
	5.6	CIT Bac	kfill ELF	.57
	5.7	SCK Fil	l	.61
6	Sun	nmary		.65
	6.1	Overvie	W	.65
	6.2	Key Fin	dings	.65
	6.3	Recomr	mendations	.66
	6.4	Limitation	ons	.66
	6.5	Perform	nance Monitoring	.67
7	Refe	erences.		.68
8	Limi	itations		.72
A	ppendi	x A A	Abbreviations	.73
Α	ppendi	xB L	imitations	.76

LIST OF TABLES

Table 1. WRS silt pond seepage water quality from Macraes Gold Mine. From Golder (2011a)	7
Table 2. RAS Pit mine schedule.	20
Table 3. SRX Pit mine schedule.	21
Table 4. CIT Pit material quantities	21
Table 5. CIT Pit material quantities	22
Table 6. Material quantities (excluding soil)	24
Table 7. Sulfur reservoir calculations for the Shepherds ELF.	30
Table 8. Sulfur reservoir calculations for the SRX ELF.	31
Table 9. Sulfur reservoir calculations for the CIT ELF backfill	31
Table 10. Sulfur reservoir calculations for the WELF	32
Table 11. Sulfur reservoir calculations for the SCK Fill	32
Table 12. Column leach test data for TZ3 and TZ4 oxidising materials	34
Table 13. Summary of ELF physical characteristics and SO ₄ (mg/L) if constructed as a WRS	35
Table 14. Average short-term and long-term release rates for TZ3 and TZ4	39
Table 15. Equilibrium phases in the geochemical modelling for solubility controls	
Table 16. Summary for ELF modelling inputs	42
Table 17. Reference concentration limits for surface water and groundwater (mg/L)	45
Table 18. Selected model results for the Shepherds ELF Scenarios	
Table 19. Selected model results for the SRX ELF Scenarios	52
Table 20. Selected model results for the WELF scenarios	56
Table 21. Selected model results for the CIT Backfill scenarios	60
Table 22. Selected model results for the SCK Fill WRS scenario.	64
LIST OF FIGURES	
Figure 1. Bendigo-Ophir Gold Project Infrastructure	
Figure 2. Sulfur content for Macraes waste rock.	
Figure 3. Total sulfur distribution curve for BOGP materials.	
Figure 4. WRS seepage sulfate concentrations, Macraes Gold Mine	8
Figure 5. WRS seepage sulfate concentrations as a function of WRS age and average WRS he	ight8
Figure 6. Average WRS height versus maximum sulfate concentrations at Macraes	
Figure 7. Fanny Creek Side Cast, Island Block Mine, West Coast	
Figure 8. Globe Progress Mine, West Coast	10
Figure 9. FWWRS seepage rates and interpolated sulfate concentration data	10
Figure 10. Graphic representation of the outer rim and horizontal ingress of oxygen at 20 m	12
Figure 11. Nitrate concentrations from various studies, mine type, and mine domains	15
Figure 12. Sulfate versus nitrate-N concentrations for Macraes WRS.	15
Figure 13. Shake flask extraction data for blasted backfill at Macraes	16

Figure 14. Nitrate concentrations for the ICI WRS seep (Argyle Diamond Mine)	17
Figure 15. Nitrate concentrations for Gap Dam, the process circuit, and East Wesley See Diamond Mine.	
Figure 16. Shepherds ELF	19
Figure 17. SRX Pit and SRX ELF	20
Figure 18. Shepherds Creek Fill Area Fill location.	22
Figure 19. Conceptual (and schematic) water balance and material distribution for the Sh	
Figure 20. Conceptual (and schematic) water balance and material distribution for the SF	RX ELF25
Figure 21. Conceptual (and schematic) water balance and material distribution for the WI	ELF26
Figure 22. Conceptual (and schematic) water balance and material distribution for the Cobackfilled pit.	
Figure 23. CIT cumulative backfill material below 510 mRL	27
Figure 24. Conceptual (and schematic) water balance and material distribution for the SC	CK Fill28
Figure 25. Cumulative released amount for sulfate based on the AMIRA CLT	34
Figure 26. Cumulative percentage of waste rock material releasing solutes over time	36
Figure 27. Comparison of model output for Shepherds WRS with no time lag to peak con and a time lag scenario.	
Figure 28. Adjustment Factors to match empirical data models: Traditional WRS	37
Figure 29. Cumulative CLT solute release rates for B, Mo, and U.	39
Figure 30. Process diagram for estimating the water quality seepage of the ELFs	43
Figure 31. Model results part 1 for the Shepherds ELF	47
Figure 32. Model results part 2 for the Shepherds ELF	48
Figure 33. Model results part 1 for the SRX ELF.	50
Figure 34. Model results part 2 for the SRX ELF.	51
Figure 35. Model results part 1 for the West ELF.	
Figure 36. Model results part 2 for the West ELF.	
Figure 37. Model results part 1 for the CIT Backfilled ELF.	
Figure 38. Model results part 2 for the CIT Backfilled ELF.	59
Figure 39. Model results part 1 for the SCK fill.	
Figure 40. Model results part 2 for the SCK fill.	63

1 INTRODUCTION

Mine Waste Management Limited (MWM) has prepared this report on the geochemical modelling of the proposed engineered landforms (ELFs) at the Bendigo-Ophir Gold Project (BOGP) for Matakanui Gold Limited (MGL) to understand potential effects on water quality from these mine domains. The modelling supports proactive source control and provides a foundation for sustainable waste rock management, aligning with INAP 4 (2024) principles for long-term environmental stewardship. Data are used in the water and load balance model (MWM, 2025b) to understand the effects on the receiving environment and improved management opportunities for ELF seepage.

1.1 Project Description

MGL is proposing to establish the BOGP, which comprises a new gold mine, ancillary facilities and environmental mitigation measures on Bendigo and Ardgour Stations in the Dunstan Mountains of Central Otago. The project site is located approximately 20 km north of Cromwell and will have a maximum disturbance footprint of 550 hectares.

The total Mineral Resource Estimate for the BOGP using a 0.5 g/t cut-off for open pit and 1.5 g/t for underground is 34.3 Mt at 2.1 g/t for 2.34 M oz (MGL, 2025). The Bendigo-Ophir resources occur in four deposits: Come in Time (CIT), Rise and Shine (RAS), Srex (SRX), Srex East (SRE). The majority of identified mineral resources are located within the RAS deposit. Three primary geological units are recognised at site:

- RSSZ Rise and Shine Shear Zone
- TZ3 Lower Greenschist facies Textural Zone 3 rocks of the Otago Schist
- TZ4 Upper Greenschist facies Textural Zone 4 rocks of the Otago Schist

The resources will be mined by open pit methods at each deposit within the project site, with underground mining methods also proposed to be utilised at RAS to access the deeper gold deposits. The majority of the mining activities, ancillary facilities and associated infrastructure will be located in the Shepherds Valley – which includes a conventional carbon-in-leach (CIL) gold processing plant and water treatment plant, a tailing storage facility, three engineered landforms, internal haul roads, topsoil stockpiles, water pipelines, underground utilities and electrical supply - with non-operational infrastructure located on the adjoining Ardgour Terrace. The BOGP also involves the taking of groundwater from the Bendigo Aquifer for use in mining-related activities and the realignment of Thomson Gorge Road via Ardgour Station.

The proposed BOGP will include the following components:

- Open pits targeting the RAS, SRX, SRE, and CIT deposits.
- An underground mine targeting the RAS deposit.
- Three ex-pit engineered landforms (ELFs) Shepherds ELF, SRX ELF, and West ELF (WELF).
- Two in-pit landforms (backfill) CIT and SRE 5.

-

Page 1 MWM-S003-Rev2

⁴ International Network for Acid Prevention: https://www.inap.com.au/acid-drainage

⁵ Note: SRE Pit is backfilled by the SRX ELF.

- Plant and processing area, where CIL extraction technologies will be used as part of the ore recovery process.
- A tailings storage facility (TSF) and TSF Embankment.
- Other ancillary support services / structures (e.g., roads, water management infrastructure, water treatment plants, etc).

These facilities will be placed in the catchment of Shepherds and Bendigo creeks (Figure 1).




Figure 1. Bendigo-Ophir Gold Project Infrastructure

1.2 Geology

1.2.1 Regional Geology

The Dunstan Mountains are an uplifted block of the Otago Schist tilted to the northwest with remnants of a Cretaceous peneplain well preserved on its northern slopes. The Otago Schist is formed from sedimentary and minor intermediate volcanics and volcaniclastics of the Caples and Torlesse tectono-stratigraphic terranes. Greenschist facies rocks of the Otago schist are sub-divided into four textural zones based on mineralogy and mineral textures. Peak metamorphic grades in the Otago Schist occurred during the Jurassic when the Zealandia micro continent formed the outboard subduction complex of the Gondwana continental margin.

The regional geology of the Central Otago goldfields surrounding the BOGP consists of chlorite and biotite schists. The Rise & Shine Shear Zone (RSSZ), a late metamorphic deformation zone (Cox et al., 2006), runs through the project site dipping at 20-30 degrees northeast. The RSSZ occurs in the

Page 2 MWM-S003-Rev2

Textural Zone 4 (TZ4) schist in close association with the Thomsons Gorge Fault, which cuts and truncates the RSSZ against the unmineralised TZ3 schist (Cox et al., 2006). There is no mineralisation associated with the TGF itself, and Au mineralisation had ceased by the time of formation of the TGF (c. 100 Ma) (Cox et al., 2006).

1.2.2 BOGP Geology

Gold mineralisation occurs along the Rise and Shine Shear Zone (RSSZ) within the Otago Schist. The Rise and Shine Shear Zone (RSSZ) has been traced for 1.7 km north-northeast beneath the unconforming TZ3 cover rocks with the bulk of the mineralisation sitting beneath 150-300 m of the lower sulfur cover rock (TZ3). The flat lying and flat plunging deposit sits within a zone up to 400 m wide and can be up to 90 m in thickness (typically 30 – 40 m).

The Thomson Gorge Fault is a post metamorphic, post mineralisation cataclastic fault zone developed primarily along the hanging wall of the RSSZ. It separates chlorite rich, TZ3 schists in the hanging wall from biotite rich TZ4 schists in the shear zone and foot wall. The main mineralisation at RAS is associated with silica-siderite/ankerite alteration with minor arsenopyrite sulfides associated with the gold. In some areas a cataclastite (brecciated) network of anastomosing, post-metamorphic quartz, occur with minor sulfide veins in a halo of the core mineralisation. Allibone (2023) also identified the presence of sphalerite ((Zn,Fe)S) and galena (PbS) at the BOGP.

Locally, a number of splay faults are interpreted coming off the main RSSZ structure which give a sense of structural control. These are also mineralised and are traceable for 10s to 100s of metres. Gold occurs as free gold particles, typically up to 400 µm but with some coarser visible gold. A minor gold component occurs associated with the arsenopyrite grains, but it is typically not in solid solution, giving rise to the free milling and highly gravity recoverable components expressed by metallurgical testing.

1.3 Environmental Geochemistry

The BOGP gold deposit is located within the Otago Schist, near Cromwell, New Zealand, and is associated with the mineralised Rise and Shine Shear Zone (RSSZ). Gold mineralisation within the RSSZ and TZ4 is dominated by elevated sulfur (S) and arsenic (As) (e.g., the mineral arsenopyrite) compared to TZ3 materials

The mineralisation associated with the BOGP and natural weathering of the gold deposit has contributed to baseline water quality being elevated in some metals, which has been acerbated by historical legacy mining activities, leading to streams in the project area being enriched in potential constituents of concern (PCOC) that include for instance, As, Co, Cu, Fe, U, and Zn that are elevated compared to proposed resource consent water quality limits (Ryder, 2025) and some others identified as being elevated on an infrequent basis such as Al, Cd, Mn, Pb, Sr, and Tl. Similarly, groundwaters are elevated in Sr.

Studies indicate that the rocks associated with the project (TZ3, TZ4, and RSSZ) will not generate acid rock drainage with >350 samples tested by industry accepted acid base accounting (ABA) techniques (e.g., AMIRA, 2002). This is a function of the high acid neutralisation capacity (ANC) of the rocks associated with carbonate minerals (e.g., dolomite) and a low sulfide mineral content (e.g., arsenopyrite, pyrite) that can generate lesser acidity. The overall ABA assessment indicates that the rocks are classified as non-acid forming (NAF).

Page 3 MWM-S003-Rev2

Nitrogenous compounds such as nitrate are also expected to be elevated in seepage from blasted rock due to the use of ammonium-nitrate fuel oil (ANFO) based explosive. This is not an uncommon issue in the mining industry.

It is expected that mining of the BOGP could affect surface- and ground- waters within the project area and these effects will include:

- Elevated total suspended solids (TSS).
- Neutral metalliferous drainage with elevated sulfate (SO₄) and the certain PCOCs such as As,
 Fe, and trace metals.
- Nitrate-rich drainage due to the use of ANFO as a bulk explosive during blasting activities.

Collectively these waters are referred to as mine impacted water (MIW) to acknowledge the different contributions to poor water quality within the project area. This report assesses the effects of PCOC and nitrate-rich drainage.

1.4 Climate

The site is situated within the Otago semi-alpine region. As a result, the climate is strongly seasonal, comprising of frosts and snow between Autumn and Spring, and dry and hot summer months (with temperatures frequently exceeding 30° C). Rainfall in the region varies spatially, typically decreasing with increasing distance from the Southern Alps (KSL, 2025).

Site recorded data indicates a mean annual rainfall that ranges from 441 to 506 mm depending on elevation. Rainfall remains broadly constant throughout the year ranging from 30 – 50 mm per month except for the months of July and August in which rainfall is notably lower. Dry spells of up to two weeks are also common in these months. Evapotranspiration is strongly seasonal with the reported long-term average ranging from approximately 6 mm in July to 136 mm in January. Due to evapotranspiration exceeding rainfall in the summer months, with the exception of storm events, runoff typically only occurs in the winter months (Santana, 2024).

Rainfall water quality is required as an input to the water and load balance model (MWM, 2025b). Further climatic information is available in Rekker (2025).

1.5 Rehabilitation

The engineered landform will be progressively rehabilitated with compacted batter slopes, brown rock and soil to support the BOGP vegetation requirements. Previously work has indicated that net percolation (i.e., % of rainfall) into the various engineered landforms will be 20-50% (MWM, 2025c). The geochemical model uses 20% as a conservative estimate of net percolation rates.

1.6 Report Objectives

The purpose of this report is to present the geochemical modelling undertaken to estimate seepage water quality for the Shepherds ELF, SRX ELF, Come in Time (CIT) Backfill, West ELF, and Shepherds Creek (SCK) Fill during operations and into the active closure and post closure phases of the BOGP. The objectives of this report are as follows:

Develop a conceptual geochemical model for each ELF.

Page 4 MWM-S003-Rev2

- Estimate water quality seepage from the ELFs during operations and into the active closure and post closure phases of the BOGP.
- Provide recommendations for management of ELF seepage based on model results.

Page 5 MWM-S003-Rev2

2 LITERATURE REVIEW AND MODEL ASSUMPTIONS

This section reviews previous studies to support the development of a conceptual geochemical modelling process for the proposed ELFs at the BOGP.

2.1 Analogue Site - Macraes

Analogue sites with comparable lithologies, mineralisation, and alteration styles are useful analogue sites to understand / identify potential geoenvironmental hazards and subsequent effects on water quality.

The Macraes Gold Mine (Macraes), near Macraes Flat, Otago has been operating for over 30 years and the gold deposit is also associated with the TZ3 / TZ4 boundary within the Otago Schist. A large quantity of publicly available information is available on Macraes.

Gold mineralisation is developed within TZ3 Otago Schist within the Hyde - Macraes Shear Zone. The Macraes Gold Project has mined portions of the HMSZ via open pit and underground methods for a period in excess of 30 years (since 1990) and continues to the present day. MWM consider the geochemistry of mineralised and unmineralised rock at the Macraes operation to be analogous to BOGP. The site therefore provides an appropriate analogue site to consider geoenvironmental hazards.

2.1.1 Sulfur Content

Sulfur content is a key consideration as to whether an analogue site is suitable as this represents the potential source hazard for acid and metalliferous drainage (AMD).

Analysis of total S data for tailings and waste rock at Macraes is comparable to BOGP with average waste rock being ~ 0.11 to 10.16 wt% S at Macraes (Figure 2) and ~ 0.094 wt% S at BOGP (Figure 3). Data presented by MWM (2024) as part of the MP4 resource consent application (RM24.184) for Macraes indicates that average sulfur for the waste rock samples ranged from 0.11 to 0.16 wt%, which agrees with Weightman (2020).




Figure 2. Sulfur content for Macraes waste rock.

Source: Weightman (2020). Note: Where Maximum Potential Acidity (MPA) = wt% S x 30.6 (units in kg H₂SO₄/t); wt% S can be determined by conversion from MPA (in wt% CaCO₃/t equivalence). Assumption that a MPA of 0.4 wt% CaCO₃ is the average of the data provided. ANC = acid neutralisation capacity. If the ANC > MPA then the rock is non-acid forming.

Page 6 MWM-S003-Rev2




Figure 3. Total sulfur distribution curve for BOGP materials.

Source: MWM (2025a)

Assumption #1: Macraes is a suitable analogue site for potential water quality effects from waste rock at the BOGP due to similar sulfur content.

2.1.2 Waste Rock Stack Seepage

Data provided by Golder (2011a) for silt ponds, located at the toe of WRS at Macraes, indicates elevated sulfate in seepage waters (Table 1). Such data provides an indication of the risks to surface waters associated with this mine domain. The assessment by Golder in 2011 for Macraes did not consider the risks associated with nitrogenous compounds. Recent work in 2020 identified that nitrate can be elevated up to 10.5 mg/L in WRS seepage (OceanaGold, 2020).

Table 1. WRS silt pond seepage water quality from Macraes Gold Mine. From Golder (2011a).

PARAMETER (1)	DEEPDELL NORTH	DEEPDELL SOUTH	BATTERY CREEK	NORTHERN GULLY	FRASERS WEST (NBWR)	MURPHYS CREEK	BACK ROAD	AVERAGE
Arsenic	0.011	0.00001	0.00001	0.001	0.001	0.00001	0.00001	0.0016
Sulfate	38.6	15.4	1,200	2,300	1,500	1,320	2,200	1084
Cyanidewad	0.00001	0.00001	0.00001	0.013	0.00001	0.00001	0.00001	0.0016
Copper	0.001	0.00001	0.00001	0.003	0.001	0.001	0.002	0.0010
Iron	0.170	0.00001	0.00001	0.93	0.42	0.52	0.91	0.3734
Lead	0.001	0.00001	0.00001	0.00001	0.00001	0.00001	0.00001	0.0001
Sodium	16	10.8	36	57.7	26.2	33	56.4	29.81
Potassium	5.5	1.89	10	12	5.47	6.69	11.7	6.72
Calcium	68.5	40.2	290	434	199	250	425	215.5
Magnesium	14.5	7.7	200	360	165	204	352	164.7
Zinc	0.00001	0.00001	0.00001	0.032	0.015	0.018	0.032	0.012
Chloride	11.5	7.1	10	10.2	4.69	6.03	9.99	7.49

^{1. -} All values presented in units of mg/L

Page 7 MWM-S003-Rev2

2.2 Macraes WRS Seepage Water Quality: Height Relationship

Babbage (2019) completed an assessment of waste rock stack (WRS) seepage water quality at Macraes as part of the Oceana Gold (New Zealand) Limited Application RM20.024 to the Otago Regional Council (ORC).

Data are available for Ca, Mg, and SO₄ with SO₄ data being presented below in Figure 4. Babbage (2019) assessed various physical parameters of each WRS including WRS footprint, volume of waste rock, and height of the WRS. Analysis indicated there is a relationship between average height of the WRS, its age, and sulfate concentrations in WRS seepage (Figure 5).

Sulfate concentrations are a useful guide to other water quality effects and often very good correlations exist between sulfate, EC ⁶, and other potential constituents of concern (PCOC) such that PCOC concentrations can be forecast from sulfate concentration.




Figure 4. WRS seepage sulfate concentrations, Macraes Gold Mine.

Source: Babbage (2019): Available: https://www.orc.govt.nz/consents-and-compliance/current-notified-applications/oceana-gold-new-zealand-limited-rm20024/




Figure 5. WRS seepage sulfate concentrations as a function of WRS age and average WRS height. Source: Babbage (2019): Available: https://www.orc.govt.nz/consents-and-compliance/current-notified-applications/oceana-gold-new-zealand-limited-rm20024/

Page 8 MWM-S003-Rev2

⁶ Electrical conductivity

Data presented in the Babbage (2019) report indicates that the average height of WRS at Macraes (in 2019) ranged from 15 m to 37 m with higher WRS generating higher sulfate concentrations. WRS at Macraes are mostly built using traditional WRS construction methods (e.g., tipheads > 10 - 20 m in height that can create grainsize segregation).

Recent work MWM (2024b) demonstrated a relationship between average WRS height and sulfate concentration using similar data sets to Babbage (2019).




Figure 6. Average WRS height versus maximum sulfate concentrations at Macraes.

Source: Mine Waste Management (2024b): https://www.orc.govt.nz/consents-and-compliance/current-notified-applications/oceana-gold-new-zealand-limited-rm24184/

Given that the source hazard (e.g., total sulfur content) at BOGP is comparable to Macraes, and rock properties are similar (non-acid forming) it is reasonable to assume that if waste rocks stacks are built at BOGP then sulfate concentrations would be a function of the WRS average height and have similar concentrations to those reported at Macraes (Figure 6). However, the BOGP propose to construct ELFs to minimise the advective flux of oxygen along coarse basal layers created by end-tipping and subsequent grainsize segregation.

Assumption #2: WRS seepage water quality at BOGP can be forecast as a function of WRS height using published empirical data from Macraes.

2.3 Concentration Versus Flow

Previous work (e.g., Mackenzie, 2010; Weber et al., 2015) has demonstrated that although contaminant concentration in seepage from waste rock stacks can remain approximately constant irrespective of flow rate, with increasing flow, the contaminant load increases proportional to flow rate (Figure 7, Figure 8). This demonstrates that the waste rock has a large reservoir of stored oxidation products that is mobilised by greater water flow through the materials driving an approximate constant concentration.

Page 9 MWM-S003-Rev2




Figure 7. Fanny Creek Side Cast, Island Block Mine, West Coast

Source: Mackenzie (2010).




Figure 8. Globe Progress Mine, West Coast

Source: Weber et al. (2015)

Assessment of flow and quality data for the Frasers West WRS (FWWRS) at Macraes (MWM 6) indicates that the key driver of sulfate load is flow rate, with minor variance in sulfate concentration (Figure 9). Again this supports modelling constant concentration (for daily time steps in any model).




Figure 9. FWWRS seepage rates and interpolated sulfate concentration data.

Source: MWM (2024b).

Page 10 MWM-S003-Rev2

Hence, numerical modelling of the proposed ELFs at the proposed BOGP will use constant concentration, with the assumption that each unit of waste rock contains a reservoir of stored oxidation products that will be mobilised by increasing flow. Decline in concentration is a function of the exhaustion of sulfides in any oxidising materials during the operational and active post closure phases of the project.

Assumption #3: WRS seepage water quality remains constant for daily time-step modelling.

2.4 Oxygen Ingress

Generally, WRS represent 60 - 80% of a site's AMD contaminant load (INAP, 2020; 2024) if the AMD source hazard is not managed appropriately. International case studies are available (e.g., Weber et al., 2017) to demonstrate the high proportion of AMD associated with waste rock domains. Hence there is a strong driver to incorporate waste rock into engineered landforms that address the key principles of AMD source control: Prevention and Minimisation.

2.4.1 Waste Rock Stacks

Waste rock that is end dumped in high lifts (>4-6 m in height) and the associated kinetic energy can result in grainsize segregation and the development of alternating coarse-textured and fine-textured bedding planes of poorly graded and well sorted material with high vertical airflow capacity (e.g., Fala et al., 2003; Wilson, 2008). This also results in an overall downward coarser grading providing higher airflow capacity deeper in the facility. In addition, the fall of rocks / cobbles from the end-tipped / dozer pushed material results in the development of a coarse basal layer with high lateral airflow capacity that provides oxygen ingress pathways into the core of the waste rock stack (WRS).

The dominant process for oxygen flux is by the advective and convective flow of oxygen (temperature differences, barometric pressure differences) along coarser waste rock layers that form within poorly constructed WRS. Work completed by Brown et al. (2014) has demonstrated that in a poorly constructed WRS, advection accounts for ~90% of oxygen ingress, and that diffusion of oxygen accounts for 10%.

Hence, a key control to prevent sulfide mineral oxidation and minimise the effects on seepage waters from WRS is to prevent the advective ingress of oxygen.

2.4.2 Engineered Landforms

International research (INAP, 2020; 2024) has demonstrated that one of the most effective methods to minimise advective ingress of oxygen into WRSs is to minimise the height of the tiphead to <4 - 6 m and ensure that each lift has a compacted engineered surface, which reduces the size of the advective cell (both vertically and horizontally into the WRS). Reducing oxygen ingress reduces sulfide mineral oxidation and hence the risks associated with AMD.

INAP (2024) note that an "Engineered Fill' approach "allows for the ability to more accurately model and predict O2 ingress and the volume and quality of recoverable seepage requiring treatment over time". This 'Engineered Fill' approach manages AMD "risks through implementation of source control, progressive reclamation, and cover systems, which allows for opportunities to move from active to passive water treatment over time thereby reducing asset liability, and likelihood of in-perpetuity management" (INAP, 2024).

Further details on ELF construction methods for BOGP are provided in MWM (2025f).

Page 11 MWM-S003-Rev2

2.4.3 Model Development

For BOGP modelling purposes, it is assumed that oxygen flux will be limited horizontally through the ELF batter slopes by controlling the advective flux of oxygen using appropriate engineering controls (e.g., lifts heights < 5 m). For modelling purposes, the design assumptions are:

2.4.3.1 20 m Wide ELF Oxidation Zones (ELF – 20 m Model)

- 20 m horizontally into each ELF lift will be oxidising (aligns with previous New Zealand case studies that show 5 - 15 m can be achieved.
- Based on an angle of repose of 37°, the vertical oxidising distance is 15 m (with 20 m used horizontally for modelling purposes).
- On flat surfaces (e.g., running lifts) the depth is 15 m top account for better compaction of materials due to vehicle movements. A graphical representation of the outer oxidising zones is shown in Figure 10.

2.4.3.2 <u>10 m Wide ELF Oxidation Zones (ELF – 10 m Model)</u>

- 10 m horizontally into each ELF lift will be oxidising (aligns with previous New Zealand case studies that show 5-15 m can be achieved but is considered an optimistic lateral distance).
- Based on an angle of repose of 37°, the vertical oxidising distance is 8 m (with 10 m used horizontally for modelling purposes).
- On flat surfaces (e.g., running lifts) the depth is 8 m.
- This scenario would reduce the volume of material exposed to oxidation.




Figure 10. Graphic representation of the outer rim and horizontal ingress of oxygen at 20 m.

A nominal value of 20 m introduces a safety factor for batter slopes compared to data from other sites in New Zealand. This is a key design criterion for the project. However:

Detailed design for the ELFs is required to demonstrate how this will be achieved.

Page 12 MWM-S003-Rev2

- Performance monitoring during construction is required to confirm that these design criteria are being met.
- Geochemical models should be adjusted to the future measured oxidation depth and oxygen flux (through the cover system).

Assumption #4 – That ELF design and construction (including cover system) will limit oxygen ingress to a depth of 20 m horizontally and 15 m vertically once the ELF is constructed (and rehabilitation is completed).

2.5 Scaling Factors

Many projects rely on a first principles approach, scaling laboratory data to the field (e.g., Kempton, 2012; Linklater et al., 2017) to determine WRS water quality. Such analyses consider physicochemical issues such as moisture content, particle size, temperature, mobility of PCOC, oxygen concentrations, and solute attenuation (e.g., precipitation). Scaling lab data to the field can introduce several uncertainties that influence model results.

For the BOGP WRS / ELF geochemical models, the modelling process is simplified by relying on appropriate analogue empirical data from Macraes (e.g., Figure 6) with minor geochemical adjustments:

- It is expected that parts of the ELF contain materials that are effectively unreactive and do not contribute to the contaminant load or water chemistry. Price (1997) notes that >75% of the mass in a WRS occurs as coarse particles in which the mineralogy is almost entirely occluded from oxygen and water with drainage chemistry being controlled by a relatively small portion of the mass which is finer grained particles. Malmström et al. (2000) noted that ~65% of the water in a waste rock stack was mobile and 35% was immobile at the Aitik Copper mine, Sweden. At the Island Copper Mine (Vancouver), Lopez et al. (1997) notes that only 42% of the total area of the pile contributes to flow. Such studies indicate that 35 58% of water interacting in a waste rock stack may be immobile and will not contribute to drainage water chemistry.
- The assumed non-reactive portion of the waste rock used in the models presented in this report is 90%. This is assuming that coarser material will decrease the amount of minerals or sulfides reacting with water. The water passing through the reactive portion is assumed to fully react. Consequently, this 10% reactive fraction is considered fully available for the release of stored oxidation products and long-term solute generation.
- A scaling factor was applied for the long-term generation of solutes that were obtained from the column leach tests to calibrate using analogue empirical data.
- Scaling of sulfate for the reactive fraction (a key indicator of AMD and poor water quality) is derived from empirical data from Macraes, which provides the ability to scale other PCOC based on column leach test data correlations for the project area. This resulted in a general scaling factor (from laboratory to field)
- This general scaling factor affects sulfate and elements associated with the long-term release rates.
- To align lab results with analogue data from Macraes, a release rate adjustment factor of 0.8575
 was applied to reactive oxidising materials (e.g., 10% of the materials in the WRS). These

Page 13 MWM-S003-Rev2

adjustments allowed the model to simulate realistic peak sulfate concentrations for a traditional WRS (e.g., ~6,200 mg/L for Shepherds WRS).

- Linklater et al. (2017) applied several scaling factors to WRS materials, including surface area correction, fraction flushed by contact water, temperature correction, and oxygen availability. Combined, these factors result in an overall multiplier of 0.012, which is nearly two orders of magnitude lower than full reactivity. In our case, the adjustment is approximately one order of magnitude; 0.1 for short-term release, multiplied by an additional 0.8575 for long-term release, yielding an overall factor of 0.08575 for the long-term release.
- PHREEQC modelling (Parkhurst & Appelo, 2013) was conducted to consider solubility control for some solutes (e.g., precipitation).

Assumption #5 – The scaling approach using CLT data to forecast sulfate and other PCOC is appropriate to understand geochemical risks for the engineered landforms.

2.6 Nitrogenous Compounds

This section identifies the source hazards associated with the use of ANFO for blasting and the potential effects on ELF Seepage waters. Derivation of nitrate loads is complicated for modelling as geochemical test work is undertaken on drillcore that has not been blasted. Hence a reliance on literature is required.

2.6.1 Literature Review

Nitrogenous compounds from waste rock in mining operations are often a byproduct of blasting agents, such as ammonium nitrate-fuel oil (ANFO), used during extraction. These compounds can leach into surrounding water systems contributing to elevated levels of nitrate and ammonia in nearby groundwater and surface water. Data presented by OceanaGold (2020) indicates that nitrate can be 10.5 mg/L in WRS ponds at Macraes.

As noted by Navarro-Valdivia et al. (2023) pit lakes can also be elevated in nitrogenous compounds due to the presence of blasting residues, with nitrate nitrogen concentrations peaking in the Golden Bar Pit Lake at 30 mg/L due to an initial nitrate load of 400 kg yet steadily decreases at 20-30% per year due to biogeochemical processes. Navarro-Valdivia et al. (2023) noted that the quantity of nitrogen as NH_4NO_3 was estimated to be 5.35 g/m^2 once the pit lake started to fill.

Navarro-Valdivia et al. (2024) indicated that there was a poor relationship between sulfate and nitrate in WRS seepage at Macraes ($R^2 = 0.43$) and that the median nitrate nitrogen value was 12.6 mg/L (equivalent to a concentration of ~56 mg/L nitrate).

Dockrey et al. (2015) report nitrate nitrogen (NO_3 -N) concentrations in coal waste rock seepages from 5 to over 100 mg/L depending on the size and age of the waste rock dump. Bailey et al. (2013) reports that measured NO_3 in seepage outflows at a diamond mine were 2,000 mg/L. Schmidt and Moffett (1979) report that concentrations of NO_3 - in mine effluent from uranium mines ranged from 60 to 80 mg/L.

Weber et al. (2021) report a range of nitrate concentrations (Figure 11) with nitrate concentrations of 68 mg/L for drainage from a waste rock dump (WRS) for an orogenic gold mine.

Page 14 MWM-S003-Rev2

Mine Type	Mine Domain	Nitrate Concentrations	
		mg/L as NO ₃	
Iron Ore	TSF	220	
Diamond	WRD - test pile	2000	
Diamond	WRD - test pile	4000	
Orogenic Gold	WRD	68	
Epithermal Gold	Low Grade Ore Stockpiles	0.14	
Volcanic Massive Sulfide	Underground	285	
Volcanic Massive Sulfide	Underground	5	
Porphyry Copper	WRD	<2	
Diamond	WRD	90 -230	
Coal Mine	WRD Catchment Drainage	<1	
Platinum	Pit	377	
Platinum	WRD	440	

Figure 11. Nitrate concentrations from various studies, mine type, and mine domains *Source: Weber et al. (2021).*

MWM (2024a) assessed nitrate data for WRS at Macraes. Available data suggests maximum NO₃-N concentrations could be up to 35-40 mg/L (Figure 12) and that nitrate-N can be \sim 2.5 to \sim 22 mg/kg in blasted waste rock at Macraes (Figure 13).




Figure 12. Sulfate versus nitrate-N concentrations for Macraes WRS.

Note: X axis is sulfate in mg/L Source: MWM (2024a): Appendix I.

Page 15 MWM-S003-Rev2




Figure 13. Shake flask extraction data for blasted backfill at Macraes.

Source: MWM (2024a).

Studies have been completed at the Argyle Diamond Mine, Western Australia on nitrate effects due to the use of ANFO (Borden et al., 2022) with nitrate concentrations in the ICI WRS seep reaching a mean peak of 300 mg/L in 2004 to 2007 declining to 170 mg/L between 2017 and 2020. The authors note that these mean values do not capture the full variability in nitrate concentration within each year, however a strong declining concentration was observed over the 20-year monitoring period. Data indicated that dry season nitrate concentrations were higher than wet season nitrate concentrations (Figure 14). Borden et al. (2022) note that:

- The higher concentrations and loads observed prior to 2015 (Figure 15) were a function of open
 pit mining and a greater quantity of ANFO being used with peak nitrate concentrations in WRS
 seeps coinciding with peak waste rock production in 1999 to 2005.
- Peaks nitrate loads during operations are a function of rapid flushing of high permeability zones.
- Long term nitrate loads are a function of finer grained low permeability zones that are not flushed by high rainfall events.
- Data for the WRS seeps suggests that toe seepage water quality will meet chronic nitrate guideline requirements (2.4 mg/L) in two to three decades.

These data suggest that for Argyle:

- Nitrate concentrations did not start to decrease till 2015, a decade after open pit operations ceased.
- Based on 20 years of monitoring data the effects of elevated nitrates are expected for another
 two to three decades. This suggests the effects of nitrate could last for 50 years once opencut
 mining ceases.

Page 16 MWM-S003-Rev2




Figure 14. Nitrate concentrations for the ICI WRS seep (Argyle Diamond Mine). *Source: Borden et al. (2022).*




Figure 15. Nitrate concentrations for Gap Dam, the process circuit, and East Wesley Seep – Argyle Diamond Mine.

Source: Borden et al. (2022).

Elevated nitrate in ELF seepage is expected to last for decades, unlike the effects of AMD which are expected to last for centuries. For instance, (Mahmood et al. (2017) notes that, as an example, a 100 m high dump, placed at an average volumetric water content of 10% and flushed at a net percolation rate of 750 mm/year would take approximately 13 years to release most of the initial nitrate within the

Page 17 MWM-S003-Rev2

dump. Data for Argyle suggest that 50 years is a reasonable timeframe to meet water quality criteria (e.g., nitrate-N concentrations of 2.4 mg/L).

2.6.2 Model Inputs

Given that the average height of the Shepherds ELF is nearly twice that of the highest WRS at Macraes, it is assumed that the peak concentration will also be roughly double. Based on this assumption, a peak nitrate-N concentration of ~80 mg/L is expected for the Shepherds ELF. For modelling purposes, it is assumed that 90% of this nitrate-N is mobilised over ~50 years for all structures, although the time to peak concentration can extend this period once the tallest parts of the ELF are contributing load.

A nitrogen content (as NH₄NO₃) of 16.6 mg/kg was assigned to reactive waste rock within each ELF to enable the peak nitrate-N concentrations of 80 mg/L to occur. This load is comparable to the data available at Macraes (Figure 13).

Assumption #6 – That ELF seepage waters will be elevated in nitrate for many decades and that the peak concentration is expected to be ~ 80 mg NO₃-N/L in the Shepherds ELF seepage waters.

Assumption #7 – That model data suggests the initial load of nitrogen (NH₄NO₃) is 16.6 mg/kg.

Assumption #8 – That 90% of nitrogen is mobilised over ~50 years once the tallest part of the structure starts contributing load.

Page 18 MWM-S003-Rev2

3 ELF CONCEPTUAL GEOCHEMICAL MODEL

This section explains the conceptual geochemical models for the proposed BOGP ELFs.

3.1 Engineered Landform Summary: RAS, SRX, and WELF

Overburden waste rock from the RAS deposit will be stored in the Shepherds ELF (Figure 16) and in the West ELF (WELF), and overburden from the SRX Pit will be stored in the SRX ELF (Figure 17):

- For the Shepherds ELF, the selected storage area, located downstream of the TSF, avoids terrain constraints, minimises the risk of sterilising nearby satellite deposits and will also act as a buttress to enhance TSF stability while accommodating 103.6 million loose cubic metres (LCM) of waste, including 3.2 million LCM from the TSF dam (MCL, 2024). The design includes a 12% contingency for changes in swell or compaction factors based on site-specific parameters.
- For the SRX ELF, the selected storage area is on top of the SRE Pit and is located upstream
 of the SRX pit to minimise the risk of sterilising nearby satellite deposits




Figure 16. Shepherds ELF.

Reference: MGL (2024).

Page 19 MWM-S003-Rev2




Figure 17. SRX Pit and SRX ELF

Source: MGL (2024).

Waste landform sequencing has been undertaken based on the assumption that arsenic concentrations are higher in the ore host rock (TZ4 and RSSZ) and for precautionary reasons it is planned to be encapsulated and capped with lower arsenic waste rock (TZ3). A base layer and encapsulating layer of inert material is typically required, with a core of non-inert material. For this reason, the ELF has a base layer of 3 metres of TZ3 material. The TSF dam embankment will also only consist of TZ3 material. Santana (2024) proposes that a 20 m thick low sulfur capping layer of TZ3 materials will encapsulate the ELF.

Mine schedules for RAS and SRX are shown in Table 2 and Table 3.

Table 2. RAS Pit mine schedule.

COMPONENT	TOTAL ROCK MINED	TOTAL WASTE	TZ3 TONNES	TZ4 TONNES	SOIL	ORE
Unit	(kt)	(kt)	(kt)	(kt)	(kt)	(kt)
Year						
-2	10,200	10,200	9,417	0	783	0
-1	30,572	30,363	29,967	149	247	209
1	25,859	24,437	20,456	3,139	842	1,422
2	24,612	21,438	16,804	4,344	291	3,173
3	24,493	22,680	19,717	2,815	148	1,813
4	24,300	23,060	20,939	1,613	508	1,240
5	24,300	24,007	22,636	1,339	33	293
6	24,267	21,880	19,530	2,184	166	2,387
7	23,112	21,575	19,401	2,171	3	1,537
8	2,258	1,355	1,019	336	0	902
Total	213,972	200,996	179,886	18,089	3,021	12,976

Reference: Santana, 2024

Page 20 MWM-S003-Rev2

Table 3. SRX Pit mine schedule.

COMPONENT	TOTAL ROCK MINED	TOTAL WASTE	TOTAL TZ3	TOTAL TZ4	TOTAL SOIL MINED	ROM MINED (>0.30g/t Au)
Unit	(kt)		(kt)	(kt)	(kt)	(kt)
Months						
1	209	80	33	47	80	0
2	209	121	79	42	51	15
3	209	105	84	21	49	26
4	309	204	185	19	61	34
5	350	237	209	28	36	47
6	350	257	253	4	59	9
7	350	224	202	22	30	75
8	350	228	214	14	64	32
9	350	255	211	44	3	84
10	350	290	277	13	30	27
11	350	216	199	17	44	73
12	350	284	247	37	3	60
13	350	299	289	10	10	38
14	350	191	162	29	54	95
15	350	269	227	42	0	70
16	350	299	292	7	2	47
17	350	239	211	28	28	82
18	350	272	234	38	0	74
19	350	242	226	16	11	94
20	350	235	205	30	10	99
21	350	232	212	20	0	111
22	350	167	104	63	0	164
23	108	35	21	14	0	69
Total	7,344	4,981	4,377	606	625	1,428

Reference: Santana, 2024

3.2 Backfill

Two pit backfills will be created:

- Waste rock will be placed in the SRE pit as backfill as part of constructing the SRX ELF. It is
 assumed the quality of materials is negligible and the ELF seepage water quality will be
 dominated by the SRX ELF.
- Waste rock will be used to backfill the CIT Pit to provide a more natural surface for mine closure.
 This will create rock that will be saturated by groundwater and also an ELF that sits above this.
 The CIT ELF model addresses these components.

No mine plan was provided for CIT, however, total estimated quantities are provided in Table 4.

Table 4. CIT Pit material quantities.

ORE (kt)	SOIL (kt)	TZ3 (kt)	TZ4 (kt)	TOTAL ROCK MINED (kt)
700	475	2,550	850	4,575

Page 21 MWM-S003-Rev2

3.3 Shepherds Creek Fill Area

A platform composed of TZ3 material will be placed in Shepherds Creek to serve as a foundation for the processing plant area. The volume of fill used is approximately 1.1 Mm³, which is considered significant, as it is comparable to the volume of the Come in Time backfill (1.5 Mm³). Given its scale, the fill is deemed geochemically relevant and is therefore included in the water and load balance model (WLBM) as an additional waste rock domain. The corresponding material volume, tonnage, and area are shown in Table 5.

Table 5. CIT Pit material quantities.

VOLUME (m3)	TONNAGE (kt)	AREA (kt)
1,109,758	2,264	2,550




Figure 18. Shepherds Creek Fill Area Fill location.

Source: MGL (2025)

3.4 Cover System

The ELF will be progressively rehabilitated with compacted batter slopes, brown rock and soil to support the BOGP vegetation requirements. Previously work has indicated that net percolation (i.e., % of rainfall) into the various engineered landforms will be 20-50% (MWM, 2025c).

The impact of the landform, including the cover systems, on net percolation (NP) is expected to be minimal due to the high surface permeability of the materials. Both the ELF and TSF are predominantly flat or north-facing, which will result in similar potential evapotranspiration (PE). However, the steeper slopes of the ELF are likely to generate more runoff than the flatter TSF, potentially leading to slightly

Page 22 MWM-S003-Rev2

lower NP for the ELF. Nevertheless, this difference is not expected to be significant, as surface permeability is likely to remain high.

Based on the findings in the report, the estimated baseline NP post-closure of 20% is used for modelling purposes.

3.5 Water Soluble PCOC

Most rocks, following blasting contain stored water soluble PCOC that can be mobilised by the flow of water through these materials (e.g., net percolation). PCOC include nitrogenous compounds derived from blasting residues, and stored oxidation products (SOP) generated by sulfide mineral oxidation or due to a natural mineral dissolution by percolating waters (e.g., gypsum).

Two processes are considered in the model:

- SOP Dissolution: This process involves the release of solutes through the dissolution of readily available soluble minerals such as anglesite. The release of solutes occurs only in the short term due to flushing of these PCOC by net percolation through the ELF.
- **Oxidation:** This refers to the oxidation of sulfides in zones of the ELF that have oxygen available, resulting in the generation of sulfate and associated solutes over the long term.

3.6 Oxygen Ingress

The WRS base case scenario is modelled with no oxygen exclusion with the assumption that all materials generate a similar amount of sulfate from water soluble PCOC, which is then ongoing from sulfide mineral oxidation.

Scenarios are run for the three engineered landforms (Shepherds, SRX, WELF) where the depth of oxidation is limited to 10 m and 20 m depth into the ELF (as explained in Section 2.4.3), and for the CIT backfill as well. From a modelling perspective, this does not affect the presence of water soluble PCOC.

3.7 Conceptual Domain Models

Four key waste rock disposal domains are proposed for the BOGP: Shepherds ELF, SRX ELF, West ELF, and CIT backfill. While they share common characteristics, they differ in material quantities, dimensions, and area. Waste rock fill is also used within Shepherds Creek as fill for the BOGP infrastructure area (e.g., processing plant). Given the quantities of materials required this has also been modelled to understand seepage water quality.

Seepage is generated from rainfall infiltration, with net percolation assumed to be 20%. Consequently, average ELF seepage rates depend on the area of each ELF and the assumed net percolation. The toe seepage flow rate is calculated in the GoldSim water balance, based on the assumption that seepage flow rates drive the load, independent of concentration. That is, while seepage flow rates may vary, the concentration is expected to remain constant (see Section 2.3).

It is assumed that the ELFs will have an oxidising outer rim composed of the geological unit TZ3, while the inner core will consist of TZ3 and TZ4. The inner material will not oxidise but will release short-term SOP, which will be available for dissolution upon interaction with infiltrating rainfall. The outer rim undergoes both ongoing oxidation of minerals (or long-term release) and SOP dissolution. Quantification of the SOP are derived from column leach tests and are detailed in Section 4.2.

Page 23 MWM-S003-Rev2

Since each ELF has different dimensions, the outer rim represents a different fraction of the total volume of each ELF. Given that the Shepherds ELF is the largest, its proportion differs accordingly. CIT is assumed to have similar proportions as SRX, as they both have similar material quantities.

The core of the ELF is assumed to experience SOP dissolution without oxidation (noting that the SOP is derived from ~20 weeks of data from the column leach test ⁷), while the outer rim (i.e., the oxidising zone) undergoes both ongoing oxidation of sulfide minerals and SOP dissolution. For modelling purposes, it is also assumed that TZ4 is located within the core of the ELF, meaning only TZ3 is present and therefore oxidises in the outer rim.

Modelling was based on earlier material quantity estimates for SRX and Shepherds, as shown in Table 6. These estimates differ slightly from those provided in the pre-feasibility study (PFS) completed in late 2024 (MGL, 2024). However, these differences are not considered significant in assessing potential effects on water quality.

PIT/DOMAIN	MATERIAL	QUANTITY (KT)
	TZ3	4,377
SRX	TZ4	606
	TZ3+TZ4	4,983
	TZ3	179,886
Shepherds	TZ4	18,089
	TZ3+TZ4	197,975
	TZ3	2,550
CIT	TZ4	850
	TZ3+TZ4	3,400
West ELF	TZ3	10,732
SCK Fill	TZ3	2,264

Table 6. Material quantities (excluding soil).

Soil volumes were not included in the model, as the interaction of water with soils, which are essentially weathered rock, represents baseline conditions. Furthermore, soil is intended for use as a cover material for the ELFs. Consequently, the material quantity assessment includes only TZ3 and TZ4, explicitly excluding soil from the calculations.

3.7.1 Shepherds ELF

The Shepherds ELF contains 197,975 kt of waste rock, being primarily composed of TZ3 (179,886 kt, representing the 90.86% of the material), and a minor part of TZ4 (18,089 kt, or 9.14% of the material). Based on topographical differences between the designed ELF surface and the base topography, it was determined that the outer rim of the ELF accounts for:

- ~18.62% of the material for a 20-m oxidising rim (and 15 m vertically).
- ~9.60% for a 10-m oxidising rim (and 8 m vertically).

Page 24 MWM-S003-Rev2

Ongoing data collection from the CLT that will be run for 12 months will validate these results.

The area of the Shepherds ELF is approximately 115 Ha. Assuming a net percolation rate of 20%, the average seepage is estimated at ~3.7 L/s.




Figure 19. Conceptual (and schematic) water balance and material distribution for the Shepherds ELF.

A distinct feature of the Shepherds ELF is that it serves as the embankment for the TSF. However, seepage from the TSF will not interact with the waste rock in the Shepherds ELF, as it will be captured by an underdrain and will be passed through the ELF. It is expected that these seepage paths mix at the Shepherds Seepage Pond. This will reduce the PCOC load mobilised from the Shepherds ELF.

3.7.2 SRX ELF

The SRX ELF contains 4,984 kt of waste rock, being primarily composed of TZ3 (4,378 kt or 87.84% of the material) and a minor presence of TZ4 (606 kt or 12.15%). Based on topographical differences between the designed ELF surface and the base topography, it was determined that the outer rim of the ELF accounts for:

- ~58.98% of the material for a 20-m oxidising rim (and 15 m vertically).
- ~33.77% for a 10-m oxidising rim (and 8 m vertically).

The area of the SRX ELF is approximately 15.6 Ha. Assuming a net percolation rate of 20%, the average seepage is estimated at ~0.5 L/s.




Figure 20. Conceptual (and schematic) water balance and material distribution for the SRX ELF.

Page 25 MWM-S003-Rev2

3.7.3 West ELF

The WELF contains 10,732 kt of waste rock, composed entirely of TZ3 material. Assuming similar proportions between outer and inner waste rock as those calculated for SRX, the following distribution is estimated.

- ~58.98% of the material for a 20-m oxidising rim (and 15 m vertically), which represents 6,329
- ~33.77% for a 10-m oxidising rim (and 8 m vertically), which represents 3,624 kt
- The area of the WELF is approximately 17.5 Ha. Assuming a net percolation rate of 20%, the average seepage is estimated at 0.56 L/s. The conceptual and schematic water balance and material distribution for this domain are shown in Figure 21.




Figure 21. Conceptual (and schematic) water balance and material distribution for the WELF.

3.7.4 CIT Backfill

Unlike the ELFs, the CIT backfill consists of waste rock being backfilled into the CIT Pit void. It is assumed that once the material is backfilled, its pores will be filled by two water sources: infiltration from rainfall through the waste rock and groundwater inflow from the pit walls. When this pore water reaches the pit's overflow level (~503 mRL), it will emerge through the waste rock as seepage.

Below 510 mRL ⁸, the pit void has a volume of 922,930 m³. Assuming a backfill density of 2.16 t/m³, the total capacity is up to 1,993,529 t. The water volume capacity is estimated using a pore space fraction of 0.3, meaning 30% of the void volume is available for water.

Considering that the total waste rock mass (TZ3 and TZ4) in the CIT backfill of 3,400,000 t, approximately 58.6% of the material will be submerged. When this occurs, ongoing oxidation (or the long-term release of solutes) is assumed to cease. However, similar to the inner portions of the ELFs, the short-term release solutes (SOP) will remain available for dissolution.

A conceptual (and schematic) water balance is shown in Figure 22 for CIT Pit, while Figure 23 shows the amount of waste rock that is flooded with time (i.e., below the phreatic surface). This estimation is an output of the water balance model, due to its dependence on the current water level of the pore

-

Page 26 MWM-S003-Rev2

⁸ Note: 510 mRL is used as a rounded value, as pit dimension staging is provided in 10 m increments.

volume filling and is used in the model to quantify how much rock has ceased oxidising. This means that 42 months post closure the level of the pore water has reached the 510 mRL and no more material can be submerged.

The groundwater inflow rate is assumed to be 1 L/s when the pore volume is fully flooded at 510 mRL (Rekker and Dumont, 2025). Therefore, the total expected flow rate from the pit volume is approximately 1.88 L/s. However, the flow rates are calculated on the water balance and will vary day to day.

In this report, the estimated water quality corresponds exclusively to the 0.88 L/s component. However, in the water balance load model, the overall water quality from this backfill accounts for the mixing between seepage from the waste rock and groundwater inflow.




Figure 22. Conceptual (and schematic) water balance and material distribution for the Come in Time backfilled pit.




Figure 23. CIT cumulative backfill material below 510 mRL.

3.7.5 SCK Fill

The SCK Fill contains 2,264 kt of waste rock, composed entirely of TZ3 material. It is the smallest waste rock domain in terms of volume, area, and average height. Due to its elongated distribution along the creek, it is assumed that there will be no inner zone of low oxygen (e.g. sub-oxic conditions), and therefore the entire volume is expected to be reactive. The conceptual and schematic water balance and material distribution for this domain are shown in Figure 24.

Page 27 MWM-S003-Rev2




Figure 24. Conceptual (and schematic) water balance and material distribution for the SCK Fill.

Due to the presence of installations on top of the SCK Fill, the net percolation rate could potentially be lower than that assumed for the other waste rock domains. As a result, seepage may also be lower. However, the extent of this reduction is difficult to estimate. Therefore, for modelling purposes, it is assumed to behave similarly to the other domains. The average seepage flow rate is estimated at 0.36 L/s.

Page 28 MWM-S003-Rev2

4 ELF GEOCHEMICAL MODELLING PROCESS

This section describes the geochemical modelling process utilised to estimate base case water quality for a WRS and the estimated water quality for the proposed ELFs at BOGP.

4.1 Data Sources

Data was obtained from MWM (2025a,d) including:

- 388 samples tested for ABA where total sulfur is used for sulfur reservoir calculations.
- 349 samples for chemical composition by 4-acid digestion and ICP-MS.
- 6 Column Leach Tests to quantify the initial stored oxidation products and long-term oxidation rates.

4.2 Modelling Approach

4.2.1 Scenarios Definition

Three scenarios are developed in this report. The first scenario corresponds to a scenario where a WRS is constructed (mine domain is fully oxidising) rather than an ELF. This scenario was developed to calibrate the modelled seepage water quality against empirical data from Macraes, assuming full oxidation of materials.

Two scenarios were then developed to estimate the expected seepage water quality under ELF-specific construction conditions. The BOGP ELFs will be built in short lifts to minimize oxygen ingress, meaning that only the outer rim of the ELF will be exposed to oxidation. This oxidation rim inherits the oxidation properties and assumptions from the WRS scenario, while the inner portion follows short-term release dynamics, where solute release is driven by water flow rather than oxidation.

For the ELFs, two oxygen ingress scenarios are considered: 20 meters and 10 meters of horizontal oxygen ingress as explained in Section 2.4.3.

4.2.2 Sulfur Reservoir Estimation

The following modelling approach was undertaken to define the initial SOP reservoirs

- 1. Define the quantities of TZ3 and TZ4 waste rock (Section 3), e.g., for the Shepherds ELF these amounts are 179,886 kt and 18,089 kt respectively.
- 2. Define the non-reactive fraction that represents the fraction of the material that is not part of the reaction due to the heterogeneous nature of waste rock (further details are provided in Section 4.2.5). This is set to 0.9 meaning that 10% of the material is available for interaction, hence, for the Shepherds ELF:
- 3. Reactive TZ3 waste rock: 179,886 kt x 0.1 = 17,989 kt
- 4. Reactive TZ4 waste rock: 18,089 kt x 0.1 = 1,809 kt
- 5. Determine how much sulfur is present that will be considered reactive. This is calculated by using the total sulfur content of the TZ3 and TZ4 material, which have been determined by

Page 29 MWM-S003-Rev2

previous studies (MWM, 2025a) and is 0.088 wt% and 0.236 wt% respectively, therefore for the Shepherds ELF:

- o Total sulfur reservoir in TZ3: 0.088% x 17,989 kt = 15,830 t.
- o Total sulfur reservoir in TZ4: $0.236\% \times 1,809 \text{ kt } x = 4,269 \text{ t.}$
- 6. The following calculation was undertaken to determine the quantities of sulfate and sulfide sulfur to understand the initial load of stored oxidation products (i.e., short-term sulfate load) and sulfide, associated with the long-term release due to oxidation of sulfides.
- 7. The amount of initial sulfate sulfur load is determined by the amount released in the AMIRA columns up to week 20 (further details are provided in Section 4.2.6).
- 8. For TZ3 it was determined that the initial load (sulfur as sulfate) is on average 2.19% of the total sulfur. For TZ4, this was calculated as 0.73%. The following calculations are provided for the Shepherds ELF:
- 9. Total sulfate sulfur reservoir for TZ3: 2.19 wt% x 15,830 t = 347 t.
- 10. Total sulfate sulfur reservoir for TZ4: 0.73 wt% x 4,269 t = 31 t.
- 11. Therefore, sulfide sulfur for TZ3 is 15,483 t and for the TZ4 it is 4,238 t.
- 12. Note: Due to the large quantity of rock, TZ3 has the largest SOP load, by an order of magnitude.
- 13. Reservoir calculations are then undertaken for all scenarios (Traditional WRS, ELF 20 m model, ELF 10 m model) for the Shepherds ELF, SRX ELF, WELF, and CIT backfill and data are provided in the following tables. For the SCK Fill (Table 11) only the WRS scenario is presented, as it was assumed to be fully oxic. Note that the SOP (or short-term sulfate load reservoir) remains the same across all scenarios, as it is not dependent on oxygen availability. Hence, only the sulfide reservoirs are affected.

Table 7. Sulfur reservoir calculations for the Shepherds ELF.

SCENARIO	COMPONENT	TZ3	TZ4	TZ3+TZ4
Total Waste Rock	Waste Rock Quantity (kt)	179,886	18,089	197,975
	Reactive Waste Rock (kt)	17,989	1,809	19,798
Wests Deals Stark Con-	Sulfur reservoir (t)	15,830	4,269	20,099
Waste Rock Stack Case	S as Sulfides (t)	15,483	4,238	19,721
	S as SOP (t)	347	31	378
	Waste Rock in Outer Rim (20-m Ox) (kt)	36,866	0	36,866
	Reactive Outer Rim (kt)	3,687	0	3,687
ELF - 20 m model	Sulfur Reservoir in Outer Rim (t)	3,244	0	3,244
	S as Sulfides (t)	3,173	0	3,173
	S as SOP (t)	347	31	378
ELF - 10 m model	Waste Rock in Outer Rim (10-m Ox) (kt)	19,011	0	19,011

Page 30 MWM-S003-Rev2

SCENARIO	COMPONENT	TZ3	TZ4	TZ3+TZ4
	Reactive Outer Rim (kt)	1,901	0	1,901
	Sulfur Reservoir in Outer Rim (t)	1,673	0	1,673
	S as Sulfides (t)	1,636	0	1,636
	S as SOP (t)	347	31	378
	Table 8. Sulfur reservoir calcula	tions for the S	SRX ELF.	
SCENARIO	COMPONENT	TZ3	TZ4	TZ3+TZ4
Total Waste Rock	Waste Rock Quantity (kt)	4,378	606	4,984
	Reactive Waste Rock (kt)	438	61	498
Waste Rock	Sulfur reservoir (t)	385	143	528
Stack Case	S as Sulfides (t)	377	142	519
	S as SOP (t)	8.4	1.0	9.5
	Waste Rock in Outer Rim (20-m Ox) (kt)	2,939	0	2,939
	Reactive Outer Rim (kt)	294	0	294
ELF - 20 m model	Sulfur Reservoir in Outer Rim (t)	259	0	259
-	S as Sulfides (t)	253	0	253
	S as SOP (t)	8.4	1.0	9.5
	Waste Rock in Outer Rim (10-m Ox) (kt)	1,683	0	1,683
	Reactive Outer Rim (kt)		168	
ELF - 10 m model	Sulfur Reservoir in Outer Rim (t)	148	0	148
	S as Sulfides (t)	Table 8. Sulfur reservoir calculations for the SRX ELF. MPONENT TZ3 TZ4 te Rock Quantity (kt) 4,378 606 ctive Waste Rock (kt) 438 61 ur reservoir (t) 385 143 Sulfides (t) 377 142 SOP (t) 8.4 1.0 te Rock in Outer Rim (20-m Ox) 2,939 0 ctive Outer Rim (kt) 294 0 ur Reservoir in Outer Rim (t) 259 0 SUlfides (t) 253 0 SOP (t) 8.4 1.0 te Rock in Outer Rim (10-m Ox) 1,683 0 ctive Outer Rim (kt) 168 0 ur Reservoir in Outer Rim (t) 148 0 Sulfides (t) 145 0 SOP (t) 8.4 1.0 be SoP (t) 8.4 1.0 TZ3 TZ4 MPONENT TZ3 TZ4 ste Rock Quantity (kt) 2,550 850 active Waste Rock (kt) 255 85 fur reservoir (t) 224 201 st Sulfides (t) 219 199 st SOP (t) 4.9 1.5	145	
	S as SOP (t)	8.4	1.0	9.5
	Table 9. Sulfur reservoir calculation	s for the CIT	ELF backfill.	
SCENARIO	COMPONENT	TZ3	TZ4	TZ3+TZ4
Total Waste Rock	Waste Rock Quantity (kt)	2,550	850	3,400
	Reactive Waste Rock (kt)	255	85	340
Waste Rock Stack	Sulfur reservoir (t)	224	201	425
Case	S as Sulfides (t)	219	199	419
	S as SOP (t)	4.9	1.5	6.4
	Waste Rock in Outer Rim (20-m Ox) (kt)	2,005	0	2,005
	Reactive Outer Rim (kt)	201	0	201
ELF - 20 m model	Sulfur Reservoir in Outer Rim (t)	176	0	176

Page 31 MWM-S003-Rev2

SCENARIO	COMPONENT	TZ3	TZ4	TZ3+TZ4
	S as SOP (t)	4.9	1.5	6.4
	Waste Rock in Outer Rim (10-m Ox) (kt)	1,148	0	1,148
	Reactive Outer Rim (kt)	115	0	115
ELF - 10 m model	Sulfur Reservoir in Outer Rim (t)	101	0	101
	S as Sulfides (t)	99	0	99
	S as SOP (t)	4.9	1.5	6.4

Table 10. Sulfur reservoir calculations for the WELF.

SCENARIO	WASTE ROCK UNIT	TZ3	TZ4	TZ3+TZ4
Total Waste Rock	Waste Rock Quantity (kt)	10,732	0	10,732
	Reactive Waste Rock (kt)	0	1,073	
Waste Rock Stack	Sulfur reservoir (t)	944	0	944
Case	S as Sulfides (t)	924	0	924
	S as SOP (t)	21	0	21
		6,330	0	6,330
	Reactive Outer Rim (kt)	633	0	633
ELF - 20 m model	Sulfur Reservoir in Outer Rim (t)	557	0	557
	S as Sulfides (t)	545	0	545
	S as SOP (t)	21	0	21
		3,624	0	3,624
	Reactive Outer Rim (kt)	362	0	362
ELF - 10 m model	Sulfur Reservoir in Outer Rim (t)	319	0	319
Case ELF - 20 m model	S as Sulfides (t)	312	0	312
	S as SOP (t)	21	0	21

Table 11. Sulfur reservoir calculations for the SCK Fill

SCENARIO	WASTE ROCK UNIT	TZ3	TZ4	TZ3+TZ4
Total Waste Rock	Waste Rock Quantity (kt)	2,264	0	2,264
Waste Rock Stack	Reactive Waste Rock (kt)	226	0	226
	Sulfur reservoir (t)	199	0	199
Case	S as Sulfides (t)	195	0	195
	S as SOP (t)	4.4	0.0	4.4

Page 32 MWM-S003-Rev2

4.2.3 Release Rates

Release rates are obtained from CLT data. Since each sample in the CLTs has a different total sulfur value, sulfur loss is calculated as a percentage of sulfur per month. The following process was followed:

- 1. Convert the total sulfur content from percentage to mg/kg 9.
- 2. Estimate the total sulfate (SO₄) released from the CLT up to week 20 and convert it to sulfur ¹⁰, which indicated that the average SO₄-S production up to week 20 of the CLT is 20.97 mg/kg for TZ3 and 22.07 mg/kg for TZ4 ¹¹.
- 3. Determine what percentage of the total sulfur that is represented by SO₄-S.
- 4. Calculate the amount of sulfide sulfur by subtracting SO₄-S from the total sulfur.
- 5. Determine the SO₄-S release rate by calculating the slope of cumulative SO₄ generation per week from week 20 onwards, converting it to mg/kg/month, and division by 2.996 to present data as SO₄-S.
- 6. Divide this value by the amount of sulfide-S to determine how much SO₄-S is released in the early stages of oxidation. Since sulfide-S will deplete over time, the release rate (and consequently the concentrations) will also decline with time, which is accounted for by the model.

These data (and the calculation process) are presented in Table 12. Results shown that TZ4 releases approximately 6 times the amount of sulfate released by TZ3, in part because the amount of total sulfur is higher (around 3 times higher), and also because the rock is more reactive (approximately 2 times higher). This supports the hypothesis that TZ4 materials should be placed in the core of the ELF away from oxygen.

Figure 25 shows the cumulative amounts of sulfate released over time. It is possible to see graphically that the amount of sulfate released in the first weeks is higher for TZ3, but after week 12, there is a clear change in the quantity of generated sulfate for this geological unit.

It is assumed a limit at week 20 for the initial amount of sulfate sulfur to account for on-going oxidation on field conditions before the material being placed on the ELFs

Page 33 MWM-S003-Rev2

⁹ by multiplying by 10,000.

¹⁰ Based on molecular weights (i.e., by dividing by 2.996)

¹¹ 20 weeks was considered a reasonable time-period as an inflection was identified in TZ3 cumulative sulfate plots indicating a change in rection kinetics (Figure 25) from short term kinetic rates to long term kinetic rates. 20 weeks was also considered a reasonable time frame for materials exposed in the field prior to being excluded from oxygen.

Table 12. Column leach test data for TZ3 and TZ4 oxidising materials.

Sample ID	TZ3 - S: 0.113% (MG19838)	TZ3 - S: 0.1025% (MG19875/76)	TZ3 - S: 0.0885% (MG43524/25)	TZ4/RSSZ - S: 0.488% (MG46045)	TZ4/RSSZ - S: 0.267% (MG40061)	TZ4/RSSZ - S: 0.226% (MG37922)	Average TZ3	Average TZ4
Total Sulfur (%)	0.113	0.1025	0.085	0.488	0.267	0.226	0.10017	0.327
Total Sulfur (mg/kg)	1130	1025	850	4880	2670	2260	1001.67	3270
SOP as Sulfur week 20 (mg/kg)	12.101	23.430	27.370	24.354	23.838	18.019	20.967	22.071
Sulfide-S (mg/kg)	1117.9	1001.6	822.6	4855.6	2646.2	2242.0	980.7	3247.9
SO ₄ -S as a percent of total S (%)	1.071	2.286	3.220	0.499	0.893	0.797	2.192	0.730
SO ₄ release rate (mg/kg/week)	0.279	0.948	1.045	5.633	4.180	3.007	0.757	4.273
SO ₄ -S release rate (mg/kg/month) ¹	0.404	1.371	1.511	8.146	6.046	4.349	1.095	6.180
Release rate (%/month) ²	0.036	0.137	0.184	0.168	0.228	0.194	0.119	0.197

^{1 -} based on slope;

^{2 -} normalised to wt% S




Figure 25. Cumulative released amount for sulfate based on the AMIRA CLT.

Page 34 MWM-S003-Rev2

4.2.4 Time Lag to Peak Concentrations and Adjustments to Empirical Data

A time lag to peak PCOC concentration is expected for the proposed ELFs. Several physical and hydrological properties influence this behaviour including:

- The rate of WRS construction, its height, and geometry can affect water infiltration and residence time, with taller or more compacted WRS promoting longer contact times with reactive materials.
- Preferential flow paths, such as fractures or loosely compacted zones, can create localised areas of rapid transport, altering concentration trends.
- The hydraulic properties of the waste rock, including permeability and porosity, determine how
 water moves through the system and interacts with reactive minerals. Granulometry and
 particle size distribution also play a role, as finer materials can retain water longer, enhancing
 dissolution and sulfate release.

Given the complexity of how water moves through such materials and the time lag to peak concentrations, empirical data and analogue models were used to estimate both the time required to reach peak concentrations and the magnitude of those peaks.

Data from Macraes (e.g., Babbage, 2019) indicates that these peaks develop over several years. For the Frasers West WRS (an average height of ~ 40.9 m: Navarro et al., 2024), it took approximately 14 years to reach peak concentrations. Assuming this timing corresponds to when the tallest portion of the waste rock stack begins contributing to seepage quality, we estimate that the peak concentrations for Shepherds ELF will occur between 25 and 30 years after construction begins. This estimate is based on the fact that the average height of the Shepherds ELF is approximately twice that of the Frasers West WRS. Hence, using height data to scale to time lag to peak concentration, the time lag to peak sulfate concentration for SRX ELF is 5 years; CIT ELF backfill is 4 years; WELF is 10 years, and 3 years for the SCK fill.

In addition, based on the analysis of peak concentrations at Macraes (MWM, 2024a), the estimated sulfate peak concentrations have been calculated for a comparable WRS and are shown in Table 13 along physical characteristics of the ELFs.

Table 13. Summar	v of ELF physica	al characteristics and SO	0 ₄ (mg/L) if constructed as a WR	S.

ELF PARAMETER	SHEPHERDS	SRX	CIT	WELF	SCK FILL
Volume (m³)	91,655,093	2,306,944	1,574,074	5,260,808	1,109,758
Quantity (kt)	197,975	4,983	3,400	10,732	2,264
Area (m²)	1,155,423	155,592	137,925	175,128	111,845
Average height (m)	79	15	11 (5) ²	30	10
Estimated flow rate (L/s)	3.7	0.5	0.44	0.56	0.36
Years until peak concentration	27	5	4	10	3
Expected WRS sulfate peak concentration (mg/L) – no engineering controls ¹	6,206	1,160	861 (460) ²	2,350	776

^{1. –} Sulfate concentrations are for a traditional WRS with no engineered controls.

Page 35 MWM-S003-Rev2

^{2. –} Numbers in brackets represent the average height and sulfate concentration of the CIT WRS above the phreatic surface.

The time lag to peak concentrations is incorporated into the model by assuming a normal distribution for the material generating the loads. This means that solute release begins progressively from the start, with the majority of the material (99%) undergoing interaction by year 40 for the Shepherds ELF model. This is represented graphically on Figure 26. It is worth noting that this adjustment does not affect the total released load as a whole, it only affects when the load is released.




Figure 26. Cumulative percentage of waste rock material releasing solutes over time.

The effect on the sulfate concentration for the Shepherds WRS geochemical model is shown on Figure 27 where there is no scaling of data for any time lag to peak concentration. Without a time lag, all materials immediately release solutes from the start of the model and decays over time due to the exhaustion of available solutes, which is caused by both short-term and long-term sulfate release.

The introduction of a time lag to acid onset and an adjustment to the quantify of material contributing to solutes attenuates this peak concentration and generates the load later in the model. Note: these results are prior to the scaling of non-reactive material or column leach test concentrations to match empirical datasets (discussed in the next section).




Figure 27. Comparison of model output for Shepherds WRS with no time lag to peak concentration and a time lag scenario.

Page 36 MWM-S003-Rev2

4.2.5 Adjustments to Match Empirical Data: Waste Rock Stack Height

PCOC concentration is a function of WRS height. This process is based on analogue data from Macraes (Section 2.2), which shares similar geochemical characteristics and climatic conditions. The ELF model is based on the assumption that the expected average WRS sulfate concentrations peak correlates with the average height of the WRS. This approach is undertaken to develop the Traditional WRS model and assumes oxygen is freely available through the WRS.

The key driver for peak sulfate in the BOGP modelling is based on the height versus sulfate relationship (Navarro-Valdivia et al., 2024), which is shown in Table 13. Two adjustment factors are implemented to align the model:

- 1. The first factor to consider is the reactive material fraction. In laboratory conditions, such as those used in CLTs, a high percentage of minerals are available for reaction due to sample preparation, which often involves grinding the material to increase surface area. However, in the field, waste rock is coarser (e.g., boulders). Minerals within the inner parts of these boulders are not expected to be available for reaction in the short and long term. Additionally, preferential flow paths form during infiltration, and these paths will only interact with the minerals they come into direct contact with, further limiting the availability of reactive materials. The non-reactive material fraction was set to 0.9, which therefore decrease the peak sulfate concentration to ~7,000 mg/L (e.g., 10% of 70,000 mg SO₄/L).
- 2. The second factor to consider is an adjustment to the release rate of sulfate. The release rate adjustment factor specifically modifies the long-term release rates (e.g., derived from oxidation). This adjustment is made to align the release rates derived from CLT data with the expected sulfate peak from empirical data. The adjustment factor to the long-term release rates was set to 0.8575 to match the ~6,200 mg/L sulfate peak that is expected from the height versus peak sulfate concentration model (e.g., Figure 6).

The effect of the non-reactive fraction factor and the long-term release rates factor are shown in Figure 28.




Figure 28. Adjustment Factors to match empirical data models: Traditional WRS.

Green line: Sulfate concentration for the non-reactive fraction set at 0.9.

Orange line: Sulfate concentration with non-reactive fraction set at 0.9 and long-term release rates adjusted with a factor of 0.8575 to match the \sim 6,200 mg/L expected sulfate peak.

Page 37 MWM-S003-Rev2

4.2.6 Other Solute Release Calculations

Six AMIRA (2002) CLTs were conducted to quantify oxidation rates and solute release from TZ3 and TZ4 materials. Time series plots for sulfate are shown in Figure 25. The cumulative solute generation, expressed in milligrams of solute per kilogram (mg/kg) of rock, was calculated for each element.

The short-term release of contaminants was estimated using the intercept of the linear trend from the long-term decay. However, this approach differed for sulfate, where the total sulfate released up to week 20 was used instead. This exception was made because the TZ4 samples exhibited a negative intercept, suggesting an absence of initial sulfate load. Given that waste rock is expected to be exposed to the atmosphere (oxygen) before placement in the ELF and then will not be excluded from oxygen immediately, it was determined that sulfate generation would occur for up to 20 weeks prior to deposition, which also matched the SOP inflection point suggesting a change in kinetic rates (Figure 25), e.g., for example, a change from dissolution driven process to slower oxidation driven processes.

The long-term release rate was estimated by calculating solute generation from week 20 onward, with some exceptions. These exceptions were based on observed decay trends for specific solutes.

Since there is no empirical quantification of the total solute release over the long term for solutes other than sulfate, it was assumed that the solute decay follows the same pattern as sulfide decay. While this assumption may be conservative, implying that solute release persists for as long as sulfides, it provides a conservative estimate for long-term environmental impact assessments. This ensures that potential risks are not underestimated, even if the actual release duration may be shorter.

Three specific exceptions for solute behaviour are shown in Figure 29. Ongoing CLT will confirm whether the approaches presented below are appropriate:

- Molybdenum follows a similar pattern to sulfate; however, a slight decrease in CLT release
 rates is observed from week 32 onwards. The release rate for Mo was determined using the
 slope of the last three cycles to consider long term release rates.
- Uranium has a decreasing trend in CLT for TZ3 materials. The trend from week 28 onward is
 used for TZ3. TZ4 has very little U and all the released mass is assumed to be released in the
 short term.
- Boron release appears to cease in all CLT over time. Consequently, its long-term release rate
 is assumed to be zero, and the total amount released is attributed to short-term release.

Page 38 MWM-S003-Rev2




Figure 29. Cumulative CLT solute release rates for B, Mo, and U.

Table 14 summarises the average release rates for solute based on the CLT data for short and long terms for each lithological unit.

Table 14. Average short-term and long-term release rates for TZ3 and TZ4.

PARAMETER	SHORT-TERM RE	LEASE (mg/kg)1	LONG-TERM RELEASE (mg/kg/week)			
	TZ3	TZ4	TZ3	TZ4		
Alkalinity	100.6841	8.457784	4.888945	1.100828		
F	0.684865	0.064659	0.008621	0.00124		
CI	7.462766	0.842568	0.028704	0.020857		
SO ₄	58.28484	47.46398	0.757372	4.273423		
P	0.240219	0	0.002427	0.004354		
Al	0.341493	0.038954	0.005617	0.003156		
SO ₄	0.01508	0.00279	0.002833	0.0002		
As	0.0283	0	0.016346	0.052076		
Ва	0.006932	0.001595	0.001158	0.000722		
В	0.176198	0.025042	0	0		
Cd	0	0	0	0		
Ca	0	0	1.354358	0.823776		
Cr	0.000884	0.000432	0	O		
Co	0.038286	0	0	3.7E-05		
Cu	0.004143	0	0.000106	7.12E-06		

Page 39 MWM-S003-Rev2

PARAMETER	SHORT-TERM RE	LEASE (mg/kg) ¹	LONG-TERM RELEASE (mg/kg/week)				
	TZ3	TZ4	TZ3	TZ4			
Fe	0.193134	0.00764	0.001586	0.000413			
Pb	0.000246	0	0	0			
Mg	0.094851	0	0.161223	0.620839			
Mn	0.008974	0.006485	0.000678	0.000747			
Hg	5.57E-05	0	0	0			
Мо	0.024109	0.02288	0.00058	0.000844			
Ni	0.001733	0.000484	0	6.38E-06			
K	1.855408	4.621057	0.591858	0.558662			
Se	0.00207	0	0.000144	0			
Ag	0	0	0	0			
Na	65.56925	7.088255	0.612655	0.182891			
Sr	0.145743	0.110983	0.042898	0.058856			
TI	0	0	0	0			
Sn	0	0	0	0			
Ti	0.005641	0	1.86E-05	0			
U	0.018802	0.0025	0.000186	0			
V	0.006116	7.09E-05	9.87E-05	0			
Zn	0.003452	0	0	0			

For calculation purposes, any value below the limit of reporting was assumed to be zero.

Note: Nitrate-N cannot be determined from CLT as the materials have not been blasted. Nitrate-N loads of 16.6 mg/kg are used in the model (see Section 2.6.2).

1. - It is assumed that ~90% of the SOP load is mobilised over 50 years to align with the mobilisation of nitrate-N.

4.2.7 Solubility Controls (PHREEQC)

Once the solute concentration is estimated, the resulting concentrations are modelled using the geochemical modelling code PHREEQC version 3.7 (Parkhurst & Appelo, 2003) with the minteq.v4 database. The objective of this step is to apply solubility controls to the concentrations and precipitate supersaturated minerals, such as Fe, Al, and Cu hydroxides, as well as other hydroxysulfates and sulfates. This is achieved using the EQUILIBRIUM PHASES keyword in PHREEQC simulations.

Certain assumptions are made, including the presence of excess dolomite in the reaction to help calculate and regulate pH. This assumption is possible, since mineralogical analyses (MWM, 2025a) identified dolomite as the main carbonate phase. Additionally, the ABA data indicates that the acid neutralisation capacity (ANC) exceeds the maximum potential acidity (MPA) by a ratio of 3 and higher, indicating a sufficient carbonate presence to neutralise the acid generated from sulfides.

Table 15. Equilibrium phases in the geochemical modelling for solubility controls.

PHASE	REACTIONS	LOG K
Dolomite(ordered)	CaMg(CO3)2 = Ca+2 + Mg+2 + 2CO3-2	-17.09
CO ₂ (g)	CO2 + H2O = 2H+ + CO3-2	-18.147
Ferrihydrite	Fe(OH)3 + 3H+ = Fe+3 + 3H2O	3.191
Basaluminite*	Al4(OH)10SO4 + 10H+ = 4Al+3 + SO4-2 + 10H2O	22.7

Page 40 MWM-S003-Rev2

PHASE	REACTIONS	LOG K
Fluorite	CaF2 = Ca+2 + 2F-	-10.5
Al(OH)3(am)	Al(OH)3 + 3H+ = Al+3 + 3H2O	10.8
Gibbsite	Al(OH)3 + 3H+ = Al+3 + 3H2O	8.291
Celestite	SrSO4 = Sr+2 + SO4-2	-6.62
Gypsum	CaSO4:2H2O = Ca+2 + SO4-2 + 2H2O	-4.61
Strontianite	SrCO3 = Sr+2 + CO3-2	-9.27
Hydroxylapatite	Ca5(PO4)3OH + H+ = 5Ca+2 + 3PO4-3 + H2O	-44.333
Malachite	Cu2(OH)2CO3 + 2H+ = 2Cu+2 + 2H2O + CO3-2	-5.306
Barite	BaSO4 = Ba+2 + SO4-2	-9.98
Cupricferrite	CuFe2O4 + 8H+ = Cu+2 + 2Fe+3 + 4H2O	5.9882
Fluorapatite*	Ca5(PO4)3F + 3H+ = 5Ca+2 + 3HPO4-2 + F-	-17.6
Alunite	KAI3(SO4)2(OH)6 + 6H+ = K+ + 3AI+3 + 2SO4-2 + 6H2O	-1.4
K-Autunite	K2(UO2)2(PO4)2 = 2UO2+2 + 2K+ + 2PO4-3	-48.244
Na-Autunite	Na2(UO2)2(PO4)2 = 2UO2+2 + 2Na+ + 2PO4-3	-47.409
Calcite	CaCO3 = Ca+2 + CO3-2	-8.48
Quartz	SiO2 + 2H2O = H4SiO4	-4
Pyromorphite	Pb5(PO4)3Cl = 5Pb+2 + 3PO4-3 + Cl-	-84.43
PbMoO4	PbMoO4 = Pb+2 + MoO4-2	-15.62
Pb3(VO4)2	Pb3(VO4)2 + 8H+ = 3Pb+2 + 2VO2+ + 4H2O	6.14
Cr(OH)3(am)	Cr(OH)3 + H+ = Cr(OH)2+ + H2O	-0.75

^{*}Added from WATEQ4F thermodynamic database.

In addition, excess oxygen is assumed, meaning that Fe is assumed to be in the Fe³⁺ state and may precipitate as an iron hydroxide. Only phases that were at some point saturated in the WRS scenario are assumed to be in equilibrium, with initial amounts set to zero, allowing only precipitation to occur.

CO₂ equilibrium (fugacity) is set to -2.5, which is one order of magnitude higher than atmospheric conditions. This assumption is based on the expectation that the dissolution of carbonates, such as dolomite, enriches the waste rock pores with CO₂, leading to higher alkalinity concentrations.

Analogue empirical data for seepage from the Devils WRS at Globe Progress, where the waste rock was present under sub-oxic conditions, indicated elevated concentrations of As and Fe (Hayton et al., 2022). Therefore, these concentrations are used as constant outputs for ELF seepage. To represent the sub-oxic conditions of the ELF, Fe and As concentrations are set at 7.6 mg/L and 0.2 mg/L, respectively based on the Globe Progress waste rocks drains concentrations (Hayton et al., 2022). There is some uncertainty in these data, but any issues can be resolved by active and passive treatment processes that are proposed for the BOGP in the active and post closure phases (MWM, 2025e).

4.3 Summary of Model Inputs and Other Considerations

A process diagram is shown in Figure 30 and summarises the process to derive water quality estimates for the proposed BOGP ELFs. Summary inputs for model are shown in Table 16.

Page 41 MWM-S003-Rev2

Table 16. Summary for ELF modelling inputs

TZ4-S (%) 0.236 % TZ3 (SO4-S)/S (%) 2.19223 % SULFATE RELEASE RATES Short-term rates 0.4 %/month Long-term rate TZ3 0.118904 %/month Long-term rate TZ4 0.196745 %/month ADJUSTMENT FACTORS non-reactive fraction 0.1 long-term rates factor 0.8575 MATERIAL QUANTITIES SHEP-TZ3 179,886 kt SHEP-TZ4 18,089 kt SRX-TZ3 606 kt CIT-TZ3 2,550 kt CIT-TZ3 850 kt WELF-TZ3 10,732 kt EXPECTED YEAR FOR PEAK CONCENTRATION SHEPHERDS 27 year SRX 5 year CIT 4 year WELF 10 W/month	PARAMETER	VALUE	UNIT
TZ4-S (%) 0.236 % TZ3 (SO4-S)/S (%) 2.19223 % SULFATE RELEASE RATES Short-term rates 0.4 %/month Long-term rate TZ3 0.118904 %/month Long-term rate TZ4 0.196745 %/month ADJUSTMENT FACTORS non-reactive fraction 0.1 ong-term rates factor 0.8575 MATERIAL QUANTITIES SHEP-TZ3 179,886 kt SRX-TZ3 4,377 kt SRX-TZ3 606 kt CIT-TZ3 2,550 kt CIT-TZ3 850 kt WELF-TZ3 10,732 kt EXPECTED YEAR FOR PEAK CONCENTRATION SHEPHERDS 27 year SRX 5 year WELF 10 Wear WELF 10 year		SULFUR RESERVOIR	
TZ3 (SO4-S)/S (%) 2.19223 % SULFATE RELEASE RATES Short-term rates 0.4 M/month Long-term rate TZ3 0.118904 M/month Long-term rate TZ4 0.196745 MATERIAL QUANTITIES SHEP-TZ3 179,886 kt SHEP-TZ4 18,089 kt SRX-TZ3 606 kt CIT-TZ3 850 kt CIT-TZ3 850 kt EXPECTED YEAR FOR PEAK CONCENTRATION SHEPHERDS SRX 5 year WELF WELF 10 year WELF	TZ3-S (%)	0.088	%
SULFATE RELEASE RATES	TZ4-S (%)	0.236	%
SULFATE RELEASE RATES	TZ3 (SO4-S)/S (%)	2.19223	%
Short-term rates 0.4	TZ4 (SO4-S)/S (%)	0.72973	%
Long-term rate TZ3		SULFATE RELEASE RATES	
ADJUSTMENT FACTORS	Short-term rates	0.4	%/month
ADJUSTMENT FACTORS non-reactive fraction 0.1 long-term rates factor 0.8575 MATERIAL QUANTITIES SHEP-TZ3 179,886 kt SHEP-TZ4 18,089 kt SRX-TZ3 4,377 kt SRX-TZ3 606 kt CIT-TZ3 2,550 kt CIT-TZ3 850 kt WELF-TZ3 10,732 kt SCK Fill-TZ3 2,264 kt EXPECTED YEAR FOR PEAK CONCENTRATION SHEPHERDS 27 year SRX 5 year CIT 4 year WELF 10 year	Long-term rate TZ3	0.118904	%/month
Description	Long-term rate TZ4	0.196745	%/month
MATERIAL QUANTITIES		ADJUSTMENT FACTORS	
MATERIAL QUANTITIES	non-reactive fraction	0.1	
SHEP-TZ3	long-term rates factor	0.8575	
SHEP-TZ4		MATERIAL QUANTITIES	
SRX-TZ3 4,377 kt SRX-TZ3 606 kt CIT-TZ3 2,550 kt CIT-TZ3 850 kt WELF-TZ3 10,732 kt SCK Fill-TZ3 2,264 kt EXPECTED YEAR FOR PEAK CONCENTRATION SHEPHERDS 27 year SRX 5 year CIT 4 year WELF 10 year	SHEP-TZ3	179,886	kt
SRX-TZ3 606 kt CIT-TZ3 2,550 kt CIT-TZ3 850 kt WELF-TZ3 10,732 kt SCK Fill-TZ3 2,264 kt EXPECTED YEAR FOR PEAK CONCENTRATION SHEPHERDS 27 year SRX 5 year CIT 4 year WELF 10 year	SHEP-TZ4	18,089	kt
CIT-TZ3 2,550 kt CIT-TZ3 850 kt WELF-TZ3 10,732 kt SCK Fill-TZ3 2,264 kt EXPECTED YEAR FOR PEAK CONCENTRATION SHEPHERDS 27 year SRX 5 year CIT 4 year WELF 10 year	SRX-TZ3	4,377	kt
Reserve	SRX-TZ3	606	kt
WELF-TZ3 10,732 kt SCK Fill-TZ3 2,264 kt EXPECTED YEAR FOR PEAK CONCENTRATION SHEPHERDS 27 year SRX 5 year CIT 4 year WELF 10 year	CIT-TZ3	2,550	kt
SCK Fill-TZ3 2,264 kt EXPECTED YEAR FOR PEAK CONCENTRATION SHEPHERDS 27 year SRX 5 year CIT 4 year WELF 10 year	CIT-TZ3	850	kt
EXPECTED YEAR FOR PEAK CONCENTRATION SHEPHERDS 27 year SRX 5 year CIT 4 year WELF 10 year	WELF-TZ3	10,732	kt
SHEPHERDS 27 year SRX 5 year CIT 4 year WELF 10 year	SCK Fill-TZ3	2,264	kt
SRX 5 year CIT 4 year WELF 10 year	EXPE	CTED YEAR FOR PEAK CONCENTRA	ATION
CIT 4 year WELF 10 year	SHEPHERDS		year
WELF 10 year	SRX		year
	CIT	4	year
SCK Fill 3 year	WELF	·-	year
	SCK Fill	3	year

Page 42 MWM-S003-Rev2

MATAKANUI GOLD LIMITED J-NZ0457-002-R-Rev1




Figure 30. Process diagram for estimating the water quality seepage of the ELFs.

Page 43 MWM-S003-Rev2

4.4 Model Limitations

The model has the following limitations:

- It is not possible to model the dynamics of nitrogen speciation accurately, as they are governed by sites-specific biochemical reactions and oxygen availability. It can be assumed that the majority of nitrogen will be speciated as nitrate, however, there could be a minor part as nitrite or ammoniacal nitrogen. The results are presented as nitrogen (total nitrogen).
- The estimated release rates for some elements may be overly conservative, as they are based on sulfide decay rates. Consequently, solute generation could be overestimated thereby maintaining high solute generation rates over time.
- The time lag to peak concentrations is influenced by the ELFs geometry, therefore the applied time lag to peak sulfate concentration is an approximate estimate based on analogue empirical data, and simplistic assumptions. However, the time frame is likely to be reasonable to estimate potential environmental risks for the BOGP.
- In-situ precipitation of ferric hydroxides is anticipated. Consequently, certain metals (e.g., As, Cu, Zn)) may be sorbed and captured by these minerals, particularly at neutral to alkaline pH where sorption capacities are elevated. While PHREEQC modelling can model this, significant uncertainty exists around the amount of available iron. Therefore, a conservative approach is adopted, and sorption is not modelled. Sorption may be higher in the outer oxidising zone of the ELF and lower in the core where oxygen is limited. Fixed Fe and As concentrations are provided to identify the risk to receiving waters and the need for management.

Page 44 MWM-S003-Rev2

5 MODEL RESULTS AND ANALYSIS

This section presents the model results for Shepherds ELF, SRX ELF, WELF, CIT Backfill, and the SCK Fill.

5.1 Water Quality Reference Criteria

Model results are compared to the proposed compliance water quality limits for the BOGP (Ryder, 2025) for surface and groundwater to understand what PCOC may be elevated from these mine domains (Table 17).

- Sulfate limit is set at 500 mg/L as a guide to understand MIW with no modifications for SW (Ryder, 2025 recommends a variable limit between 500 and 1,000 mg/L based on hardness and chloride modifications)
- No modifications (e.g., hardness) were applied to the limits.
- Boron limit (ANZG, 2018 limits for 90% of freshwater level of protection) was used for reference purposes at 1.5 mg/L.

Table 17. Reference concentration limits for surface water and groundwater (mg/L).

SURFACE WATER REFERENCE LIMIT	GROUNDWATER REFERENCE LIMIT
0.08	1
0.001	1
0.0018	0.5
-	0.4
0.034	0.01
2.4	11.3
	0.01
0.074	0.02
-	0.02
500	250
-	4
- -	0.03
0.015	1.5
0.0033	0.05
	0.08 0.001 0.0018 - 0.034 2.4 0.074 - 500 - - 0.015

Source: Ryder (2025); Units in mg/L

Results are displayed in time-series plots together with the GW and SW limits and a summary table of results.

5.2 General Observations

The following general observations are provided for the results:

• Water quality is expected to be circum-neutral pH with low acidity. This is due to the abundance of carbonate minerals and a low sulfide content.

Page 45 MWM-S003-Rev2

- Peak sulfate concentrations, a function of average ELF height, were determined for Shepherds ELF (~27 years), SRX ELF (~5 years), CIT ELF (~4 years), WELF (~10 years), and SCK Fill (~3 years).
- When the results for the two scenarios overlap (e.g., 10 m and 20 m oxygen exclusion zones), it indicates that the solutes originate from short-term release, where oxidation has no impact on the results, and therefore, results are the same.
- The first 50 years are strongly influenced by the short-term release of SOP. This is particularly evident for nitrate-nitrogen (NO₃-N), boron (B), cobalt (Co), and zinc (Zn), which are generally elevated and are associated with SOP (see Table 14). Reducing water ingress would reduce the rate that these PCOC are mobilised.
- Sulfate concentrations are > 500 mg/L for the Shepherds ELF, SRX ELF, and WELF. Sulfate concentrations are < 500 mg/L in the CIT backfill and the SCK Fill.
- Nitrate-N concentrations are > 2.4 mg/L in seepage from all waste rock disposal areas. Duration
 of elevated nitrate in seepage is expected to range from 25 100 years but may be shorter due
 to biogeochemical processes that would remove the nitrate.
- Results indicate that the following trace metals: Sb, Co, Mo, Mn, Se, Sr, U, and Zn, are generally
 over the respective water quality reference limits.
- Results indicate that Al, B, Cd, Cr, Cu, Hg, and Pb, are below the respective water quality reference limits in all cases. These PCOC are not considered an issue for this mine domain.
- Constant concentrations are assumed for As (0.2 mg/L) and Fe (7.6 mg/L) based on empirical
 data for sub-oxic conditions (e.g., Globe Progress Waste Rock Stack, Hayton et al., 2022).
 These concentrations are above the proposed water quality reference limit (Ryder, 2025) and
 will require management. The SCK Fill assumes full oxidation, which results in low Fe
 concentrations.
- Zn is overall below both limits, however peak concentrations are slightly above the SW reference limit (0.0155 > 0.015 mg/L) for Shepherds ELF.

The following subsections present specific results and observations for each ELF.

5.3 Shepherds ELF

Results for the model scenarios for the Shepherds ELF are shown in Figure 31 and Figure 32 with selected outputs shown in Table 17.

The following observations are provided:

- In general, the highest concentrations of PCOC (especially SOP), can be found in Shepherds ELF, due to its higher material volume and higher height.
- Sulfate concentrations are similar across both scenarios (10 and 20 m oxygen exclusion) where
 oxygen is restricted to the outer rim of the ELF, peaking at approximately 1,100 mg/L. After
 year 50, sulfate concentrations declined to below 750 mg/L for both the 10 m and 20 m oxygen
 exclusion scenarios.

Page 46 MWM-S003-Rev2

- NO₃-N concentration peaks at ~ 80 mg/L.
- . Sb, U, and Mn behave similarly to sulfate, likely associated with oxidation of sulfides.




Figure 31. Model results part 1 for the Shepherds ELF.

Page 47




Figure 32. Model results part 2 for the Shepherds ELF.

Page 48 MWM-S003-Rev2

MATAKANUI GOLD LIMITED J-NZ0457-002-R-Rev1

Table 18. Selected model results for the Shepherds ELF Scenarios

	PARAMETER	Al	В	Со	Mn	Мо	NO3-N	Sb	Se	SO4	Sr	U	Zn	V	Cr
SCENARIO	SW REF LIMIT	0.08	-	0.001 ^a	-	0.034	2.4 ^b	0.074ª	-	500	-	-	0.015		0.0033°
	GW REF LIMIT	1	-	1	0.4	0.01	11.3	0.02	0.02	250	4	0.03	1.5		0.05
	YEAR														
ELF - 20 m model	1	0.0028	0.001	0.0002	0.0008	0.0012	0.08	0.0026	0.0001	1	0.04	0.000	0.0000	0.0001	0.00002
ELF - 20 m model	5	0.0028	0.023	0.0029	0.0129	0.0191	1.32	0.0426	0.0022	16	0.67	0.005	0.0003	0.0019	0.00017
ELF - 20 m model	10	0.0030	0.175	0.0218	0.0997	0.1464	9.96	0.3315	0.0172	120	5.18	0.037	0.0020	0.0147	0.00017
ELF - 20 m model	27	0.0035	1.378	0.1718	0.9529	1.2953	78.36	3.3105	0.1712	1102	15.73	0.341	0.0155	0.1398	0.00019
ELF - 20 m model	50	0.0033	0.490	0.0611	0.6704	0.7442	27.86	2.5623	0.1315	773	15.21	0.212	0.0055	0.0980	0.00019
ELF - 20 m model	100	0.0031	0.044	0.0055	0.3322	0.2996	2.51	1.3664	0.0697	373	12.41	0.094	0.0005	0.0484	0.00018
ELF - 20 m model	150	0.0030	0.004	0.0005	0.1772	0.1530	0.23	0.7386	0.0377	198	10.81	0.049	0.0000	0.0258	0.00004
ELF - 20 m model	199	0.0029	0.000	0.0000	0.0970	0.0831	0.02	0.4051	0.0206	108	6.14	0.027	0.0000	0.0141	0.00000
ELF - 10 m model	1	0.0028	0.001	0.0002	0.0005	0.0010	0.08	0.0014	0.0001	1	0.02	0.000	0.0000	0.0001	0.00002
ELF - 10 m model	5	0.0028	0.023	0.0029	0.0082	0.0151	1.32	0.0231	0.0012	10	0.37	0.004	0.0003	0.0012	0.00017
ELF - 10 m model	10	0.0029	0.175	0.0218	0.0633	0.1152	9.96	0.1791	0.0094	80	2.87	0.027	0.0020	0.0093	0.00017
ELF - 10 m model	27	0.0034	1.377	0.1716	0.5840	0.9791	78.27	1.7697	0.0927	722	14.51	0.239	0.0155	0.0861	0.00019
ELF - 10 m model	50	0.0032	0.490	0.0610	0.3785	0.4944	27.84	1.3431	0.0693	447	12.94	0.132	0.0055	0.0555	0.00018
ELF - 10 m model	100	0.0030	0.044	0.0055	0.1742	0.1644	2.51	0.7063	0.0361	197	10.74	0.050	0.0005	0.0254	0.00017
ELF - 10 m model	150	0.0029	0.004	0.0005	0.0916	0.0798	0.23	0.3810	0.0194	102	5.77	0.025	0.0000	0.0133	0.00004
ELF - 10 m model	199	0.0029	0.000	0.0000	0.0500	0.0429	0.02	0.2089	0.0106	56	3.16	0.014	0.0000	0.0073	0.00000

Units in mg/L

Bold red text indicates values greater than the GW and SW reference limit.

Bold orange text indicates values greater than the SW reference limit.

Bold purple text indicates values greater than the GW reference limit.

Page 49 MWM-S003-Rev2

a: Chronic value is used for reference.

b: Annual median used for NO₃-N

c: Cr(III) recommended compliance limit is used.

5.4 SRX ELF

Selected results for the model scenarios for the SRX ELF are shown in Figure 33 and Figure 34 and selected outputs for key years shown in Table 18.

The following observations are provided:

 Sulfate concentrations peak at 646 mg/L for the ELF (20 m oxygen exclusion model) and at 402 mg/L for the ELF (10 m oxygen exclusion model).




Figure 33. Model results part 1 for the SRX ELF.

Page 50 MWM-S003-Rev2




Figure 34. Model results part 2 for the SRX ELF.

Page 51 MWM-S003-Rev2

MATAKANUI GOLD LIMITED J-NZ0457-002-R-Rev1

Table 19. Selected model results for the SRX ELF Scenarios

	PARAMETER	Al	В	Со	Mn	Мо	NO3-N	Sb	Se	SO4	Sr	U	Zn	V	Cr
SCENARIO	SW REF LIMIT	0.08	-	0.001a	-	0.034	2.4 ^b	0.074a	-	500	-	-	0.015	0	0.0033c
	GW REF LIMIT	1	-	1	0.4	0.01	11.3	0.02	0.02	250	4	0.03	1.5	0	0.05
	YEAR														
ELF - 20 m model	1	0.0028	0.031	0.0034	0.0402	0.0468	1.58	0.151	0.0077	45	2.32	0.013	0.0003	0.0057	0.00017
ELF - 20 m model	5	0.0033	0.418	0.0449	0.5755	0.6579	21.11	2.173	0.1111	646	14.44	0.179	0.0040	0.0820	0.00019
ELF - 20 m model	10	0.0032	0.331	0.0355	0.5343	0.5880	16.70	2.049	0.1047	599	14.14	0.164	0.0032	0.0764	0.00019
ELF - 20 m model	27	0.0032	0.146	0.0157	0.4146	0.4125	7.37	1.651	0.0843	464	13.19	0.121	0.0014	0.0597	0.00018
ELF - 20 m model	50	0.0031	0.048	0.0052	0.3031	0.2784	2.44	1.239	0.0632	339	12.12	0.086	0.0005	0.0439	0.00018
ELF - 20 m model	100	0.0030	0.004	0.0005	0.1609	0.1393	0.22	0.669	0.0341	180	10.15	0.044	0.0000	0.0234	0.00005
ELF - 20 m model	150	0.0029	0.000	0.0000	0.0869	0.0745	0.02	0.363	0.0185	97	5.50	0.024	0.0000	0.0126	0.00000
ELF - 20 m model	199	0.0029	0.000	0.0000	0.0477	0.0408	0.00	0.199	0.0101	53	3.02	0.013	0.0000	0.0069	0.00000
ELF - 10 m model	1	0.0028	0.031	0.0034	0.0251	0.0339	1.58	0.088	0.0045	28	1.36	0.008	0.0003	0.0035	0.00017
ELF - 10 m model	5	0.0032	0.418	0.0448	0.3572	0.4710	21.09	1.261	0.0646	402	12.64	0.119	0.0040	0.0503	0.00018
ELF - 10 m model	10	0.0032	0.330	0.0355	0.3278	0.4113	16.69	1.186	0.0607	369	12.36	0.107	0.0032	0.0463	0.00018
ELF - 10 m model	27	0.0031	0.146	0.0157	0.2470	0.2691	7.36	0.951	0.0486	277	11.55	0.075	0.0014	0.0353	0.00018
ELF - 10 m model	50	0.0030	0.048	0.0052	0.1767	0.1702	2.44	0.712	0.0363	198	10.81	0.051	0.0005	0.0255	0.00017
ELF - 10 m model	100	0.0029	0.004	0.0005	0.0924	0.0807	0.22	0.384	0.0196	103	5.81	0.026	0.0000	0.0134	0.00005
ELF - 10 m model	150	0.0029	0.000	0.0000	0.0498	0.0427	0.02	0.208	0.0106	56	3.15	0.014	0.0000	0.0072	0.00000
ELF - 10 m model	199	0.0028	0.000	0.0000	0.0273	0.0234	0.00	0.114	0.0058	30	1.73	0.008	0.0000	0.0040	0.00000

Units in mg/L

a: Chronic value is used for reference.

b: Annual median used for NO₃-N

c: Cr(III) recommended compliance limit is used.

Bold red text indicates values greater than the GW and SW reference limit.

Bold orange text indicates values greater than the SW reference limit.

Bold purple text indicates values greater than the GW reference limit.

Page 52 MWM-S003-Rev2

5.5 West ELF

Results for the model scenarios for the West ELF are shown in Figure 35 and Figure 36, and selected outputs for key years are shown in Table 19.

The following observations are provided:

• Sulfate concentrations are peaking at around 1,300 mg/L in the 20 m oxygen exclusion model, which is higher than those estimated for Shepherds. This is primarily because a greater proportion of material is expected to be located in the outer rim (e.g., large surface area), which reduces the relative impact of short-lift construction compared to Shepherds. In addition, the peak at Shepherds is broader (due to its 79 m average height), meaning the load is distributed over several years, whereas the peak at WELF is sharper and more concentrated.

Page 53 MWM-S003-Rev2




Figure 35. Model results part 1 for the West ELF.

Page 54 MWM-S003-Rev2




Figure 36. Model results part 2 for the West ELF.

Page 55 MWM-S003-Rev2

MATAKANUI GOLD LIMITED J-NZ0457-002-R-Rev1

Table 20. Selected model results for the WELF scenarios

	PARAMETER	Al	В	Co	Mn	Мо	NO3-N	Sb	Se	SO4	Sr	U	Zn	V	Cr
SCENARIO	SW REF LIMIT	0.08	-	0.001 ^a	-	0.034	2.4 ^b	0.074ª	-	500	-	-	0.015	0	0.0033°
	GW REF LIMIT	1	-	1	0.4	0.01	11.3	0.02	0.02	250	4	0.03	1.5	0	0.05
	YEAR														
ELF - 20 m model	1	0.0028	0.009	0.0020	0.0212	0.0190	0.82	0.087	0.0045	26	1.32	0.007	0.0002	0.0033	0.00005
ELF - 20 m model	5	0.0033	0.240	0.0521	0.5828	0.5208	21.81	2.404	0.1243	716	14.78	0.182	0.0047	0.0914	0.00019
ELF - 20 m model	10	0.0036	0.401	0.0871	1.0979	0.9763	36.45	4.536	0.2342	1275	14.26	0.339	0.0079	0.1708	0.00019
ELF - 20 m model	27	0.0034	0.178	0.0387	0.8889	0.7770	16.20	3.692	0.1895	1003	15.34	0.261	0.0035	0.1343	0.00019
ELF - 20 m model	50	0.0033	0.059	0.0128	0.6664	0.5756	5.36	2.777	0.1420	760	15.27	0.189	0.0012	0.0986	0.00019
ELF - 20 m model	100	0.0031	0.005	0.0012	0.3597	0.3082	0.48	1.502	0.0766	403	12.68	0.099	0.0001	0.0525	0.00003
ELF - 20 m model	150	0.0030	0.000	0.0001	0.1948	0.1667	0.04	0.819	0.0415	217	11.00	0.054	0.0000	0.0284	0.00000
ELF - 20 m model	199	0.0029	0.000	0.0000	0.1069	0.0914	0.00	0.447	0.0228	119	6.76	0.029	0.0000	0.0156	0.00000
ELF - 10 m model	1	0.0028	0.009	0.0020	0.0122	0.0113	0.82	0.049	0.0026	16	0.75	0.004	0.0002	0.0020	0.00005
ELF - 10 m model	5	0.0032	0.240	0.0521	0.3356	0.3094	21.79	1.372	0.0717	440	12.77	0.114	0.0047	0.0554	0.00018
ELF - 10 m model	10	0.0033	0.400	0.0869	0.6306	0.5766	36.40	2.584	0.1346	813	15.26	0.210	0.0078	0.1027	0.00019
ELF - 10 m model	27	0.0032	0.178	0.0387	0.5075	0.4507	16.19	2.098	0.1082	615	14.15	0.156	0.0035	0.0787	0.00019
ELF - 10 m model	50	0.0032	0.059	0.0128	0.3790	0.3297	5.35	1.576	0.0808	439	12.94	0.110	0.0012	0.0568	0.00018
ELF - 10 m model	100	0.0030	0.005	0.0012	0.2040	0.1750	0.48	0.852	0.0434	229	11.11	0.057	0.0001	0.0298	0.00003
ELF - 10 m model	150	0.0029	0.000	0.0001	0.1105	0.0945	0.04	0.462	0.0235	123	6.99	0.030	0.0000	0.0161	0.00000
ELF - 10 m model	199	0.0029	0.000	0.0000	0.0606	0.0519	0.00	0.253	0.0129	68	3.83	0.017	0.0000	0.0088	0.00000

Units in mg/L

a: Chronic value is used for reference.

b: Annual median used for NO₃-N

c: Cr(III) recommended compliance limit is used.

Bold red text indicates values greater than the GW and SW reference limit.

Bold orange text indicates values greater than the SW reference limit.

Bold purple text indicates values greater than the GW reference limit.

Page 56 MWM-S003-Rev2

5.6 CIT Backfill ELF

Results for the model scenarios for the CIT backfill ELF are shown in Figure 37 and Figure 38 with selected outputs for key years shown in Table 20.

The following observations are provided:

- Sulfate concentrations are similar across both scenarios where oxygen is restricted to the outer rim of the ELF, and in both scenarios remain below 500 mg/L.
- In general, the concentrations in the CIT backfill are low due to the following reasons:
 - o The ELF has the least amount of waste rock, resulting in lower initial loads.
 - A significant portion of the ELF will be submerged during the first four years, preventing the material from undergoing ongoing oxidation.
 - It is assumed that a portion of the available material will remain inaccessible for oxidation due to the low-lift construction method.

Page 57 MWM-S003-Rev2




Figure 37. Model results part 1 for the CIT Backfilled ELF.

Page 58 MWM-S003-Rev2




Figure 38. Model results part 2 for the CIT Backfilled ELF.

Page 59 MWM-S003-Rev2

MATAKANUI GOLD LIMITED J-NZ0457-002-R-Rev1

Table 21. Selected model results for the CIT Backfill scenarios.

	PARAMETER	Al	В	Со	Mn	Мо	NO3-N	Sb	Se	SO4	Sr	U	Zn	V	Cr
SCENARIO	SW REF LIMIT	0.08	-	0.001a	-	0.034	2.4 ^b	0.074ª	-	500	-	-	0.015	0	0.0033°
	GW REF LIMIT	1	-	1	0.4	0.01	11.3	0.02	0.02	250	4	0.03	1.5	0	0.05
	YEAR														
ELF - 20 m model	1	0.0029	0.079	0.0050	0.0680	0.0992	2.70	0.226	0.0114	68	3.57	0.021	0.0004	0.0086	0.00017
ELF - 20 m model	5	0.0032	0.462	0.0290	0.4259	0.6041	15.73	1.444	0.0727	430	13.03	0.132	0.0026	0.0542	0.00018
ELF - 20 m model	10	0.0032	0.364	0.0228	0.3869	0.5197	12.39	1.352	0.0682	396	12.72	0.118	0.0021	0.0502	0.00018
ELF - 20 m model	27	0.0031	0.160	0.0101	0.2873	0.3291	5.47	1.084	0.0549	305	11.86	0.084	0.0009	0.0391	0.00018
ELF - 20 m model	50	0.0030	0.053	0.0033	0.2032	0.2014	1.81	0.811	0.0412	222	11.06	0.058	0.0003	0.0287	0.00018
ELF - 20 m model	100	0.0029	0.005	0.0003	0.1054	0.0926	0.16	0.437	0.0223	117	6.62	0.029	0.0000	0.0153	0.00007
ELF - 20 m model	150	0.0029	0.000	0.0000	0.0567	0.0487	0.01	0.237	0.0121	63	3.58	0.016	0.0000	0.0082	0.00001
ELF - 20 m model	199	0.0028	0.000	0.0000	0.0311	0.0266	0.00	0.129	0.0066	35	1.97	0.009	0.0000	0.0045	0.00000
ELF - 10 m model	1	0.0029	0.079	0.0050	0.0454	0.0799	2.70	0.132	0.0066	43	2.14	0.015	0.0004	0.0053	0.00017
ELF - 10 m model	5	0.0031	0.462	0.0289	0.2812	0.4802	15.73	0.839	0.0419	268	11.63	0.093	0.0026	0.0331	0.00018
ELF - 10 m model	10	0.0031	0.363	0.0228	0.2506	0.4031	12.38	0.783	0.0392	244	11.37	0.081	0.0021	0.0303	0.00018
ELF - 10 m model	27	0.0030	0.160	0.0101	0.1767	0.2344	5.46	0.622	0.0314	181	9.70	0.054	0.0009	0.0230	0.00018
ELF - 10 m model	50	0.0030	0.053	0.0033	0.1198	0.1300	1.81	0.462	0.0234	128	7.09	0.035	0.0003	0.0165	0.00017
ELF - 10 m model	100	0.0029	0.005	0.0003	0.0602	0.0540	0.16	0.248	0.0126	67	3.76	0.017	0.0000	0.0087	0.00007
ELF - 10 m model	150	0.0028	0.000	0.0000	0.0322	0.0278	0.01	0.134	0.0068	36	2.03	0.009	0.0000	0.0047	0.00001
ELF - 10 m model	199	0.0028	0.000	0.0000	0.0176	0.0151	0.00	0.073	0.0038	20	1.12	0.005	0.0000	0.0026	0.00000

Units in mg/L

Bold red text indicates values greater than the GW and SW reference limit.

Bold orange text indicates values greater than the SW reference limit.

Bold purple text indicates values greater than the GW reference limit.

Page 60 MWM-S003-Rev2

a: Chronic value is used for reference.

b: Annual median used for NO₃-N

c: Cr(III) recommended compliance limit is used.

5.7 SCK Fill

Results for the SCK Fill model are shown in Figure 39 and Figure 40 with selected outputs for key years shown in Table 21Figure 18.

The following observations are provided:

- Only the WRS scenario is presented, as it is assumed that all materials are oxidising.
- Sulfate concentrations peak at 327 mg/L.
- Arsenic concentrations are assumed to be 0.2 mg/L, consistent with the other waste rock facilities. Yet, as the system is assumed to be oxygenated, iron concentrations remain low according to PHREEQC modelling (due to precipitation as iron hydroxides). These hydroxides could potentially adsorb excess arsenic.

Page 61 MWM-S003-Rev2




Figure 39. Model results part 1 for the SCK fill.

Page 62 MWM-S003-Rev2




Figure 40. Model results part 2 for the SCK fill.

Page 63 MWM-S003-Rev2

MATAKANUI GOLD LIMITED J-NZ0457-002-R-Rev1

Table 22. Selected model results for the SCK Fill WRS scenario.

	PARAMETER	Al	В	Со	Mn	Мо	NO3-N	Sb	Se	SO4	Sr	U	Zn	V	Cr
SCENARIO	SW REF LIMIT	0.08	-	0.001	-	0.034	2.4	0.074ª	-	500	-	-	0.015	0	0.0033
	GW REF LIMIT	1	-	1	0.4	0.01	11.3	0.02	0.02	250	4	0.03	1.5	0	0.05
	YEAR														
WRS	1	0.0029	0.023	0.0050	0.0798	0.0704	2.09	0.331	0.0170	95	5.00	0.024	0.0005	0.0122	0.00012
WRS	5	0.0031	0.072	0.0156	0.2757	0.2425	6.52	1.143	0.0588	327	11.95	0.082	0.0014	0.0421	0.00018
WRS	10	0.0031	0.056	0.0122	0.2588	0.2267	5.13	1.074	0.0552	304	11.76	0.076	0.0011	0.0392	0.00018
WRS	27	0.0031	0.025	0.0054	0.2091	0.1812	2.26	0.871	0.0445	240	11.19	0.060	0.0005	0.0311	0.00012
WRS	50	0.0030	0.008	0.0018	0.1572	0.1353	0.75	0.656	0.0335	178	9.93	0.044	0.0002	0.0231	0.00004
WRS	100	0.0029	0.001	0.0002	0.0850	0.0728	0.07	0.355	0.0181	95	5.38	0.023	0.0000	0.0124	0.00000
WRS	150	0.0029	0.000	0.0000	0.0461	0.0394	0.01	0.193	0.0098	51	2.92	0.013	0.0000	0.0067	0.00000
WRS	199	0.0028	0.000	0.0000	0.0253	0.0216	0.00	0.106	0.0054	28	1.60	0.007	0.0000	0.0037	0.00000

Units in mg/L

Bold red text indicates values greater than the GW and SW reference limit.

Bold orange text indicates values greater than the SW reference limit.

Bold purple text indicates values greater than the GW reference limit.

Page 64 MWM-S003-Rev2

a: Chronic value is used for reference.

b: Annual median used for NO₃-N

c: Cr(III) recommended compliance limit is used.

6 SUMMARY

The following summary is provided to explain the modelling process, model outcomes, management requirements, and recommendations.

6.1 Overview

The geochemical modelling process for the proposed BOGP ELFs were designed to estimate mineimpacted water and evaluate best-practice construction methods to mitigate environmental risks. The study utilised site-specific data, predictive modelling, and analogue comparisons to develop an understanding of PCOC generation processes under varying conditions. Key components included

- Quantifying sulfur reservoirs, oxidation rates, and contaminant release mechanisms, as well as integrating field-based scaling factors.
- Traditional WRS calibration modelling: Representing a traditional WRS scenario with unrestricted oxygen ingress, leading to sulfide oxidation and relatively low arsenic and iron concentrations in seepage. Models were calibrated with analogue data.
- ELF modelling: Engineered scenarios incorporated reduced oxygen availability, resulting in lower PCOC concentrations yet higher arsenic and iron levels due to limited iron hydroxide formation (sub-oxic conditions).
- Data Sources: Laboratory testing (e.g., ABA, leachate, and kinetic tests) and empirical observations informed model parameters, with key sulfur contents and oxidation rates derived for TZ3 and TZ4 (RSSZ) lithological units.

6.2 Key Findings

The following key findings are presented:

- Sulfur content is a primary driver of poor water quality, with TZ4 and RSSZ materials presenting higher sulfur content, higher release rates, and AMD risks compared to TZ3.
- TZ4 was found to release sulfate at a rate six times higher than TZ3 due to its higher sulfur content and reactivity. Such data confirms the importance of placing these materials away from oxygen in the core of the ELF.
- Identified PCOCs are sulfate, As, Co, Fe, Nitrogen, Sr, Se, Sb, Mo, Mn, Se, Sr, and U.
- A traditional WRS construction process is likely to generate elevated PCOC and prolonged AMD generation. This should be avoided to reduce long-term reliance on water management activities by the construction of an ELF that minimises oxygen ingress.
- Engineered landforms provide notable improvements in water quality by limiting oxygen and water ingress, reducing sulfide oxidation rates, and capping high-sulfur material with nonreactive layers.
- Hydrogeochemical Processes: Short-term contaminant release from SOPs and long-term sulfide oxidation are critical considerations for modelling and management.

Page 65 MWM-S003-Rev2

6.3 Recommendations

This study has identified and recommends the following management opportunities that will minimise the long-term risks to water quality for waste rock storage at the BOGP:

- Proceed with the proposed ELF design, ensuring TZ3 materials encapsulate high-sulfur materials (TZ4) to minimise oxygen ingress.
- Proceed with short lift heights at 5 m height and confirm that grainsize segregation is minimised and that oxygen is reduced to < 5% after 20 m horizontal distance into the ELF and that the oxygen profiles (from oxygen probe monitoring) demonstrate that oxygen ingress is diffusion controlled. Higher heights may be possible if advective oxygen ingress is prevented by engineering controls. Advective oxygen ingress is the driver for higher long term PCOC loads.</p>
- Install cover systems to further mitigate risks as the final landform is created. Consider cover systems to minimise net percolation and oxygen flux as the key drivers of long term PCOC load.
- Establish a comprehensive monitoring program for water quality, oxidation rates, and cover system performance. Adapt management strategies based on observed trends and evolving conditions.
- Continue validating laboratory-to-field scaling factors using site-specific data, particularly for TZ3 and TZ4 materials, to refine long-term predictions.
- Confirm oxygen flux rates to further refine models.

By adopting these recommendations, the project can effectively manage geoenvironmental risks while aligning with best-practice approaches for sustainable waste rock management. As noted by INAP (2024): "while it is true that designing and constructing a mine rock stockpile with a focus on source control can add upfront incremental costs to the project, a proactive approach allows for the ability to effectively understand, plan and reduce long term environmental risks and liabilities for a smaller range of anticipated outcomes".

6.4 Limitations

The model is based on the results of laboratory tests, and on assumptions from analogue data. Performance monitoring is recommended to confirm model expectations. The following assumptions are noted:

- A net percolation rate of 20% is a reasonable estimate. Further work is needed to confirm the
 reliability of this assumption as flow is a key driver of contaminant load. Site-specific trials
 should be undertaken to validate net percolation rates.
- It is assumed that ELF design and construction will limit diffusive oxygen ingress to a depth of 20 m horizontally once the ELF is constructed (and the cover system and rehabilitation is completed). This needs to be managed by MGL to ensure the models are valid. Such details are provided in the ELF Management Plan.
- It is assumed that the scaling approach using column data to forecast sulfate and other PCOC is appropriate to understand geochemical risks for the engineered landforms.

Page 66 MWM-S003-Rev2

- It is assumed that ELF seepage waters will be elevated in nitrate for many decades (> 50 years) and that this would equate to a load of 16.6 mg/kg of nitrogen as (NH₄NO₃).
- It is not possible to model the dynamics of nitrogen speciation accurately, as they are governed
 by site-specific biochemical reactions and oxygen availability. It is assumed that the majority of
 nitrogen will be speciated as nitrate, however, there could be a minor part as nitrite or
 ammoniacal nitrogen.
- The time lag to peak concentrations is influenced by the ELFs geometry, therefore the applied time lag to peak sulfate concentration is an approximate estimate based on analogue empirical data, and simplistic assumptions. However, the time frame is likely to be reasonable to estimate potential environmental risks for the BOGP.
- In-situ precipitation of ferric hydroxides is anticipated. Consequently, certain metals may be sorbed (e.g., As, Cu, Zn) and captured by these minerals, particularly at neutral to alkaline pH where sorption capacities are elevated. While PHREEQC modelling could model this for this case, uncertainty exists around the amount of available iron. Therefore, a conservative approach is adopted, and sorption is not modelled. Sorption may be higher in the outer oxidising zone of the ELF and lower in the core where oxygen is limited.

6.5 Performance Monitoring

The following performance monitoring activities are required to validate model inputs and ensure the effectiveness of the ELFs:

- Confirm the sulfur content of materials placed in the ELF ensuring that lower sulfur TZ3
 materials are placed on the outside of the ELF. Testing should include shake-flask testing to
 validate the quantity of sulfate and nitrogenous compounds present in blasted rock to validate
 model inputs.
- Confirm that advective oxygen ingress is excluded from the core of the ELF by the construction
 of oxygen probes into each lift during construction of the ELF.
- Confirm water quality for ELF seepage aligns with geochemical models including sulfate and nitrate. Update models where significant differences are observed.
- The geochemical model relies on laboratory data and analogue assumptions; field validation is required.
- If performance monitoring indicates unacceptable loads, then adaptive management actions should be considered including additional source control actions (e.g., engineered cover systems), reducing oxidation depth to 10 m into the ELF, a longer period of active treatment and/or the development of passive treatment systems to manage the PCOC concentrations and loads.

Page 67 MWM-S003-Rev2

7 REFERENCES

- AMIRA, 2002. ARD Test Handbook Project P387A Prediction and Kinetic Control of Acid Mine Drainage. AMIRA International Limited. Melbourne, Australia.
- Babbage, 2019. Waste Rock Stack Seepage Assessment. Report prepared for OceanaGold Limited, 12 pp. Available: https://www.orc.govt.nz/media/8437/oceana-gold-new-zealand-limited-consent-application-part-2.pdf.
- Bailey, B., Smith, L.J.D., Blowes, D., Ptacek, C. Smith, L., Sego, D. 2013. The Diavik Waste Rock Project: Persistence of contaminants from blasting agents in waste rock effluent. Applied Geochemistry 36 (2013) pp. 256-270.
- Borden, R.K., Brown, P.L., Sturgess, S., 2022. Geochemical and hydrological evolution of mine impacted waters at the Argyle Diamond Mine, Western Australia. Applied Geochemistry 139 (2022).
- Brown, P. L., Logsdon, M. J., Vinton, B., Schofield, I. & Payne, K. 2014. Detailed characterisation of the waste rock dumps at the Kennecott Utah Copper Bingham Canyon Mine Optionality for Closure. In: Miller, H. & Preuss, L., eds. Eighth Australian Workshop on Acid and Metalliferous Drainage, May 2014. Adelaide, South Australia. 1-12.
- Canadian Federal Environmental Quality Guidelines, 2020. Canadian Environmental Protection Act, 1999. Federal Environmental Quality Guidelines, Strontium, 10 pp.
- Cox, L., MacKenzie, D. J., Craw, D., Norris, R. J., & Frew, R. (2006). Structure and geochemistry of the Rise & Shine Shear Zone mesothermal gold system, Otago Schist, New Zealand. New Zealand Journal of Geology and Geophysics, 49(4), 429-442
- Dockrey, J., Martin, A., Stockwell, J., Kennedy, C., Day, S., 2015. Role of Nitrate in the Remobilization and Attenuation of Selenium in Coal Mine Waste Environments. MEND Report 10.3. The Mine Environment Neutral Drainage Program.
- Fala, O., Aubertin, M., Molson, J., Bussière, B., Wilson, G.W., Chapuis, R., Martin, V., 2003. Numerical Modelling of Unsaturated Flow in Uniform and Heterogeneous Waste Rock Piles. In "Proceedings of the Sixth International Conference on Acid Rock Drainage", Cairns, Australia, 14-17 July (Eds. T Farrell and G Taylor), pp. 895 -902. Australian Institute of Mining and Metallurgy, Carlton, Victoria.
- Golder, 2011a. Macraes Phase III Project Groundwater Contaminant Transport Assessment Deepdell Creek, North Branch Waikouaita River and Murphy's Creek Catchments. Report 0978110-562-R006 vD. Appendix 14 to the OceanaGold AEE. 93 pp. https://www.orc.govt.nz/consents-and-compliance/current-notified-applications/archived-applications/oceana-gold-new-zealand-limited-application-rm10351

Page 68 MWM-S003-Rev2

- INAP, 2020. Rock Placement Strategies to Enhance Operational and Closure Performance of Mine Rock Stockpiles. Phase 1 Work Program Review, Assessment & Summary of Improved Construction Methods. Report prepared for the International Network for Acid Prevention (INAP) by Okane and Earth Systems. 105 pp.
- INAP, 2024. ARD/AMD Source Control for Mine Rock Stockpiles Phase 3. Report prepared for the International Network for Acid Prevention (INAP) by Okane. 53 pp: https://www.inap.com.au/wp-content/uploads/2024-6-Jun-27-1043-222-001-Source-Control-for-MRS-Ph-3-Rev-0.pdf.
- Kempton, H. (2012). A review of scale factors. In Proceedings of the 9th International Conference on Acid Rock Drainage (ICARD), Ottawa, ON, Canada
- Kōmanawa Solutions Ltd (KSL), 2025. Rise & Shine Gold Project Surface Water & Catchment Existing Environment & Effects Assessment DRAFT. Matakanui Gold Limited. RN: Z24002BOG2-Rev2.
- Linklater, C., Watson, A., Hendry, A., Chapman, J., Crosbie, J., Defferrard, P., Pit Lake Water Quality Modelling at Century Mine. Ninth Australian Workshop on Acid and Metalliferous Drainage, November 2017, Burnie, Tasmania, pp 206 214.
- Lopez, D.L., Smith, L., & Beckie, R., 1997. Modelling water flow in waste rock piles using kinematic wave theory. In proceedings of the Fourth International Conference on Aci rock Drainage, Vancouver, B.C., Canada, May 31 June 6, 1997. Vol. 2, pp. 497 513.
- Mackenzie, A., 2010. Characterization of Drainage Chemistry in Fanny Creek Catchment and Optimal Passive AMD Treatment Options for Fanny Creek. A thesis submitted in partial fulfilment of the requirements for the degree of Master of Science in Geology, University of Canterbury.
- Mahmood, F.N., Barbour, S.L., Kennedy, C., Hendry, M.J., 2017. Nitrate release from waste rock dumps in the Elk Valley, British Columbia, Canada. Science of the Total Environment 605–606 (2017) 915–928
- Malmström, M. E., Destouni, G., Banwart, S. A., & Strömberg, B. H. (2000). Resolving the scale-dependence of mineral weathering rates. Environmental science & technology, 34(7), 1375-1378.
- Meiers, G, 2020. A Case Study of the Influence of Shorter Tips in Mine Rock Storage on Internal Air Flow Capacity. BC-MEND Metal Leaching and Acid Rock Drainage Workshop. December 1 -3, 2020 Vancouver, British Columbia, Canada Zoom Conference.
- MWM, 2024a. Macraes Mine Phase 4.3 Environmental Geochemistry Assessment OceanaGold Macraes Mine Site. Mine Waste management report J-NZ0229-004-R-Rev0 dated 28 February 2024. Oceana Gold (New Zealand) Limited Macraes Mine Application No. RM24.184 Appendix 8: https://www.orc.govt.nz/consents-and-compliance/current-notified-applications/oceana-gold-new-zealand-limited-rm24184/
- MWM, 2024b. BWWRS Geochem Model. Mine Waste Management Report J-NZ0229-M-009-Rev0.

 Oceana Gold (New Zealand) Limited Macraes Mine Application No. RM24.184 Appendix 31

 Annexure 03. https://www.orc.govt.nz/consents-and-compliance/current-notified-applications/oceana-gold-new-zealand-limited-rm24184/

Page 69 MWM-S003-Rev2

- MWM, 2025a. Factual Report: Geoenvironmental Hazards: Bendigo-Ophir Gold Project. Mine Waste Management Report J-NZ0233-008-R-Rev1 for Matakanui Gold Limited.
- MWM, 2025b. Water and Load Balance Model: Bendigo-Ophir Gold Project. Mine Waste Management Report J-NZ0266-016-Rev0 for Matakanui Gold Limited.
- MWM, 2025c. Net Percolation Assessment for the Proposed Bendigo-Ophir Gold Project Mine Waste Storage Facilities. Mine Waste Management Report J-NZ0455-001-M-Rev1 for Matakanui Gold Limited.
- MWM, 2025d. Factual Report: Column Leach Test (Interim): Bendigo-Ophir Gold Project. Mine Waste Management Report J-NZ0233-015-R-Rev0 for Matakanui Gold Limited.
- MWM, 2025e. Water Treatment Study, Bendigo-Ophir Gold Project. Mine Waste Management Report J-NZ0464-002-R-Rev0 for Matakanui Gold Limited.
- MWM, 2025f. Engineered Landform Design Philosophy. Mine Waste Management Report J-NZ0233-009-M-Rev1 for Matakanui Gold Limited.
- Navarro-Valdivia, L., Weber, P.A., Tuck, J., Hillman, C., 2023. Natural Decay of ANFO-Derived Nitrate in Pit Lakes: Insights from the Golden Bar Pit Lake, Macraes Gold Mine, Otago, New Zealand. 2023. AuslMM New Zealand Branch Annual Conference. Available: https://www.ausimm.com/news-and-media/community-news/new-zealand-branch-2023-annual-conference-presentations--abstracts
- Navarro-Valdivia, L., Weber, P., Hillman, C., 2024. Forecasting Water Quality from Waste Rock Stacks

 A Relationship with Height. Paper presented at the AuslMM New Zealand Branch Annual
 Conference 19-21 August 2024, Wellington.
- Oceana Gold (NZ) Ltd 2020. Deepdell North Stage III Project Assessment of Environmental Effects
 Part 1. Dated 29 January 2020, 252 pp. https://www.orc.govt.nz/consents-and-compliance/current-notified-applications/oceana-gold-new-zealand-limited-rm20024/
- Parkhurst, D. L., & Appelo, C. A. J., 2013. Description of input and examples for PHREEQC version 3—a computer program for speciation, batch-reaction, one-dimensional transport, and inverse geochemical calculations. US geological survey techniques and methods, 6(A43), 497.
- Pope, J., Weber, P.A., Olds, W.E., 2016. Control of acid mine drainage by managing oxygen ingress into waste rock dumps at bituminous coal mines in New Zealand. Proceedings of IMWA 2016, Mining Meets Water Conflicts and Solutions. Carsten Drebenstedt, Michael Paul (Eds.) Leipzig, Germany, July 11-15, 2016, p 363-371.
- Price, W.A., 1997. Guidelines and Recommended Methods for the Prediction of Metal leaching and Acid Rock Drainage at Minesites in British Columbia.
- Ritchie, A.I.M., 1994. The Waste Rock Environment. Chapter 5: p133-161. In Short-course Handbook on Environmental Geochemistry of Sulfide Mine-Wastes, Mineralogical Association of Canadam Waterloo, Ontario, Eds: J.L. Jambor and D.W. Blowes.

Page 70 MWM-S003-Rev2

- Rekker, J., 2025. Rise & Shine Gold Project Surface Water & Catchment Existing Environment & Effects Assessment (Report Series No. Z24002BOG2-Rev0). Kōmanawa Solutions Ltd, Christchurch.
- Rekker, J. H., & Dumont, M. 2025. Rise & Shine Gold Project Groundwater Existing Environment & Effects Assessment. Kōmanawa Solutions Client Report No. Z24002BOG1. Kōmanawa Solutions Ltd, Christchurch.
- Ryder, G.I. 2025. Recommended water quality compliance limits for the Bendigo-Ophir Gold Project.

 Prepared for Matakanui Gold Limited by Greg Ryder Consulting.
- Santana, 2024. Bendigo-Ophir Pre-Feasibility Study. Report prepared by Matakanui Gold Limited, 330 pp.
- Schmidt, J.W., Moffett, D., 1979. Overview of Canadian environmental research in the uranium mining industry. Environment Canada, Environmental Protection Service, Technology Transfer Seminar Notes, Uranium Mining and Environment, April 11, 1979, Vancouver.
- Weber, P.A., Olds, W.O., Crombie, F.H., Thomas, D.G., Pope, J., Pizey, M.H., 2013. Acid mine drainage investigations at the Reddale Coal mine, Reefton, New Zealand. New Zealand AusIMM Conference, Nelson 25 28 August, 2013, 535 545.
- Weber, P.A., Olds, W.E., Bird, B., Pearce, J., 2015. Forecasting long term water quality at closure for current mining operations. New Zealand Annual AuslMM Branch Conference, Dunedin, 31 August 2 September 2015, pp 495-505.
- Weber, P.A., McKeown, M., Christensen, D., Mueller, S., O'Kane, M., Bird, B., 2017. Forecasting long term water quality after closure: Boliden Aitik Cu mine. New Zealand Annual AuslMM Branch Conference, Christchurch, 10 13 September, p 353 361.
- Weber, P.A., Reid, N., Robson, T., 2021. Nitrate and AMD: An Opportunity to Innovate? Virtual ICARD 2021 | Meeting Challenge through Innovation. 23 September 2021. Available: https://www.inap.com.au/2021-virtual-icard-conference/
- Wilson, G.W., 2008. Why are we still battling ARD. In "Proceedings of the Sixth Australian Workshop on Acid and Metalliferous Drainage", Burnie, Tasmania. 15-18 April 2008. (Eds LC Bell, BMD Barrie, B Baddock, and RW MacLean) pp. 101 112 (ACMER: Brisbane).

Page 71 MWM-S003-Rev2

8 **LIMITATIONS**

Attention is drawn to the document "Limitations", which is included in Appendix B of this report. The statements presented in this document are intended to provide advice on what the realistic expectations of this report should be, and to present recommendations on how to minimise the risks associated with this project. The document is not intended to reduce the level of responsibility accepted by Mine Waste Management, but rather to ensure that all parties who may rely on this report are aware of the responsibilities each assumes in doing so.

Page 72 MWM-S003-Rev2

APPENDIX A ABBREVIATIONS

ABBREVIATION	DEFINITION
ABA	Acid base accounting
AMD	Acid and metalliferous drainage, which can also include low metal saline drainage
ANFO	Ammonium nitrate fuel oil (explosive)
ANC	Acid neutralisation capacity
BOGP	Bendigo-Ophir Gold Project
CIL	Carbon in Leach
CIT	Come in Time
CLT	Column Leach Test
CSM	Conceptual site model
DOC	Dissolved organic carbon
ELF	Engineered Landform
INAP	International Networks for Acid Prevention
LCM	Loose cubic metres
LOM	Life of mine
MIW	Mine impacted water
MPA	Maximum potential acidity
MGL	Matakanui Gold Limited
Mt	Million tonnes
MWM	Mine Waste Management Limited
NAF	Non-acid forming
NAPP	Net acid production potential
NP	Net percolation
PAF	Potentially acid forming
PCOC	Potential constituents of concern
PFS	Pre-feasibility study
QA/QC	Quality assurance and quality control
RAS	Rise and Shine
ROM	Run of mine
RSSZ	Rise and Shine Shear Zone
SCK Fill	Shepherds Creek Fill
SOP	Stored Oxidation Products
Srex	SRX
Srex East	SRE
TSF	Tailings storage facility

ABBREVIATION	DEFINITION
TSS	Total suspended solids
TZ3	Textural Zone 4 of the Otago Schist
TZ4	Textural Zone 4 of the Otago Schist
WELF	West ELF
WRS	Waste Rock Stack

APPENDIX B LIMITATIONS

This Document has been provided by Mine Waste Management Ltd (MWM) subject to the following limitations:

This Document has been prepared for the particular purpose outlined in MWM's proposal and no responsibility is accepted for the use of this Document, in whole or in part, in other contexts or for any other purpose.

The scope and the period of MWM's services are as described in MWM's proposal, and are subject to restrictions and limitations. MWM did not perform a complete assessment of all possible conditions or circumstances that may exist at the site referenced in this Document. If a service is not expressly indicated, do not assume it has been provided. If a matter is not addressed, do not assume that any determination has been made by MWM in regards to it.

Conditions may exist which were undetectable given the limited nature of the enquiry MWM was retained to undertake with respect to the site. Variations in conditions may occur between investigatory locations, and there may be special conditions pertaining to the site which have not been revealed by the investigation and which have not therefore been taken into account in the Document. Accordingly, additional studies and actions may be required.

In addition, it is recognised that the passage of time affects the information and assessment provided in this Document. MWM's opinions are based upon information that existed at the time of the production of this Document. It is understood that the services provided allowed MWM to form no more than an opinion of the actual conditions of the site at the time the site was reviewed and cannot be used to assess the effect of any subsequent changes in the quality of the site, or its surroundings, or any laws or regulations.

Any assessments made in this Document are based on the conditions indicated from published sources and the investigation described. No warranty is included, either express or implied, that the actual conditions will conform exactly to the assessments contained in this Document.

Where data supplied by the client or other external sources, including previous site investigation data, have been used, it has been assumed that the information is correct unless otherwise stated. No responsibility is accepted by MWM for incomplete or inaccurate data supplied by others.

MWM may have retained subconsultants affiliated with MWM to provide services for the benefit of MWM. To the maximum extent allowed by law, the Client acknowledges and agrees it will not have any direct legal recourse to, and waives any claim, demand, or cause of action against, MWM's affiliated companies, and their employees, officers and directors.

This Document is provided for sole use by Matakanui Gold Limited and is confidential to it and its professional advisers. No responsibility whatsoever for the contents of this Document will be accepted to any person other than the Client. Any use which a third party makes of this Document, or any reliance on or decisions to be made based on it, is the responsibility of such third parties. MWM accepts no responsibility for damages, if any, suffered by any third party as a result of decisions made or actions based on this Document.

MWM acknowledges that this report will be relied on by a Panel appointed under the Fast Track Approvals Act 2024 and these disclaimers do not prevent that reliance.





Water Treatment Study

Bendigo-Ophir Gold Project

9 October 2025

J-NZ0464-002-R-Rev2





Water Treatment Study

Bendigo-Ophir Gold Project

Document Number: J-NZ0464-002-R-Rev2

Document Date: 9 October 2025

Prepared for:

Matakanui Gold Limited

15a Chardonnay Street, Cromwell, 9310

Prepared by:

Mine Waste Management Limited

 $5 \; \text{Sir William Pickering Drive, Burnside, Christchurch 8053, New Zealand} \\$

+64 3 242 0221

www.minewaste.com.au

REVISION	DATE	AUTHOR	RECORD OF REVIEW
RevA	4-3-25	LN/PW	PW
RevB	7-3-25	LN/PW	PW
RevC	22-6-25	PW	PW
Rev0	5-8-25	PW	PW
Rev1	15-9-25	PW	PW
Rev2	9-10-25	PW	PW

EXECUTIVE SUMMARY

Mine Waste Management Limited (MWM) has been engaged by Matakanui Gold Limited (MGL) to provide guidance on water treatment for Mine Impacted Water (MIW) for the proposed Bendigo-Ophir Gold Project (BOGP).

Objectives of this Study

The objectives of this report are to:

- Review the expected water treatment requirements during the Active Closure and Post Closure
 Phases of the BOGP when treated MIW will be released from site.
- Provide guidance on the Water Treatment Plant (WTP) that will be operational during the Active Closure Phase of the BOGP.
- Provide guidance on the Passive Treatment System(s) (PTS) that will be required during the Post Closure Phase of the BOGP.

Findings

The water and load balance model (WLBM) and other studies indicate that the BOGP needs to focus on the management and treatment of MIW that will contain potential constituents of concern (PCOC). Specifically:

- Water management to minimise the amount of water that requires treatment during the closure phases.
- Treatment of MIW by a WTP within the Shepherds Creek catchment during the active closure phase until PTS can be successfully established after a number of decades (~ 50 years).
- Partial passive treatment of the SRX Pit Lake overflow in the Rise and Shine catchment.
- PTS are likely to be operational for many decades once installed.

The following PCOC may require treatment by the WTP and PTS to achieve the proposed water quality limits for the BOGP (Ryder, 2025):

- Nitrogenous compounds (N) that include nitrate (NO₃) and ammoniacal-N (Amm-N).
- Sulfate (SO₄).
- Metals and metalloids that may include Aluminium (Al), arsenic (As), cadmium (Cd), cobalt
 (Co), copper (Cu), chromium (Cr), iron (Fe), manganese (Mn), molybdenum (Mo), nickel (Ni),
 lead (Pb), antimony (Sb), selenium (Se), strontium (Sr), uranium (U), and zinc (Zn)
- Cyanide (CN) within the tailings water.

Management

Water management during the Operational Phase of the BOGP will involve discharge of only episodic runoff from haul roads and ELF surfaces. All other MIW (e.g., landform seepage) will be collected, used, and stored on site within the TSF. In the Active Closure Phase and Post Closure Phase, MIW will be treated and discharged to the receiving environment.

Order of magnitude (OoM) studies indicate that active and passive water treatment can achieve closure water quality objectives as defined by Ryder (2025), although further feasibility studies are required to confirm treatment performance and the ability to transfer from active to passive treatment.

Project Description

MGL is proposing to establish the BOGP, which comprises gold mining operations, processing operations, ancillary facilities and environmental mitigation measures on Bendigo and Ardgour Stations in the Dunstan Mountains of Central Otago. The project site is located approximately 20 km north of Cromwell and will have a maximum disturbance footprint of 550 hectares.

The total Mineral Resource Estimate for the BOGP using a 0.5 g/t cut-off for open pit and 1.5 g/t for underground is 34.3 Mt at 2.1 g/t for 2.34 M oz (MGL, 2025). The Bendigo-Ophir resources occur in four deposits: Come in Time (CIT), Rise and Shine (RAS), Srex (SRX), Srex East (SRE). The majority of identified mineral resources are located within the RAS deposit. Three primary geological units are recognised at site:

- RSSZ Rise and Shine Shear Zone
- TZ3 Lower Greenschist facies Textural Zone 3 rocks of the Otago Schist
- TZ4 Upper Greenschist facies Textural Zone 4 rocks of the Otago Schist

The proposed BOGP will include the following components:

- Open pits targeting the RAS, SRX, SRE, and CIT deposits.
- An underground mine targeting the RAS deposit.
- Three ex-pit engineered landforms (ELFs) Shepherds ELF, SRX ELF, and West ELF (WELF).
- Two in-pit landforms (backfill) CIT and SRE¹.
- Plant and processing area, where CIL extraction technologies will be used as part of the ore recovery process. This includes the Shepherds Creek Fill (SCK Fill).
- A tailings storage facility (TSF) and TSF Embankment.
- Other ancillary support services / structures (e.g., roads, water management infrastructure, water treatment plants, etc).

¹ Note: SRE Pit is backfilled by the SRX ELF.

Further details are available in MWM (2025c).

Managed for TSS separate to the active WTP. At closure rehabilitated surfaces are assumed

treatment. Passive treatment is required. 20% Net percolation (MWM, 2025b)

to be suitable for discharge with TSS

management.

Further details are available in MWM (2025c). It is assumed this water will not require active

Water Treatment

During the Active Closure Phase, water treatment is required by a WTP once the project switches from a process of internal water management for MIW (during operations) to discharge of MIW from site after closure of the mine. WLBM results indicates that the WTP can be replaced by PTS within decades of mining cessation, which then defines the commencement of the Post Closure Phase.

Flow Rates

Flow rates that require treatment are presented in Table E1. Flow rates are based on a net percolation (NP) rate of 20% of rainfall. It is proposed that a NP rate of 20% may be achievable, with appropriate engineering controls (i.e., an engineered cover system).

MINE DOMAIN	WTP DESIGN CRITERIA (L/s)	PTS (L/s)	COMMENTS
Shepherds ELF	4	4	20% Net percolation (MWM, 2025b)
SRX ELF ^{1,2}	-	1	20% Net percolation (MWM, 2025b)
West ELF ²	1	1	20% Net percolation (MWM, 2025b)
Shepherds TSF	13.4	3	Flow is expected to be ~13.4 L/s decreasing to 3 L/s after 5 years (MWM, 2025c).
RAS Underground Portal	6	6	Flow from the RAS Underground is not expected for 20-30 years after closure (MWM, 2025c).

1.5

8

1

Table E1: Estimated average water quantity per mine domain.

1.5

1

Active Water Treatment

Non-NMD impacted

CIT Pit Backfill

SRX Pit

SCK Fill ²

water

Active treatment is expected for a number of decades (~ 50 years). During this period, the BOGP processing plant would be disestablished and the passive treatment system established. Process Flow (2025) note that the WTP will include the following processes:

- Surge sump
- Pontoon mounted pumps for plant feed
- Metal hydroxide precipitation and settling
- Gypsum precipitation and settling

^{1.} Active treatment for SRX ELF and SRX Pit is not anticipated.

Flow rates rounded up to 1 L/s

- Ettringite precipitation and settling
- · Carbonation and pH trimming
- · Treated water sump
- Sludge management

Other processes that will likely be needed in addition to the active WTP are:

- Cyanide destruct on the Shepherds TSF influent stream.
- Potential additional nitrate removal after WTP via biological processes.

Process Flow (2025) indicate that the proposed water quality objectives (Ryder, 2025) can be achieved, although further work is required to develop the OoM study to a feasibility study (FS) level. Further details are provided in Appendix B. The WTP will operate until passive treatment systems can be installed to successfully treat MIW.

Passive Treatment System

Based on the identified PCOC for the BOGP a multi-stage passive treatment system is expected. This would include:

- Sediment management to mitigate any residue sediment and prevent the PTS from being overwhelmed with sediment.
- Oxidation to encourage Fe(OH)₃ precipitation and adsorption of metals such as As and V.
- Anaerobic treatment to remove nitrate, reduce sulfate concentrations, and precipitate metals as sulfides.
- A polishing pond to remove secondary contaminants generated in the anaerobic treatment stage (e.g., sulfide (HS-), ammoniacal nitrogen, and low dissolved oxygen).

Preliminary treatment efficiencies for the PTS are provided in Table E2. These efficiencies will require validation once mining commences, and MIW is available for trials. Data highlighted in yellow have lower confidence and further work is needed to confirm the passive treatment systems will be appropriate.

Table E2: PTS Treatment Efficiencies

PARAMETER	REMOVAL EFFICIENCIES 1
Calcium	-43.2%
Magnesium	8%
Aluminium	83.3%
Arsenic	99% 2
Iron	99.1%
Nickel	97.9%
Zinc	99.8%
Manganese	86.4%
Cadmium	85.2 ³

PARAMETER	REMOVAL EFFICIENCIES 1
Cobalt	98.4%
Copper	85.6 ³
Uranium	74% ³
Vanadium	90% 8
Other metals	98% 4
Sulfate	30% ⁵
Nitrate nitrogen	99%
Ammoniacal nitrogen	99% ⁶
Cyanide	90% 7

- 1. where data are taken from Table 9 for MSR and limestone is assumed to be part of the treatment media.
- 2. where data are taken from Hayton et al. (2022) = 95% removal with additional Fe to increase As removal to 99% (e.g., Raven et al., 1998).
- 3. where data are obtained from Trumm et al. (2024).
- 4. where data are assumed to be comparable to other metals removed by a MSR (Table 9).
- 5. Based on 30% removal as determined from literature (Figure 21).
- 6. Assumed to be 99% to be in alignment with nitrate removal efficiencies. Further work is required.
- 7. Based on studies by Álvarez et al. (2004).
- 8. Zhang et al. (2022).

TABLE OF CONTENTS

1	Ir	ntroduction	1
	1.1	Background	1
	1.2	Mine Plan	2
	1.3	Report Objectives	2
2	Р	Project Description	4
	2.1	Introduction	4
	2.2	Surface Water	5
3	M	fline Impacted Water	7
	3.1	Baseline Studies	7
	3.2	Geoenvironmental Hazards	7
	3.3	MIW Summary	7
4	Р	Proposed Compliance Monitoring	8
	4.1	Mine Impacted Water	8
	4.2	Proposed Water Quality Limits	8
5	F	low Rates	11
	5.1	Average Flow Rates	11
	5.2	Model Flow Rates	12
	5	.2.1 ELF and TSF Flows	12
	5	.2.2 RAS Pit and RAS Underground	12
	5	.2.3 SRX Pit Void	13
	5	.2.4 CIT Backfill Pit	14
6	V	Vater Quality: Active water Treatment	16
	6.1	Shepherds TSF Water Quality	16
	6.2		
	6.3	RAS Underground	18
7	Р	rinciples of Water Treatment	20
	7.1	Overview	
	7.2	Treatment Technology Selection: Active Treatment versus Passive Treatment	21
	7.3		
8	Α	ctive Closure Phase: Water Treatment Plant	
	8.1	Introduction	
	8.2		
	8.3		
	8.4	•	
9	Р	Post Closure Phase: Passive Treatment Systems	
	9.1	Introduction	
	9.2		
	9	.2.1 Aeration	
		9.2.1.1 Trompe	27

	9.2.1	.2 Mechanical Aeration	27
	9.2.1	.3 Bubble Diffusers	28
9.	2.2	Ferric Treatment of High Arsenic MIW	28
9.	2.3	Vertical Flow Reactor Technologies	28
9.	2.4	Summary	29
9.3	Ae	robic Passive Treatment of TSF seepage: Cyanide	29
9.4	An	aerobic Passive Treatment of Mine Impacted Water	29
9.	4.1	Anaerobic Treatment of MIW	29
9.	4.2	Enhanced Passive Treatment Systems of MIW	31
9.5	Se	condary Contaminants	33
9.	5.1	Chemical Oxidation	33
9.	5.2	Zero Valent Iron	33
9.	5.3	Adsorbents	34
9.6	Pa	ssive Treatment System Efficiencies	34
9.	6.1	Arsenic and Iron Treatment Efficiency	35
9.	6.2	Sulfate Treatment Efficiency	35
9.	6.3	Nitrogen Treatment Efficiency	36
9.	6.4	Metals	36
10	Furth	er Work	38
10.1	•	Transition to the Post Closure Phase	38
10.2	2 .	Active Water Treatment Plant	38
10.3	3	Passive Treatment System	38
11	Refe	rences	40
12	Limit	ations	44
Appen	dix A	Abbreviations	
Appen	dix B	WTP OoM Design Report	
Appen	dix C	Limitations	

LIST OF TABLES

Table 1. BOGP Mine Plan	2
Table 2. Proposed surface water quality compliance limits for the BOGP.	8
Table 5: Proposed groundwater quality compliance limits for the BOGP	10
Table 3: Estimated average water quantity per mine domain	11
Table 4: TSF seepage water quality (Closure).	16
Table 5. Water Quality Data (Year 27) for WTP design – 20 m Oxygen Exclusion Model	17
Table 6. RAS Underground water quality (Year 27)	18
Table 7. General Guidelines for Selection Active versus Passive Treatment	21
Table 9. MSR Treatment Efficiencies	37
Table 9. PTS Treatment Efficiencies	39
LIST OF FIGURES	
Figure 1. BOGP mineral permit boundaries showing MEP60311 and PEP60882	5
Figure 2. Bendigo-Ophir Gold Project area and water quality monitoring sites	
Figure 3: ELF and TSF seepage flow rates.	12
Figure 4: RAS Pit Void model results – water volume and level	13
Figure 5: RAS Pit Void model results – underground portal discharge.	13
Figure 6: SRX Pit Void model results – water volume and level	14
Figure 7: SRX Pit Void model results - overflow rate	14
Figure 8: CIT Pit Void model results – water volume and level.	15
Figure 9: CIT Pit Void model results – outflow rates	15
Figure 10. Hierarchy of MIW Treatment Controls	20
Figure 11. Periodic table for passive treatment.	26
Figure 12. A simple trompe schematic	27
Figure 13. Arsenic and antimony loads – Globe Pit Lake, Reefton.	28
Figure 14. Energy yield and common oxidation-reduction (redox) sensitive species	30
Figure 15. The Redox Ladder	30
Figure 16. Globe Progress field trials	31
Figure 17. Globe Progress field trials	31
Figure 18. E-PTS bioreactor effluent sulfate concentrations.	32
Figure 19. Nitrate treatment concentrations in the laboratory reactor effluent.	32
Figure 20. Sulfide concentrations following treatment.	34
Figure 21. Performance of field-scale bioremediation systems for sulfate removal	35
Figure 22. Nitrate + nitrite nitrogen concentration in the bioreactor effluents	36
Figure 23. Ammoniacal nitrogen concentration in bioreactor effluents	36

1 INTRODUCTION

Mine Waste Management Limited (MWM) has been engaged by Matakanui Gold Limited (MGL) to provide guidance on water treatment for Mine Impacted Water (MIW) for the proposed Bendigo-Ophir Gold Project (BOGP).

The water and load balance model (WLBM) (MWM, 2025c) indicates that the BOGP needs to focus on the management and treatment of MIW that will contain potential constituents of concern (PCOC). Specifically:

- Water management to minimise the amount of water that requires treatment during the closure phases.
- Treatment of MIW by a WTP within the Shepherds Creek catchment during the active closure phase until PTS can be successfully established after a number of decades (~ 50 years).
- Partial passive treatment of the SRX Pit Lake overflow in the Rise and Shine catchment.
- PTS are likely to be operational for many decades once installed.

1.1 Background

MGL is proposing to establish the BOGP, which comprises gold mining operations, processing operations, ancillary facilities and environmental mitigation measures on Bendigo and Ardgour Stations in the Dunstan Mountains of Central Otago. The project site is located approximately 20 km north of Cromwell and will have a maximum disturbance footprint of 550 hectares.

The total Mineral Resource Estimate for the BOGP using a 0.5 g/t cut-off for open pit and 1.5 g/t for underground is 34.3 Mt at 2.1 g/t for 2.34 M oz (MGL, 2025). The Bendigo-Ophir resources occur in four deposits: Come in Time (CIT), Rise and Shine (RAS), Srex (SRX), Srex East (SRE). The majority of identified mineral resources are located within the RAS deposit. Three primary geological units are recognised at site:

- RSSZ Rise and Shine Shear Zone
- TZ3 Lower Greenschist facies Textural Zone 3 rocks of the Otago Schist
- TZ4 Upper Greenschist facies Textural Zone 4 rocks of the Otago Schist

The proposed BOGP will include the following components:

- Open pits targeting the RAS, SRX, SRE, and CIT deposits.
- An underground mine targeting the RAS deposit.
- Three ex-pit engineered landforms (ELFs) Shepherds ELF, SRX ELF, and West ELF (WELF).
- Two in-pit landforms (backfill) CIT and SRE².
- Plant and processing area, where CIL extraction technologies will be used as part of the ore recovery process. This includes the Shepherds Creek Fill (SCK Fill).

Page 1 MWM-S003-Rev2

² Note: SRE Pit is backfilled by the SRX ELF.

- A tailings storage facility (TSF) and TSF Embankment.
- Other ancillary support services / structures (e.g., roads, water management infrastructure, water treatment plants, etc).

1.2 Mine Plan

The proposed mine plan is shown in Table 1 as a schedule of activities. The transition from active treatment to passive treatment is expected to be in the order of decades and will require further studies during the operational phases of the proposed BOGP.

Table 1. BOGP Mine Plan

MONTH	YEAR	MINING PHASE	DESCRIPTION OF PHASE
		Pre-startup	Detailed design phase
0 to 6	0 to 0.5	Startup	Pioneering / RAS Pre-Strip, Initial Jean Creek Silt Pond, earthworks at process plant.
6 to 24	0.5 to 2	Project Development	Construction of process plant, TSF, Shepherds Silt Pond, North Diversion Channel, Commissioning, mining RAS pre- strip (Pre-strip ends month 19).
		Operations	
25 to 54	3 to 4.5	RAS pit mining on its own	Operations (pit ore production in month 20. UG Development begins month 54)
54 to 72	4.5 to 5	RAS pit with UG development	Operations (UG Ore production begins month 70)
72 to 132	6 to 11	RAS pit plus RAS UG	Operations (UG Ore production months 70 to 150)
		RAS Pit plus RAS UG plus CIT Pit	Operations (CIT Pit mined months 102 to 114)
		RAS Pit plus RAS UG, plus CIT backfilled, plus Srex	Operations (Srex Pit mined months 145 onwards)
120 - 160	10 to 13.3	RAS UG continues on its own with CIT and Srex open pit feeds	Operations (all mining halted month 160)
		Closure	
160 - 372	11 to 31	Active Closure ¹	All mining halted. Active closure of pits, TSF, and wider site, plus setup of active water treatment plant (option).
372 -	31 onwards	Post-Closure	Passive treatment and maintenance

TSF = Tailings Storage Facility; UG = Underground

1.3 Report Objectives

The objectives of this report are to:

Review the expected water treatment requirements during the Active Closure and Post Closure
 Phases of the BOGP when treated MIW will be released from site.

Page 2 MWM-S003-Rev2

^{1.} Presented as two decades as part of the Pre-feasibility Mine Plan

- Provide guidance on the Water Treatment Plant (WTP) that will be operational during the Active Closure Phase of the BOGP.
- Provide guidance on the Passive Treatment System(s) (PTS) that will be required during the Post Closure Phase of the BOGP.
- Provide recommendations to advance the current studies from an order of magnitude (OoM)
 desktop assessment to a feasibility Study (FS) stage.

Page 3 MWM-S003-Rev2

2 PROJECT DESCRIPTION

This section provides an introduction to the BOGP.

2.1 Introduction

MGL is proposing to establish the BOGP (Figure 1), which comprises gold mining operations, processing operations, ancillary facilities and environmental mitigation measures on Bendigo and Ardgour Stations in the Dunstan Mountains of Central Otago. The project site is located approximately 20 km north of Cromwell and will have a maximum disturbance footprint of 550 hectares.

The total Mineral Resource Estimate for the BOGP using a 0.5 g/t cut-off for open pit and 1.5 g/t for underground is 34.3 Mt at 2.1 g/t for 2.34 M oz (MGL, 2025). The Bendigo-Ophir resources occur in four deposits: Come in Time (CIT), Rise and Shine (RAS), Srex (SRX), Srex East (SRE). The majority of identified mineral resources are located within the RAS deposit. Three primary geological units are recognised at site:

- RSSZ Rise and Shine Shear Zone
- TZ3 Lower Greenschist facies Textural Zone 3 rocks of the Otago Schist
- TZ4 Upper Greenschist facies Textural Zone 4 rocks of the Otago Schist

The resources will be mined by open pit methods at each deposit within the project site, with underground mining methods also proposed to be utilised at RAS to access the deeper gold deposits. The majority of the mining activities, ancillary facilities and associated infrastructure will be located in the Shepherds Valley with non-operational infrastructure located on the adjoining Ardgour Terrace. The BOGP also involves the taking of groundwater from the Bendigo Aquifer for use in mining-related activities and the realignment of Thomson Gorge Road via Ardgour Station.

The following mine facilities are proposed (Figure 2):

- Open pits targeting the RAS, SRX, SRE, and CIT deposits.
- An underground mine targeting the RAS deposit.
- Three ex-pit engineered landforms (ELFs) Shepherds ELF, SRX ELF, and West ELF (WELF).
- Two in-pit landforms (backfill) CIT and SRE³.
- Plant and processing area, where CIL extraction technologies will be used as part of the ore recovery process.
- A tailings storage facility (TSF) and TSF Embankment.
- Other ancillary support services / structures (e.g., roads, water management infrastructure, water treatment plants, etc).

These facilities will be placed in the catchment of Shepherds and Bendigo creeks. Understanding baseline water quality (surface and groundwater) is important to enable the establishment of site-specific water quality compliance criteria for any resource consent that may be granted in the future.

_

Page 4 MWM-S003-Rev2

³ Note: SRE Pit is backfilled by the SRX ELF.




Figure 1. BOGP mineral permit boundaries showing MEP60311 and PEP60882.

2.2 Surface Water

The project area covers several catchments and sub-catchments (Figure 2), including:

- Shepherds Creek: This creek runs permanently through the project area and then intermittently from the Ardgour Terrace towards the Lindis River. An irrigation water-take on Shepherds Creek (RM17.301.15) downstream of SC1 monitoring site takes all available surface water in normal flow conditions, which is supplied to an irrigation dam, so the creek does not flow past this point. There is potential for groundwater to flow past this point via a thin layer of alluvial gravels along the creek bed.
- Jean Creek: This creek is an intermittent tributary to Shepherds Creek.
- Rise and Shine Creek: This creek joins Clearwater Creek south-east of the Come in Time Battery and flows into Bendigo Creek.
- Clearwater Creek: Flows into Bendigo Creek.
- Bendigo Creek: Several irrigation water-takes are in place on this creek (RM20.079.01 and RM20.079.02).

Page 5 MWM-S003-Rev2




Figure 2. Bendigo-Ophir Gold Project area and water quality monitoring sites.

Baseline water quality data indicates that PCOC are elevated in the BOGP area due to historic mining activities and natural mineralisation (MWM, 2024a).

Page 6 MWM-S003-Rev2

3 MINE IMPACTED WATER

The BOGP is located within the Otago Schist and is associated with the mineralised Rise and Shine Shear Zone (RSSZ) which juxtapose lower greenschist facies Textural Zone 3 (TZ3) and mid to upper greenschist facies Textural Zone 4 (TZ4) schists in their hanging walls and footwalls respectively. This mineralisation is dominated by sulfur (S) and arsenic (As) (e.g., the mineral arsenopyrite) with other trace metals also being potentially elevated but at much lower concentrations (e.g., cobalt, (Co), copper (Cu), chromium (Cr), antimony (Sb), and zinc (Zn)).

3.1 Baseline Studies

The proposed BOGP water quality compliance limits (Ryder, 2025) are used as a screening tool to determine whether baseline water quality is elevated. The assessment (MWM, 2025a) indicated that:

- Shepherds Creek is elevated in copper (Cu).
- Bendigo Creek is elevated in arsenic (As), cobalt (Co), Cu, and iron (Fe).
- <u>Groundwater</u> is elevated in As, Cu, Fe, zinc (Zn), and on occasion strontium (Sr) within the project area. Thallium (Tl) was elevated on one occasion (although this appears anomalous).

3.2 Geoenvironmental Hazards

All BOGP materials are classified as non-acid forming (NAF), with circum-neutral pH drainage expected from mine domains that contain the materials. However, neutral metalliferous drainage is likely to occur with elevated levels of arsenic (As), sulfate (SO₄), trace metal, and nitrogenous compounds. The most significant AMD source hazard for waste rock relates to the TZ4 and RSSZ materials, some of which will be waste rock, and some will be processed (to extract gold) producing tailings.

Data for waste rock indicates that the TZ4 and RSSZ lithologies contain ~95.3% of arsenic and 21.9% of sulfur yet represents only 9.3% of the waste rock that will be disturbed. Hence, appropriate management of TZ4 and RSSZ materials to reduce sulfide mineral oxidation is a critical step to minimise deleterious effects, i.e., manage 9.3% of the waste rock well to mitigate 95.3% of the arsenic risk in the engineered landforms (ELFs) that will contain the waste rock.

The key PCOC that are likely to be associated with MIW include: aluminium (AI), As, Co, Cu, chromium (Cr), Fe, manganese (Mn), molybdenum (Mo), nickel (Ni), lead (Pb), strontium (Sr), uranium (u), zinc, (Zn), cyanide (CN), ammoniacal nitrogen (Amm-N) and nitrate nitrogen (NO₃-N).

3.3 MIW Summary

It is expected that mining of the BOGP will affect waters within the project area including:

- Elevated total suspended solids (TSS).
- Neutral metalliferous drainage (NMD) with elevated sulfate (SO₄) and the certain PCOCs such as As, Fe, and potentially lesser amounts of trace metals.
- Nitrate-rich drainage due to the use of ANFO and cyanide.

Collectively these waters are referred to as MIW to acknowledge the different contributions to poor water quality within the project area.

Page 7 MWM-S003-Rev2

4 PROPOSED COMPLIANCE MONITORING

This section summarises the proposed water quality limits for the BOGP.

4.1 Mine Impacted Water

Studies completed by MWM indicate that the following PCOC may be elevated and require treatment:

- Nitrogenous compounds (N) that include nitrate (NO₃) and ammoniacal-N (Amm-N).
- Sulfate (SO₄).
- Metals and metalloids that may include Aluminium (Al), arsenic (As), cadmium (Cd), cobalt (Co), copper (Cu), chromium (Cr), iron (Fe), manganese (Mn), molybdenum (Mo), nickel (Ni), lead (Pb), antimony (Sb), selenium (Se), strontium (Sr), uranium (U), and zinc (Zn)
- Cyanide (CN) within the tailings water.

4.2 Proposed Water Quality Limits

PCOC that have been identified for the BOGP based on baseline water quality studies, environmental geochemistry studies, and proposed water quality compliance limits are shown in Table 3. Limits are based on:

- Ecotoxicity assessments developed by Ryder (2025) for the proposed surface water compliance sites
- Groundwater limits are based on New Zealand Drinking Water Standards (MoH, 2022).

The proposed compliance monitoring locations are shown in Figure 2 for surface waters and groundwaters.

For conceptual desk-top studies, it is proposed that the WTP and PTS design should be based on the more stringent water quality criteria (i.e., the lower compliance value) for surface and groundwaters to ensure that treated waters comply with both criteria.

These proposed water quality criteria for the BOGP (Ryder, 2025) are summarised in Table 2 for surface water and Table 3 for groundwater.

Table 2. Proposed surface water quality compliance limits for the BOGP.

PARAMETER (units are mg/l unless stated otherwise)	COMPLIANCE LIMIT
pH (unitless)	6.5 - 9.0
Turbidity (NTU)	5 (over a 5-year rolling period, 80% of samples, when flows are at or below median flow, are to meet the limit)
Ammoniacal-nitrogen (NH ₃ -N)	≤0.24 (annual median) <0.4 (annual 95 th percentile)
Nitrate-nitrogen (NO ₃ -N)	<2.4 (annual median) <3.5 (annual 95 th percentile)
Cyanide (CN)	0.011 (un-ionised HCN, measured as [CN], ANZG, 2018)

Page 8 MWM-S003-Rev2

PARAMETER (units are mg/l unless stated otherwise)	COMPLIANCE LIMIT				
Sulfate (SO ₄)	A. If hardness is <100 mg/L (CaCO ₃), the sulfate compliance limit = 500 mg/L.				
	B. If chloride is <5 mg/L, the sulfate compliance limit = 500 mg/L				
	C. If the hardness is 100–500 mg/L AND if chloride is 5–<25 mg/L, the sulfate compliance limit is (in mg/L):				
	[-57.478 + 5.79*(hardness mg/L CaCO ₃) + 54.163*(chloride mg/L)] * 0.65				
	D. If hardness is between 100 and 500 mg/L AND if chloride is between ≥25 and ≤500 mg/L, the sulfate limit is (in mg/L):				
	[1276.7+5.508*(hardness mg/L CaCO ₃) +1.457*(chloride mg/L)] * 0.65				
	A minimum of 12 samples must be collected over any rolling 12-month period.				
	For compliance limits in A to D, no more than 20% of samples collected over a rolling 12-month period may exceed the relevant compliance limit.				
	E. An acute compliance limit = 1,000 mg/L averaged over 4 days and not to be exceeded more than once in a one-year period, OR in more than 10% of samples over a one-year period.				
Aluminium (AI) (dissolved)	≤0.08				
Antimony (Sb) (total)	0.074 (chronic, the average of 5 (monthly) samples over a 5-month period)				
	0.250 (acute, not to be exceeded at any time)				
Arsenic (As(V)) (dissolved)	≤0.042				
Cadmium (Cd)	≤0.0004				
(dissolved)	See below for adjustment algorithm				
Chromium (Cr)	≤0.0033 (CrIII)				
(dissolved)	≤0.006 (CrVI) See below for adjustment algorithm				
Cobalt (Co) (dissolved)	0.001 (chronic)				
	0.11 (acute, not to exceed)				
	See below for adjustment algorithm				
Copper (Cu) (dissolved)	≤0.0018				
Molybdenum (dissolved)	≤0.034				
Zinc (Zn) (dissolved)	0.015				
	See below for adjustment algorithm				
Adjustments					
Cd (dissolved)	HMTV = TV (H/30) $^{0.89}$, where hardness-modified trigger value (HMTV) = (μ g/L), trigger value (TV) (μ g/L) at a hardness of 30 mg/L as CaCO $_3$; H, measured hardness (μ g/L as CaCO $_3$) of a fresh surface water.				
Cr (dissolved	HMTV = TV (H/30) $^{0.82}$, where hardness-modified trigger value (HMTV) = (μ g/L), trigger value (TV) (μ g/L) at a hardness of 30 mg/L as CaCO ₃ ; H, measured hardness (mg/L as CaCO ₃) of a fresh surface water.				
Co (dissolved)	Cobalt (µg/L)= exp{(0.414[ln(hardness CaCO3 mg/L)] - 1.887}				
Sb (total)	(chronic) the average of 5 (monthly) samples over a 5-month period (acute) not to be exceeded at any time				
Zn (dissolved)	HMTV = TV (H/30) $^{0.85}$, where hardness-modified trigger value (HMTV) = (μ g/L), trigger value (TV) (μ g/L) at a hardness of 30 mg/L as CaCO ₃ ; H, measured hardness (mg/L as CaCO ₃) of a fresh surface water.				

Source: MGL (2025)

HMTV = hardness modified toxicity value.

TV = toxicity value.

H = hardness.

Page 9 MWM-S003-Rev2

Table 3: Proposed groundwater quality compliance limits for the BOGP.

PARAMETER (units are mg/L unless stated otherwise)	COMPLIANCE LIMIT
Nitrate-nitrogen (NO ₃ -N)	11.3 (MAV)*
Cyanide (CN-)	0.6 (MAV)
Sulfate (SO ₄)	≤250 (taste threshold)
Aluminium (Al)	1 (MAV)
Antimony (Sb)	0.02 (MAV)
Arsenic (As(V))	0.01 (MAV)
Cadmium (Cd)	0.004 (MAV)
Chromium (Cr)	≤0.05(MAV)
Cobalt (Co)	<1 (livestock drinking water)
Copper (Cu)	≤0.5
Iron (Fe)	≤0.3
Lead (Pb)	0.01 (MAV)
Manganese (Mn)	0.4 (MAV)
Molybdenum (Mo)	<0.01
Strontium (Sr)	4
Uranium (U)	0.03 (MAV)
Zinc (Zn)	≤1.5

Source: MGL (2025)

MAV = maximum acceptable value - from NZ drinking water standards

The PCOC presented in Table 2 and Table 3 were identified from the baseline studies, source hazard assessment, geochemical modelling, and the water and load balance modelling to understand potential effects of the BOGP.

Page 10 MWM-S003-Rev2

5 FLOW RATES

This section summarises the long-term average flow rates for each mine domain that may require treatment during the Active Closure and Post Closure phases of the BOGP.

5.1 Average Flow Rates

Average flow rates are estimated from the Water and Load Balance Model (MWM, 2025c). It is assumed that the use of average flow rates is suitable for the WTP OoM Study and the PTS Concept Study. Peak flows may require either a larger capacity plant or a surge pond prior to any treatment. Further work is required to advance the designs to a FS level including understanding the treatment requirements for peak flow rates.

Table 4 provides a summary of flow rates for the various mine domains that require treatment. These flow rates are preliminary and are intended to provide guidance for the OoM study on the WTP design. For the OoM WTP Study it is recommended that the design include suitable contingency for variable flow rates. Active treatment is not required for SRX Pit - It is expected that the water quality from this mine domain will be acceptable for release to the receiving environment (e.g., Rise and Shine Creek / Bendigo Creek) with passive treatment.

Table 4: Estimated average water quantity per mine domain.

MINE DOMAIN	WTP DESIGN CRITERIA (L/s)	PTS (L/s)	COMMENTS
Shepherds ELF	4	4	20% Net percolation (MWM, 2025b)
SRX ELF ^{1, 2}	-	1	20% Net percolation (MWM, 2025b)
West ELF ²	1	1	20% Net percolation (MWM, 2025b)
Shepherds TSF	13.4	3	Flow is expected to be ~13.4 L/s decreasing to 3 L/s after 5 years (MWM, 2025c).
RAS Underground Portal	6	6	Flow from the RAS Underground is not expected for 20-30 years after closure (MWM, 2025c).
CIT Pit Backfill	1.5	1.5	Further details are available in MWM (2025c).
SRX Pit	-	8	Further details are available in MWM (2025c). It is assumed this water will not require active treatment. Passive treatment is required.
SCK Fill ²	1	1	20% Net percolation (MWM, 2025b)
Non-AMD impacted water	-	-	Managed for TSS separate to the active WTP. At closure rehabilitated surfaces are assumed to be suitable for discharge with TSS management.

^{1.} Active treatment for SRX ELF and SRX Pit are not anticipated.

Flow rates (Table 4) are based on a net percolation (NP) rate of 20% of rainfall. It is proposed that a NP rate of 20% may be achievable, with appropriate engineering controls (i.e., an engineered cover system), which would halve the flow rates (MWM, 2025c).

Page 11 MWM-S003-Rev2

^{2.} Flow rates rounded up to 1 L/s

5.2 Model Flow Rates

The section summarises the flow rates for the mine domains presented in Table 4 to provide a visual guide to the flow variance.

5.2.1 ELF and TSF Flows

Model results for seepage flow rates from the ELFs and TSF are shown in Figure 3:

- Average flow rates for the Shepherds and other ELFs of approximately 4 and 1 L/s respectively.
- TSF seepage decays through the draindown period as the system equilibrates to lesser influent
 water (e.g., no process water, only rainfall), with average long term seepage flow rates of
 approximately 2 L/s. Flow rates typically vary between 1 and 3 L/s in the long term. Further
 details are provided in EGL (2025).




Figure 3: ELF and TSF seepage flow rates.

5.2.2 RAS Pit and RAS Underground

Model results for RAS Pit Void are shown in Figure 4 and Figure 5, and suggest:

- Stabilisation of the pit lake rebound in approximately 25 years, with a water level around 492 m asl (slightly above the adopted portal elevation of 490 m asl).
- Model results do not suggest the pit lake will spill over the pit crest low point (565 m asl).
- Discharge of pit lake water via the underground portal will start once the pit lake water level is above 490 m asl, and typically range between 4 to 7 L/s, with an average of about 6 L/s.

Page 12 MWM-S003-Rev2




Figure 4: RAS Pit Void model results - water volume and level.




Figure 5: RAS Pit Void model results - underground portal discharge.

5.2.3 SRX Pit Void

Model results for SRX Pit Void are shown in Figure 6 and Figure 7, and suggest:

- The pit void will fill and spill quickly (~ 6 months) owing to the low pit crest elevation and high groundwater inflow rate.
- The variability in overflow rate from the pit lake is higher than other pit voids due to the
 contribution of runoff from undisturbed areas reporting to the pit. Periodic high outflow rates are
 predicted, 140 L/s or higher, but average outflow rate is approximately 8 L/s.

Page 13 MWM-5003-Rev2




Figure 6: SRX Pit Void model results – water volume and level.




Figure 7: SRX Pit Void model results - overflow rate.

5.2.4 CIT Backfill Pit

Model results for CIT Pit Void are shown in Figure 8 and Figure 9, and suggest:

- The backfilled pit void will fill and spill at around 3.5 years.
- Outflow rates via groundwater pathways are low <0.1 L/s, with the majority of outflow via spilling at the pit crest at an average of approximately 1.5 L/s.

Page 14 MWM-S003-Rev2




Figure 8: CIT Pit Void model results – water volume and level.




Figure 9: CIT Pit Void model results – outflow rates.

Page 15 MWM-S003-Rev2

6 WATER QUALITY: ACTIVE WATER TREATMENT

This section summarises the water quality from the various mine domains that require treatment at closure of the BOGP by the active water treatment plant.

6.1 Shepherds TSF Water Quality

TSF seepage water quality at mine closure (Year 11) is presented in Table 5. Further details on how the water quality was derived are provided in MWM (2025e). Constant concentration is assumed.

Table 5: TSF seepage water quality (Closure).

	, , , ,
PARAMETER	CLOSURE TSF SEEPAGE WATER QUALITY
Alkalinity (mg CaCO ₃ /L)	73.21
pH (pH units)	6.41
EC (µS/cm)	4,121
Ca	297
Cl	804
F	1.93
Mg	99
Na	847
K	50.8
TOC	-
Al	0.01
Ag	0.0068
As	2.05
В	0.825
Cd	0.0002
Co	0.053
Cr	0.0055
Cu	0.001
Fe	15.3
Mn	0.59
Мо	0.14
Ni	0.678
Pb	0.0275
Sb	0.18
Se	0.003
Sr	4.4
TI	0.001
U	0.028
V	0.004
Zn	0.0296
Cyanide - WAD	0.35
Sulfate	954
Ammoniacal-N	2
Nitrate-N	0.005

Note: All units in mg/L unless otherwise stated. Green data are LOR

WAD - Weakly Acid Dissociable cyanide; If no data are provided these are identified by ' - '.

Page 16 MWM-S003-Rev2

6.2 ELF and CIT Backfill Water Quality

Water quality for the ELFs is provided in Table 6, which shows the water quality for Year 27, when maximum loads are being derived from the Shepherds ELF to provide peak concentration data for the design of the WTP.

Constant concentrations are assumed for As (0.2 mg/L) and Fe (7.6 mg/L) based on empirical data for sub-oxic conditions (e.g., Globe Progress Waste Rock Stack, Hayton et al., 2022). These concentrations are above the proposed water quality reference limit (Ryder, 2025) and will require management. The SCK Fill assumes full oxidation, which results in low Fe concentrations.

Table 6. Water Quality Data (Year 27) for WTP design – 20 m Oxygen Exclusion Model

STATION	TSF SEEPAGE	SHEPHERDS ELF SEEPAGE	WELF SEEPAGE	CIT PIT BACKFILL	SCK FILL SEEPAGE	MIW COMBINED ¹
Acidity	0.01	0	0	0	0	0.03
Al	0.011	0.003	0.003	0.005	0.003	0.013
Alkalinity	73	189	183	190	158	160
As	2.06	0.20	0.20	0.08	0.20	0.61
В	0.83	0.87	0.10	0.09	0.01	0.59
Са	297	51	51	39	36	107
Cd	0.0002	0	0	0.0001	0	0.0001
Cl	806	63	37	12	8	223
Со	0.053	0.109	0.023	0.004	0.003	0.061
Cr	0.00636	0.00020	0.00019	0.00040	0.00007	0.00170
Cu	0.00100	0	0	0.00021	0	0.00049
DOC	0	0	0	0.206	0	0.038
F	1.94	6.30	6.12	1.39	2.37	3.90
Fe	15.3	7.6	7.6	2.4	7.6	8.7
Hg	0	0	0	0.00014	0.00000	0.00003
K	51	683	672	84	159	372
Mg	100	38	37	20	24	49
Mn	0.594	0.819	0.774	0.103	0.182	0.567
Мо	0.140	1.005	0.672	0.119	0.157	0.535
NO3-N	2.01	49.64	9.54	0.73	1.33	22.89
Na	848	922	734	127	170	673
Ni	0.6784	0.0121	0.0010	0.0013	0.0001	0.1652
Pb	0.0276	0.0001	0.0001	0.0002	0.0000	0.0068
Sb	0.1802	2.9986	3.2208	0.3622	0.7601	1.6317
Se	0.0030	0.1544	0.1649	0.0196	0.0388	0.0826
SO4	954	957	888	110	208	730
Sr	4.40	16.15	15.91	3.77	10.89	10.12
TI	0	0	0	0.00021	0.00000	0.00005
CN	0.35	0	0	0	0	0.08238724
U	0.0280	0.2751	0.2225	0.0299	0.0515	0.1468
V	0.0040	0.1200	0.1155	0.0135	0.0269	0.0633

Page 17 MWM-S003-Rev2

STATION	TSF SEEPAGE	SHEPHERDS ELF SEEPAGE	WELF SEEPAGE	CIT PIT BACKFILL	SCK FILL SEEPAGE	MIW COMBINED ¹
Zn	0.0296	0.0098	0.0021	0.0014	0.0003	0.0117
pH (pH unit)	6.41	7.93	7.92	8.03	7.92	6.72
Hardness	1,151	285	280	179	190	469

Units in mg/L unless stated otherwise: DOC = dissolved organic carbon

6.3 RAS Underground

As discussed in MWM (2025e) seepage from the RAS Underground will be comparable to the RAS Pit Lake. The RAS Underground is not expected to commence discharge until Year 26. Water Quality for Year 26 is provided in Table 7.

Table 7. RAS Underground water quality (Year 27)

PARAMETER	RAS UNDERGROUND			
Acidity	0.44			
Al	0.100			
Alkalinity	182			
As	0.09			
В	0.05			
Ca	59			
Cd	0.0001			
CI	14			
Со	0.000			
Cr	0.00058			
Cu	0.00302			
DOC	0.090			
F	0.23			
Fe	7.9			
Hg	0.00006			
K	34			
Mg	37			
Mn	0.014			
Мо	0.020			
NO3-N	4.35			
Na	42			
Ni	0.0009			
Pb	0.0035			
Sb	0.0234			
Se	0.0008			
SO4	141			
Sr	0.79			

Page 18 MWM-S003-Rev2

^{1.} weighted average

PARAMETER RAS UNDERGROUND

TI	0.00031			
CN	0			
U	0.0094			
V	0.0006			
Zn	0.0022			
pH (pH unit)	5.91			
Hardness	299			

Units in mg/L unless otherwise stated

Page 19 MWM-S003-Rev2

7 PRINCIPLES OF WATER TREATMENT

This section discusses the principles of water treatment for the BOGP.

7.1 Overview

Water treatment should be the last option evaluated to manage mine water discharges (INAP, 2021) and a hierarchy of controls are proposed to minimise the requirements for water treatment (Figure 10). As noted by the Australian Commonwealth (DFAT, 2016) "It makes good business sense, in addition to being leading practice, to avoid and minimise the production of acid mine drainage (AMD), and to treat AMD only as a last resort if other approaches have failed."




Figure 10. Hierarchy of MIW Treatment Controls *Source: INAP (2021).*

(===:):

Previous studies completed as part of an assessment of environmental effects for the BOGP have already considered these hierarchy of controls:

- Source control technologies for the proposed engineered landforms are proposed, which are
 expected to significantly reduce contaminant loads in the longer term (MWM, 2025d). Further
 discussion on source control is provided in Section 10 Further Work that recommends
 additional studies to assess the options to reduce net percolation rates (which mobilises
 PCOC).
- Clean water diversion is part of the overall water management philosophy including minimising water ingress into the engineered landforms (MWM, 2025f).
- Water reuse is proposed during the operational phase where MIW is reused for process water and possibly dust suppression (MWM, 2025c).

This report discusses water treatment.

Page 20 MWM-S003-Rev2

7.2 Treatment Technology Selection: Active Treatment versus Passive Treatment

Estimates of flow rates (Table 4) suggest that active treatment using a WTP is required for up to ~20 L/s during the Active Treatment Phase and up to 25 L/s for the PTS (split over two PTS) during the Post Closure Phase.

Passive systems, in general, can only handle relatively small flows (usually less than 50 L/s) unless a significant area is available for passive treatment to be successful (INAP, 2021). A common reference document (Taylor et al., 2005) provides general criteria for passive treatment (Table 9). However, INAP (2021) note that 'Under neutral to slightly acidic conditions, much higher flows can be treated through passive treatment, especially where sufficient real estate is available and where the concentrations of iron, which is often the largest problematic dissolved constituent, can be decreased through aeration.' MIW at BOGP will be circum-neutral, hence PTS limitations on flow rates are unlikely given the flows proposed in Table 4.

INAP (2021) also note that "most successful passive treatment projects are treating less than 1,000 m^3 per day", however there are two examples where treatment of 6,500 m^3 per day (~75 L/s) was maintained for up to 19 years.

TREATMENT SYSTEM	AVERAGE ACIDITY RANGE	AVERAGE ACIDITY LOAD	AVERAGE FLOW RATE	TYPICAL pH RANGE	MAX pH ATTAINABLE
	(mg CaCO ₃ /L)	(kg CaCO₃/day)	(L/s)		
Passive	1 - 800	1 – 150	< 50	>2	7.5 – 8.0
Active	1 – 10,000	1 – 50,000	No defined limit	No defined limit	14
BOGP	<50 ¹	~50 ²	~30	Circum-	-

Table 8. General Guidelines for Selection Active versus Passive Treatment

Source: Taylor et al. (2005).

- 1. Based on 7.6 mg/L as Fe(iii) converted to acidity mg CaCO₃/L).
- 2. Based on 30 L/s (see Table 4) Active = 27 L/s; passive = 32 L/s.

Based on this review, it is anticipated that the flow rates expected for the BOGP in the Active Phase and Post Closure Phase can be managed by both active and passive treatment technologies.

7.3 MIW Redox Geochemical Characteristics

MIW can be summarised into three broad geochemical groups:

- Oxic waters waters that contain measurable dissolved oxygen.
- Suboxic waters waters that lack measurable oxygen or sulfide but contain significant dissolved iron (> ~0.1 mg/L).
- Reducing waters (anoxic) waters that contain both dissolved iron and sulfide.

Mine impacted water at BOGP are likely to have a number of different redox states:

- TSF seepage is likely to be suboxic or be reduced.
- ELF seepage is likely to be suboxic with elevated Fe.

Page 21 MWM-S003-Rev2

- Pit lakes are likely to be oxic.
- RAS Underground is likely to be suboxic/oxic (e.g., may contain some elevated iron that has not hydrolysed by interaction with air as water seeps from the portal).

The various mine waters will be mixed prior to treatment through the WTP and PTS. The mixing will be optimised to encourage beneficial geochemical reactions that include, for instance, Fe hydrolysis with As and trace metal removal (via adsorption).

Page 22 MWM-S003-Rev2

8 ACTIVE CLOSURE PHASE: WATER TREATMENT PLANT

The Active Closure Phase of the BOGP commences once mining is complete (i.e., no further ore processing) and the MIW management at site transitions from water retention to treat and release.

8.1 Introduction

Active closure of the site commences in Year 11 (Table 1) with final rehabilitation of mine domains and transition from water storage to water treatment by an active water treatment plant. An OoM design has been developed by Process Flow (2025) for active treatment of MIW. This is included as Appendix C.

As noted by INAP (2021) "Surge ponds may be a valuable feature in the case of highly variable mine drainage flows and pollutant loads as this will afford some protection against surcharging the treatment system. It is typically not economically feasible to build very large raw water retention ponds nor is it economical to build small ponds and very large treatment plants". The surge pond capacity will be considered during the BOGP detailed design stage when peak flow rates will be considered. For this study, the average flow rates presented in Table 4 are used.

8.2 Location

The proposed location for the Active WTP is located within the Shepherds Creek catchment. Process Flow note the size and footprint requirements for the WTP and Surge and Treated water ponds is as follows.

- WTP Footprint An area approximately 100 m x 60 m is recommended to be located near the surge and treated water ponds.
- WTP Surge Pond 14,000 m³
- WTP Treated Water Pond 2,000 m³

8.3 Technology Selection

Process Flow (2025) note that the selected process involves:

- Surge sump
- · Pontoon mounted pumps for plant feed
- Metal hydroxide precipitation and settling
- Gypsum precipitation and settling
- Ettringite precipitation and settling
- Carbonation and pH trimming
- Treated water sump
- Sludge management

Other processes that will likely be needed in addition to the active WTP are:

Cyanide destruct on the Shepherds TSF influent stream

Page 23 MWM-S003-Rev2

• Potential additional nitrate removal after WTP via biological processes.

8.4 Summary

Process Flow indicate that the proposed water quality objectives (Ryder, 2025) can be achieved, although further work is required to develop the OoM study to a FS level. Further details are provided in Appendix B. The WTP will operate until passive treatment systems can be installed.

Page 24 MWM-S003-Rev2

9 POST CLOSURE PHASE: PASSIVE TREATMENT SYSTEMS

The Post Closure Phase for the BOGP commences once MIW can be treated by passive treatment system technology. Based on the WLBM (MWM, 2025c) and expected sulfate concentrations at SC01, it is expected that transition from active to passive treatment can occur within a few decades depending on water management processes.

This section discusses passive treatment technologies. Passive treatment technologies for treatment of MIW are defined as biological and/or chemical processes that neutralise acidity and precipitate metals via oxidation or reduction using natural processes that do not require regular human intervention or maintenance (INAP, 2021). In general, a passive system should function for many years without a major retrofit to replenish materials and should operate with no or low electrical power.

9.1 Introduction

Based on the contaminants of concern identified at the BOGP a multi-stage passive treatment system is expected. This would include:

- Sediment management to mitigate any residue TSS and prevent the PTS from being overwhelmed with sediment.
- Oxidation to encourage Fe(OH)₃ precipitation and adsorption of metals such as As.
- Aerobic treatment of tailings seepage waters for cyanide.
- Anaerobic treatment to remove nitrate, reduce sulfate concentrations, and precipitate metals as sulfides.
- A polishing pond to remove secondary contaminants generated in the anaerobic treatment stage (e.g., sulfide (HS-), ammoniacal nitrogen, and low dissolved oxygen).

Gusek and Waples (2009) developed a periodic table of elements for passive treatment (Figure 11), which demonstrates the applicability of oxic and anaerobic treatment systems to PCOC identified at BOGP. Figure 11 provides useful context but does not cover all elements. For instance, Trumm et al (2024) noted that a mussel shell anaerobic bioreactor at Echo Mine, Reefton removed 96% of Cs; 82% of Rb, and 98% of La, which is not shown in Figure 11.

Page 25 MWM-S003-Rev2




Figure 11. Periodic table for passive treatment.

Source: INAP (2021).

The following locations are potentially available for the construction of PTS at the BOGP after closure of the mine:

- Shepherds Sediment Pond footprint.
- SRX ELF toe seepage pond and/or SRX Pit.
- BOGP Infrastructure area to treat seepage from the Shepherds ELF, Shepherds TSF, RAS underground, WELF, and the CIT Backfill Pit.

Passive treatment during the operational phase of the mine is generally not viable due to the MIW being affected by significant sediment loads (TSS). However, the Operational Phase is an ideal time to test and confirm PTS technologies can achieve water quality objectives.

9.2 Oxidation of Suboxic Waters

Oxidation is a common approach for the treatment of waters discharging from suboxic / reduced environments (e.g., seepage from the ELF, underground workings, etc.) impacted by iron (Fe) and arsenic (As). The oxidation treatment process involves aerating water (to increase the dissolved oxygen content), which allows Fe^{2+} to oxidise to Fe^{3+} and form insoluble ferric hydroxide, $Fe(OH)_3$ precipitates. Arsenic is removed through this process by co-precipitation / adsorption to the ferric hydroxide.

9.2.1 Aeration

Aeration is a common technology used to remove sulfide from water. This is demonstrated by the fact that hydrogen sulfide gas escapes (volatilizes) rapidly from water and can be identified by its distinct

Page 26 MWM-S003-Rev2

odour⁴. Aeration can also be used to remove ammoniacal nitrogen and is common for wastewater treatment.

The following physical aeration systems are available to increase aeration of the PTS effluent to increase dissolved oxygen and remove ammoniacal N and un-ionised hydrogen sulfide.

9.2.1.1 <u>Trompe</u>

A trompe (Figure 12) utilises falling water to compress air, drawing air into a vertical downpipe as water flows through an airhead (Leavitt et al., 2015)⁵. The high velocity of the falling water carries entrained air down the pipe, which is then separated from the water in a chamber located below the discharge elevation. To generate air pressure, a drop of approximately four feet is required between the inlet head and discharge pipe, and the height of the discharge pipe controls the pressure generated (Leavitt and Danehy, 2011; Leavitt et al, 2015). Trompes can be installed in series for sites with multiple flow rates, and multiple airheads and downpipes.

The Curley passive treatment site in Pennsylvania installed a trompe to assist in the treatment of mine-impacted drainage. The mine drainage had Fe concentration of 23 mg/L (Dorman, 2019). The study found that the trompe added over 3 mg/L of dissolved oxygen, which was sufficient to oxidise 82 - 97% of the Fe present in the influent water (Dorman, 2019).




Figure 12. A simple trompe schematic

Air entrained in the water is compressed in the plenum, or reservoir, and delivered via pipeline Source: Trumm 2013

9.2.1.2 Mechanical Aeration

Powered mechanical aeration systems are available for wastewater treatment systems (e.g., agitators), however, the electricity requirements are likely to be prohibitive once power is removed from the site in

Page 27 MWM-S003-Rev2

⁴ Further details are available: https://extension.uga.edu/publications/detail.html?number=C858-15.

⁵ Further details are available from the U.S. Department of the Interior: https://www.osmre.gov/node/794.

the Post Closure Phase. Alternatively, solar options are available to generate compressed air (e.g., CWS, 2023).

9.2.1.3 Bubble Diffusers

Bubble diffusers or similar generate high surface area air particles to allow sufficient chemical oxidation of sulfide and ammoniacal nitrogen. Fine bubble diffusers create fine bubbles by pushing air through tiny holes in the diffuser plate, resulting in a large water-air interface and high oxygen transfer rate (Dorman, 2019).

Fine bubble diffusers may not be suitable for waters with high suspended solids like a mine drainage oxidation pond due to fouling from metal hydroxides or biofilm layers (Dorman, 2019; Schmidt 2004). However, the proposed polishing pond will have low dissolved metal content. Trials during the detailed design phase will confirm if fouling is a problem.

9.2.2 Ferric Treatment of High Arsenic MIW

Where waters are aerated but retain elevated As concentrations the addition of Fe to trigger further ferric hydroxide formation and remove As by co-precipitation / adsorption is a common treatment approach, and is used in many active treatment systems. Passive treatment systems can also use FeCl₃ addition. For instance, OceanaGold treated the Globe Pit Lake with FeCl₃ to reduce elevated arsenic concentrations (Navarro et al., 2022). This is shown in Figure 13 which demonstrates significant decreases in As following the addition of Fe.




Figure 13. Arsenic and antimony loads – Globe Pit Lake, Reefton. *Source: Navarro et al. (2022)*

9.2.3 Vertical Flow Reactor Technologies

Work completed by Hayton (2022) demonstrated that one option to treat arsenic and iron was a vertical flow reactor (VFR). A full-scale VFR has subsequently been constructed at the Globe-Progress Mine. The following link provides further information on the system:

https://oceanagold.com/2021/01/27/delivering-innovative-passive-water-treatment-at-reefton/

Page 28 MWM-S003-Rev2

The Globe-Progress Mine VFR aerates Fe- and As- rich waters from the waste rock stack seepage and tailings storage facility underdrains and then filters (downwards flow) the Fe-precipitates (with As adsorbed to the Fe-floc) through a gravel-bed. Treated waters are then discharged from site.

The use of Fe hydroxides to co-precipitate / adsorb and treat As-impacted mine waters is a proven technology for As treatment and could be applied at the BOGP where required. This could include seepage from the TSF, ELFs, and RAS Underground, etc. If Fe is limited in the influent water stream, this could be added by a simple FeCl₃ dosing system.

9.2.4 Summary

The precipitation of iron as hydroxide minerals may also assist in the removal of additional pollutants. Several ionic species, such as arsenic and molybdenum, coprecipitate or adsorb onto ferric hydroxide (INAP, 2021), which will help with these PCOC if they are elevated in MIW.

9.3 Aerobic Passive Treatment of TSF seepage: Cyanide

Aerobic passive treatment of TSF seepage may be required following active treatment for residual cyanide that may be present in concentrations up to 0.35 mg/L. This could be co-incidental with the passive oxidation and removal of Fe and As.

Studies state that that cyanide move only a short distance through soil before being biologically converted under aerobic conditions to nitrates via microbial attenuation to ammonia and then to nitrate (Mudder et al., 2001). It was also found that cyanides are immobilized after reacting with trace metals through chelation processes (Mudder et al., 2001). Álvarez et al (2004) indicated that passive treatment of cyanide is viable with 90.36% removal of Cyanidewad.

9.4 Anaerobic Passive Treatment of Mine Impacted Water

Anaerobic passive treatment can be used to mitigate the effects of poor water quality during the Post Closure Phase, which might be impacted by:

- Metals
- Nitrogenous compounds
- Sulfate

9.4.1 Anaerobic Treatment of MIW

There are numerous types of anaerobic treatment system for sulfate-rich waters, however all anaerobic PTS rely on Equation 1 to convert sulfate to sulfide, which can then be removed as either metal sulfides (e.g., pyrite that can also contain other trace elements, e.g., As, Zn, Ni, Pb, etc) or be converted to elemental sulfur. This process can only occur under anoxic conditions when there is a labile source of carbon to provide electrons and sulfate is available to receive the electrons (assuming microbes will naturally be present).

Equation 1:
$$SO_4^{2-} + 2CH_2O \xrightarrow{SRB} 2HCO_3^{-} + H_2S$$
 Where $SRB = sulfate \ reducing \ bacteria$.

 H_2S is a common anaerobic degradation by-product where sulfate is present. H_2S can be found in natural sediments and is found in industrial wastes and landfill leachates (ANZECC, 2000). Mine-impacted waters can also be elevated in sulfate that can be converted to hydrogen sulfide under anoxic

Page 29 MWM-S003-Rev2

conditions where labile organic carbon is available. This process is driven by microbes seeking energy to drive metabolic activity where energy is obtained from the transfer of electrons from electron-rich (reduced) substrates (e.g., organic matter) to electron-deficient (oxidised) species (e.g., nitrate, sulfate, etc). This is shown schematically in Figure 14 and an explanation of relative oxidation-reduction potential (Eh) for these reactions is shown in Figure 15.




Figure 14. Energy yield and common oxidation-reduction (redox) sensitive species.




Figure 15. The Redox Ladder

Source: Sapkota et al. (2022)

As shown in Figure 14 and Figure 15, anaerobic passive treatment systems can also treat nitrate impacted waters.


A number of options for As-Fe-SO₄ impacted waters were assessed for OceanaGold's Globe Progress Mine (bioreactors and vertical flow reactors) (Hayton et al., 2022). The bioreactors included 4 different substrates:

- B-LC: Biosolids with less compost.
- M-LC: mussel shells with less compost.
- B-MC: biosolids with more compost.

Page 30 MWM-S003-Rev2

M-MC: mussel shells with more compost.

Data (Hayton et al., 2022) indicated that for a hydraulic residence time (HRT) of 50 hours there was a significant reduction in As in mine-impacted waters. The bioreactors were fed water from the sites combined underdrains (median chemistry: 28.5 mg Fe/L, 1.7 mg As/L and 425 mg SO₄/L). Results are shown graphically in Figure 16 and Figure 17.






Figure 16. Globe Progress field trials

Percentage removal for As and Fe. B-LC: Biosolids with less compost, M-LC: mussel shells with less compost, B-MC: biosolids with more compost, and M-MC: mussel shells with more compost.

Sources: Hayton et al. (2022).




Figure 17. Globe Progress field trials

Percentage removal for sulfate. B-LC: Biosolids with less compost, M-LC: mussel shells with less compost, B-MC: biosolids with more compost, and M-MC: mussel shells with more compost. Source: Hayton (2020).

9.4.2 Enhanced Passive Treatment Systems of MIW

Enhanced passive treatment systems (E-PTS) are bioreactors that are enhanced by the addition of nutrients to passive bioreactors to increase the rates of water treatment (Christenson et al., 2022). Nutrient addition (e.g., liquid carbon) was undertaken on laboratory bioreactors, to test contaminant removal rates with varying substrates, temperatures, HRT and nutrient addition rates, in order to optimise parameter selection for field trials.

Trial results indicated that the SO₄ removal rates observed in the laboratory trials were more than 25 times higher than those of standard passive bioreactors, which typically remove 0.3 mol/m³/day of SO₄ from mine water (Figure 18). The highest SO₄ removal rates observed were 15 mol/m³/day and the SO₄

Page 31 MWM-S003-Rev2

removal rates consistently exceeded 7 mol/m³/day (Christenson et al., 2022). It was noted that sulfide, dissolve organic carbon, and ammoniacal nitrogen could be elevated.




Figure 18. E-PTS bioreactor effluent sulfate concentrations.

Source: Christenson et al. (2022).

E-PTS have also been investigated as an option to treat nitrate-rich waters (e.g., Christenson et al., 2018) using nitrate-reducing bacteria (NRB) and water-soluble carbon compounds:

Equation 2:
$$4NO_3 + 4H^+ + 5CH_2O \rightarrow 2N_2 + 7H_2O + 5CO_2$$

NRB have been used in woodchip bioreactors to successfully reduce nitrate concentrations in agricultural and other enriched waters (Christianson et al., 2017). Similar systems could also be applied to nitrate rich MIW resulting from the use of nitrogen-based explosives. Results demonstrated a significant decrease in nitrate concentrations compared to the influent water quality (Figure 19).




Figure 19. Nitrate treatment concentrations in the laboratory reactor effluent.

Source: Christenson et al. (2018).

Page 32 MWM-S003-Rev2

9.5 Secondary Contaminants

A polishing pond is required to remove secondary contaminants generated in the anaerobic treatment stage. This is likely to include low oxygen waters elevated in secondary contaminants such as sulfide (HS-) and ammoniacal nitrogen. Sulfide and ammoniacal nitrogen have been identified in passive treatment systems by odour for hydrogen sulfide and by water measurement for ammoniacal nitrogen (e.g., Crombie et al., 2011). The generation of HS- can also potentially generate health and safety issues due to H₂S gas. Several options are discussed to explain how these secondary contaminants can be removed.

9.5.1 Chemical Oxidation

Chemical oxidation is often used when mechanical aeration or passive technologies are not possible or practical. Chemical oxidants include, for instance: chlorine, hydrogen peroxide (H_2O_2) , sodium hypochlorite (NaClO: e.g., household bleach), calcium hypochlorite $(Ca(ClO)_2)$, and potassium permanganate $(KMnO_4)$.

9.5.2 Zero Valent Iron

Elevated sulfide can create ecotoxicity issues in waters affected by MIW. However, the sulfide readily combines with metals (often Fe) to form acid volatile sulfides, precursors to the formation of pyrite / marcasite, which can remove the sulfide from solution:

Equation 3:
$$Fe_2O_3(s) + 4SO_4^{2-} + 8CH_2O + \frac{1}{2}O_2 \rightarrow FeS_2(s) + 8HCO_3^{-} + 4H_2O$$

Iron-based compounds have been used previously for the removal of sulfide by precipitation, which can include zero valent iron (ZVI) materials such as scrap iron. Robinson et al. (2022) used sulfide scrubber (SCR) technology that involved the use of magnetite, hematite, and iron filings:

Equation 4:
$$Fe^{2+} + S^{2-} \rightarrow FeS$$

Results (Robinson et al., 2022) indicated that the effluent from the SCR systems contained concentrations of sulfide that were lower than the other passive treatment systems using organic matter and limestone by orders of magnitude (Figure 20).

Other research has noted that the use of ZVI led to minimal levels of toxic hydrogen sulfide in the treated effluent due to its efficient precipitation of sulfide as metal sulfides, which included Fe-sulfides generated by the anoxic corrosion of ZVI (Ayala-Parra et al., 2016).

Liao et al. (2022) notes that metal sulfide precipitation is a common method to treat sulfide-containing wastewater that allows rapid precipitation of the sulfide salt and selective precipitation of heavy metals, and that zinc is commonly chosen as precipitation agent to recover sulfide due to its higher chemical stability compared to other transition metals.

Page 33 MWM-S003-Rev2




Figure 20. Sulfide concentrations following treatment.

Biochemical reactors (BCR); fixed-bed anaerobic bioreactors (FBAR) and Sulfide Scrubber (SCR) systems.

Source: Robinson et al (2022).

This sulfide precipitation approach could be applied to the effluent of a bioreactor. Ideally this would be undertaken prior to any oxidation step to encourage Fe-sulfide precipitation under reducing conditions. This could be incorporated as multi-step treatment approach whereby a scrubber system is used after an anaerobic treatment process. Materials could include iron fillings, waste galvanised steel, and possible Fe-rich sludge mixed with gravel to provide suitable permeability.

9.5.3 Adsorbents

There are various materials that are frequently employed as adsorbents to treat waters impacted by contaminants, including zeolites, clay minerals, activated carbon, and polymers (e.g., hydrogels). Zeolite was selected for this review as a suitable adsorbent material that may be suitable for the BOGP PTS.

Zeolite is a naturally occurring hydrated aluminosilicate mineral with a negative charge. The negative charge allows for the adsorption of certain positively charged ions. In aqueous solution, the negative charge is generally neutralized by Na⁺, however, NH₄⁺ is preferentially adsorbed to the zeolite matrix. Zeolite has been used for decades to decrease the concentrations of ammonium in municipal effluents and, more recently, in freshwater environments (Burgess et al., 2004). Removal mechanisms include ion exchange and adsorption (Guida et al., 2020).

Zeolite materials are available in New Zealand (e.g., Blue Pacific Minerals) and are commonly used as kitty litter.

9.6 Passive Treatment System Efficiencies

This section reviews the treatment efficiency of passive treatment systems. The efficiencies are included in the WLBM to determine estimated water quality after PTS.

Page 34 MWM-S003-Rev2

9.6.1 Arsenic and Iron Treatment Efficiency

Hayton et al. (2022) reports that a vertical flow reactor removed 95% of arsenic and 99% of iron, although when the hydraulic residence time (HRT) was lower the removal efficiency decreased to 75% and 84% respectively.

Other studies (Raven et al., 1998) indicate that Adsorption maxima of approximately 0.60 (0.58) and 0.25 (0.16) molAs.molFe⁻¹ were achieved for arsenite and arsenate, respectively, at pH 4.6 (pH 9.2 in parentheses). For passive treatment purposes a removal efficiency of 99% is used.

Zhang et al. (2022) indicates that Fe oxyhydroxides can also be used to remove vanadium with studies indicating removal efficiencies of 84 – 92%. A nominal value of 90% has been used as the treatment efficiency within the WLBM.

9.6.2 Sulfate Treatment Efficiency

It is proposed that a sulfate treatment efficiency of 30% is applied to mine-impacted waters treated by passive anaerobic treatment systems. This efficiency is in alignment with recent literature reviews of field-scale bioremediation systems. For instance, Zak et al. (2021) noted that bioremediation systems (BIOS) can achieve a variable range of sulfate removal efficiencies (Figure 21). Analysis of these data indicate that the average treatment removal efficiency is 30.7% for sulfate influent concentrations that range from 2.5 to 8,000 mg/L. Such sulfate ranges are within the bounds expected at BOGP.

The efficiency proposed will require validation through large scale field trials. The efficiency is applied to passive treatment systems in the WLBM.

D. Zak et al. Earth-Science Reviews 212 (2021) 103446

Table 2
Performance of field-scale bioremediation systems. CS=Composite System. CW=Constructed Wetland. SF=Surface Flow. SSF=Sub-Surface Flow. PRB=Permeable Reactive Barrier. *=refers to the cell of CS performing under anaerobic conditions. **=Water temperature reported in the studies. References: 1.Barton and Karathanasis (1999); 2. Hedin (2003); 3. Ji et al. (2008); 4. Di Luca et al. (2011); 5. Mitsch and Wise (1998); 6. Morrison and Aplin (2009); 7. Wieder (1993); 8. Woulds and Ngwenya (2004); 9. Wu et al. (2011); 10. Wu et al. (2012); 11. Benner et al. (2002); 12. Gibert et al. (2013); 13. Herbert et al. (2000); 14. Benner et al. (1999); 15. Caraballo et al. (2011); 16. Song et al. (2012); 17. Behum et al. (2011); 18. Matthies et al. (2012).

Reference	Type	Area/Volume	Duration	Plants	pH	T ^a (°C)/Climate	Substrate	SO ₄ inflow (mg	SO ₄ ² removal
		(m^2/m^3)	(y)					L-1)	(%)
1	CS/SSF*	1,022/705	1.5	Yes*	3.4	Temperate, USA	Limestone/ Organic*	3034	53.5
2	CS/SF*	49,000/-	2		6.2	Temperate, USA		1085	5.6
3	CS	-/-			2.1-7.7	Temperate/South Korea		2.5–3046	0-62
4	CW/SF	2,000/900	1	Yes	9-10	12.8-27**		270-1649	24-66
5	CW/SF/ SSF	3,869/3,757	1	Yes	3	Temperate, USA	Limestone/ Organic	1672	29
6	CW/SF	440/132	3	Yes	5.6-6.7	5.9-15.8**	Organic	355-969	15-25
7	CW/SF	180/54	2	Yes	2.9	Temperate, USA	Limestone/Peat	3132	0-14
8	CW/SF	-/-	0.5	Yes	2.6	Temperate, Scotland	Limestone/ Organic	900	17–18
9	CW/SSF	6/3	0.7	Yes		Temperate, Germany	Sand/Gravel	283.1	7
10	CW/SSF	6/3	6	Yes	6.7	Temperate, Germany	Sand/Gravel	790-995	32-54
10	CW/SSF	6/3	6	No	6.7	Temperate, Germany	Sand/Gravel	790-995	12-0
11	PRB	60/216	4	No	5-6	Continental, Canada	Gravel/Organic	2304-2880	13-50
12	PRB	154/580	3	No	3.5-4.5	Temperate, Spain	Calcite/Organic/ Fe	1000	2-43
13	PRB	60/216	2	No	4.6	Continental, Canada	Gravel/Organic	2400-8000	70
14	PRB	60/216	2	No	4-6	Continental, Canada	Gravel/Organic	1000-5000	74
15	Bioreactor	120/-	1.8	No	2.6	16,8-22,2**	Limestone/ Organic	900	20-40
16	Bioreactor	-/0.0035	0.5	No	3_4	Temperate, South Korea	Organic	1277	20-48
17	Bioreactor	/5,887	3	No	2-3	Temperate, USA	Limestone/ Organic	up to 4100	30
18	Bioreactor	1,511;1,124/ 1,209;899	6	No	5.8; 5.0	Temperate, UK	Limestone/ Organic	369/1074	13-40

Figure 21. Performance of field-scale bioremediation systems for sulfate removal.

Source: Zak et al., 2021.

Note: where a range is provided, half the range is used to determine treatment efficiency

Page 35 MWM-S003-Rev2

9.6.3 Nitrogen Treatment Efficiency

Nitrogenous compounds (e.g., nitrate) will be treated through the anaerobic passive treatment system. It is removed in preference to sulfate due to the higher energy yield (Figure 14) and nitrate is expected to be low after anaerobic treatment (although ammoniacal nitrogen is expected to increase and will be treated as a secondary contaminant. Christensen (2022) using enhanced PTS technologies (e.g., the addition of water soluble carbon) reports that near-complete nitrate removal occurred in all bioreactors (17 mg/L influent to <0.5 mg/L effluent NO₃-N) yet ammoniacal nitrogen was elevated in some trials and above proposed water quality limits for the BOGP (Table 3). These data are provided in Figure 22 and Figure 23.




Figure 22. Nitrate + nitrite nitrogen concentration in the bioreactor effluents.

Source: Christensen et al. (2022)




Figure 23. Ammoniacal nitrogen concentration in bioreactor effluents.

Source: Christensen et al. (2022)

For this review, it is assumed that nitrate nitrogen will be totally removed by passive treatment and that 50% of the influent is converted to ammoniacal nitrogen. Ammoniacal nitrogen will be treated by aeration and biological conversion to N_2 gas.

9.6.4 Metals

Various passive treatment systems have been installed in New Zealand, some of which use waste mussel shells (e.g., Weber et al., 2015). Trumm et al. (2022) reports that the removal efficiencies of a

Page 36 MWM-S003-Rev2

mussel shell bioreactor (MSR) for acid rock drainage were 91.4% (Fe), 97.6% (Al), 83.3% (Zn), 85.6% (Cd), 85.2% (Co), 85.6% (Cu), and 87.0% (Ni). This is comparable to other studies for the treatment of acid rock drainage where Crombie et al. (2011) reports the removal of 96-99% of Al, Fe, Ni, and Zn with mean Ni decreasing from 0.27 mg/L to 0.0028 mg/L and mean Zn decreasing from 1.18 mg/L to 0.008 mg/L. Sinclair and Weber (2022) note that within a MSR treating circum-neutral MIW that (based on median data) 99% of the Fe; 98% of the Ni, and 99.8% of the Zn was removed. However, only 40% of the Al was removed (from 0.005 to 0.003 mg/L), but this is likely to be a function of the very low Al concentration.

Generally, these systems work well for metals that can be reprecipitated as sulfides or hydrolyse as the pH increases through the treatment system. The dataset provided by Sinclair and Weber (2002) was selected to derive metal removal efficiencies for the WLBM. This dataset was selected for the following reasons:

- Circum-neutral drainage that will be comparable to the BOGP MIW.
- Low metal loads, although iron is moderately elevated (as is expected at BOGP).
- A robust dataset provided over many months of operation.

Where the metal removal efficiencies could not be determined from Sinclair and Weber (2022) as the contaminants were below the limit of reporting (e.g., Cd, Cr, Cu, Pb) it is assumed they would be removed by similar mechanisms. As shown in Figure 11, these metals are also removed by anaerobic passive treatment systems and removal efficiency of 99% was applied. This will require validation by lab and field trials.

PARAMETER	REMOVAL EFFICIENCIES (%)
Calcium ¹	-43.2 ¹
Magnesium	8
Aluminium	83.3 ²
Iron	99.1
Nickel	97.9
Zinc	99.8
Manganese	86.4
Cadmium	85.2 ³
Cobalt	98.4
Copper	85.6 ³
Uranium	74 ³
Vanadium	90 4
Other metals	98 ⁵

Table 9. MSR Treatment Efficiencies

- 1. Negative numbers indicate an increase (e.g., an increase in Ca indicates minor dissolution of the shells.
- 2. Data taken from Trumm et al. (2022). This is considered to be more reasonable due to the very low Al concentrations in the treated water assessed by Sinclair and Weber (2022).
- 3. Data from Trumm et al. (2024).
- 4. Zhang et al. (2022).
- 5. Assumed to be comparable to other metals. Further laboratory and field work is required.

Page 37 MWM-S003-Rev2

10 FURTHER WORK

Further work is required to advance the WTP and PTS studies towards a FS level to confirm technology suitability, costs, and management requirements prior to the systems being installed. Further work should be undertaken once MIW is available from the project area as this will help with water treatability trials. The following section summarises the work that needs to be undertaken.

10.1 Transition to the Post Closure Phase

Modelling (MWM, 2025c) indicates that the transition from active to passive treatment in the Shepherds Creek catchment could occur within 50 years of the cessation of mining. The transition point is a function of:

- Cover system performance (e.g., NP being 20% of rainfall).
- Flow rate and quality.
- PTS treatment efficiency.
- Dilution within Shepherds Creek and Bendigo Creek catchments
- Dilution within the downgradient alluvial aquifers.

Active treatment is not required in the Rise and Shine Creek catchment with partial treatment of the SRX Pit Lake overflow being required. Modelling was based on treatment of the average flow (8 L/s).

10.2 Active Water Treatment Plant

Process Flow indicate that the proposed water quality objectives (Ryder, 2025) can be achieved, although further work is required to develop the OoM study to a feasibility study level. Further details are provided in Appendix B. The WTP will operate until passive treatment systems can be installed.

The WLBM (MWM, 2025c) assumes the water is treated and meets the proposed water quality objectives.

10.3 Passive Treatment System

Trials should be undertaken using BOGP site specific MIW, prior to the site transitioning from active to passive treatment, to assess the treatability of waters by:

- Oxidation to encourage Fe(OH)₃ precipitation and adsorption of metals such as As, V, and other trace metals.
- Anaerobic treatment to remove nitrate, reduce sulfate concentrations, and precipitate metals as sulfides.
- A polishing pond to remove secondary contaminants generated in the anaerobic treatment stage (e.g., hydrogen sulfide (HS-), ammoniacal nitrogen, and low dissolved oxygen).

The technology development pathway should include:

Bench-scale trials to validate OoM study assumptions.

Page 38 MWM-S003-Rev2

- Site-based pilot trials (PFS⁶).
- Operational trials (FS).

For the WLBM the following efficiencies (Table 11) are proposed to understand effects to the receiving environment. These will require validation once mining commences, and MIW is available for trials. Data highlighted in Yellow have lower confidence and further work is needed to confirm the passive treatment systems will be appropriate.

Table 10. PTS Treatment Efficiencies

PARAMETER	REMOVAL EFFICIENCIES 1
Calcium ¹	-43.2%
Magnesium ¹	8%
Aluminium	83.3%
Arsenic	99% ²
Iron	99.1%
Nickel	97.9%
Zinc	99.8%
Manganese	86.4%
Cobalt	98.4%
Uranium	74% ³
Vanadium	90% 8
Other metals	98% 4
Sulfate	30% ⁵
Nitrate nitrogen	99% ⁶
Ammoniacal nitrogen	99% ⁶
Cyanide	90% ⁷

- 1. where data are taken from Table 10 for MSR and limestone of some form is assumed to be part of the treatment media.
- 2. where data are taken from Hayton et al. (2022) = 95% removal with additional Fe to increase As removal to 99% (e.g., Raven et al., 1998).
- 3. where data are obtained from Trumm et al. (2024).
- 4. where data are assumed to be comparable to other metals removed by a MSR (Table 10).
- 5. Based on 30% removal as determined from literature (Figure 21).
- 6. Assumed to be 99% to be in alignment with nitrate removal efficiencies. Further work is required.
- 7. Based on studies by Álvarez et al. (2004). Further work is required.
- 8. Zhang et al. (2022).

Page 39 MWM-S003-Rev2

⁶ Prefeasibility Study

11 REFERENCES

- ANZECC, 2000. Australian and New Zealand guidelines for fresh and marine water quality. Australian and New Zealand Environment and Conservation Council, Agriculture and Resource Management Council of Australia and New Zealand.
- Australian and New Zealand Environment and Conservation Council (ANZG) and Agriculture and Resource Management Council of Australia and New Zealand (ARMCANZ) 2018. Australian and New Zealand Guidelines for Fresh and Marine Water Quality. Canberra.
- Álvarez, R., Ordóñez, A., Martínez, T., Loredo, J., Pendás, F., Younger, P.,2004. Passive treatment for the removal of residual cyanide in drainage from closed gold mine tailing ponds. Available: https://www.researchgate.net/publication/228512053 Passive treatment for the removal of residual cyanide in drainage from closed gold mine tailing ponds
- Ayala-Parra, P., Sierra-Alvarez, R., & Field, J. A., 2016. Treatment of acid rock drainage using a sulfate-reducing bioreactor with zero-valent iron. Journal of hazardous materials, 308, 97-105.
- Babbage, 2019. Waste Rock Seepage Assessment. Report for OceanaGold (New Zealand) Limited. Consent Application Part 2, RM20.024: https://www.orc.govt.nz/consents-and-compliance/current-notified-applications/oceana-gold-new-zealand-limited-rm20024/.
- Burgess, R. M., Perron, M. M., Cantwell, M. G., Ho, K. T., Serbst, J. R., & Pelletier, M. C., 2004. Use of zeolite for removing ammonia and ammonia-caused toxicity in marine toxicity identification evaluations. Archives of environmental contamination and toxicology, 47, 440-447.
- Christenson, H., Skews, R., Trumm, D., Pope, J., Newman, N., Lee, G., Ross, D., Boyt, C., 2022. Enhanced Passive Treatment of Sulfate and Nitrate Enriched Mine Water: Laboratory Optimisation Experiments. In: Pope, J.; Wolkersdorfer, C.; Rait, R.; Trumm, D.; Christenson, H.; Wolkersdorfer, K.: IMWA 2022 Reconnect. p. 47 52; Christchurch, New Zealand (International Mine Water Association).
- Christenson, H., Weber, P., Pope, J., Newman, N., Trumm, D., 2018. Enhanced passive treatment systems: addition of nutrients to bioreactors. New Zealand Annual AuslMM Branch Conference, Tauranga, 10 13 September, p 97 -104.
- Christenson, H., Weber, P., Pope, J., Trumm, D., Olds, W., 2017: Enhancing Mine Drainage Treatment by Sulphate Reducing Bacteria Using Nutrient Additives. In: Wolkersdorfer, C.; Sartz, L.; Sillanpää, M. & Häkkinen, A.: Mine Water & Circular Economy (Vol II). p. 1196 1204; Lappeenranta, Finland (Lappeenranta University of Technology).
- Crombie, F.M., Weber, P.A., Lindsay, P., Thomas, D.G., Rutter, G.A., Shi, P., Rossiter, P., Pizey, M.H. (2011). Passive treatment of acid mine drainage using waste mussel shell, Stockton coal mine, New Zealand. In Proc. 7th Australian Acid and Metalliferous Drainage Workshop, 21- 24 June 2011, Darwin, Australia. Ed L.C. Bell and B. Braddock (JK Tech Pty Ltd).
- CWS 2023. Solar Powered Aeration Systems. https://cwscol.com/solar-powered-aeration-systems.php
- DFAT, 2016. Preventing acid and metalliferous drainage, Leading Practice Sustainable Development Program for the Mining Industry, September 2016, Commonwealth of Australia, Canberra, 211

Page 40 MWM-S003-Rev2

- pp. https://www.industry.gov.au/sites/default/files/2019-04/lpsdp-preventing-acid-and-metalliferous-drainage-handbook-english.pdf
- Dorman, D., 2019. The Role of Solar-Powered Float-Mix Aerators on Iron Retention in Passive Treatment Oxidation Ponds. MSc Thesis. University of Oklahoma. 149 pp.
- Engineering Geology Limited (EGL), 2025. Matakanui Gold Limited Bendigo-Ophir Gold Project Shepherds Tailings Storage Facility Technical Report. EGL Report 9702.
- Guida, S., Potter, C., Jefferson, B., & Soares, A., 2020. Preparation and evaluation of zeolites for ammonium removal from municipal wastewater through ion exchange process. Scientific Reports: 10(1), 1-11.
- Gusek J, Waples JS. 2009. A periodic table of passive treatment for mining influenced water. In: Proceedings 8th International Conference on Acid Rock Drainage (ICARD) and Securing the Future: Mining, Metals & the Environmental in a Sustainable Society 2009; 2009 June 22-26; Skelleftea (Sweden); 584-593.
- Hayton, S., Trumm, D., Horton, T., Pope, J., Ross, D., Williams, M., 2022. Passive Treatment Options for the Removal of Elevated Iron and Arsenic from Circum-neutral Mine Affected Water. In: Pope, J.; Wolkersdorfer, C.; Rait, R.; Trumm, D.; Christenson, H.; Wolkersdorfer, K.: IMWA 2022 Reconnect. p. 147 152; Christchurch, New Zealand (International Mine Water Association).
- INAP, 2021. GARD Guide Chapter 7 Mine Water Treatment March 2021. Published by the International Network for Acid Prevention. www.inap.com.au/wp-content/uploads/GARD-Guide-Chapter-7 Final REV1 JULY2021 ISSUED-1.pdf
- Leavitt, B. and Danehy. T., 2011. TROMPE: From The Past Will Come the Future. OSMRE National Technology Transfer Team (NTTT), Applied Science Fact Sheet. U.S. Department of the Interior, Office of Surface Mining Reclamation and Enforcement, 2 pp.
- Leavitt, B., Page B. J., Mahony R. M., Danehy. T. P., Neely C. A. and Dunn M. H., 2015. TROMPE: From The Past Will Come the Future. Summary Final Report. Cooperative Agreement S11AC2033. Applied Science Program, U.S. Department of the Interior, Office of Surface Mining Reclamation And Enforcement, 46 pp.
- Liao, P. L., Mahasti, N. N. N., & Huang, Y. H., 2022. The recovery of sulfur as ZnS particles from sulfidecontained wastewater using fluidized bed homogeneous crystallization technology. Chemical Engineering Journal, 430, 133170.
- Taumata Arowai , 2022. Drinking Water Standards for New Zealand. Wellington: Ministry of Health. https://www.legislation.govt.nz/regulation/public/2022/0168/latest/whole.html
- Mudder, TI Botz, MM & Smith, A 2001, The Chemistry and Treatment of Cyanidation Wastes, 2nd edn, Mining Journal Books Ltd, London.
- MWM, 2025a. Baseline Water Quality Report Bendigo-Ophir Gold Project. Mine Waste Management Report J-NZ0233-006-R-Rev0.

Page 41 MWM-S003-Rev2

- MWM, 2025b. Net Percolation Assessment for the proposed Bendigo-Ophir Gold Project mine waste storage facilities. Mine Waste Management Report J-NZ0455-001-M-Rev0 for Matakanui Gold Limited.
- MWM, 2025c. Water Load Balance Model Report Bendigo-Ophir Gold Project. Mine Waste Management Report: J-NZ0233-016-R-Rev0.
- MWM, 2025d. Engineered Landform Water Quality Forecast Report Bendigo-Ophir Gold Project. Mine Waste Management Report: J-NZ0457-002-R-Rev0.
- MWM, 2025e. Source Term Definition Report Bendigo-Ophir Gold Project. Mine Waste Management Report J- NZ0475-001-R-Rev0.
- MWM, 2025f. Engineered Landform Design Philo hy. Mine Waste Management Report J-NZ0233-009-M-Rev0.
- MWM (2025g). Factual Report: Geoenvironmental Hazards Bendigo-Ophir Gold Project. Mine Waste Management report: J-NZ0233-008-R-Rev0.
- Navarro, L., Hayton, S., Williams, M., Weber, P., 2022. Globe Progress Lake Closure performance monitoring and adaptive management. In: Pope, J.; Wolkersdorfer, C.; Rait, R.; Trumm, D.; Christenson, H.; Wolkersdorfer, K.: IMWA 2022 Reconnect. p. 323 328; Christchurch, New Zealand (International Mine Water Association).
- Navarro-Valdivia, L., Weber, P., Hillman, C., 2024. Forecasting Water Quality from Waste Rock Stacks

 A Relationship with Height. Paper presented at the AuslMM New Zealand Branch Annual
 Conference 19-21 August 2024, Wellington.
- Process Flow, 2025. BOGP Post Closure Active Water Treatment Plant (WTP) Order of Magnitude (Oom) Study. Process Flow Report PFL-2426-PRJ-RPT-00001 for Matakanui Gold Limited.
- Raven, K. P., Jain, A., & Loeppert, R. H. (1998). Arsenite and arsenate adsorption on ferrihydrite: kinetics, equilibrium, and adsorption envelopes. *Environmental science & technology*, 32(3), 344-349.
- Robinson J., Andrews I. and Dodd J., 2022. Construction of a passive sulfate treatment system. Mine Closure 2022, Brisbane, Australia. p 367-374.
- Ryder, G.I. 2025. Recommended water quality compliance limits for the Bendigo-Ophir Gold Project. Prepared for Matakanui Gold Limited by Greg Ryder Consulting
- Sapkota, Y., Duball, C., Vaughan, K., Rabenhorst, M.C., Berkowitz, J.F., 2022. Indicator of Reduction in Soil (IRIS) devices: A review. Science of the Total Environment 852 (2022) 158419.
- Sinclair, E.J.P., Weber, P., 2022. Managing Legacy AMD to Achieve Successful Mine Closure. In: Pope, J.; Wolkersdorfer, C.; Rait, R.; Trumm, D.; Christenson, H.; Wolkersdorfer, K.: IMWA 2022 Reconnect. p. 511 516; Christchurch, New Zealand (International Mine Water Association).
- Trumm, D., 2013. Trompes, trace elements and bubbles: AMD treatment trends in the USA. AusIMM New Zealand Branch Annual Conference 2013. 8 pp.

Page 42 MWM-S003-Rev2

- Trumm, D., Moynihan, E., Young, G., Pope, J., 2022. Passive Treatment of AMD using a Full-Scale Upflow Mussel Shell Reactor, Echo Coal Mine, New Zealand. In: Pope, J.; Wolkersdorfer, C.; Rait, R.; Trumm, D.; Christenson, H.; Wolkersdorfer, K.: IMWA 2022 Reconnect. p. 511 516; Christchurch, New Zealand (International Mine Water Association).
- Trumm, D., Moynihan, Eamon., Young, G., 2024. Performance of the largest upflow mussel shell bioreactor in New Zealand for the treatment of AMD. In: AusIMM New Zealand Branch Annual Conference, Wellington 20-22 August 2024. PowerPoint presentation.
- Taylor, J., Pape, S., Murphy, N., 2005. A summary of passive and active treatment technologies for acid and metalliferous drainage (AMD). In Proc. Fifth Australian Workshop on Acid Drainage, 29-31 August 2005, Fremantle, Western Australia. ACMER.
- Weightman, E., Craw, D., Rufaut, C., Kerr, G., & Scott, J., 2020. Chemical evolution and evaporation of shallow groundwaters discharging from a gold mine, southern New Zealand. Applied Geochemistry, 122, 104766.
- Zak, D., Hupfer, M., Cabezas, A., Jurasinski, G., Audet, J., Kleeberg, A., McInnes, R., Kristiansen, S., Petersen, R., Liu, H., Goldhammer, T., 2021. Sulphate in freshwater ecosystems: A review of sources, biogeochemical cycles, ecotoxicological effects and bioremediation. Earth-Science Reviews 212 (2021) 103446.
- Zhang, R., Lu, J., Dopson, M., Leiviska, T., 2022. Vanadium removal from mining ditch water using commercial iron products and ferric groundwater treatment residual-based materials. Chemosphere Volume 286, Part 2, January 2022. https://www.sciencedirect.com/science/article/pii/S004565352102289X?ref=pdf download&fr=RR-2&rr=9504a21efc2f74d2

Page 43 MWM-S003-Rev2

12 **LIMITATIONS**

Attention is drawn to the document "Limitations", which is included in Appendix C of this report. The statements presented in this document are intended to provide advice on what the realistic expectations of this report should be, and to present recommendations on how to minimise the risks associated with this project. The document is not intended to reduce the level of responsibility accepted by Mine Waste Management, but rather to ensure that all parties who may rely on this report are aware of the responsibilities each assumes in doing so.

Page 44 MWM-S003-Rev2

APPENDIX A ABBREVIATIONS

ABBREVIATION	DEFINITION
AMD	Acid and metalliferous drainage, which can also include low metal saline drainage
BIOS	Bioremediation systems
BOGP	Bendigo-Ophir Gold Project
CIT	Come in Time deposit
Eh	Oxidation-reduction potential
E-PTS	Enhanced passive treatment system
ELF	Engineered landform
FS	Feasibility study
HRT	Hydraulic residence time
MGL	Matakanui Gold Limited
MIW	Mine impacted water
MSR	Mussel shell reactor
MWM	Mine Waste Management Ltd
NAF	Non-acid forming
NMD	Neutral and metalliferous drainage
NP	Net percolation
NRB	Nitrate-reducing bacteria
OoM	Order of magnitude
PCOC	Potential constituents of concern
PTS	Passive treatment system
RAS	Rise and Shine deposit
RSSZ	Rise and Shine Shear Zone
SCR	Sulfide scrubber
SCK Fill	Shepherds Creek fill
SRE	Srex East deposit
SRX	Srex deposit
TSS	Total suspended solids
TSF	Tailings storage facility
TZ3	Lower Greenschist facies Textural Zone 3 rocks of the Otago Schist
TZ4	Upper Greenschist facies Textural Zone 4 rocks of the Otago Schist
VFR	Vertical flow reactor
WELM	West engineered landform
WLBM	Water and Load Balance Model

ABBREVIATION	DEFINITION
WTP	Water treatment plant
ZVI	Zero valent iron

APPENDIX B WTP OoM DESIGN REPORT



BOGP Post Closure Active Water Treatment Plant (WTP)

Order of Magnitude (Oom) Study

Prepared For: Matakanui Gold Limited

Prepared By: Process Flow

Date: 9/10/2025

Document Number: PFL-2426-PRJ-RPT-00001



Revision Control

Revision	Status	Description	Author	Checked	Approved	Date
A	Draft	Issued for Client Comment	G Smith	E Manhart		12/05/2025
В	Draft Client Review	Issued for Client Review	E Manhart	G Smith		26/05/2025
0	Use	Issued for Use	E Manhart	G Smith	G Smith	16/06/2025
1	Use	Revised Flow Rates	E Manhart	G Smith	G Smith	28/09/2025
2	Use	Revised Tables	G Smith	G Smith		2/10/2025
3	Use	Revised following client comments	E Manhart	G Smith	G Smith	9/10/2025



EXECUTIVE SUMMARY

This report provides an order of magnitude assessment of the water treatment requirements following BOGP mine closure. During the mine closure phase, water treatment will be required by an active Water Treatment Plant (WTP) for years eleven to thirty-one. There are three water management stages during the project.

- Internal water management during the operations phase
- Active water treatment post closure (Summarised in this report)
- Passive water treatment within decades of the mining cessation

This report details the recommended process requirements for an active WTP with the capacity to treat an average flow of 26.9 l/sec.

Potential constituents of concern (PCOC) have been identified for the BOGP based on baseline water quality studies, environmental geochemistry studies, and proposed water quality compliance limits: It is expected that mining of the BOGP will affect waters within the project area, and these effects will include:

- Elevated total suspended solids (TSS) in surface waters.
- Neutral metalliferous drainage (NMD) that may have elevated PCOC such as arsenic (As), Sulphate (SO₄), and trace metals.
- Nitrate-rich drainage due to the use of ANFO.

Following a review of predicted water quality and a literature review of available treatment processes, and the suitability of these processes to remove the PCOCs, an Ettringite precipitation process is recommended.

Known commercial chemical precipitation sulphate removal processes include the SAVMIN process, the CESR (Cost effective Sulphate removal Process) and the Outotec (now Metso) Ettringite process.

The available treatment processes for Ettringite precipitation have been developed for Sulphate concentrations above 2000mg/l, which indicate performance removal of sulphate to 200-100mg/l. (Within the proposed consent limits for surface and ground waters).

Ettringite formation can also provide a polishing effect, allowing precipitation of metals, Ni, Cd, Cu, Zn, Cr, As and Se, often below their compliance limits and laboratory detection limits. Boron, fluoride and up to 30% of chloride and nitrate-nitrite in wastewater have also been removed (Reinsel 1999)

During the operations phase of the project and prior to detailed design of the active WTP it is highly recommended that detailed testing of the actual BOGP water quality take place. This testing should simulate each of the required precipitation steps which would give real data to present and reference for final water quality. This would also give certainty about the effectiveness of the treatment process on the BOGP proposed mine water quality and assurance that the water treatment system will achieve the final water quality and cater for final flow rates.

From the water quality and literature review, the proposed sulphate and metals removal processes will have several sludge management streams with different product outputs, some which will need disposal either on site or off site and some that could be recycled or form a product for export off site.



TABLE OF CONTENTS

1	Introduction	6
1.1	Project Description	6
1.2	Introduction	6
1.3	Surface Water	8
2	Disclaimer	10
3	Process Objectives and Assumptions	11
3.1	Reference Information	11
3.2	Process Objectives	13
3.3	Definition of Plant Flow Rates	13
3.3.1	Average Flow Rates	13
3.4	Definition of Mine Water Quality (Plant Feed Envelope)	14
3.4.1	Shepherds TSF Water Quality	14
3.4.2	ELF and CIT Backfill Water Quality	15
3.4.3	RAS Underground Water Quality	17
3.5	Discharge Water Requirements	18
3.6	Plant Location and Footprint	20
4	Preliminary Process Design	21
4.1	Treatment Literature Review	21
4.1.1	Active Treatment Processes reviewed	21
4.1.2	Design Considerations	23
4.1.3	Treatment Process Site Specific Testing	24
4.2	Treatment Plant Process	24
4.2.1	Savmin Process Summary	24
4.2.2	Metal Hydroxide precipitation and settling	25
4.2.3	Gypsum precipitation and settling	25
4.2.4	Ettringite precipitation and settling	26
4.2.5	Carbonation and pH trimming	26
4.2.6	Recycling of Aluminium Hydroxide	26
4.3	Treatment Process Equipment	26
4.4	Surge Sump	27
4.5	Pontoon Mounted Pumps	27
4.6	Treated Water Sump	28
47	Sludge Management	28



4.7.1	Total Sludge Processing Capacity – Theoretical	. 28
4.8	Other Treatment Processes	. 29
4.8.1	Cyanide Destruct – Shepherds TSF Influent Stream	. 29
4.8.2	Nitrate Removal	. 30
Appendix A	- Process Flow Sheets	. 32



1 INTRODUCTION

Process Flow Limited (PFL) has been engaged by Matakanui Gold Limited (MGL) to provide guidance on water treatment for Mine Impacted Water (MIW) for the proposed Bendigo-Ophir Gold Project (BOGP).

Input water quality data used in this study has been referenced from J-NZ0464-002-R-Rev1 Report on Water Treatment requirements by Mine Waste Management, dated 7 October 2025.

The MWM water and load balance model (WLBM) indicates that the BOGP needs to focus on the management and treatment of MIW that will contain potential constituents of concern (PCOC).

The following PCOC may require treatment by the WTP and PTS to achieve the proposed water quality limits for the BOGP (Ryder, 2025):

- Nitrogenous compounds (N) that include nitrate (NO3) and ammoniacal-N (Amm-N).
- Sulfate (SO4).
- Metals and metalloids that may include Aluminium (Al), arsenic (As), cadmium (Cd), cobalt (Co), copper (Cu), chromium (Cr), iron (Fe), manganese (Mn), molybdenum (Mo), nickel (Ni), lead (Pb), antimony (Sb), selenium (Se), strontium (Sr), uranium (U), and zinc (Zn)
- Cyanide (CN) within the tailings water.

Our work specifically involves carrying out an order of magnitude (OoM) study for:

• Treatment of MIW by a WTP during the active closure phase, until the PTS can be successfully established (~ 50 years after closure).

1.1 Project Description

This section provides an introduction to the BOGP.

1.2 Introduction

MGL is proposing to establish the BOGP (Figure 1), which comprises gold mining operations, processing operations, ancillary facilities and environmental mitigation measures on Bendigo and Ardgour Stations in the Dunstan Mountains of Central Otago. The project site is located approximately 20 km north of Cromwell and will have a maximum disturbance footprint of 550 hectares.

The total Mineral Resource Estimate for the BOGP using a 0.5 g/t cut-off for open pit and 1.5 g/t for underground is 34.3 Mt at 2.1 g/t for 2.34 M oz (MGL, 2025). The Bendigo-Ophir resources occur in four deposits: Come in Time (CIT), Rise and Shine (RAS), Srex (SRX), Srex East (SRE). The majority of identified mineral resources are located within the RAS deposit. Three primary geological units are recognised at site:

- RSSZ Rise and Shine Shear Zone
- TZ3 Lower Greenschist facies Textural Zone 3 rocks of the Otago Schist
- TZ4 Upper Greenschist facies Textural Zone 4 rocks of the Otago Schist



The resources will be mined by open pit methods at each deposit within the project site, with underground mining methods also proposed to be utilised at RAS to access the deeper gold deposits. The majority of the mining activities, ancillary facilities and associated infrastructure will be located in the Shepherds Valley with non-operational infrastructure located on the adjoining Ardgour Terrace. The BOGP also involves the taking of groundwater from the Bendigo Aquifer for use in mining-related activities and the realignment of Thomson Gorge Road via Ardgour Station.

The following mine facilities are proposed (Figure 2):

- Open pits targeting the RAS, SRX, SRE, and CIT deposits.
- An underground mine targeting the RAS deposit.
- Three ex-pit engineered landforms (ELFs) Shepherds ELF, SRX ELF, and West ELF (WELF).
- Two in-pit landforms (backfill) CIT and SRE¹.
- Plant and processing area, where CIL extraction technologies will be used as part of the ore recovery process.
- A tailings storage facility (TSF) and TSF Embankment.
- Other ancillary support services / structures (e.g., roads, water management infrastructure, water treatment plants, etc).

These facilities will be placed in the catchment of Shepherds and Bendigo creeks. Understanding baseline water quality (surface and groundwater) is important to enable the establishment of site-specific water quality compliance criteria for any resource consent that may be granted in the future.

¹ Note: SRE Pit is backfilled by the SRX ELF.






Figure 1. BOGP mineral permit boundaries showing MEP60311 and PEP60882.

1.3 Surface Water

The project area covers several catchments and sub-catchments (Figure 2), including:

- Shepherds Creek: This creek runs permanently through the project area and then intermittently from the Ardgour Terrace towards the Lindis River. An irrigation water-take on Shepherds Creek (RM17.301.15) downstream of SC01 monitoring site takes all available surface water in normal flow conditions, which is supplied to an irrigation dam, so the creek does not flow past this point. There is potential for groundwater to flow past this point via a thin layer of alluvial gravels along the creek bed.
- Jean Creek: This creek is an intermittent tributary to Shepherds Creek.
- Rise and Shine Creek: This creek joins Clearwater Creek south-east of the Come in Time Battery and flows into Bendigo Creek.
- Clearwater Creek: Flows into Bendigo Creek.
- Bendigo Creek: Several irrigation water-takes are in place on this creek (RM20.079.01 and RM20.079.02).






Figure 2. Bendigo-Ophir Gold Project area and water quality monitoring sites.

Baseline water quality data indicates that PCOC are elevated in the BOGP area due to historic mining activities and natural mineralisation. (MWM J-NZ0464-002-R-Rev1)



2 DISCLAIMER

This report provides information that is preliminary in nature and has been prepared to provide the client with water treatment information suitable for an "Order of Magnitude" assessment for the overall project. The information provided is not suitable for detailed design or construction purposes and the information should not be used as a specification for tendering or any other construction related purpose.

This report has been prepared solely for the benefit of Matakanui Gold Limited. No liability is accepted by this company or any employee or sub-consultant of this company with respect to its use by any other person/parties.

This disclaimer shall apply notwithstanding that the memo may be made available to other persons for an application for permission or approval or to fulfil a legal requirement.

This report has been prepared for the particular purpose outlined in the Process Flow Proposal and no responsibility is accepted for the use of this Document, in whole or in part, in other contexts or for any other purpose.

Any assessments made in this report are based on the conditions indicated from published sources and the investigation described. No warranty is included, either express or implied, that the actual conditions will conform exactly to the assessments contained in this memo.

Where data supplied by the client or other external sources, including previous site investigation data, have been used, it has been assumed that the information is correct unless otherwise stated. No responsibility is accepted by Process Flow Limited for incomplete or inaccurate data supplied by others.

Process Flow acknowledges that this report will be relied on by a Panel appointed under the Fast Track Approvals Act 2024 and these disclaimers do not prevent that reliance.

The information presented in this report is based on a literature review of known water treatment process technologies for primarily sulphate and metals removal. The information presented is preliminary, and test-work should be carried during the mining phase of the project (prior to active closure) to confirm design assumptions and prove final water qualities can be achieved for the flows required.



3 PROCESS OBJECTIVES AND ASSUMPTIONS

3.1 Reference Information

- J-NZ0464-002-R-Rev1 Report on Water Treatment requirements by Mine Waste Management, dated 7 October 2025.
- Barabash Sarah J., Ph.D., Nicholson R.V. (Ron), Ph.D., P.Geo. (ON), (2019) In-Pit Batch
 Treatment of Arsenic Laboratory Studies and Field Trial, June 2019, MEND Report 3.60.1
- Bowell, R. (2004). A review of sulfate removal options for mine waters.
 https://www.researchgate.net/publication/242630869_A_review_of_sulfate_removal_options_for_mine_waters
- Bratty M, Blumenstein E, Conroy K, Jankhah S, Pretorius C, Rutkowski T, Van Niekerk A, Vassos T. Golder Associates, (2014) Challenges and Best Practices in Metal Leaching and Acid Rock Drainage – Established and Innovative Sulfate Removal Treatment Processes, 2014 Dec 4, 21st Annual British Columbia ML/ARD Workshop.
- Brown M, Barley B, Wood H, 2007, Minewater Treatment Technology, Application and Policy, IWA Publishing, Volume 6, DOI: https://doi.org/10.2166/9781780402185 ISBN electronic: 9781780402185.
- Dou W, Zhou Z, Jiang L, Jiang A, Huang R, Tian X, Zhang W, Chen D, (2017) Sulfate removal from wastewater using ettringite precipitation: Magnesium ion inhibition and process optimization, Journal of Environmental Management 196 pp518-526, Elsevier.
- GARD Guide Chapter 7 Mine Water Treatment, 2021 March
- Lorax Environmental. (2023). Treatment of sulphate in mine effluents, International Network for Acid Prevention.
- Mitchell Daysh, Bendigo-Ophir Gold Project Project Description for Technical Reports
- Paul L. Younger, Stephen A Banwart, and Robert S Hedin (2002), Minewater Hydrology, Pollution, Remediation, Kluwer Academic Publishers.
- Reinsel, Mark A, A new process for sulphate removal from industrial waters. Proceedings America Society of Mining and Reclamation. 1999 pp546-550. https://doi.org/10.2100/JASMR99010546.
- Ryder (2025), Recommended water quality compliance limits for the Bendigo-Ophir Gold Project, Ryder Consulting.
- Smit, J P, (1999/2012), The Treatment of Polluted Mine Water, Mine, Water & Environment, 1999 IMWA Proceedings, Congress, Sevilla, Spain, International Mine Water Association 2012.



- Water Services (Drinking Water Standards for New Zealand) Regulations 2022
- Zahedi R, Mirmohammadi S J, 2022, Sulfate removal from chemical industries' wastewater using ettringite precipitation process with recovery of Al(OH)3, Applied Water Science (2022) 12: 226, Springer, https://doi.org/10.1007/s13201-022-M01748-7
- Palmer S A K, Breton M A, Nunno Thomas J, Sullivan D M and Surprenant N F, (1987) Treatment
 Technologies for Metal/Cyanide-containing waste Volume III, USEPA EPA/6000/2-87/106
- SGS Mineral Services T3 SGS 018 (2005) Cyanide Destruction
- Gokelma M, Birich A, Srecko S and Friedrich B, 2016, A Review on Alternative Gold Recovery Reagents to Cyanide, Journal of Materials Science and Chemical Engineering, 2016, 4, 8-17, Scientific Research Publishing
- Young, C.A. and Jordan, T.S., 1995, Cyanide Remediation: Current and Past Technologies, Proceedings of the 10th Annual Conference of Hazardous Waste Research, Department of Metallurgical Engineering, Montana Tech, Butte, MT59701



3.2 Process Objectives

During the Active Closure Phase, water treatment is required by a water treatment plant (WTP) once the project switches from a process of internal water management for MIW (during operations) to discharge of MIW from site after closure of the mine. Model results indicate that the WTP can be replaced by a passive treatment system (PTS) within decades of mining cessation, which then defines the commencement of the Post Closure Phase.

3.3 Definition of Plant Flow Rates

This section summarises the long-term average flow rates for each mine domain that may require treatment during the Active Closure and Post Closure phases of the BOGP.

3.3.1 Average Flow Rates

Average flow rates are estimated from the Water and Load Balance Model. It is assumed that the use of average flow rates is suitable for the WTP OoM Study and the PTS Concept Study. Peak flows may require either a larger capacity plant or a surge pond prior to any treatment. Further work is required to advance the designs to a feasibility Study (FS) level including understanding the treatment requirements for peak flow rates.

Table 1 provides a summary of flow rates for the various mine domains that require treatment. These flow rates are preliminary and are intended to provide guidance for the OoM study on the WTP design. For the OoM WTP Study it is recommended that the design include suitable contingency for variable flow rates. Active treatment is not required for SRX Pit - It is expected that the water quality from this mine domain will be acceptable for release to the receiving environment (e.g., Rise and Shine Creek / Bendigo Creek) with passive treatment.

Table 1: Estimated average water quantity per mine domain.

MINE DOMAIN	WTP DESIGN CRITERIA (L/s)	PTS (L/s)	COMMENTS
Shepherds ELF	4	4	20% Net percolation
SRX ELF ^{1, 2}	-	1	20% Net percolation
West ELF ²	1	1	20% Net percolation
Shepherds TSF	13.4	3	 Flow is expected to be ~13.4 L/s decreasing to 3 L/s after 5 years
RAS Underground Portal	6	6	 Flow from the RAS Underground is not expected for 20-30 years after closure
CIT Pit Backfill	1.5	1.5	 Further details are available in MWM J-NZ0464-002-R-Rev1
SRX Pit	-	8	 Further details are available in MWM J- NZ0464-002-R-Rev1. It is assumed this water will not require active



MINE DOMAIN	WTP DESIGN CRITERIA (L/s)	PTS (L/s)	COMMENTS
			treatment. Passive treatment is required.
SCK Fill ²	1	1	20% Net percolation
Non-AMD impacted water	-	-	 Managed for TSS separate to the active WTP. At closure rehabilitated surfaces are assumed to be suitable for discharge with TSS management.

^{1.} Active treatment for SRX ELF and SRX Pit are not anticipated.

Table sourced from MWM J-NZ0464-002-R-Rev1

This results in an active water treatment plant with the capacity to treat an average flow of 26.9 l/sec.

3.4 Definition of Mine Water Quality (Plant Feed Envelope)

This section summarises the water quality from the various mine domains that require treatment at closure of the BOGP by the active water treatment plant. Peak concentrations are provided for the following streams

- Shepherds ELF
- West ELF
- Shepherds TSF
- RAS Underground Portal
- CIT Pit Backfill
- SCK Fill

3.4.1 Shepherds TSF Water Quality

TSF seepage water quality at mine closure (Year 11) is presented in Table 2. Further details on how the water quality was derived are provided in MWM J-NZ0464-002-R-Rev1

Constant concentration is assumed.

Table 2: TSF seepage water quality (Closure).

PARAMETER	CLOSURE TSF SEEPAGE WATER QUALITY
Alkalinity (mg CaCO₃/L)	73.21
pH (pH units)	6.41
EC (μS/cm)	4,121
Ca	297
Cl	804
F	1.93
Mg	99
Na	847
K	50.8
TOC	<u>-</u>

^{2.} Flow rates rounded up to 1 L/s



PARAMETER	CLOSURE TSF SEEPAGE WATER QUALITY
Al	0.01
Ag	0.0068
As	2.05
В	0.825
Cd	0.0002
Со	0.053
Cr	0.0055
Cu	0.001
Fe	15.3
Mn	0.59
Mo	0.14
Ni	0.678
Pb	0.0275
Sb	0.18
Se	0.003
Sr	4.4
Tl	0.001
U	0.028
V	0.004
Zn	0.0296
Cyanide - WAD	0.35
Sulfate	954
Ammoniacal-N	2
Nitrate-N	0.005

Note: All units in mg/L unless otherwise stated. Green data are LOR and are included in the source term as '0' WAD – Weakly Acid Dissociable cyanide; If no data are provided these are identified by '-'.

3.4.2 ELF and CIT Backfill Water Quality

Water quality for the ELFs is provided in Table 3, (Table sourced from MWM J-NZ0464-002-R-Rev1) which shows the water quality for Year 27, when maximum loads are being derived from the Shepherds ELF to provide peak concentration data for the design of the WTP.

Constant concentrations are assumed for As (0.2 mg/L) and Fe (7.6 mg/L) based on empirical data for sub-oxic conditions (e.g., Globe Progress Waste Rock Stack, Hayton et al., 2022). These concentrations are above the proposed water quality reference limit (Ryder, 2025) and will require management. The SCK Fill assumes full oxidation, which results in low Fe concentrations.

Table 3. Water Quality Data (Year 27) for WTP design – 20 m Oxygen Exclusion Model

STATION	TSF SEEPAGE	SHEPHERDS ELF SEEPAGE	WELF SEEPAGE	CIT PIT BACKFILL	SCK FILL SEEPAGE	MIW COMBINED*
Acidity	0.01	0	0	0	0	0.03
Al	0.011	0.003	0.003	0.005	0.003	0.013
Alkalinity	73	189	183	190	158	160
As	2.06	0.20	0.20	0.08	0.20	0.61



STATION	TSF SEEPAGE	SHEPHERDS ELF SEEPAGE	WELF SEEPAGE	CIT PIT BACKFILL	SCK FILL SEEPAGE	MIW COMBINED*
В	0.83	0.87	0.10	0.09	0.01	0.59
Ca	297	51	51	39	36	107
Cd	0.0002	0	0	0.0001	0	0.0001
Cl	806	63	37	12	8	223
Со	0.053	0.109	0.023	0.004	0.003	0.061
Cr	0.00636	0.00020	0.00019	0.00040	0.00007	0.00170
Cu	0.00100	0	0	0.00021	0	0.00049
DOC	0	0	0	0.206	0	0.038
F	1.94	6.30	6.12	1.39	2.37	3.90
Fe	15.3	7.6	7.6	2.4	7.6	8.7
Hg	0	0	0	0.00014	0.00000	0.00003
K	51	683	672	84	159	372
Mg	100	38	37	20	24	49
Mn	0.594	0.819	0.774	0.103	0.182	0.567
Мо	0.140	1.005	0.672	0.119	0.157	0.535
NO3-N	2.01	49.64	9.54	0.73	1.33	22.89
Na	848	922	734	127	170	673
Ni	0.6784	0.0121	0.0010	0.0013	0.0001	0.1652
Pb	0.0276	0.0001	0.0001	0.0002	0.0000	0.0068
Sb	0.1802	2.9986	3.2208	0.3622	0.7601	1.6317
Se	0.0030	0.1544	0.1649	0.0196	0.0388	0.0826
SO4	954	957	888	110	208	730
Sr	4.40	16.15	15.91	3.77	10.89	10.12
TI	0	0	0	0.00021	0.00000	0.00005
CN	0.35	0	0	0	0	0.08238724
U	0.0280	0.2751	0.2225	0.0299	0.0515	0.1468
V	0.0040	0.1200	0.1155	0.0135	0.0269	0.0633
Zn	0.0296	0.0098	0.0021	0.0014	0.0003	0.0117
pH (pH unit)	6.41	7.93	7.92	8.03	7.92	6.72
Hardness	1,151	285	280	179	190	469

Units in mg/L *MIW Combined - This is a weighted average



3.4.3 RAS Underground Water Quality

As discussed in MWM J-NZ0464-002-R-Rev1 seepage from the RAS Underground will be comparable to the RAS Pit Lake. The RAS Underground is not expected to commence discharge until Year 26. Water Quality for Year 26 is provided in Table 4.

Table 4 RAS Underground water quality (Year 27)

PARAMETER	RAS UNDERGROUND		
Acidity	0.44		
Al	0.100		
Alkalinity	182		
As	0.09		
В	0.05		
Ca	59		
Cd	0.0001		
CI	14		
Со	0.000		
Cr	0.00058		
Cu	0.00302		
DOC	0.090		
F	0.23		
Fe	7.9		
Hg	0.00006		
K	34		
Mg	37		
Mn	0.014		
Мо	0.020		
NO3-N	4.35		
Na	42		
Ni	0.0009		
Pb	0.0035		
Sb	0.0234		
Se	0.0008		
SO4	141		
Sr	0.79		
TI	0.00031		
CN	0		
U	0.0094		
V	0.0006		
Zn	0.0022		
pH (pH unit)	5.91		
Hardness	299		

Units in mg/L



3.5 Discharge Water Requirements

PCOC that have been identified for the BOGP based on baseline water quality studies, environmental geochemistry studies, and proposed water quality compliance limits are shown in Table 3. Limits are based on:

- Ecotoxicity assessments developed by Ryder (2025) for the proposed surface water compliance sites
- Groundwater limits are based on New Zealand Drinking Water Standards (MoH, 2022).

The proposed compliance monitoring locations are shown in Figure 2 for surface waters and groundwaters.

For conceptual desk-top studies, it is proposed that the WTP and PTS design should be based on the more stringent water quality criteria (i.e., the lower compliance value) for surface and groundwaters to ensure that treated waters comply with both criteria.

These proposed water quality criteria for the BOGP (Ryder, 2025) are summarised in Table 5.

Table 5. Proposed Water Quality Compliance Limits for the BOGP

PARAMETER	SURFACE WATER	GROUNDWATER	
(UNITS ARE mg/L UNLESS STATED OTHERWISE)	RECOMMENDED COMPLIANCE LIMIT(S)	RECOMMENDED COMPLIANCE LIMIT(S)	
pH (unitless)	6.5 - 9.0	-	
Turbidity (NTU)	5 (over a 5-year rolling period, 80% of samples, when flows are at or below median flow, are to meet the limit)	-	
Ammoniacal- nitrogen (NH₃-N)	≤0.24 (annual median) <0.4 (annual 95 th %)¹	-	
Nitrate-nitrogen	<2.4 (annual median)	11.3 (MAV) ²	
(NO ₃ -N)	<3.5 (annual 95th %)		
Cyanide (CN ⁻)	0.011 (un-ionised HCN, measured as [CN], ANZG 2018) ¹	0.6 (MAV)	
Sulfate (SO ₄ ²⁻)	 If hardness is <100 mg/L (CaCO₃), the sulfate compliance limit = 500 mg/L. If chloride is <5 mg/L, the sulfate compliance limit = 500 mg/L. If the hardness is 100-500 mg/L AND if chloride is 5-<25 mg/L, the sulfate compliance limit is (in mg/L): [-57.478 + 5.79*(hardness mg/L CaCO₃) + 54.163*(chloride mg/L)] * 0.65 If hardness is between 100 and 500 mg/L AND if chloride is between ≥25 and ≤500 mg/L, the sulfate limit is (in mg/L):	≤250 (taste threshold)	



PARAMETER	SURFACE WATER	GROUNDWATER
(UNITS ARE mg/L UNLESS STATED OTHERWISE)	RECOMMENDED COMPLIANCE LIMIT(S)	RECOMMENDED COMPLIANCE LIMIT(S)

For compliance limits in the points above, no more than 20% of samples collected over a rolling 12-month period may exceed the relevant compliance limit.

 An acute compliance limit = 1,000 mg/L averaged over 4 days and not to be exceeded more than once in a one-year period, OR in more than 10% of samples over a one-year period.

Aluminium (Al)	≤0.08	1 (MAV)
Antimony (Sb) (total)	0.074 (chronic) 0.250 (acute)	0.02 (MAV)
Arsenic (As(V))	≤0.042	0.01 (MAV)
Cadmium (Cd)	≤0.0004³	0.004 (MAV)
Chromium (Cr)	≤0.0033 (Cr(III)) ⁴ ≤0.006 (Cr(VI)) ⁴	≤0.05(MAV, Total Cr)
Cobalt (Co)	0.001 (chronic) ⁵ 0.11 (acute, not to exceed) ⁵	<1 (livestock drinking water)
Copper (Cu)	≤0.0018	≤0.5
Iron (Fe) (total)	-	≤0.3
Lead (Pb)	-	0.01 (MAV)
Manganese (Mn)	-	0.4 (MAV)
Molybdenum (Mo)	≤0.034	<0.01
Selenium (Se)	-	0.02
Strontium (Sr) (total)	-	4
Uranium (U)	-	0.03 (MAV)
Zinc (Zn)	≤0.015 ⁶	≤1.5

All limits are dissolved unless noted as total

The PCOC presented in section 3.4 were identified from the baseline studies, source hazard assessment, geochemical modelling, and the water and load balance modelling to understand potential effects of the BOGP.

[&]quot;-" = no limit recommended.

¹ = refer to Ryder (2025), for concentration adjustments.

 $^{^{2}}$ MAV = Maximum acceptable value – From the NZ drinking water standards.

³ Cd (dissolved) is adjusted by the following algorithm: HMTV = TV*(H/30)*0.89, where hardness-modified trigger value (HMTV) = (μ g/L), trigger value (TV) (μ g/L) at a hardness of 30 mg/L as CaCO3; H, measured hardness (mg/L as CaCO3) of a fresh surface water.

 $^{^4}$ = Cr (dissolved) is adjusted by the following algorithm: Chromium (mg/L) = Toxicity value (mg/L)*(H (mg/L)/30) $^{0.82}$

⁵ = Co (dissolved) is adjusted by the following algorithm: Cobalt (μ g/L)= exp {(0.414[In(hardness CaCO $_3$ mg/L)] - 1.887}

 $^{^6}$ = Zn (dissolved) is adjusted by the following algorithm: Zinc (mg/L) = Toxicity value (mg/L)*(H (mg/L)/30) $^{0.85}$




3.6 Plant Location and Footprint

The proposed location for the Active WTP is located on Shepherds creek near the mine regeneration zone (area labelled "Water Treatment Plant" on the image shown below).

The size and footprint requirements for the WTP and Surge and Treated water ponds is as follows.

- WTP Footprint An area approximately 100 m x 60 m TBA is recommended to be located near the surge and treated water ponds.
- WTP Surge Pond 14,000 m³ (see section 4.4 for detail and sizing philosophy)
- WTP Treated Water Pond 2,000 m³ (see section 4.6 for detail and sizing philosophy)





4 PRELIMINARY PROCESS DESIGN

The following is a description of the preliminary level process design which has been developed for the purpose of selecting plant options. This description should be read in conjunction with the preliminary design process flow diagrams PFL-2426-PRO-PFD-00001 to 00003 (Sheets 1 to 3) included in Appendix A of this report.

The selected process is based on known water treatment process technologies for primarily sulphate and metals removal as described in the following sections. It should be noted that the design selection is preliminary, and test-work should be carried during the mining phase of the project (prior to active closure) to confirm design assumptions and prove final water qualities can be achieved.

The process selected involves the following unit processes.

- Surge Sump
- Pontoon mounted pumps for plant feed
- Metal hydroxide precipitation and settling
- Gypsum precipitation and settling
- Ettringite precipitation and settling
- Carbonation and pH trimming
- Treated Water Sump
- Sludge Management

Other processes that will likely be needed in addition to the active WTP are:

- Cyanide Destruct on the Shepherds TSF influent stream
- Potential additional nitrate removal after the WTP via biological processes

4.1 Treatment Literature Review

A range of Active Treatment technologies for sulphate and metals removal exist, including Ettringite Precipitation, Biological Sulphate Removal, Ion Exchange, Reverse Osmosis, Electrocoagulation, Treatment and Extraction of Rare Earth Metals. This section is a review of the processes currently available at bench and pilot trial and full plant scale for sulphate and metals removal.

4.1.1 Active Treatment Processes reviewed

The following active treatment processes were reviewed for suitability for sulphate and metals removal:

- Biological processes
- Membrane treatment including Reverse Osmosis
- Ion exchange
- Electrocoagulation
- Treatment and extraction of rare earth elements
- Chemical Treatment and Mineral Precipitation (Lime addition, Barium Salts addition, CESR, Savmin, Outotec/Metso, (GARD, 2021; Lorax, 2023))



The processes that are still only under bench scale and research and development stage are:

- Electrocoagulation (developed to bench scale)
- Treatment and extraction of rare earth elements (This is under research and development only (GARD, 2021)

With the passage of time, these treatment options may become viable however at this stage they are not considered a proven technology suitable for full scale plant application for this BOGP project.

Reverse Osmosis, Ion exchange and Biological Processes have been discounted for this project as active treatment options.

Reverse Osmosis may be appropriate if sulphate concentration was lower than the sum of all metals and chloride (if operational and capital consideration allowed).

Reverse Osmosis and membrane processes generally produce large quantities of membrane reject waters (brine) which requires reprocessing and disposal. Capital and operating costs for membranes are high, with RO operating pressures high, and chemical use for fouling removal has potential to be high (Lorax, 2023). Operational issues associated with RO and Membranes include high fouling and cleaning rates with membrane longevity is shown to be reduced in these applications (Lorax, 2023).

Ion exchange processes do not have long track record for this application at full plant size, although information about trials at pilot scale are available (Lorax, 2023). Ion exchange processes produce quantities of gypsum sludges, and high amounts of brine which need further processing. They are not widespread in use for this application (Bratty et al,2014). One ion exchange technology, the GYP-CIX process is suitable for treated mine waters with high levels of TDS, sulphate and calcium (up to 2000mg/l). It uses calcium hydroxide and sulphuric acid to regenerate the ion exchange resins. Costing of resins would have to be done to compare lime and other chemical costs to see if this process would be viable. For this BOGP project it has been discounted due to insufficient information on its long-term use at full scale for this application.

Biological Processes can be limited by sufficient organic carbon and nutrients in mine influence waters and the presence of heavy metals limiting growth. (Lorax 2023, Bratty et al, 2014)

Biological treatment with sulphate-reducing bacteria is suitable to low or moderate sulphate loadings (Qian et al., 2015; Silva et al., 2012), but its application is usually hindered by the shortage of organics, the inhibition of high salinity and metal ions in the wastewater (Mothe et al., 2017), and the generation of hydrogen sulphide (Runtti et al., 2016). (Dou. W, 2017)

There has been limited application of Biological Treatment in Active Water Treatment systems and is more successful used in Passive Treatment systems. (Bratty et al, 2014)

Sulphate removal using chemical precipitation include processes of lime addition, barium salts addition and proprietary processes such as the CESR (Cost Effective Sulphate Removal process), Savmin, Oututec/(Metso) processes (GARD, 2021; Lorax, 2023).

(It is noted in literature that Barium Sulphate is highly insoluble and as an alternative to Calcium Hydroxide, the addition of Barium Hydroxide is extremely effective at removing sulphate. Barium Hydroxide is however, an expensive, corrosive and toxic treatment chemical and this rarely represents a cost-effective treatment option to use this as a hydroxide for this stage of the process. (Gard, 2021).)



For mine water that is net acidic, where low residual metal and sulphate concentrations are needed in the treated discharge water, and the sulphate concentration is higher than the sum of metals and chloride, where carbon sources (crude or refined) are not available or are expensive, then the Savmin process is recommended as an appropriate technology (Younger et al 2002).

Ettringite Precipitation (addition of Lime and Al(OH) $_3$ can be used to remove sulphate and heavy metals. Ettringite (3CaO.2CaSO $_4$.Al $_2$ O $_3$.31H $_2$ O) has very low solubility and therefore sulphate concentrations are low in treated water after precipitation and settling.

The Main unit operations for known processes for sulphate removal with Ettringite precipitation involve:

- 1. Metals Precipitation pH lift with Lime to the range of 11.5 to 12 (Calcium Hydroxide, rather that barium), this enables Al dissolution
- 2. Gypsum Precipitation
- 3. Ettringite Precipitation Al³⁺ addition to remove sulphate as precipitated ettringite
- 4. pH reduction of the treated water with CO2 to meet effluent discharge criteria and precipitate CaCO3

Ettringite sludge must be separated by gravitation separation and or filtration (Reinsel 1999, Lorax Environmental 2003, Outotec 2014).

Known commercial chemical precipitation sulphate removal processes include the SAVMIN process, the CESR (Cost effective Sulphate removal Process) and the Outotec (now Metso) Ettringite process. All commercial processes follow similar principles:

SAVMIN uses aluminium oxide (aluminiumtryhydroxide in amorphous or gibbsite form) to create ettringite, with recovery. CESR uses a proprietor Al containing chemical from cement production, without recovery of aluminium source. The Outotec process does not contain a separate lime addition step. (Lorax Environmental 2003, Outotec 2014).

The processes have been developed for Sulphate concentrations above 2000mg/l, with performance levels providing removal of sulphate to 200-100mg/l. Ettringite formation can also provide a polishing effect, allowing precipitation of metals, Ni, Cd, Cu, Zn, Cr, As, Se, Cd, Boron, fluoride and chlorite and nitrate, in waste up to 30% have been removed (Reinsel 1999, Outotec 2014)

4.1.2 Design Considerations

Operating costs for the SAVMIN process depend on reagent use which depends on levels of sulphate and univalent cations (Na, K, NH4 etc present in the feed water (Smit, 1999)).

Typically, there are low settling rates for the liquid/solid separation phases (Smit 1999). For this reason, conventional high-flow thickeners are preferred for the solid-liquid separation phases in the treatment process (Lorax, 2023). Mixing times for each phase varies from 30-60 minutes but will depend on site specific water quality.



Magnesium ions can interfere with sulphate removal by inhibiting the formation of ettringite (Zahedi et al, 2022).

It is reported that Mg^{2+} has adverse effects on the formation of ettringite in cement paste (De Weerdt et al., 2014), and prevents sulphate removal as gypsum (Tolonen et al., 2015). However, the effects of Mg^{2+} on ettringite, precipitation are scarcely reported, and it should be essential for process design and very useful for understanding the precipitation behaviour in real wastewater rich in Mg^{2+} and sulphate. (Dou. W, 2017), also

The study by Dou. W, et al shows that Mg²⁺ has a significant inhibitory effect on sulphate removal by ettringite precipitation and that an additional precipitation step prior to ettringite precipitation is needed to remove magnesium hydroxide as a settled precipitate (as well as metal hydroxides). Dou.W, 2017 et al found in their study that High Caustic alkalinity (using Sodium Hydroxide) and low Mg are the most suitable conditions to precipitate ettringite.

Others have found that using calcium hydroxide as the initial step is effective in reducing magnesium concentration by conversion to insoluble magnesium hydroxide precipitate at pH 12. (Zahedi et al, 2022, Smit, 1999 and Lorax, 2023)

The operating parameters such as molar ratios of SO_4^{2-}/Ca^{2+} and SO_4^{2-}/Al^{3+} , and pH value have a significant effect on the sulphate removal process efficiency (Aygun et al. 2018, as cited in Zahedi 2022).

4.1.3 Treatment Process Site Specific Testing

The sulphate removal process is not commonly used in New Zealand and elsewhere there are limited full size treatment plant sites with available design data to reference.

The ability to test the on-site mine influenced water, or a laboratory formed mimic water, similar to the BOGP proposed water quality and then simulate each of these precipitation steps would give real data to present and reference for final water quality. This would also give more certainty about the effectiveness of the treatment process on the BOGP proposed mine water quality and assurance that the water treatment system will achieve the final water quality. It is proposed that during the detailed design phase that this level of bench scale and pilot scale testing be performed.

4.2 Treatment Plant Process

Of the chemical precipitation processes, a process like the SAVMIN process is proposed for this project.

4.2.1 Savmin Process Summary

The Savmin process uses precipitation reactions to remove sulphates from minewater. This process also removes heavy metals and calcium. The first stage is addition of lime to raise pH and precipitate out metals and magnesium as hydroxides.

After separating out the hydroxides, the resulting supersaturated calcium sulphate solution is contacted with gypsum crystals, which catalyse the precipitation of calcium sulphate (gypsum). Due to the slow settling rate of the precipitates, the most cost-effective equipment for the solid-liquid separation stages of the process are parallel-plate cone clarifiers.



In the third stage of the process, aluminium hydroxide is added to the solution which causes formation of the insoluble salt ettringite, which removes calcium and sulphate from solution.

The solution is then treated with carbon dioxide to lower the pH (process pH values in the first and third stages of the process need to be maintained at 11.6 to 12). The lower pH causes the precipitation of pure calcium carbonate which is separated from the water by filtration.

The final stage of the process is the recycling of ettringite, in which the ettringite slurry is which is treated with sulphuric acid to regenerate aluminium hydroxide.

Reported removal rates are: Heavy metals removed to below drinking water levels; 99% of calcium; 100% of magnesium and 98% of Sulphate. Sodium, chloride, potassium and fluoride are not removed. (Brown. et al, 2002)

4.2.2 Metal Hydroxide precipitation and settling

The metal hydroxide precipitation step is part of both the Savmin and CESR (Cost Effective Sulphate removal process) and generally consists of addition of Hydrated lime (Calcium Hydroxide) to a pH of 10.5-11, mixing from 30- 60 minutes (Reinsel.M,1999). Levels of pH of up to 12-12.5 have been documented and mixing time up to 3 hours.

Settling of the precipitated metals and magnesium as hydroxides occurs and this sludge will need further processing via thickening, dewatering and disposal.

With respect to the BOGP project, during the closure phase in the 50 years when the active treatment system will be used, if Chemical precipitation processes are chosen, large volumes of sludge will be produced (as a byproduct of water treatment) will be created.

Further studies need to be completed to determine the quantity and quality of the water treatment residues (including sludge) for both active and passive treatment systems and identify appropriate disposal options and locations. The sludge should be disposed of at a suitable facility or studies should be undertaken to confirm onsite management options.

4.2.3 Gypsum precipitation and settling

Following removal of the settled metal hydroxides, the liquid is contacted with gypsum to provide active surfaces and catalyse the precipitation of the supersaturated gypsum (Smit, 1999). This precipitated gypsum is then thickened and filtered with some leaving the process and some recycled to the mixing tank as the seed gypsum. It is noted that the sulphate content of the water leaving this stage is dependent on the pH. Higher pH will result in lower sulphate concentrations. The pH in this stage is determined by the settling of the metal hydroxides from the previous stage (at high pH, poor settling occurs).

As gypsum interferes with the precipitation reaction of ettringite, it is important that all gypsum is removed from the feed water before the ettringite formation process steps. (Lorax, 2023).



4.2.4 Ettringite precipitation and settling

Following the precipitation and removal of gypsum, Aluminium Hydroxide is added to the liquid phase. This allows the insoluble salt ettringite to precipitate which results in the removal of both sulphate and calcium from the solution (Smit, 1999).

The stoichiometry of the formation of ettringite with the addition of aluminium is:

$$6Ca^{2+} + 3SO_4^{2-} + 2AI (OH)_3 + 38H_2O <--> Ca_6AI_2(SO_4)_3(OH)_{12}.26H_2O + 6H_3O^+$$

The optimal pH range for the formation of ettringite is 11.6-12.0. The pH is maintained in this range by the addition of lime. Literature suggests that for efficient sulphate removal, a multistage reactor is required to produce an ettringite product with good liquid solid separation characteristics (Smit 1999). The ettringite is removed from the process using thickening, filtration.

Long mixing phases for the aluminium hydroxide/ettringite formation were reported in some instances, up to 61h mixing (Zahedi et al, 2022).

4.2.5 Carbonation and pH trimming

At this stage the waste water stream, with a pH 11-12 and dissolved SO4 <200mg/L is treated with carbon dioxide gas to lower the pH and to prevent scaling. The reduction of pH is prior to discharge to the receiving environment such as surface water or to the nitrate removal system. Relatively pure $CaCO_3$ is precipitated and removed by filtration or settling. Alternatively, pH can be adjusted to precipitate $Ca(HCO_3)_2$. (Lorax, 2023)

If treated water will be used again in the process, as service water, (for mixing, dosing chemical makeup water and washing), then reduction of pH and stabilisation to prevent deposition of hard carbonate scale on filters and distribution piping is required.

4.2.6 Recycling of Aluminium Hydroxide

Aluminium hydroxide is recovered by thickening and filtration and reused in the third stage as the ettringite formation catalyst (Lorax, 2023).

This recovery is achieved by taking the ettringite slurry from the Ettringite Precipitation phase, adding sulphuric acid to lower the pH and decompose the ettringite. This decomposition takes place in gypsum saturated water at a liquid to solid ratio that allows the calcium and sulphate ions to remain in solution as supersaturated calcium sulphate (Smit 1999). The stoichiometry is the reverse of the ettringite formation reaction.

Instead of sulphuric acid, CO2 can be used, however it converts half of the calcium from the ettringite forms solid calcium carbonate. Some of the regenerated aluminium hydroxide then has to be removed from the circuit as a bleed to control the buildup of calcium carbonate (Smit 1999).

4.3 Treatment Process Equipment



The SAVMIN process contains precipitation reactions in conventional stirred reactors at ambient pressure and temperature. The reactors will be mixing tanks, with mechanical agitators, and settling/clarification vessels in the most part and associated slurry and sludge pumps.

During settling phases of this treatment, settling rates potentially will be lower than conventional thickeners, but sludge volumes may be high, so allowance should be made on site for tall deep cone settlers. The Wren Parallel Cone clarifiers are mentioned in literature. These either have no moving parts for the settling phase or have rotating flocculator in the centre cylinder. Parallel settlers are also mentioned in literature, as an option for a smaller site footprint, but scale removal provisions for maintenance in design would have to be paramount and a less restricted settling vessel may be preferable if site space allows.

Most of the vessels will contain water to pH 12 or thereabouts. There will also be chemical dosing of strong acids such as sulphuric acid and acid coagulants (Aluminium Sulphate and Aluminium Hydroxide). Durability of vessels, piping and pumps will be paramount in design, as will chemical safety during maintenance.

Most of the pipelines and pumping and vessels will involve materials in liquid, slurry or sludge form with the propensity for scale formation from calcium carbonate, gypsum and ettringite, so allowance should be made for scale removal maintenance and redundancy for all equipment in case of blockage and scale removal maintenance downtime.

EQUIPMENT DESCRIPTION	PROCESSES USED		
Mixing Vessels	Stage 1, 2 and 3 plus lime saturation and Ettringite decomposition		
Settling Clarifiers	Stage 1, 2 and 3		
Chemical Dosing systems	Lime, Aluminium Hydroxide, Aluminium Sulphate, Carbon Dioxide Sulphuric Acid		
Sludge Handling, Dewatering and disposal systems	Metal Hydroxide, Gypsum, Ettringite, Calcium Carbonate		

4.4 Surge Sump

A surge sump located adjacent to plant has been included in the design. Primarily this is to allow a pumped (fixed speed) feed to the plant. Recommended sump/pond sizing is based seven days storage at average flow.

PLANT FEED RATE	DURATION/RETENTION	RECOMMENDED SUMP VOLUME	
Average Flow Rate (26.9 l/sec)	7 Davs	16,269 m ³	
96.84 m3/hr	, Days	10,203 111	

4.5 Pontoon Mounted Pumps

A pontoon mounted pump system with duty/standby pumps is recommended to reclaim MIW from the surge sump for plant feed. Therefore, two centrifugal pumps are recommended (each capable of feeding the plant at full flow. The required pump specification is as follows.



PUMP DETAILS	TECHNICAL DATA
Actual Calculated Flow	(30 l/sec) 108 m³/hr each (VSD Driven)

4.6 Treated Water Sump

A treated water surge sump located adjacent to plant has been included in the design. Primarily this is to allow retention time on treated water prior to discharge. Additional residence time post treatment is recommended as a polishing pond to allow for any carry over of final impurities to settle before discharge. Recommended sump/pond sizing is based on 24 hours storage at maximum flow.

PLANT FEED RATE	DURATION/RETENTION	RECOMMENDED SUMP VOLUME
Average Flow Rate (26.9 l/sec) 96.84 m3/hr	24 Hours	2,324 m³

4.7 Sludge Management

From the water quality and literature review, the proposed sulphate and metals removal processes will have several sludge management streams with different product outputs, some which will need disposal either on site or off site and some that could be recycled or form a product for export off site.

- Metal hydroxide sludge will need to be thickened and dewatered prior to transport to disposal
 in an appropriate landfill off site. There may be potential to process this further to recover
 certain metal if this was desired.
- 2. Gypsum sludge will be collected, processed and mainly be recycled on site, but there may be the need to export some gypsum product off site or to on-site disposal.
- 3. Ettringite sludge will partially be recycled and again disposal will be required in an appropriate landfill off site.
- 4. Calcium Carbonate Sludge, which may contain impurities will also have to be thickened, dewatered and disposed in an appropriate landfill off site.

Theoretical maximum TSS and metals quantities predicted will give a total precipitated solids amount of in g/m3 (% solids w/v) of influent to the WTP. Preliminary theoretical design suggests that a range of 5-10% of the total flows from the various processes will be required to report to the settlement column underflow. Further design will require test work on mimic waters to confirm proposed sludge volumes and dry weight percentages expected.

Preliminary theoretical sludge volumes based on 5-10% range of total underflows, with dry weight percentage of 0.5-1% would give the following sludge qualities. Note that not all the total underflows need disposal as some will be recycled, but this represents the total sludge processing capacity needed, not total disposal.

4.7.1 Total Sludge Processing Capacity – Theoretical

DESCRIPTION	DATA
Total Underflow 5-15% Plant flow	4.8 -15 m ³ /hr
Solids in Total Underflow (assume 0.5-1%)	5-10 kg/m ³
Dry Weight Solids (kg/Hr at average flow rate)	24-150 kg/hr



DESCRIPTION	DATA
Dry Weight Solids (T/Year at average flow rate)	210.2-1,314.0 kg/year
	(Assuming 24 WTP hour continuous operation)
Wet solids at spadable consistency 20% solids T/year	1051.2 T/yr – 6570.0 T/yr

There are number of methods/technologies for available for dewatering of the settler underflow sludge, these include.

- Mechanical dewatering centrifuge, belt press filters etc
- Wet/dry stacking of tailings (tailings dam)
- Bag dewatering technologies vertical bag, geo bags etc

4.8 Other Treatment Processes

Other processes that will likely be needed in addition to the active WTP are:

- Cyanide Destruct on the Shepherds TSF influent stream
- Potential additional nitrate removal after WTP via biological processes

4.8.1 Cyanide Destruct – Shepherds TSF Influent Stream

As part of baseline water quality studies and environmental geochemistry studies, (MWM, 2025). It is reported that the influent stream from Shepherds TSF will have low concentrations of Cyanide present. Modelling indicates that this could be approximately 0.35mg/L. Compliance limits allow 0.6 mg/L in ground water and 0.011 mg/L in surface water (Ryder, 2025). Therefore, treatment may be required for this influent stream. Cyanide is highly toxic even in very low concentrations.

Cyanide removal is required for the waste flows coming from the Shepherds TSF area. This is estimated to contain Cyanide at around 0.35 mg/L. The recommended compliance limits for Cyanide are: 0.011mg/L (Surface Water) and 0.6mg/l (MAV Groundwater).

To provide more efficient treatment, it is anticipated the cyanide treatment would be carried out on the Shepherds TSF Stream only, prior to combining this with flows from other areas of the mine. Information from BOGP PFS document for the Bendigo Mine states that an Air/SO2 circuit has been chosen as the preferred form of Cyanide treatment for the process due to the amenability of the ore to this type of process and this is expected "to reduce the weakly acid dissociable cyanide to less than 30ppm at discharge" (30ppm=30mg/L).

Various forms of Cyanide treatment have been used in gold mines worldwide, including Alkaline Chlorination, Hydrogen Peroxide, SO2/Air, Ferrous Sulphate Complexation, Ozonation, Caro's Acid, Biological Treatment, Thermal destruction (SGS 2005, Palmer et al 1987) and UV Oxidation. Copper is used as a catalyst in some of these processes.

Of the cyanide removal processes, there are various advantages and disadvantages for each. A brief comment on some of the technologies is offered below.

Alkaline Chlorination is a very common process for cyanide removal and is reported to be inexpensive and effective. However, it has the potential to generate hazardous by-products and more recently is



considered to be undesirable due the potential for negative environmental effects including high discharge of chloride and hypochlorite anions (Young and Jordan, 1995). It is also unable to remove some cyanide metal complexes known as SADs (Strong Acid Dissociable Complexes).

In terms of performance, it was shown that the Ozonation process at a San Diego plating plant reduced cyanide from 1.02mg/L in the Influent to 0.08mg/L in the effluent (Palmer et al, 1987). Ozonation was reported to have high operating costs.

More recently, UV oxidation has also been shown to be effective.

Wet Air Oxidation was reported to remove 99% of cyanide at a waste treatment facility in California from influent concentrations of 110mg/L to 0.035mg/L in the effluent (Palmer et al, 1987). This technology is more commonly used in domestic wastewater applications but is also used in industrial waste treatment to lesser extent.

The SO2/Air processes include a range of technologies. One such process called the INCO Process used at a Gold Mill site has been shown to reduce cyanide concentrations from around 40mg/L to 0.07mg/L in industrial applications (Palmer et al, 1987) however we have not established if this technology can achieve concentrations lower than this.

During the mining phase of the project, it is recommended that detailed testing of the BOGP water quality from Shepherds TSF take place to determine actual levels of Cyanide present prior to detailed design of a cyanide destruct process.

4.8.2 Nitrate Removal

Nitrate removal may be required but again this will need to be confirmed by test work.

Ettringite formation can also provide a polishing effect, allowing precipitation of metals, Ni, Cd, Cu, Zn, Cr, As and Se, often below their compliance and laboratory detection limits. Boron, fluoride and up to 30% of chloride and nitrate-nitrite in wastewater have also been removed (Reinsel 1999).

If required following test work, additional nitrate treatment systems can be added as a bolt on to the back end of the plant, depending on the amount of removal required. Options include the following.

- Fluidised bed reactors (FBR)
- Ion exchange
- Wetland (if polishing required)

Note that biological processes can be limited by sufficient organic carbon and nutrients in mine influence waters and the presence of heavy metals limiting growth. (Lorax 2023, Bratty et al, 2014)

4.8.2.1 Fluidised Bed Reactor

Fluidised bed reactors can be effective in removing nitrates from mine wastewater. They use a biological process where the wastewater flows upwards through a bed of granular materials, such as sand or activated carbon. This allows the growth of biofilm within the FBR using the denitrification process, converting nitrate to nitrogen gas in anoxic conditions. (Metcalf and Eddy, 2003).

Design would include the sizing appropriately of the following:



- Upflow velocities
- Bed depth
- Specific surface area
- Hydraulic retention times

A pilot size trial with similar water would provide more accurate sizing for a full-size plant.

4.8.2.2 Ion Exchange

As mentioned earlier in this document, any ion exchange processes will generate a brine waste stream which will have to be disposed of off-site.

4.8.2.3 Wetlands

There are three types of wetlands that differ in form, function and applicability:

- Aerobic wetlands (reed beds)
- Compost wetlands
- Reducing and Alkalinity Producing Systems (RAPS)

Aerobic wetlands can legitimately be regarded as proven technology when applied to ferruginous net alkaline waters. (Brown Barley and Wood, (2007)).

The two principle aims of mine water treatment in wetlands are.

- 1. To neutralise acidity and
- 2. To precipitate out metals.

Constructed wetlands need to comprise the following five components:


- 1. Substrates (which may have widely varying rates of hydraulic conductivity
- 2. Plants adapt to water saturated anaerobic conditions
- 3. Wate column (water flowing in or above the substrate)
- 4. Vertebrates and invertebrates
- 5. Aerobic and microorganisms

Natural wetlands are biologically complex and cover large land areas. When designing constructed wetlands, care must be taken when reducing them to minimal components and treatment areas for minewater processing purposes. Such loss of biological complexity may prevent the achievement of a balanced self-sustaining ecosystem which is the aim of passive treatment. (Brown Barley and Wood, (2007))

At this stage it is not possible to quantify the amount of nitrate that would be removed by a wetland system prior to detailed design.



APPENDIX A - PROCESS FLOW SHEETS



Parameter	Unîts	Stream 1 TSF Seepage	Stream 2 Shepherds ELF Seepage	Stream 3 WELF Seepage	3 1 4 0 W F - C 7 F	Stream 5 CIT Pit Backfill		Stream 7 MIW combined
Flow Rate	I/sec	13.4	4	1	6	1.5	1	26.9
Acidity	mg/L	0.01	0	0	0.44	0	Ó	0.03
Al	mg/L	0.011	0.003	0.003	0.1	0.005	0.003	0.013
Alkalinity	mg/L	73	189	183	182	190	158	150
As	mg/L	2.06	0.2	0.2	0.09	0.08	0.2	0.61
B	mg/L	0.83	0.87	0.1	0.05	0.09	0.01	0.59
Са	mg/L	297	51	51	59	39	36	107
Cd	mg/L	0,0002	0	0	0,0001	0.0001	0	0.0001
Cl	mg/L	806	63	37	14	12	8	223
Co	mg/L	0.053	0.109	0.023	o	0.004	0.003	0.051
Cr	mg/L	C.00636	0.0002	0.00019	0,00058	0.0004	0.00007	0.0017
Cu	mg/L	0.001	0	0	0.00302	0.00021	0	0.00049
DOC	mg/L	0	0	0	0.09	0.206	0	0.038
F	mg/L	1 94	6.3	5.12	0.23	1.39	2.37	3.9
Fe	mg/L	15.3	7.6	7.6	7.9	2,4	7.6	8.7
Hg	mg/L	0	0	0	0.00006	0.00014	0	0.00003
К	mg/L	51	683	672	34	84	159	372
Mg	mg/L	100	38	37	37	20	24	49
Mn	mg/L	0.594	0.819	0.774	0.014	0.103	0.182	0.567
Mo	mg/L	0.14	1.005	0.672	0.02	0.119	0.157	0.535
NO3-N	mg/L	2.01	49.64	9.54	4.35	0.73	1.33	22.89
Na	mg/L	848	922	734	42	127	170	673
Ni	mg/L	0.6784	0.0121	0.001	0.0009	0.0013	0.0001	0.1652
Pb	mg/L	V.0276	9.0001	0.0001	0.0035	0.0002	0	0.0068
Sb	mg/L	0.1802	2.9986	3.2208	0.0234	0.3622	0.7601	1.6317
Se	mg/L	0.003	0.1544	0.1649	0.0008	0.0196	0.0388	0.0826
504	mg/L	954	957	888	141	110	208	730
Sr	mg/L	4.4	16.15	15.91	0.79	3.77	10.89	10.12
TI	mg/L	0	0	0	0.00031	0.00021	0	0.00005
CN	mg/L	0.35	0	0	0	0	0	0.082
υ	mg/L	0.028	0.2751	0.2225	0.0094	0.0299	0.0515	0.1468
V	mg/L	0.004	0.12	0.1155	0.0006	0.0135	0.0269	0.0633
Zn	mg/L	0.0296	0.0098	0.0021	0.0022	0.0014	0.0003	0.0117
pH	mg/L	6,41	7.93	7.92	5.91	8.03	7.92	6.72
Hardness	mg/L	1151	285	280	299	179	190	469


O TH	ESE PLAN	NS AND THE DESIGNS SHOWN THEREIN REMAIN TH	E PROPERTY OF PRO	CESSI	LOW LIMIT	TED AND MAY NOT BE CO	OPIED IN ANY FORM (INCLUDING THE MA	NUFACTURE OF ALL OR PART OF THE DESIGNS SHOWN) WITHOUT PRIOR PERMI	SSION IN WRITIN
Ŧ					\blacksquare				
С	02/10/25	ISSUED FOR INFORMATION	DAB	- 2				PROCESS FLOW	
3:	13/06/25	ISSUED FOR INFORMATION	DAB	-				The second secon	
A	11/03/25	ISSUED FOR REVIEW	DAB	- 0	49			PROCESS FLOW LIMITED	
EV	DATE	REVISION	BY	CKD	APPD			4/38 ESTUARY PLACE,	
CAD FILE TYPE AUTOCAD/AUTOCAD LT			AUTOCAD/AUTOCAD LT				RICHMOND 7020	and the second s	
AD FILE NA	ILE NAME PFL-2428-PRO-PFD-00000182 C DWG			D FILE NAME	DRG No.	REFERENCE DRAWINGS	T +84 3 540 2625 www.processflow.com		

PROCESS FLO	W
OCESS FLOW LIMITED	

DESIGNED	GS	11/03/25	
DRAWN	DAB	11/03/25	
CHECKED			
APPROVED			
SCALE	NTS	-	
VENDOR DRG, No.			

ISSUED FOR INFORMATION BOGP ACTIVE WATER TREATMENT PLANT

PLANT FEED ENVELOPE PROCESS FLOW DIAGRAM SHEET 1 OF 1 ORIGINAL DRAWING SIZE A1 DRAWING NUMBER PFL-2426-PRO-PFD-000001_C



APPENDIX C LIMITATIONS

MWM-S003-Rev2

This Document has been provided by Mine Waste Management Ltd (MWM) subject to the following limitations:

This Document has been prepared for the particular purpose outlined in MWM's proposal and no responsibility is accepted for the use of this Document, in whole or in part, in other contexts or for any other purpose.

The scope and the period of MWM's services are as described in MWM's proposal, and are subject to restrictions and limitations. MWM did not perform a complete assessment of all possible conditions or circumstances that may exist at the site referenced in this Document. If a service is not expressly indicated, do not assume it has been provided. If a matter is not addressed, do not assume that any determination has been made by MWM in regards to it.

Conditions may exist which were undetectable given the limited nature of the enquiry MWM was retained to undertake with respect to the site. Variations in conditions may occur between investigatory locations, and there may be special conditions pertaining to the site which have not been revealed by the investigation and which have not therefore been taken into account in the Document. Accordingly, additional studies and actions may be required.

In addition, it is recognised that the passage of time affects the information and assessment provided in this Document. MWM's opinions are based upon information that existed at the time of the production of this Document. It is understood that the services provided allowed MWM to form no more than an opinion of the actual conditions of the site at the time the site was reviewed and cannot be used to assess the effect of any subsequent changes in the quality of the site, or its surroundings, or any laws or regulations.

Any assessments made in this Document are based on the conditions indicated from published sources and the investigation described. No warranty is included, either express or implied, that the actual conditions will conform exactly to the assessments contained in this Document.

Where data supplied by the client or other external sources, including previous site investigation data, have been used, it has been assumed that the information is correct unless otherwise stated. No responsibility is accepted by MWM for incomplete or inaccurate data supplied by others.

MWM may have retained subconsultants affiliated with MWM to provide services for the benefit of MWM. To the maximum extent allowed by law, the Client acknowledges and agrees it will not have any direct legal recourse to, and waives any claim, demand, or cause of action against, MWM's affiliated companies, and their employees, officers and directors.

This Document is provided for sole use by Matakanui Gold Limited and is confidential to it and its professional advisers. No responsibility whatsoever for the contents of this Document will be accepted to any person other than the Client. Any use which a third party makes of this Document, or any reliance on or decisions to be made based on it, is the responsibility of such third parties. MWM accepts no responsibility for damages, if any, suffered by any third party as a result of decisions made or actions based on this Document.

MWM acknowledges that this report will be relied on by a Panel appointed under the Fast Track Approvals Act 2024 and these disclaimers do not prevent that reliance.



APPENDIX N WATER LOAD BALANCE MODEL

Water and Load Balance Model Report

Bendigo-Ophir Gold Project

10 October 2025

J-NZ0233-016-R-Rev1





Water and Load Balance Model Report

Bendigo-Ophir Gold Project

Document Number: J-NZ0233-016-R-Rev1

Document Date: 10 October 2025

Prepared for:

Matakanui Gold Limited

15a Chardonnay Street, Cromwell, 9310

Prepared by:

Mine Waste Management Limited

5 Sir William Pickering Drive, Burnside, Christchurch 8053, New Zealand

+64 3 242 0221

www.minewaste.com.au

REVISION	DATE	AUTHOR	RECORD OF REVIEW
RevA	25/06/2025	BO/EW/LN/JG/RB	RB/PW
RevB	08/08/2025	LN/RB/JG	RB/PW
RevC	15/09/2025	RB/JG/LN	RB/PW
Rev0	25/09/2025	RB	PW
Rev1	10/10/2025	PW/RB	PW

Page ii www.minewaste.com.au

EXECUTIVE SUMMARY

This report describes the development of a site-wide water and load balance model (WLBM), which will support the Assessment of Environmental Effects (AEE) for the Bendigo-Ophir Gold Project (BOGP) for Matakanui Gold Limited (MGL).

Objectives of this Study

The primary objectives of the modelling exercise were as follows:

- Forecast operational and closure phase water balance conditions for the BOGP.
- Forecast instream water quality at the proposed resource consent compliance locations as compared to proposed water quality limits for the operational and closure phases.
- Forecast changes in stream flows as a result of the BOGP for the operational and closure phases.

Findings

The BOGP operational and post-closure assessment findings are summarised below.

Operational Phase

The Operational Phase calculations suggest the following:

- Water balance calculations suggest that the site will be in a water deficit condition up to Year 8. After this point, dewatering from satellite pits (i.e., SRX¹ and to a lesser extent CIT²) may push the site to a water surplus condition for the last few years of mine life without additional controls. Engineering controls (e.g., construct the water treatment plant prior to closure) are available to manage potential water surpluses, and can be evaluated during detailed design phases. Ongoing site water balance reconciliation for the BOGP will be required to confirm water balance conditions remain in a water deficit condition.
- Based on mine features that will retain water on site and not be discharged to the receiving
 environment during operations, mean flows at SC01 and RS03 are estimated to be reduced by
 approximately 17% and 13% respectively, at the full life of mine project footprint. Low flow
 conditions will also increase, showing the seven day mean annual low flow decreasing by
 approximately 27% and 15%, for SC01 and RS03 respectively.
- Interpretation of the mixing model results suggests surface water quality at SC01 and RS03 will remain below the proposed compliance limits for both surface and groundwater if groundwater is used for dust suppression.

Ī

¹ Srex Pit

² Come in Time Pit

Post-Closure Phase

The Post-Closure WLBM results suggest the following:

- Pit voids will fill with water and discharge mine-impacted water (MIW) at average rates of approximately 6 L/s, 8 L/s and 1.5 L/s, from the RAS³ Pit (via the RAS underground workings), SRX Pit, and CIT Pit, respectively. RAS Pit Lake will reach a stable condition at ~25 years, and SRX and CIT pits will do so in <5 years.
- Of the mine waste storage facilities (MWSFs), using a net percolation rate of 20%, Shepherds engineered landform (ELF) will have the highest average seepage rate of MIW of approximately 4 L/s, followed by the TSF⁴ seepage rate of approximately 2 L/s on average. SRX ELF, WELF⁵, and SCK Fill⁶ all had seepage rates of approximately 1 L/s or less.
- In the post closure phase, creek flows will increase, with average flows increasing by approximately 60% at Shepherds Creek (at SC01) and 50% at Rise and Shine Creek (at RS03). Low flow conditions will also increase, with the seven day mean annual low flow increasing by approximately 530% and 280%, for SC01 and RS03 respectively.
- Model results suggest that active water treatment within the Shepherds Creek catchment will be needed for 50 years, when concentrations of SO₄, Mo, and Sb after passive treatment are below the surface water and groundwater limits, for the base case model scenario.
- Water quality findings for the base case model at RS03 indicate:
 - No limits are exceeded after partial passive treatment of the average flow (8 L/s) from SRX
 Pit.
 - o Active treatment of MIW from SRX Pit and SRX ELF is not required.

Operational Management Recommendations

The following management recommendations are proposed for the Operations Phase:

Back to back wet years and changes of water balance assumptions (e.g., dust suppression
water sources) may move the site into a water surplus condition. As such, detailed water
balance modelling by mine stage and that includes rainfall variability is recommended to
support detailed mine design and improve confidence in a water deficit being maintained.
Development of an adaptive management process related to the site water balance would also
support proactive management of identified risks.

-

³ Rise and Shine Pit

⁴ Tailings Storage Facility

⁵ West ELF

⁶ Shepherds Creek

- A site water balance reconciliation should be completed regularly (e.g., annually or more frequent) to confirm water balance model results are appropriate, and/or make model updates to improve confidence in model results projected into the future.
- Clean water sources (i.e., bore water) should be used for dust suppression.
- Pit sump water could potentially be used for dust suppression early on in mine life. Adaptive
 management processes should be developed to proactively manage and respond if
 performance and/or compliance monitoring data suggests use of pit sump water may begin to
 provide a risk of non-compliance (i.e., potential to cause exceedance of water quality limits at
 SC01 and RS03).
- Other water management options include the early construction, during operations, of the water treatment plant if prolonged water surplus conditions eventuate.

Closure Management Recommendations

The following management recommendations are proposed for the active- and post- closure phases:

- Active water treatment in the Shepherds Creek catchment through a water treatment plant (WTP) is required until passive treatment systems can achieve the proposed water quality compliance limits.
- Passive treatment of the SRX Pit Lake is required to achieve water quality limits at RS03. Noting
 that passive treatment is modelled at 8 L/s (average SRX Pit flow rate) with higher flows being
 untreated.
- Active and passive water treatment systems need to be developed to a detailed design level:
 - o For the WTP, these studies need to be completed within the first few years of the mine commencing so that the technology is ready for operations and closure. Early design of the WTP would mean it is ready as part of any adaptive management process for water management.
 - Passive water treatment systems should be designed once the project is operational using actual water quality from the project mine domains to confirm the proposed approach is appropriate.
- The majority of PCOC loads originate from Shepherds ELF and the TSF; therefore, performance monitoring of both flow rates and water quality is recommended at these locations.
- Model results suggest that active water treatment within the Shepherds Creek catchment will
 be needed for 50 years, when concentrations of SO₄, Mo, and Sb after passive treatment are
 below the surface water and groundwater limits, for the base case model scenario.
- Diverting Shepherds ELF and TSF seepage to the RAS Pit Lake for dilution was also assessed as a management option. Results indicate that at closure of the BOGP, the proposed water quality limits can be achieved without active treatment. The exception to this is molybdenum.

Active treatment is required until Mo decreases to a concentration that can be managed by passive treatment technologies.

 Performance monitoring is necessary to assess whether treatment is required using these management mechanisms.

Forward Works

The following forward works are proposed:

- A transient operational site wide water and load balance model needs to be developed prior to
 mine commencing to improve confidence in water accumulation or losses over time and water
 quality, particularly for seasonal dynamics. Such a model will support detailed design of the
 TSF.
- Additional ground investigations, groundwater monitoring, and detailed modelling will be required at the detailed design to confirm mine waste storage facility seepage collection systems will achieve anticipated collection requirements.
- The collection of performance monitoring data to improve model input data reliability is required, including:
 - o Water quantity and quality data from mine domains and water movement around the site.
 - Water quantity and quality data as compliance locations.
 - Records of pit lake filling levels over time.
- Once the mine is operational, collection of water quantity and quality data (obtained as part of
 performance monitoring) should be compared to the developed operational site wide water
 balance model periodically to confirm model results remain reasonable. Model revisions and/or
 re-calibration may be required if material differences are apparent.
- A cover system trial should be established early on in mine life to demonstrate that a NP of 20% of mean annual rainfall can be achieved. Such a study would provide confidence that water quality closure objectives can be achieved and support closure planning.

TABLE OF CONTENTS

1		Intr	oduc	tion	1
	1.	1	Obj	ectives and Scope	1
		1.1.	.1	Objectives	1
		1.1.	.2	Scope of Work	1
2		Pro	ject [Description	2
	2.	1	Proj	ect Background	2
	2.2	2	Min	e Plan	3
	2.3	3	Wat	ter Management	3
	2.4	4	Pro	posed Compliance Limits	6
3		Clin	natic	Setting	9
	3.	1	ВО	GP Climatic Data	9
	3.2	2	ВО	GP Synthetic Climate Dataset	10
4		Оре	eratio	onal Phase Assessment	13
	4.	1	Intro	oduction	13
	4.2	2	Оре	erational Water Management Risks	13
	4.3	3	Inte	rnal MIW Water Balance	14
		4.3.	.1	Internal MIW Water Sources and Water Loss	14
		4.3.	.2	Annual Site Water Balance	15
		4.3.	.3	Internal MIW Water Quality	18
		4.3.	.4	Changes to Creek Flows	18
	4.4	4	Sur	ficial MIW Water Quality	19
		4.4.	.1	Approach	19
		4.4.	.2	Runoff Generation	19
		4.4.	.3	Source Terms	20
		4.4.	.4	Mixing Model Results	22
	4.	5	Sun	nmary	27
	4.6	6	Red	commendations	28
5		Act	ive a	nd Post Closure Phase Assessment	29
	5.	1	Mod	del Description	29
		5.1.	.1	Overview	29
	5.2	2	Wat	ter Balance Model Inputs	30
		5.2.1		Climate Inputs	30
		5.2	.2	Catchment Delineation	31
		5.2	.3	Runoff Model	32
		5.2.4		Pit Voids	33
		5.2.	.5	Mine Waste Storage Facilities	34
		5.2.	.6	Water Treatment	36
	5.3	3	Loa	d Balance Inputs	36
	5.4	4	Mod	del Evaluation	42

5.4.1	Model QA/QC	42
5.4.2	Model Calibration	
5.4.3	Model Limitations	
5.4.3	1 Water Balance	44
5.4.3	2 Load Balance	45
5.5 Mo	del Results	
5.5.1	Water Balance Results	46
5.5.1	1 Mine Domains	46
5.5.1	2 Creek Flows	50
5.5.2	Load Balance Results	52
5.5.2	1 Introduction	52
5.5.2	2 RAS Pit Lake	53
5.5.2	3 SRX Pit Lake	56
5.5.2	4 CIT Backfill	60
5.5.2	5 Shepherds Creek (SC01)	63
5.5.2	6 Rise and Shine Creek (RS03)	70
5.5.2	7 Assessment SC01: Surface Water Quality Compliance	77
5.5.2	8 Assessment SC01: Groundwater Quality Compliance	77
5.5.2	9 Assessment RS03: Surface Water and Groundwater Quality Compliance	78
5.5.2	10 Water Quality Compliance Summary: SC01 and RS03	79
5.6 Sc	enario Modelling – Water Management Opportunities	80
5.6.1	Model Background	80
5.6.2	Model Results	80
6 Summa	ry and Recommendations	84
6.1 Su	mmary	84
6.1.1	Operational Phase Model Results	84
6.1.2	Post-Closure Phase Model Results	84
6.2 Op	erational Management Recommendations	85
6.3 Clo	sure Management Recommendations	85
6.4 For	ward Works	86
7 Limitation	ons	88
8 Referer	ices	89
Appendix A	Abbreviations	
Appendix B	Climate Analysis	
Appendix C	Surficial MIW Water QuaLity Model Results	
Appendix D	Closure Model Results at SC01 and RS03	
Appendix E	Limitations	

LIST OF TABLES

Table 1: BOGP Mine plan schedule	3
Table 2: Key mine domain footprints.	1
Table 3: MIW management approach for operational and closure phases.	4
Table 4: Proposed surface water compliance limits.	6
Table 5: Proposed groundwater compliance limits.	7
Table 6: Internally managed MIW sources and sinks of water.	14
Table 7: Water balance input basis	15
Table 8: Total water balance proportion.	18
Table 9: Calculated changes in creek flow summary statistics at end of the operation phase	19
Table 10: Mine domain runoff source areas.	20
Table 11: Runoff coefficients for different daily totals.	20
Table 12: Source terms used for the solute mixing model	21
Table 13: Mixing model results for bore water dust suppression scenario including the maximum are average concentrations for each analyte and percentage of generated readings which exceed proposed compliance limits	
Table 14: Synthetic vs projected climate summaries.	31
Table 15: Catchment delineations and undisturbed surface areas	32
Table 16: Runoff coefficients for the water balance model	33
Table 17: Pit void model summary	33
Table 18: MWSF model input parameter summary.	35
Table 19. Source Term Water Quality Part 1 of 2	36
Table 20. Source Term Water Quality Part 2 of 2.	38
Table 21: SC01 flow statistic comparison.	44
Table 22: Forecast creek flow summary statistics.	52
Table 23: Summary of used reference limits for screening.	52
Table 24. Average annual Inflow Loads to RAS Pit Lake	56
Table 25: Average annual inflow loads to SRX Pit Lake.	60
Table 26: Average annual inflow Loads to CIT Backfilled Void.	63
Table 27: Removal efficiencies for the passive treatment system.	64
Table 28: Average annual inflow loads to RS03.	73
Table 29. Yearly average water quality (SC01) before and after passive treatment against the SW reference limits.	77
Table 30: Comparison of yearly averages for SC01 before and after passive treatment against the GW Limits. Percent is calculated on the total 200 years of the model.	78
Table 31: Comparison of yearly averages for RS03 before and after passive treatment against the Limits. Percent is calculated on the total 200 years of the model	
Table 32: Comparison of yearly averages for RS03 before and after passive treatment against the GW Limits. Percent is calculated on the total 200 years of the model.	79
Table 33: Summary table of exceedances screened against reference surface water (SW) and groundwater (GW) limits for SC01 and RS03.	79

LIST OF FIGURES

Figure 1: BOGP mine domains.	2
Figure 2: Location and areas of key mine domains within SC01 and RS03 catchments	3
Figure 3 Location of meteorological stations.	9
Figure 4: Srex Met vs Cromwell EWS PET	. 10
Figure 5: Annual rainfall totals of synthetic rainfall dataset	.11
Figure 6: Annual PET totals of synthetic rainfall dataset.	.11
Figure 7: Average monthly synthetic climate data summary.	.12
Figure 8: Separation of Internal and Surficial MIW during the operational phase at the BOGP site	. 14
Figure 9: Annual water balance results	. 18
Figure 10: Modelled sulfate concentrations at SC01, where bore water is used for dust suppression	
Figure 11: Sulfate exceedance probability in SC01 where bore water is used for dust suppression	. 26
Figure 12: Bottom 10% exceedance probability for sulfate concentrations where bore water is used dust suppression at SC01	. 26
Figure 13: Modelled sulfate concentrations at RS03, where bore water is used for dust suppression	
Figure 14: Sulfate exceedance probability at RS03 where bore water is used for dust suppression	
Figure 15: Bottom 10% exceedance probability for sulfate concentrations where bore water is used dust suppression at RS03.	
Figure 16: Schematic diagram of MIW and non-impacted rainfall and runoff for the closure phases at the BOGP site.	
Figure 17: Srex Met vs Cromwell EWS maximum temperature.	.31
Figure 18. Seepage Water Quality for Waste Rock Domains at the BOGP. Part 1 of 2	.40
Figure 19. Seepage Water Quality for Waste Rock Domains at the BOGP. Part 2 of 2	.41
Figure 20: Daily flow rate comparison.	.43
Figure 21: Daily flow rate comparison (log scale).	.43
Figure 22: Flow exceedance comparison.	.44
Figure 23: Cumulative water volume comparison.	.44
Figure 24: RAS Pit Void model results – water volume and level	.47
Figure 25: RAS Pit Void model results – underground portal discharge.	.47
Figure 26: SRX Pit Void model results – water volume and level	.48
Figure 27: SRX Pit Void model results - overflow rate	.48
Figure 28: CIT Pit Void model results – water volume and level.	.49
Figure 29: CIT Pit Void model results – outflow rates	.49
Figure 30: ELF and TSF seepage flow rates.	. 50
Figure 31: SC01 forecasted flows regime.	.51
Figure 32: RS03 forecasted flows regime.	.51
Figure 33. RAS Pit Lake water quality results. Part 1 of 2	. 54

Figure 34.	RAS Pit Lake water quality results. Part 2 of 2.	55
Figure 35.	SRX Pit Lake water quality results. Set 1 of 2.	.57
Figure 36.	SRX Pit Lake water quality results. Set 2 of 2.	58
Figure 37.	CIT Backfilled Void water quality results. Part 1 of 2.	61
Figure 38.	CIT Backfilled Void water quality results. Part 2 of 2	62
	Yearly average water quality results at Shepherds Creek (SC01) treated and untreated Part 1 of 2.	65
	Yearly average water quality results at Shepherds Creek (SC01) treated and untreated Part 2 of 2.	66
	Stacked yearly average inflow load contributions to SC01 for selected parameters (Set 1	
	Stacked yearly average inflow load contributions to SC01 for selected parameters (Set 2	
Figure 43.	Yearly average water quality results at Rise and Shine Creek (RS03). Part 1 of 2	71
Figure 44.	Yearly average water quality results at Rise and Shine Creek (RS03). Part 2 of 2	72
	Stacked yearly average inflow load contributions to RS03 for selected parameters (Set 1	
	Stacked yearly average inflow load contributions to SC01 for selected parameters (Set 2	
Figure 47.	Scenarios results for parameters above the GW Limit for the base case scenario	81
Figure 48.	Scenario model results at SC01. Part 1 of 2.	82
Figure 49.	Scenario model results at SC01. Part 2 of 2.	.83

1 INTRODUCTION

This report describes the development of a site-wide water and load balance model (WLBM), which will support the Assessment of Environmental Effects (AEE) for the Bendigo-Ophir Gold Project (BOGP) for Matakanui Gold Limited (MGL).

1.1 Objectives and Scope

1.1.1 Objectives

The primary objectives of the modelling exercise were as follows:

- Forecast operational and closure water balance conditions for the BOGP.
- Forecast stream water quality at the proposed resource consent compliance locations as compared to proposed water quality limits for the operational and closure phases.
- Forecast changes in stream flows as a result of the BOGP.

1.1.2 Scope of Work

Mine impacted water (MIW) management during the operational phase of mining will involve discharge of only episodic runoff from haul roads and engineered landforms (ELFs) via sediment control structures. All other MIW (e.g., landform seepage from the ELFs and the tailings storage facility (TSF) will be collected and stored for re-use on site (e.g., processing plant water) or be returned to the TSF impoundment. MIW management in the closure/post-closure phase, will require some seepages to be treated and discharged to the receiving environment. In this analysis, we partition the operational phase and closure/post-closure phase separately as follows:

- Operational phase spreadsheet based models and associated calculations used to describe average annual water balance and runoff event discharges of MIW (Section 4).
- Closure/post-closure phase GoldSim models and associated calculations, used to describe
 the evolution of water-quality over time, that results from the discharge of treated MIW (Section
 5).

It is noted that during mine operations there will be the opportunity for proactive management of potential water-quality impacts. This will contrast with long term post-closure water management, where on-site presence is typically limited. The increased model complexity and effort required to describe closure/post-closure conditions is therefore appropriate. It is recommended that future updates to the modelling should expand the GoldSim model to include the operational phase to support mine water management planning.

Page 1 MWM-S003-Rev2

2 PROJECT DESCRIPTION

MGL is proposing to establish the BOGP, which comprises gold mining operations, processing operations, ancillary facilities and environmental mitigation measures on Bendigo and Ardgour Stations in the Dunstan Mountains of Central Otago. The project site is located approximately 20 km north of Cromwell and will have a maximum disturbance footprint of 610 hectares.

2.1 Project Background

The total Mineral Resource Estimate for the BOGP using a 0.5 g/t cut-off for open pit and 1.5 g/t for underground is 34.3 Mt at 2.1 g/t for 2.34 M oz (MGL, 2025). The Bendigo-Ophir resources occur in four deposits: Come in Time (CIT), Rise and Shine (RAS), Srex (SRX), Srex East (SRE). The majority of identified mineral resources are located within the RAS deposit. Three primary geological units are recognised at site:

- RSSZ Rise and Shine Shear Zone.
- TZ3 Lower Greenschist facies Textural Zone 3 rocks of the Otago Schist.
- TZ4 Upper Greenschist facies Textural Zone 4 rocks of the Otago Schist.

The resources will be mined by open pit methods at each deposit within the project site, with underground mining methods also proposed to be utilised at RAS to access the deeper gold deposits. The majority of the mining activities, ancillary facilities and associated infrastructure will be located in the Shepherds Valley with non-operational infrastructure located on the adjoining Ardgour Terrace. The BOGP also involves the taking of groundwater from the Bendigo Aquifer for use in mining-related activities and the realignment of Thomson Gorge Road via Ardgour Station.

The following mine facilities are proposed (Figure 1):

- Open pits targeting the RAS, SRX, SRE, and CIT deposits.
- An underground mine targeting the RAS deposit.
- Three ex-pit ELFs Shepherds ELF, SRX ELF, and West ELF (WELF).
- Two in-pit landforms (backfill) CIT and SRE⁷.
- Plant and processing area, where CIL extraction technologies will be used as part of the ore recovery process. This includes the Shepherds Creek Fill (SCK Fill).
- A TSF and TSF Embankment.
- Other ancillary support services / structures (e.g., roads, water management infrastructure, water treatment plants, etc).

These facilities will be placed in the catchment of Shepherds and Rise and Shine creeks.

Page 2 MWM-S003-Rev2

⁷ Note: SRE Pit is backfilled by the SRX ELF.

2.2 Mine Plan

The mine plan for the Bendigo-Ophir site is outlined in Table 1. The schedule describes the timing of construction of different mine-site infrastructure and water-management components (illustrated in Figure 1), and subsequent mining operations. The schedule is also used to inform development of operational phase and closure phase water-management plans.

Table 1: BOGP Mine plan schedule.

MONTH	YEAR	MINING PHASE	DESCRIPTION OF PHASE	
		Pre-startup	Detailed design phase	
0 to 6	0 to 0.5	Startup	Pioneering / RAS Pre-Strip, Initial Jean Creek Silt Pond, earthworks at process plant.	
6 to 24	0.5 to 2	Project Development	Construction of process plant, TSF, Shepherds Silt Pond, North Diversion Channel, Commissioning, mining RAS pre- strip (Pre-strip ends month 19). Construction of the WELF begins.	
		Operations		
25 to 54	2 to 4.5	RAS pit mining on its own	Operations (pit ore production in month 20. UG Development begins month 54). WELF construction complete.	
54 to 72	4.5 to 5	RAS pit with UG development	Operations (UG Ore production begins month 70)	
72 to 132	6 to 11	RAS pit plus RAS UG	Operations (UG Ore production months 70 to 150)	
		RAS Pit plus RAS UG plus CIT Pit	Operations (CIT Pit mined months 102 to 114)	
		RAS Pit plus RAS UG, plus CIT backfilled, plus SRX	Operations (SRX Pit mined months 145 onwards)	
120 - 160	10 to 13.3	RAS UG continues on its own with CIT and SRX open pit feeds	Operations (all mining halted month 160)	
Closure				
160 - 372	11 to 31	Active Closure ¹	All mining halted. Active closure of pits, TSF, and wider site, plus setup of active water treatment plant (option).	
372 -	31 onwards	Post-Closure	Passive treatment and maintenance	

UG = Underground

Key BOGP domains and their footprint area are summarised in Table 2.

Page 3 MWM-S003-Rev2

^{1.} Presented as two decades as part of the Pre-feasibility Mine Plan.

Source: BOGP_high_level_schedule_PFSconsent.xlsx (Santana, 2025)

Table 2: Key mine domain footprints.

MINE DOMAIN	CATCHMENT	AREA	NOTES
TSF	SC01	608,338 m ²	Maximum TSF footprint.
Shepherds ELF	RS03	1.11 km ²	Maximum ELF footprint.
SRX ELF	RS03	0.15 km ²	Maximum ELF footprint.
WELF	RS03	0.17 km ²	Maximum ELF footprint.
SCK Fill	SC01	0.11 km ²	Maximum footprint.
DAC Dit	SC01/RS03	0.64 km ²	72% in SC01 catchment
RAS Pit			28% in RS03 catchment.
CIT Pit	SC01/RS03	0.14 km^2	87% in SC01 catchment
			13% in RS03 catchment.
SRX Pit	RS03	0.15 km^2	Maximum footprint.
SRE Pit	RS03	0.10 km ²	Maximum footprint.
Infrastructure Area	SC01	0.05 km ²	Includes Mill and ROM.
Haul Danda	SC01/RS03	0.39 km ²	82% in SC01 catchment
Haul Roads			8% in RS03 catchment.

Page 1 MWM-S003-Rev2

MATAKANUI GOLD LIMITED J-NZ0233-016-R-Rev1




Figure 1: BOGP mine domains.

Page 2 MWM-S003-Rev2

2.3 Water Management

To help understand the origin and quantity of rainfall and runoff being derived from different infrastructure areas and domains, the site is divided into surface water monitoring locations and their upstream catchment areas (Figure 2). Surface water quantity and quality are referenced with respect to the proposed downstream resource consent compliance monitoring locations at SC01 and RS03. These catchments are shown in Figure 2.

The water management strategy for the BOGP is also divided into operational and closure/post-closure phases:

- Operational Phase: most MIW will be retained on site for use (e.g., for process water, dust suppression, etc.), with the only discharge from disturbed areas being surface runoff from haul roads, the infrastructure area, and ELFs via sediment control structures. Seepage from landforms will not be discharged off site.
- Active Closure and Post Closure phases (Closure Phase): seepage from ELFs, the TSF, and pit void water will be collected and treated, initially with an active water treatment plant (Shepherds Creek catchment) until loads have reduced such that passive treatment can be utilised to meet water quality objectives.




Figure 2: Location and areas of key mine domains within SC01 and RS03 catchments.

Page 3 MWM-S003-Rev2

The water management approach for each key mine domain element (that has potential to produce MIW) are summarised for operational and closure phases in Table 3. These descriptions form the basis of the water quality and water balance calculations in subsequent sections of this report.

Table 3: MIW management approach for operational and closure phases.

MINE DOMAIN	DESCRIPTION	OPERATIONAL PHASE	CLOSURE PHASE
TSF	Condition	Active tailings deposition.	Rehabilitated.
	Surface Runoff	Runoff retained within facility. Diversion channels established to minimise run-on.	Runoff assumed to be clean and discharges to Shepherds Creek.
	Seepage	TSF seepage collected and conveyed to TSF or used for process water.	TSF seepage collected and conveyed for treatment.
Shepherd s ELF	Condition	Active mine rock placement.	Rehabilitated.
	Surface Runoff	Runoff sheeted to sediment pond and then discharged to Shepherds Creek (if water	Runoff assumed clean and discharged to Shepherds Creek.
		quality is suitable). Otherwise pumped to the mine	Diversion channels maintained to minimise run-on (i.e., to reduce seepage flows).
		water circuit for reuse. Diversion channels established to minimise run-on.	
	Seepage	ELF seepage collected and conveyed to TSF or used for process water.	ELF seepage collected and conveyed for treatment.
RAS Pit Void	Condition	Active dewatering of pit.	Dewatering ceases and pit lake development.
	Surface Runoff	Rise and Shine Creek diverted around pit extent.	Reports to pit lake.
		Collected in pit sumps and used for dust suppression if suitable and/or process water	
	Seepage	None.	Pit lake discharges via RAS underground workings portal and conveyed for treatment.
Undergro und Workings	Condition	Workings actively dewatered. Paste backfilling of stopes.	Workings flooded and provide discharge pathway for RAS pit lake water discharge.
·	Surface Runoff	None.	None.
	Seepage	Dewatering used for processing or conveyed to TSF.	Portal discharge collected and conveyed for treatment.
CIT Pit Void	Condition	Pit void actively dewatered.	Void backfilled, rehabilitated and filled with water.
	Surface Runoff	Collected in pit sumps and used for dust suppression.	Runoff assumed clean and discharges to Shepherds Creek.
	Seepage	Collected in pit sumps and used for dust suppression if suitable and/or process water	Backfill seepage collected and conveyed for treatment.

Page 4 MWM-S003-Rev2

MINE DOMAIN	DESCRIPTION	OPERATIONAL PHASE	CLOSURE PHASE
WELF	Condition	Active mine rock placement.	Rehabilitated.
	Surface Runoff	Runoff sheeted to local sediment pond. Discharged to Rise and Shine Creek (RS03) if water quality is suitable, otherwise conveyed to TSF.	Runoff assumed clean and discharges to Rise and Shine Creek (RS03). Diversion channels maintained to minimise run-on where practicable.
	Seepage	Collected in pit sumps and used for dust suppression if suitable and/or process water	Reports to SC01 via treatment.
Process Plant/Infra	Condition	Area operational.	Rehabilitated.
structure Area	Surface Runoff	Diversion in place to limit run-on. Runoff sheeted to local sediment ponds and discharged to receiving environment if suitable. Otherwise, conveyed to mine water circuit.	Runoff assumed clean and discharged to Shepherds Creek.
	Seepage	No significant seepage expected.	No significant seepage expected.
Shepherd s Creek Valley Fill	Condition	Lower gorge has to be filled, to create sufficient width for services (e.g., infrastructure). Shepherd channel designed to take a 1% AEP event	Valley infill to remain. Channel continues to support 1% annual exceedance probability (AEP). Non-channel area assumed rehabilitated.
	Surface Runoff	Clean water diversions that bypass the TSF and ELF drop into new channel in Shepherds Creek valley until past the mine infrastructure.	Runoff assumed clean and discharged to Shepherds Creek.
	Seepage	Any seepage that expresses at surface to downstream extent of fill will be collected and conveyed to TSF or used for process water.	If water quality is not suitable for discharge, collected and treated. If suitable, then discharged to Shepherds Creek.
SRE Pit Void	Condition	Pit void actively dewatered.	Dewatering stops. Pit void backfilled with SRX ELF overtop and floods.
	Surface Runoff	Collected in pit sumps and used for dust suppression if suitable and/or process water. Diversions in place to minimise run-on.	Reports to SRX Pit Lake.
	Seepage	None.	Reports to SRX Pit Lake.
SRX Pit Void	Condition	Pit void actively dewatered.	Dewatering stops. Pit void floods to develop pit lake and spills to Rise and Shine Creek.
	Surface Runoff	Collected in pit sumps and used for dust suppression if suitable and/or process water Diversions in place to minimise run-on.	Reports to SRX Pit Lake. Partial passive treatment of SRX Pit Lake overflow (8 L/s) is required to achieve the proposed water quality compliance limits at RS03.
	Seepage	None.	Reports to SRX Pit Lake. Partial passive treatment of SRX Pit Lake overflow (8 L/s) is required to achieve the proposed water quality compliance limits at RS03.

Page 5 MWM-S003-Rev2

MINE DOMAIN	DESCRIPTION	OPERATIONAL PHASE	CLOSURE PHASE
SRX ELF	Condition	Active mine rock placement.	Rehabilitated.
	Surface Runoff	Runoff sheeted to local sediment pond. Discharged to	Runoff assumed clean and discharges to Rise and Shine Creek.
	Rise and Shine Creek is water		Diversion channels maintained to minimise run-on where practicable.
		Diversion channels established minimise run-on where practicable.	
	Seepage	Seepage collected at local sump and conveyed to TSF or used for process water.	Reports to SRX Pit Lake. Pit lake spill partially treated (8 L/s).
Haul Roads	Condition	Haul roads operational.	Rehabilitated.
Koaus	Surface Runoff	Diversion in place to limit run-on. Runoff sheeted to local sediment ponds and discharged to receiving environment if suitable. Otherwise, conveyed to TSF or used for process water.	Runoff assumed clean and discharged to Shepherds Creek and Rise and Shine Creek.
	Seepage	No significant seepage expected.	No significant seepage expected.

2.4 Proposed Compliance Limits

Proposed compliance limits are described in the BOGP Water Management Plan (MGL, 2025) and tabulated below for surface water (Table 4) and groundwater (Table 5). These limits were used to screen model results against in Sections 4 and 5.

Table 4: Proposed surface water compliance limits.

PARAMETER (units are mg/l unless stated otherwise)	COMPLIANCE LIMIT		
pH (unitless)	6.5 - 9.0		
Turbidity (NTU)	5 (over a 5-year rolling period, 80% of samples, when flows are at or below median flow, are to meet the limit)		
Ammoniacal-nitrogen	≤0.24 (annual median)		
(NH ₃ -N)	<0.4 (annual 95 th percentile)		
Nitrate-nitrogen (NO ₃ -N)	<2.4 (annual median)		
	<3.5 (annual 95 th percentile)		
Cyanide (CN)	0.011 (un-ionised HCN, measured as [CN], ANZG, 2018)		
Sulfate (SO ₄)	A. If hardness is $<100 \text{ mg/L}$ (CaCO ₃), the sulfate compliance limit = 500 mg/L .		
	B. If chloride is <5 mg/L, the sulfate compliance limit = 500 mg/L		
	C. If the hardness is 100–500 mg/L AND if chloride is 5–<25 mg/L, the sulfate compliance limit is (in mg/L):		
	[-57.478 + 5.79*(hardness mg/L CaCO ₃) + 54.163*(chloride mg/L)] * 0.65		
	D. If hardness is between 100 and 500 mg/L AND if chloride is between ≥25 and ≤500 mg/L, the sulfate limit is (in mg/L):		
	[1276.7+5.508*(hardness mg/L CaCO ₃) +1.457*(chloride mg/L)] * 0.65		
	A minimum of 12 samples must be collected over any rolling 12-month period.		
	For compliance limits in A to D, no more than 20% of samples collected over a rolling 12-month period may exceed the relevant compliance limit.		

Page 6 MWM-S003-Rev2

	E. An acute compliance limit = 1,000 mg/L averaged over 4 days and not to be exceeded more than once in a one-year period, OR in more than 10% of		
	samples over a one-year period.		
Aluminium (AI) (dissolved)	≤0.08		
Antimony (Sb) (total)	0.074 (chronic, the average of 5 (monthly) samples over a 5-month period)		
	0.250 (acute, not to be exceeded at any time)		
Arsenic (As(V)) (dissolved)	≤0.042		
Cadmium (Cd)	≤0.0004		
(dissolved)	See below for adjustment algorithm		
Chromium (Cr)	≤0.0033 (CrIII)		
(dissolved)	≤0.006 (CrVI)		
	See below for adjustment algorithm		
Cobalt (Co) (dissolved)	0.001 (chronic)		
	0.11 (acute, not to exceed)		
	See below for adjustment algorithm		
Copper (Cu) (dissolved)	≤0.0018		
Molybdenum (dissolved)	≤0.034		
Zinc (Zn) (dissolved)	0.015		
	See below for adjustment algorithm		
Adjustments			
Cd (dissolved)	HMTV = TV (H/30) $^{0.89}$, where hardness-modified trigger value (HMTV) = (μ g/L), trigger value (TV) (μ g/L) at a hardness of 30 mg/L as CaCO ₃ ; H, measured hardness (mg/L as CaCO ₃) of a fresh surface water.		
Cr (dissolved	HMTV = TV (H/30) $^{0.82}$, where hardness-modified trigger value (HMTV) = (μ g/L), trigger value (TV) (μ g/L) at a hardness of 30 mg/L as CaCO ₃ ; H, measured hardness (mg/L as CaCO ₃) of a fresh surface water.		
Co (dissolved)	Cobalt (µg/L)= exp{(0.414[ln(hardness CaCO3 mg/L)] - 1.887}		
Sb (total)	(chronic) the average of 5 (monthly) samples over a 5-month period (acute) not to be exceeded at any time		
Zn (dissolved)	HMTV = TV (H/30) $^{0.85}$, where hardness-modified trigger value (HMTV) = (μ g/L), trigger value (TV) (μ g/L) at a hardness of 30 mg/L as CaCO ₃ ; H, measured hardness (mg/L as CaCO ₃) of a fresh surface water.		

Source: MGL (2025)

HMTV = hardness modified toxicity value.

TV = toxicity value.

H = hardness.

Table 5: Proposed groundwater compliance limits.

PARAMETER (units are mg/L unless stated otherwise)	COMPLIANCE LIMIT
Nitrate-nitrogen (NO ₃ -N)	11.3 (MAV)*
Cyanide (CN-)	0.6 (MAV)
Sulfate (SO ₄)	≤250 (taste threshold)
Aluminium (Al)	1 (MAV)
Antimony (Sb)	0.02 (MAV)
Arsenic (As(V))	0.01 (MAV)
Cadmium (Cd)	0.004 (MAV)
Chromium (Cr)	≤0.05(MAV)

Page 7 MWM-S003-Rev2

PARAMETER (units are mg/L unless stated otherwise)	COMPLIANCE LIMIT
Cobalt (Co)	<1 (livestock drinking water)
Copper (Cu)	≤0.5
Iron (Fe)	≤0.3
Lead (Pb)	0.01 (MAV)
Manganese (Mn)	0.4 (MAV)
Molybdenum (Mo)	<0.01
Strontium (Sr)	4
Uranium (U)	0.03 (MAV)
Zinc (Zn)	≤1.5

Source: MGL (2025)

MAV = maximum acceptable value – from NZ drinking water standards.

Page 8 MWM-S003-Rev2

3 CLIMATIC SETTING

This section summarises the climatic data for the BOGP, which provides key inputs to the WLBM.

The site is situated within the Otago semi-alpine region. As a result, the climate is strongly seasonal, comprising of frosts and snow between Autumn and Spring, and dry and hot summer months (with temperatures frequently exceeding 30° C). Rainfall in the region varies spatially, typically decreasing with increasing distance from the Southern Alps (KSL, 2025a). At the BOGP, three meteorological stations have been installed since 2022:

- Lake Clearview (340 m above sea level, asl).
- Come in Time (475 m asl).
- Srex, formerly Shreks Met (753 m asl).

The location of these stations and regional stations is shown in Figure 3.




Figure 3 Location of meteorological stations.

Source: Chater (2024a).

Notes: BOGP stations shown in blue, regional stations shown in red. Shreks is now referred to at SRX.

3.1 BOGP Climatic Data

Site recorded data indicates a mean annual rainfall (between November 2022 through January 2025) that ranges from 442 to 506 mm depending on elevation for data collected between (KSL, 2025a), with

Page 9 MWM-S003-Rev2

Lake Clearview being the lowest and Srex being the highest. An increasing rainfall-altitude relationship is observed. Rainfall remains broadly constant throughout the year ranging from 30 – 50 mm per month except for the months of July and August in which rainfall is notably lower. Dry spells of up to two weeks are also common in these months. Evapotranspiration is strongly seasonal with the reported long-term average ranging from approximately 6 mm in July to 136 mm in January. Due to evapotranspiration exceeding rainfall in the summer months, with the exception of storm events, runoff typically only occurs in the winter months (Santana, 2024).

3.2 BOGP Synthetic Climate Dataset

Synthetic climate datasets were developed to increase the length of climate records beyond the handful of years available from site meteorological stations:

- A synthetic daily rainfall dataset was developed by Chater (2024a). This was scaled to the Srex meteorological station (elevation: 753 m above sea level), based on a relationship between rainfall and elevation derived by Chater (2024b) that was representative of the Shepherds and Rise and Shine Creek catchments. The synthetic rainfall record was developed for the Lake Clearview meteorological station (elevation: 340 m asl) and spanned the period 03/06/1949 through to 16/02/2025 (~75 years). These reference works (Chater, 2024a, 2024b) are provided in Appendix B.
- A synthetic daily potential evapotranspiration (PET) record was developed by establishing a relationship between the Srex meteorological station and the Cromwell EWS (retrieved from https://cliflo.niwa.co.nz/ October 2024) station potential evaporation data. The relationship was based on overlapping data between 2/12/2022 and 1/12/2024 (~2 years), the following linear regression equation: Srex PET = 0.715 x Cromwell EWS PET + 0.5078 (Figure 4). The synthetic record established ranged between 7/04/2006 through to 12/12/2024 (~19 years).




Figure 4: Srex Met vs Cromwell EWS PET.

Page 10 MWM-S003-Rev2

Annual totals of the synthetic rainfall and PET datasets are shown in Figure 5 and Figure 6, respectively. On average, annual, PET (~930 mm/year) is close to twice that of rainfall (~500 mm/year). The wettest year was 1995, where ~760 mm of rain fell. The average annual synthetic PET compares well with evaporation pan data from NIWA climate stations Bendigo 2, Clyde Dam, and Cromwell 2, multiplied by a typically used conversion factor of 0.7 (average of ~1010 mm/year).

Figure 7 summarises the average monthly climate setting for the synthetic dataset, showing a strong water deficit in the summer months and a slight water surplus in the winter months.




Figure 5: Annual rainfall totals of synthetic rainfall dataset.




Figure 6: Annual PET totals of synthetic rainfall dataset.

Page 11 MWM-S003-Rev2




Figure 7: Average monthly synthetic climate data summary.

Page 12 MWM-S003-Rev2

4 OPERATIONAL PHASE ASSESSMENT

This section assesses the potential effects to the receiving environment during the Operational Phase of the mine.

4.1 Introduction

There are two key water types that need to be managed as part of the BOGP water management strategy:

- 1. **Internal MIW**: Waters that will be managed internally and will not be discharged during the operational phase of the BOGP. This includes process water, seepage from ELFs, the TSF, water from pit voids, and the underground (Figure 8).
- Surficial MIW: Waters that will be discharged during the operational phase of the BOGP. These
 waters are derived from routing of runoff from haul roads, infrastructure areas⁸, and ELF
 surfaces through sediment control structures (ponds and/or sumps) (Figure 8), and subsequent
 discharge to the receiving streams (Shepherds Creek and Rise and Shine Creek).

4.2 Operational Water Management Risks

As a result, the key MIW risks to downstream water quality for the Operational Phase are:

- For Internal MIW: A prolonged site water surplus conditions (under normal operating conditions) could exceed site water storage capacity and result in discharge of Internal MIW to the receiving environment. Additional controls may need to be engaged to prevent direct discharge. Further discussion on this issue is provided in Section 4.3.
- For Surficial MIW: Elevated sulfate, potential constituents of concern (PCOC) such as arsenic (As), and suspended sediments concentrations in runoff from haul roads, the infrastructure area, and the ELF surfaces. It is assumed that sediment will be managed by routing runoff from these sources through sediment control structures⁹. These structures are not anticipated to reduce sulfate or PCOC; therefore, non-compliance could potentially occur during and/or following runoff events. Further discussion on this issue is provided in Section 4.4.

Page 13 MWM-S003-Rev2

⁸ Note: the infrastructure area excludes the process plant area, ore stockpiles, and other areas of impacted water, which will be used for processing, or will be diverted to the TSF.

⁹ This risk is managed by the erosion and sediment control management plan.




Figure 8: Separation of Internal and Surficial MIW during the operational phase at the BOGP site.

4.3 Internal MIW Water Balance

This section assesses the risks for an Internal MIW water surplus and then subsequent discharge to the receiving environment.

4.3.1 Internal MIW Water Sources and Water Loss

The BOGP Internal MIW water balance is calculated from the annual volumes of water sources and sinks. Sources include, for instance, raw water for processing, rainfall (and subsequent runoff) to the TSF, and pit dewatering, whereas sinks include, for instance, evapotranspiration and water locked up in tailings (Table 4).

Table 6: Internally managed MIW sources and sinks of water.

SOURCES	SINKS	
Rainfall directly onto the TSF.	Evaporation from the TSF.	
Rainfall runoff from undisturbed areas between diversion	Water retained in tailings.	
channels and the TSF.	Evaporation of water used for dust suppression.	
Seepage from the ELFs.	Water used for paste production.	
Runoff from the plant area.		
Dewatering from active pits.		
Dewatering from underground workings.		
Raw water input to the processing plant.		

Page 14 MWM-S003-Rev2

4.3.2 Annual Site Water Balance

A site water balance of the internally managed MIW source and sinks was developed on an annual basis over the operational mine phase from Year 2 through Year 13 (see Table 1 for mine plan schedule). Given the uncertainty in water quality and quality for some sources, two scenarios were included in the water balance, a Low Case and High Case. These cases show the range in potential water balance conditions for the site. Components of the annual site water balance are described in Table 5. Annual average rainfall and potential evaporation from the synthetic climate dataset described in Section 3 was used. The implication of wetter years on the water balance is discussed alongside the water balance results.

Seepage from the TSF, and any water reclaimed from the TSF pond for ore processing, were not included in the water balance as they will be returned to the TSF and therefore do not contribute to a change in the water balance.

Table 7: Water balance input basis.

COMPONENT	DESCRIPTION			
COMPONENT	LOW CASE	HIGH CASE		
	WATER SOURCES			
TSF direct rainfall	Adopts maximum TSF footprint of 608,338 m ² .	No change from Low Case.		
Runoff to TSF	Adopts an estimated footprint of 300,000 m ² (that represents the undisturbed area reporting to the TSF and not diverted by clean water channels) and a runoff of coefficient of 10% (based on synthetic average flows developed for SC01 by KSL [2025a]).	No change from Low Case.		
Shepherds ELF seepage	Assumes an ELF footprint of 1,107,928 m ² . Progressive rehabilitation of 5% of this area per year, which equates to 55% at the end of mine life was adopted. For non-rehabilitated areas, a net percolation rate of 60% of annual rainfall was adopted, and 20% for rehabilitated portions (based on MWM 2025a) (vii).	As per Low Case, except net percolation was increased to 80%.		
RAS Pit dewatering	The area of the open pit void was increased over time from Year 2, assuming the full footprint (643,390 m²) was reached by Year 10. A pit wall runoff coefficient of 50% and groundwater inflow of 5 L/s (KSL, 2024) were adopted for the full pit footprint and reduced based on the reduced footprint over time.	As per Low Case, except runoff coefficient was increased to 70%.		
Underground dewatering	KSL (2025b) estimated in inflow of 30 L/s that represented the full underground development using the Goodman et al. (1965) equation. However, many examples have shown that the Goodman equation tends to overestimate inflows to tunnels. For example, work by Moon and Fernandez (2009) suggest at depths of 150 m below the phreatic surface, inflows could be only 30% of that calculated by the Goodman equation once drawdown and effective stress around a tunnel is taken into account. Therefore, a groundwater inflow rate for the RAS underground workings 200 m below the phreatic surface would be in the region 9 L/s. Once ventilation losses (5 L/s adopted) are taken into account, the net water source equates to 4 L/s for the water balance assessment.	No change from Low Case.		
Process Plant raw water	Estimate provided by MACA Interquip ⁽ⁱⁱ⁾ . Does not vary with average vs wet year condition.	No change from Low Case.		

Page 15 MWM-S003-Rev2

COMPONENT	DESCRIPTION	ESCRIPTION	
COMPONENT	LOW CASE	HIGH CASE	
SCK Valley Fill	Assumes a footprint of 111,845 m ² and a net percolation of 20% (based on MWM 2025a) where the fill is rehabilitated from the start of mining.	No change from Low Case.	
SRX ELF	Assumes a footprint of 200,799 m ² and a net percolation rate of 60% of annual rainfall (unrehabilitated). Active from Year 12.	No change from Low Case except net percolation increased to 80%.	
Western ELF	Assumes a footprint of 200,799 m ² Active from Year 2, then rehabilitated from Year 4 onwards. Net percolation rate of 60% of annual rainfall adopted for unrehabilitated period, and this was reduced to 20% once rehabilitated.	No change from Low Case except net percolation increased to 80% for unrehabilitated period.	
CIT Pit dewatering	Given the pit is only operating for ~12 months, it was assumed that water quality would not deteriorate significantly and be suitable for use as dust suppression.	Assumes a footprint of 135,357 m ² and a runoff coefficient of 70%, plus groundwater inflows of 3.5 L/s (KSL, 2024). Only active during Year 9, then backfilled and rehabilitated.	
SRX Pit dewatering	Given the pit is only operating for ~24 months, it was assumed that water quality would not deteriorate significantly and be suitable for use as dust suppression.	Assumes a footprint of 135,934 m ² and a runoff coefficient of 70%, plus groundwater inflows of 23 L/s (KSL, 2024). Only active during from Year 12 onwards.	
SRE Pit dewatering	Given the pit is only operating for <12 months, it was assumed that water quality would not deteriorate significantly and be suitable for use as dust suppression.	Assumes a footprint of 10,461 m ² and a runoff coefficient of 70%, plus groundwater inflows of 1 L/s (KSL, 2024). Only active during Year 12, then backfilled with SRX ELF.	
Plant area runoff.	Adopts an estimated footprint of 300,000 m ² and a runoff coefficient of 10%.	No change from Low Case.	
	WATER SINKS		
TSF pond evaporation	Adopts a maximum TSF footprint of 608,338 m ² and an open water evaporation estimate of 1,000 mm/year ⁽ⁱⁱⁱ⁾ . Does not vary with average vs wet year condition.	No change from Low Case.	
Water retained in tailings	Estimate provided by EGL ^(iv) for 1.5 mega tonne per day nominal processing rate. Does not vary with average vs wet year condition.	No change from Low Case.	
Paste production	Estimate of 3 L/s from MGL ^(viii) .	No change from Low Case.	

Table Notes:

- i. Average annual rainfall (500 mm) was based on the 73-year synthetic rainfall record developed for the site, scaled to the elevation of the Srex meteorology station.
- ii. C. Warden personal communication 25 November 2024.
- iii. Open-water evaporation estimate based on Srex meteorology station PET (~930 mm/year) multiplied by 1.05 as per Allen et al. (1998).
- iv. E. Torvelainen personal communication 18 November 2024.
- v. R. Redden personal communication 21 November 2024.
- vii. R. Redden personal communication 22 November 2024.
- vii. MWM (2025a) has estimated a net percolation rate of 60-80% for exposed (unrehabilitated ELFs), and 20% for rehabilitated ELFs.
- viii. R. Redden personal communication 22 November 2024.

Page 16 MWM-S003-Rev2

Results from the water balance are presented graphically in Figure 9, and the total proportion over the mine life from each source and sink is tabulated in Table 6. Results suggest the following:

- For the Low Case, a water deficit condition is maintained, which reduced through time to ~10,000 m³/year from Year 12 onwards.
- The High Case results are similar, except for Year 9 and Year 12 onwards where CIT Pit and SRX Pit dewatering are managed within the MIW circuit.
- The largest water sources include rainfall on the TSF, Shepherds ELF seepage, RAS Pit dewatering, and the process plan raw water demand.

The dominant water-deficit condition for the Low Case is consistent with regional meteorological data which indicates a dry temperate climate (KSL, 2025a). This is characterised by an average annual PET nearly twice that of average annual rainfall.

Although only an annual average rainfall year is used, it is noted that following the wettest year on record (1995, with 760 mm falling), the subsequent three years had close to average annual rainfall (480 mm, 560 mm, and 520 mm), suggesting for the Low Case, that the site could 'recover' from a wet year except potentially towards the end of mine life when the deficit becomes smaller.

The High Case is less promising, where the CIT Pit and SRX Pit dewatering could drive the site into a water surplus condition without any additional controls in place. However, it is noted that the available estimate of groundwater inflow to SRX Pit of 23 L/s (KSL, 2024) is higher than the average creek flow in Rise and Shine Creek by a factor of approximate 3, and therefore highly conservative. The conservative nature of the estimate notwithstanding, if a lower groundwater inflow rate is applied to the High Case of say 3 L/s, a water surplus condition is still reached, but of much less magnitude.

If the site were to enter into a consistent water surplus condition, the following engineering controls could be considered to additional water:

- Use of evaporation cannons to increase evaporative losses.
- Increase water storage capacity on site for additional water storage prior to an active water treatment plant being commissioned.
- Commission the water treatment plant during operations rather than at closure to allow discharge of water surpluses.

Page 17 MWM-S003-Rev2




Figure 9: Annual water balance results.

Table 8: Total water balance proportion.

COMPONENT	LOW CASE	HIGH CASE
	WATER SOURCES	
TSF direct rainfall	29%	26%
Runoff to TSF	1%	1%
Shepherds ELF seepage	23%	17%
RAS Pit dewatering	20%	21%
Underground dewatering	5%	4%
Process Plant raw water	17%	15%
SCK Valley Fill	1%	1%
SRX ELF	1%	1%
Western ELF	2%	2%
CIT Pit dewatering	0%	1%
SRX Pit dewatering	0%	10%
SRE Pit dewatering	0%	<1%
Plant area runoff.	1%	1%
	WATER SINKS	
TSF pond evaporation	53%	As per Low Case.
Water retained in tailings	42%	As per Low Case.
Paste production	5%	As per Low Case.

Note: values are rounded so may not sum to 100% for all sources or sinks.

4.3.3 Internal MIW Water Quality

Internal MIW water quality is not assessed given it will not be discharged to the receiving environment under normal operating conditions.

4.3.4 Changes to Creek Flows

Changes to creek flows were calculated based on the runoff generation described in Section 4.4.2, and reflect the mine footprint at life of mine (i.e., maximum disturbance footprint). Calculation results are presented in Table 7, showing reductions to average flow of 17% and 13% for SC01 and RS03,

Page 18 MWM-S003-Rev2

respectively. It is noted here that flow changes will be lower at the start of mine life and increase over time as the mine footprint expands.

Table 9: Calculated changes in creek flow summary statistics at end of the operation phase.

	MEAN FLOW (L/s)	MEDIAN FLOW (L/s)	7D MALF (L/s)
SC01 Simulated Baseline	19.2	13.2	4.42
SC01 Simulated LOM	15.9	10.2	3.24
SC01 difference between baseline and LOM	-3.3 (-17%)	-3 (-23%)	-1.18 (-27%)
RS03 Simulated Baseline	14.5	10	3.34
RS03 Simulated LOM	12.6	8.7	2.84
RS03 difference between baseline and LOM	-1.9 (-13%)	-1.3 (-13%)	-0.5 (-15%)

7D MALF = seven day mean annual low flow.

Note flow values are rounded to reflect inferred accuracy.

4.4 Surficial MIW Water Quality

This section assesses the risks for Surficial MIW discharge to the downstream receiving environment during and/or after high rainfall events.

4.4.1 Approach

This section describes the use of conservative solute mixing models (i.e., no geochemical reactions such as mineral precipitation) to assess water quality during the Operational Phase. The models include solute associated with runoff from haul road and infrastructure areas, ELF surfaces, mixed with runoff from the undisturbed parts of a given catchment. Separate models were developed for SC01 and RS03. Life-of-mine footprints were used within the analysis to provide a conservative assessment. The models were run at daily time steps using the 11-year period synthetic rainfall record period, to account for the influence of climatic variability.

Derivation of runoff rates and solute source terms are described in the following sections.

4.4.2 Runoff Generation

Runoff was estimated for each mine area/domain reporting to compliance locations SC01 and RS03. Areal footprints adopted for each mine domain are tabulated in Table 8. The domains are grouped into areas of similar runoff response type (i.e., haul roads, ELF's, infrastructure and undisturbed) but are not necessarily physically connected. All runoff is assumed to report to the relevant compliance location within the same daily timestep that rainfall occurs. Runoff was calculated differently for disturbed and undisturbed areas as follows:

 Daily runoff for undisturbed areas was estimated using an 11-year synthetic daily unit runoff dataset derived by KSL (2025a) for SC01. This approach was used rather than the Runoff Model described in Section 5.2.3 because the Runoff Model does not replicate high flow events well, and this is when runoff from disturbed mine surfaces will be highest. The synthetic daily runoff should represent these dynamics better.

Page 19 MWM-S003-Rev2

Runoff from ELF surfaces, haul roads, and the infrastructure area was estimated based on the
different runoff coefficients for different daily rainfall totals and the synthetic rainfall dataset
spanning the same 11-year period used for estimating runoff for undisturbed areas. The runoff
coefficients were based on previous work at the Macraes Mine (Golder, 2011) and are shown
in Table 9.

Silt ponds on the site (e.g., Shepherds Silt Pond) will be designed to detain peak flows from 1 in 10-year, storm events. Maximum outflow from such silt ponds will range from 134 to 278 L/s for the 1-hour and 24-hour storm events respectively (EGL personal communication, 2024). Based on the daily runoff coefficients in Table 9, and the synthetic rainfall record, runoff would pass through the silt pond within a day (for 95% of the time). As such, the influence of the silt pond is unlikely to be significant for average daily water quality at compliance locations and is therefore not accounted for in this assessment. The same assumption was made for sediment control structures related to the haul roads or infrastructure areas.

Table 10: Mine domain runoff source areas.

SOURCE TYPE	TOTAL AREA REPORTING TO SC01 (Ha)	TOTAL AREA REPORTING TO RS03 (Ha)	REMARK
Haul roads	32	7	
Infrastructure areas	11	-	All mine infrastructure is within the Shepherds Creek catchment.
ELF surfaces	136 (Shepherds ELF, CIT, and Shepherds Fill)	33 (SRX ELF and WELF)	All engineered landform surfaces assumed to be similar.
Undisturbed areas	871	769	Total SC01 and RS03 catchment area minus areas disturbed by mining.

Further details on mine domain areas are provided in Table 2.

Table 11: Runoff coefficients for different daily totals.

RAINFALL DEPTH (mm/day)	HAUL ROADS AND INFRASTRUCTURE AREAS	ELF SURFACES
0 to 10	0.05	0
10 to 50	0.2	0.05
50 to 90	0.4	0.15
90	0.7	0.4

Source: Golder (2011).

4.4.3 Source Terms

Water running off mine impacted surfaces can be elevated in PCOC. The source of water used for dust suppression on mine impacted surfaces (e.g., haul roads) can also affect the run-off water quality.

Source terms have been developed to represent mine impacted surfaces where aquifer bore water has been used for dust suppression (no additional PCOC load other than that mobilised by water-rock interaction).

Pit sump water is anticipated to increase in solute concentration (e.g., sulfate) over time as the pit wall exposure increases. Application of this water source for dust suppression would elevate dissolved concentrations of runoff from a given surface. By contrast, if groundwater from a dedicated water supply bore is used for dust suppression, then dissolved concentrations of runoff would tend to be lower.

Page 20 MWM-S003-Rev2

Groundwater source terms for dust suppression scenarios are therefore used in the mixing model to provide a range of resulting surface water quality.

Source terms for baseline surface water and mine impacted surfaces are tabulated in Table 10 based on MWM (2025b).

The source terms for mine impacted surfaces with bore water dust suppression had elevated components such as iron, which are not generally mobile in neutral/alkaline oxidised conditions. This source term was therefore run through PHREEQC ¹⁰ with equilibrium phases to provide a more realistic source term.

The TZ4/RSSZ bore water dust suppression source term had lower sulfate concentrations than the mine impacted surfaces dust suppression source term that used the pit water source term. This source term is considered to be conservative since hauls roads and most ELF surfaces will be TZ3, which is a lower geochemical risk material. See MWM (2025b) for further details.

Table 12: Source terms used for the solute mixing model.

PARAMETER	BASELINE SW SC01	BASELINE SW RS03	TZ4 / RSSZ MINE IMPACTED SURFACES -BORE DS ¹
Report reference	J-NZ0475-001-R-Rev0 Table 3	J-NZ0475-001-R-Rev0 Table 4	J-NZ0475-001-R-Rev0 Table 20 run with PHREEQC equilibrium phases.
Alkalinity (mg CaCO ₃ /L)	216	39.1	140.5
pH (pH units)	8.11	7.42	8.4
EC (μS/cm)	488.9	86.4	1,037
Ca	60.8	11.1	90.4
Cl	6.08	1.33	20
F	0.103	0.057	0.83
Mg	21.3	1.99	76.42
Na	20.3	39.5	59
K	2.01	0.578	7.1
TOC	2.08	1.75	-
Al	0.00454	0.00756	0.00016
As	0.00239	0.0085	0
В	0.03304	0	0.104
Cd	0	0.0001	0
Со	0.00026	0.00025	0
Cr	0.00056	0.00059	0
Cu	0.00055	0.00046	0
Fe	0.011	0.0375	0
Hg	0	0	-
Mn	0.00265	0.0095	0.039
Мо	0.00051	0	0.045

¹⁰ A computer program for speciation, batch-reaction, one-dimensional transport, and inverse geochemical calculations. US geological survey techniques and methods, 6(A43), 497 (Parkhurst, D. L., & Appelo, C. A. J., 2013).

Page 21 MWM-S003-Rev2

-

PARAMETER	BASELINE SW SC01	BASELINE SW RS03	TZ4 / RSSZ MINE IMPACTED SURFACES -BORE DS ¹
Report reference	J-NZ0475-001-R-Rev0 Table 3	J-NZ0475-001-R-Rev0 Table 4	J-NZ0475-001-R-Rev0 Table 20 run with PHREEQC equilibrium phases.
Ni	0.00035	0.00035	0.003
Pb	0	0	0.003
Sb	0.00053	0	0.14
Se	0.0025	0	0
Sr	0.947	0.136	1.84
TI	0.00023	0	0
U	0.0051	0.00012	0.016
V	0	0	0
Zn	0.0017	0.00229	0.007
Sulfate	40.5	1.57	320
Ammoniacal-N	0.0103	0.0092	0.012
Nitrate-N	0.083	0.0088	0.094

Note: All units in mg/L unless otherwise stated.

SW = surface water

Note: Green data were <LOR and are included in the source term as '0'.

Source: Orange cells are from OceanaGold (2020a) Blue cells from Golder 2011. Yellow cells reduced from original source term after running with PHREEQC equilibrium phases.

1. Where there is a relationship between sulfate and the constituent for the sulfate concentration of interest, then the TZ3 relationship is used.

4.4.4 Mixing Model Results

The mixing model results for SO₄ concentrations in SC01 for bore water used as dust suppression are presented in Figure 10 through Figure 12, while Figure 13 through Figure 15 presents results for RS03. The mixing model result graphs for analytes where the mine impacted source term is greater than 0 are provided in Appendix C.

Mixing model results where bore water is used for dust suppression are presented in Table 11, with model results presented as maximum daily, and 30-day rolling mean, concentrations. Fixed value proposed compliance limits were used to screen model results against. The percentage of simulated concentrations which exceed proposed compliance limits are also presented. Surface water compliance limits were compared to the daily model results (except for antimony due to the 5-month average compliance condition; 30 day rolling mean results were used instead), while the groundwater limits were compared to a 30-day rolling mean of the model results to account for mixing processes along groundwater flow paths.

The only parameter that showed any potential for exceedance of the proposed compliance limits is molybdenum (Mo), with exceedances up to 2% of the time for surface water, but none for groundwater. However, review of the model results revealed that exceedances only occurred when there was a mismatch between the synthetic flow record and the synthetic rainfall record. For example, when rainfall (and disturbed surface runoff) was high, but the synthetic flow record reported low flows (e.g., 4/02/2013, 21/03/2018, and 29/05/2021). These rare mismatches occurred because the source of each dataset differs in location, with the rainfall based on a relationship to Cromwell, and the flow record based on a relationship to Cluden (~40 km apart). One would expect daily rainfall patterns to differ slight

Page 22 MWM-S003-Rev2

on occasion. As a result, the apparent Mo exceedance is interpreted to be an artifact of the mixing model limitations rather than pose a real risk of non-compliance.

Overall, interpretation of the mixing model results suggests surface water quality will remain below the proposed compliance results for both surface and groundwater.

Page 23 MWM-S003-Rev2

MATAKANUI GOLD LIMITED J-NZ0233-016-R-Rev1

Table 13: Mixing model results for bore water dust suppression scenario including the maximum and average concentrations for each analyte and percentage of generated readings which exceed proposed compliance limits.

	PROPOSEI	O COMPLIANCE LIMITS	SC01 - BORE WA	ATER DUST SUPF	PRESSION		RS03 - BOF	RE WATER DUST	SUPPRESSION	N
	SW SC01, RS03	GW (MW-101, MW- 103, MW-103)	MAXIMUM DAILY CONC. (mg/L)	% EXCEEDING SW COMPLIANCE	MAX 30 DAY MEAN CONC. (mg/L)	% EXCEEDING ^B GW COMPLIANCE	MAXIMUM DAILY CONC. (mg/L)	% EXCEEDING SW COMPLIANCE	MAX 30 DAY MEAN CONC (mg/L)	% EXCEEDING ^E GW COMPLIANCE
Alkalinity (mg CaCO3/L)	-	_	216.0	-	216.0	-	17.52	_	1.7	_
Ca	_	_	90.29	_	65.7	_	89.5	_	12.88	_
CI	_	_	19.97	_	8.4	_	19.80	_	1.75	_
F	-	_	0.83	_	0.2	_	0.822	_	0.074	_
Mg	_	_	76.25	_	30.4	_	75.59	_	3.66	_
Na	_	_	58.88	_	26.7	_	58.78	_	39.94	_
K	_	_	7.085	_	2.8	_	7.03	_	0.724	_
TOC	_	_		_		_		_		_
Al	0.08	1 (MAV)	0.00454	0%	0.0045	0%	0.00756	0%	0.0074	0%
As	0.042	0.01 (MAV)	0.039	0%	0.0085	0%	0.0085	0%	0.0084	0%
В	_	_	0.10	_	0.045	_	0. 102	_	0.002	_
Cd ^A	0.0004	0.004 (MAV)	_	_	_	_	_	_	_	_
Co ^A	0.001	1	_	_	_	_	_	_	-	_
Cr (diss) ^A	0.0033 (Cr(III))	- 0.05 (MAV)	_	-	-		_	-	_	
Or (dioo)	0.006 (Cr(VI))	0.00 (1411/14)	-	-	_	_	_	_	_	_
Cu ^A	0.0018	0.5	_	_	_		_	_	_	
Fe ^A	_	0.3	_	_	_	_	_	_	_	_
Hg	-	_	-	_	-	_	-	_	-	_
Mn	-	0.4 (MAV)	0.0389	_	0.0086	0%	0.0387	_	0.0086	0%
Мо	0.034	0.01	0.045	2.3% ^c	0.0078	0%	0.0445	0.4% ^c	0.0048	0%
Ni	_	_	0.30	_	0.00079	_	0.30	_	0.00062	_

Page 24 MWM-S003-Rev2

MATAKANUI GOLD LIMITED J-NZ0233-016-R-Rev1

	PROPOSED	COMPLIANCE LIMITS	SC01 - BORE WA	SC01 - BORE WATER DUST SUPPRESSION		RS03 - BORE WATER DUST SUPPRESSION				
	SW SC01, RS03	GW (MW-101, MW- 103, MW-103)	MAXIMUM DAILY CONC. (mg/L)	% EXCEEDING SW COMPLIANCE	MAX 30 DAY MEAN CONC. (mg/L)	% EXCEEDING ^B GW COMPLIANCE	MAXIMUM DAILY CONC. (mg/L)	% EXCEEDING SW COMPLIANCE	MAX 30 DAY MEAN CONC (mg/L)	% EXCEEDING ^B GW COMPLIANCE
Pb	_	0.01 (MAV)	0.0031		0.00052	0%	0.0031		0.00032	0%
Sb	0.074 ^B (chronic)	- 0.02 (MAV)	0.14	0%	0.024	- 0%	0.14	0%	0.014	- 0%
- SD	0.250 (acute)	0.02 (WAV)	0.14	0%		070	0.14	0%		070
Se ^A	_	_	-	_	_	-	-	-	-	_
Sr	_	4	1.84	0%	1.09	0%	1.82	0%	0.31	0%
TIA	_	_	_	_	_	_	_	_	_	_
U	_	0.03	0.0161	_	0.0069	0%	0.016	_	0.0018	0%
V ^A	_	_	_	_	_	_	_	_	_	_
Zn	0.015	1.5	0.0070	0%	0.00195	0%	0.0069	0%	0.0023	0%
Sulfate	500	250	319.2	0.0%	86.6	0%	316.5	0.0%	34.3	0%
	0.24 (median)		0.040	0.004	0.044		0.040	0.004	0.0005	
Amm-N	0.4 (95 th percentile)	-	0.012	0.0%	0.011	_	0.012	0.0%	0.0095	_
	2.4 (median)									
Nitrate-N	3.5 (95 th percentile)	11.3	0.094	0.0%	0.085	0.0%	0.093	0.0%	0.018	0.0%

Note: Values of 0 result from both surface water and mine impacted water source terms being <LOR. SW = surface water: GW = groundwater

Page 25 MWM-S003-Rev2

A mine impacted water source term has a value of 0 for these analytes. B based on 30-day rolling mean. C due to misalignment between rainfall and flow in mixing model, discussed further in text.




Figure 10: Modelled sulfate concentrations at SC01, where bore water is used for dust suppression. *Note: dates on graph are representative of the synthetic flow record, not mine life.*




Figure 11: Sulfate exceedance probability in SC01 where bore water is used for dust suppression.




Figure 12: Bottom 10% exceedance probability for sulfate concentrations where bore water is used for dust suppression at SC01.

Page 26 MWM-S003-Rev2




Figure 13: Modelled sulfate concentrations at RS03, where bore water is used for dust suppression. *Note: dates on graph are representative of the synthetic flow record, not mine life.*




Figure 14: Sulfate exceedance probability at RS03 where bore water is used for dust suppression.




Figure 15: Bottom 10% exceedance probability for sulfate concentrations where bore water is used for dust suppression at RS03.

4.5 Summary

Water balance calculations suggest that the site will be in a water deficit condition up to Year 8. After this point, dewatering from satellite pits (i.e., SRX and to a lesser extent CIT) may push the site to a water surplus condition for the last few years of mine life without additional controls. Engineering controls (e.g., construct the water treatment plant prior to closure) are available to manage potential water surpluses, and can be evaluated during detailed design phases. Ongoing water balance

Page 27 MWM-S003-Rev2

reconciliation of the site will be required to confirm water balance conditions remain in a water deficit condition.

Creek flows will be reduced by approximately 13 to 17% on average by the life of mine. Reduction would be lower earlier in mine life with a lower disturbance footprint.

Interpretation of the mixing model results suggests surface water quality at SC01 and RS03 will remain below the proposed compliance limits for both surface and groundwater if groundwater is used for dust suppression.

4.6 Recommendations

The following recommendations are provided:

- A transient operational site wide water balance model be developed prior to mine development
 to improve confidence in water accumulation or losses over time, particularly to understand
 seasonal dynamics. Such a model will likely be needed to support detailed design of the TSF.
- A site water balance reconciliation be completed regularly (e.g., annually or more frequent) to confirm water balance model results are appropriate, and/or make model updates to improve confidence in model results projected into the future.

Discharge of runoff will be monitored with contingencies in place. Adaptive management processes need to be developed to proactively manage and respond if performance and/or compliance monitoring suggests these discharges provide risk of non-compliance. Contingencies could include for example:

- Use fresh groundwater for dust suppression surfaces that will discharge runoff to the receiving environment. This will lower the sulfate load buildup at surface available for transport via runoff.
- Collect and contain runoff within the mine water circuit.
- Use of evaporation cannons to increase evaporative losses.
- Increase water storage capacity on site.
- Commission the water treatment plant during operations rather than at closure.
- Storage of water within pits or other purpose designed infrastructure.

Page 28 MWM-S003-Rev2

5 ACTIVE AND POST CLOSURE PHASE ASSESSMENT

This section assesses the potential effects to the receiving environment during the active and post closure phases of the mine.

5.1 Model Description

The objective of the WLBM is to mechanistically model the water management system at the BOGP. Inputs to the model are based on reported or derived values; some inputs were derived empirically. Hydrological, geochemical, and operational processes that influence water quantity and quality on site are represented in the model and calibrated to existing monitoring data. The model is built to simulate future water management scenarios and predict factors and behaviours that will inform decision making for closure.

5.1.1 Overview

The BOGP WLBM was developed using GoldSim dynamic system modelling software used for simulation of mine water and load balances (Version 15). The water balance uses a daily precipitation timeseries generated with a stochastic climate generator based on statistics from long-term climate data series (as described in Section 3).

The model was divided into two surface water catchments: Shepherds Creek and Rise and Shine Creek. Daily precipitation rates were applied to each catchment area to estimate overland runoff flow volume. A runoff coefficient based on montane landcover and topography was then applied to this volume to account for a proportional loss of water to evapotranspiration and infiltration to groundwater.

The load balance is based on a mass balance approach. It calculates loading rates by assigning source term concentrations to the flows determined in the water balance and generates water quality projections for both onsite and downstream locations. Source terms are applied as constant concentration (where concentration is assumed to remain the same over time), or constant load (where concentration is estimated based on dividing a constant load), and the flow rate for that day. The later means that at low flow rates the concentration is higher, and at higher flows, there is more dilution, hence, less concentrated waters.

Mechanisms represented in the model include:

- Runoff from undisturbed catchments, including conveyance via water diversion structures.
- Filling and discharge of open pit voids, including RAS pit water discharging via the underground workings.
- ELF and TSF runoff and seepage.

The model is run on a daily time step. Results can be provided as monthly mean or median values to align with proposed water quality consent conditions. The selection of model output as monthly projections is therefore considered adequate to inform water management decisions. The model projects 200 years forward from closure. A schematic of model representation of mine site key domains and flow of water and sediment load is illustrated in Figure 16.

Page 29 MWM-S003-Rev2




Figure 16: Schematic diagram of MIW and non-impacted rainfall and runoff for the closure phases at the BOGP site.

Note: An active water treatment plant (WTP) is proposed for the Active closure Phase. When PCOC loads decrease sufficiently the WTP will be replaced by passive water treatment systems, which defines the start of the Post Closure Phase (Table 1). Partial passive treatment of the SRX Pit Lake overflow is proposed (8 L/s) to ensure water quality limits are achieved at RS03.

5.2 Water Balance Model Inputs

5.2.1 Climate Inputs

The Stochastic Climate Library (v2.2.0) tool was used to generate future rainfall and PET timeseries using a first-order autoregressive multivariate model condition based on the rainfall state and nested in monthly and annual models. Input data for the model included:

- Synthetic daily rainfall data described in Section 3.
- Synthetic daily PET data described in Section 3.
- A synthetic daily maximum temperature record was developed in the same manner as for PET, following a linear regression equation: Srex Max Temp = 0.7554 x Cromwell EWS Max Temp 0.1099 (Figure 17).

Page 30 MWM-S003-Rev2




Figure 17: Srex Met vs Cromwell EWS maximum temperature.

Table 12 compares statistical summaries of the synthetic data series with the forward climate realisation, showing a close agreement between annual totals for rainfall and PET.

0.7.4.7.10.17.10.4.1	YEARLY RA	INFALL (mm)	YEARLY PET (mm)		
STATICITICAL DESCRIPTIOR	SYNTHETIC DATA SERIES	FORWARD PROJECTION	SYNTHETIC DATA SERIES	FORWARD PROJECTION	
Mean	498	505	932	935	
Median	493	508	938	933	
Standard Deviation	96	108	33	29	

Table 14: Synthetic vs projected climate summaries.

Climate data was retrieved for the project for the SSP2-4.5 scenario, for the 1995-2014 base period and for projections for 2080-2099 (https://map.climatedata.environment.govt.nz/ (accessed 20/01/2025). Annual climate change factors were applied to the projected climate data to account for changes in future climate as follows:

- Rainfall factor 1.07 (+7% annual rainfall).
- PET factor 1.045 (+4.5% annual PET based on an annual daily average air temperature increase of 1.8 °C applied to the Penman [1946] method).

The factors were applied to increase linearly from 1 at the start of the model to fully reach the above defined factors after 65 years of simulation time, approximately representing 2080-2099. Beyond this period the factors remained the same.

5.2.2 Catchment Delineation

Catchment boundaries were derived based on the topographic watershed divides using QGIS open-source topographic maps (QGIS, 2025). Mine area footprints provided by MGL (such as pits, ELFs, and

Page 31 MWM-S003-Rev2

TSF) were removed from the total catchment areas to derive the undisturbed surface areas. Areas of topsoil deposits were included within the undisturbed footprints. Surface areas were calculated based on areal footprints. The catchments and undisturbed surface area inputs used in the model are summarised in Table 13 below.

Table 15: Catchment delineations and undisturbed surface areas.

CATCHMENT DELINIATION	DESCRIPTION	MINE DOMAINS	UNDISTURBED SURFACE AREA (km²)
Rise and Shine	Rise and Shine Creek sources in	SRX Pit	7.60
Creek Catchment	the central and southeastern extent of the mine area and flows	SRX ELF	
Catchinent	northeast.	RAS Pit (28% of footprint)	
	Includes Clearwater Creek.	CIT Pit (13% of footprint)	
		WELF	
		Monitoring location RS03 – this marks location of outflows from RS03 out of model.	
Shepherds	Extends across the northern half	TSF	9.79
Creek	of the mine area. Shepherds Creek flows southeast across the catchment extent.	Shepherds ELF	
Catchment		RAS Pit (72% of footprint)	
		CIT Pit (87% of footprint)	
		Shepherds Creek Valley Fill	
		Monitoring location SC01 – marks location of outflows from SC01 out of model.	

5.2.3 Runoff Model

The Runoff Model utilised for generating flows from undisturbed surface water areas (Table 13) was based on modifications to the Snow Melt Runoff Model by Martinec et al. (2008). For the purpose of this model the influence of snow melt was assumed negligible. Daily discharge (runoff) is calculated by superimposing daily rainfall on calculated recession and baseflow using the following equation:

$$Q_{n+1} = C \times R \times A \times (1 - k_{n-1}) + Q_n \times k_{n-1}$$

Where:

- Q is the average daily discharge.
- C is the runoff coefficient.
- R is the rainfall contributing to runoff.
- k is the recession coefficient.
- A is the area of the catchment.

The input parameters used for each flow source are summarised in Table 14, with the runoff coefficient varying by month. Selection of parameters was based on professional judgment and attaining a reasonable fit with observed flows at SC01. See Section 5.4.2 for further description on undisturbed runoff model calibration.

Page 32 MWM-S003-Rev2

Table 16: Runoff coefficients for the water balance model.

PARAMETER		VALUE
	_January	0.02
	February	0.02
	March	0.03
	_April	0.04
	_May	0.08
D # O #:-: (O)	_June	0.15
Runoff Coefficient (C)	July	0.3
	August	0.3
	_September	0.12
	October	0.06
	November	0.06
	December	0.03
Recession Coefficient (k)		0.955

5.2.4 Pit Voids

Pit voids were represented in the model as pool elements, accounting for inflows, outflows, and changes in water storage within the pit void. Model inputs are summarised in Table 15.

Table 17: Pit void model summary.

	,			
MODEL FEATURE	DESCRIPTION			
Post-closure setting	 RAS Pit: Open void and pit lake develops. Connected to underground workings via fractured rock mass associated with crown pillar. SRX Pit: Open void and pit lake develops. CIT Pit: Backfilled void with both saturated and unsaturated mine rock. 			
Pit void dimensions, including volume/surface	Provided by MGL in file RAS2503_FTA_ST5 volumes.xlsx. Spill points were defined by the pit crest low points as follows: RAS Pit: 610 meters above sea level (m asl).			
area stage relationship, and spill points elevation.	 SRX Pit: 755 m asl. CIT Pit: 510 m asl. For the RAS Pit, the volume of underground workings was assumed negligible compared to the pit void volume. 			
	For the backfilled CIT pit, a mine rock porosity value of 0.3 was adopted based on the expectation that the mine rock will be relatively coarse with little fines (MWM, 2025a).			
Direct rainfall onto pit lake (when present)	Only relevant for RAS and SRX. Forward rainfall projection as described in Section 5.2.1 of this report. Pit lake surface area dynamically calculated based on provided stage-surface relationship.			
Pit wall runoff	Only relevant for RAS and SRX. Daily climatic water balance (rainfall-PET) suggested 80% of rainfall was available to generate runoff, while at a monthly scale, only 45% was available. Given the pit walls of exposed rock are likely to have little capacity for infiltration or water storage that can be evaporated at a future time, a runoff coefficient of 60% of rainfall was adopted as the approximate mid-point between the daily and monthly available rainfall. This value was applied uniformly in time, with no differentiation between winter vs summer given insufficient data to define such seasonal variation.			
	Exposed pit wall footprint dynamically calculated based on provided stage-surface relationship.			
Groundwater inflow	Based on numerical groundwater model results reported in (KSL, 2024). Inflows rates were defined to decrease linearly as void water level increases over time and hydraulic gradient decreases.			

Page 33 MWM-S003-Rev2

MODEL FEATURE	DESCRIPTION					
-	 RAS Pit: 3 L/s when pit empty, dropping to 1 L/s when water level stabilised as higher level. SRX Pit: 25 L/s when pit empty, dropping to 5 L/s when water level stabilised as higher level. CIT Pit: 3.5 L/s when pit empty, dropping to 1 L/s when water level stabilised as higher level. RAS Pit: assumed negligible. SRX Pit: defined based on Runoff Model described in Section 5.2.3. CIT Pit: assumed negligible. Only relevant for CIT. Described in Section 5.2.5 Only relevant of RAS and SRX. The forward PET projection as described in Section 5.2.1 of 					
evaporation	this report. Pit lak relationship.	e surface area	a dynamically calculated based on provided stage-surface			
Groundwater outflow			g horizonal outflow only. Not significant for SRX as lower Shine Creek (spill point elevation close to creek level) than			
	PARAMETER	CIT	RAS			
	Hydraulic conductivity	10 ⁻⁸ m/s, based on bulk rock mass.	10 ⁻⁵ m/s, based on zone of enhanced fracturing.			
	Discharge to discharge point	250 m, distance between outflow zone and Shepherds Creek.	50 m, based on approximate lateral thickness of zone of enhanced fracturing between pit wall and closest underground workings.			
	Discharge head	430 m asl, nearby Shepherds Creek elevation.	490 m asl, approximate underground portal elevation.			
	Pit lake head	Calculated dy	namically as pit void water level changes.			
	Outflow width	200 m, based on approximate lateral width of pit shell at discharge zone.	200 m, based on approximate lateral width underground workings at discharge zone.			
	Outflow thickness	Calculated dynamically as pit void water level changes.	50 m, based on approximate thickness of zone of enhanced fracturing.			

5.2.5 Mine Waste Storage Facilities

Mine Waste Storage Facilities (MWSFs) represented in the model included the:

• Shepherds ELF.

Page 34 MWM-S003-Rev2

- SRX ELF.
- Western ELF.
- · CIT backfilled pit void.
- TSF.

The SCK Fill was also represented as a MWSF. From near the top of the valley, clean water diversions will be used to allow clean water to bypass the TSF and Shepherds ELF. The diversions will drop onto a constructed channel in the lower SCK Fill that will extend to the Run of Mine (ROM) at least (the natural creek may need to be lifted past the process area). Areas below the ROM where there is minimal ore exposure will be channelled via silt retention ponds to Shepherds channel (or possibly the natural creek). The lower gorge has to be filled to create sufficient width for services. The Shepherd channel shall be formed through this section to take a 1% AEP event (D. Stretch, MGL, personal communication, 16 April 2025).

Run off from the Shepherds ELF is directed to the Shepherds Silt Pond and then discharged through a decant to the Shepherds channel after settling. In a large storm event, the silt pond can discharge directly by spill way to the Shepherds channel. Run off from the valley below the silt pond shall also be captured in sediment treatment ponds and discharged into Shepherds channel.

Mechanistically, the MWSFs were represented in a similar manner, with runoff being calculated as a proportion of daily rainfall, net percolation into the facility also calculated as a proportion of daily rainfall, and seepage out of a facility calculated as a function of water storage within the facility with a reservoir element. Model inputs are summarised in Table 16.

Table 18: MWSF model input parameter summary.

	' '	•				
MODEL FEATURE	DESCRIPTION					
Post-closure setting.	The cover system established at closur across all MWSFs (MWM, 2025a).	e is anticipated to perform similarly				
Runoff	Defined as a proportion of daily rainfall, with runoff coefficients increasing a rainfall depth increased, as follows:					
	DAILY RAINFALL	RUNOFF COEFFICIENT				
	<5 mm	0				
	≥ 5 mm but < 10 mm	0.05				
	≥ 10 mm but < 50 mm	0.1				
	≥ 50 mm but < 90 mm	0.15				
	> 90 mm 0.2					
	Modified from previous work at Macraes Mine (Golder, 2011) to achieve an average runoff yield similar, but slightly lower, than Shepherds Creek yield of ~10% of average rainfall. The values adopted achieved a yield of ~7% of average rainfall.					
	Applies to all MWSFs.					
Net percolation (NP)	20% of daily rainfall, as per MWM (202	5a).				
	Applies to all MWSFs.					
	Varies by MWSF as follows:					
	Shepherds ELFs, SRX ELF, SCK Fill, CIT Backfill: mine rock assumed to					
Initial condition	be wetted up and at semi-stable seepage rates.					
	TSF: set to achieve an initial flow rate of approximately 13.4 L/s as per EGL					
	(2025) and then stabilised at rate based on NP.					

Page 35 MWM-S003-Rev2

Recession Coefficient (k, -) Recession equation: MWSF Storage Volume x (1-k). Varies by MWSF as follows:

- Shepherds ELFs, SRX ELF, SCK Fill, and CIT Backfill: set to 0.995 to achieve a relatively stable seepage rate. Translates to 5% of water stored in MWSF discharged as seepage.
- TSF: set to 0.998 to achieve a relatively stable seepage rate after approximately 5 years of drain down as per EGL (2025).

5.2.6 Water Treatment

Active water treatment in the Shepherds Creek catchment is proposed during the Active Closure Phase and passive water treatment systems are proposed for BOGP in the Post Closure Phase (Table 1) for MIW in the Shepherds Creek catchment and for partial treatment of the SRX Pit Lake overflow (8 L/s being the average pit lake overflow rate). Active treatment will run until passive treatment systems can achieve compliance with water quality compliance limits. The model did not account for any hydrological influence of such systems (i.e., water passes through them within the daily timestep).

Further details on active and passive water treatment are provided in MWM (2025d). Passive treatment efficiencies are also provided in Table 25.

5.3 Load Balance Inputs

Each of the water balance components shown in Figure 16 are associated with the water quality source terms as presented in Table 17 and Table 18. The derivation of the data in these tables is described in detail in the *Source Term Definition Report* by MWM (2025b).

Table 19. Source Term Water Quality Part 1 of 2.

SOURCE TERM	ELF_RO_ST	PW_RO_ST	TSF_RO_ST	CC01_UND_ST
DESCRIPTION	Rehabilitated ELF Runoff Water Quality	Pit Walls Runoff	Rehabilitated TSF Runoff	Surface water quality for Clearwater Creek
MWM (2025b) REPORT SECTION	Section 8.3. Table 20 Source terms: Mine Impacted Surfaces and Rehabilitated Surfaces Brown Rock	Section 6.4.1. Table 16 BOGP Pit Wall Runoff Source Term	Section 8.3. Table 20 Source terms: Mine Impacted Surfaces and Rehabilitated Surfaces Brown Rock	Section 4.1.2 Table 4 Surface Water Quality Source Terms for Bendigo Creek (CC01)
UNITS / PARAMETER	mg/L	mg/L	mg/L	mg/L
Al	0.155	0.114	0.155	0.01231
Alkalinity	140.5	61.3	140.5	14.7
As	0.02	0.093	0.02	0.001
В	0.064	0.046	0.064	0.0175
Ca	15.68	55	15.68	3.88
Cd	0.0001	0.0001	0.0001	0.00009
CI	3.1	13	3.1	0.794
Со	0.0005	0.0005	0.0005	0.00021
Cr	0.0005	0.0005	0.0005	0.00056

Page 36 MWM-S003-Rev2

SOURCE TERM	ELF_RO_ST	PW RO ST	TSF RO ST	CC01 UND ST
Cu	0.001	0.0034	0.001	0.00043
DOC	2.01	0	2.01	1.23
F	0.34	0.21	0.34	0.055
Fe	0.14	9.1	0.14	0.0293
Hg	-	-		0.00024
K	8.66	39	8.66	0.335
Mg	1.95	37	1.95	0.844
Mn	0.0115	0.014	0.0115	0.0009
Мо	0.147	0.023	0.147	0.00033
NO3-N + Amm-N	0.4	40	0.4	0.0096
Na	32.88	33	32.88	2.35
Ni	0.0005	0.0009	0.0005	0.00056
Pb	0.00019	0.004	0.00019	0.00022
Sb	0.049	0.027	0.049	0.00044
Se	0.00025	0.00025	0.00025	0.0022
SO ₄	470	160	470	0.843
Sr	0.67	0.91	0.67	0.042
TI	0.00025	0.00025	0.00025	0.00019
TOC	2.01	0	2.01	1.23
CN	0	0	0	0
U	0.053	0.0106	0.053	0.00009
V	0.0005	0.0005	0.0005	0.0005
Zn	0.001	0.002	0.001	0.00161
рН	8.4	8.2	8.4	7.03

In addition, the seepage water quality forecast for five waste rock domains (Shepherds ELF, SRX ELF, WELF, CIT Backfill, and SCK Fill) were developed in detail in the *Engineered Landform Water Quality Forecast Model Report* (MWM, 2025c). Four of the five domains are assumed to start generating seepage 11 years before closure (assuming that BOGP takes 11 years to be completed). Therefore, peak concentrations for WELF, SCK Fill, and SRX ELF occur during operation. Peak concentration for Shepherds ELF occurs in Active Closure phase, same as CIT ELF Backfill, as it is assumed the latter will be backfilled at closure. These model outputs with time are presented in Figure 18 and Figure 19.

Page 37 MWM-S003-Rev2

MATAKANUI GOLD LIMITED J-NZ0233-016-R-Rev1

Table 20. Source Term Water Quality Part 2 of 2.

SOURCE TERM	RS03_UND_ST	RS04_UND_ST	SC03_UND_ST	GW_MDD015_ST	Rain_ST	TSF_Seepage_ST
MWM (2025b) REPORT SECTION	Section 4.1.2 Table 4 Surface Water Quality Source Terms for Bendigo Creek (RS03)	Section 4.1.2 Table 4 Surface Water Quality Source Terms for Bendigo Creek (RS04)	Section 4.1.1 Table 3 Surface Water Quality Source Terms for Shepherds Creek (RS04)	Section 4.2.1 Table 6 Water Quality Source Terms for Groundwater (MDD015)	Section 3.1.1. Table 2. Rainfall Quality Source Term Data.	Section 9.3.2. Table 23 Process Water Quality and Tailings Seepage Water
PARAMETER/UNITS	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
Al	0.00756	0.00686	0.0064	0.0061	-	0.01
Alkalinity	39.1	72.8	136.2	201.6	0.81	73.21
As	0.0085	0.001	0.00079	0.024	-	2.05
В	0.0188	0.011	0.028	0.0331	-	0.825
Ca	11.1	23.3	40.9	38.9	0.11	297
Cd	0.0001	0.00003	0.00011	0.00008	-	0.0002
CI	1.33	1.96	2.74	9.42	0.31	804
Co	0.00025	0.00013	0.00029	0.00019	-	0.053
Cr	0.00059	0.00026	0.00062	0.0005	-	0.0055
Cu	0.00046	0.00083	0.00055	0.0003	-	1.598
DOC	1.75	2.75	2.01	0.3	-	0
F	0.057	0.059	0.119	0.162	-	1.93
Fe	0.0375	0.068	0.0215	0.0147	-	15.3
Hg	0.00026	0.00011	0.0003	0.0002	-	0
K	0.578	1.18	1.43	1.44	0.88	50.8
Mg	1.99	3.74	10.2	16.2	0.09	99
Mn	0.0095	0.006	0.00357	0.0068	-	0.59
Мо	0.00033	0.00022	0.00044	0.0004	-	0.14
NO3-N + Amm-N	0.0088	0.0033	0.1507	0.0051	0.06	2.005
Na	39.5	5.15	36.2	43.6	0.32	848
Ni	0.00035	0.00049	0.00036	0.0003	-	0.678

Page 38 MWM-S003-Rev2

MATAKANUI GOLD LIMITED J-NZ0233-016-R-Rev1

SOURCE TERM	RS03_UND_ST	RS04_UND_ST	SC03_UND_ST	GW_MDD015_ST	Rain_ST	TSF_Seepage_ST
Pb	0.00025	0.00008	0.00029	0.0002	-	0.0275
Sb	0.0005	0.00017	0.00058	0.0004	-	0.18
Se	0.0025	0.0008	0.0029	0.0018	-	0.003
SO ₄	1.57	2.8	14.4	10.3	0.18	954
Sr	0.136	0.315	0.675		-	4.4
TI	0.00023	0.00005	0.00027	0.0003	-	0
TOC	1.75	2.75	2.01	0.3	-	0
CN	0	0	0	0	0	0.35
U	0.00012	0.0003	0.0022	0.001	-	0.028
V	0.0005	0.0005	0.0005	0.0005	-	0.004
Zn	0.00229	0.00142	0.0015	0.0015	-	0.0296
рН	7.42	7.51	7.88	8.1	5.2	6.41

Page 39 MWM-S003-Rev2




Figure 18. Seepage Water Quality for Waste Rock Domains at the BOGP. Part 1 of 2.

Page 40 MWM-5003-Rev2




Figure 19. Seepage Water Quality for Waste Rock Domains at the BOGP. Part 2 of 2. CN = Cyanide.

Page 41 MWM-S003-Rev2

5.4 Model Evaluation

5.4.1 Model QA/QC¹¹.

The WLBM was reviewed as part of internal QA/QC and this included the following steps:

- Checking that data sources are documented.
- Verification that storages, inflows, and outflows are correctly located and allocated to the right source and sink.
- Cross checking of flows to ensure they are not duplicated or missed.
- Verification of model functions and expressions to ensure they are working as intended.
- For the calibration period, predictions were evaluated through comparison to monitoring data.
- Using professional judgement and experience to evaluate if results reflect the understanding of the project and model inputs.

5.4.2 Model Calibration

The Runoff Model was history matched against a synthetic flow record for SC01. The synthetic record was developed based on the relationship established between SC01 and Cluden Stream @ Stockyards (KSL, 2025a): SC01 flow = 0.03974838 x Cluden flow – 0.25974622. The synthetic flow record timespan covered 23/11/2012 through 31/01/2025 (~12 years). History matching to the Rise and Shine Creek data was considered not worthwhile due to water takes of unknown volume and timing from this creek for drilling purposes. The Runoff Model was driven by the synthetic rainfall record described in Section 5.2.1.

Initially, the Australian Water Balance Model was used in an attempt to reproduce the synthetic flow record, but model performance was found to be poor. Thus, the Runoff Model was utilised as described in Section 5.2.3. History matching with the Runoff Model was completed using a manual trial and error approach, with a focus on balancing the match between:

- Daily average simulated and observed stream flow rates (Figure 20 and Figure 21).
- Flow exceedance probability (Figure 22).
- Cumulative water volume (Figure 23).

Findings from the history matching were as follows:

History matching was unable to achieve a satisfactory fit to both high and low flow conditions; a trade-off between fitting one or the other was apparent. One of the main causes behind this was the use of synthetic rainfall and flow records from two different physiographic locations, namely a low valley bottom setting for the Cromwell EWS station and a mountainous terrain catchment reporting to Cluden @ Stockyards. Although the synthetic records are reasonable approximations of average conditions at Bendigo, they are unlikely to represent well individual storm/rainfall events which drive high flow conditions. On balance, the fit to the lower flow

Page 42 MWM-S003-Rev2

¹¹ Quality Assurance / Quality Control

- conditions was prioritised as there is less dilutive capacity during these conditions, so the risk of exceeding in stream water quality objectives is higher (i.e., a conservative choice).
- Low flow conditions were slightly under predicted (e.g., Figure 21), which all else being equal, would conservatively result in higher modelled instream water quality concentrations.
- Average flow statistics were reasonably well matched (Table 19), while the 7 day mean annual low flow was under predicted.
- The overall fit to daily average flow data, flow exceedance probability, and cumulative water volume is considered reasonable for representing conditions at the spatial scale of the Project. Mismatch to observed data is typically a result of under predicting higher flow conditions.




Figure 20: Daily flow rate comparison.




Figure 21: Daily flow rate comparison (log scale).

Page 43 MWM-S003-Rev2




Figure 22: Flow exceedance comparison.




Figure 23: Cumulative water volume comparison.

Table 21: SC01 flow statistic comparison.

METRIC	SYNTHETIC RECORD	MODEL RESULTS
Mean flow (L/s)	19.0	18.1
Median flow (L/s)	12.7	12.3
7-day MALF (L/s)	4.5	2.40

MALF = mean annual low flow.

5.4.3 Model Limitations

5.4.3.1 Water Balance

As discussed in Section 5.4.2, the Runoff Model did not provide a strong match to high or (daily average) peak flow conditions. In addition, peak flows typically occur at a finer temporal scale than the modelled daily time step. As such, the Runoff Model, and by extension the wider Water Balance Model results are not appropriate to inform engineering design criteria that are sensitive peak flows.

The Runoff Model was history matched to SC01 flows, which spatially average flow generation over the entire catchment. However, higher elevation sub-catchments (e.g., area reporting to SC03) are known to have higher unit flow yields (KSL, 2025a). As such, the Runoff Model may not be reliable at forecasting flows at smaller, lower elevation portions of the Project area.

Page 44 MWM-S003-Rev2

Pit lake evaporation was derived based on the SRX climate station record. It is known that deep lakes (e.g., >5 m) can display different patterns in lake evaporation than PET derived from land-based weather stations, where radiation energy can be stored within the in warmer months and released in colder months (Jenson and Allen, 2016). In addition, PET from land-based weather stations may not reflect well wind, water temperature, and pit wall shading effects specific to pit lake evaporation (McJannet et al., 2019). This is a noted uncertainty in the model, particularly for the pit voids, but no more uncertain than other model elements.

Model inputs and outputs to the mine domain components of the WLBM were not calibrated and typically informed by experience at mine sites in similar settings (e.g., Macraes Mine, etc.). Performance monitoring during operations and post-closure will be essential to confirm model results are reasonable.

Seepage collection systems are assumed to collect and recover 100% of load associated with mine waste storage facilities. Additional ground investigations, groundwater monitoring, and detailed modelling will be required at detailed design.

5.4.3.2 Load Balance

Load balance limitations are outlined below:

- Conservative transport assumption: The model assumes that all parameters are transported downstream without accounting for geochemical reactions. This means that processes such as precipitation (e.g., formation of hydroxy-sulfates) and adsorption are not represented. As a result, elements known to be removed from solution, such as Al, Fe, and As, are likely overestimated. Other trace metals (e.g., Co, Mo, V), may also be affected. These processes can occur within pit lakes or along flow pathways.
- Nitrate decay in pit lakes: A decay rate has been applied to nitrate to reflect biological denitrification processes, as observed in pit lakes at Macraes (Navarro-Valdivia et al., 2023).
 This accounts for partial natural attenuation of nitrate concentrations within the receiving water bodies.
- **Nitrogen:** Nitrogen speciation is not modelled (e.g., ammoniacal nitrogen, nitrite, nitrate). Total nitrogen concentrations are used in the model, however they are presented as Nitrate-N, as it is assumed that is the predominant nitrogen species in typical oxic MIW.
- **pH:** pH is expected to remain neutral to alkaline in this load balance. To account for "pH transport," the hydrogen ion concentration (estimated from the source terms using the equation pH = $-\log_{10}[H^+]$) is used instead. It remains relatively stable, but this does not account for carbonate speciation, which is likely to control and buffer pH at neutral levels due to the high alkalinity expected from the dissolution of carbonate minerals in the schists.
- Source terms assumptions: The model applies average water quality conditions across the
 simulation period. This limits its ability to capture short-term water quality variability, such as
 the ones caused by storm events, seasonal dry periods, which can influence contaminant
 mobility and concentrations. As more information becomes available, additional processes,
 such as decaying concentrations of pit walls or load contributions from rehabilitated areas, can
 be incorporated.

Page 45 MWM-S003-Rev2

- Pit lake full mixing approach: The model does not simulate physical processes such as
 density-driven stratification or mixing within pit lakes or water bodies. In reality, thermal
 stratification can influence redox conditions, nutrient cycling, and the timing and depth of
 contaminant release (e.g. from bottom layers). The current approach assumes full mixing of the
 pit lake. It is assumed that some stratification may occur, but annually this stratification would
 break down in winter.
- No biogeochemical processes: Whilst a nitrate decay rate is included for water bodies, other biologically mediated processes (e.g., sulfate reduction, organic matter degradation, iron reduction) are not explicitly represented. These processes can significantly influence redoxsensitive elements (e.g. Fe, Mn, U, As) and could result in either attenuation or remobilisation depending on conditions.

5.5 Model Results

Model results for water balance and load balance are described separately in this section.

5.5.1 Water Balance Results

Water balance model results are described separately for mine domains (e.g., RAS Pit water level) and creek flows (e.g., SC01) in the following subsections.

5.5.1.1 Mine Domains

Model results for RAS Pit Void are shown in Figure 24 and Figure 25, and suggest:

- Stabilisation of the pit lake rebound in approximately 25 years, with a water level around 492 m asl (slightly above the adopted portal elevation of 490 m asl).
- Model results do not suggest the pit lake will spill over the pit crest low point (565 m asl).
- Discharge of pit lake water via the underground portal will start once the pit lake water level is above 490 m asl, and typically range between 4 to 7 L/s, with an average of about 6 L/s.

Page 46 MWM-S003-Rev2




Figure 24: RAS Pit Void model results - water volume and level.




Figure 25: RAS Pit Void model results - underground portal discharge.

Model results for SRX Pit Void are shown in Figure 26 and Figure 27, and suggest:

- The pit void will fill and spill quickly (~ 6 months) owing to the low pit crest elevation and high groundwater inflow rate.
- The variability in overflow rate from the pit lake is higher than other pit voids due to the
 contribution of runoff from undisturbed areas reporting to the pit. Periodic high outflow rates are
 predicted, 120 L/s or higher, but average outflow rate is approximately 8 L/s.

Page 47 MWM-5003-Rev2




Figure 26: SRX Pit Void model results – water volume and level.




Figure 27: SRX Pit Void model results - overflow rate.

Model results for CIT Pit Void are shown in Figure 28 and Figure 29, and suggest:

- The backfilled pit void will fill and spill at around 3.5 years.
- Outflow rates via groundwater pathways are low <0.1 L/s, with the majority of outflow via spilling at the pit crest at an average of approximately 1.5 L/s.

Page 48 MWM-S003-Rev2




Figure 28: CIT Pit Void model results – water volume and level.




Figure 29: CIT Pit Void model results – outflow rates.

Model results for seepage flow rates from the ELFs and TSF are shown in Figure 30, and suggest:

- Average flow rates for the Shepherds ELFs of approximately 4 L/s, with flow rates typically varying between 2 and 6 L/s. Seepage flow rates from SRX ELF, WELF, and SCK Fill approximately 0.5 L/s or less on average.
- TSF seepage decays through the drain down period in accordance with input described in Section 5.2.5, with average long term seepage flow rates of approximately 2 L/s. Flow rates typically vary between 1 and 3 L/s in the long term.

Page 49 MWM-S003-Rev2




Figure 30: ELF and TSF seepage flow rates.

Note: SRX ELF seepage flow rate is similar to the WELF, so plots behind this trace.

5.5.1.2 Creek Flows

Forecasted changes to the Shepherds Creek flow regime (at SC01) are shown in Figure 31, while Clearwater Creek changes (at RS03) are shown in Figure 32. Summary statistics are presented in Table 20. Forecast baseline conditions, based off the Runoff Model (See Section 5.2.3), are shown for comparison.

Overall model results suggest the project will increase the water flow passing through the compliance points. Average and median flows increase between 50 and 60%, while low flows increase more significantly, ranging between increases of appropriately 280 to 530%. The main cause in flow increase, especially for lower flow conditions, is the increased seepage from ELFs and TSFs. The RAS pit lake storage and outflow dynamics are also a contributing factor, albeit less influential.

Page 50 MWM-S003-Rev2




Figure 31: SC01 forecasted flows regime.




Figure 32: RS03 forecasted flows regime.

Page 51 MWM-S003-Rev2

Table 22: Forecast creek flow summary statistics.

	PEAK FLOW (L/s))	MEAN FLOW (L/s)	MEDIAN FLOW (L/s)	7D MALF (L/s)	5YR-7D LF (L/s)
SC01 Simulated Baseline	176	18	12	2	1
SC01 Simulated Post-Closure	563	29	23	13	11
Change	387	11	11	11	10
	(+220%)	(+59%)	(+92%)	(+535%)	(+787%)
RS03 Simulated Baseline	117	12	8	1	1
RS03 Simulated Post-Closure	229	18	14	5	5
Change	113	6	6	4	4
	(+97%)	(+52%)	(+70%)	(+282%)	(+426%)

⁷D MALF = seven day mean annual low flow.

5YR-7D LF is the lowest weekly average flow that has a reoccurrence interval of 1 in 5 years.

Note flow values are rounded to reflect inferred accuracy.

5.5.2 Load Balance Results

This section discusses the load components of the WLBM.

5.5.2.1 Introduction

This section presents the WLBM results for the load balance:

- Yearly average tabulated results, covering up to 200 years, are provided in Table 21.
- Relevant components of the WLBM are presented including Shepherds Creek (SC01) and Rise and Shine Creek (RS03).
- Results for SC01 and RS03 are screened against recommended surface water and groundwater limits from the proposed compliance water quality standards (Ryder, 2025) as shown in Table 21.

Table 23: Summary of used reference limits for screening.

PARAMETER	SURFACE WATER LIMIT (mg/L)	GW LIMIT (mg/L)	SOURCE SW LIMIT / GW LIMIT
Al	0.08	1	Ryder (2025)
As	0.042	0.01	Ryder (2025)
В	-	2.4	ANZG (2018) 90% Protection
Cyanide (CN)	0.011	0.6	Ryder (2025)
Cd	0.0004 5	0.004	Ryder (2025)
Со	0.001 ^{2,5}	1	SW Chronic; Ryder (2025)
Cr	0.0033 3,5	0.05	SW Cr(III); Ryder (2025)
Cu	0.0018	0.5	Ryder (2025)
Fe	-	0.3	Ryder (2025)
Mn	-	0.4	Ryder (2025)
Мо	0.034	0.01	Ryder (2025)
NO3-N	2.4	11.3	SW Annual Median Ryder (2025)
Pb	-	0.01	Ryder (2025)
SO4	500 ¹	250	Ryder (2025)

Page 52 MWM-S003-Rev2

PARAMETER	SURFACE WATER LIMIT (mg/L)	GW LIMIT (mg/L)	SOURCE SW LIMIT / GW LIMIT
Sb	0.074 ⁴	0.02	Ryder (2025)
Se	-	0.02	Ryder (2025)
Sr	-	4	Ryder (2025)
U	-	0.03	Ryder (2025)
Zn	0.015 ⁵	1.5	Ryder (2025)

- 1. No modification has been applied to this limit and a set value of 500 mg/L is used for assessment purposes.
- 2. Where the lower chronic limit has been applied 0.001 mg/L.
- 3. Where Cr(III) limits are used as proposed by Ryder (2025) being the lower limit for Cr (i.e., Cr(VI) is 0.006 mg/L).
- 4. The lower chronic limit (total) has been applied (0.074 mg/L) as a fixed value for annual data.
- 5. Where hardness modification has not been applied as a conservative approach

5.5.2.2 RAS Pit Lake

RAS Pit Lake receives input from three inflows: groundwater, pit wall runoff, and rainfall. Of these, only groundwater and pit wall runoff contribute significant loads. Rainfall is included in the water balance, but it only provides dilution and contributes minor loads of sulfate and nitrate-N.

The water quality results for selected parameters are show in Figure 33 and Figure 34. Results show that compared to the reference limits, parameters are mostly lower. Parameters that are above at least one of the reference limits are: NO3-N, Al, Sb, As, Fe, Cu and Mo.

Page 53 MWM-S003-Rev2




Figure 33. RAS Pit Lake water quality results. Part 1 of 2.

Page 54 MWM-5003-Rev2




Figure 34. RAS Pit Lake water quality results. Part 2 of 2.

The average inflow loads to the RAS Pit Lake are shown on Table 22. The data show that pit wall runoff is the dominant source of contaminants, responsible for nearly all the assessed parameters.

Groundwater Inflow: Groundwater is the dominant source of Se (89 g/year, 68% of the total Se load). It also contributes significantly to boron (17%), chromium (23%), vanadium (23%), manganese (12%),

Page 55 MWM-5003-Rev2

and zinc (18%). Whilst its influence is limited, groundwater still accounts for the majority of selenium reaching the lake.

Pit Wall Runoff

Pit wall runoff is the main driver of load for 17 of the 18 parameters assessed, contributing more than 98% of the load for elements such as Al, Fe, Mo, NO3-N, Pb, Sb, SO₄, Sr, and U. Copper and arsenic are also largely derived from pit wall contributions, exceeding 93%. Nitrate loads are high, associated with blasting residues. There is a 25% yearly decay of nitrogen due to bacterial activity based on empirical evidence (Navarro-Valdivia et al., 2023).

GW INFLOW PARAMETER PIT WALL **RAINFALL TOTAL** Al (kg/yr) 19.3 (98.5%) 0 (0%) 0.30 (1.5%) 19.6 As (kg/yr) 1.2 (7.0%) 15.8 (93.0%) 0 (0%) 17.0 B (kg/yr) 1.6 (17.4%) 7.8 (82.6%) 0 (0%) 9.4 Co (g/yr) 9.4 (10.0%) 84.8 (90.0%) 0(0%)94.2 Cr (g/yr) 24.8 (22.6%) 84.8 (77.4%) 0 (0%) 109.6 Cu (g/yr) 14.9 (2.5%) 576.3 (97.5%) 0 (0%) 591.2 Fe (kg/yr) 0.73 (0.0%) 1,543 (100.0%) 0 (0%) 1,543 Mn (g/yr) 337.2 (12.4%) 0 (0%) 2,710 2,373 (87.6%) Mo (kg/yr) 0.02 (0.5%) 3.9 (99.5%) 0 (0%) 3.9 NO3-N (kg/yr) 0.25 (0.0%) 6,780 (99.9%) 3.7 (0.1%) 6.784 Pb (g/yr) 9.9 (1.4%) 678.0 (98.6%) 0 (0%) 688.0 Sb (kg/yr) 0.02 (0.4%) 4.6 (99.6%) 0 (0%) 4.6 Se (g/yr) 89.3 (67.8%) 42.4 (32.2%) 0 (0%) 131.6 SO4 (kg/yr) 510.8 (1.8%) 27,121 (98.1%) 11.1 (0.0%) 27,643 Sr (kg/yr) 0 (0%) 154.3 (100.0%) 154.3 0 (0%) U (g/yr) 49.6 (2.7%) 1,797 (97.3%) 0(0%)1,846 V (g/yr) 24.8 (22.6%) 84.8 (77.4%) 0 (0%) 109.6 Zn (g/yr) 74.4 (18.0%) 339.0 (82.0%) 0 (0%) 413.4

Table 24. Average annual Inflow Loads to RAS Pit Lake.

It is assumed in the WLBM that the RAS Pit Lake water flows to the Shepherds Creek via the underground workings, being an input to the SC01 monitoring point.

5.5.2.3 SRX Pit Lake

SRX Pit Lake receives input from four sources: groundwater inflow, pit wall runoff, SRX ELF seepage, and undisturbed runoff. Rainfall is present in the water balance but is mostly a dilution process, with no significant load.

The water quality results for selected parameters are shown in Figure 35 and Figure 36. Compared to the reference limits, most parameters are below the water quality limits. Parameters that exceed at least one of the reference limits include NO₃-N, As, Co, Sb, Fe, and Mo. Other elements are below the reference limits. Partial passive treatment of the SRX Pit Lake overflow is proposed (8 L/s) to ensure compliance with regards to water quality objectives at RSO3.

Page 56 MWM-S003-Rev2




Figure 35. SRX Pit Lake water quality results. Set 1 of 2.

Page 57 MWM-5003-Rev2




Figure 36. SRX Pit Lake water quality results. Set 2 of 2.

The average inflowing loads for the SRX Pit Lake are shown Table 23. The data indicate that SRX ELF seepage contributes the greatest load for a wide range of PCOC. Pit wall runoff and groundwater also play key roles, each dominating a smaller group of parameters.

Groundwater Inflow: Groundwater is the primary source for the following parameters:

Selenium (285 g/year, 84%).

Page 58 MWM-S003-Rev2

- Boron (5.2 kg/year, 70%).
- Chromium (79 g/year, 71%).
- Vanadium (79 g/year, 63%).
- Zinc (237 g/year, 61%).
- Manganese (,56%).
- Cobalt (30 g/year, 54%).

Pit Wall Runoff: Pit wall runoff is elevated for five parameters:

- Aluminium (4.1 kg/year, 75%).
- Copper (122.4 g/year, 56%).
- Iron (327.6 kg/year, 71%).
- Nitrate-N (1,440 kg/year, 99.8%).
- Lead (144 g/year, 80%).

This reflects the metal mobilisation of the exposed pit walls and nitrate contributions due to blasting residues.

SRX ELF Seepage: SRX ELF seepage is elevated for ten parameters:

- Arsenic (3.3 kg/year, 32%).
- Cobalt (111 g/year, 67%).
- Manganese (6 kg/year, 76%).
- Molybdenum (5.5 kg/year, 86%).
- Sulfate (6,600 kg/year, 47%).
- Antimony (24.5 kg/year, 96%).
- Selenium (1,248 g/year, 79%).
- Strontium (279.2 kg/year, 85%).
- Uranium (1.7 kg/year, 75%).
- Vanadium (868 g/year, 87%).

These results reflect the significant impact of the ELF on the pit lake.

Undisturbed Runoff: Runoff from undisturbed areas contributes modest but non-negligible loads for several parameters such as:

- Cu (47.9 g/year; 22%).
- Zn (82 g/year; 20%).
- Cr (15 g/year; 13%).

Page 59 MWM-S003-Rev2

• B (640 g/year; 7%).

Al (400 g/year; 7%).

• Sr (18.2 kg/year; 6%).

For most other elements, the contribution from undisturbed areas remains below 5%, indicating a generally minor role in overall contaminant loads.

Table 25: Average annual inflow loads to SRX Pit Lake.

PARAMETER	GW INFLOW	PIT WALL	RAINFALL	SRX ELF SEEPAGE	UNDISTURBED. RUN-OFF	TOTAL
Al (kg/yr)	0.96 (17.5%)	4.1 (74.4%)	0 (0%)	0.05 (0.9%)	0.40 (7.2%)	5.5
As (kg/yr)	3.8 (36.1%)	3.3 (31.8%)	0 (0%)	3.3 (31.6%)	0.06 (0.5%)	10.5
B (kg/yr)	5.2 (65.1%)	1.7 (20.6%)	0 (0%)	0.52 (6.4%)	0.64 (7.9%)	8
Co (g/yr)	30.1 (27.1%)	18.0 (16.2%)	0 (0%)	55.5 (49.9%)	7.5 (6.8%)	111
Cr (g/yr)	79.1 (69.8%)	18.0 (15.9%)	0 (0%)	1.2 (1.1%)	15.0 (13.2%)	113.3
Cu (g/yr)	47.5 (21.8%)	122.4 (56.2%)	0 (0%)	0 (0%)	47.9 (22.0%)	217.8
Fe (kg/yr)	2.3 (0.5%)	327.6 (71.2%)	0 (0%)	126.3 (27.4%)	3.9 (0.9%)	460.2
Mn (g/yr)	1,076 (21.8%)	504.1 (10.2%)	0 (0%)	2,998 (60.9%)	346.4 (7.0%)	4,924
Mo (kg/yr)	63.3 (1.7%)	828.1 (22.5%)	0 (0%)	2,769 (75.4%)	12.7 (0.3%)	3,673
NO3-N (kg/yr)	0.81 (0.1%)	1,440 (98.1%)	1.2 (0.1%)	26.1 (1.8%)	0.19 (0.0%)	1,468
Pb (g/yr)	31.6 (17.5%)	144.0 (79.7%)	0 (0%)	0.36 (0.2%)	4.6 (2.6%)	180.6
Sb (g/yr)	0.06 (0.5%)	0.97 (7.3%)	0 (0%)	12.2 (92.1%)	0.01 (0.1%)	13.3
Se (g/yr)	284.7 (29.5%)	9.0 (0.9%)	0 (0%)	624.2 (64.7%)	46.2 (4.8%)	964.1
SO4 (kg/yr)	1,629 (14.9%)	5,761 (52.8%)	3.7 (0.0%)	3,350 (30.7%)	161.7 (1.5%)	10,905
Sr (kg/yr)	0 (0%)	32.8 (17.2%)	0 (0%)	139.6 (73.3%)	18.2 (9.5%)	190.5
U (g/yr)	158.2 (11.2%)	381.6 (27.1%)	0 (0%)	849.9 (60.4%)	17.3 (1.2%)	1,407
V (g/yr)	79.1 (14.1%)	18.0 (3.2%)	0 (0%)	434.3 (77.5%)	28.9 (5.2%)	560.2
Zn (g/yr)	237.3 (59.9%)	72.0 (18.2%)	0 (0%)	5.0 (1.3%)	82.0 (20.7%)	396.3

5.5.2.4 CIT Backfill

The CIT Backfill Pit Void functions as a backfilled pit that temporarily stores water like a high-permeability reservoir and eventually overflows. It receives inflows from groundwater and CIT Backfill seepage, which together account for all PCOC loads. Rainfall is not part of the load balance as there is no direct precipitation to a pit lake surface, as it enters the system through the backfill material, as seepage.

The water quality results for selected parameters are shown in Figure 37 and Figure 38. Compared to the reference limits, most parameters are below the thresholds. Parameters that exceed the reference limits include Sb, As, Fe, Mo, U, Se, and Co. Other elements are below the reference limits.

Page 60 MWM-S003-Rev2




Figure 37. CIT Backfilled Void water quality results. Part 1 of 2.

Page 61 MWM-5003-Rev2




Figure 38. CIT Backfilled Void water quality results. Part 2 of 2.

The average inflowing loads for the CIT Backfill are shown on Table 24.

Groundwater Inflow: Groundwater is the primary contributor for five parameters:

Cu – 9.6 g/year (100%).

Page 62 MWM-5003-Rev2

- Pb 6.4 g/year (91%).
- Cr 16 g/year (86%).
- Zn 48 g/year (84%).
- Al 195 g/year (69%).

CIT Backfill Seepage: Seepage from the CIT Backfill dominates the load for the other 13 parameters as shown on Table 24. This pattern reflects significant mobilisation from within the backfill, due to oxidation of reactive materials and short-term solute release.

Table 26: Average annual inflow Loads to CIT Backfilled Void.

PARAMETER	CIT BACKFILL SEEPAGE	GW INFLOW	TOTAL
Al (g/yr)	43.6 (18.2%)	195.3 (81.8%)	238.9
As (kg/yr)	2.9 (79.3%)	0.77 (20.7%)	3.7
B (g/yr)	785.9 (42.6%)	1,060 (57.4%)	1846.0
Co (g/yr)	49.3 (89.0%)	6.1 (11.0%)	55.4
Cr (g/yr)	1.3 (7.5%)	16.0 (92.5%)	17.3
Cu (g/yr)	0 (0%)	9.6 (100%)	9.6
Fe (kg/yr)	111.9 (99.6%)	0.47 (0.4%)	112.4
Mn (kg/yr)	2.0 (90.4%)	0.22 (9.6%)	2.3
Mo (kg/yr)	2.2 (99.4%)	0.01 (0.6%)	2.2
NO3-N (kg/yr)	26.8 (99.4%)	0.16 (0.6%)	26.9
Pb (g/yr)	0.32 (4.7%)	6.4 (95.3%)	6.7
Sb (kg/yr)	8.0 (99.8%)	0.01 (0.2%)	8.0
Se (g/yr)	403.8 (87.5%)	57.6 (12.5%)	461.5
SO4 (kg/yr)	2,200 (87.0%)	329.8 (13.0%)	2,529
Sr (kg/yr)	103.8 (100.0%)	0 (0%)	103.8
U (g/yr)	586.9 (94.8%)	32.0 (5.2%)	618.9
V (g/yr)	283.7 (94.7%)	16.0 (5.3%)	299.7
Zn (g/yr)	4.4 (8.5%)	48.0 (91.5%)	52.5

5.5.2.5 Shepherds Creek (SC01)

SC01 is the proposed compliance monitoring location at the outlet of the Shepherds Creek catchment, which integrates flows from multiple sources, including the TSF, RAS Pit Lake, Shepherds ELF, CIT Backfill Pit Lake, WELF, SCK Fill, and several runoff areas. This location represents the combined load of all upstream activities within the catchment and reflects the cumulative impact of seepage and surface pathways.

During the Active Closure Phase, it is assumed all mine impacted waters are treated by the WTP (Process Flow, 2025; MWM, 2025d) and that active treatment continues until passive treatment system can be installed and achieve compliance with the proposed water quality closure criteria. The post-closure model intentionally excludes the active WTP to evaluate whether closure criteria can be met without it, and to determine for how long active treatment would be required if implemented.

A passive treatment system is included in the WLBM using removal efficiencies detailed on the *Water Treatment Study* (MWM, 2025d). Both untreated and treated cases are presented in the figures below

Page 63 MWM-S003-Rev2

to represent the impact of the passive treatment on mine-impacted waters and demonstrate the time period required for active treatment. The PCOC treatment efficiencies are shown in Table 25.

Table 27: Removal efficiencies for the passive treatment system.

PARAMETER	REMOVAL EFFICIENCIES (%)
Arsenic	99
Calcium ¹	-43.2
Magnesium	8
Aluminium	83.3
Iron	99.1
Nickel	97.9
Zinc	99.8
Manganese	86.4
Cadmium	85.2
Cobalt	98.4
Copper	85.6
Uranium	74
Vanadium	90
Sulfate	30
Cyanide	90
Nitrogen (Amm-N and NO3-N)	99
Other metals	98

A negative value means Ca increases following treatment.

Source: MWM (2025d).

The mine-impacted waters that are treated by the passive treatment system at SC01 include six components: TSF seepage, Shepherds ELF seepage, groundwater flow from the RAS Pit Lake (via the underground workings), overflow from the CIT Backfill, WELF seepage, and seepage from the SCK Fill.

Some sources are not considered to be captured by the treatment system and may contribute additional load downstream of the treatment system but aren't considered to be significant contributors to loads. These include the portion of CIT Backfill outflow that reaches SC01 via groundwater, as well as runoff from the CIT Backfill, Shepherds ELF, TSF, and SCK Fill.

The water quality results for selected parameters are shown in Figure 39 and Figure 40 for untreated and treated simulations. Compared to the surface water and groundwater quality limits, most parameters are below the thresholds. Parameters that exceed at least one of the water quality limits at SC01 include:

- Untreated: SO₄, NO₃-N, Sb, As, Co, Fe, Mo CN, Se, and Sr.
- After passive treatment:SO₄, Sb, and Mo.

Hence, active treatment is required for CN, SO₄, Sb, and Mo if no other water management option is applied. CN is expected to naturally (not included in the model) so performance monitoring should monitor the decay of CN. Active treatment would still be required for SO₄ up to year 35, Sb up to year 20, and Mo up to year 50.

Page 64 MWM-S003-Rev2




Figure 39. Yearly average water quality results at Shepherds Creek (SC01) treated and untreated scenarios. Part 1 of 2.

Page 65 MWM-5003-Rev2




Figure 40. Yearly average water quality results at Shepherds Creek (SC01) treated and untreated scenarios. Part 2 of 2.

The load balance for the untreated SC01 shows that TSF Seepage and Shepherds ELF Seepage are the primary contributors for most parameters, with some notable influence from RAS Pit Lake outflow and other sources. The load profile reflects the cumulative water quality impacts of seepage, runoff, and groundwater pathways from multiple facilities.

Page 66 MWM-5003-Rev2

TSF Seepage: TSF seepage is the dominant source for 9 parameters:

- CN (23.6 kg/year, 100%).
- As (138.9 kg/year, 73.7%).
- Pb (1,862 g/year, 71.6%).
- Zn (1,999 g/year, 57.1%).
- B (55.7 kg/year, 50%).
- Cr (429.6 g/year, 48.4%).
- Co (3,580 g/year, 48.3%).
- SO₄ (64,438 kg/year, 33.3%).
- Fe (1,037 kg/year, 29.0%).

Shepherds ELF Seepage: Shepherds ELF seepage has 8 parameters that are elevated:

- V (6,232 kg/year, 73.9%).
- Sb (165.2 kg/year, 72.2%).
- Se (8.5 kg/year, 68.0%).
- NO₃-N (1,525 kg/year, 64.7%).
- Mo (45.8 kg/year, 57.1%).
- Sr (1,387 kg/year, 53.8%).
- U (13.3 kg/year, 52.9%).
- Co (3,343 g/year, 45.1%).
- Mn (42.7 kg/year, 43.4%).

These two inflows collectively account for the majority of loading for nearly all parameters at SC01. In many cases, both sources contribute significantly to the same element. For example:

- Co is split between TSF seepage (3.58 kg/year, 48.3%) and Shepherds ELF seepage (3.34 kg/year, 45.1%).
- Fe receives notable contributions from both TSF seepage (1,037 kg/year, 29%) and Shepherds ELF seepage (905.5 kg/year, 25.3%).

RAS Pit Lake Groundwater Outflow: RAS Pit Lake outflow is the main contributor for two parameters:

- Al (16.2 kg/year, 48.7%).
- Cu (488.9 g/year, 53.8%).

The individual components that contribute to the overall load (t/yr) at SC01 are presented in Figure 41 and Figure 42. Results indicate that the key loads are derived from the TSF and Shepherds ELF.

Page 67 MWM-S003-Rev2




Figure 41. Stacked yearly average inflow load contributions to SC01 for selected parameters (Set 1 of 2).

Page 68 MWM-5003-Rev2




Figure 42. Stacked yearly average inflow load contributions to SC01 for selected parameters (Set 2 of 2).

Page 69 MWM-5003-Rev2

5.5.2.6 Rise and Shine Creek (RS03)

RS03 receives inflows from multiple sources, including natural run-off catchments (upper and lower), undisturbed areas (CC Creek), and the SRX Pit Lake Overflow (which includes the SRX ELF) and the SRX ELF run-off. Among these, SRX Pit Lake overflow is the dominant contributor for a wide range of parameters, indicating a substantial impact on downstream water quality.

The water quality results for selected parameters are shown in Figure 43 and Figure 44 for untreated and treated simulations. All PCOC are low and below the water quality limits except for As, Fe, and NO₃. Partial passive treatment of SRX Pit Lake overflow (8 L/s) reduces concentrations to below surface water and groundwater limits.

Page 70 MWM-S003-Rev2




Figure 43. Yearly average water quality results at Rise and Shine Creek (RS03). Part 1 of 2.

Page 71 MWM-5003-Rev2




Figure 44. Yearly average water quality results at Rise and Shine Creek (RS03). Part 2 of 2.

Primary Contributor to Water Quality at RS03: SRX Pit Lake Overflow

This inflow is the main source of loading for 18 parameters, and it has to be noted that the pit lake receives water inflows from the SRX ELF (seepage and runoff), highlighting its critical role in the downstream chemistry. Notable contributions include:

As: 10.5 kg/year (93.8%).

Page 72 MWM-5003-Rev2

- Fe: 457.2 kg/year (96.4%).
- NO₃-N: 1,184 kg/year (99.4%).
- Sb: 13.3 kg/year (94.5%).
- Mn: 4.9 kg/year (79.3%).
- SO₄: 10,855 kg/year (61%).
- Sr: 190.2 kg/year (75.2%).
- U: 1,404 g/year (64.4%).
- V: 560 g/year (76.9%).

It also supplies the highest loads for several other metals, such as Cu (217 g/year, 50.8%), Zn (395 g/year, 43.4%), and Al (5.5 kg/year, 51.1%), though in these cases, other inflows also contribute significantly.

Some parameters receive important secondary contributions from other sources, even though SRX Pit Lake Overflow remains dominant. These include:

- Boron (B): 8 kg/year (58.8%) from SRX Pit Lake, with 2.9 kg/year (21.6%) from the Clearwater Creek (C. Creek); 1.6 kg/year (11.4%) from Undisturbed Upper Runoff.
- Cr: 112.9 g/year (43.7%) from SRX Pit Lake, but 94 g/year (36.4%) from C. Creek.
- Zn: 495 g/year (43.4%) from SRX Pit Lake, with relevant contributions from Undisturbed Upper: 201 g/year (22%) and C. Creek: 271 (29.7%).

Whilst the pit lake dominates total mass loading, natural catchments and undisturbed areas also play a relevant role for some trace metals, especially for Cr and Zn.

Table 28: Average annual inflow loads to RS03.

PARAMETER	SRX ELF RUNOFF	SRX PIT LAKE OVERFLOW	C. CREEK UNDIST.	UNDIST. RUNOFF UPPER	UNDIST. RUNOFF LOWER	WELF RUNOFF	TOTAL
Al (kg/yr)	1.0 (9.3%)	5.5 (51.1%)	2.1 (19.3%)	0.97 (9.1%)	0.10 (0.9%)	1.1 (10.3%)	10.7
As (kg/yr)	0.13 (1.2%)	10.5 (93.8%)	0.17 (1.5%)	0.14 (1.3%)	0.11 (1.0%)	0.14 (1.3%)	11.2
B (kg/yr)	0.41 (3.0%)	8.0 (58.8%)	2.9 (21.6%)	1.6 (11.4%)	0.25 (1.8%)	0.45 (3.3%)	13.6
Co (g/yr)	3.2 (1.8%)	110.8 (63.5%)	35.3 (20.2%)	18.4 (10.6%)	3.3 (1.9%)	3.5 (2.0%)	174.6
Cr (g/yr)	3.2 (1.2%)	112.9 (43.7%)	94.2 (36.4%)	36.9 (14.3%)	7.7 (3.0%)	3.5 (1.4%)	258.5
Cu (g/yr)	6.5 (1.5%)	216.5 (50.8%)	72.3 (17.0%)	117.7 (27.6%)	6.0 (1.4%)	7.1 (1.7%)	426.1
Fe (kg/yr)	0.90 (0.2%)	457.2 (96.4%)	4.9 (1.0%)	9.6 (2.0%)	0.49 (0.1%)	0.99 (0.2%)	474.2
Mn (g/yr)	0.07 (1.2%)	4.9 (79.3%)	0.15 (2.4%)	0.85 (13.7%)	0.12 (2.0%)	0.08 (1.3%)	6.2
Mo (g/yr)	949.2 (16.5%)	3,668 (63.8%)	55.5 (1.0%)	31.2 (0.5%)	4.3 (0.1%)	1,044 (18.1%)	5,752
NO3-N (kg/yr)	2.6 (0.2%)	1,184 (99.4%)	1.6 (0.1%)	0.47 (0.0%)	0.11 (0.0%)	2.8 (0.2%)	1,191

Page 73 MWM-S003-Rev2

PARAMETER	SRX ELF RUNOFF	SRX PIT LAKE OVERFLOW	C. CREEK UNDIST.	UNDIST. RUNOFF UPPER	UNDIST. RUNOFF LOWER	WELF RUNOFF	TOTAL
Pb (g/yr)	1.2 (0.5%)	179.4	37.0	11.3 (4.9%)	3.3	1.3 (0.6%)	233.5
1 b (g/y1)		(76.8%)	(15.8%)		(1.4%)		
Sh (alur)	0.32	13.3 (94.5%)	0.07 (0.5%)	0.02 (0.2%)	0.01	0.35 (2.5%)	14.1
Sb (g/yr)	(2.3%)				(0.0%)		
Co. (alve)	1.6 (0.1%)	963.5	370.1	113.4	32.6	1.8 (0.1%)	1,483
Se (g/yr)		(65.0%)	(25.0%)	(7.6%)	(2.2%)		
COA (kakus)	3,035	10,855	141.8	397.0	20.5	3,337	17,786
SO4 (kg/yr)	(17.1%)	(61.0%)	(0.8%)	(2.2%)	(0.1%)	(18.8%)	
Cr (lealur)	4.3 (1.7%)	190.2	7.1 (2.8%)	44.7	1.8	4.8 (1.9%)	252.8
Sr (kg/yr)		(75.2%)		(17.7%)	(0.7%)		
11 (~, /, , , , ,	342.2	1,404	15.1 (0.7%)	42.5 (1.9%)	1.6	376.3	2,182
U (g/yr)	(15.7%)	(64.4%)		, ,	(0.1%)	(17.2%)	
\/ (a/\r)	3.2 (0.4%)	560.0	84.1	70.9 (9.7%)	6.5	3.5 (0.5%)	728.4
V (g/yr)	. ,	(76.9%)	(11.5%)	, ,	(0.9%)	, ,	
7n (a/ur)	6.5 (0.7%)	394.8	270.9	201.3	29.9	7.1 (0.8%)	910.5
Zn (g/yr)	. ,	(43.4%)	(29.7%)	(22.1%)	(3.3%)	, ,	

The individual components that contribute to the overall load (t/yr) at RS03 are presented in Figure 45 and Figure 46. Load derived from the SRX Pit Lake is the dominant source of PCOC.

Page 74 MWM-S003-Rev2




Figure 45. Stacked yearly average inflow load contributions to RS03 for selected parameters (Set 1 of 2).

No Cyanide (CN) is used in this catchment, so the CN load is zero.

Page 75 MWM-5003-Rev2




Figure 46. Stacked yearly average inflow load contributions to SC01 for selected parameters (Set 2 of 2).

Page 76 MWM-5003-Rev2

5.5.2.7 <u>Assessment SC01: Surface Water Quality Compliance</u>

Using yearly average concentrations at SC01 (both untreated and treated), a summary table (Table 27) was prepared to compare the effect of passive treatment against the water quality reference limits.

The following observations can be made:

- Always below the limit: Al, Cr, Cu, Mn, SO4, and Zn remained consistently below the limits both before and after treatment.
- Improved to below the limit after passive treatment: Co, CN, Sb, As, Mo, NO₃-N, and SO₄, shifted from exceeding the surface water (SW) limits in untreated conditions to being below the limit after treatment.

Table 29. Yearly average water quality (SC01) before and after passive treatment against the SW reference limits.

		% ¹ YEARS GREATER THAN THE SW LIMIT		
ELEMENT	STATUS	BEFORE	AFTER	
Со	Improved	100	0	
CN	Improved	100	0	
Sb	Improved	100	0	
As	Improved	100	0	
Мо	Improved	100	0	
NO3-N	Improved	31.5	0	
SO4	Always Below the Limit	0	0	
Al	Always Below the Limit	0	0	
Cu	Always Below the Limit	0	0	
Mn	Always Below the Limit	0	0	
Zn	Always Below the Limit	0	0	
Cr	Always Below the Limit	0	0	

^{1.} Percent is calculated on the total 200 year of the model.

Elements not assessed are Ni, Fe, Pb, U, Se, Sr, B, and V, as no surface water limits are defined.

5.5.2.8 <u>Assessment SC01: Groundwater Quality Compliance</u>

The water quality results at SC01 before and after passive treatment were screened against the groundwater quality limits (Table 28). Results indicated:

- Always below the limit: Al, Mn, Pb, Cu, B, Co, Zn, Cr, and CN.
- Improved elements to below the GW limit are: As, Fe, U, Sr, Se, NO3-N.
- Persistent elements that, whilst improved, still remain above the groundwater (GW) limit for a number of years: SO₄, Mo, and Sb.

Page 77 MWM-S003-Rev2

Table 30: Comparison of yearly averages for SC01 before and after passive treatment against the GW Limits. Percent is calculated on the total 200 years of the model.

	_	% ¹ YEARS GREATER	THAN THE GW LIMIT
ELEMENT	STATUS	BEFORE	AFTER
Мо	Persistent	100	13.5
SO4	Persistent	27	10.5
Sb	Persistent	100	1
As	Improved	100	0
Fe	Improved	100	0
U	Improved	35.5	0
Se	Improved	30	0
Sr	Improved	17	0
NO3-N	Improved	9.5	0
Mn	Always Below the Limit	0	0
Al	Always Below the Limit	0	0
Pb	Always Below the Limit	0	0
Cu	Always Below the Limit	0	0
CN	Always Below the Limit	0	0
В	Always Below the Limit	0	0
Со	Always Below the Limit	0	0
Zn	Always Below the Limit	0	0
Cr	Always Below the Limit	0	0

^{1.} Percent is calculated on the total 200 year of the model.

5.5.2.9 Assessment RS03: Surface Water and Groundwater Quality Compliance

For RS03, a comparison against both GW and SW limits is provided in Table 30 and Table 30. The results indicate that there are no exceedances after passive treatment.

Table 31: Comparison of yearly averages for RS03 before and after passive treatment against the SW Limits. Percent is calculated on the total 200 years of the model.

	_	% ¹ YEARS GREATER	THAN THE SW LIMIT
ELEMENT	STATUS	BEFORE	AFTER
NO3-N	Improved	15	0
Sb	Always Below the Limit	0	0
Со	Always Below the Limit	0	0
Мо	Always Below the Limit	0	0
SO4	Always Below the Limit	0	0
Al	Always Below the Limit	0	0
As	Always Below the Limit	0	0
Cu	Always Below the Limit	0	0
CN	Always Below the Limit	0	0
Zn	Always Below the Limit	0	0
Cr	Always Below the Limit	0	0

^{1.} Percent is calculated on the total 200 year of the model.

Page 78 MWM-S003-Rev2

Table 32: Comparison of yearly averages for RS03 before and after passive treatment against the GW Limits. Percent is calculated on the total 200 years of the model.

	_	% ¹ YEARS GREATER	THAN THE GW LIMIT
ELEMENT	STATUS	BEFORE	AFTER
As	Improved	99.5	0
Fe	Improved	99.5	0
Sb	Improved	54.5	0
Мо	Improved	31	0
SO4	Always Below the Limit	0	0
NO3-N	Always Below the Limit	0	0
Al	Always Below the Limit	0	0
Pb	Always Below the Limit	0	0
Cu	Always Below the Limit	0	0
CN	Always Below the Limit	0	0
U	Always Below the Limit	0	0
Se	Always Below the Limit	0	0
Sr	Always Below the Limit	0	0
В	Always Below the Limit	0	0
Со	Always Below the Limit	0	0
Mn	Always Below the Limit	0	0
Zn	Always Below the Limit	0	0
Cr	Always Below the Limit	0	0

^{1.} Percent is calculated on the total 200 year of the model.

5.5.2.10 Water Quality Compliance Summary: SC01 and RS03

A summary table of model exceedances (as a percent of years over the 200 years of the model) for SC01 after treatment and RS03 is shown in Table 31.

Table 33: Summary table of exceedances screened against reference surface water (SW) and groundwater (GW) limits for SC01 and RS03.

PARAMETER	SC01 - TREATED		RS03 - T	REATED
TAININETER	SW Limits	GW Limits	SW Limits	GW Limits
As	-	-	-	-
U	-	-	-	-
Со	-	-	-	-
SO ₄	-	10.5%	-	-
Мо	-	13.5%	-	-
Sb	-	1%	-	-
Fe	-	-	-	-
NO3-N	-	-	-	-
Cu	-	-	-	-
CN	-	-	-	-

Page 79 MWM-S003-Rev2

The following observations and findings summarise key water quality outcomes at monitoring points SC01 and RS03. They focus on the duration and extent of exceedances relative to groundwater and surface water limits.

Water quality findings at SC01:

- Groundwater limits are exceeded even after passive treatment for SO₄ (to Year 35), Mo (to Year 50), and Sb (to Year 20). For surface waters, all parameters are predicted to remain below the limits after passive treatment.
- Exceedances are linked to peak concentrations from Shepherds ELF seepage.

Water quality findings at RS03:

All PCOC are predicted to be below the groundwater and surface water quality limits after partial
passive treatment of the SRX Pit Lake overflow (8 L/s).

5.6 Scenario Modelling - Water Management Opportunities

Scenario modelling was undertaken to understand management opportunities.

5.6.1 Model Background

A PCOC load analysis for SC01 indicates that the dominant sources are the TSF seepage and Shepherds ELF seepage. It was noted that:

- Model analysis associated with minor inflows have negligible influence on SC01 water quality outcomes.
- Net percolation rates have a strong effect on the duration of active treatment using the WTP.

To evaluate water management options for the Shepherds ELF and TSF an additional scenario was modelled and compared to the base case model (NP20) presented in previous sections. This is an alternative management scenario in which the TSF and ELF seepage is redirected into the RAS Pit Lake to promote dilution and a generate a time lag before discharge, decreasing peak concentrations.

5.6.2 Model Results

Parameters that were above the groundwater limit for the NP20 base case scenario are shown in Figure 47 where it can be observed that Mo surpasses the GW limit in some years. Other results are presented in Figure 48 and Figure 49. Groundwater limits are used at SC01 to confirm that compliance can be achieved without dilution within the downgradient aquifer.

Diverting Shepherds ELF and TSF seepage to RAS Pit Lake results in lower peak concentrations at SC01. This is attributed to the pit lake providing dilution and a temporal load sink. A portion of the contaminant mass is retained within the pit, effectively delaying release and smoothing concentration peaks. By decreasing the peak concentrations, some of exceedances are avoided for SO₄, Mo, and Sb, although Mo still remains elevated over the yearly time steps.

Page 80 MWM-S003-Rev2




Figure 47. Scenarios results for parameters above the GW Limit for the base case scenario.

Page 81 MWM-5003-Rev2




Figure 48. Scenario model results at SC01. Part 1 of 2.

Page 82 MWM-5003-Rev2




Figure 49. Scenario model results at SC01. Part 2 of 2.

Page 83 MWM-5003-Rev2

6 SUMMARY AND RECOMMENDATIONS

6.1 Summary

The BOGP operational and post-closure assessment findings are summarised below.

6.1.1 Operational Phase Model Results

The Operational Phase calculations suggest the following:

- Water balance calculations suggest that the site will be in a water deficit condition up to Year 8. After this point, dewatering from satellite pits (i.e., SRX and to a lesser extent CIT) may push the site to a water surplus condition for the last few years of mine life without additional controls. Engineering controls (e.g., construct the water treatment plant prior to closure) are available to manage potential water surpluses, and can be evaluated during detailed design phases. Ongoing site water balance reconciliation of the site will be required to confirm water balance conditions remain in a water deficit condition.
- Based on mine features that will retain water on site and not be discharged to the receiving environment during operations, creek flows at SC01 are estimated to be reduced by approximately 17% on average at the full life of mine, while RS03 reduced by 13%. 7D MALF will reduce by 27% and 15% at SC01 and RS03, respectively.
- Interpretation of the mixing model results suggests surface water quality at SC01 and RS03 will
 remain below the proposed compliance limits for both surface and groundwater if groundwater
 is used for dust suppression.

6.1.2 Post-Closure Phase Model Results

The Post-Closure WLBM results suggest the following:

- Pit voids will fill with water and discharge MIW at average rates of approximately 6 L/s, 8 L/s,
 1.5 L/s, from the RAS Pit, SRX Pit, and CIT Pit, respectively. RAS Pit Lake will reach a stable condition at ~25 years, with SRX and CIT pits will do so in <5 years.
- Of the MWSFs, Shepherds ELF, using a net percolation rate of 20%, will have the highest average seepage rate of MIW of approximately 4 L/s, followed by the TSF seepage rate of approximately 2 L/s on average. SRX ELF, WELF, and SCK Fill all had seepage rates of approximately 0.5 L/s or less.
- Creek flows will increase, with average flows increasing by approximately 60% and 50% at Shepherds Creek (at SC01) and Rise and Shine Creek (at RS03), respectively. Low flow conditions also increased, showing 7D MALF increasing by approximately 530% and 280%, respectively. These increases are mainly attributed to:
 - The higher infiltration and NP rates of the ELFs resulting in more stable seepage hydrodynamics.
 - The storage and discharge water filled pit voids.

Page 84 MWM-S003-Rev2

- Without active water treatment, water quality findings for the base case model at SC01, based on yearly time steps indicate:
 - Groundwater limits are exceeded after passive treatment has been implemented for molybdenum (Mo) (to Year 50), SO₄ (to Year 35), and Sb (to Year 20).
 - o Surface water limits are not exceeded after passive treatment is implemented.
 - Exceedances, especially for SO₄ and Sb are related to peak concentrations from Shepherds ELF seepage. This indicates that for the base case model that active water treatment is required for up to 50 years.
- Water quality findings for the base case model at RS03 indicate:
 - No limits are exceeded after passive treatment.
 - Active treatment of MIW from SRX Pit and SRX ELF is not required.

6.2 Operational Management Recommendations

The following management recommendations are proposed for the Operations Phase:

- Prolonged wet years and changes of water balance assumptions (e.g., dust suppression water sources) may move the site into a water surplus condition. As such, detailed water balance modelling by mine stage and that includes rainfall variability is recommended to support detailed mine design and improve confidence in a water deficit being maintained. Development of an adaptive management process related to the site water balance would also support proactive management of identified risks.
- A site water balance reconciliation be completed regularly (e.g., annually or more frequent) to confirm water balance model results are appropriate, and/or make model updates to improve confidence in model results projected into the future.
- Pit sump water can potentially be used for dust suppression early on in mine life. An adaptive
 management process should be developed to proactively manage and respond if performance
 and/or compliance monitoring data suggests use of pit sump water may begin to provide a risk
 of non-compliance.
- Accordingly, plan for use of clean water sources (i.e., bore water) for dust suppression.
 Calculations suggests later in mine life that the use of pit sump water for dust suppression could have the potential to cause exceedance of compliant limits at SC01 and RS03.
- Other water management options include the early construction, during operations, of the water treatment plant if prolonged water surplus conditions eventuate.

6.3 Closure Management Recommendations

The following management recommendations are proposed for the active closure and post closure phases:

Active water treatment in the Shepherds Creek catchment through a WTP is required until
passive treatment systems can achieve the proposed water quality compliance limits at SC01.

Page 85 MWM-S003-Rev2

- Passive treatment of the SRX Pit Lake is required to achieve water quality limits at RS03. Noting
 that passive treatment is modelled at 8 L/s (average SRX Pit flow rate) with higher flows being
 untreated.
- Active and passive water treatment systems need to be developed through to a detailed design level:
 - o For the WTP, these studies need to be completed within the first few years of the mine commencing so that the technology is ready for operation and closure (if needed). Early design of the WTP would mean it is ready as part of any adaptive management process for water management.
 - Passive water treatment systems should be designed once the project is operational using actual water quality from the project mine domains to confirm the proposed approach is appropriate.
- The majority of PCOC loads originate from Shepherds ELF and the TSF; therefore, performance monitoring of both flow rates and water quality is recommended at these locations.
- Modelled outcomes indicate that active water treatment will be required for approximately 50 years. This duration reflects the time needed for concentrations of Mo, SO₄ and Sb to reduce following passive treatment to levels that comply with applicable surface water and groundwater quality limits for the base case model scenario.
- Other management option is diverting Shepherds ELF and TSF seepage to the RAS Pit Lake for dilution which according to the modelling, decreases concentrations of SO₄ and Sb to below GW limits. Mo can reach elevated concentrations at times, with exceedances occurring intermittently until year 50.
- Performance monitoring is necessary to confirm management mechanisms.

6.4 Forward Works

The following forward works are proposed:

- A transient operational site wide water and load balance model needs to developed prior to mine commencing to improve confidence in water accumulation or losses over time and water quality, particularly for seasonal dynamics. Such a model will support detailed design of the TSF.
- Additional ground investigations, groundwater monitoring, and detailed modelling will be required at the detailed design to confirm mine waste storage facility seepage collection systems will achieve anticipated collection requirements.
- The collection of performance monitoring data to improve model input data reliability is required, including:
 - o Water quantity and quality data from mine domains and water movement around the site.
 - o Water quantity and quality data as compliance locations.
 - Records of pit lake filling levels over time.

Page 86 MWM-S003-Rev2

- Once the mine is operational, collection of water quantity and quality data (obtained as part of performance monitoring) should be compared to the developed operational site wide water balance model periodically to confirm model results are reasonable. Model revisions and/or calibration may be required if a material difference is apparent.
- A cover system trial should be established early on in mine life to demonstrate that a NP of 20% of mean annual rainfall can be achieved. Such a study would provide confidence that water quality closure objectives can be achieved and support closure planning.
- Additional scenario modelling to understand opportunities and threats including:
 - o Higher rainfall.
 - Lower and higher net percolation rates.
 - o Variance to the proposed passive water treatment efficiencies.
- The closure WLBM needs to be updated once sufficient data are available to calibrate the model (e.g., cover system performance and net percolation rates; source terms; water treatment efficiencies, etc).

Page 87 MWM-S003-Rev2

7 **LIMITATIONS**

Attention is drawn to the document "Limitations", which is included in Appendix E of this report. The statements presented in this document are intended to provide advice on what the realistic expectations of this report should be, and to present recommendations on how to minimise the risks associated with this project. The document is not intended to reduce the level of responsibility accepted by Mine Waste Management, but rather to ensure that all parties who may rely on this report are aware of the responsibilities each assumes in doing so.

Page 88 MWM-S003-Rev2


8 REFERENCES

- Allen, R.G., Pereira, L.S., Raes, D. and Smith, M., 1998. Crop evapotranspiration-Guidelines for computing crop water requirements-FAO Irrigation and drainage paper 56. FAO, Rome, 300(9), p.D05109.
- ANZG, 2018. Australian and New Zealand guidelines for fresh and marine water quality. Australian and New Zealand Environment and Conservation Council, Agriculture and Resource Management Council of Australia and New Zealand.
- Chater, M., 2024a. Extension of synthetic rainfall time series, Bendigo Project. Technical memorandum prepared for Santana Minerals. Dated August 2024.
- Chater, M., 2024b. Estimated rainfall-altitude relationship, Bendigo Project Area. Technical memorandum prepared for Santana Minerals. Dated 4 April 2024.
- Engineering Geology Ltd (EGL), 2025. Bendigo-Ophir Gold Project Shepherds Tailings Storage Facility Technical Report. Prepared for Matakanui Gold Limited. Document reference: 9702. Dated 15 July 2025.
- Golder, 2011. Site Wide Surface Water Model Macraes Phase III Project. Technical report prepared for Oceana Gold (New Zealand) Limited. Document number 0978110562 R008vD. Dated April 2011.
- Goodman, R., Moye, D., Schalkwyk, A., Javendel, I., 1965. Ground-water inflow during tunnel driving. Eng. Geol. 2 (2), 39–56.
- Jensen, M.E. and Allen, R.G., 2016. Evaporation, evapotranspiration, and irrigation water requirements: Task Committee on Revision of Manual 70.
- Kōmanawa Solutions Ltd (KSL), 2024. Groundwater Modelling & Analysis for Mining Bendigo Ophir Gold Deposit. Matakanui Gold limited. RN: Z23002.1.
- Kōmanawa Solutions Ltd (KSL), 2025a. Rise & Shine Gold Project Surface Water & Catchment Existing Environment & Effects Assessment. Report for Matakanui Gold Limited. RN: Z24002BOG2-Rev2.
- Kōmanawa Solutions Ltd (KSL), 2025b. Bendigo Ophir Gold Mine Project Groundwater Existing Environment & Effects Assessment. Report for Matakanui Gold Limited. RN: Z24002BOG-Rev2.
- Macara, G. R., 2015. The Climate and Weather of Otago, NIWA Science and Technology Series No. 67, p. 44.
- Martinec, J., Rango, A., and Roberts, R., 2008. Snowmelt Runoff Model (SRM) User's Manual. Version 1.11. USDA Jornada Experimental Range, New Mexico State University.
- Matakanui Gold Ltd. (MGL), 2025. BOGP Water Management Plan. Rev 0. Dated 25 September 2025.
- McJannet, D, Hawdon, A, Baker, B, Ahwang, K, Gallant, J, Henderson, S & Hocking, A. 2019. Evaporation from coal mine pit lakes: measurements and modelling. Mine Closure 2019


Page 89 MWM-S003-Rev2

- Mine Water Management (MWM), 2025a. Net Percolation Assessment for the Proposed Bendigo-Ophir Gold Project Mine Waste Storage Facilities. Technical memorandum prepared for Matakanui Gold Limited. Document number: J-NZ0455-001-M-Rev2. Dated 1 August 2025.
- Mine Water Management (MWM), 2025b. Source Term Definition Report Bendigo-Ophir Gold Project. Technical report prepared for Matakanui Gold Limited. Document number: J-NZ0475-001-R-Rev0.
- Mine Waste Management (MWM), 2025c. Engineered Landform Water Quality Forecast Model Report Bendigo-Ophir Gold Project. Technical report prepared for Matakanui Gold Limited. Document number: J-NZ0457-002-R-RevB.
- Mine Waste Management (MWM), 2025d. Water Treatment Study Bendigo Ophir Gold Project. Mine waste Management report J-NZ0464-002-R-Rev0.
- Moon, J. and Fernandez, G, 2009. Effect of Excavation-Induced Groundwater Level Drawdown on Tunnel Inflow in a Jointed Rock Mass. Engineering Geology. (110) 33-42.
- Navarro-Valdivia, L., Weber, P.A., Tuck, J., Hillman, C., 2023. Natural Decay of ANFO-Derived Nitrate in Pit Lakes: Insights from the Golden Bar Pit Lake, Macraes Gold Mine, Otago, New Zealand. 2023. AuslMM New Zealand Branch Annual Conference. Available: https://www.ausimm.com/news-and-media/community-news/new-zealand-branch-2023-annual-conference-presentations--abstracts
- Oceana Gold (NZ) Ltd, 2020. Deepdell North Stage III Project Assessment of Environmental Effects
 Part 1. Dated 29 January 2020, 252 pp. https://www.orc.govt.nz/consents-and-compliance/current-notified-applications/oceana-gold-new-zealand-limited-rm20024/
- Parkhurst, D. L., & Appelo, C. A. J., 2013. Description of input and examples for PHREEQC version 3—a computer program for speciation, batch-reaction, one-dimensional transport, and inverse geochemical calculations. US geological survey techniques and methods, 6(A43), 497.
- QGIS Development Team, 2025. *QGIS Geographic Information System*. http://qgis.org. Accessed 01/2025.
- Ryder, G., 2025. Bendigo-Ophir Gold Project: Recommended water quality compliance limits for the Bendigo-Ophir Gold Project. Report for Matakanui Gold by Greg Ryder Consulting.
- Santana Minerals Limited (Santana), 2024. Bendigo-Ophir Pre-Feasibility Study. Report prepared by Santana Minerals Limited, 330 pp.
- Santana Minerals Limited (Santana), 2025. *Pit lake volume and surface area data file:*Ras_SRE_CIT_watervolume_10m_incr. Provided to MWM in excel format 03/02/2025.

Page 90 MWM-S003-Rev2



ARRDE\/IATIONI	EVDI ANATIONI
ABBREVIATION	EXPLANATION Assessment of anxionamental officials
AEE	Assessment of environmental effects
AEP	Annual exceedance probability
BOGP	Bendigo-Ophir Gold Project
CCreek	Clearwater Creek
CIL	Carbon-in-leach
CIT	Come in Time
ELF	Engineered Landform
GW	Groundwater
LOM	Life of mine
LOR	Limit of reporting
MAV	Maximum acceptable value
MIW	Mine-impacted water
MGL	Matakanui Gold Limited
MWM	Mine Waste Management Ltd
MWSF	Mine waste storage facility
NAF	Non-acid forming
NAPP	Net acid production potential
NP	Net percolation
PCOC	Potential constituents of concern
PET	Potential evapotranspiration
PSD	Particle size distribution
QA/QC	Quality assurance and quality control
ROM	Run of mine
Srex	SRX
Srex East	SRE
SW	Surface waters
TSF	Tailings storage facility
UG	Underground
WELF	West ELF
WLBM	Water and Load Balance Model
WTP	Water Treatment Plant



MEMORANDUM

то	Hamish McLauchlan, Santana Minerals
FROM	Mandy Chater, Hydrology Consultant ¹
DATE	19 February 2023
SUBJECT	Development of synthetic rainfall time series, Bendigo Project

Matakanui Gold Ltd requested that synthetic rainfall record be created, for the purpose of water balance assessment, water treatment considerations, and model development at their Bendigo Project site.

Also, an assessment of data availability for rainfall frequency analysis was requested. This is for design purpose. Comment was sought as to what work is required, and whether further data collection is needed to undertake the analysis.

This memo provides detail on the approach and outcomes, in fulfilment of these requests.

Contents:

- 1. Task Brief
- Collation of Data Inputs
- 3. Data Quality Assurance (QA)
- 4. Data comparisons and initial regressions
- 5. Finalized regression and consideration of wind direction
- Model script and generation of synthetic rainfall record
- Test model data against actual; reliability and shortcomings
- Applications of the synthetic data
- 9. Model refinement and data assessment for frequency analysis

Mandy Chater, MSc (Geography). 20+ years' experience in hydrological analysis and environmental science (NIWA, ECAN, West Coast Regional Council, Solid Energy/Bathurst Resources)

1 Task Brief

Long term rainfall estimates are required for the development of a GoldSim model, to be used for water management purposes at Matakanui Gold's 'Bendigo Project' site.

It was requested that "synthetic" rainfall record, at a daily interval, to be developed for a period of ten years or more. The actual length of synthetic record being dependent on the availability of data suitable for generating reliable rainfall estimates.

The availability of data for storm design purposes was also to be sought, and recommendations for further data collection and work around this be made.

The following documents the approach to developing the daily synthetic rainfall record.

2 Collation of Data Inputs

Figure 1 below shows the location of the Bendigo Project in the context of New Zealand's lower South Island. Figure 2, at a closer scale, shows the location of the three Matakanui Gold meteorological stations, for which rainfall record is to be extended. The terrain is obvious in its complexity, but also noteworthy is that the study area is at the most inland point of New Zealand, and therefore the climate has a far more continental tendency than other parts of the country.

A full suite of meteorological parameters is measured at each of the meteorological sites (Figure 2), at ten minute interval. The sites are telemetered using Harvest Technology cell phone communication and the data (unvalidated) can be easily downloaded from a user portal. Records begin in November 2022 and are available up to date.

In terms of extending the 14 months of record (available at the time of this analysis) all available recorded rainfall in the vicinity the Matakanui Gold gauges was considered. The availability of these surrogate (or predictor) sites was investigated via the following channels:

- <u>CliFlo</u> New Zealand's National Climate Database (managed by NIWA, and from which data can be downloaded by any subscribed user). The data pool here is large and varied. Many sites include only daily observations. Rainfall sites within a 50 km radius of the Matakanui Gold gauges, that had daily record or better, were initially considered. Records that were incomplete were disregarded. From here records were grouped by whether or not they overlapped with the Matakanui Gold record (therefore current). Those that didn't overlap could be used in a "secondary regression" (i.e regressed with a third site which did overlap with the Matakanui Gold record), but such gauges were given less preference due to inaccuracies introduced by using a secondary regression.
- Otago Regional Council (ORC): rainfall for water resource management purposes is widely collected by Regional Councils and not necessarily fed through to the CliFlo database. The Otago Regional Council (ORC) provides a very good online environmental database, and the data is easily accessible. Available ORC records were all from sites further from the Matakanui Gold gauges than the closest gauges found in CliFlo. However the ORC gauges record at ten minute interval, where many of the nearer CliFlo sites have only daily record. The ORC sites are therefore important where design rainfall estimates are concerned as for the relatively small catchment areas concerned, rainfall intervals of much less than one day will be relevant.
- <u>"Land Air Water Aotearoa" (LAWA):</u> No extra rainfall information, beyond that available on CliFlo and ORC websites, was found on the LAWA website.




Figure 1: Study location with respect to respect to lower half of New Zealand's South Island



Figure 2: Matakanui Gold Meteorological (Met) sites at the Bendigo Project area, flanked by Dunstan Mountains to the east, and the Clutha River Valley and Pisa Range to the north-west.

Table 1 details the CliFlo sites within 30 kilometres of the Lake Clearview Met Station, and highlights sites that are potentially most useful as predictor sites for generating synthetic records at the Bendigo Project site. Figure 3 gives the location of these potentially useful sites.

Table 2 details the ORC and Clif Flo sites that would be useful for gaining an understanding of the occurrence of extreme rainfall at the Matakanui Gold sites, as a means of providing design rainfall estimates for the latter. The location of the most promising gauges with short interval record can be seen in Figure 4.

Table 1: Sites with daily rainfall record in near vicinity to Matakanui Gold gauges - CliFlo database

Sites with daily rainfall record in near vicinity to Matakanui Gold gauges - CliFlo database

denotes potential primary regression site - data overlaps with Matakanui Gold records (Nov 2022 onwards).

denotes secondary site of interest due to vicinity or length of record

				Percent	Dist km
Agent Number	Name	Start Date	End Date	Complete	(from Lake Clearview Met)
5243	Bendigo 2	1/05/1978	31/05/1992	100	3.3
5242	Bendigo 1	1/01/1956	30/06/1979	100	3.6
5241	Mt Pisa Station	1/05/1908	31/05/1924	90	6.1
5233	Lochar	1/04/1947	31/03/1956	80	6.8
5234	Queensbury Ews	1/11/1978	31/05/1992	100	6.9
5236	Tarras	1/01/1902	31/07/1986	80	12.2
5528	Northburn	1/11/1978	31/05/1992	100	12.5
5228	Willowbank	1/11/1953	30/06/1963	90	16.1
26381	Cromwell Ews	6/04/2006	17/01/2024	100	16.7
5529	Cromwell 2	1/07/1984	31/07/2007	100	16.8
5526	Cromwell M.W.D.	1/06/1949	30/06/1985	100	16.8
5524	Cromwell Sub Stn	1/04/1976	31/10/2023	20	19.3
5530	Matakanui	1/05/1947	31/12/2021	100	19.6
5523	Ripponvale	1/09/1925	31/03/1961	100	20.5
5225	Luggate	30/06/1913	28/02/2006	90	22
5240	Upper Meg Power Stn	1/05/1953	31/05/2013	100	23.3
7426	Wanaka Aero Aws	30/04/1992	16/01/2024	100	24
5227	Lagoon Valley	1/01/1949	31/08/1964	100	25.4
5231	Merrivale	21/04/1953	31/05/1963	100	25.4
5224	Mt Barker	1/01/1967	31/01/2011	90	26.1
5232	Cardrona	1/01/1948	31/12/2014	100	26.2
5542	Clyde	1/08/1973	31/10/1977	90	26.4

				Percent	Dist km
Agent Number	Name	Start Date	End Date	Complete	(from Lake Clearview Met)
5229	Lindis Pass	1/11/1947	31/08/1948	100	27.4
5522	Waitiri Stn	1/01/1954	31/12/1968	70	28
5540	Bannockburn	1/07/1971	30/04/2018	90	28.7
5544	Ophir 2	1/04/1924	30/11/2023	90	28.9
5223	Wanaka	1/09/1927	31/08/1990	100	29.1
5230	Geordie Hill	1/05/1987	31/01/1990	80	29.1
5546	Ophir 1	1/11/1914	31/01/1931	20	29.2
5543	Clyde Dam	1/05/1978	30/06/2007	100	29.4
5535	Lauder Ews	20/08/1985	17/01/2024	100	29.6
43486	Lauder Raine Ews	29/04/2016	4/12/2023	100	29.6
5537	Lauder Flat	1/01/1945	30/11/2023	100	29.6
5249	Lauder Station	1/01/1987	31/01/1990	100	29.6
5541	Clyde, Fraser St	1/08/1896	30/09/1989	90	29.6
5216	Albert Town	1/12/1970	11/08/1972	100	29.6
41237	Wanaka Cws	29/10/2015	15/01/2024	100	29.7
5532	Lauder Pel	1/08/1981	31/05/1986	100	29.7
5531	Lauder	1/11/1947	31/03/1965	100	30
5217	Wanaka, Park Hq	5/09/1990	31/01/1994	100	30.1
39564	Clyde 2 Ews	25/05/2011	17/01/2024	100	30.8
5220	Maungawera	1/10/1915	30/04/1944	90	30.8
26567	Lauder 2	1/01/2000	31/03/2023	100	31.1

Table 2: Rain gauge sites with short duration record, for extreme event analysis, in near vicinity to Matakanui Gold gauges

Rain gauge sites with short duration rainfall in near vicinity to Matakanui Gold gauges

denotes the most likley useful sites, on the basis of vicinity/geography and length of record.

CliFlo data base

Agent Number	Name	Start Date	End Date	Altitude (m)	Dist km (from Lake Clearview Met)
26381	Cromwell Ews	5-Apr-06	7-Feb-24	213	14
41237	Wanaka Cws	28-Oct-15	7-Feb-24	331	28.9
39564	Clyde 2 Ews	17-May-12	7-Feb-24	170	30
5535	Lauder Ews	31-Dec-95	7-Feb-24	375	32.1
43486	Lauder Raine Ews	27-Apr-16	4-Dec-23	375	32.2
43904	Alexandra Ews	18-Apr-19	7-Feb-24	132	36.2
41331	Queenstown Ews	24-Feb-16	7-Feb-24	322	51.5
40257	Mt Larkins Ews	4-Nov-21	7-Feb-24	1900	64.9
18593	Ranfurly Ews	21-Nov-00	7-Feb-24	450	66.1
35098	Albert Burn	21-Apr-10	7-Feb-24	1280	68.1
18437	Middlemarch Ews	30-Aug-00	4-Feb-24	213	92.1

Otago Regional Council

Name	Start Date	End Date	Altitude (m)	Dist km (from Lake Clearview Met)
Cluden Stream at Stockyards	25/05/2021	current	357	19.1
Manuherikia at Tunnel Hill	18/03/2008	current	807	41.7
Lauder Creek at Lauder Basin	26/01/2022	current	1520	25.9
Ida Burn at Hills Creek	1/01/1988	current	580	41.4
Tairei at Ranfurly (NIWA)	21/11/2000	current	427	63
Poolburn at Merino Ridges	21/04/2009	current	440	39.3
Dunstan Peaks (ECAN)	26/08/2017	current	575	53.6




Figure 3: Potentially most useful predictor sites (red) for generating synthetic rainfall record at the Bendigo project site (Wanaka EWS excluded)



Figure 4: Location of the most promising sites for making rainfall intensity estimates (green) at the Bendigo Project site.

3 Data Quality Assurance (QA)

All relevant rainfall data was downloaded from the Matakanui Gold harvest portal and the NIWA climate data base. The Harvest data is available Pacific/Auckland or UTC time zones only (UTC being 12 hour behind NZ standard time). All climate station data is logged in NZ standard time (i.e does change for daylight saving) or UTC. Thus all records were downloaded in UTC as that was the only time unit to make the records temporally compatible.

The data was then loaded into Hilltop Software which provides tools for managing and analysing time series data.

The Matakanui Gold data was overplotted cumulatively and showed good overall agreement – with the higher gauges receiving slightly more rainfall as would be expected (Figure 5).

The cumulative comparison was then combed at a ten-day timestep to highlight any discrepancies in any of the records. Several discrepancies appeared, and, alongside the Cromwell EWS rainfall, were investigated. When considering temperature and wind direction data, it could be seen that most of the data discrepancies are likely to relate to snowfall at the higher elevation.

There remains one large unexplained anomaly in the Lake Clearview record on 21/22 February 2023, and this can be seen in Figure 5. Lake Clearview received 6.2mm of rainfall over this time, whereas adjacent sites Come in Time, Shreks, Cromwell, and Lauder received 43.8mm, 42.6mm, 38.6mm, and 57.6 mm respectively. This shortfall of rainfall at Lake Clearview was hugely anomalous compared to the rainfall relationships throughout the rest of the record. The storm event involved high air temperatures preceding a (cold) frontal passage, and a complicated wind pattern. At the time of writing this report comment is still being sought as to whether the gauge may have been blocked or similar at the time. However, as the relationships either side of the anomaly remain "as expected", it's unlikely there was recorder error at Lake Clearview on 21/22 February 2023, and so the discrepancy is in fact real. It is unknown with what frequency such a disparity would occur, but it is assumed rarely, in that it is not seen elsewhere in the record. Therefore it was chosen to treat the event as an outlier going forwards (essentially discard), as it is way outside the expected rainfall pattern.




Figure 5: Cumulative rainfall at the three Matakanui Gold gauges and Cromwell EWS, November 2022 to date

There was a large body of rainfall data downloaded from the Climate database. Data from the Climate database has already had checks undertaken, therefore it was decided only the surrogate data adopted in the final regressions needed to be combed for further quality assurance.

4 Data Comparisons and Initial regressions

Rainfall was compared, proportionally, between gauges to get an initial feel for the rainfall distributions. Box and Whisker plots nicely summarised where the rainfall records sit with respect to one another, in terms of amount and variability.

Firstly the three Matakanui Gold gauges, one for which we are wanting to extend rainfall record, were considered. Figure 5 shows the relationship of Lake Clearview and Shreks rainfall, as a proportion of that received at the middle rain gauge "Come In Time". The Clearview distribution has a median of 1, is well centred, and has few outliers. The "Shreks" median is naturally higher at 1.1; but with more variability shown in the data. Figure 5 suggests the "Come in Time" rainfall is actually very similar to that of Lake Clearview. This was confirmed when the cumulative rainfall plot in Figure 4 was started on 1/03/2023 (beyond the discussed February 2023 anomaly).

Of the three Matakanui Gold gauges the Lake Clearview site, is of most similar altitude to the potential surrogate sites Bendigo1, Bendigo2, Tarras, Cromwell, Matakanui, Lauder and Ophir (Figure 3). Further to that, in comparison to to the higher two gauges, the Lake Clearview gauge likely suffers less from snow, freezing, and wind (undercatch). Therefore, of the three Matakanui Gold rainfall sites Lake Clearview was chosen as the key "hinge" site - to regress with adjacent predictor sites. (Record extension at "Come In Time" and "Shreks" could be carried out subsequently - based on their close relationship with Lake Clearview).




Figure 5: Box and Whisker plots of comparative rainfall between the 3 Matakanui Gold Sites (refer Figure 2)

With the "hinge" site chosen, the most suitable surrogate sites for producing synthetic record at that hinge site were then considered. Cromwell and Lauder offered the two best options, due to their overlapping record with Lake Clearview (Table 1). Any other sites, bar Ophir2, would require 'secondary' regressions. Ophir2 and Lauder are of similar location, but with Lauder being an 'atmospheric research station' it was logical to use this (likely more reliable) data over the Ophir2 record. A general comparison showed that Lake Clearwater rainfall is about 118% of that received at Cromwell, and similar to slightly more of that that received at Lauder.

Figures 6 and 7 show initial regressions for Lake Clearview rainfall with Cromwell and Lauder, respectively, for the time the Lake Clearview site has been running. The regression for the "Lake Clearview versus Cromwell EWS" comparison is obviously tighter. Although Lake Clearview receives similar overall amounts of rainfall to Lauder, Figure 7 suggests that this rain is not necessarily concurrent. Noticeable also is the number of days where it was raining at Lauder but no, or little, rain occurred at Lake Clearview. The slope of the regression with Lauder is influenced (flattened) by the lower limit (zero) for rainfall, and a regression with Lauder would produce a number of 'false rain days' for Lake Clearview.

At this stage, as another check, "Shreks" Met was also regressed against Lauder. The "Shreks versus Lauder" regression did produce a stronger relationship than that of "Lake Clearview versus Lauder". However, the regression still contained more scatter than the "Lake Clearview versus Cromwell EWS" regression. This validated the use of that Lake Clearview as the key "hinge' site; and the use of Cromwell rainfall record for extending the of Lake Clearview record.




Figure 6: Initial regression between Lake Clearview (lowest Matakanui Gold site) rainfall and that at potential surrogate site <u>Cromwell EWS</u>.




Figure 7: Initial regression between Lake Clearview (lowest Matakanui Gold site) rainfall and that at potential surrogate site <u>Lauder EWS</u>

5 Finalised regression and consideration of wind direction

A QA check on the chosen surrogate rainfall site of Cromwell EWS was then undertaken. The Cromwell EWS rainfall was plotted cumulatively with concurrent data from NIWA's Lauder climate centre. The comparison showed a consistent relationship (Figure 8). This comparative plot was then fine combed at a 30-day interval. Although there were inevitable discrepancies, none of them would constitute as erroneous data. A script was run to check if there was any missing record across the entire dataset (i.e time step of over one hour between values), and none was found.




Figure 8: Cromwell EWS rainfall verses Lauder - April 2006 to January 2024

The regression between Cromwell EWS and Lake Clearview in Figure 6 shows perhaps a diverging into 2 different relationships, as rainfall increases. Rainfall in the area is typically pre-frontal (from the north-west quarter) or post-frontal (from the south/southeast quarter) in the area. Because of the way the different air streams interact with the topography it was hypothesised that the relationship between Cromwell and Lake Clearview rainfall could be dependent on these prevailing wind directions. (It is acknowledged that rainfall can also be associated with widespread low pressure systems over the South island – but the "directional" effect would remain). Wind direction data from Cromwell EWS was therefore used to isolate rainfall according to those predominant north-west and south-east quarter flows. The windrose for Cromell EWS is given in Figure 9. With consideration of windspeeds, and the channelling effects of the terrain surrounding Cromwell , "south-east quarter flows were actually considered as any direction from 100 through to 235 degrees , and "north-west" quarter flows any directions logged between 235 and 99 degrees.




Figure 9: Wind rose for Cromwell EWS Met Station. Wind directions between 100 and 235 degrees (as highlighted blue) being considered "south-east quarter" events. All other directions were considered "north-west quarter" events.

The Clearview versus Cromwell EWS paired data was coupled with both the "average daily" and the "end of day" wind direction at Cromwell EWS. Obviously there are limitations in categorising daily rainfall as "northwest" or "southeast", due to wind direction often changing within a day. It was found that the data split into two more discrete regressions when the subsets were defined by the "end of day" wind direction. Inevitably there were some outliers – and these were investigated. Three data points were removed where it was obvious that rain was borne from both the northwest and the southeast direction, within the same day.

Figure 10 shows the two direction dependent regressions. There is quite a lot of scatter across both regression and the application of the two regressions actually produce a similar long-term amount of rainfall as the single regression in Figure 6. However it is felt that, storm by storm, the match between modelled and actual rainfall will improve by applying the two different regressions. Due to its vicinity, and sheltering effects of the Pisa range, it is logical that the Clearview gauge, would receive more rainfall from southeast quarter than from north-west quarter storms - relative to Cromwell. This which is what the regressions reflect.




Figure 10: Cromwell EWS verses Lake Clearview daily rainfall, by wind direction

6 Model Script and generation of synthetic rainfall record

It can be seen in Table 1 that the Cromwell EWS rainfall site was a successor to Cromwell MWD and Cromwell2. Grid locations show all these sites to be within 100m of one another. There is overlap between each of the records.

Where they overlap, the Cromwell MWD and Cromwell2 records are exactly the same. However the Crowmwell2 rainfall proves to be slightly, though consistently, higher than that of Cromwell EWS. The Cromwell EWS rainfall data is collected via an automated gauge and the record is logged electronically. It is assumed that the Cromwell EWS data is the more accurate record of the two sites.

On this basis of the above was <u>it was decided to generate synthetic record for Clearview based on</u> <u>Cromwell EWS record alone, for the following reasons</u>:

- 18 years of reliable synthetic record could be produced from Cromwell EWS, where the brief requested that ten years or more of reliable daily record, for model and water management purposes, be developed.
- Cromwell EWS rainfall showed to have a good workable correlation to that Lake Clearview, but the record from Cromwell EWS was not consistent with the predecessor sites Cromwell MWD and Cromwell2.
- Wind direction record at Cromwell starts in April 2006, the same time as the Cromwell EWS record begins.

QA checks on the Cromwell wind direction data were at this point undertaken. A period of obviously erroneous data (anomaly 1), and a period of missing direction data (anomaly 2), were found. These anomalies were dealt with in the following way:

Anomaly 1: Wind vane stuck about 330 though to 30 degrees mid October to end November 2019 (yellow highlight Figure 11). On this basis of wind direction at other sites, most of the rainfall during this time was actually borne out of the north west quarter, so the "330 to 30 degree" record sufficed. There was one exception where rainfall was obviously from the south, so for the purposes of the model direction was changed to 180 degrees for 2 days (9th and 10th November, green highlight in Figure 11).

Anomaly 2: Missing wind direction record mid May to mid August 2020. On the basis of higher rainfall at eastern sites Matakanui and Lauder for the major rainfall events over this periods, it is assumed that the wind direction during rainfall events was predominately from the southeast quarter. There is one small event at the end of the period for which this is likely not the case but this will have minimal effect on the final synthetic record. The wind direction at Cromwell was therefore set to 180 degrees for this period for which there is missing wind direction record.




Figure 11: Period of erroneous wind direction data at Cromwell EWS mid October to end November 2019.

With all the check and balances carried on the data inputs a script was written to generate estimated rainfall at Lake Clearview from Cromwell EWS. The script considers the prevailing wind direction at any given time to adopt the applicable regression. As the model is run on hourly rainfall and wind direction data, it changes from one regression to another immediately as wind direction changes. Figure 13 shows the entire synthetic rainfall record for Lake Clearview, plotted cumulatively. The period for which actual Clearview record is available highlighted green. The synthetic rainfall record can be readily exported to excel at a daily timestep.




Figure 12: Graph confirming the direction function in the model is working and sensible.




Figure 13: Modelled rainfall data for Lake Clearview. Green highlight is period for which actual Like Clearview data exists.

7 Test model data against actual; reliability and shortcomings

The regression between Cromwell EWS and Lake Clearview rainfall showed the relationship to have some inconsistency, at a daily interval. This is not surprising given the complexity of the surrounding terrain and variable directions of rain bearing wind. So two separate relationships were fitted to the data, according to wind direction, to try and alleviate some of this temporal inconsistency. It was opted not to incorporate other adjacent gauges in a multiple regression approach, as such a model would still be specific to wind direction, would be harder to replicate, and shortcomings in the model output would be harder to account for. Cromwell EWS was used over the next most applicable predictor site, Lauder, due the daily relationship with Lauder being more inconsistent than with Cromwell. With the "Cromwell EWS" regressions then applied, there are number of ways we can test the model output displayed in Figure 13:

1. Overplot of modelled rainfall at Clearview with actual recorded data:

Figure 14 shows the modelled against actual record from November 2022, and Figure 15 from 1st March 2023, so to exclude the February 2023 outlier event. The comparison is good, but obviously complicated by the February 2023 outlier. Modelled rainfall is significantly more than actual in Figure 14, and slightly less than actual in Figure 15. As the February 2023 was appears to be far outside the expected norms (as detailed in Section3), little weight was given to matching the modelled record to this event. The model versus actual rainfall match in Figure 15 is considered a better measure of the model accuracy.




Figure 14: Modelled cumulative rainfall at Lake Clearview (black) with actual recorded data (brown) for the entire period there is concurrent data. (includes large rainfall anomaly in February 2023)




Figure 15: Modelled cumulative rainfall at Lake Clearview (black) with actual recorded data (brown) from 1/03/2023 to January 2024 – to exclude the large, likely misleading, anomaly in February 2023.

2. Regional comparison of average annual rainfall for Lake Clearview synthetic record with other sites in the vicinity, (to ensure the synthetic record is sensible with respect to location and altitude)

Figure 16 uses Box and Whisker plots to compare actual Lake Clearview rainfall, with that from gauges in closest vicinity. This is done the basis of each gauge's relationship to Cromwell. Cromwell record spans over a long time, and so overlaps with all these gauges at different points in time. It is acknowledged here that there is a slight disparity between the current Cromwell EWS site and the former Cromwell sites, but the below comparison is still considered useful. Figure 16 suggest that in the longer term we would expect Lake Clearview cumulative rainfall (dark green) to be less than Tarras and Matakanui, similar to Bendigo 1 (the closest gauge to Clearview), and more than Bendigo2 and Lauder.




Figure 16: Box and Whisker plots of rainfall in the vicinity if Lake Clearview, expressed as a proportion of that received at in Cromwell.

The mean annual rainfall for the predicted Clearview record (2006 to 2024) is consistent in rank, to that which is expected (Table3). Therefore the model, over time, is not generating bulk rainfall totals at Lake Clearview that are inconsistent with adjacent sites. Where Figures 14 and 15 compared the modelled rainfall against actual, the comparison in Table 3 validates the 18 years of modelled rainfall in a more regional type context.

Table 3: Mean annual rainfall for gauges within vicinity of Lake Clearview.

	Rainfall (mm)	Altitude:
Cromwell EWS	394	213m
Bendigo2	418	210m
Bendigo1	445	213m
Lauder EWS	452	375m
Predicted Lake Clearview (2006 to date)	463	340m
Tarras	472	280m
Matakanui (windward)	516	338m

Analysis of individual storm events should show the modelled data to be aligned with actual lake Clearview data.

This often was the case, but for some rainfall events the difference between modelled and actual was quite significant. This of course reflects the scatter of data points around the relationship used. This needs to be recognised as one of the shortcomings of the model - it replicates rainfall at a monthly and annual interval well, but cannot-be-assumed-to-be-100% accurate day by day. In terms of water management outcomes the model provides a robust estimate of the rainfall input into the catchment over time. Inaccuracies at a daily timestep must be assumed. However the inaccuracies are not considered positively or negatively biased (Figure 17)




Figure 17: Millimetre difference between predicted and actual Lake Clearview rainfall.

8 Application of the synthetic data

The modelled data has been generated in Hilltop software at an hourly timestep and can be exported and supplied at any interval greater than this. It represents at-site daily rainfall estimates from 2006 to date at the Lake Clearview recorder site.

The estimate of catchment wide rainfall over the entire area of the Bendigo Project site is beyond the scope of this report. To date no delineation of the mine catchment area, and that area which is requiring water treatment, has been provided. However the Lake Clearview gauge shows a solid relationship to the higher two gauges ("Come In Time" and "Shreks"). Thus extrapolation of the synthetic Lake Clearview record across the entire catchment would be viable, and reasonably accurate.

It is noted here that the record from nearby Bendigo1 (see Figure 3) appeared to be closely aligned to that of Lake Clearview, albeit perhaps slightly less. Bendigo 1 record, which spans from 1956 to 1979, may be quite useful in terms of indicating likely number of annual rain days, rainfall variability etc. Climate change considerations would need to be kept at the forefront here though.

Unfortunately as only at a daily timestep the Bendigo1 record wouldn't be overly useful for extreme rainfall analysis, as storm durations of 12 hours or less are likely the most relevant with the small catchment area concerned.

9 Model refinement and data assessment for frequency analysis.

The predicted rainfall record for Lake Clearview can be further validated as more actual rainfall for Lake Clearview is collected. Documenting any site visits, issues with the gauge, change of calibration etc would be very useful. Then data can be more easily validated, and there would be better grounds for including or excluding outlier data. It may be that model could be improved by including more regressions based around wind direction; but it's questionable how many gains would be made by doing so.

The brief for this project also requested that a data assessment be made for storm analysis and design purposes at the Bendigo Project site. At the moment there is insufficient rainfall record to carry out rainfall frequency analysis directly on the Lake Clearview, "Come In Time" or "Shreks" rainfall record. At least ten years of data is really required here. However, there are other sites in the region that could be used to normalise the rainfall intensities that have been recorded thus far at the Matakanui Gold gauges. The location of these gauges can be found in Figure 4. Normalised estimates of rainfall intensity and frequency could still only be considered "indicative", although the reliability of the estimates would improve as time goes on.

There are no further data requirements for storm design estimates, as the catchment is already well monitored. However an assessment of rainfall "concentration times", using the current Matakanui Gold rainfall and flow data, is needed. By doing so intensity /frequency estimates can be made for durations that are likely to be the most damaging to infrastructure.

MEMORANDUM

то	Hamish McLauchlan, Santana Minerals
FROM	Mandy Chater, Hydrology Consultant
СС	Ryan Burgess
DATE	4 th April 2024
SUBJECT	Estimated rainfall-altitude relationship, Bendigo Project Area

Matakanui Gold Ltd requested that a relationship between rainfall and altitude at their Bendigo Project Area be established. This is for the purpose of integrating rainfall over entire catchment areas, and so requiring rainfall estimates for areas beyond the vicinity of the actual gauges.

A relationship has been established based on rainfall from the 3 Bendigo project gauges, and on the Otago Regional Council's Cluden and Lauder Basin gauges for extending to higher altitudes.

In November 2022 three automated rain gauges were established in the Bendigo Project Area. Work has already been undertaken to create an estimated ten-year daily rainfall record for the lowest gauge (Lake Clearview). The likely expression of this ten year rainfall higher up in the catchment can be established from concurrent data for the 3 Bendigo gauges; and for the very highest portion of the catchment through the relationship between the nearby Cluden (357m) and Lauder Basin (1502m) gauges, which are run by Otago Regional Council. See Figure 1 for gauge locations.

Regression analysis showed that on a daily timestep the rainfall relationship between the respective Bendigo sites in inconsistent. The regressions tend to be clustered by non-rainfall days, and are susceptible to days where there is only rainfall at one site, or times when rain may fall as snow. Also, it could be seen that the temporal distribution of rainfall is inconsistent. Particularly, longer term rainfall totals at the higher sites tend to depend on a few anomalous storms where the rainfall at altitude is substantially higher (as opposed to a relationships which is constant across all rainfall events).

To establish the overall rainfall relationship between the respective Bendigo sites, monthly and annual running rainfall totals were calculated, to step away from the daily and weekly anomalies. Even monthly running totals were reasonably volatile, when compared to one another, still being affected by the daily inconsistencies discussed above. Therefore annual running total rainfall calculations were utilised. The annual running totals excluded the 21st and 22nd February 2023 record. Over these days all gauges in the region recorded significant rainfall (45mm+), but Lake Clearview only received 6mm. With its' inclusion, this event dominated the subsequent ratio calculations for an entire year, and thus detracted from the likely rainfall relationships. The annual running rainfall totals for the 3 Bendigo sites are shown in Figure 2. The Shreks and "Come In Time" running totals are then expressed as a portion of the Lake Clearview running total in Figure 3.

The median value of the Shreks/Lake Cleaview running total is 1.11, and the median value for "Come In time"/"Lake Clearview" running total is 1.01. Encouragingly these values are very similar to the monthly running total calculations – where (since 1 April 2023) the median value for the Shreks/Cleaview ratio is 1.11 and the median value for the "Come In time"/Clearview is ratio 0.98. Being only 135m higher than Lake Clearview, the "Come In Time" gauge appears to receive little if any additional rainfall. Being 413m higher, the Shreks gauge shows a definite increase in rainfall rates.




Figure 1: Location of Bendigo Project gauges, along with Otago Regional Council's "Cluden" and "Lauder Basin" gauges. The Bendigo Project catchment area extends to 950m.




Figure 2: Annual running rainfall totals for 3 Bendigo project gauges.




Figure 3: Shreks and "Come In Time" running annual rainfall totals, expressed at a proportion of Lake Clearview running annual rainfall total.

With the Cluden rain gauge (357m) being of very similar height to that of Lake Clearview gauge (540m), it could be compared to the much higher Lauder Basin gauge as way of extending the rainfall-altitude relationship above the Shreks gauge (753m). Cluden and Lauder Basin gauges are located about 18km to the north-east of the Bendigo gauges, but still within the Dunstan Mountain range. There is likely some disparity in the Cluden-Lauder Basin rainfall relationship, to that in the Bendigo Project Area, due to localised topographic effects. However the Cluden to Lauder Basin relationship is only needed to help to extend the relationship from Shreks gauge to the top of the Bendigo project catchment area (950m) – so is considered useful in this case.

The same annual and monthly running total approach was taken – with Lauder Basin then being expressed as a proportion of Cluden. The respective median values of those comparisons were 1.51 and 1.58. The traces did show more fluctuation, which is to be expected due to the larger altitudinal difference, and the sites being offset horizontally but about 5km. For this reason daily rainfall correlation was also considered. In this snowfall was obvious by a number of days in winter where rainfall occurred at Cluden not at Lauder Basin. June to September months were removed, along with non-rainfall days and the correlation was repeated. The paired data showed a lot of scatter, but a fitted linear regression indicated Lauder basin rainfall to be approximately 1.198 times that of Cluden. It is thought here that, again, a few large isolated storms have a large bearing on the overall totals received at Lauder Basin – explaining the lower ratio (to Cluden) produced by daily regression.

Of these 3 separately derived ratios the highest (1.58) and lowest (1.198) were added to the plot in Figure 4, along with an average value of 1.389. This was done to support (or otherwise) a linear fit through the Bendigo Project data alone (Clearview, Come In Time and Shreks). The polynomial curve, fitted through all the available data points, was used to calculate a likely amount of rainfall at ridgeline (950m). This is calculation is shown as a green dot in Figure 4 and is fairly consistent with linear regression at 950m.

It is recommended that that the polynomial equation in Figure 4 be adopted as a means of calculating rainfall at different altitudes across the Bendigo Project area. Due to storm variability the relationship cannot always be considered accurate for a daily or lesser intervals.




Figure 4: Estimated rainfall-altitude relationship in the Bendigo project area.

MEMORANDUM

ТО	Hamish McLauchlan, Santana Minerals
FROM	Mandy Chater, Hydrology Consultant ¹
DATE	August 2024
SUBJECT	Extension of synthetic rainfall time series, Bendigo Project

Synthetic rainfall for the Bendigo 'Lake Clearview Site" has been extended back to 1949. This follows an initial extension of the data back to 2006 using rainfall and wind direction from "Cromwell EWS". The procedure for this initial extension is documented in "Development of a synthetic rainfall database at Bendigo".

The extension back to 1949 uses slightly less reliable rainfall inputs, and does not consider wind direction like the "back to 2006" extension. However, comparison with long term rainfall records in the region indicate the synthetic rainfall back to 1949 is sensible, and consistent with patterns at other gauges. This is especially where monthly or annual rainfall is concerned. Predicted rainfall on any given day though has less reliability.

This memo details how the record was extended back from 2006 to 1949, and builds on the detail already supplied the "Development of a synthetic rainfall database at Bendigo" memo.

^{1.} Mandy Chater, MSc (Geography). 20+ years' experience in hydrological analysis and environmental science (NIWA, Environment Canterbury, West Coast Regional Council, Solid Energy/Bathurst Resources)

1 Data Inputs

Figure 1 and Table 1 below recap the use of Cromwell rainfall for creating synthetic rainfall data at Lake Clearview; based on vicinity and data availability.

The initial extension was limited back to 2006 only for the following reasons;

- 18 years of reliable synthetic record could be produced from Cromwell EWS, where the brief requested that ten years or more of reliable daily record, for model and water management purposes, be developed.
- Cromwell EWS rainfall showed to have a good workable correlation to that at Lake Clearview, but the
 record from "Cromwell EWS" was not consistent with the predecessor sites "Cromwell MWD" and
 "Cromwell 2".
- Wind direction record at Cromwell starts in April 2006, the same time as the Cromwell EWS rainfall record begins.

With a longer length of record now requested, it was chosen to continue with the use of Cromwell rainfall as a surrogate, but the points on the availability of wind direction data, and the inconsistency between the Cromwell gauges, needed to be addressed.

The 2006 to 2023 synthetic rainfall data was generated from 2 regressions - which were applied to the Cromwell data depending on wind direction. The slope of the regressions proved to be different depending on storm direction, so the use of the wind direction allowed rainfall to be supposedly predicted with better accuracy (on a day to day basis). The regression in Figure 2, which is on <u>all</u> "Cromwell EWS versus Lake Clearview" daily rainfall (so no storm direction consideration), has a slope of 1.1975. The slope of the south-east storm regression was 1.310 and of the north-west storm regression was 1.062. Therefore the application of the "all data" slope of 1.1975 did produce overall rainfall totals similar to those produced by the two "direction dependent" regressions. So for the purpose of deriving rainfall totals it was deemed that excluding the direction component was appropriate; but recognising that the predicted record prior to 2006 was likely to be less accurate on a day to day basis.

A relook at the rainfall data confirmed the inconsistency between the Cromwell EWS and Cromwell 2 rainfall data – where they overlap (April 2006 to July 2007). Grid locations show the <u>Cromwell MWD</u>, <u>Cromwell 2</u> and <u>Cromwell EWS</u> sites to be within 100m of one another. As it is available at hourly time steps, the Cromwell EWS (electronic weather station) data is obviously from an automated gauge; whereas MWD and Cromwell 2 data is very likely from manual daily readings. For this reason, the Cromwell EWS data is considered the more accurate record. (The Cromwell 2 and earlier Cromwell MWD data, where they overlap, is virtually the same)

Figure 3 below expresses the Cromwell EWS rainfall as a proportion of Cromwell 2 – showing the former to read slightly lower than the latter most of the time. The largest discrepancies are for daily rainfall less than 3mm, where the discrepancy is inflated and not of great relevance from a water resource point of view. However, even for the larger events there is a bias in the data comparison. This bias needed to be addressed to make a continuous surrogate dataset, to which the Cromwell EWS V Lake Clearview regression could then be applied. <u>The Cromwell 2 and Cromwell MWD rainfall record was therefore multiplied by 0.9</u> – as this correction resulted in the total Cromwell 2 data matching the total Cromwell EWS data – for the period which they overlap.




Figure 1: Gauges that were considered for the initial development of "Lake Clearview" synthetic rainfall record.

Table 1: Sites with daily rainfall record in near vicinity to Bendigo Project gauges - CliFlo database

denotes potential primary regression site - data overlaps with Matakanui Gold records (Nov 2022 onwards),
denotes secondary site of interest due to vicinity or length of record

				Percent	Dist km
Agent Number	Name	Start Date	End Date	Complete	(from Lake Clearview Met)
5243	Bendigo 2	1/05/1978	31/05/1992	100	3.3
5242	Bendigo 1	1/01/1956	30/06/1979	100	3.6
5241	Mt Pisa Station	1/05/1908	31/05/1924	90	6.1
5233	Lochar	1/04/1947	31/03/1956	80	6.8
5234	Queensbury Ews	1/11/1978	31/05/1992	100	6.9
5236	Tarras	1/01/1902	31/07/1986	80	12.2
5528	Northburn	1/11/1978	31/05/1992	100	12.5
5228	Willowbank	1/11/1953	30/06/1963	90	16.1
26381	Cromwell Ews	6/04/2006	17/01/2024	100	16.7
5529	Cromwell 2	1/07/1984	31/07/2007	100	16.8
5526	Cromwell M.W.D.	1/06/1949	30/06/1985	100	16.8
5524	Cromwell Sub Stn	1/04/1976	31/10/2023	20	19.3
5530	Matakanui	1/05/1947	31/12/2021	100	19.6
5523	Ripponvale	1/09/1925	31/03/1961	100	20.5
5225	Luggate	30/06/1913	28/02/2006	90	22
5240	Upper Meg Power Stn	1/05/1953	31/05/2013	100	23.3
7426	Wanaka Aero Aws	30/04/1992	16/01/2024	100	24
5227	Lagoon Valley	1/01/1949	31/08/1964	100	25.4
5231	Merrivale	21/04/1953	31/05/1963	100	25.4
5224	Mt Barker	1/01/1967	31/01/2011	90	26.1
5232	Cardrona	1/01/1948	31/12/2014	100	26.2
5542	Clyde	1/08/1973	31/10/1977	90	26.4

				Percent	Dist km
Agent Number	Name	Start Date	End Date	Complete	(from Lake Clearview Met)
5229	Lindis Pass	1/11/1947	31/08/1948	100	27.4
5522	Waitiri Stn	1/01/1954	31/12/1968	70	28
5540	Bannockburn	1/07/1971	30/04/2018	90	28.7
5544	Ophir 2	1/04/1924	30/11/2023	90	28.9
5223	Wanaka	1/09/1927	31/08/1990	100	29.1
5230	Geordie Hill	1/05/1987	31/01/1990	80	29.1
5546	Ophir 1	1/11/1914	31/01/1931	20	29.2
5543	Clyde Dam	1/05/1978	30/06/2007	100	29.4
5535	Lauder Ews	20/08/1985	17/01/2024	100	29.6
43486	Lauder Raine Ews	29/04/2016	4/12/2023	100	29.6
5537	Lauder Flat	1/01/1945	30/11/2023	100	29.6
5249	Lauder Station	1/01/1987	31/01/1990	100	29.6
5541	Clyde, Fraser St	1/08/1896	30/09/1989	90	29.6
5216	Albert Town	1/12/1970	11/08/1972	100	29.6
41237	Wanaka Cws	29/10/2015	15/01/2024	100	29.7
5532	Lauder Pel	1/08/1981	31/05/1986	100	29.7
5531	Lauder	1/11/1947	31/03/1965	100	30
5217	Wanaka, Park Hq	5/09/1990	31/01/1994	100	30.1
39564	Clyde 2 Ews	25/05/2011	17/01/2024	100	30.8
5220	Maungawera	1/10/1915	30/04/1944	90	30.8
26567	Lauder 2	1/01/2000	31/03/2023	100	31.1




Figure 2: Regression between Lake Clearview and Cromwell EWS rainfall (All data)




Figure 3: Cromwell EWS rainfall expressed as a proportion of Cromwell2 rainfall (for overlapping data, April 2006 to July 2007)

2 Data Quality Assurance (QA)

A QA check on Cromwell2 and Cromwell MWD was undertaken across their length of record. Rainfall from these stations was plotted cumulatively with concurrent data from Tarris, Matakanui and Lauder Flat. The comparison showed consistent relationships (Figures 4 and 5). The comparative plots were then fine combed at a 6-month interval. Although there were inevitable discrepancies, none of them would constitute as erroneous data. A script was run to check if there was any missing record across the entire dataset (i.e time step of over one day between values). A few missing days were found at Cromwell 2 - but by which time the gauge was running concurrently with Cromwell EWS.

The QA check incidentally highlighted quite a lot of missed daily readings at the other comparative sites (Lauder Flat and Tarras). This further validates the continued use of Cromwell data - being from a gauge that appears to have been was read very consistent by staff at Ministry of Works and Development, and its' successors.




Figure 4: Cromwell MWD rainfall plotted cumulatively with Tarras and Lauder Flat (a period of missing record at Lauder Flat in 1981 presents as a flat line)




Figure 5: Cromwell2 rainfall plotted cumulatively with Matakanui and Lauder Flat

3 Generation of synthetic rainfall record

With the QA checks proving Cromwell data back to 1949 to be complete record, the regression slope of 1.1975 was applied to the "Cromwell MWD x 0.9" and "Cromwell 2 x 0.9" data - to generate estimated daily record for Lake Clearview. The predicted records for Lake Clearview were then amalgamated into one continuous data record. Record generated from Cromwell EWS was used as a priority over that generated from Cromwell 2 (for the period that both gauges were running); and the record derived from Cromwell EWS was that using the 2 different regressions dependent on wind direction (April 2006 to 2023)

Figure 6 shows the entire synthetic rainfall record for Lake Clearview, plotted cumulatively. This synthetic rainfall record can be readily exported to excel at a daily timestep, or greater.

Table 3 shows there has been little change in the mean annual rainfall of the predicted data whether the initial 2006 to 2023, or the extended 1950 to 2023 record is used. Lauder Flat, like "Clearview predicted", also produces a lower mean annual rainfall value using the 1950 to 2023 record. (That trend at Matakanui is the opposite, but being windward to southeast storms Matakanui may not be representative of trends at Lake Clearview).

Ten-year return period estimates of annual rainfall minima, calculated from the two respective lengths of record, were found to be similar. However annual rainfall maxima results did show a bit of difference (specifics beyond the scope of this memo). What is noticeable is the larger variability in annual rainfall, at Cromwell, and so in the Lake Clearview predicted record, since about the mid 1990s. See Figure 7.




Figure 6: Modelled rainfall data for Lake Clearview 1949 to 2023

Table 3: Mean annual rainfall for gauges within vicinity of Lake Clearview.

Mean annual rainfall for gauges within vicinit	<u>ty of Lake Clearview:</u>	
	Rainfall (mm)	Altitude:
Cromwell EWS	394	213m
Bendigo2	418	210m
Bendigo1	445	213m
Lauder EWS	452	375m
Predicted Lake Clearview (2006 to 2023)	463	340m
Predicted Lake Clearview (1950 to 2023)	450	340m
Matakanui (windward)	516	338m




Figure 7: Annual Lake Clearview rainfall estimates from successive Cromwell gauge sites.





Figure 8: Annual Lake Clearview rainfall estimates from successive Cromwell gauge sites, with adjacent gauges at Lauder






Figure 1: Calculated alkalinity concentrations for SC01. Note Bore water and pit sump water dust suppression have the same source term.




Figure 2: Exceedance probability – alkalinity in SC01.




Figure 3: Top 10% exceedance probability for alkalinity in SC01.




Figure 4: Calculated alkalinity concentrations for RS03. Note Bore water and pit sump water dust suppression have the same source term.




Figure 5: Exceedance probability – alkalinity in RS03.




Figure 6: Top 10% exceedance probability for alkalinity in RS03.




Figure 7: Simulated calcium concentrations in SC01 for bore water and pit water dust suppression scenarios.




Figure 8: Exceedance probability - calcium in SC01.




Figure 9: Top 10% exceedance probability for calcium in SC01.




Figure 10: Simulated calcium concentrations in RS03 for bore water and pit water dust suppression scenarios.




Figure 11: Exceedance probability – calcium in RS03.




Figure 12: Top 10% exceedance probability for calcium in RS03.




Figure 13: Simulated chloride concentrations in SC01 for bore water and pit water dust suppression scenarios.




Figure 14: Exceedance probability – chloride in SC01.




Figure 15: Top 10% exceedance probability for chloride in SC01.




Figure 16: Simulated chloride concentrations in RS03 for bore water and pit water dust suppression scenarios.




Figure 17: Exceedance probability – chloride in RS03.




Figure 18: Top 10% exceedance probability for chloride in RS03.




Figure 19: Simulated fluorine concentrations in SC01 for bore water and pit water dust suppression scenarios.




Figure 20: Exceedance probability – fluorine in SC01.




Figure 21: Top 10% exceedance probability for fluorine in SC01.




Figure 22: Simulated fluorine concentrations in RS03 for bore water and pit water dust suppression scenarios.




Figure 23: Exceedance probability – fluorine in RS03.




Figure 24: Top 10% exceedance probability for fluorine in RS03.




Figure 25: Simulated magnesium concentrations in SC01 for bore water and pit water dust suppression scenarios.




Figure 26: Exceedance probability – magnesium in SC01.




Figure 27: Top 10% exceedance probability for magnesium in SC01.




Figure 28: Simulated magnesium concentrations in RS03 for bore water and pit water dust suppression scenarios.




Figure 29 Exceedance probability – magnesium in RS03.




Figure 30: Top 10% exceedance probability for magnesium in RS03.




Figure 31: Simulated sodium concentrations in SC01 for bore water and pit water dust suppression scenarios.




Figure 32: Exceedance probability - sodium in SC01.




Figure 33: Top 10% exceedance probability for sodium in SC01.




Figure 34: Simulated sodium concentrations in RS03 for bore water and pit water dust suppression scenarios.




Figure 35: Exceedance probability – sodium in RS03.




Figure 36: Top 10% exceedance probability for sodium in RS03.




Figure 37: Simulated potassium concentrations in SC01 for bore water and pit water dust suppression scenarios.




Figure 38: Exceedance probability – potassium in SC01.




Figure 39: Top 10% exceedance probability for potassium in SC01.




Figure 40: Simulated potassium concentrations in RS03 for bore water and pit water dust suppression scenarios.




Figure 41: Exceedance probability – potassium in RS03.




Figure 42: Top 10% exceedance probability for potassium in RS03.




Figure 43: Modelled aluminium concentrations in SC01 over time.




Figure 44: SC01 exceedance probability - aluminium.




Figure 45: SC01 10% exceedance probability - aluminium.




Figure 46: Modelled aluminium concentrations in RS03 over time.




Figure 47: RS03 exceedance probability - aluminium.




Figure 48: RS03 10% exceedance probability - aluminium.




Figure 49: Modelled arsenic concentrations in SC01 over time.




Figure 50: SC01 exceedance probability - arsenic.




Figure 51: SC01 10% exceedance probability - arsenic.




Figure 52: Modelled arsenic concentrations in RS03 over time.




Figure 53: RS03 exceedance probability - arsenic.




Figure 54: RS03 10% exceedance probability - arsenic.




Figure 55: Modelled boron concentrations in SC01 over time.




Figure 56: SC01 exceedance probability - boron.




Figure 57: SC01 10% exceedance probability - boron.




Figure 58: Modelled boron concentrations in RS03 over time.




Figure 59: RS03 exceedance probability - boron.




Figure 60: RS03 10% exceedance probability - boron.




Figure 61: Modelled cobalt concentrations in SC01 over time.




Figure 62: SC01 exceedance probability - cobalt.




Figure 63: SC01 10% exceedance probability - cobalt.




Figure 64: Modelled cobalt concentrations in RS03 over time.




Figure 65: RS03 exceedance probability - cobalt.




Figure 66: RS03 10% exceedance probability - cobalt.




Figure 67: Modelled chromium concentrations in SC01 over time.




Figure 68: SC01 exceedance probability - chromium.




Figure 69: SC01 10% exceedance probability - chromium.




Figure 70: Modelled chromium concentrations in RS03 over time.




Figure 71: RS03 exceedance probability - chromium.




Figure 72: RS03 10% exceedance probability - chromium.




Figure 73: Modelled copper concentrations in SC01 over time.




Figure 74: SC01 exceedance probability - copper.




Figure 75: SC01 10% exceedance probability - copper.




Figure 76: Modelled copper concentrations in RS03 over time.




Figure 77: RS03 exceedance probability - copper.




Figure 78: RS03 10% exceedance probability - copper.




Figure 79: Modelled iron concentrations in SC01 over time.




Figure 80: SC01 exceedance probability - iron.




Figure 81: SC01 10% exceedance probability - iron.




Figure 82: Modelled iron concentrations in RS03 over time.




Figure 83: RS03 exceedance probability - iron.




Figure 84: RS03 10% exceedance probability - iron.




Figure 85: Modelled manganese concentrations in SC01 over time.




Figure 86: SC01 exceedance probability - manganese.




Figure 87: SC01 10% exceedance probability - manganese.




Figure 88: Modelled manganese concentrations in RS03 over time.




Figure 89: RS03 exceedance probability - manganese.




Figure 90: RS03 10% exceedance probability - manganese.




Figure 91: Modelled molybdenum concentrations in SC01 over time.




Figure 92: SC01 exceedance probability - molybdenum.




Figure 93: SC01 10% exceedance probability - molybdenum.




Figure 94: Modelled molybdenum concentrations in RS03 over time.




Figure 95: RS03 exceedance probability - molybdenum.




Figure 96: RS03 10% exceedance probability - molybdenum.




Figure 97: Modelled nickel concentrations in SC01 over time.




Figure 98: SC01 exceedance probability - nickel.




Figure 99: SC01 10% exceedance probability - nickel.




Figure 100: Modelled nickel concentrations in RS03 over time.




Figure 101: RS03 exceedance probability - nickel.




Figure 102: RS03 10% exceedance probability - nickel.




Figure 103: Modelled lead concentrations in SC01 over time.




Figure 104: SC01 exceedance probability - lead.




Figure 105: SC01 10% exceedance probability - lead.




Figure 106: Modelled lead concentrations in RS03 over time.




Figure 107: RS03 exceedance probability - lead.




Figure 108: RS03 10% exceedance probability - lead.




Figure 109: Modelled antimony concentrations in SC01 over time.




Figure 110: SC01 exceedance probability - antimony.




Figure 111: SC01 10% exceedance probability - antimony.




Figure 112: Modelled antimony concentrations in RS03 over time.




Figure 113: RS03 exceedance probability - antimony.




Figure 114: RS03 10% exceedance probability - antimony.




Figure 115: Modelled strontium concentrations in SC01 over time.




Figure 116: SC01 exceedance probability - strontium.




Figure 117: SC01 10% exceedance probability - strontium.




Figure 118: Modelled strontium concentrations in RS03 over time.




Figure 119: RS03 exceedance probability - strontium.




Figure 120: RS03 10% exceedance probability - strontium.




Figure 121: Modelled uranium concentrations in SC01 over time.




Figure 122: SC01 exceedance probability - uranium.




Figure 123: SC01 10% exceedance probability - uranium.




Figure 124: Modelled uranium concentrations in RS03 over time.




Figure 125: RS03 exceedance probability - uranium.




Figure 126: RS03 10% exceedance probability - uranium.




Figure 127: Modelled vanadium concentrations in SC01 over time.




Figure 128: SC01 exceedance probability - vanadium.




Figure 129: SC01 10% exceedance probability - vanadium.




Figure 130: Modelled vanadium concentrations in RS03 over time.




Figure 131: RS03 exceedance probability - vanadium.




Figure 132: RS03 10% exceedance probability - vanadium.




Figure 133: Modelled zinc concentrations in SC01 over time.




Figure 134: SC01 exceedance probability - zinc.




Figure 135: SC01 10% exceedance probability - zinc.




Figure 136: Modelled zinc concentrations in RS03 over time.




Figure 137: RS03 exceedance probability - zinc.




Figure 138: RS03 10% exceedance probability - zinc.




Figure 139: Modelled sulfate concentrations in SC01 over time.




Figure 140: SC01 exceedance probability - sulfate.




Figure 141: SC01 10% exceedance probability - sulfate.




Figure 142: Modelled sulfate concentrations in RS03 over time.




Figure 143: RS03 exceedance probability - sulfate.




Figure 144: RS03 10% exceedance probability - sulfate.




Figure 145: Modelled ammoniacal N concentrations in SC01 over time.




Figure 146: SC01 exceedance probability - ammoniacal N.




Figure 147: SC01 10% exceedance probability - ammoniacal N.




Figure 148: Modelled ammoniacal N concentrations in RS03 over time.




Figure 149: RS03 exceedance probability - ammoniacal N.




Figure 150: RS03 10% exceedance probability - ammoniacal N.




Figure 151: Modelled nitrate concentrations in SC01 over time.




Figure 152: SC01 exceedance probability - nitrate.




Figure 153: SC01 10% exceedance probability - nitrate.




Figure 154: Modelled nitrate concentrations in RS03 over time.




Figure 155: RS03 exceedance probability - nitrate.





Figure 156: RS03 10% exceedance probability - nitrate.



Year	Scenario	Station	Flow Rate (L/s)	рн	Hardness (mg CaCO3/L)	Acidity (mg CaCO3/L)	Alkalinity (mg CaCO3/L)	AI (mg/L)	As (mg/L)	B (mg/L)	Ca (mg/L)	Cd (mg/L)	CI (mg/L)	Co (mg/L) (Cr (mg/L)		OOC ng/L)	F (mg/L) (Fe Hg	L) (mg	Mg/L) (mg/	g M	Vin Mo g/L) (mg/L)	NO3-N (mg/L)	Na (mg/L)	NI (mg/L)	Pb (mg/L)	Sb (mg/L)	Se (mg/L)	SO4 (mg/L)	Sr (mg/L)					V Zn	
	MIW-to-RAS_PL-NP20	SC01 Untreated		8 7.92	156			0.0164		0.0696		0.00009			.00054		1.66	1.08	1.36 0.000				0.14 0.1287			0.00074		0.55442		199		0.0002				.0210 0.002	
	MIW-to-RAS_PL-NP20 MIW-to-RAS_PL-NP20	SC01 Untreated SC01 Untreated		5 7.91 1 7.91	160 149				0.0377 0.0222	0.0674 0.0503		0.00009		0.00960 0 0.00526 0			1.64	1.10 0.67	1.40 0.000 0.80 0.000				0.14 0.1258 0.08 0.0751				0.00026 0.00027									.0213 0.002 .0120 0.001	
3	MIW-to-RAS PL-NP20	SC01 Untreated SC01 Untreated	12.77	7 7.91 5 7.92	151 150				0.0238 0.0254	0.0505 0.0517		0.00010		0.00543 0 0.00460 0				0.72	0.87 0.000 0.85 0.000				0.08 0.0785 0.07 0.0728			0.00056 0.00060	0.00027 0.00026	0.33511 0.28544		127 118						.0128 0.001 .0109 0.001	
5	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Untreated	25.40	0 7.92	151	0.00	147.4	0.0133	0.0249	0.0514	39.7	0.00010	6.7	0.00415 0	.00056	0.00049	1.63	0.65	0.82 0.000	24 5	6.2 12	2.6	0.07 0.0679	1.72	96.5	0.00062	0.00026	0.26006	0.01556	107	1.86	0.0002	1.5656 (0.0000 0.	0235 0.	.0100 0.001	17
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Untreated SC01 Untreated		5 7.92 3 7.92	153 151				0.0275			0.00009		0.00445 0				0.71	0.92 0.000				0.07 0.0742			0.00066	0.00026	0.28699		111						.0110 0.001	
	MIW-to-RAS PL-NP20	SC01 Untreated	15.57	7 7.92	154	0.00	148.6	0.0122	0.0289	0.0548	39.9	0.00009	7.2	0.00437 0	.00055	0.00047	1.58	0.75	0.97 0.000	24 6	4.7 13	3.1	0.08 0.0776	1.72	105.3	0.00068	0.00026	0.29802	0.01746	113	2.14	0.0002	1.5230 0	0.0000 0.	0260 0	.0113 0.001	17
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Untreated SC01 Untreated		3 7.92 8 7.93	151 155				0.0259			0.00009			.00055		1.62		1.05 0.000		5.7 12 7.0 13		0.07 0.0691 0.08 0.0814		95.4	0.00066 0.00072	0.00026	0.25505		104 114				0.0000 0.		.0097 0.001	
- 11	MIW-to-RAS PL-NP20	SC01 Untreated	17.46	6 7.93	151	0.00	147.5		0.0263			0.00009		0.00352 0				0.69	0.87 0.000			2.6	0.07 0.0701	1.33	95.2	0.00064	0.00026									.0098 0.001	
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Untreated SC01 Untreated		6 7.93 7 7.39	154 180				0.0308			0.00009		0.00400 0 0.00672 0					1.04 0.000	23 6	3.5 15		0.08 0.0803	1.85	120.7	0.01441	0.00026	0.28060	0.01628	134						.0115 0.001 .0108 0.002	
14	MIW-to-RAS PL-NP20	SC01 Untreated	30.55	5 6.73	235	0.06	148.5	0.0260	0.1673	0.1583	57.7	0.00010	58.6	0.01377 0	.00088	0.00082		1.01	3.07 0.000	19 7	7.3 22	2.0	0.12 0.1170	3.00	171.9	0.04230	0.00231	0.32011	0.01763	203	2.76	0.0002	1.1911 (0.0211 0.	0342 0.	.0127 0.004	40
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Untreated SC01 Untreated	25.60	0 6.52 5 6.50	291 296				0.2577	0.2348		0.00010	91.2		.00107		0.95	1.34	4.62 0.000 4.71 0.000	15 10	5.6 28 5.7 29	8.7 9.2	0.17 0.1632 0.18 0.1656	4.28			0.00355			273 275	3.54					.0171 0.005 .0171 0.005	
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Untreated SC01 Untreated		9 6.49 8 6.50	298 284	0.12		0.0311	0.2653	0.2493		0.00010		0.02307 0 0.02146 0	.00110		0.94	1.34	4.73 0.000 4.36 0.000				0.18 0.1684 0.17 0.1609				0.00370									.0173 0.005 .0167 0.005	
19	MIW-to-RAS PL-NP20	SC01 Untreated	29.07	7 6.46	290	0.12	153.0	0.0315	0.2511	0.2438	69.1	0.00010	89.8	0.02266 0	.00107	0.00103	0.99	1.31	4.54 0.000	15 10	7.4 28	8.6	0.18 0.1689	3.49	239.6	0.06605	0.00351	0.43238	0.02288	275	3.48	0.0002	0.9425 (0.0329 0.	0468 0.	.0175 0.005	56
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Untreated SC01 Untreated		0 6.45	288 299			0.0315	0.2464	0.2422		0.00010	88.0 94.3		.00105		0.94	1.32	4.51 0.000				0.18 0.1708 0.19 0.1815				0.00344			276 291		0.0002		0.0321 0.		.0178 0.005 .0188 0.005	
22	MIW-to-RAS_PL-NP20	SC01 Untreated	28.89	9 6.42	296 290	0.13	154.6	0.0327	0.2581	0.2563	70.1	0.00010	92.4	0.02407 0	.00108	0.00106	0.96	1.37	4.73 0.000	15 11	5.8 29	9.4	0.19 0.1814	3.29	252.0	0.06768	0.00361	0.46720	0.02460	290	3.63	0.0002	0.9075	0.0336 0.	0502 0.		58
	MIW-to-RAS_PL-NP20 MIW-to-RAS_PL-NP20	SC01 Untreated SC01 Untreated		7 6.44 9 6.38	305				0.2467	0.2467 0.2678		0.00010		0.02314 0 0.02531 0				1.34	4.57 0.000 4.96 0.000				0.18 0.1767				0.00345									.0200 0.006	
	MIW-to-RAS_PL-NP20 MIW-to-RAS_PL-NP20	SC01 Untreated SC01 Untreated		7 6.44 6 6.42	279 277	0.13 0.13			0.2279	0.2303	66.5	0.00010	81.3	0.02145 0 0.02122 0	.00101	0.00101	1.06		4.27 0.000			7.4	0.17 0.1687 0.17 0.1699	2.76	232.9	0.05892	0.00320	0.44533	0.02366	270 272		0.0002				.0179 0.005 .0181 0.005	
27	MIW-to-RAS PL-NP20	SC01 Untreated	34.50	0 6.37	296	0.15	155.1	0.0343	0.2547	0.2552	69.8	0.00010	90.7	0.02407 0	.00106	0.00108	0.95	1.42	4.83 0.000	15 12	3.7 29	9.7	0.19 0.1896	3.24	257.7	0.06586	0.00356	0.50369	0.02643	301	3.79	0.0002	0.8914 0	0.0327 0.	0529 0.	.0201 0.005	57
28	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Untreated SC01 Untreated		1 6.31 0 6.33	310 308				0.2734	0.2711		0.00010		0.02573 0 0.02522 0			0.87	1.50	5.18 0.000				0.21 0.2008				0.00382			315 312						.0215 0.006 .0212 0.005	
30	MIW-to-RAS PL-NP20	SC01 Untreated	29.67	7 6.37	287	0.15	154.5	0.0330		0.2364	67.9	0.00010	84.5	0.02200 0	.00103	0.00105	1.01	1.34	4.52 0.000	15 11	6.8 28	8.5	0.18 0.1773	2.64	243.1	0.06115	0.00334	0.47719	0.02519	284	3.63	0.0002	0.9575 (0.0304 0.	0498 0.	.0190 0.005	54
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Untreated SC01 Untreated		0 6.39 1 6.37	281 285	0.15 0.15			0.2298	0.2282		0.00010		0.02111 0 0.02130 0			1.04	1.31	4.40 0.000 4.53 0.000				0.18 0.1734 0.18 0.1772		236.9	0.05890	0.00323	0.46824	0.02475	281 286	3.57					.0186 0.005 .0192 0.005	
33	MIW-to-RAS PL-NP20	SC01 Untreated SC01 Untreated		8 6.34 1 6.25	289 315				0.2401			0.00010		0.02161 0 0.02504 0			0.98		4.67 0.000				0.19 0.1807 0.22 0.2079				0.00336									.0198 0.005 .0227 0.006	
35	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Untreated	34.76	6 6.33	302	0.18	156.0	0.0339	0.2576	0.2440	70.7	0.00010	90.8	0.02266 0	.00106	0.00111	0.92	1.46	4.99 0.000	14 12	8.3 30	0.4	0.20 0.1883	2.73	259.4	0.06585	0.00361	0.52705	0.02759	303	3.95	0.0002	0.8763 (0.0328 0.	0530 0.	.0208 0.005	56
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Untreated SC01 Untreated		3 6.27 9 6.30	317 304				0.2802	0.2607	73.7 71.3	0.00010		0.02434 0		0.00116		1.57	5.41 0.000 5.03 0.000			2.2	0.21 0.2010	2.77	277.5	0.07182	0.00392	0.56672	0.02949	322 304	4.20 3.96	0.0002	0.7970 0	0.0358 0.	0563 0. 0527 0	.0223 0.005 .0207 0.005	59 56
38	MIW-to-RAS PL-NP20	SC01 Untreated	29.11	1 6.37	277	0.15	154.6	0.0326	0.2198	0.2056	65.8	0.00010	77.1	0.01850 0	.00099	0.00103	1.06	1.29	4.28 0.000	16 11	0.4 27	7.3	0.17 0.1615	1.98	225.1	0.05558	0.00309	0.45601	0.02418	269	3.52	0.0002	1.0026	0.0277 0.	0462 0.	.0178 0.004	49
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Untreated SC01 Untreated		4 6.39 3 6.41	280 263				0.2224	0.2057		0.00010		0.01851 0 0.01619 0	.00100		1.05		4.34 0.000 3.96 0.000				0.17 0.1608 0.16 0.1487				0.00313			266 252						.0180 0.004 .0166 0.004	
41	MIW-to-RAS PL-NP20	SC01 Untreated	28.85	5 6.27	310	0.20	158.0	0.0357	0.2690	0.2373	72.2	0.00010	93.5	0.02167 0	.00108	0.00115	0.85	1.54	5.30 0.000	14 13	3.6 31	1.5	0.20 0.1900	2.57	264.3	0.06795	0.00376	0.55296	0.02878	313	4.15	0.0002	0.8137 (0.0339 0.	0540 0.	.0215 0.005	56
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Untreated SC01 Untreated	34.50 25.84	0 6.35 4 6.24	286 314				0.2327	0.2068		0.00010			.00101		0.82	1.35	5.45 0.000				0.18 0.1641 0.21 0.1920				0.00329									.0184 0.005 .0218 0.005	
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Untreated SC01 Untreated		4 6.31 4 6.22	287 323				0.2350	0.2017		0.00010		0.01785 0 0.02166 0				1.38	4.67 0.000 5.69 0.000				0.18 0.1642 0.21 0.1945				0.00330				3.77	0.0002	0.9345 (0.0293 0.	0474 0.	.0188 0.004 .0222 0.005	49 57
46	MIW-to-RAS PL-NP20	SC01 Untreated	34.57	7 6.35	273	0.16	153.9	0.0337	0.2148	0.1819	64.9	0.00010	73.9	0.01568 0	.00097	0.00104	1.07	1.28	4.28 0.000	16 10	6.2 27	7.0	0.16 0.1495	1.90	212.9	0.05340	0.00303	0.44223	0.02342	262	3.50	0.0002	1.0014	0.0267 0.	0437 0.	.0170 0.004	45
	MIW-to-RAS_PL-NP20 MIW-to-RAS_PL-NP20	SC01 Untreated SC01 Untreated		6 6.33 2 6.29	287 292				0.2333	0.1933		0.00010			.00101		0.95	1.36	4.63 0.000 4.87 0.000				0.17 0.1568 0.18 0.1634			0.05839	0.00329	0.47025		272 285						.0181 0.004 .0189 0.004	
49	MIW-to-RAS_PL-NP20 MIW-to-RAS_PL-NP20	SC01 Untreated	34.76	6 6.32	278	0.17	154.2	0.0346	0.2220	0.1798	65.8	0.00010	76.0	0.01528 0	.00098	0.00106	1.04	1.31	4.44 0.000	15 10	7.2 27	7.5	0.16 0.1489	1.96	214.5	0.05514	0.00313	0.44720	0.02360	266	3.57	0.0002	0.9722 (0.0276 0.	0437 0.	.0171 0.004	46
	MIW-to-RAS_PL-NP20	SC01 Untreated SC01 Untreated		4 6.27 6 6.33	295 287	0.19 0.18		0.0354	0.2473 0.2350	0.1942	67.6	0.00010	80.1		.00101	0.00109	0.93	1.44	4.70 0.000				0.18 0.1610 0.17 0.1521				0.00347	0.49128		285 273						.0187 0.004 .0176 0.004	
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Untreated SC01 Untreated		7 6.30 5 6.30	289 289				0.2391			0.00010		0.01543 0 0.01508 0				1.39	4.79 0.000 4.77 0.000				0.17 0.1530 0.17 0.1501				0.00336									.0178 0.004 .0175 0.004	
54	MIW-to-RAS PL-NP20	SC01 Untreated	33.39	9 6.30	286	0.18	154.7	0.0347	0.2340	0.1744	67.4	0.00010	79.2	0.01444 0	.00100	0.00109	0.98	1.37	4.70 0.000	15 10	8.8 28	8.5	0.17 0.1463	1.93	216.5	0.05788	0.00329	0.45507	0.02391	268	3.70	0.0002	0.9258 (0.0291 0.	0432 0.	.0172 0.004	46
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Untreated SC01 Untreated		4 6.27 2 6.31	293 285	0.19		0.0351	0.2452			0.00010		0.01481 0 0.01377 0			0.94	1.42	4.92 0.000 4.70 0.000				0.17 0.1503 0.16 0.1424				0.00344			276 265						.0178 0.004 .0168 0.004	
57	MIW-to-RAS PL-NP20	SC01 Untreated SC01 Untreated	31.36	6 6.27	288 301	0.19			0.2391			0.00010	80.3	0.01378 0	.00101	0.00110		1.40	4.82 0.000 5.22 0.000	15 10	8.8 28	8.8	0.17 0.1442	1.94	215.9	0.05884	0.00335	0.45629	0.02391	270						.0171 0.004	
59	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Untreated	37.36	6 6.31	282	0.18	154.1	0.0352	0.2295	0.1596	66.6	0.00010	76.9	0.01267 0	.00099	0.00109	1.00	1.34	4.63 0.000	15 10	2.5 28	8.0	0.18 0.1519 0.16 0.1355	1.85	205.4	0.05646	0.00323	0.42961	0.02260	259	3.61	0.0002	0.9377 (0.0285 0.	0405 0.	.0182 0.004 .0160 0.004	44
60	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Untreated SC01 Untreated		1 6.22 3 6.23	303 306				0.2633	0.1762 0.1749		0.00010		0.01420 0 0.01402 0			0.85	1.51	5.31 0.000 5.32 0.000				0.18 0.1508 0.18 0.1470			0.06488 0.06557	0.00368	0.48600		287 280						.0181 0.004 .0178 0.004	
62	MIW-to-RAS PL-NP20	SC01 Untreated	21.52	2 6.19	319	0.23	158.4	0.0378	0.2857	0.1852	74.1	0.00010	95.7	0.01487 0	.00110	0.00121	0.78	1.59	5.69 0.000	13 12	0.7 32	2.5	0.19 0.1556	1.93	240.3	0.07105	0.00399	0.50538	0.02609	298	4.19	0.0002	0.7364	0.0359 0.	0459 0.	.0188 0.005	51
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Untreated SC01 Untreated		1 6.34 4 6.30	276 286				0.2194	0.1466 0.1512		0.00010		0.01120 0 0.01165 0	.00098		0.97	1.27	4.39 0.000 4.75 0.000				0.15 0.1223 0.16 0.1281			0.05399	0.00310	0.39323								.0146 0.004 .0158 0.004	
65	MIW-to-RAS PL-NP20	SC01 Untreated	33.00	0 6.31	272	0.17	153.4	0.0334	0.2146	0.1394	64.7	0.00010	71.0	0.01045 0	.00096	0.00105	1.05	1.27	4.37 0.000	16 9	2.4 26	6.8	0.14 0.1190	1.59	187.4	0.05219	0.00302	0.38828	0.02060	237	3.43	0.0002	0.9913 (0.0264 0.	0361 0.	.0144 0.004	40
67	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Untreated SC01 Untreated	30.07	9 6.24 7 6.29	299 286	0.19	155.0	0.0337	0.2552 0.2349	0.1470	67.7	0.00010	77.9		.00100	0.00109	0.98	1.35	5.14 0.000 4.74 0.000	15 9	7.5 28	8.4	0.17 0.1344 0.15 0.1235	1.62	198.3	0.05758	0.00358	0.40898	0.02155	248	3.61	0.0002	0.9317 (0.0291 0.	0373 0.		43
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Untreated SC01 Untreated		4 6.30 4 6.17	286 324				0.2347	0.1451		0.00010	77.7		.00100		0.98	1.35	4.75 0.000 5.89 0.000			8.4	0.15 0.1221 0.19 0.1469	1.62	197.0		0.00330							0.0291 0. 0.0368 0.		.0150 0.004 .0181 0.005	
70	MIW-to-RAS PL-NP20	SC01 Untreated	27.85	5 6.30	282	0.18	155.3	0.0333	0.2289	0.1395	67.0	0.00010	75.7	0.01019 0	.00100	0.00108	1.00	1.31	4.61 0.000	16 9	2.2 27	7.9	0.15 0.1162	1.42	190.4	0.05606	0.00322	0.38675	0.02046	239	3.50	0.0002	0.9559 (0.0284 0.	0353 0.	.0142 0.004	42
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Untreated SC01 Untreated		9 6.37 2 6.22	262 303	0.16 0.21		0.0328	0.2003	0.1239		0.00010			.00094		0.86	1.18	4.07 0.000 5.31 0.000		1.7 25 4.3 30		0.13 0.1046	1.34	170.5 210.5	0.04851	0.00283	0.34325	0.01840	219 269		0.0002		0.0246 0. 0.0325 0.		.0126 0.003 .0160 0.004	
73	MIW-to-RAS_PL-NP20	SC01 Untreated	28.20	0 6.29	283	0.19	155.5	0.0345	0.2316	0.1365	67.2	0.00010	76.2	0.00975 0	.00100	0.00109	1.00	1.31	4.67 0.000	15 9	1.0 28	8.0	0.14 0.1143	1.48	188.5	0.05657	0.00326	0.38132	0.02013	240	3.50	0.0002	0.9408	0.0287 0.	0349 0.	.0140 0.004	42
	MIW-to-RAS_PL-NP20 MIW-to-RAS_PL-NP20	SC01 Untreated SC01 Untreated	20.42	0 6.25 2 6.23	294 302	0.21	158.3	0.0350	0.2482 0.2592	0.1465	70.9	0.00010	85.1	0.01026 0 0.01054 0	.00105	0.00115	0.88	1.43	5.01 0.000 5.22 0.000	14 9	9.4 30	0.3	0.15 0.1202 0.16 0.1219	1.51	204.3	0.06346	0.00347 0.00362	0.41637	0.02175	256	3.80	0.0002	0.8413 (0.0322 0.	0370 0	.0148 0.004 .0152 0.004	45
	MIW-to-RAS_PL-NP20	SC01 Untreated SC01 Untreated	29.33	3 6.36 2 6.36	270 266	0.17			0.2099	0.1231		0.00010		0.00844 0 0.00803 0						17 8	0.3 26	6.3	0.13 0.1002 0.13 0.0996	1.19	171.2	0.05118	0.00297 0.00288	0.33597	0.01802	216	3.21					.0123 0.003 .0122 0.003	
78	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Untreated	36.33	3 6.32	270	0.17	153.9	0.0335	0.2120	0.1208	64.5	0.00010	69.0	0.00815 0	.00096	0.00105	1.07	1.20	4.34 0.000	16 8	1.3 26	6.5	0.13 0.1011	1.47	170.9	0.05117	0.00299	0.34072	0.01818	221	3.27	0.0002	1.0083 (0.0260 0.	0314 0.	.0124 0.003	38
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Untreated SC01 Untreated		0 6.24 3 6.28	294 284			0.0368	0.2502			0.00010		0.00948 0 0.00869 0			0.92		5.07 0.000 4.74 0.000				0.15 0.1146				0.00351									.0141 0.004 .0130 0.004	
81	MIW-to-RAS PL-NP20	SC01 Untreated	32.28	8 6.26	289	0.20	155.7	0.0359	0.2426	0.1301	68.2	0.00010	78.6	0.00881 0	.00101	0.00112	0.94	1.32	4.95 0.000	14 8	9.2 28	8.8	0.14 0.1091	1.67	186.1	0.05876	0.00339	0.37344	0.01959	241	3.59	0.0002	0.8839 (0.0299 0.	0337 0.	.0135 0.004	41
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Untreated SC01 Untreated		6 6.30 8 6.24	278 294	0.19 0.21	155.7		0.2503	0.1310	69.2		81.1	0.00812 0 0.00878 0	.00103	0.00114				14 8	9.5 29	9.4	0.13 0.1018 0.15 0.1083	1.73	188.0		0.00350		0.01957	243	3.63	0.0002	0.8628 0	0.0310 0.	0335 0.	.0125 0.004 .0135 0.004	42
84	MIW-to-RAS PL-NP20	SC01 Untreated		2 6.29 3 6.37	282 262	0.19	154.2	0.0337	0.2317	0.1223	67.1	0.00010	75.3	0.00802 0	.00100	0.00110	1.00	1.23	4.70 0.000	15 8	1.8 27	7.9	0.13 0.0987 0.12 0.0904	1.56	175.4	0.05640		0.34087	0.01807	224	3.39	0.0002	0.9514 (0.0287 0.	0307 0.	.0123 0.004 .0109 0.003	40
	MIW-to-RAS PL-NP20	O SUT Officered	31.50	0.07	202	0.17	101.9	0.0343	0.2041	0.1099	00.0	J.000 IU	00.5	0.0003110		5.00104	1.70	6.111	4.10 0.000	/.	2.01 20		J. 12 0.0904	1.40	107.7	J.04510	3.00200	3.00252	0.01024	210	0.10	3.0002			JE00 0.	J.05 0.003	

	Year Scenario	Station	Flow Rate	pH	Hardness (mg	Acidity (mg	Alkalinity (mg	Al	As B (mg/L	Ca	Cd	CI	Со	Cr		оос		e Hg	к	Mg	Mn	Мо	NO3-N	Na	NI	Pb	Sb	Se	SO4	Sr			CN U		
				ļ. ļ	CaCO3/L)		,																												
			37.91	6.29	304 279		156.0 153.0	0.0379		71.1																									
							153.4	0.0348																											
	91 MIW-to-RAS PL-NP20	SC01 Untreated	25.97	6.21	299	0.22	155.2	0.0359	0.2624 0.126	70.3	0.00010	84.4	0.00805	0.00105	0.00116	0.85	1.30	5.32 0.000	14 85.6	30.1	0.14	0.1008	1.69	184.8	0.06381	0.00366	0.35602	0.01857	238	3.66	0.0002 0.	.8142 0.	0326 0.0	313 0.0	127 0.00
										62.7	0.00010	64.6	0.00596						16 66.1	25.3	0.11														
	95 MIW-to-RAS PL-NP20											72.6	0.00661																						
	96 MW-to-RAS PL-NP20 97 MW-to-RAS PL-NP20																																		
	98 MIW-to-RAS PL-NP20											82.2	0.00722																						
	101 MIW-to-RAS PL-NP20						156.3	0.0362	0.2637 0.119	70.3	0.00010	83.7	0.00713		0.00117	0.84	1.22	5.39 0.000	13 79.2	30.1	0.14	0.0917	1.66	176.2	0.06357	0.00365	0.32728	0.01707	230	3.61	0.0002 0.	.7988 0.	0325 0.0	288 0.0	116 0.00
										69.2	0.00010	77.8	0.00682																						
Column C	100 111111 10 10 10 10 10 10 10 10 10 10											70.7	0.00580	0.00097	0.00108																				
										68.1	0.00010																								
	108 MIW-to-RAS_PL-NP20	SC01 Untreated	27.35	6.24	289	0.21	154.8	0.0355	0.2489 0.110	68.3	0.00010	78.9	0.00628	0.00102	0.00114	0.91	1.09	5.08 0.000	14 69.5	28.8	0.12	0.0808	1.56	161.9	0.06006	0.00346	0.28442	0.01500	214	3.36	0.0002 0.	.8653 0.	0307 0.0	257 0.0	100 0.00
10 10 10 10 10 10 10 10	111 MIW-to-RAS_PL-NP20	SC01 Untreated	27.83	6.29	275	0.19	154.0	0.0348	0.2277 0.102	65.6	0.00010	72.1	0.00562	0.00098	0.00108	1.00	0.99	4.63 0.000	15 62.0	27.0	0.11	0.0739	1.31	149.1	0.05477	0.00317	0.25339	0.01355	200	3.11	0.0002 0.	.9411 0.	0280 0.0	238 0.0	0.00
The part of the																																			
The color of the																																			
Trigon Property	115 MIW-to-RAS PL-NP20															0.00																			
11 March A. P. A. P. S. 15 15 15 15 15 15 15 1																																			
	118 MIW-to-RAS PL-NP20		32.15	6.29	274												0.93	4.64 0.000	15 57.8	26.9	0.10									3.04	0.0002 0.	.9514 0.	0280 0.0	220 0.0	0.00
19 March A.																																			
The part of the	121 MIW-to-RAS PL-NP20	SC01 Untreated	30.37	6.27	285	0.20	154.1	0.0355	0.2445 0.105	67.6	0.00010	77.3	0.00565	0.00101	0.00113	0.94	0.96	4.96 0.000	15 59.7	28.2	0.11	0.0698	1.47	150.3	0.05923	0.00342	0.24004	0.01276	201	3.17	0.0002 0.	.8919 0.	0303 0.0	225 0.0	0.00
Section Sect	122 MIW-to-RAS PL-NP20																0.94	1.88 0.000	15 58.4	27.9	0.11														
	124 MIW-to-RAS PL-NP20																																		
The part of the	125 MIW-to-RAS PL-NP20																																		
2 Marth And P. A. Price 200 Commender 72 B. 20 L.																						0.0663													
Section Company Comp	128 MIW-to-RAS PL-NP20	SC01 Untreated	27.26	6.21	293	0.22	154.2	0.0361	0.2589 0.107	69.1	0.00010	81.4	0.00573	0.00103	0.00117	0.87	0.95	5.28 0.000	14 59.3	29.2	0.11	0.0682	1.67	152.4	0.06263	0.00361	0.23583	0.01244	203	3.27	0.0002 0.	.8329 0.	0321 0.0	219 0.0	0.00
13 Mart PARA PRA PRA PRA 200 Columbridge 31.0 32 5.00 5.																																			
State Continue State S	131 MIW-to-RAS PL-NP20	SC01 Untreated	33.80	6.30	267	0.18	151.8	0.0348	0.2196 0.095	64.0	0.00010	68.9	0.00482	0.00096	0.00107	1.04	0.81	4.48 0.000	16 49.5	26.1	0.09	0.0599	1.37	132.9	0.05282	0.00308	0.19586	0.01065	183	2.86	0.0002 0.	.9729 0.	0270 0.0	197 0.0	0.00
13 May No. PAR. P. M. P. P. S.												70.1	0.00488																						
							154.1	0.0390	0.2707 0.110	69.8		84.7	0.00582	0.00104	0.00120																				
13 MW-9-M-94 Pa-Pa-Pa-Pa-Pa-Pa-Pa-Pa-Pa-Pa-Pa-Pa-Pa-P																																			
3	137 MIW-to-RAS_PL-NP20		24.60	6.24	289	0.21	153.8	0.0352	0.2536 0.104	68.5	0.00010	79.9	0.00545	0.00102	0.00114	0.90	0.86	5.11 0.000	14 52.8	28.6	0.10	0.0611	1.41	144.8	0.06167	0.00354	0.20639	0.01100	192	3.11	0.0002 0.	.8636 0.	0.0	197 0.0	0.00
14 MIN -PA-MA P. P.N. P.P. 20 20 20 14 30 0.032 0.157 0.035 0.032 0.017 0.005 0.005 0.001 0.017 0.05 0.005 0.001 0.017 0.05 0.005 0.001 0.017 0.05 0.005 0.001 0.017 0.05 0.005 0.001 0.017 0.05 0.005 0.001 0.017 0.05 0.005 0.001 0.017 0.05 0.005 0.001 0.017 0.05 0.005 0.001 0.017 0.05 0.005 0.001 0.017 0.05 0.005 0.001 0.017 0.05 0.005 0.001 0.017 0.05 0.005 0.001 0.017 0.05 0.005 0.001 0.017 0.05 0.005 0.001 0.017 0.05 0.005 0.001 0.017 0.005 0.0																																			
14 Mary-Park P., Park P.,																																			
16 Mary 16-PAGE Ph/920 SOFI Uniffeeder 25.4 4.5 2.7 2.7 0.32 15.4 0.0339 0.0991 0.099	141 MIW-to-RAS PL-NP20											81.8	0.00552	0.00103	0.00117																				
He Marty Propage Propage Soft Unfreader Soft												71.3 84.0	0.00482	0.00097	0.00109					26.6		0.0548								3.27	0.0002 0.	.9607 0. .7708 0.	0281 0.0	180 0.0 203 0.0	072 0.00
146 MIN-D-RAS PL-NP20 3001 Infriended 32.2 6.30 3.7 5.00 0.18 15.5 0.0342 0.2198 0.0098 0.0017 0.0098 0.0017 0.0098 0.0017 0.0098 0.0017 0.0098 0.0017 0.0098 0.0017 0.0098 0.0017 0.0098 0.0017 0.0098 0.0017 0.0098 0.0018 0.00	144 MIW-to-RAS PL-NP20	SC01 Untreated	32.34	6.27	273	0.19	151.7	0.0342	0.2301 0.096	65.1	0.00010	71.7	0.00481	0.00097	0.00109	0.98	0.76	4.72 0.000	15 46.2	26.8	0.09	0.0547	1.49	131.1	0.05521	0.00321	0.17892	0.00974	177	2.90	0.0002 0.	.9336 0.	0283 0.0	180 0.0	062 0.00
14 MW - 16 - MA - 16 MW - 16 - MA - 16 MW - 16												88.7 65.7	0.00592 0.00441										1.69	153.2	0.06883	0.00393	0.21229	0.01103	170	2.70	0.0002 0. 0.0002 1.	./339 0. .0005 0	0353 0.0	203 0.0 172 0.0	0.00 0.00 0.00
149 MM***********************************	147 MIW-to-RAS PL-NP20	SC01 Untreated	35.23	6.30	273	0.19	151.6	0.0337	0.2293 0.096	65.2	0.00010	71.7	0.00479	0.00097	0.00109	1.00	0.74	4.67 0.000	15 44.5	26.7	0.09	0.0526	1.44	129.7	0.05534	0.00321	0.17067	0.00935	174	2.84	0.0002 0.	.9517 0.	0283 0.0	173 0.0	0.00
190 MM**-P-MP2 9 C01 Untreated 30.10 5.24 280 0.20 151.9 0.388 0.239 0.1000 6.65 0.00010 7.24 0.	148 MIW-to-RAS PL-NP20																																		
151 MMV-b-RAS PL-NP20 SOUT Unfreated 3.9.2 6.30 2.73 0.19 151.2 0.358 0.2097 6.5.1 0.0001 72.4 0.0086 0.0097 0.00110 72.4 0.0086 0.0091 70.72 4.80 0.00915 4.34 2.70 0.09 0.552 1.5.2 12.6 0.0586 0.0030 0.01868 0.0093 0.0186 0.0091 71.7 2.82 0.0002 0.2980 0.0289 0.02910 0.0058 0.0081	150 MIW-to-RAS PL-NP20		30.10	6.24		0.10	151.9	0.0358	0.2439 0.100	66.6	0.00010	76.0	0.00504	0.00099	0.00113		0.76	4.98 0.000	14 46.0	27.7	0.09		1.59	134.1	0.05880	0.00340	0.17571	0.00945	183	2.95	0.0002 0.	.8795 0.	0301 0.0	179 0.0	0.00
153 MW-16-RAS PL-NP20 SC01 Unifresided 3.37 6.28 2.77 0.19 151.9 0.055 0.0501 0.0591	101		39.52	6.30		0.19	151.2	0.0352	0.2320 0.096	65.1	0.00010	72.4	0.00480		0.00110	0.99	0.72	4.73 0.000	15 43.4	26.8	0.09	0.0527	1.50	128.8	0.05593	0.00325	0.16553	0.00901	177	2.82	0.0002 0.	.9264 0.	0286 0.0	173 0.0	0.00
154 MW-16-RAS PL-NP20 SC01 Untreated 29.77 6.26 272 0.19 150.9 0.055 0.2316 0.0951 0.0951 0.0050 0.00010 1.55 MW-16-RAS PL-NP20 SC01 Untreated 29.77 6.25 279 0.20 151.5 0.0350 0.2310 0.0957 6.49 0.00010 7.78 0.0047 0.00091 0.00110 0.94 0.78 0.0047 0.00091 0.00110 0.0001	153 MIW-to-RAS PL-NP20		34.37	6.28	275	0.20	151.1	0.0354	0.2359 0.097	65.6	0.00010	73.6	0.00487	0.00098	0.00111	0.97	0.72	4.80 0.000	15 43.3	27.0	0.09	0.0523	1.52	129.6	0.05696	0.00330	0.16411	0.00891	178	2.82	0.0002 0.	.9129 0.	0292 0.0	172 0.0	0.00
186 MW-16-RAS PL-NP20 SC01 Untreated 31.63 6.26 2.78 0.29 15.11 0.0356 0.0357 6.99 0.0091 0.0	154 MIW-to-RAS PL-NP20	SC01 Untreated	33.78	6.28	272	0.19	150.9	0.0350	0.2316 0.096	65.0	0.00010	72.1	0.00476	0.00097	0.00110	0.98	0.70	4.73 0.000	15 42.3	26.7	0.09	0.0514	1.50	127.4	0.05573	0.00323	0.16042	0.00876	175	2.78	0.0002 0.	.9248 0.	0285 0.0	169 0.0	0.00
157 MMY-16-RAS PL-NP20 SC01 Unitreated 3.5.6 6.2 278 0.22 151.1 0.355 0.2371 0.0973 6.5.5 0.00010 70.6 1.00043 0.00097 0.00111 0.87 0.74 5.24 0.00014 4.5.2 2.71 0.09 0.0514 1.56 128.3 0.0556 0.03370 0.15471 0.00055 0.0005 0.0005 0.0000 1.00000 0.																																			
198 MW-lb-RAS PL-NP20 SC01 Unineated 28.08 6.21 289 0.22 152.1 0.334 0.257 0.0580 0.0010 8.0 0.0010 0.0017 0.85 0.00013 45.1 28.8 0.001 0.0581 0.0010 0.0017 0.85 0.00013 45.1 28.8 0.0010 0.0017 0.85 0.00013 45.1 28.8 0.0010 0.0017 0.85 0.00013 45.1 28.8 0.0010 0.0017 0.85 0.00013 45.1 28.8 0.0010 0.0017 0.85 0.0010 0.0017 0.85 0.0010 0.0017 0.85 0.0017 0.0017 0.85 0.0017	157 MIW-to-RAS PL-NP20	SC01 Untreated	31.63	6.26	275	0.20	151.1	0.0356	0.2371 0.097	65.5	0.00010	73.6	0.00483	0.00097	0.00111	0.96	0.70	4.85 0.000	14 42.3	27.1	0.09	0.0514	1.56	128.3	0.05696	0.00330	0.15937	0.00865	177	2.78	0.0002 0.	.8982 0.	0292 0.0	169 0.0	055 0.00
160 MM-16-RAS PL-NP20 SC01 Untreated 28.00 6.21 289 0.22 152.1 0.0374 0.2615 0.1044 68.3 0.00010 1.00117 0.85 0.74 5.3 4.000010 4.46 2.9 0.00010 0.0013 0.154 0.0000 0.00001 4.6 0.00001 0.0013 0.00001 0.0013 0.00001 0.00001 0.0010 0.00001 0.0010 0.00001 0.0010 0.0010 0.0010 0.0010 0.00001 0.00001 0.00001 0.00001 0.000001 0.00												79.6 70.8																							
162 MMV-lb-RAS PL-NP20 SCP1 Untreated 23.0 6 3.0 6 4.0 18 15.0 5.0 300 0.284 1 0.117 71.4 0.00010 88.8 0.00578 0.0016 0.0012 0.77 7 7.7 5.7 1 0.0013 4.7 2 30.5 0.10 0.0553 1.60 145.2 0.06826 0.0334 0.1753 0.00914 197 3.04 0.0002 0.7350 0.0016 0.0012 0.0077 153 0.0001 0.0018	160 MIW-to-RAS_PL-NP20	SC01 Untreated	28.08	6.21	289	0.22	152.1	0.0374	0.2615 0.104	68.3	0.00010	81.1	0.00530	0.00101	0.00117	0.85	0.74	5.33 0.000	13 45.1	28.8	0.10	0.0540	1.71	136.7	0.06309	0.00363	0.16862	0.00892	189	2.93	0.0002 0.	.8016 0.	0323 0.0	175 0.0	0.00
163 MmV-lb-RAS PL-NP20 SC01 Untreated 32.6 6.3 264 0.18 150.5 0.335 0.2183 0.922 6.3 0.0001 68.1 0.00046 0.00058 0.0016 1.00 0.00058 0.0016 1.0 0.00058 0.0016 0.00058 0.00																																			
164 MMV-lb-RAS PL-NP20 SC01 Unifrested 3.03 6.28 274 0.19 151.4 0.0326 0.2330 0.0551 6.5.3 0.00010 72.1 0.00470 0.00056 0.01015 36.3 0.2561 0.1884 0.05586 0.00324 0.14696 0.00809 154 2.54 0.0002 0.9298 0.0262 0.0151 0.0051 0.0	163 MIW-to-RAS PL-NP20		32.10	6.33	264	0.18	150.5	0.0335	0.2183 0.092	63.5	0.00010	68.1	0.00446	0.00095	0.00106	1.05	0.63	4.41 0.000	16 36.8	25.6	0.08	0.0456	1.22	119.2	0.05271	0.00306	0.13647	0.00767	163	2.50	0.0002 0.	.9889 0.	0270 0.0	152 0.0	0.00
165 MmV-lb-RAS PL-NP20 SC01 Uniterated 25.90 6.23 286 0.21 15.24 0.034 0.2539 0.021 75.0 0.0010 0.00115 0.089 0.091 0.00115 0.089 0.091 0.00115 0.089 0.091 0.00115 0.089 0.091 0.00115 0.089 0.091 0.00115 0.089 0.091 0.00115 0.089 0.091 0.00115 0.089 0.091 0.00115 0.089 0.091 0.00115 0.089 0.091 0.00115 0.089 0.091 0.00115 0.089 0.091 0.00115 0.089 0.091 0.00115 0.089 0.091 0.00115 0.089 0.091 0.00115 0.089 0.00115 0.00115 0.089 0.00115 0.089 0.00115 0.089 0.00115 0.089 0.00115 0.00115 0.089 0.00115 0.00115 0.089 0.00115 0.00115 0.089 0.00115 0.	164 MIW-to-RAS PL-NP20											72.1	0.00470	0.00096	0.00108				15 39.3	26.9			1.38	124.4	0.05586	0.00324	0.14606	0.00809	164						
167 MMV-10-RAS PL-NP20 SC01 Unificiated 30.08 6.28 274 0.19 151.4 0.038 0.238 0.0961 6.54 0.00010 72.7 0.00473 0.00097 0.00110 0.98 0.64 4.75 0.00015 38.2 26.9 0.08 0.0460 1.39 124.0 0.05838 0.0336 0.14072 0.00779 167 2.58 0.0002 0.9311 0.0289 0.0152 0.00094 0.0018 0.	165 MW-to-RAS PL-NP20 166 MW-to-RAS PL-NP20																																		
168 MmV-lo-RAS PL-NP20 SC01 Untreated 19.24 6.29 274 0.19 151.4 0.039 0.2335 0.0395 6.1 0.00072 0.00110 0.98 0.64 4.76 0.00015 3.0 2.6.8 0.08 0.0457 1.40 123.5 0.05850 0.03350	167 MIW-to-RAS PL-NP20	SC01 Untreated	30.08	6.28	274	0.19	151.4	0.0338	0.2338 0.096	65.4	0.00010	72.7	0.00473	0.00097	0.00110	0.98	0.64	4.75 0.000	15 38.2	26.9	0.08	0.0460	1.39	124.0	0.05638	0.00326	0.14072	0.00779	167	2.58	0.0002 0.	.9311 0.	0289 0.0	152 0.0	0.00
170 MMW-1o-RAS PL-NP20 SC01 Unitreated 27.85 6.29 271 0.19 151.8 0.0334 0.2280 0.0945 64.8 0.00010 70.9 0.00462 0.00006 0.00108 1.00 0.62 4.62 0.00016 36.4 26.4 0.08 0.043 1.24 121.0 0.05501 0.00318 0.13300 0.00745 163 2.47 0.0002 0.9556 0.0282 0.0147 0.0006 0.00	168 MIW-to-RAS PL-NP20									65.4	0.00010	72.6 91.0	0.00472	0.00097	0.00110	0.98	0.64	4.76 0.000	15 38.0	26.8	0.08	0.0457							166	2.56	0.0002 0.	.9297 0. 6973 0	0288 0.0	151 0.0	0.00
171 MMW-10-RAS PL-NP20 SC01 Untreated 36.59 6.36 252 0.16 150.0 0.0329 0.1995 0.0861 61.1 0.00010 61.8 0.00403 0.00102 1.12 0.56 4.08 0.00017 32.3 24.2 0.07 0.0417 1.18 19.7 0.04764 0.00280 0.11819 0.00686 152 2.26 0.0002 1.0494 0.0244 0.0141 0.004	170 MIW-to-RAS PL-NP20	SC01 Untreated	27.85	6.29	271	0.19	151.8	0.0334	0.2280 0.094	64.8	0.00010	70.9	0.00462	0.00096	0.00108	1.00	0.62	4.62 0.000	16 36.4	26.4	0.08	0.0443	1.24	121.0	0.05501	0.00318	0.13300	0.00745	163	2.47	0.0002 0.	.9556 0.	0282 0.0	147 0.0	0.00
	171 MIW-to-RAS PL-NP20	SC01 Untreated	36.69	6.36	252	0.16	150.0	0.0329	0.1995 0.086	61.1	0.00010	61.8	0.00403	0.00091	0.00102	1.12	0.56	4.08 0.000	17 32.3	24.2	0.07	0.0417	1.18	109.7	0.04764	0.00280	0.11819	0.00686	152	2.26	0.0002 1.	.0494 0.	0.0	141 0.0	0.00

	Year	Scenario	Station	Flow Rate (L/6)	рН	Hardness (mg CaCO3/L)	Acidity (mg CaCO3/L)	Alkalinity (mg CaCO3/L)	Al (mg/L)	As (mg/L)		Ca (mg/L)	Cd (mg/L)	CI (mg/L)	Co (mg/L)	Cr (mg/L)	Cu (mg/L)	DOC (mg/L)		Fe 1g/L)	Hg (mg/L) (r			Mn Mo			NI (mg/L)	Pb (mg/L)	Sb (mg/L)	Se (mg/L)		Sr ng/L) (m				V L) (mg/L)	Zn (mg/L)
	172	MIW-to-RAS PL-NP20	SC01 Untreated	23.42	6.21	,		,	0.0372	0.2614	0.1041	68.4	0.00010	80.8	0.00524	0.00101	0.00117	0.86	0.69	5.32 (0.00013	41.1	28.9	0.09 0.04	99 1.5	3 132.9	0.06295	0.00362	0.15027	0.00801	183	2.72 0.0	0002 0.80	48 0.03	323 0.01	63 0.0051	0.0040
							0.15	152.1	0.0346	0.2307																											
	176	MIW-to-RAS PL-NP20	SC01 Untreated	29.33	6.35	260	0.17	151.7	0.0319	0.2092	0.0892	62.9	0.00010	65.2	0.00424	0.00094	0.00104	1.09	0.56	4.23	0.00017	32.1	25.1	0.07 0.04	00 1.0	112.7	0.05042	0.00294	0.11567	0.00673	151	2.24 0.0	0002 1.03	83 0.02	258 0.01	35 0.0040	0.0035
	177	MIW-to-RAS PL-NP20	GOO! GITTE COICE																			31.9	24.7	0.07 0.04	03 1.2												
	179	MIW-to-RAS PL-NP20		28.50	6.24	283	0.21	153.0	0.0369	0.2495	0.1009	67.2	0.00010	77.3	0.00500	0.00100	0.00115	0.92	0.63	5.08 (0.00014	37.4	28.0	0.08 0.04	54 1.5	126.5	0.06020	0.00348	0.13382	0.00727	176	2.50 0.0	0002 0.86	29 0.03	308 0.01	53 0.0046	0.0039
	180	MIW-to-RAS PL-NP20																				34.8	26.7	0.08 0.04	35 1.4												
	181	MIW-to-RAS PL-NP20																																			
	183	MIW-to-RAS PL-NP20		30.58	6.24	283					0.1004	67.1	0.00010	77.2	0.00499	0.00100	0.00115	0.91	0.61	5.10 (0.00014	36.3	28.0	0.08 0.04	45 1.6	1 125.2	0.06019	0.00348	0.12869	0.00702	172	2.44 0.0	0002 0.86	26 0.03	308 0.01	46 0.0044	0.0039
	184	MIW-to-RAS PL-NP20		36.22 51.53	6.29	272								71.8	0.00464	0.00097	0.00110	1.00	0.57	4.71 (0.00015	33.4	26.6	0.08 0.04	09 1.4	118.4	0.05582	0.00324	0.11750	0.00664	159	2.28 0.0	0002 0.95	13 0.02	286 0.01	35 0.0040	0.0037
	186	MIW-to-RAS PL-NP20		30.73	6.20			152.3	0.0379	0.2679	0.1056	68.9	0.00010	82.7	0.00533	0.00102	0.00119	0.83	0.63	5.48 (0.00013	37.9	29.2	0.09 0.04	54 1.8	130.6	0.06463	0.00372	0.13328	0.00708	181	2.50 0.0	0002 0.78	24 0.03	331 0.01	51 0.0045	0.0040
No. 10. Column												63.2	0.00010																								
						282																			20 1.3	123.2	0.06070	0.00348	0.11607	0.00638							
	196	MIW-to-RAS_PL-NP20	SC01 Untreated	31.33	6.27	279	0.20	151.6	0.0357	0.2458	0.0994	66.5	0.00010	76.1	0.00490	0.00099	0.00113	0.93	0.57	4.99 (0.00014	32.8	27.5	0.08 0.04	13 1.4	7 121.0	0.05940	0.00343	0.11305	0.00625	167	2.22 0.0	0002 0.87	79 0.0	304 0.01	36 0.0038	0.0038
March A.	199	MIW-to-RAS PL-NP20	SC01 Untreated	25.61	6.25	284	0.21	152.5	0.0345	0.2506	0.1005	67.4	0.00010	77.6	0.00500	0.00100	0.00113	0.91	0.57	5.07 (0.00014	32.9	28.0	0.08 0.04	00 1.4	122.5	0.06064	0.00349	0.11275	0.00626	164	2.22 0.0	0002 0.87	30 0.03	311 0.01	32 0.0038	0.0039
The color of the																																					
The color of the		MINT 10 10 10 1 E 141 E0	SC01 Treated	13.61	7.91	153	0.00	141.9	0.0145	0.0022	0.0503	41.7	0.00010	6.6	0.00036	0.00055	0.00052	1.80	0.67	0.04 (0.00025	66.2	11.9	0.01 0.01	0.1	7 107.4	0.00034	0.00025	0.00972	0.00278	100	0.63 0.0	0002 1.72	05 0.00	0.01	09 0.0016	0.0013
Second Property Column C																																					
Section Column																							12.2	0.01 0.01	90 0.1												
The part of the	6 1	MIW-to-RAS PL-NP20																				62.1	12.5	0.01 0.00	B3 0.1												
1																		1.58	0.67	0.04 (0.00024	56.4	12.7		91 0.1 83 0.1	5 96.4 5 105.3											
Tolera T	9 1	MIW-to-RAS PL-NP20																	0.68	0.04 (0.00024	55.7	12.3	0.01 0.00	90 0.1						83	0.57 0.0	0002 1.55	22 0.00	0.00	92 0.0014	0.0012
2 Miles P-MAR P, MPD 1501 Telephon 1,3 M 78 182 0.000 0.0004 0.0																																					
Lamber-9-Act Fundame 1.5 2.5 1.5 2.5 1.5 2.5				15.36	7.93	162						44.0	0.00009	7.2	0.00031	0.00047	0.00044	1.55	0.79	0.04 (0.00023	66.2	12.8		91 0.1	106.1	0.00029	0.00022			92	0.56 0.0	0002 1.48	88 0.00	0.01	0.0015	
1 Number-Part Part 1 2 2 2 2 2 2 2 2 2				27.37	7.39	195						53.1	0.00010	23.7	0.00034	0.00046	0.00043	1.51	0.80	0.04 (0.00023	63.5															
The property The				25.60	6.52	338																															
13 MIN-SHAPE PLANES COLT TRIME 28 J 64 S.50 39 C.11 30 MIN-SHAPE PLANES 30 30 MI																				0.06	0.00015	105.7															
The part of the				29.68	6.50	328																									192	0.40 0.0	0002 0.97	48 0.00	0.01	38 0.0019	0.0007
2 HWY-6-MC 2, H-920 SCOTT-marked 380 6.0.1 54.5 0.012 0.007 2.596 3.0 0.007 0.				29.07	6.46													0.99	1.31	0.06	0.00015	107.4	26.7	0.03 0.00	88 0.1	2 239.6	0.00156	0.00020	0.01110	0.00175	200	0.39 0.0	0002 0.94	25 0.00	0.01	43 0.0020	0.0007
22 MIN-PARS_PAPED SOST Treated 3.47 & 6.41 SIX 15.1 \$4.4 C 0.13 \$1.42 C 0.072 C 0.007 \$2.007 \$2.000 \$2.007 \$2.000 \$2.007 \$2.000 \$2.007 \$2.000 \$2.007 \$2.000 \$2.007 \$2.000 \$2.007 \$2.0000 \$2.0000 \$2.0000 \$2.0000 \$2.0000 \$2.0000 \$2.0000 \$2.0000																						115.3	26.5	0.03 0.00	90 0.1	2 239.9	0.00153	0.00020	0.01129	0.00177	200						
24 MM-S-PARS PL-4929 SOFT Treated 32 79 6.38 38S 0.15 IS-1 09110 0.0337 0.2870 96.4 0.00001 1.08 1.0331 0.00001 0.00001 1.08 1.0331 0.00001 0.00001 1.08 1.0331 0.0000												92.7	0.00010	92.4	0.00053	0.00030	0.00029		1.37	0.06	0.00015	115.8	27.4	0.03 0.00	91 0.1	1 252.0	0.00159	0.00020	0.01182	0.00173	210	0.38 0.0	0002 0.90	75 0.00	0.01	52 0.0021	0.0007
25 MIM-S-HARD PLAPPE OCT Trended 33.27 6.44 0.20 0.13 153.7 0.030 0.0305 0.2003 0.0001 1.56 1.20 0.000 0.00000 0.0000 0.0000 0.0000 0.0000 0.0000 0.0000 0.0000 0.0000 0.0000 0.0000 0.0000 0.0000 0.0000 0.0000 0.0000 0.0000 0.0000 0.00000 0.				31.47 24.79	6.44	336						90.5	0.00010	96.3						0.06 (0.00015	122.8	26.8	0.03 0.00	86 0.1 85 0.1	1 245.5	0.00153	0.00020	0.01153	0.00179	203	0.39 0.0	0002 0.94	75 0.00	032 0.01	48 0.0021 56 0.0022	0.0007
27 MW-9-M-9-M-9-M-9-M-9-M-9-M-9-M-9-M-9-M-9	25	MIW-to-RAS PL-NP20	SC01 Treated	32.27	6.44	322	0.13	153.7	0.0130	0.0035	0.2303	86.5	0.00010	81.3	0.00050	0.00033	0.00031	1.06	1.28	0.06	0.00016	109.4	25.6	0.03 0.00	96 0.1	232.9	0.00142	0.00021	0.01156	0.00184	197	0.41 0.0	0002 1.00	0.00	0.01	47 0.0020	0.0008
29 MM-9-M-9-M-9-M-9-M-9-M-9-M-9-M-9-M-9-M	26 1			36.06	6.42	319												1.06				110.8	25.5	0.03 0.01	0.1	2 232.7	0.00140	0.00020	0.01183	0.00185	199						
30 MM-b-PAGP, PLAPPS SOFT Treated	28 1	MIW-to-RAS PL-NP20		26.21	6.31	361	0.17	156.5	0.0114	0.0037	0.2711	96.7	0.00010	97.4	0.00054	0.00027	0.00026	0.87	1.50	0.06	0.00014	132.2	29.1	0.03 0.00	B3 0.1	273.8	0.00164	0.00019	0.01279	0.00170	226	0.36 0.0	0002 0.83	39 0.00	0.01	62 0.0024	0.0006
37 MW-19-RG PLMP3																																					
33 MMV-b-RAS PL-MP29 GOTT Treated 32-91 6.37 329 0.15 154.6 0.0137 0.0037 0.2296 86.2 0.00010 0.271 0.0036 0.2037 0.0030 0.00027 0.0036 0.00037 0.0036 0.00037 0.0036 0.00			SC01 Treated	32.60	6.39	325	0.15	154.2	0.0142	0.0037	0.2282	87.2	0.00010	81.5	0.00050	0.00032	0.00031	1.04	1.31	0.06	0.00016	114.3	26.0	0.03 0.01	06 0.1	236.9	0.00142	0.00020	0.01232	0.00182	205	0.41 0.0	0002 0.97	35 0.00	0.01	54 0.0021	0.0007
34 MWW-b-RAS PLAP20 SCOIT Treated 26.41 6.25 368 0.19 157.6 0.0134 0.0004 0.2665 98.2 0.00005 0.00025	32	MIW-to-RAS PL-NP20		32.91	6.37	329								82.7	0.00049	0.00031	0.00030		1.35	0.06	0.00015					241.6	0.00143	0.00020	0.01250	0.00181	208	0.40 0.0	0002 0.94	93 0.00	030 0.01	55 0.0022	0.0007
35 MMY-1-PAG PN-P20 SCH Treside 3.37 0 0.18 156.0 0.117 0.0036 0.240 9.57 0.0001 9.77 0.0006 0.00024 0.003 0.00024 0.003 0.000000000000000000000000000000				26.41	6.25	368	0.19	157.6	0.0134	0.0040	0.2665	98.2	0.00010	98.9	0.00052	0.00025	0.00025	0.82	1.59	0.07	0.00013	140.2	29.8	0.03 0.01	0.1	280.6	0.00165	0.00019	0.01412	0.00162	241	0.35 0.0	0002 0.76	0.00	0.01	74 0.0025	0.0006
36 MMYDRAS PIL-MP20 SC01 Treated 23.91 6.30 354 0.18 157.3 0.014 0.0031 0.0032 0.0032 0.0033 0.0032 0.0033 0.0032 0.0030 0.003	35	MIW-to-RAS PL-NP20																0.92	1.46			128.3	28.3	0.03 0.00	83 0.1	259.4	0.00154	0.00019	0.01262	0.00175	218	0.38 0.0	0002 0.87	63 0.00	0.01	56 0.0023	0.0007
38 MW-16-RAS PL-NP20 SC011 Treated 31.94 6.39 323 0.15 154.6 0.0137 0.0033 0.2035 0.565 5.5 0.00010 1.75.1 0.0046 0.00033 0.00031 1.05 1.03 0.00000000000000000000000000000000																																					
41 MW-10-RAS PL-NP20 SC011 Treated 28.8 5.27 \$61 0.20 \$1.004 \$0.0035 \$0.0034 \$1.13 \$1.21 \$0.06 \$0.00014 \$13.3 \$2.3 \$0.00 \$0.0019 \$0.0031 \$0.00021 \$0.0031 \$0.00021 \$0.0031 \$0.00021 \$0.0031 \$0.00021 \$0.0031 \$0.00021 \$0.0031 \$0.00021 \$0.0031 \$0.00021 \$0.00031 \$0.00021 \$0.00031 \$0.00021 \$0.00031 \$0.00021 \$0.0003	38 1	MIW-to-RAS PL-NP20	SC01 Treated	29.11	6.37	319	0.15	154.6	0.0137	0.0035	0.2056	85.5	0.00010	77.1	0.00046	0.00033	0.00032	1.06	1.29	0.06	0.00016	110.4	25.5	0.03 0.00	99 0.1	1 225.1	0.00136	0.00020	0.01193	0.00185	196	0.42 0.0	0002 1.00	26 0.00	0.01	45 0.0020	0.0008
41 MW-16-RAS PL-NP20 SC011 Treated 34.56 6.27 351 0.20 158.0 0.0116 0.0031 0.0055 0.056 8.6 0.00010 51.1 0.00045 0.00031 0.0																																					
4 MMV-lo-RAS PL-NP20 SC01 Treated 31.64 6.24 366 0.20 158.8 0.025 0.0035 0.2075 90 0.00010 9.5 0.000	41 1	MIW-to-RAS PL-NP20	SC01 Treated	28.85	6.27	361	0.20	158.0	0.0118	0.0037	0.2373	96.4	0.00010	93.5	0.00047	0.00027	0.00026	0.85	1.54	0.06	0.00014	133.6	29.3	0.03 0.00	83 0.0	264.3	0.00158	0.00019	0.01311	0.00168	225	0.36 0.0	0002 0.81	37 0.00	0.01	58 0.0023	0.0006
45 MW-10-RAS PL-NP20 SC01 Treated 31.64 6.31 333 0.17 155.4 0.0126 0.0035 0.2017 89 0 0.00010 81.1 0.00023 0.0021 0.00023 0.77 156.0 0.0126 0.00011 17.1 26.8 0.001 0.00010 0.				34.50	6.35	331																		0.03 0.00	91 0.1												
45 MW-1o-RAS PL-NP20 SC01 Treated 34.57 6.35 314 0.16 15.99 0.014 0.003 0.0016 0.0001 0.0	44 1	MIW-to-RAS_PL-NP20	SC01 Treated	31.64	6.31	333	0.17	155.4	0.0126	0.0035	0.2017	89.0	0.00010	81.1	0.00043	0.00031	0.00029	0.98	1.38	0.06	0.00015	117.1	26.8	0.03 0.00	88 0.1	232.5	0.00141	0.00020	0.01208	0.00179	202	0.39 0.0	0002 0.93	45 0.00	0.01	45 0.0021	0.0007
47 MW-16-RAS PL-NP20 SC011 Treated 34.56 6.33 332 0.18 155.3 0.0123 0.0034 0.00034 0.00034 0.00034 0.00035 0.10 25.4 0.00140 0.00020 0.00173 0.0004 0.00020 0.00073 0.0004 0.00034 0				23.54	6.22	378													1.63	0.07	0.00013	139.3	30.7	0.03 0.00	B1 0.0	274.2	0.00167	0.00018	0.01351	0.00159	235	0.33 0.0	0002 0.73	48 0.00	0.01	51 0.0024	0.0005
48 MW-16-RAS PL-NP20 SC01 Treated 33.72 6.29 339 0.18 156.1 0.133 0.0031 0.00012 0.00012 0.00012 0.00012 0.00012 0.00013 0.0014 0.00012 0.00013 0.0014 0.00012 0.00012 0.00013 0.0014 0.00012 0.00013 0.0014 0.00012 0.00012 0.00013 0.0014 0.00012 0.00013 0.0014 0.00012 0.00013 0.0014 0.00012 0.00013 0.0014 0.00012 0.00013 0.0014 0.00012 0.00013 0.0014 0.00012 0.00013 0.0014 0.00012 0.00014 0.0011				34.56	6.33	332						88.88	0.00010	80.4	0.00042	0.00031	0.00030	1.00	1.36	0.06	0.00015	113.1	26.7	0.03 0.00	B3 0.1	226.4	0.00140	0.00020	0.01163	0.00180	197	0.40 0.0	0002 0.95	27 0.00	029 0.01	39 0.0020	0.0007
Si MMY-16-PAS PL-NP20 SC01 Treated 22.64 6.27 342 0.19 155.9 0.0130 0.0036 0.1942 91.5 0.00010 84.4 0.00040 0.00028 0.00031 0.00030 0.	48 1	MIW-to-RAS_PL-NP20	SC01 Treated	31.72	6.29	339	0.18	156.1	0.0133	0.0037	0.1969	90.7	0.00010	83.3	0.00041	0.00029	0.00029	0.95	1.43	0.06	0.00014	118.4	27.4	0.03 0.00	93 0.1	233.7	0.00144	0.00019	0.01239	0.00173	207	0.38 0.0	0002 0.88	98 0.00	0.01	46 0.0021	0.0007
51 MMV-lo-RAS PL-NP20 SC01 Treated 33.96 6.33 3.32 0.18 154.9 0.0136 0.0037 0.1831 88.8 0.00010 80.1 0.00339 0.0031 0.00309 0.0031 0.00309 0.0031 0.00309 0.0031 0.00309 0.0031 0.00309 0.0031 0.00309 0.0031 0.00309 0.0031 0.00309 0.0031 0.00309 0.0031 0.00309 0.0031 0.00309 0.0031 0.00309 0.0031 0.00309 0.0031 0.00309 0.0031 0.00309 0.00	50	MIW-to-RAS PL-NP20	GOOT ITEMES					10-712	0.0140	0,0000	0.1120																										
53 MMV-lo-RAS PL-NP20 SC01 Treated 33.95 6.30 334 0.19 155.0 0.0134 0.0036 0.103 89.6 0.00010 81.0 0.00029 0.097 1.38 0.0020 0.00029 0.97 1.38 0.06 0.00015 110.9 26.9 0.03 0.0091 0.10 221.2 0.00142 0.00020 0.01179 0.00173 199 0.39 0.0020 0.0185 0.0030 0.0030 0.0030 0.0030 0.00029 0.98 1.37 0.06 0.00014 110.9 0.00170 10.8 26.6 0.02 0.0092 0.0186 0.00029 0.0186 0.00029 0.00030 0.00	51	MIW-to-RAS PL-NP20	SC01 Treated	38.96	6.33	332	0.18	154.9	0.0136	0.0036	0.1833	88.88	0.00010	80.1	0.00039	0.00031	0.00030	0.99	1.37	0.06	0.00015	111.2	26.7	0.03 0.00	94 0.1	221.7	0.00140	0.00020	0.01189	0.00175	199	0.39 0.0	0002 0.92	73 0.00	029 0.01	40 0.0020	0.0007
55 MM·lo-RAS PL-NP20 SC01 Treated 33.39 6.30 330 0.18 154.7 0.0135 0.0036 0.1744 88.5 0.00010 79.2 0.00038 0.00030 0.098 1.37 0.06 0.00015 108.8 26.6 0.02 0.0092 0.10 216.5 0.00139 0.00020 0.01167 0.00174 196 0.39 0.0020 0.2858 0.0029 0.0135 0.0001 0.0007 0.00075 0.0007						335																															
56 MMV-lo-RAS PL-NP20 SC01 Treated 36.22 6.31 330 0.18 154.7 0.0133 0.0036 0.1688 88.3 0.00010 78.6 0.00037 0.00030 0.0031 0.0037 0.00030 0.003 0.00 0.0015 106.9 26.5 0.02 0.0090 0.10 213.0 0.0018 0.00020 0.01147 0.00174 193 0.39 0.0022 0.9286 0.0029 0.0133 0.0019 0.0007	54	MIW-to-RAS PL-NP20	SC01 Treated	33.39	6.30	330	0.18	154.7	0.0135	0.0036	0.1744	88.5	0.00010	79.2	0.00038	0.00030	0.00030	0.98	1.37	0.06	0.00015	108.8	26.6	0.02 0.00	92 0.1	216.5	0.00139	0.00020	0.01167	0.00174	196	0.39 0.0	0002 0.92	58 0.00	029 0.01	36 0.0019	0.0007
	55	MIW-to-RAS PL-NP20		29.44	6.27	340		155.5				91.0	0.00010	82.8 78.6	0.00037	0.00029	0.00028	0.94	1.42	0.06	0.00014	112.8	27.4	0.03 0.00	90 0.1	223.5	0.00144	0.00019	0.01177	0.00170	200	0.38 0.0	0002 0.88	45 0.00	0.01	36 0.0020	0.0007
	57							155.0	0.0136	0.0036	0.1696	89.5	0.00010	80.3	0.00036	0.00030	0.00029	0.96	1.40	0.06	0.00015	108.8	26.9	0.02 0.00	92 0.1	215.9	0.00140	0.00019	0.01168	0.00174	197	0.38 0.0	0002 0.89	93 0.00	030 0.01	35 0.0019	0.0007

Year	Scenario	Station	Flow Rate (L/s)	рН	Hardness (mg CaCO3/L)	Acidity (mg CaCO3/L)	Alkalinity (mg CaCO3/L)	Al (mg/L)	As (mg/L)				CI mg/L)	Co (mg/L)	Cr (mg/L)	Cu (mg/L)	DOC (mg/L)		e g/L)	Hg (mg/L) (Mn Mo mg/L) (mg/L	NO3-N (mg/L)	Na (mg/L)	NI (mg/L)	Pb (mg/L)	Sb (mg/L)	Se (mg/L)		Sr T			U (mg/L)	V Zn (mg/L) (mg/L)
58	MW-to-RAS PL-NP20	SC01 Treated	29.69	6.24	351	0.21	156.3	0.0124	0.0037	0.1784	93.8 0.	.00010	86.6	0.00036	0.00027	0.00026	0.87	1.49	0.06	0.00014	116.2	28.3	0.03 0.008	1 0.09	228.8	0.00149	0.00019	0.01189	0.00163	205	0.36 0.0	002 0.827	8 0.0032	0.0136	0.0020 0.0006
	10 10 10 1 2 111 20	SC01 Treated	37.36		326	0.18	154.1	0.0142	0.0036							0.00030				0.00015			0.02 0.009												0.0018 0.0007
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Treated SC01 Treated	27.91 27.83	6.22	354 357	0.21 0.21			0.0038		94.6 0. 95.4 0.				0.00027	0.00026	0.85			0.00013			0.03 0.008 0.03 0.006			0.00151									0.0020 0.0006 0.0020 0.0006
	MW-to-RAS PL-NP20	SC01 Treated	21.52	6.19	373	0.23			0.0038	0.1852	99.8 0.	.00010	95.7	0.00035	0.00024	0.00024	0.78	1.59	0.07	0.00013	120.7	30.2	0.03 0.007	4 0.08	240.3	0.00163	0.00018	0.01206	0.00152	214	0.33 0.0	002 0.736	4 0.0036	0.0136	0.0021 0.0005
63	MW-to-RAS PL-NP20	SC01 Treated SC01 Treated	32.01		318 331	0.17 0.19			0.0035		85.4 0				0.00032					0.00016		25.3	0.02 0.008	0.10		0.00132									0.0017 0.0007
65	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Treated SC01 Treated	33.00	6.30	313	0.19			0.0033		88.8 0. 84.2 0.	.00010	71.0	0.00033	0.00030	0.00028	1.05			0.00015	92.4	25.0	0.02 0.006 0.02 0.009	0.09	187.4	0.00137	0.00020	0.01029	0.00172	180					0.0018 0.0007 0.0017 0.0008
66	MW-to-RAS PL-NP20	SC01 Treated	26.89	6.24	348	0.21			0.0036	0.1595	93.3 0.	.00010	84.7	0.00033	0.00028	0.00027	0.89				106.1	28.0	0.02 0.007	1 0.09	213.6	0.00147	0.00019	0.01084	0.00163	192					0.0018 0.0006
67	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Treated SC01 Treated	30.07 32.44	6.29	331 331	0.19			0.0034		88.9 0				0.00030	0.00029	0.98			0.00015			0.02 0.007			0.00138									0.0017 0.0007 0.0017 0.0007
69	MW-to-RAS PL-NP20	SC01 Treated	19.24	6.17	381	0.24	159.8	0.0111	0.0038	0.1735	101.8 0.	.00010	97.2	0.00032	0.00023	0.00022	0.73	1.63	0.07	0.00012	117.8	30.7	0.03 0.006	5 0.08	235.4	0.00165	0.00018	0.01158	0.00145	211	0.32 0.0	002 0.697	0.0037	0.0129	0.0020 0.0005
70	MW-to-RAS PL-NP20	SC01 Treated SC01 Treated	27.85	6.30	326 301	0.18 0.16			0.0034		87.7 O. 81.1 O.	.00010	75.7	0.00031	0.00031	0.00030	1.00	1.31	0.06				0.02 0.007		190.4	0.00135	0.00020	0.00996	0.00171						0.0017 0.0007 0.0015 0.0008
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Treated		6.22		0.10		0.0143			94.6 0.				0.00034		0.86						0.02 0.008			0.00122									0.0018 0.0006
	MW-to-RAS PL-NP20	SC01 Treated	28.20	6.29	328	0.19			0.0036	0.1365	88.1 0.	.00010	76.2	0.00030	0.00031	0.00030	1.00	1.31	0.06	0.00015	91.0	26.2	0.02 0.008	3 0.10	188.5	0.00136	0.00020	0.01008		176	0.39 0.0	002 0.940	0.0029	0.0114	0.0016 0.0007
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Treated SC01 Treated	23.80 20.42		342 352	0.20		0.0130	0.0037		91.7 0. 94.4 0.			0.00030		0.00028	0.92			0.00014			0.02 0.008			0.00144									0.0017 0.0007 0.0017 0.0006
	MW-to-RAS PL-NP20	SC01 Treated	29.33	6.36	311	0.17	154.7	0.0127	0.0033	0.1231	83.8 0.	.00010	69.1	0.00029	0.00034	0.00032	1.09	1.18	0.06	0.00017	80.3	24.6	0.02 0.007	5 0.10	171.2	0.00127	0.00021	0.00906	0.00178	159	0.42 0.0	002 1.038	0.0026	0.0103	0.0015 0.0008
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Treated SC01 Treated	36.22 36.33		306 311	0.17			0.0034		82.3 0. 83.7 0.				0.00034	0.00032	1.09			0.00017			0.02 0.008			0.00123									0.0015 0.0008
	MW-to-RAS PL-NP20	SC01 Treated	28.50	6.24	342	0.17			0.0037							0.00032	0.92			0.00014			0.02 0.008												0.0016 0.0007
	MIW-to-RAS_PL-NP20 MIW-to-RAS_PL-NP20	SC01 Treated SC01 Treated	30.63	6.28	328	0.19	155.2		0.0036	0.1283	88.3 0.	.00010	76.1	0.00028	0.00031	0.00030	0.99	1.28	0.06	0.00015	86.1	26.2	0.02 0.008	3 0.10	181.5	0.00137	0.00020	0.00964	0.00164	172	0.39 0.0	002 0.932	0.0029	0.0109	0.0015 0.0007
	MIW-to-RAS_PL-NP20 MIW-to-RAS_PL-NP20	SC01 Treated SC01 Treated	32.28 37.66	6.26	335 322	0.20 0.19			0.0036		90.0 0. 86.6 0.	.00010	73.7	0.00028	0.00029 0.00031	0.00028	1.01			0.00014 0.00015			0.02 0.008 0.02 0.008			0.00140 0.00134					0.39 0.0	0.883	5 0.0028	0.0110	0.0016 0.0007 0.0015 0.0007
		SC01 Treated		6.24		0.21			0.0036			.00010					0.91						0.02 0.007			0.00144									0.0016 0.0006
	MIW-to-RAS_PL-NP20 MIW-to-RAS_PL-NP20	SC01 Treated SC01 Treated	36.22 51,53	6.29	327 301	0.19 0.17			0.0034		87.9 0. 81.3 0.				0.00031	0.00030	1.00			0.00015			0.02 0.006 0.02 0.009			0.00136									0.0015 0.0007 0.0013 0.0008
86	MW-to-RAS PL-NP20	SC01 Treated	30.73	6.21	355	0.22	156.0	0.0127	0.0038	0.1344	95.2 0.	.00010	86.6	0.00026	0.00026	0.00025	0.83	1.39	0.06	0.00013	92.7	28.5	0.02 0.007	4 0.09	194.6	0.00152	0.00018	0.00982	0.00145	184	0.34 0.0	002 0.782	5 0.0033	0.0109	0.0016 0.0006
87	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Treated SC01 Treated	37.91 33.91	6.29	322 329	0.19 0.20			0.0036		86.7 0. 88.5 0.				0.00031		1.00 0.97						0.02 0.008 0.02 0.007			0.00135 0.00138									0.0014 0.0007 0.0014 0.0007
89	MW-to-RAS PL-NP20	SC01 Treated	30.12	6.24	346	0.21	154.8	0.0126	0.0037	0.1272	92.8 0.	.00010	83.3	0.00026	0.00028	0.00027	0.88	1.30	0.06	0.00014	85.4	27.6	0.02 0.007	2 0.09	184.2	0.00148	0.00019	0.00920	0.00150	174	0.36 0.0	002 0.835	5 0.0032	0.0102	0.0015 0.0006
90	MW-to-RAS PL-NP20	SC01 Treated SC01 Treated	35.38 25.97		313 349	0.18			0.0035		84.3 0	.00010			0.00032		1.05						0.02 0.008			0.00130									0.0013 0.0007
91	MW-to-RAS PL-NP20 MW-to-RAS PL-NP20	SC01 Treated		6.20		0.22			0.0038			.00010								0.00014			0.02 0.006			0.00149									0.0015 0.0006
93	MW-to-RAS PL-NP20	SC01 Treated	23.03	6.24	339	0.21	155.3		0.0037		91.3 0.				0.00028		0.91						0.02 0.007		175.9	0.00144									0.0014 0.0006
	MW-to-RAS PL-NP20 MW-to-RAS PL-NP20	SC01 Treated SC01 Treated	35.74 37.37	6.34	299 320	0.17			0.0033		80.8 0. 86.1 0				0.00034	0.00033	1.10			0.00016	66.1 72.2	25.4	0.02 0.008 0.02 0.007	0.10		0.00121					0.42 0.0	002 1.038	0.0025	0.0091	0.0012 0.0008 0.0013 0.0007
96	//////////////////////////////////////	SC01 Treated	31.33	6.27	335	0.20			0.0036		90.2 0	.00010	78.9	0.00025	0.00029	0.00028	0.93	1.18	0.06	0.00014	76.6	26.7	0.02 0.007	4 0.09	170.7	0.00142	0.00019	0.00856	0.00152	164	0.37 0.0	002 0.877	0.0030	0.0096	0.0013 0.0007
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Treated SC01 Treated	30.73 23.98	6.30	318 345	0.18 0.21			0.0035		85.6 0. 92.7 0.				0.00032		1.02 0.87			0.00016			0.02 0.007 0.02 0.006			0.00132									0.0013 0.0007 0.0014 0.0006
	MW-to-RAS PL-NP20	SC01 Treated	25.61		340	0.21			0.0035		91.5 0			0.00024		0.00027	0.07	1.17	0.06	0.00014	75.6		0.02 0.005	B 0.09	170.8	0.00144	0.00019	0.00797	0.00151	160		002 0.873			
	MW-to-RAS PL-NP20	SC01 Treated	42.56		292	0.16			0.0036			.00010					1.15			0.00017			0.02 0.010			0.00119									0.0011 0.0008
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Treated SC01 Treated	26.70	6.22	350 332	0.22		0.0116	0.0037		93.8 0. 89.3 0.				0.00026		0.84			0.00013			0.02 0.006			0.00148									0.0013 0.0006 0.0013 0.0007
	MW-to-RAS PL-NP20	SC01 Treated	26.38	6.21	343	0.21			0.0037		92.2 0.				0.00027		0.87						0.02 0.007			0.00146				166	0.35 0.0	002 0.814	9 0.0032	0.0094	0.0013 0.0006
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Treated SC01 Treated	28.47 38.06	6.25	332 315	0.20		0.0140	0.0037	0.1116	89.4 0. 84.8 0.			0.00024	0.00029	0.00028	1.03	1.11	0.06	0.00014	71.0 64.0	26.5	0.02 0.008	3 0.09 5 0.10	163.0	0.00141	0.00019	0.00837				002 0.870			0.0012 0.0007 0.0012 0.0007
		SC01 Treated	28.37	6.24	335	0.21			0.0036	0.1110	90.0 0.	.00010	78.4	0.00024	0.00029	0.00028	0.92	1.10	0.06	0.00014	70.2	26.7	0.02 0.006	9 0.09	162.5	0.00141				157	0.36 0.0	002 0.872	0.0030	0.0088	0.0012 0.0007
	MIW-to-RAS_PL-NP20 MIW-to-RAS_PL-NP20	SC01 Treated SC01 Treated	33.28 27.35	6.30	319 336	0.19 0.21			0.0035		90.4 0	.00010			0.00031		1.01 0.91			0.00015			0.02 0.007			0.00133									0.0012 0.0007 0.0012 0.0006
109	MIW-to-RAS_PL-NP20	SC01 Treated	29.20	6.28	323	0.19	153.8	0.0131	0.0035	0.1056	87.2 0.	.00010	74.2	0.00024	0.00031	0.00030	0.99	1.01	0.06	0.00015	64.0	25.6	0.02 0.007	3 0.09	153.0	0.00136	0.00020	0.00749	0.00155	149	0.38 0.0	002 0.937	0.0029	0.0085	0.0011 0.0007
110		SC01 Treated SC01 Treated	21.36	6.20	354 318	0.22		0.0121	0.0037		95.3 O. 85.8 O.				0.00026	0.00025	0.83			0.00013			0.02 0.006 0.02 0.008			0.00153									0.0012 0.0006 0.0011 0.0007
112	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Treated	26.07	6.25	331	0.20	155.2	0.0130	0.0036	0.1073	89.2 0.	.00010	76.9	0.00023	0.00029	0.00028	0.93	1.04	0.06	0.00014	65.7	26.4	0.02 0.007	2 0.09	156.4	0.00139	0.00019	0.00759	0.00147	153	0.36 0.0	002 0.880	0.0030	0.0086	0.0011 0.0007
113	MW-to-RAS PL-NP20	SC01 Treated SC01 Treated		6.33		0.18 0.18			0.0033		83.1 0. 82.2 0.				0.00033		1.06				57.6 56.6	24.4	0.02 0.006	9 0.10		0.00126									0.0011 0.0008 0.0010 0.0008
115	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Treated		6.22	346	0.10			0.0037			.00010					0.85	1.08	0.06	0.00013	68.5	27.7	0.02 0.006	6 0.09	163.5	0.00148	0.00019	0.00753	0.00137	159					0.0012 0.0006
116	MW-to-RAS PL-NP20	SC01 Treated SC01 Treated	31.26	6.25 6.26	342 339	0.21			0.0036		92.1 0. 91.4 0.				0.00028	0.00027	0.89	1.04			65.7	27.3	0.02 0.006 0.02 0.005	0.09	159.8	0.00146	0.00019	0.00714	0.00142	154 150					0.0011 0.0006 0.0011 0.0006
117	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Treated SC01 Treated		6.26		0.21			0.0035		91.4 0. 85.6 0.					0.00027	1.00						0.02 0.005		157.3	0.00145	0.00019	0.00693	0.00145	142					0.0011 0.0006
119	MW-to-RAS PL-NP20	SC01 Treated	30.91	6.28	323	0.19			0.0035	0.1023	87.1 0.	.00010	74.0	0.00023	0.00030	0.00029	0.98	0.94	0.06	0.00015	58.8	25.6	0.02 0.006	B 0.09	146.8	0.00136	0.00020	0.00687	0.00151	144	0.38 0.0	002 0.928	0.0029	0.0079	0.0010 0.0007
120	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Treated SC01 Treated	33.09 30.37	6.28	318 331	0.19 0.20			0.0035		85.9 O. 89.2 O		72.1	0.00023	0.00031	0.00030	0.99	0.92		0.00015			0.02 0.006 0.02 0.006		143.7	0.00133	0.00020	0.00681	0.00152	141	0.38 0.0	002 0.942	0.0028	0.0079	0.0010 0.0007 0.0010 0.0007
122	MW-to-RAS PL-NP20	SC01 Treated	30.36	6.27	328	0.20	154.0	0.0130	0.0036	0.1036	88.3 0.	.00010	75.9	0.00023	0.00030	0.00029	0.96	0.94	0.06	0.00015	58.4	26.0	0.02 0.007	0.09	147.8	0.00139	0.00019	0.00687	0.00147	146	0.37 0.0	002 0.903	7 0.0030	0.0079	0.0010 0.0007
	MW-to-RAS PL-NP20 MW-to-RAS PL-NP20	SC01 Treated SC01 Treated	32.99 25.93	6.30		0.19 0.21			0.0034		86.2 0. 90.9 0.				0.00031		0.99	0.90	0.06	0.00015			0.02 0.006 0.02 0.006			0.00134				139	0.38 0.0	002 0.945	0.0028	0.0076	0.0010 0.0007 0.0010 0.0006
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Treated SC01 Treated	33.80	6.32	306	0.21		0.0121			82.6 0				0.00028		1.06				51.5	24.2	0.01 0.007	4 0.10		0.00144									0.0010 0.0008
	MW-to-RAS PL-NP20	SC01 Treated	37.53		303	0.18			0.0035		81.8 0.				0.00033		1.06						0.01 0.007			0.00125									0.0009 0.0008
128	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Treated SC01 Treated	35.89 27.26	6.27	326 342	0.20	153.1 154.2	0.0135	0.0036	0.1022	87.8 0. 91.9 0.	.00010		0.00022	0.00029	0.00029	0.95			0.00014			0.02 0.007 0.02 0.005			0.00138	0.00019		0.00144			002 0.890			0.0010 0.0007 0.0010 0.0006
129	MW-to-RAS PL-NP20	SC01 Treated	30.20	6.24	339	0.21		0.0121	0.0036	0.1069	91.4 0.	.00010	80.8	0.00022	0.00028	0.00027	0.89	0.93	0.06	0.00014	57.9	27.0	0.02 0.006	0.09	150.6	0.00146	0.00019	0.00645	0.00138	147	0.35 0.0	002 0.846	1 0.0032	0.0075	0.0010 0.0006
		SC01 Treated SC01 Treated	30.82 33.80		314 308	0.19 0.18			0.0035		84.9 0. 83.3 0.				0.00031		1.01						0.01 0.007			0.00132									0.0009 0.0007 0.0009 0.0007
132	MW-to-RAS_PL-NP20	SC01 Treated	34.10	6.29	312	0.19	151.9	0.0141	0.0036	0.0961	84.1 0.	.00010	70.1	0.00023	0.00031	0.00031	1.01	0.82	0.06	0.00015	50.3	24.7	0.01 0.008	0.10	134.3	0.00131	0.00020	0.00655	0.00150	137	0.38 0.0	002 0.948	0.0027	0.0077	0.0009 0.0007
	MIW-to-RAS_PL-NP20 MIW-to-RAS_PL-NP20	SC01 Treated SC01 Treated	37.10	6.27	317 348	0.19		0.0132		0.0974	85.4 O	.00010			0.00030	0.00029	0.98	0.83	0.06	0.00015	51.3	25.1	0.01 0.007	1 0.10 5 0.09		0.00133				137	0.37 0.0	002 0.925	0.0028	0.0074	0.0009 0.0007 0.0010 0.0006
135	MW-to-RAS PL-NP20	SC01 Treated	35.84	6.27	332	0.21		0.0	0.0035	0.1031	89.4 0.	.00010			0.00029		0.92	0.86	0.06	0.00014	53.2	26.4	0.02 0.005	0.09	143.4	0.00142	0.00019	0.00598	0.00141	140	0.36 0.0	002 0.875	7 0.0031	0.0070	0.0009 0.0007
136	MW-to-RAS PL-NP20	SC01 Treated SC01 Treated	25.89	6.21	351 336	0.23			0.0035		94.3 0. 90.7 0.	.00010	85.2	0.00021	0.00026	0.00025	0.83				57.0	27.9	0.02 0.004	5 0.08		0.00153									0.0010 0.0006
138	MW-to-RAS PL-NP20 MW-to-RAS PL-NP20	SC01 Treated SC01 Treated	30.12	6.32	303	0.21		0.0118		0.0924	82.0 0.	.00010	67.0	0.00023	0.00033	0.00032	1.06						0.02 0.005			0.00145									0.0009 0.0006
139	MW-to-RAS PL-NP20	SC01 Treated	32.83	6.33	307	0.18	151.8	0.0121	0.0033	0.0928	82.9 0.	.00010	67.8	0.00023	0.00032	0.00031	1.05	0.75	0.06	0.00016	45.2	24.2	0.01 0.006	0.10	127.9	0.00128	0.00020	0.00549	0.00157	125	0.39 0.0	002 1.006	5 0.0027	0.0066	0.0009 0.0008
140	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Treated SC01 Treated		6.36		0.16			0.0034		77.5 0. 92.1 0.	.00010				0.00034				0.00017 0.00014			0.01 0.008 0.02 0.005			0.00117									0.0008 0.0008
142	MW-to-RAS PL-NP20	SC01 Treated	35.33	6.30	314	0.19	151.7	0.0131	0.0035	0.0962	84.9 0.	.00010	71.3	0.00023	0.00031	0.00030	1.01	0.76	0.06	0.00015	45.9	24.8	0.01 0.006	9 0.10	131.0	0.00133	0.00020	0.00579	0.00150	131	0.38 0.0	002 0.960	7 0.0028	0.0069	0.0008 0.0007
143	MW-to-RAS PL-NP20	SC01 Treated	26.44	6.20	347	0.23	154.5	0.0127	0.0038	0.1083	93.4 0.	.00010	84.0	u.00021	U.00025	u.00025	0.82	0.87	u.07	u.00013	54.0	27.7	0.02 0.006	0.08	148.3	0.00151	0.00018	0.00619	0.00125	148	u.33 0.0	0.770	o.0033	0.0072	0.0009 0.0006

Year	Scenario	Station	Flow Rate (L/s)	рН	Hardness (mg CaCO3/L)	Acidity (mg CaCO3/L)	Alkalinity (mg CaCO3/L)	AI (mg/L)	As (mg/L)	B (mg/L)	Ca (mg/L)	Cd (mg/L)	CI (mg/L)	Co (mg/L)	Cr (mg/L)	Cu (mg/L)	DOC (mg/L)		Fe ig/L)	Hg (mg/L) (m		Mg M ng/L) (mg		NO3-N (mg/L)	Na (mg/L)	NI (mg/L)	Pb (mg/L)	Sb (mg/L)	Se (mg/L)		Sr TI g/L) (mg/L	TOC (mg/L)	CN (mg/L)	U (mg/L) (I	V Zn mg/L) (mg/L)
	MIW-to-RAS_PL-NP20	SC01 Treated	32.34		316	0.19		0.0128		0.0961		0.00010			0.00030	0.00029	0.98						.01 0.006					0.00569			0.37 0.000				0.0008 0.0007
	MIW-to-RAS_PL-NP20	SC01 Treated SC01 Treated	24.04	6.18	358 299	0.24		0.0118	0.0038	0.1126		0.00010			0.00024								.02 0.005					0.00590			0.31 0.000				0.0009 0.0005
145	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Treated		6.30					0.0034			0.00010			0.00033					0.00016			.01 0.006					0.00599							0.0008 0.0007
148	MIW-to-RAS PL-NP20	SC01 Treated	32.28	6.25	322	0.20		0.0134			86.9	0.00010	74.5	0.00022	0.00029	0.00029	0.94				46.3	25.6 0	.01 0.007	1 0.09	133.2	0.00137		0.00583		135	0.36 0.000	0.8890	0.0029	0.0070 0	0.0008 0.0007
149	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Treated SC01 Treated	35.34	6.29 6.24	305 326	0.18 0.20		0.0146	0.0036	0.0929		0.00010			0.00032								.01 0.008					0.00594							0.0008 0.0007
151	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Treated		6.30	316	0.20		0.0137		0.0966		0.00010			0.00029								.01 0.007					0.00569							0.0008 0.0007
152	MIW-to-RAS PL-NP20	SC01 Treated		6.28			101.2		0.0036						0.00030					0.00015			.01 0.007					0.00575							0.0008 0.0007
153	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Treated SC01 Treated	34.37 33.78	6.28 6.28		0.20		0.0135		0.0977		0.00010			0.00030		0.97						.01 0.007					0.00558							0.0008 0.0007
155	MIW-to-RAS PL-NP20	SC01 Treated	29.77	6.25	324	0.20			0.0036			0.00010			0.00029						43.8	25.7 0	.01 0.006	6 0.09				0.00544							0.0008 0.0007
156	MIW-to-RAS PL-NP20	SC01 Treated SC01 Treated		6.29	314 319				0.0036			0.00010			0.00030		0.98			0.00015			.01 0.007					0.00545							0.0008 0.0007
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Treated		6.22					0.0036			0.00010			0.00030								.01 0.007					0.00530							0.0008 0.0007
	MIW-to-RAS PL-NP20	SC01 Treated	37.61	6.29	311	0.19	150.4		0.0036		84.1	0.00010	70.8	0.00022	0.00031	0.00030	1.00	0.67	0.06	0.00015	39.9	24.6	.01 0.007	9 0.10	123.9	0.00133	0.00020	0.00555	0.00143	129	0.000	0.9367	0.0028	0.0068	0.0007 0.0007
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Treated SC01 Treated	28.08		338				0.0038	0.1044		0.00010			0.00027		0.85						.01 0.006					0.00549			0.33 0.000				0.0008 0.0006
		SC01 Treated		6.22		0.22		0.0111	0.0038			0.00010			0.00027		0.85						.01 0.004					0.00479			0.33 0.000				0.0008 0.0006
163	MIW-to-RAS PL-NP20	SC01 Treated	32.10	6.33	305	0.18	150.5	0.0135	0.0035	0.0922	82.4	0.00010	68.1	0.00022	0.00032	0.00031	1.05	0.63	0.06	0.00016	36.8	24.0 0	.01 0.007	2 0.10	119.2	0.00129	0.00020	0.00510	0.00149	122	0.000	0.9889	0.0027	0.0064	0.0007 0.0007
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Treated SC01 Treated	30.69	6.28	317 300			0.0111	0.0033	0.0951		0.00010			0.00030		0.97						0.004					0.00449							0.0007 0.0007
	MIW-to-RAS_PL-NP20	SC01 Treated	26.90	6.23	333			0.0137		0.1021		0.00010			0.00032		0.89						.01 0.005					0.00312							0.0007 0.0006
	MIW-to-RAS_PL-NP20	SC01 Treated	30.08	6.28	317	0.19			0.0034			0.00010			0.00030								.01 0.005	8 0.09	124.0			0.00472							0.0007 0.0007
	MIW-to-RAS_PL-NP20 MIW-to-RAS_PL-NP20	SC01 Treated SC01 Treated		6.29	317 364	0.19 0.24			0.0034			0.00010			0.00030		0.98						.01 0.005					0.00471			0.36 0.000				0.0007 0.0007
170	MIW-to-RAS_PL-NP20	SC01 Treated	27.85	6.29	313	0.19	151.8	0.0124	0.0034	0.0945	84.7	0.00010	70.9	0.00022	0.00031	0.00030	1.00	0.62	0.06	0.00016	36.4	24.7 0	.01 0.006	1 0.09	121.0	0.00133	0.00020	0.00467	0.00144	121	0.37 0.000	0.9556	0.0028	0.0059	0.0007 0.0007
	MIW-to-RAS PL-NP20	SC01 Treated SC01 Treated		6.36	289 338	0.16		0.0145		0.0861		0.00010			0.00034		1.12 0.86						.01 0.008					0.00510							0.0007 0.0008
173	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Treated	28.20	6.29	315	0.19			0.0036			0.00010			0.00026					0.00015	36.1		.01 0.006	9 0.09	121.2			0.00488							0.0007 0.0007
174	MIW-to-RAS PL-NP20	SC01 Treated	23.80	6.25	328	0.20	153.5	0.0130		0.1002		0.00010			0.00029		0.92						.01 0.006					0.00490							0.0007 0.0007
175	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Treated SC01 Treated		6.22					0.0035			0.00010			0.00027								.01 0.004					0.00442							0.0007 0.0006
177	MIW-to-RAS PL-NP20	SC01 Treated		6.35	294	0.17			0.0034						0.00034								.01 0.007					0.00470							0.0006 0.0008
178	MIW-to-RAS PL-NP20	SC01 Treated		6.31	299				0.0034						0.00033					0.00016	32.6							0.00478							0.0006 0.0008
179	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Treated SC01 Treated	28.50 30.63	6.24 6.27	329 316	0.21	153.0 151.9		0.0037	0.1009	85.8	0.00010	77.3	0.00021	0.00028	0.00028	0.92	0.63 0.59	0.06	0.00014 0.00015	37.4 34.8	26.1 0	.01 0.007	0.09	126.5	0.00143	0.00019	0.00494	0.00130	130	0.34 0.000	0.8629	0.0031	0.0062 0	0.0007 0.0007
181	MIW-to-RAS PL-NP20	SC01 Treated	32.28	6.26	323	0.20			0.0036		87.0	0.00010	74.6	0.00021	0.00029	0.00028	0.94	0.61	0.06	0.00014	36.0	25.6 0	.01 0.006	8 0.09	122.8	0.00138	0.00019	0.00478	0.00133	126	0.35 0.000	0.8838	0.0030	0.0061	0.0006 0.0007
	MIW-to-RAS PL-NP20	SC01 Treated		6.29		0.19			0.0036			0.00010			0.00031		1.01			0.00015			.01 0.007					0.00487							0.0006 0.0007
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Treated SC01 Treated		6.24	329 315				0.0036			0.00010			0.00028		1.00						.01 0.006					0.00454							0.0006 0.0006
	MIW-to-RAS PL-NP20	SC01 Treated	51.53	6.37	291	0.17	149.1	0.0153	0.0036	0.0872	78.8	0.00010	62.9	0.00023	0.00034	0.00033	1.10	0.52	0.06	0.00016	29.8	22.9 0	.01 0.008	8 0.11	107.6	0.00122	0.00020	0.00504	0.00151	117	0.40 0.000	1.0279	0.0025	0.0064	0.0008
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Treated SC01 Treated	30.73	6.20	342 311	0.23		0.0127	0.0037	0.1056		0.00010			0.00026		1.00			0.00013			.01 0.006					0.00460							0.0006 0.0006
	MIW-to-RAS PL-NP20	SC01 Treated		6.26	318				0.0035			0.00010			0.00030								.01 0.006					0.00473							0.0006 0.0007
	MIW-to-RAS PL-NP20	SC01 Treated	30.12	6.23	334				0.0037			0.00010			0.00027								.01 0.006					0.00440							0.0006 0.0006
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Treated SC01 Treated	35.38 25.97	6.31	303 337	0.18		0.0135	0.0035	0.0913		0.00010			0.00032		1.05 0.85						.01 0.007				0.00020	0.00442				0.9893			0.0006 0.0007
	MIW-to-RAS_PL-NP20	SC01 Treated	22.72	6.20	341	0.22		0.0125		0.1058		0.00010			0.00026		0.84						.01 0.005					0.00440			0.31 0.000				0.0006 0.0006
	MIW-to-RAS_PL-NP20 MIW-to-RAS_PL-NP20	SC01 Treated SC01 Treated		6.24	328 290			0.0128	0.0037	0.1010		0.00010			0.00028		0.91			0.00014			.01 0.006					0.00436							0.0006 0.0006
	MIW-to-RAS PL-NP20	SC01 Treated	37.37		310	0.17	150.3			0.0933		0.00010			0.00034		1.00						.01 0.006					0.00431							0.0006 0.0007
	MIW-to-RAS PL-NP20	SC01 Treated		6.27	325				0.0036			0.00010			0.00029		0.93						.01 0.006					0.00433							0.0006 0.0007
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	SC01 Treated SC01 Treated		6.30	308 334				0.0035			0.00010			0.00031								.01 0.006					0.00428							0.0006 0.0007
199	MIW-to-RAS PL-NP20	SC01 Treated	25.61	6.25		0.21	152.5	0.0114	0.0035	0.1005	89.1	0.00010	77.6	0.00021	0.00028	0.00027	0.91	0.57	0.06	0.00014	32.9	26.1 0	.01 0.004	8 0.09	122.5	0.00143	0.00019	0.00382	0.00130	120	0.000	0.8730	0.0031	0.0051	0.0006
	MIW-to-RAS PL-NP20	RS03 Untreated RS03 Untreated	23.45	6.57	60 113	0.02			0.0069			0.00007	2.6	0.00033	0.00043	0.00065	1.73	0.10 0.27	0.26		3.7 16.4	4.5 0	.01 0.008	0 0.80 9 2.89	12.7	0.00052	0.00024	0.01090	0.00193	24	0.24 0.000	1.6651	0.0000	0.0029 0	0.0008 0.0015
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	RS03 Untreated		6.56					0.0218			0.00007			0.00044							10.5 0	.02 0.018	3 2.64	36.3			0.05917							0.0026 0.0016
3	MIW-to-RAS PL-NP20	RS03 Untreated		6.50		0.10			0.0238		27.9	0.00007	6.2		0.00045		1.27	0.31	1.03	0.00017	19.5	11.1 0	.02 0.022	7 2.99	39.1	0.00061	0.00048	0.07240	0.00503	42					0.0031 0.0016
5	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	RS03 Untreated RS03 Untreated		6.53 6.57	114 106	0.10		0.0177	0.0232	0.0329		0.00007			0.00045		1.29				18.8 16.6		.02 0.022		38.3			0.07039 0.06148							0.0030 0.0016 0.0027 0.0016
- 6	MIW-to-RAS PL-NP20	RS03 Untreated	15.66	6.55	109	0.09	109.0	0.0168	0.0214	0.0306	26.7	0.00007	5.7	0.00105	0.00045	0.00074	1.39	0.29	0.91	0.00017	17.2	10.2 0	.02 0.019	8 2.56	35.1	0.00059	0.00043	0.06427	0.00462	37	0.64 0.000	1.3703	0.0000	0.0064	0.0028 0.0016
7	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	RS03 Untreated		6.57	108				0.0210			0.00007			0.00045			0.28					.02 0.018					0.06068							0.0026 0.0016
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	RS03 Untreated RS03 Untreated		6.54	111 110	0.09		0.0171	0.0221	0.0303		0.00007			0.00045								.02 0.019					0.06370 0.05911							0.0027 0.0016
10	MIW-to-RAS PL-NP20	RS03 Untreated	11.91	6.56	120	0.09	123.8	0.0165	0.0238	0.0314	29.3	0.00007	6.4	0.00095	0.00046	0.00072	1.27	0.31	0.93	0.00017	17.4	11.5 0	.02 0.019	2 2.43	38.4	0.00057	0.00044	0.06481	0.00470	37	0.65 0.000	1.2601	0.0000	0.0063	0.0028 0.0016
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	RS03 Untreated RS03 Untreated	16.41	6.55	112 115	0.09	114.8	0.0171		0.0295		0.00007		0.00081	0.00046	0.00072	1.31	0.28					.02 0.017			0.00056		0.05503				1.2914			0.0024 0.0016
	MIW-to-RAS PL-NP20	RS03 Untreated		6.56	104			0.0174		0.0300		0.00007			0.00046		1.40				14.8		.02 0.016					0.05405							0.0027 0.0016
	MIW-to-RAS PL-NP20	RS03 Untreated	21.90		101	0.09		0.0172		0.0267		0.00007			0.00044		1.45				14.7		.02 0.016					0.05397							0.0024 0.0016
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	RS03 Untreated RS03 Untreated	16.50 17.93	6.52	112 113	0.10	111.8 114.9		0.0233	0.0288	27.4	0.00007	5.8 5.9		0.00044	0.00075	1.34						.02 0.019			0.00056	0.00046	0.06631				1.3280 12 1.3118			0.0028 0.0016
17	MIW-to-RAS_PL-NP20	RS03 Untreated	17.10	6.58	114	0.09	116.6	0.0162	0.0224	0.0283	27.9	0.00007	5.9	0.00071	0.00045	0.00072	1.34	0.29	0.89	0.00017	15.5	10.7 0	.02 0.016	5 2.28	34.5	0.00054	0.00042	0.05727	0.00430	34	0.62 0.000	1.3229	0.0000	0.0056	0.0025 0.0016
18	MIW-to-RAS_PL-NP20	RS03 Untreated	18.87	6.57	105	0.09	106.3	0.0165	0.0201	0.0263	26.0	0.00007	5.3	0.00062	0.00045	0.00073	1.40	0.25	0.85	0.00017	13.6	9.8 0	.02 0.014	5 2.30	30.2	0.00053	0.00042	0.04892	0.00385	32	0.56 0.000	1.3860	0.0000	0.0050	0.0022 0.0016
	MIW-to-RAS_PL-NP20 MIW-to-RAS_PL-NP20	RS03 Untreated RS03 Untreated		6.57	108 105	0.09			0.0211			0.00007			0.00045		1.38	0.27					.02 0.015					0.05324							0.0023 0.0016
21	MIW-to-RAS PL-NP20	RS03 Untreated	18.10	6.58	112	0.09	113.7	0.0164	0.0221	0.0272	27.4	0.00007	5.7	0.00063	0.00045	0.00072	1.36	0.28	0.89	0.00017	15.0	10.5	.02 0.015	9 2.26	33.1	0.00053	0.00042	0.05549	0.00419	34	0.62 0.000	1.3469	0.0000	0.0054	0.0024 0.0016
22	MIW-to-RAS PL-NP20	RS03 Untreated		6.58	109				0.0212			0.00007			0.00045								.02 0.014	7 2.23	31.5			0.05062							0.0022 0.0016
		RS03 Untreated RS03 Untreated		6.58	107 115				0.0208			0.00007			0.00045		1.39						.02 0.014 .02 0.015					0.04857							0.0022 0.0016 0.0023 0.0016
25	MIW-to-RAS PL-NP20	RS03 Untreated	20.36	6.56	104	0.09	104.6	0.0170	0.0201	0.0252	25.7	0.00007	5.1	0.00049	0.00045	0.00073	1.40	0.24	0.87	0.00017	12.7	9.6 0	.02 0.013	3 2.35	28.6	0.00052	0.00043	0.04467	0.00362	31	0.55 0.000	1.3831	0.0000	0.0047 0	0.0020 0.0016
26	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	RS03 Untreated RS03 Untreated		6.53 6.54	99 107	0.09	97.9	0.0176	0.0198	0.0244	24.6	0.00007	4.8	0.00050	0.00044	0.00075	1.44	0.24	0.92	0.00016	13.3 15.2	9.2 0	.02 0.014	1 2.51	27.5	0.00052	0.00044	0.04713	0.00370	33 35	0.58 0.000	1.4185	0.0000	0.0049 0	0.0021 0.0016
28	MIW-to-RAS PL-NP20	RS03 Untreated	14.59	6.54	110	0.09	110.0	0.0169	0.0225	0.0258	26.9	0.00007	5.5	0.00052	0.00045	0.00074	1.35	0.27	0.97	0.00017	14.8	10.4 0	.02 0.015	0 2.45	31.7	0.00052	0.00044	0.05395	0.00409	34	0.64 0.000	1.3379	0.0000	0.0052	0.0023 0.0016
29	MIW-to-RAS PL-NP20	RS03 Untreated	17.52	6.56	112	0.09	113.5	0.0167	0.0225	0.0260	27.4	0.00007	5.6	0.00050	0.00045	0.00073	1.33	0.26	0.93	0.00017	14.1	10.6	.02 0.014	3 2.32	31.8	0.00051	0.00043	0.05095	0.00396	33	0.61 0.000	1.3165	0.0000	0.0050	0.0022 0.0016

Year	Scenario	Station	Flow Rate (L/6)	рН	Hardness (mg CaCO3/L)	Acidity (mg CaCO3/L)	Alkalinity (mg CaCO3/L)	AI (mg/L)	As (mg/L) B		Ca mg/L)	Cd (mg/L)	CI (mg/L)	Co (mg/L)	Cr (mg/L)	Cu (mg/L)	DOC (mg/L)	F (mg/L) (Fe mg/L)	Hg (mg/L) (K mg/L)				O3-N ng/L) (Na mg/L)	NI (mg/L)	Pb (mg/L)	Sb (mg/L)	Se (mg/L)			TI TO			V (mg/L	Zn (mg/L)
	MIW-to-RAS_PL-NP20	RS03 Untreated	17.98		104	0.08		0.0166			25.9					0.00072	1.40	0.23		0.00017	12.3		0.02		2.18	28.5			0.04339				0.0002 1.3				0.0016
	MIW-to-RAS_PL-NP20 MIW-to-RAS_PL-NP20	RS03 Untreated RS03 Untreated	20.10 19.95	6.57	104	0.09			0.0202		25.7 C				0.00045		1.41	0.23		0.00017	12.4		0.02 0		2.24				0.04367				0.0002 1.3				
33	MIW-to-RAS PL-NP20	RS03 Untreated		6.53					0.0208		25.1				0.00044						13.3		0.02 (0.04680				0.0002 1.3				
35	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	RS03 Untreated RS03 Untreated		6.50				0.0180	0.0240		27.3 C				0.00044		1.31			0.00016	15.3 13.9		0.02 0	0.015/	2.63				0.05571	0.00414			0.0002 1.2				
36	MIW-to-RAS PL-NP20	RS03 Untreated	14.56	6.56	114				0.0230		28.0 0				0.00045		1.33			0.00017	13.5		0.02 0	0.0131	2.25				0.04846				0.0002 1.3				
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	RS03 Untreated RS03 Untreated	18.61	6.59	105				0.0221		26.1				0.00046			0.24			12.1		0.02 0	0.0109	2.05			0.00040	0.03606	0.00322	29		0.0002 1.3				
	MIW-to-RAS PL-NP20	RS03 Untreated RS03 Untreated		6.59	107	0.08			0.0204		26.5 0				0.00045		1.40	0.22		0.00017	11.2		0.01 0	0.0111	2.09	28.0	0.00050		0.03884				0.0002 1.3				
41	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	RS03 Untreated	16.77	6.54	110				0.0231		27.1				0.00044						14.1		0.02 (0.0138	2.43	30.4	0.00050	0.00044	0.05066	0.00389	33		0.0002 1.30				
42	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	RS03 Untreated RS03 Untreated		6.60					0.0202		25.8 C				0.00044					0.00017	11.3		0.01 0						0.03967 0.04656				0.0002 1.4				
	MIW-to-RAS PL-NP20	RS03 Untreated	18.51	6.52	105	0.10	104.2	0.0176	0.0214	0.0237	25.7	0.00007	5.1	0.00034	0.00044	0.00075	1.37	0.22	0.96	0.00017	12.0	9.8	0.01	0.0118	2.52	27.3	0.00050	0.00045	0.04087	0.00340	31	0.58	0.0002 1.34	477 0.0	0.00	3 0.001	8 0.0016
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	RS03 Untreated RS03 Untreated	13.04	6.53	120	0.10			0.0253		29.0 C				0.00045		1.26			0.00017	13.9		0.02 0		2.45				0.04937				0.0002 1.3				
47	MIW-to-RAS PL-NP20	RS03 Untreated	21.62	6.57	106	0.09	106.5	0.0167	0.0211	0.0236	26.1	0.00007	5.1	0.00032	0.00045	0.00073	1.40	0.22	0.90	0.00017	11.6	9.8	0.01	0.0113	2.21	27.4	0.00050	0.00042	0.04004	0.00339	29	0.58	0.0002 1.3	875 0.0	0.00	1 0.001	8 0.0016
		RS03 Untreated RS03 Untreated		6.54					0.0209		25.7 C				0.00044					0.00016	11.4		0.01 0		2.40				0.03873				0.0002 1.39				
50	MIW-to-RAS PL-NP20	RS03 Untreated	16.92	6.54	106	0.09	105.8	0.0173	0.0217	0.0234	26.0	0.00007	5.1	0.00031	0.00044	0.00074	1.38	0.22	0.95	0.00016	11.8	9.9	0.01	0.0116	2.38	27.3	0.00049	0.00044	0.04051	0.00338	31	0.60	0.0002 1.36	602 0.0	0.00	13 0.001	8 0.0016
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	RS03 Untreated RS03 Untreated	24.18 21.53	6.56					0.0209		25.8 C				0.00044		1.41	0.21		0.00017	11.1		0.01 0	0.0111	2.27				0.03754				0.0002 1.39				
53	MIW-to-RAS_PL-NP20	RS03 Untreated	20.60	6.57	104	0.09	104.7	0.0168	0.0206	0.0230	25.7	0.00007	4.9	0.00029	0.00044	0.00074	1.43	0.21	0.89	0.00017	10.8	9.6	0.01	0.0107	2.20	26.0	0.00049	0.00042	0.03658	0.00319	29	0.57	0.0002 1.40	0.0	0.00	0.001	7 0.0016
		RS03 Untreated RS03 Untreated		6.56	102				0.0203		25.4 C				0.00044		1.44			0.00017	10.5	9.9	0.01 0	0.0108	2.28		0.00049		0.03482		30	0.58	0.0002 1.4	667 0.0	0.00	0.001	7 0.0016
56	MIW-to-RAS_PL-NP20	RS03 Untreated RS03 Untreated	22.05	6.55	105	0.09	104.9	0.0175	0.0212	0.0232	25.8 C	0.00007	5.0	0.00028	0.00044	0.00075	1.40	0.20	0.94	0.00017 0.00016	10.8	9.8		0.0106	2.39	26.0	0.00049	0.00044	0.03587 0.03566	0.00315	30	0.57	0.0002 1.3	800 0.0	0.00	0.001	7 0.0016
58	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	RS03 Untreated	16.43	6.51	108	0.10	108.2	0.0177	0.0229	0.0235	26.5	0.00007	5.2	0.00028	0.00044	0.00075	1.35	0.22	1.02	0.00016	11.7	10.3	0.01 (0.0111	2.55	27.4	0.00049	0.00046	0.03910	0.00331	31	0.61	0.0002 1.3	343 0.0	0.00	0.001	8 0.0016
59	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	RS03 Untreated RS03 Untreated	22.69 15.27	6.54	104	0.09	104.6 109.7	0.0177	0.0213		25.7 C		5.0		0.00044		1.40	0.20		0.00017	10.7	9.7	0.01 0		2.36				0.03533				0.0002 1.3				
61	MIW-to-RAS PL-NP20	RS03 Untreated	16.03	6.54	112	0.10	113.5	0.0169	0.0234	0.0239	27.4	0.00007	5.4	0.00027	0.00045	0.00073	1.31	0.22	0.99	0.00017	11.3	10.7	0.01 (0.0104	2.38	28.4	0.00048	0.00045	0.03779	0.00327	29	0.60	0.0002 1.29	993 0.0	0.00	9 0.001	7 0.0016
62	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	RS03 Untreated RS03 Untreated		6.56	120				0.0244		29.3 C				0.00046		1.25			0.00017	11.1		0.01 0	0.0103					0.03706 0.02878				0.0002 1.3				
64	MIW-to-RAS PL-NP20	RS03 Untreated	18.98	6.55			107.0	0.0168	0.0211	0.0230	26.3	0.00007	5.1	0.00025	0.00044	0.00074	1.39	0.19	0.93	0.00017	9.8	9.9	0.01	0.0089	2.40	25.4	0.00049	0.00044	0.03083	0.00291	27	0.54	0.0002 1.3	755 0.0	0.00	34 0.001	5 0.0016
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	RS03 Untreated RS03 Untreated	19.86 15.88	6.54	100	0.09	99.3 112.3		0.0199	0.0222	24.7 C	0.00007			0.00044		1.43	0.18	0.91	0.00016	9.5		0.01 0	0.0093	2.36	27.4	0.00049	0.00043	0.02999	0.00284	28	0.53 0	0.0002 1.4	104 0.0 382 0.0	0.00	36 0.001 38 0.001	7 0.0016
67	MIW-to-RAS PL-NP20	RS03 Untreated	18.02	6.56	107	0.09			0.0213	0.0233	26.4	0.00007	5.1	0.00025	0.00045	0.00073	1.38	0.19	0.89	0.00017	9.6			0.0090	2.20	25.8	0.00048	0.00043	0.03050	0.00292	27	0.54	0.0002 1.36	605 0.0	0.00	35 0.001	5 0.0016
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	RS03 Untreated RS03 Untreated		6.56		0.09			0.0214		26.4 C				0.00044		1.38			0.00017	9.7		0.01 0		2.26				0.03080				0.0002 1.3				
	MIW-to-RAS PL-NP20	RS03 Untreated	17.26	6.59	110	0.08	113.8		0.0211	0.0239	27.1	0.00007			0.00046		1.35	0.18	0.83	0.00017	8.8	10.2	0.01	0.0083	2.01	26.3	0.00048	0.00041	0.02736	0.00280	26		0.0002 1.3				
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	RS03 Untreated RS03 Untreated	13.25	6.57	101	0.10			0.0194	0.0226	25.1 C	0.00007	5.4	0.00023	0.00044	0.00074	1.44			0.00017	10.3		0.01 (0.0098		27.3	0.00049	0.00041	0.02565				0.0002 1.4				
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	RS03 Untreated RS03 Untreated		6.57	109				0.0217		26.8 C				0.00045		1.36	0.19		0.00017	9.2		0.01 0		2.13	26.1	0.00048	0.00042	0.02896	0.00285	27		0.0002 1.3				
75	MIW-to-RAS PL-NP20	RS03 Untreated	12.36	6.56	117	0.09	121.1	0.0163	0.0232	0.0246	28.5	0.00007	5.7	0.00024	0.00046	0.00071	1.28	0.19	0.91	0.00017	9.3	11.1	0.01	0.0084	2.14	28.3	0.00047	0.00043	0.02908	0.00289		0.54	0.0002 1.26	686 0.0	0.00	33 0.001	4 0.0016
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	RS03 Untreated RS03 Untreated		6.62	109			0.0159	0.0204		27.0 0				0.00046		1.37	0.17		0.00018	7.9 8.0	9.1	0.01 0		1.83				0.02393	0.00265	24		0.0002 1.3				3 0.0016
78	MIW-to-RAS_PL-NP20	RS03 Untreated	22.12	6.56	97	0.09	96.1	0.0171	0.0192	0.0215	24.1	0.00007	4.4	0.00022	0.00043	0.00074	1.47	0.17	0.88	0.00016	8.5	8.8	0.01 (0.0084	2.25	21.8	0.00049	0.00042	0.02607	0.00263	26	0.53	0.0002 1.44	454 0.0	0.00	0.001	3 0.0015
		RS03 Untreated RS03 Untreated		6.55	107			0.0171	0.0222		26.3 C				0.00044		1.38	0.19		0.00017	9.6 8.8		0.01 0		2.25				0.03046				0.0002 1.30				
	MIW-to-RAS_PL-NP20	RS03 Untreated RS03 Untreated	18.55	6.52	105	0.10	104.7	0.0177	0.0216		25.8 C				0.00044		1.38	0.18		0.00016	9.2		0.01 0		2.49		0.00048		0.02772		28		0.0002 1.30				
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	RS03 Untreated	17.56	6.53	106	0.10	106.3	0.0173	0.0220	0.0227	26.1	0.00007	5.0	0.00022	0.00044	0.00075	1.39	0.18	0.97	0.00016	9.3	9.9	0.01 (0.0086	2.41	24.5	0.00048	0.00044	0.02834	0.00276	27	0.57	0.0002 1.36	685 0.0	0.00	0.001	4 0.0015
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	RS03 Untreated RS03 Untreated		6.57	102	0.09			0.0202		25.3 C				0.00044		1.43			0.00017	8.3		0.01 0						0.02481				0.0002 1.4				
86	MIW-to-RAS PL-NP20	RS03 Untreated	16.91	6.54	107	0.10	107.4	0.0173	0.0230	0.0224	26.5	0.00007	5.0	0.00022	0.00043	0.00075	1.41	0.19	1.02	0.00016	9.9	10.0	0.01	0.0093	2.42	24.9	0.00048	0.00044	0.03123	0.00287	28	0.63	0.0002 1.3	896 0.0	00.0	6 0.001	5 0.0015
87	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	RS03 Untreated RS03 Untreated		6.56					0.0200		24.8 C				0.00043		1.44	0.17 0.17	0.89	0.00016 0.00016	8.2 8.3	9.2	0.01 0	0.0082 0.0078	2.21				0.02466				0.0002 1.4				
89	MIW-to-RAS PL-NP20	RS03 Untreated		6.56					0.0223	0.0231	26.8	0.00007			0.00044		1.37	0.18	0.94	0.00017	8.8 7.6	10.2	0.01	0.0082	2.26	25.0	0.00048	0.00043	0.02643	0.00268	26	0.55	0.0002 1.34	473 0.0	0.00	0.001	3 0.0016
90	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	RS03 Untreated RS03 Untreated	14.21		108	0.09		0.0168	0.0197	0.0228	25.2 C	0.00007	5.1	0.00022	0.00044 0.00044	0.00074	1.36	0.17	0.95	0.00017 0.00017	8.5		0.01 0	0.0077	2.32	24.5	0.00047	0.00044	0.02192 0.02510	0.00261	25	0.53	0.0002 1.40 0.0002 1.34	474 0.0	0.00	0.001	3 0.0015
92	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	RS03 Untreated RS03 Untreated		6.54	116				0.0238		28.3 C				0.00045		1.28	0.18 0.18		0.00017	8.7		0.01 (0.0080 0.0075					0.02591				0.0002 1.2				
94	MIW-to-RAS PL-NP20	RS03 Untreated	22.05	6.55	100	0.09	100.2	0.0173	0.0195	0.0222	24.7	0.00007	4.6	0.00021	0.00044	0.00074	1.42	0.15	0.87	0.00017	7.3	9.2	0.01	0.0071	2.30	21.6	0.00048	0.00043	0.01997	0.00236	25	0.45	0.0002 1.39	986 0.0	0.00	9 0.001	1 0.0016
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	RS03 Untreated RS03 Untreated		6.56	102				0.0207		25.4 C				0.00044		1.43			0.00017	8.0 7.8		0.01 0		2.22				0.02319				0.0002 1.4				
97	MIW-to-RAS PL-NP20	RS03 Untreated	19.21	6.58	105	0.08	107.7	0.0167	0.0205	0.0228	26.2	0.00007	4.9	0.00021	0.00045	0.00073	1.42	0.16	0.86	0.00017	7.5	9.7	0.01	0.0070	2.11	23.3	0.00048	0.00041	0.02101	0.00244	24	0.47	0.0002 1.40	052 0.0	0.00	0.001	2 0.0016
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	RS03 Untreated RS03 Untreated		6.53				0.0170	0.0226		27.4				0.00044		1.35	0.17		0.00017	8.3 7.8		0.01 0		2.35		0.00048		0.02348				0.0002 1.3				
100	MIW-to-RAS PL-NP20	RS03 Untreated	28.74	6.60	101	0.08	104.1	0.0170	0.0194	0.0226	25.3	0.00007	4.7	0.00021	0.00044	0.00073	1.43	0.15	0.81	0.00017	6.9	9.3	0.01	0.0071	2.03	22.1	0.00048	0.00040	0.01882	0.00231	25	0.43	0.0002 1.40	0.0	0.00	9 0.001	1 0.0016
102	MIW-to-RAS_PL-NP20	RS03 Untreated RS03 Untreated	15.49		108	0.09	109.3	0.0174		0.0231	27.1 C	0.00007	5.1	0.00021	0.00043	0.00074	1.35	0.16	0.95	0.00016	8.6 7.9	10.1	0.01 (0.0076	2.60	24.0	0.00048	0.00044		0.00246	26	0.48	0.0002 1.3	307 0.0	00.00	0.001	2 0.0016
103	MIW-to-RAS_PL-NP20	RS03 Untreated RS03 Untreated	14.64	6.49	111	0.11	112.0	0.0182	0.0238	0.0235	27.1 0	0.00007	5.3	0.00021	0.00044	0.00075		0.17	1.05	0.00017	8.6 8.2	10.6	0.01	0.0080	2.65	25.0	0.00047	0.00048	0.02399	0.00253		0.51	0.0002 1.2	785 0.0	0.00	0.001	2 0.0016
105	MIW-to-RAS_PL-NP20	RS03 Untreated	24.10	6.56	103	0.09	104.1	0.0171	0.0207	0.0225	25.5	0.00007	4.8	0.00021	0.00044	0.00074	1.40	0.15	0.90	0.00017	7.3	9.5	0.01 (0.0069	2.22	22.4	0.00048	0.00043	0.02003	0.00236	24	0.45	0.0002 1.3	830 0.0	00.00	28 0.001	1 0.0016
	MIW-to-RAS_PL-NP20 MIW-to-RAS_PL-NP20	RS03 Untreated RS03 Untreated		6.55	105	0.09			0.0213		26.0 C	0.00007			0.00044		1.41	0.16		0.00017	7.6		0.01 0	0.0070	2.28	22.8	0.00048	0.00043	0.02077 0.01976	0.00239	25		0.0002 1.3				
108	MIW-to-RAS PL-NP20	RS03 Untreated	15.87	6.53	108	0.10	108.5	0.0173	0.0220	0.0229	26.5	0.00007	5.0	0.00021	0.00044	0.00075	1.38	0.16	0.96	0.00017	7.7	10.1	0.01	0.0069	2.40	23.4	0.00048	0.00045	0.02068	0.00238	25	0.46	0.0002 1.36	618 0.0	00.00	28 0.001	1 0.0016
109	MIW-to-RAS PL-NP20	RS03 Untreated RS03 Untreated		6.57					0.0212		26.4 C				0.00045		1.38	0.16		0.00017	7.1		0.01 0						0.01925				0.0002 1.30				
111	MIW-to-RAS PL-NP20	RS03 Untreated	17.09	6.55	109	0.09	112.3	0.0173	0.0217	0.0237	26.8	0.00007	5.2	0.00021	0.00045	0.00073	1.33	0.15	0.90	0.00017	7.0	10.3	0.01 (0.0067	2.27	24.0	0.00048	0.00044	0.01822	0.00230	25	0.42	0.0002 1.30	0.0	0.00	28 0.001	0 0.0016
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	RS03 Untreated RS03 Untreated	15.56 24.20	6.52	101	0.09	113.8		0.0232		27.3 C	0.00007	5.3 4.7	0.00021	0.00045	0.00074	1.32	0.16 0.15	0.99	0.00017	7.7 6.9	9.4	0.01 0	0.0064	2.45	21.4	0.00048	0.00043	0.02038	0.00224	24	0.42	0.0002 1.29	977 0.0	0.00	26 0.001	0 0.0015
114	MIW-to-RAS PL-NP20	RS03 Untreated	22.85	6.56	98	0.09	98.3		0.0196 0.0233	0.0217	24.5	0.00007	4.4	0.00020	0.00043	0.00074	1.46	0.14	0.88	0.00016	6.8 8.0	9.0	0.01	0.0068	2.24	20.4	0.00048	0.00042	0.01783 0.02158	0.00221	25	0.42	0.0002 1.4	383 0.0	0.00	28 0.001	0 0.0015
115	MIW-to-RAS PL-NP20	NOUS UNITERIED	17.14	0.52	109	0.10	109.4	0.0176	0.0233	0.0220	20.0	1.00001	5.0	v.uuu21	J.00043	J.00076	1.30	0.10	1.03	V.00010	0.0	10.0	0.01] (0.0072	2.33	20.0	0.00047	0.00040	U.UZ 100	v.uu239	20	u.40 L	2.000Z 1.34	++2 0.0	JJU U.UU.	J 0.001	L 0.0015

Year	Scenario	Station	Flow Rate (L/s)	рН	Hardness (mg CaCO3/L)	Acidity (mg CaCO3/L)	Alkalinity (mg CaCO3/L)	AI (mg/L)	As (mg/L)	B (mg/L)	Ca (mg/L)	Cd (mg/L)	CI (mg/L)	Co (mg/L)	Cr (mg/L)	Cu (mg/L)	DOC (mg/L)		Fe mg/L)	Hg (mg/L)	K (mg/L)	Mg (mg/L)			3-N Na g/L) (mg/		Pb (mg/L)	Sb (mg/L)	Se (mg/L)		Sr mg/L) (m				V (mg/L)	Zn (mg/L)
116	MIW-to-RAS PL-NP20	RS03 Untreated	18.65	6.56	110	0.09	112.6	0.0168	0.0228	0.0232	27.1	0.00007	5.2	0.00021	0.00044	0.00073	1.34	0.16	0.95	0.00017	7.5	10.4	0.01 0.0	066	2.27 2/	1.1 0.0004	7 0.00044	0.02003	0.00236	24	0.45 0.0	0002 1.32	69 0.00	00 0.002	8 0.0011	0.0016
		RS03 Untreated	17.76		111	0.09		0.0164				0.00007			0.00045					0.00017	7.1	10.4	0.01 0.0	063	2.13 24		7 0.00042					0002 1.33				
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	RS03 Untreated RS03 Untreated	19.63	6.57	102 105	0.09		0.0167				0.00007			0.00044			0.14 0.15		0.00017	6.5	9.4	0.01 0.0				8 0.00042 8 0.00042					0002 1.40 0002 1.37				
	MIW-to-RAS PL-NP20	RS03 Untreated	20.08	6.55	102	0.09		0.0171			25.3	0.00007	4.7	0.00020	0.00044	0.00074	1.42	0.14	0.90	0.00017	6.7	9.4	0.01 0.0	062	2.29 2	1.3 0.0004	8 0.00043	0.01688	0.00218	24	0.41 0.0	0002 1.40	31 0.00	00 0.002	6 0.0010	0.0015
121	MIW-to-RAS PL-NP20	RS03 Untreated	18.74		109 107	0.09		0.0166				0.00007			0.00044					0.00017	7.0	10.1	0.01 0.0				7 0.00042			24	0.42 0.0	0002 1.36	11 0.00	00 0.002	7 0.0011	0.0016
122	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	RS03 Untreated RS03 Untreated	20.67	6.58	107	0.09		0.0166			25.9	0.00007	4.8	0.00020	0.00044	0.00073	1.39			0.00017	6.6	9.9	0.01 0.0	059	2.12 2	1.9 0.0004	8 0.00042 8 0.00042	0.016/4	0.00221	23	0.40 0.0	0002 1.37 0002 1.38	98 0.00	00 0.002	5 0.0010	0.0016
124	MIW-to-RAS PL-NP20	RS03 Untreated	15.77	6.58	113	0.09		0.0164			27.7	0.00007	5.3	0.00021	0.00045	0.00073	1.35			0.00017	6.8	10.6	0.01 0.0	061	2.11 2/	4.4 0.0004	7 0.00042	0.01759	0.00227	23	0.41 0.0	0002 1.33	54 0.00	00 0.002	6 0.0010	0.0016
125	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	RS03 Untreated RS03 Untreated	21.05 22.20		102 97	0.09		0.0171				0.00007			0.00044			0.14		0.00017	6.3		0.01 0.0				8 0.00043 9 0.00044					0002 1.39 0002 1.42				
127	MIW-to-RAS PL-NP20	RS03 Untreated	21.16	6.54	104	0.10	104.3	0.0177	0.0222	0.0222	25.7	0.00007	4.8	0.00020	0.00043	0.00075	1.39	0.15	1.00	0.00016	7.2	9.7	0.01 0.0	068	2.44 2	1.8 0.0004	8 0.00045	0.01845	0.00223	25	0.43 0.0	0002 1.37	32 0.00	00 0.002	8 0.0010	0.0015
128	MIW-to-RAS PL-NP20	RS03 Untreated RS03 Untreated		6.53	107 109	0.10		0.0171				0.00007	4.9	0.00020	0.00044	0.00074	1.37			0.00017	7.0 6.8		0.01 0.0		2.36 22	2.6 0.0004	8 0.00044 7 0.00043	0.01778	0.00223	24	0.42 0.0	0002 1.35	00.00	00 0.002	6 0.0010	0.0015
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	RS03 Untreated	18.49			0.09						0.00007			0.00044					0.00017	6.1	9.4	0.01 0.0				8 0.00041					0002 1.38				
131	MIW-to-RAS PL-NP20	RS03 Untreated	20.66	6.57	102	0.09	103.5	0.0172	0.0202	0.0224	25.3	0.00007	4.7	0.00020	0.00044	0.00073	1.42	0.14	0.87	0.00017	6.2		0.01 0.0	061	2.17 21	1.1 0.0004	8 0.00042	0.01479		24	0.37 0.0	0002 1.39	74 0.00	00 0.002	6 0.0009	0.0016
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	RS03 Untreated RS03 Untreated	20.49 21.17		101	0.09		0.0177	0.0207	0.0221		0.00007			0.00043					0.00016	6.5	9.4	0.01 0.0			0.7 0.0004	8 0.00044	0.01545				0002 1.39				
134	MIW-to-RAS PL-NP20	RS03 Untreated	14.20	6.50	110	0.10	110.4	0.0181	0.0240	0.0231		0.00007	5.1	0.00021	0.00044	0.00075	1.33	0.15	1.06	0.00016	7.4	10.4	0.01 0.0	069	2.55 23	3.2 0.0004	7 0.00047	0.01853	0.00223	26	0.43 0.0	0002 1.30	29 0.00	00 0.002	9 0.0010	0.0015
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	RS03 Untreated RS03 Untreated	21.53 14.87		109	0.10		0.0173		0.0231		0.00007			0.00044					0.00017	6.8	10.3	0.01 0.0				8 0.00045 7 0.00043					0002 1.32				
		RS03 Untreated	14.97	6.59	113			0.0160				0.00007			0.00044					0.00017	6.0		0.01 0.0				7 0.00041					0002 1.32				
		RS03 Untreated RS03 Untreated			103	0.08	106.6	0.0166	0.0196	0.0228	25.7	0.00007	4.8	0.00020	0.00045	0.00072	1.41	0.13	0.80	0.00017	5.5	9.5 9.7	0.01 0.0	054	2.01 21	1.4 0.0004	8 0.00040	0.01242	0.00201	22	0.33 0.0	1.38	349 0.00	00 0.002	3 0.0009	0.0016
	MIW-to-RAS_PL-NP20 MIW-to-RAS_PL-NP20	RS03 Untreated RS03 Untreated	21.62 26.78	6.59 6.55	105 94	0.08		0.0163				0.00007			0.00045 0.00043					0.00017	5.8		0.01 0.0 0.01 0.0				9 0.00041					0002 1.38				0.0016
		RS03 Untreated	17.08		108	0.10		0.0171				0.00007			0.00043					0.00016	6.9 5.8	10.1	0.01 0.0				7 0.00044					0002 1.37				
	MIW-to-RAS_PL-NP20 MIW-to-RAS_PL-NP20	RS03 Untreated RS03 Untreated	21.92 14.61	6.59	102 113	0.08		0.0164				0.00007			0.00044					0.00017	5.8 6.8	10.7	0.01 0.0				8 0.00040 7 0.00047					0002 1.41				
144	MIW-to-RAS PL-NP20	RS03 Untreated	18.82	6.52	103	0.10	103.0	0.0176	0.0214	0.0224	25.3	0.00007	4.7	0.00020	0.00044	0.00075	1.37	0.14	0.97	0.00016	6.3	9.6	0.01 0.0	057	2.48 20	0.0004	8 0.00045	0.01402	0.00203	24	0.36 0.0	0002 1.35	38 0.00	00 0.002	4 0.0009	0.0015
145	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	RS03 Untreated RS03 Untreated	13.22	6.52 6.55	118	0.10		0.0173	0.0253			0.00007 0.00007			0.00045 0.00044					0.00017	7.0 5.7	9.2	0.01 0.0				7 0.00046 8 0.00043					0002 1.24 0002 1.38				
147	MIW-to-RAS PL-NP20	RS03 Untreated	21.94	6.57	104	0.09	105.4	0.0168	0.0211	0.0224	25.8	0.00007	4.7	0.00020	0.00044	0.00074	1.41	0.14	0.91	0.00017	6.0	9.6	0.01 0.0	054	2.18 21	1.1 0.0004	8 0.00042	0.01360	0.00204	22	0.36 0.0	0002 1.39	32 0.00	00 0.002	3 0.0009	0.0016
148	MIW-to-RAS PL-NP20	RS03 Untreated RS03 Untreated	18.37 20.92		102	0.09		0.0174				0.00007			0.00043					0.00016	6.0 5.8	9.5	0.01 0.0	057			8 0.00044					0002 1.40				
150	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	RS03 Untreated	17.11		104	0.09		0.0173				0.00007			0.00044			0.13			6.2		0.01 0.0				8 0.00044					0002 1.40				
151	MIW-to-RAS PL-NP20	RS03 Untreated			103	0.09	103.9		0.0208		25.5	0.00007			0.00044			0.13		0.00017	5.9	9.5	0.01 0.0	056	2.24 20	0.0004	8 0.00043	0.01295	0.00198			0002 1.39				
152	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	RS03 Untreated RS03 Untreated	21.76 20.80		102 102	0.09		0.0171				0.00007			0.00043			0.13		0.00016	5.8	9.4	0.01 0.0 0.01 0.0	056	2.24 20	0.3 0.0004	8 0.00042	0.01284	0.00196			0002 1.41				
154	MIW-to-RAS PL-NP20	RS03 Untreated		6.56	101	0.09	102.0	0.0171	0.0203	0.0221	25.2	0.00007	4.6		0.00044			0.13	0.89	0.00017	5.7	9.3	0.01 0.0	054	2.26 20	0.0004	8 0.00042	0.01212	0.00194	23	0.34 0.0	0002 1.41	93 0.00	00 0.002	3 0.0008	0.0016
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	RS03 Untreated RS03 Untreated	17.06 22.21	6.54	105 103	0.09		0.0173				0.00007			0.00044					0.00017	6.0 5.9		0.01 0.0				8 0.00044					0002 1.36 0002 1.38				
	MIW-to-RAS PL-NP20	RS03 Untreated	18.39	6.53	103	0.09	103.0		0.0211	0.0222		0.00007	4.6	0.00020	0.00043	0.00075	1.42	0.13		0.00017	5.9	9.5	0.01 0.0	055	2.39 20		8 0.00044					0002 1.39				
		RS03 Untreated	16.51		107	0.10		0.0177				0.00007			0.00044					0.00016	6.3 5.8		0.01 0.0	055	2.52 2		8 0.00046					0002 1.33				
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	RS03 Untreated RS03 Untreated	22.81 15.32		103 108	0.09		0.0177				0.00007			0.00044					0.00017	6.3		0.01 0.0				8 0.00044 7 0.00046					0002 1.37 0002 1.32				
		RS03 Untreated	16.09	6.54	111	0.10	112.8	0.0169	0.0234	0.0232		0.00007	5.2	0.00020	0.00044	0.00073	1.31			0.00017	6.1		0.01 0.0				7 0.00045			22	0.34 0.0	0002 1.30	0.00	00 0.002	2 0.0009	0.0016
	MIW-to-RAS PL-NP20 MIW-to-RAS_PL-NP20	RS03 Untreated RS03 Untreated	12.21 20.91	6.56	119 108	0.09	124.5 112.8	0.0164	0.0244	0.0247	29.0	0.00007			0.00045		1.25	0.14		0.00017	5.9	11.3	0.01 0.0	050	2.12 25	5.4 0.0004	6 0.00044 8 0.00041				0.33 0.0	0002 1.24 0002 1.32	69 0.00	00 0.002	2 0.0009	0.0016
164	MIW-to-RAS_PL-NP20	RS03 Untreated	19.00	6.55	106	0.09	106.6	0.0169	0.0212	0.0225	26.1	0.00007	4.8	0.00020	0.00044	0.00074	1.39	0.13	0.93	0.00017	5.6		0.01 0.0	046	2.38 20	0.0004	8 0.00044	0.01087	0.00189	21	0.32 0.0	0002 1.37	759 0.00	00 0.002	0.0008	0.0016
		RS03 Untreated RS03 Untreated	19.86 15.88	6.54	99 110	0.09		0.0174				0.00007			0.00043					0.00016	5.4		0.01 0.0				8 0.00043 7 0.00044					0002 1.41 0002 1.33				
167	MIW-to-RAS_PL-NP20	RS03 Untreated	18.02	6.56	106	0.09	108.6	0.0167	0.0213	0.0229	26.2	0.00007	4.9	0.00020	0.00044	0.00073	1.38	0.13	0.89	0.00017	5.4	9.9	0.01 0.0	048	2.19 21	1.4 0.0004	8 0.00043	0.01075	0.00191	21	0.31 0.0	0002 1.36	0.00	00 0.002	0.0008	0.0016
168		RS03 Untreated RS03 Untreated	20.42	6.56	106 121	0.09		0.0168				0.00007			0.00044					0.00017	5.5		0.01 0.0				8 0.00043 6 0.00045					0002 1.36				
170	MIW-to-RAS PL-NP20	RS03 Untreated	17.26	6.59	109	0.08	113.4	0.0163	0.0211	0.0236	26.9	0.00007	5.1	0.00020	0.00045	0.00071	1.35	0.13	0.83	0.00017	5.1	10.1	0.01 0.0	045	2.00 22	2.4 0.0004	8 0.00041	0.00976	0.00191	21	0.29 0.0	0002 1.33	20 0.00	00 0.002	0.0008	0.0016
171	MIW-to-RAS PL-NP20	RS03 Untreated RS03 Untreated	23.94	6.57 6.53	100 111	0.08		0.0171				0.00007			0.00044					0.00017	5.0		0.01 0.0 0.01 0.0				8 0.00041 7 0.00045					0002 1.41				
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	RS03 Untreated	17.65		108	0.10		0.0173				0.00007			0.00044					0.00017	5.3		0.01 0.0				8 0.00042					0002 1.34				
174	MIW-to-RAS PL-NP20	RS03 Untreated		6.56		0.09		0.0168				0.00007			0.00045					0.00017	5.4	10.6	0.01 0.0	048	2.17 23		7 0.00043					0002 1.31				
1/5	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	RS03 Untreated RS03 Untreated		6.56 6.62		0.09		0.0163				0.00007			0.00046					0.00017	5.4 4.7		0.01 0.0		2.13 24 1.82 22	2.3 0.0004	7 0.00043 8 0.00039	0.01027	0.00193	20		0002 1.26				
177	MIW-to-RAS PL-NP20	RS03 Untreated	23.27	6.56	98	0.09		0.0170			24.6	0.00007	4.4	0.00020	0.00043	0.00074	1.45	0.12	0.85	0.00017	4.9	9.0	0.01 0.0	046	2.23 18	3.9 0.0004	8 0.00042	0.00874	0.00177	21	0.29 0.0	0002 1.42	94 0.00	00 0.002	0.0007	0.0015
178	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	RS03 Untreated RS03 Untreated	22.12 16.39	6.56	96 106	0.09		0.0171			24.0	0.00007			0.00043			0.12 0.13		0.00016	5.1		0.01 0.0				8 0.00042 7 0.00043			22	0.30 0.0	0002 1.44 0002 1.36	54 0.00 00 0.00	00 0.002	3 0.0007	0.0015
180	MIW-to-RAS PL-NP20	RS03 Untreated	18.30	6.56	104	0.09	105.7	0.0171	0.0211	0.0226	25.7	0.00007	4.7	0.00020	0.00044	0.00073	1.38	0.12	0.91	0.00017	5.2	9.7	0.01 0.0	049	2.22 20	0.0004	8 0.00043	0.00984	0.00184	22	0.30 0.0	0002 1.36	34 0.00	00 0.002	2 0.0008	0.0016
	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	RS03 Untreated RS03 Untreated		6.52	104 102	0.10		0.0177				0.00007	4.7	0.00020	0.00043	0.00075	1.38			0.00016	5.5 5.3	9.7	0.01 0.0	050			8 0.00045 8 0.00043					0002 1.36 0002 1.38				
	MIW-to-RAS PL-NP20	RS03 Untreated	17.56		102	0.09		0.0176		0.0222		0.00007			0.00044		1.40			0.00016	5.5	9.8	0.01 0.0	048			8 0.00044					0002 1.36				
		RS03 Untreated	22.28		101	0.09		0.0165				0.00007			0.00044					0.00017	5.0	9.3	0.01 0.0				8 0.00041					0002 1.41				
		RS03 Untreated RS03 Untreated	32.87 16.91	6.54	94 107	0.08	106.9	0.0173	0.0182	0.0210		0.00007 0.00007			0.00043			0.11	1.02	0.00016	5.7	9.9	0.01 0.0			0.5 0.0004	9 0.00040					0002 1.49				0.0015
187	MIW-to-RAS PL-NP20	RS03 Untreated	22.62	6.56	99	0.09	100.0	0.0171	0.0200	0.0218	24.7	0.00007	4.4	0.00020	0.00043	0.00074	1.44	0.12	0.89	0.00016	5.0	9.1	0.01 0.0	049	2.20 19	9.0 0.0004	8 0.00042	0.00914	0.00177	22	0.29 0.0	0002 1.41	87 0.00	00 0.002	2 0.0007	0.0015
		RS03 Untreated RS03 Untreated	19.56 17.40		100	0.09		0.0168				0.00007			0.00043					0.00016	5.0	9.2	0.01 0.0	045 046			8 0.00042 7 0.00043									0.0015
190	MIW-to-RAS_PL-NP20	RS03 Untreated	21.95	6.58	101	0.08	102.2	0.0168	0.0197	0.0221	25.1	0.00007	4.6	0.00020	0.00044	0.00073	1.43	0.12	0.85	0.00017	4.8	9.2	0.01 0.0	045	2.13 19	9.5 0.0004	8 0.00041	0.00837	0.00177	21	0.28 0.0	1.40	72 0.00	00 0.002	0.0007	0.0016
		RS03 Untreated RS03 Untreated	14.21 12.97	6.54	107 115	0.09		0.0168		0.0227	26.4	0.00007	4.9		0.00044		1.36	0.12		0.00017	5.3	10.0	0.01 0.0	044	2.32 2	1.1 0.0004	7 0.00044	0.00942	0.00181	21		0002 1.34				
193	MIW-to-RAS PL-NP20	RS03 Untreated	13.89	6.58	115	0.09	121.0	0.0165	0.0230	0.0245	28.2	0.00007	5.5	0.00021	0.00046	0.00071	1.28	0.13	0.88	0.00017	5.0	10.9	0.01 0.0	044	2.03 24	4.0 0.0004	7 0.00042	0.00902	0.00188	22	0.27 0.0	0002 1.25	88 0.00	00 0.002	1 0.0007	0.0016
194	MIW-to-RAS PL-NP20	RS03 Untreated RS03 Untreated	22.05	6.55 6.56	99 102	0.09		0.0173				0.00007			0.00044			0.12		0.00017	4.8	9.1 9.4	0.01 0.0	046			8 0.00043 8 0.00042					0002 1.39				0.0016
195	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	RS03 Untreated RS03 Untreated			106	0.09		0.0169			26.3	0.00007			0.00044					0.00017	4.9	9.4	0.01 0.0	045	2.04 20		8 0.00042					0002 1.40				
197	MIW-to-RAS PL-NP20	RS03 Untreated	19.21	6.58	105	0.08	107.4	0.0167	0.0205	0.0227	26.1	0.00007	4.8	0.00020	0.00044	0.00073	1.42	0.12	0.86	0.00017	4.8	9.6	0.01 0.0	045	2.11 20	0.0004	8 0.00041	0.00856		21	0.28 0.0	0002 1.40	52 0.00	00 0.002	0.0007	0.0016
198	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20	RS03 Untreated RS03 Untreated		6.53 6.57	110 111	0.09		0.0170				0.00007			0.00044			0.13 0.13		0.00017	5.3 5.0		0.01 0.0 0.01 0.0				7 0.00044					0002 1.33				0.0016
0	MIW-to-RAS PL-NP20	RS03 Treated	23.45	6.57	77	0.02	64.6	0.0027	0.0001	0.0199	24.1	0.00007	2.6	0.00001	0.00001	0.00001	1.73	0.10	0.00	0.00017	3.7	4.1	0.00 0.0	002	0.01 12	2.7 0.0000	1 0.00000	0.00022	0.00004	17	0.00 0.0	1.66	51 0.00	00 0.000	8 0.0001	0.0000
1]	MIW-to-RAS PL-NP20	rcS03 Treated	14.34	6.57	139	0.09	114.1	0.0028	0.0002	0.0318	39.5	u.00007	6.0	0.00002	0.00001	0.00001	1.31	0.27	0.01	0.00017	16.4	9.9	0.00 0.0	U04	u.03 38	o.7 0.0000	0.00001	0.00118	0.00009	25	0.01 0.0	0002 1.29	139 0.00	UO 0.001	ы 0.0003	0.0000

	Year	Scenario	Station	Flow Rate (L/s)	рН	Hardness (mg CaCO3/L)	Acidity (mg CaCO3/L)	Alkalinity (mg CaCO3/L)	Al (mg/L)	As (mg/L)	B (mg/L)	Ca (mg/L)	Cd (mg/L)	CI (mg/L)	Co (mg/L)	Cr (mg/L)	Cu (mg/L)	DOC (mg/L)		Fe ng/L)	Hg (mg/L) (n			Mn Mo g/L) (mg/L)	NO3-N (mg/L)	Na (mg/L)	NI (mg/L)	Pb (mg/L)	Sb (mg/L)		SO4 Sr (mg/L) (mg/L	TI (mg/L)	TOC (mg/L)	CN (mg/L)	U (mg/L) (V Zn mg/L) (mg/L)
	2	MIW-to-RAS PL-NP20	RS03 Treated	14.78	6.56	137	0.09	112.4	0.0029	0.0002	0.0322	38.8	0.00007	5.9	0.00002	0.00001	0.00001	1.32	0.28	0.01	0.00017	17.1	9.7	0.00 0.000	4 0.03	36.3	0.00001	0.00001	0.00126	0.00009	27 0.0	1 0.0002	1.3019	0.0000	0.0017	0.0003 0.0000
			RS03 Treated	15.66	6.55	134	0.09					38.3	0.00007	5.7	0.00002	0.00001	0.00001	1.39	0.29	0.01	0.00017	17.2	9.4	0.00 0.000	4 0.03	35.1	0.00001	0.00001	0.00129	0.00009	26 0.0	1 0.0002	1.3703	0.0000	0.0017	.0003 0.0000
	7	MIW-to-RAS PL-NP20																																		
				15.21	6.54	137						38.9	0.00007	5.8	0.00002	0.00001	0.00001	1.36	0.30						4 0.03	35.4	0.00001	0.00001	0.00127	0.00009						
			RS03 Treated	11.91	6.56	148	0.09	123.8	0.0028	0.0002	0.0314	41.9	0.00007	6.4	0.00002	0.00001	0.00001	1.27	0.31	0.01	0.00017	17.4	10.6	0.00 0.000	4 0.02	38.4	0.00001	0.00001	0.00130	0.00009	26 0.0	1 0.0002	1.2601	0.0000	0.0016	0.0003 0.0000
Second Column	14	MIW-to-RAS PL-NP20		21.90	6.57	125	0.09					35.9	0.00007		0.00001	0.00001	0.00001	1.45	0.27	0.01	0.00016				3 0.02	30.1	0.00001	0.00001	0.00108	80000.0	24 0.0	1 0.0002	1.4231	0.0000	0.0014	0.0002 0.0000
				17.10	6.58	141																									24 0.0	1 0.0002	1.3229	0.0000	0.0014	0.0002 0.0000
Section Sect																																				
				18.44	6.57	133																														
The stand The				18.10	6.58	138																	_													
2 Wilson 1 Wilson 2																																				
S WAS AL AND RELEASE SETTINGS				15.30	6.58	132						40.5	0.00007																							
## PART OF STATE 19 10 10 10 10 10 10 10	25	MIW-to-RAS_PL-NP20	RS03 Treated	20.36	6.56	128	0.09	104.6	0.0028	0.0002	0.0252	36.8	0.00007	5.1	0.00001	0.00001	0.00001	1.40	0.24	0.01	0.00017	12.7	8.9	0.00 0.000	3 0.02	28.6	0.00001	0.00001	0.00089	0.00007	22 0.0	1 0.0002	1.3831	0.0000	0.0012	0.0002 0.0000
## PART																																				
Supplies And Park (1972) - 10 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	28	MIW-to-RAS_PL-NP20	RS03 Treated	14.59	6.54	135	0.09	110.0	0.0028	0.0002	0.0258	38.5	0.00007	5.5	0.00001	0.00001	0.00001	1.35	0.27	0.01	0.00017	14.8	9.5	0.00 0.000	3 0.02	31.7	0.00001	0.00001	0.00108	80000.0	24 0.0	1 0.0002	1.3379	0.0000	0.0014	0.0002 0.0000
1 Mile SAMA, PANIS S. 1931 TAMES S. 1931 TAM	29	MIW-to-RAS PL-NP20	RS03 Treated	17.52	6.56	138	0.09	113.5	0.0028	0.0002	0.0260	39.2	0.00007	5.6	0.00001	0.00001	0.00001	1.33	0.26	0.01	0.00017		9.7	0.00 0.000	3 0.02	31.8	0.00001	0.00001	0.00102	0.00008	23 0.0	1 0.0002	1.3165	0.0000	0.0013	0.0002 0.0000
Second Column																																				
32 WILLIAM STATE PARTY NAME	32	MIW-to-RAS PL-NP20		19.95	6.54	128		103.0	0.0029	0.0002	0.0244	36.6	0.00007					1.41	0.24	0.01	0.00016		8.9	0.00 0.000	3 0.02	28.2	0.00001	0.00001	0.00091	0.00007	23 0.0	1 0.0002	1.3856	0.0000	0.0012	0.0002 0.0000
35 WIN PART AND PART	33	MIW-to-RAS PL-NP20																																		
35 Mars Andre August	35	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20										38.9	0.00007	5.5												31.0	0.00001	0.00001	0.00099	0.00008						
35 Mars - Pade 2 - No. 1	36	MIW-to-RAS PL-NP20																							3 0.02											
Signal services (S. 1992)	37	MIW-to-RAS PL-NP20																	0.24						2 0.02	31.1										
## 1985 PARTIEL ST. 1855 PARTIEL ST. 185	39	MIW-to-RAS PL-NP20																	0.22	0.01	0.00017		9.1	0.00 0.000	2 0.02											
42 WH-9-M-9-M-9-P-9-P-9-P-9-P-9-P-9-P-9-P-9-P	40	MIW-to-RAS PL-NP20										34.3	0.00007																							
4 WW-9-MG PLWPD ROST Treated 1.5 6.5 7.5 1.0 1.5 0.000 0.0000 0.																																				
## WHIN-SHAD PLAPSON 0505 Trained 1.3.6 6.5 12 6.000 1.00000 1.00000 1.0000 1.00000 1.0000 1.0000 1.0000 1.0000 1.0000 1.0000 1.	43	MIW-to-RAS PL-NP20	RS03 Treated	14.39	6.51	141	0.10	115.3	0.0030	0.0002	0.0250	39.9	0.00007	5.6	0.00001	0.00001	0.00002	1.32	0.25	0.01	0.00016	13.4	10.0	0.00 0.000	3 0.03	30.7	0.00001	0.00001	0.00093	0.00007	23 0.0	1 0.0002	1.2981	0.0000	0.0012	0.0002 0.0000
##WH-9-AS PL-APP2 R503 Treated ## 21.09 6.55 125 0.09 161.4 0.0001 0.000																																				
## WH-PARP PLAPS2 RSS Treated ## 1.5 6.5 128 0.00 10.0																																				
Feb Mark-S-PAR PA-979 RG03 Treated 20.6 6 6.55 129 0.09 10.1 0 0.0002 0.0002 0.0007 1.00007 1.000007 0.0007 0.0000	47	MIW-to-RAS PL-NP20		21.62	6.57	130	0.09	106.5	0.0028	0.0002	0.0236	37.4	0.00007	5.1	0.00001	0.00001	0.00001		0.22	0.01	0.00017		9.0	0.00 0.000	2 0.02	27.4	0.00001	0.00001	0.00080	0.00007	20 0.0	1 0.0002	1.3875	0.0000	0.0011	0.0002 0.0000
S MMY-S-PAR PL-MP2P R503 Treaded 16.52 6.55 129 0.099 15.6 0.0092 0.0022 0.023 37.6 0.00007 5.0 0.00007 5.0 0.00000 0.00001 0.00001 1.8 0.000 0.00001 0.												36.8	0.00007						0.21	0.01 0	0.00016		8.9	0.00 0.000	2 0.02	26.4	0.00001						1.3953	0.0000	0.0011	0.0002 0.0000
\$\frac{\text{NMM-PerkQP} \ PL-NP20 \ R931 \ Treatment \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \																																				
\$\frac{\text{S}\text{MM}\caps{-Max}\text{P}\caps{-New}\text{D}\text{R}\text{P}\caps{-New}\text{D}\text{R}\text{P}\caps{-New}\text{D}\text{R}\text{D}\text{P}\caps{-New}\text{D}\text{R}\text{D}\text{P}\caps{-New}\text{D}\text{R}\text{D}\text{N}\text{D}\text{P}\text{D}\tex																																				
SE MINN-SPRASP, PLANEDR ROSO Trended 19.75 (5.58) 129 0.09 102.8 0.0093 0.0002 0.0022 37.0 0.00001 0.00001 0.00001 1.45 0.0000 0.00001		MIW-to-RAS_PL-NP20	RS03 Treated																																	
5f MW-1a-FAS P1-MP20 R503 Treated 22.05 5.55 129 0.09 104.9 0.0029 0.0020 0.0020 0.00001 0.00001 0.000001 0.00001 0.00001 0.000001 0.00001	54	MIW-to-RAS PL-NP20		19.75	6.56	127		102.8	0.0029	0.0002	0.0228	36.4	0.00007	4.8	0.00000	0.00001	0.00001	1.44	0.20	0.01	0.00017	10.0	8.7	0.00 0.000	2 0.02	25.3	0.00001	0.00001	0.00070	0.00006	20 0.0	1 0.0002	1.4158	0.0000	0.0010	0.0002 0.0000
Star Min-Lo-Pick Pick Pick Pick Pick Pick Pick Pick		HITT TO TO TO TE THE ZO																					9.2	0.00 0.000	2 0.02	26.7										
86 MWD-RAS PL-NP20 R503 Treated 16.43 6.51 134 0.10 109.2 0.0030 0.0002 0.231 38.6 0.00007 5.2 0.00000 0.00001 1.0007 1.00002 0.0002 0.2 25.4 0.00001 0.00001 0.0007 1.0007 0.0000 0.00001 0.00001 0.00001 1.0007 0.0000 0.00001 0.0	57		RS03 Treated	18.28	6.53	128	0.09	103.7	0.0029	0.0002	0.0229	36.8	0.00007	4.9	0.00000	0.00001	0.00002	1.42	0.20	0.01	0.00016	10.8	8.9	0.00 0.000	2 0.02	25.6	0.00001	0.00001	0.00071	0.00006	21 0.0	1 0.0002	1.3965	0.0000	0.0010	0.0002 0.0000
Fig. Sept.	58	MIW-to-RAS PL-NP20																							2 0.03											
61 MM-16-RAS PL-NP20 RS03 Treated 16.03 6.54 138 0.10 113.5 10.0022 0.0020 0.0000 0.00	60	MIW-to-RAS PL-NP20 MIW-to-RAS PL-NP20																																		
State Minter-Ras Pinter Resident 12.19 6.55 1.48 0.09 125.1 0.0027 0.0020 0.0020 0.0203 4.19 0.00000 0.00001 0.00001 1.25 0.22 0.01 0.00017 1.11 1.1 1.6 0.5 0.00 0.0002 0.02 3.6 0.00001	61	MIW-to-RAS PL-NP20		16.03	6.54	138		113.5	0.0028	0.0002	0.0239	39.2	0.00007	5.4	0.00000	0.00001	0.00001	1.31	0.22				9.8	0.00 0.000	2 0.02	28.4	0.00001	0.00001	0.00076	0.00007	20 0.0	1 0.0002	1.2993	0.0000	0.0010	0.0002 0.0000
65 MM-b-RAS PL-NP20 RS03 Treated 15.98 6.55 132 0.09 97.3 0.0029 0.0002 0.022 35.4 0.00007 4.7 0.00000 0.00001 1.35 0.19 0.01 0.0001 0.0001 0.0000 0.00001 0.00001 0.00000 0.00001 0.00001 0.00000 0.00001 0.00001 0.00001 0.00000 0.00001 0.0	62	MIW-to-RAS PL-NP20				148																				30.8										
65 MMY-b-RAS PL-NP20 RS03 Treated 15.86 6.55 132 0.09 99.3 0.0022 0.0022 3.5 0.0000 0.0000 1.0000 1.0000 1.0000 1.0000 1.0000 0.	64	MIW-to-RAS PL-NP20	RS03 Treated	18.98	6.55	132	0.09	107.0	0.0028	0.0002	0.0230	37.6	0.00007	5.1	0.00000	0.00001	0.00001	1.39	0.19	0.01	0.00017	9.8	9.1	0.00 0.000	2 0.02	25.4	0.00001	0.00001	0.00062	0.00006	19 0.0	1 0.0002	1.3755	0.0000	0.0009	0.0001 0.0000
67 MMY-b-RAS PL-NP20 RS03 Treated 10.61 6.54 150 0.09 190.2 0.0022 0.0223 37.7 0.00007 5.1 0.00001 0.00001 1.38 0.19 0.01 0.00017 9.6 9.2 0.0 0.0002 0.022 5.8 0.00001	65	MIW-to-RAS PL-NP20																1.43	0.18						2 0.02	23.5										
69 MM·-b-RAS PL-NP20 RS03 Treated 20.42 6.56 132 0.09 108.2 0.002 0.0021 37.7 0.00007 5.1 0.00001 1.38 0.19 0.01 0.00017 9.7 9.7 9.2 0.0 0.0002 0.02 25.6 0.00001 0.00006 1.000001 0.00006 1.00001 0.00001 0.00000 0.000000																									2 0.02											0.0002 0.0000
69 MM·b-RAS PL-NP20 RS03 Treated 10.61 6.54 150 0.09 125.9 0.0022 0.0225 3 8.7 0.0002 0.00007 5.3 0.0000 0.00001 1.27 0.22 0.01 0.00017 1.0.8 10.7 0.01 0.0002 0.02 2.3 0.0001 0.00001 0.00005 0.00005 0.0000 0.00001	68	MIW-to-RAS PL-NP20		20.42	6.56	132	0.09	108.2		0.0002	0.0231	37.7	0.00007	5.1	0.00000	0.00001	0.00001	1.38	0.19	0.01	0.00017	9.7	9.2	0.00 0.000	2 0.02	25.6	0.00001	0.00001	0.00062	0.00006	19 0.0	1 0.0002	1.3676	0.0000	0.0009	0.0001 0.0000
Time MM-ib-RAS PL-NP20 RS03 Treated 23.94 6.57 125 0.08 102.4 0.0029 0.0002 0.0226 3.9.4 0.00007 5.4 0.0000 0.00001 1.44 0.17 0.01 0.00017 8.4 8.5 0.00 0.0002 0.022 23.3 0.00001 0.00005 10.0005 10.0005				10.61	6.54	150												1.27	0.22																	
T3 MM-b-RAS PL-NP20 R503 Treated 13.25 6.55 135 0.10 11.10 0.0029 0.0020 0.0020 3.40 0.00007 5.2 0.00000 0.00001 1.34 0.20 0.10 0.00017 1.3 9.8 0.00 0.0002 0.22 27.3 0.00001 0.00006 0.00006 0.00006 0.00006 0.00006 0.00006 0.000000 0.00000 0.00000 0.00000 0.00000 0.000000 0.000000 0.000																																				
75 MIN-16-RAS PL-NP20 R503 Treated 14.50 6.56 140 0.09 118.8 0.0022 0.0022 0.0022 3.9 8 0.00007 5.7 8 0.00000 0.00001 1.33 0.19 0.01 0.00017 9.4 9.8 8 0.00000000 0.0000	72	MIW-to-RAS PL-NP20	RS03 Treated	13.25	6.53	138	0.10	114.0	0.0029	0.0002	0.0238	39.4	0.00007	5.4	0.00000	0.00001	0.00001	1.34	0.20	0.01	0.00017		9.8	0.00 0.000	2 0.02	27.3	0.00001	0.00001	0.00066	0.00006	20 0.0	1 0.0002	1.3253	0.0000	0.0010	0.0002 0.0000
Fig. MIM*-lb-RAS_PL-NP20 R503 Treated 12.36 6.56 144 0.09 12.11 0.0027 0.0002 0.0208 4.08 0.00007 5.7 0.00000 0.00001 1.28 0.19 0.01 0.00017 9.3 1.2 0.00 0.0001 0.00001 0.0005 0.00001 0.00005 0.000005 18 0.01 0.0002 1.2868 0.0000 0.0005 0.00001 0.0005 0.00005																																				
Fig. MMV-b=RAS_PL-NP20 RS03 Treated 20.08 6.52 135 0.08 113 0.028 0.0002 0.0202 0.228 3.6 0.00007 5.3 0.00000 0.00001 1.37 0.17 0.01 0.00015 7.9 9.3 0.00 0.0001 0.000	75	MIW-to-RAS_PL-NP20																					10.2	0.00 0.000	2 0.02											
79 MMY-16-RAS PL-NP20 RS03 Treated 22.12 6.55 129 0.09 96.1 0.0029 0.0020 0.0215 34.6 0.00007 4.9 0.000001 0.00001 1.38 0.19 0.01 0.00017 9.5 8 9.0 0.0000000001 0.0002 0.02 24.3 0.00001 0.00001 0.00005 18 0.01 0.00001 0.00005 18 0.01 0.00001 0.00	76	MIW-to-RAS_PL-NP20	RS03 Treated	20.08	6.62			113.9	0.0026	0.0002	0.0238	38.6	0.00007	5.3	0.00000	0.00001	0.00001	1.37	0.17	0.01	0.00018	7.9	9.3	0.00 0.000	1 0.02	25.7	0.00001	0.00001	0.00048	0.00005	17 0.0	1 0.0002	1.3479	0.0000	0.0008	0.0001 0.0000
79 MMV-Io-RAS PL-NP20 RS03 Treated 16.39 6.55 132 0.09 106.1 0.0029 0.0022 0.0229 3.7.7 0.00007 5.0 0.00001 0.00001 0.00001 0.00001 0.00001 1.38 0.19 0.01 0.00017 9.6 9.2 0.00 0.0022 25.3 0.00001 0.				23.27	6.56	123	0.09					35.4	0.00007	4.6					0.16	0.01 0	0.00017		8.3	0.00 0.000	0.02	22.1	0.00001	0.00001								
80 MNV-lo-RAS PL-NP20 RS03 Treated 18.30 6.56 129 0.09 106.1 0.0029 0.0022 0.0228 37.0 0.00007 4.9 0.00000 0.00001 0.00001 1.38 0.18 0.01 0.00017 8.8 9.0 0.00 0.0002 0.02 24.3 0.00001 0.0000		MIW-to-RAS PL-NP20	RS03 Treated	16.39	6.55	132	0.09	108.3	0.0029	0.0002	0.0229	37.7	0.00007						0.19	0.01	0.00017	0.0	9.2	0.00 0.000	2 0.02	25.3	0.00001					1 0.0002	1.3600	0.0000	0.0009	0.0001 0.0000
1 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	80	MIW-to-RAS PL-NP20		18.30	6.56	129																	9.0	0.00 0.000	2 0.02	24.3						1 0.0002	1.3634	0.0000	0.0009	.0001 0.0000
81 MINV-1b-RAS PL-NP20 RS03 Treated 18.55 6.52 129 0.10 104.7 0.0030 0.0002 0.0225 3.63 0.00007 4.9 0.00000 0.00001 0.	81	MIW-to-RAS PL-NP20																							2 0.02											
83 MMV-to-RAS PL-NP20 RS03 Treated 17.56 6.53 131 0.10 106.3 0.0029 0.0002 0.0022 7 37.4 0.00007 5.0 0.00001 0.00001 1.39 0.18 0.01 0.00016 9.3 9.1 0.00 0.0002 0.02 24.5 0.00001 0.00007 0.00005 0.00005 19 0.01 0.0002 1.3685 0.0000 0.0009	83	MIW-to-RAS PL-NP20	RS03 Treated	17.56	6.53	131	0.10	106.3	0.0029	0.0002	0.0227	37.4	0.00007	5.0	0.00000	0.00001	0.00001	1.39	0.18	0.01	0.00016	9.3	9.1	0.00 0.000	2 0.02	24.5	0.00001	0.00001	0.00057	0.00006	19 0.0	1 0.0002	1.3685	0.0000	0.0009	0.0001 0.0000
84 MNV-lo-RAS PL-NP20 RS03 Treated 22.28 6.57 126 0.09 102.9 0.0028 0.0002 0.0022 36.3 0.00007 4.7 0.00000 0.00001 1.43 0.17 0.01 0.00017 8.3 8.6 0.00 0.0002 0.02 23.1 0.00001 0.00001 0.00001 0.00001 0.00001 1.00001 0.0000	84	MIW-to-RAS PL-NP20																					8.6	0.00 0.000	2 0.02	23.1										
86 MW-lo-RAS PL-NP20 RS03 Treated 16.91 6.54 133 0.10 107.4 0.0029 0.0002 0.0024 37.9 0.00007 5.0 0.00000 0.00001 0.00002 1.41 0.19 0.01 0.00016 9.9 9.2 0.00 0.0002 0.02 24.9 0.0001 0.00001 0.00001 0.00005 20 0.01 0.0002 1.3896 0.0000 0.0009	86	MIW-to-RAS PL-NP20	RS03 Treated	16.91	6.54	133	0.10	107.4	0.0029	0.0002	0.0224	37.9	0.00007	5.0				1.41	0.19			9.9	9.2	0.00 0.000	2 0.02	24.9	0.00001	0.00001	0.00062	0.00006	20 0.0	1 0.0002	1.3896	0.0000	0.0009	0.0001 0.0000
67 MINV-19-RAS PL-NP20 RS03 Treated 22.62 6.56 124 0.09 100.4 0.0029 0.0002 0.0219 3.5.6 0.00007 4.6 0.00000 0.00001 1.44 0.17 0.01 0.00016 8.2 8.4 0.00 0.0002 0.02 22.4 0.00001 0.00004 0.00005 18 0.01 0.0002 1.4167 0.0000 0.0008	87	MIW-to-RAS PL-NP20	RS03 Treated	22.62	6.56	124	0.09	100.4	0.0029	0.0002	0.0219	35.6	0.00007	4.6								8.2	8.4	0.00 0.000	2 0.02	22.4	0.00001	0.00001	0.00049	0.00005	18 0.0	1 0.0002	1.4187	0.0000	0.0008	.0001 0.0000

Year	Scenario	Station	Flow Rate (L/s)	рН	(mg CaCO3/L)	Acidity (mg CaCO3/L)	Alkalinity (mg CaCO3/L)	Al (mg/L)	As (mg/L)			Cd (mg/L)	CI (mg/L)	Co (mg/L)	Cr (mg/L)		DOC (mg/L) (Fe ng/L) (Hg (mg/L) (K (mg/L)	Mg (mg/L)				Na mg/L) (ob g/L)			SO4 Sr mg/L) (mg/L	T1 (mg/l	TOC L) (mg/L)		U (mg/L)	V Zn (mg/L) (mg/L)
88 MIV	/-to-RAS PL-NP20	RS03 Treated	19.56	6.56	125	0.09	,	0.0028	0.0002	0.0220	36.0 0	00007	47	0.00000	0.00001	0.00001	1.43			0.00016	8.3	$\overline{}$	0.00 0.		0.02	22.7 0			0.00049 0.0				02 1.4124		0.0008	0.0001 0.0000
	/-to-RAS_PL-NP20	RS03 Treated	17.40	6.56	134	0.09	110.7	0.0028	0.0002	0.0231	38.3 0	0.00007	5.1	0.00000	0.00001	0.00001	1.37	0.18	0.01	0.00017	8.8	9.4	0.00 0.	0002	0.02	25.0 0	0.00001 0.0	0001 0	0.00053 0.0	00005	18 0.0	0.00	02 1.3473	0.0000	0.0008	0.0001 0.0000
		RS03 Treated RS03 Treated	21.95 14.21		125 133	0.08			0.0002		36.0 0 38.0 0				0.00001		1.43			0.00017	7.6 8.5	8.5 9.3	0.00 O. 0.00 O.		0.02		0.00001 0.0 0.00001 0.0									0.0001 0.0000 0.0001 0.0000
92 MIV		RS03 Treated	12.97	6.54	143	0.09			0.0002		40.5 0		5.6	0.00000	0.00001	0.00001		0.17	0.01 0	0.00017	8.7		0.00 0.	0002	0.02	27.2	0.00001 0.0	0001 0	0.00052 0.0	00005	19 0.0	0.00	02 1.3474	4 0.0000	0.0008	0.0001 0.0000
93 MM	/-to-RAS PL-NP20	RS03 Treated	13.89		143	0.09			0.0002		40.6				0.00001		1.28			0.00017	8.1		0.00 0.				0.00001 0.0									0.0001 0.0000
94 MW		RS03 Treated RS03 Treated	22.05 23.39	6.55	123 127	0.09			0.0002	0.0222	35.4 C	0.00007	4.6	0.00000	0.00001	0.00001	1.42			0.00017	7.3 8.0		0.00 0.	0001	0.02	21.6 0	0.00001 0.0 0.00001 0.0	0001 0	0.00040 0.0							0.0001 0.0000 0.0001 0.0000
96 MM	I-to-RAS PL-NP20	RS03 Treated	19.21	6.59	131	0.08	108.6	0.0027	0.0002	0.0227	37.8	.00007	4.9	0.00000	0.00001	0.00001	1.43	0.17	0.01	0.00017	7.8	9.0	0.00 0.	0001	0.02	23.7	0.00001 0.0	0001 0	0.00046 0.0	00005	17 0.0	0.00	02 1.4155	0.0000	0.0008	0.0001 0.0000
97 MW		RS03 Treated RS03 Treated	19.21 13.90		130 137	0.08			0.0002		37.5 0 39.0 0				0.00001					0.00017	7.5 8.3		0.00 O. 0.00 O.				0.00001 0.0 0.00001 0.0									0.0001 0.0000
99 MIV	/-to-RAS PL-NP20	RS03 Treated	15.49	6.57	138	0.09	115.0	0.0027	0.0002	0.0236	39.2	.00007	5.3	0.00000	0.00001	0.00001	1.33	0.17	0.01	0.00017	7.8	9.6	0.00 0.	0001	0.02	25.3	0.00001 0.0	0001 0	0.00044 0.0	00005	17 0.0	0.00	02 1.3152	2 0.0000	0.0007	0.0001 0.0000
100 MW	I-to-RAS PL-NP20	RS03 Treated RS03 Treated	28.74 15.05	6.60	126 137	0.08			0.0002		36.2 0 38.8 0	0.00007			0.00001		1.43	0.15		0.00017	6.9 8.6		0.00 O. 0.00 O.		0.02	22.1 0	0.00001 0.0 0.00001 0.0	0001 0	0.00038 0.0	00005						0.0001 0.0000 0.0001 0.0000
102 MIV	101010120	RS03 Treated	15.49			0.10	109.3				37.9				0.00001					0.00017	7.9	9.0	0.00 0.		0.03				0.00049 0.0							0.0001 0.0000
103 MW	/-to-RAS PL-NP20	RS03 Treated	14.64	6.49	137	0.11		0.0030	0.0002	0.0235	38.8	.00007	5.3	0.00000	0.00001	0.00002	1.30	0.17	0.01	0.00017	8.6		0.00 0.	0002	0.03	25.0 0	0.00001 0.0	0001 0			19 0.0	0.00	02 1.2785	0.0000	0.0008	0.0001 0.0000
		RS03 Treated RS03 Treated	16.55 24.10		135 127	0.10		0.0030	0.0002		38.4 0 36.5 0			0.00000	0.00001	0.00001	1.31			0.00017	7.3	9.6 8.8	0.00 0.		0.02		0.00001 0.0 0.00001 0.0			00005			02 1.2910			0.0001 0.0000
106 MW	/-to-RAS PL-NP20	RS03 Treated	16.37	6.55	130	0.09	106.1	0.0028	0.0002	0.0225	37.2	0.00007	4.9	0.00000	0.00001	0.00001	1.41	0.16	0.01	0.00017	7.6	9.0	0.00 0.	0001	0.02	22.8	0.00001 0.0	0001 0	0.00042 0.0	00005	17 0.0	0.00	02 1.3912	0.0000	0.0007	0.0001 0.0000
		RS03 Treated RS03 Treated	20.75 15.87		130	0.09	106.7		0.0002		37.2 0 37.9 0				0.00001					0.00017	7.3	8.9	0.00 0.		0.02		0.00001 0.0 0.00001 0.0		0.00040 0.0							0.0001 0.0000
109 MW	/-to-RAS PL-NP20	RS03 Treated	17.94	6.57	132	0.09	109.5	0.0028	0.0002	0.0230	37.8	.00007	5.0	0.00000	0.00001	0.00001	1.38	0.16	0.01 0	0.00017	7.1	9.1	0.00 0.	0001	0.02	23.4	0.00001 0.0	0001 0	0.00039 0.0	00005	17 0.0	0.00	02 1.3607	7 0.0000	0.0007	0.0001 0.0000
		RS03 Treated RS03 Treated	12.35 17.09		144 135	0.09		0.0028	0.0002		40.9 0 38.4 0				0.00001				0.01 0	0.00017	7.7	10.2	0.00 0.		0.02	26.3 0	0.00001 0.0 0.00001 0.0		0.00042 0.0				02 1.2814			0.0001 0.0000 0.0001 0.0000
		RS03 Treated	15.56		138	0.10			0.0002		39.1 0				0.00001					0.00017	7.7		0.00 0.		0.02		0.00001 0.0									0.0001 0.0000
		RS03 Treated RS03 Treated	24.20 22.85		125 121	0.09			0.0002		36.0 0 35.1 0				0.00001					0.00017 0.00016	6.9		0.00 O.				0.00001 0.0 0.00001 0.0		0.00036 0.0 0.00036 0.0							0.0001 0.0000 0.0001 0.0000
115 MIM	/-to-RAS PL-NP20	RS03 Treated RS03 Treated	17.14	6.52	135	0.10	109.4		0.0002	0.0228	38.3	0.00007	5.0	0.00000	0.00001	0.00002	1.36	0.16	0.01	0.00016	8.0	9.5	0.00 0.	0001	0.03		0.00001 0.0		0.00036 0.0		18 0.0	0.00	02 1.3442	0.0000	0.0008	0.0001 0.0000
116 MM	/-to-RAS PL-NP20	RS03 Treated	18.65		136	0.09			0.0002		38.8				0.00001		1.34			0.00017	7.5		0.00 0.				0.00001 0.0									0.0001 0.0000
		RS03 Treated RS03 Treated	17.76 19.63		137	0.09			0.0002		39.2 0 36.5 0				0.00001	0.00001	1.35			0.00017	7.1 6.5	9.6 8.7	0.00 0.			21.5 0	0.00001 0.0 0.00001 0.0		0.00037 0.0		16 0.0					0.0001 0.0000 0.0001 0.0000
119 MIM	/-to-RAS PL-NP20	RS03 Treated	19.12	6.57	130	0.09	107.0	0.0028	0.0002	0.0226	37.3	.00007	4.9	0.00000	0.00001	0.00001	1.40	0.15	0.01	0.00017	6.8	9.0	0.00 0.	0001	0.02	22.4	0.00001 0.0	0001 0			16 0.0	0.00	02 1.3797	7 0.0000	0.0007	0.0001 0.0000
120 MW		RS03 Treated RS03 Treated	20.08 18.74		126 135	0.09			0.0002		36.2 C				0.00001					0.00017	6.7 7.0		0.00 O. 0.00 O.				0.00001 0.0		0.00034 0.0							0.0001 0.0000
122 MIW	/-to-RAS PL-NP20	RS03 Treated	18.74		132	0.09			0.0002		37.8				0.00001		1.39			0.00017	6.6	9.1	0.00 0.	0001			0.00001 0.0		0.00033 0.0							0.0001 0.0000
123 MW		RS03 Treated RS03 Treated	20.67 15.77		129 139	0.09			0.0002		37.1 C	0.00007			0.00001					0.00017	6.5	8.9	0.00 O. 0.00 O.	0001			0.00001 0.0 0.00001 0.0		0.00032 0.0							0.0001 0.0000 0.0001 0.0000
125 MW	/-to-RAS PL-NP20	RS03 Treated	21.05	6.56	126	0.09	102.8	0.0029	0.0002	0.0223	36.1 0	.00007	4.7	0.00000	0.00001	0.00001	1.42	0.14	0.01	0.00017	6.3	8.6	0.00 0.	0001	0.02	21.0	0.00001 0.0	0001 0	0.00030 0.0	00004	16 0.0	0.00	02 1.3951	0.0000	0.0007	0.0001 0.0000
126 MW	/-to-RAS PL-NP20	RS03 Treated RS03 Treated	22.20 21.16		120 129	0.09			0.0002		34.6				0.00001		1.45			0.00016	6.5 7.2		0.00 0.		0.02		0.00001 0.0 0.00001 0.0									0.0001 0.0000 0.0001 0.0000
		RS03 Treated	14.99		132	0.10			0.0002		36.8 C				0.00001					0.00016	7.0		0.00 0.		0.02		0.00001 0.0									0.0001 0.0000
		RS03 Treated	18.01	6.55	135	0.09		0.0028		0.0232	38.5		5.1	0.00000	0.00001	0.00001	1.34	0.15		0.00017	6.8	9.4	0.00 0.	0001	0.02	23.3			0.00034 0.0				02 1.3288			0.0001 0.0000
		RS03 Treated RS03 Treated	18.49 20.66		127 126	0.09			0.0002		36.4 0 36.2 0				0.00001					0.00017	6.1		0.00 0.		0.02		0.00001 0.0 0.00001 0.0		0.00029 0.0							0.0001 0.0000
		RS03 Treated	20.49		125	0.09			0.0002		35.9				0.00001					0.00016	6.5	8.6	0.00 0.	0001	0.02		0.00001 0.0									0.0001 0.0000
		RS03 Treated RS03 Treated	21.17 14.20	6.50	123 135	0.10 0.10	98.5 110.4		0.0002	0.0217	35.3 0 38.4 0			0.00000	0.00001	0.00002	1.43		0.01 0	0.00016	7.4	9.6	0.00 0.		0.02	23.2 0	0.00001 0.0		0.00032 0.0	00004	18 0.0		02 1.4066			0.0001 0.0000
		RS03 Treated	21.53	6.54	135	0.10			0.0002		38.3	0.00007			0.00001					0.00017	6.8	9.5	0.00 0.	0001	0.02		0.00001 0.0					0.00	02 1.3268	0.0000	0.0007	0.0001 0.0000
		RS03 Treated RS03 Treated	14.87 14.97		139	0.09			0.0002		39.5 C				0.00001					0.00017	6.6	9.7	0.00 O.	0001			0.00001 0.0 0.00001 0.0									0.0001 0.0000 0.0001 0.0000
138 MW	/-to-RAS_PL-NP20	RS03 Treated		6.59		0.08			0.0002	0.0228	36.8	0.00007			0.00001		1.41			0.00017	5.5	8.7	0.00 0.	0001	0.02	21.4 0	0.00001 0.0	0001 0	0.00025 0.0	00004	16 0.0	0.00	02 1.3849	0.0000	0.0006	0.0001 0.0000
		RS03 Treated RS03 Treated	21.62 26.78	6.59	130 117	0.08	93.1		0.0002	0.0228	37.4 C	0.00007			0.00001		1.41	0.14	0.01 0	0.00017	5.8	8.9 7.8	0.00 0.	0001	0.02		0.00001 0.0 0.00001 0.0				15 0.0	0.00	02 1.3891 02 1.4715	5 0.0000	0.0006	0.0001 0.0000 0.0001 0.0000
141 MIW	/-to-RAS PL-NP20	RS03 Treated	17.08	6.54	134	0.10	109.0	0.0029	0.0002	0.0225	38.2 0	.00007	4.9	0.00000	0.00001	0.00001	1.39	0.15	0.01 0	0.00016	6.9	9.3	0.00 0.	0001	0.02	22.3	0.00001 0.0	0001 0	0.00034 0.0	00004	17 0.0	0.00	02 1.3720	0.0000	0.0007	0.0001 0.0000
142 MIV	/-to-RAS PL-NP20 /-to-RAS PL-NP20	RS03 Treated RS03 Treated	21.92 14.61	6.59	126 139	0.08			0.0002	0.0223	36.4 C	0.00007	4.7	0.00000	0.00001	0.00001				0.00017	5.8 6.8	8.6	0.00 O. 0.00 O.	0001			0.00001 0.0 0.00001 0.0		0.00027 0.0							0.0001 0.0000
144 MIV	I-to-RAS PL-NP20	RS03 Treated	18.82	6.52	127	0.10	103.0		0.0002		36.3		4.7	0.00000	0.00001	0.00001		0.14	0.01	0.00016	6.3		0.00 0.	0001	0.02	20.9	0.00001 0.0	0001 0	0.00028 0.0	00004	17 0.0	0.00	02 1.3538	0.0000	0.0006	0.0001 0.0000
145 MIW	/-to-RAS PL-NP20	RS03 Treated RS03 Treated	13.22 21.40			0.10			0.0003		41.0 0 35.4 0				0.00001		1.26			0.00017	7.0		0.00 O. 0.00 O.				0.00001 0.0 0.00001 0.0									0.0001 0.0000 0.0001 0.0000
147 MIW	/-to-RAS PL-NP20	RS03 Treated	21.94	6.57	129	0.09	105.4	0.0028	0.0002	0.0224	36.9	.00007	4.7	0.00000	0.00001	0.00001	1.41	0.14	0.01	0.00017	6.0	8.9	0.00 0.	0001	0.02	21.1 0	0.00001 0.0	0001 0	0.00027 0.0	00004	15 0.0	0.00	02 1.3932	2 0.0000	0.0006	0.0001 0.0000
148 MIW	/-to-RAS PL-NP20	RS03 Treated RS03 Treated	18.37 20.92	6.54	127 123	0.09			0.0002		36.3 C	0.00007			0.00001		1.42			0.00016	6.0 5.8	8.7	0.00 O. 0.00 O.	0001	0.02		0.00001 0.0 0.00001 0.0									0.0001 0.0000 0.0001 0.0000
150 MIV	/-to-RAS PL-NP20	RS03 Treated	17.11	6.54	129	0.09	104.8	0.0029	0.0002	0.0224	36.8	.00007	4.7	0.00000	0.00001	0.00001	1.38	0.14	0.01	0.00016	6.2	8.9	0.00 0.	0001	0.02	21.1 0	0.00001 0.0	0001 0	0.00028 0.0	00004	16 0.0	0.00	02 1.3651	0.0000	0.0006	0.0001 0.0000
151 MIW	/-to-RAS PL-NP20	RS03 Treated	24.47			0.09			0.0002		36.5				0.00001					0.00017	5.9		0.00 0.	0001	0.02		0.00001 0.0									0.0001 0.0000
		RS03 Treated RS03 Treated	21.76 20.80		126 127	0.09			0.0002		36.3 C				0.00001 0.00001	0.00001				0.00016 0.00017	5.8 5.7	8.6	0.00 0.	0001	0.02		0.00001 0.0 0.00001 0.0		0.00026 0.0							0.0001 0.0000 0.0001 0.0000
154 MIW	/-to-RAS PL-NP20	RS03 Treated	19.92	6.56	125	0.09	102.0	0.0029	0.0002	0.0221	36.0 0	0.00007	4.6	0.00000	0.00001	0.00001	1.44	0.13	0.01	0.00017	5.7	8.6	0.00 0.	0001	0.02	20.0	0.00001 0.0	0001 0	0.00024 0.0	00004	16 0.0	0.00	02 1.4193	0.0000	0.0006	0.0001 0.0000
		RS03 Treated RS03 Treated	17.06 22.21		130 128	0.09		0.0029	0.0002		37.1 0 36.6 0				0.00001					0.00017	6.0 5.9		0.00 0.		0.02		0.00001 0.0 0.00001 0.0		0.00026 0.0							0.0001 0.0000
157 MIV	/-to-RAS PL-NP20	RS03 Treated	18.39	6.53	127	0.09	103.0	0.0029	0.0002	0.0222	36.4 0	.00007	4.6	0.00000	0.00001	0.00002	1.42	0.13	0.01 0	0.00016	5.9	8.8	0.00 0.	0001	0.02	20.3	0.00001 0.0	0001 0	0.00025 0.0	00004	16 0.0	0.00	02 1.3992	2 0.0000	0.0006	0.0001 0.0000
		RS03 Treated RS03 Treated	16.51 22.81		132 127	0.10			0.0002	0.0227	37.6 C			0.00000	0.00001	0.00002	1.35			0.00016	6.3 5.8	9.3 8.8	0.00 0.	0001	0.03	21.6 0	0.00001 0.0 0.00001 0.0			00004	17 0.0		02 1.3366			0.0001 0.0000 0.0001 0.0000
160 MW	/-to-RAS_PL-NP20	RS03 Treated	15.32	6.51	134	0.10	109.0	0.0030	0.0002	0.0228	38.0 0	.00007	5.0	0.00000	0.00001	0.00001	1.35	0.14	0.01	0.00016	6.3	9.4	0.00 0.	0001	0.02	21.9	0.00001 0.0	0001 0	0.00027 0.0	00004	17 0.0	0.00	02 1.3258	0.0000	0.0006	0.0001 0.0000
		RS03 Treated RS03 Treated	16.09 12.21		137	0.10			0.0002		38.8 C				0.00001					0.00017	6.1 5.9	9.7	0.00 0.	0001	0.02	22.7 0	0.00001 0.0 0.00001 0.0	0001 0	0.00026 0.0		15 0.0 16 0.0	0.00	02 1.3006	0.0000	0.0006	0.0001 0.0000 0.0001 0.0000
163 MIV	/-to-RAS_PL-NP20	RS03 Treated	20.91	6.59	134	0.08	112.8	0.0028	0.0002	0.0236	38.3	.00007	5.1	0.00000	0.00001	0.00001	1.35	0.13	0.01	0.00017	5.2	9.3	0.00 0.	0001	0.02	22.5	0.00001 0.0	0001 0	0.00020 0.0	00004	15 0.0	0.00	02 1.3269	0.0000	0.0006	0.0001 0.0000
		RS03 Treated RS03 Treated	19.00 19.86		130 122	0.09			0.0002		37.3 0 35.2 0				0.00001		1.39			0.00017	5.6 5.4		0.00 O.		0.02		0.00001 0.0 0.00001 0.0									0.0001 0.0000 0.0001 0.0000
166 MIW	/-to-RAS PL-NP20	RS03 Treated		6.55	135	0.09			0.0002		38.6		414	0.00000	0.00001	0.00001				0.00016	5.8	9.5	0.00 0.	0001	0.02				0.00021 0.0		15 0.0	0.00	02 1.3382	2 0.0000	0.0006	0.0001 0.0000
167 MIW	/-to-RAS PL-NP20	RS03 Treated	18.02	6.56	131	0.09	108.6	0.0028	0.0002	0.0229	37.6	.00007	4.9	0.00000	0.00001	0.00001	1.38	0.13	0.01	0.00017	5.4	9.1	0.00 0.	0001	0.02	21.4	0.00001 0.0	0001 0	0.00022 0.0		15 0.0	0.00	02 1.3605	0.0000	0.0006	0.0001 0.0000
168 MIV		RS03 Treated RS03 Treated	20.42 10.61		131 149	0.09		0.0028 0.0028	0.0002		37.5 C				0.00001					0.00017	5.5		0.00 O. 0.00 O.				0.00001 0.0 0.00001 0.0									0.0001 0.0000 0.0001 0.0000
170 MIW	/-to-RAS PL-NP20	RS03 Treated	17.26			0.08			0.0002		38.5 0				0.00001		1.35			0.00017	5.1		0.00 0.		0.02	22.4	0.00001 0.0	0001 0	0.00020 0.0							0.0001 0.0000
171 MIV		RS03 Treated RS03 Treated	23.94 13.25	6.57	124 137	0.08 0.10			0.0002		35.8 C				0.00001	0.00001	1.44	0.12 0.13	0.01 0	0.00017	5.0 5.8	9.6	0.00 O. 0.00 O.	0001	0.02		0.00001 0.0 0.00001 0.0									0.0001 0.0000 0.0001 0.0000
173 MIV	/-to-RAS PL-NP20	RS03 Treated	17.65			0.09				0.0233			5.0	0.00000	0.00001	0.00001	1.36	0.13	0.01	0.00017	5.3	9.3	0.00 0.	0001	0.02	22.0	0.00001 0.0	0001	0.00021 0.0	00004	15 0.0	0.00	02 1.3403	0.0000	0.0006	0.0001 0.0000

Year	Scenario	Station	Flow Rate (L/s)	рН	(mg	(mg CaCO3/L)	Alkalinity (mg CaCO3/L)	AI (mg/L)	As (mg/L)		Ca mg/L) (CI mg/L)	Co (mg/L)	Cr (mg/L)		DOC (mg/L) (Fe ng/L)	Hg (mg/L) (K (mg/L) (Mg (mg/L) (Mn M mg/L) (mg			NI (mg/L)	Pb (mg/L)	Sb (mg/L)	Se (mg/L)	SO4 Si (mg/L) (mg	r T //L) (mg			U (mg/L)	V (mg/L)	Zn (mg/L)
174 N	IW-to-RAS PL-NP20	RS03 Treated	14.50	6.56	139	0.09	116.4	0.0028	0.0002	0.0239	39.6	.00007	5.3 (0.00000	0.00001	0.00001	1.33	0.13	0.01	0.00017	5.4	$\overline{}$	0.00 0.0	01 0	02 23.1	1 0.00001	0.00001	0.00021	0.00004	16 0	.01 0.0	002 1.312	6 0.0000	0.0006	0.0001	0.0000
		RS03 Treated	12.36			0.09			0.0002		40.6						1.28			0.00017	5.4		0.00 0.0						0.00004			002 1.268				
	IW-to-RAS PL-NP20 IW-to-RAS PL-NP20	RS03 Treated RS03 Treated	20.08 23.27		134 122	0.08			0.0002		38.4 C			0.00000			1.45			0.00018	4.7		0.00 0.0						7 0.00004 7 0.00004			002 1.347 002 1.429				
178 N	IW-to-RAS PL-NP20	RS03 Treated	22.12	6.56	119	0.09	95.8	0.0029	0.0002	0.0213	34.4	.00007	4.2 (0.00000	0.00001	0.00001	1.47	0.12	0.01	0.00016	5.1	8.0	0.00 0.0	01 0.	02 18.1	1 0.00001	0.00001	0.00019	0.00004	15 0	.01 0.0	1.445	4 0.0000	0.0006	0.0001	0.0000
179 N	IW-to-RAS PL-NP20	RS03 Treated RS03 Treated	16.39 18.30		131	0.09			0.0002	0.0226	37.5 C	.00007		0.00000			1.38			0.00017	5.5 5.2	9.1	0.00 0.0	01 0	02 21.0				0.00004			002 1.360 002 1.363				
181 N	IW-to-RAS PL-NP20 IW-to-RAS PL-NP20	RS03 Treated	18.55		128	0.10			0.0002	0.0224	36.7	.00007	4.7 (0.00000	0.00001	0.00001	1.38			0.00017	5.5	8.9	0.00 0.0	01 0	02 20.3				0.00004	16 0	.01 0.0	002 1.360	3 0.0000	0.0006	0.0001	0.0000
182 N	IW-to-RAS PL-NP20	RS03 Treated	22.87 17.56		126	0.09			0.0002		36.1 C			0.00000						0.00016	5.3	8.7	0.00 0.0	01 0.					0.00004			002 1.380				
183 N	IW-to-RAS PL-NP20 IW-to-RAS PL-NP20	RS03 Treated RS03 Treated	17.56 22.28		130 125	0.10			0.0002		36.1			0.00000			1.39			0.00016	5.5		0.00 0.0						0.00004			002 1.368 002 1.412				
185 N	IW-to-RAS PL-NP20	RS03 Treated	32.87			0.08			0.0002	0.0210	33.9	.00007		0.00000						0.00016	4.8	7.7	0.00 0.0	01 0.					7 0.00003			002 1.494				
186 N	IW-to-RAS PL-NP20 IW-to-RAS PL-NP20	RS03 Treated RS03 Treated	16.91 22.62		132	0.10			0.0002		37.7 C	.00007		0.00000						0.00016	5.7 5.0	9.1	0.00 0.0	01 0	02 20.5	0.00001	0.00001	0.00022	0.00004	16 0		002 1.389 002 1.418				
188 N	IW-to-RAS PL-NP20	RS03 Treated	19.56	6.56	124	0.09	101.2	0.0028	0.0002	0.0218	35.8	.00007	4.5 (0.00000	0.00001	0.00001	1.43	0.12	0.01	0.00016	5.0	8.5	0.00 0.0	01 0.	02 19.2	2 0.00001	0.00001	0.00018	0.00004	15 0	.01 0.0	002 1.412	4 0.0000	0.0005	0.0001	0.0000
	IW-to-RAS PL-NP20	RS03 Treated RS03 Treated	17.40 21.95		134	0.09			0.0002		38.1 C			0.00000			1.37			0.00017	5.3		0.00 0.0						0.00004			002 1.347				
	IW-to-RAS PL-NP20	RS03 Treated	14.21		125	0.09		0.0028			37.8			0.00000		0.00001	1.36			0.00017	5.3		0.00 0.0			1 0.00001			0.00004			002 1.407 002 1.347				0.0000
	IW-to-RAS PL-NP20	RS03 Treated	12.97			0.09			0.0002	0.0242	40.3	.00007	5.4	0.00000	0.00001					0.00017	5.3		0.00 0.0			7 0.00001						002 1.262				
	IW-to-RAS PL-NP20 IW-to-RAS PL-NP20	RS03 Treated RS03 Treated	13.89 22.05		142 123	0.09			0.0002		40.4 C			0.00000			1.28			0.00017	5.0 4.8		0.00 0.0			0.00001			0.00004			002 1.258 002 1.398				
	IW-to-RAS PL-NP20	RS03 Treated	23.39		126	0.09			0.0002		36.2	.00007		0.00000						0.00017	5.1		0.00 0.0						0.00004			002 1.406				
	IW-to-RAS_PL-NP20	RS03 Treated RS03 Treated	19.21 19.21	6.59	131 130	0.08		0.0027	0.0002	0.0226	37.6 0			0.00000			1.43			0.00017	4.9		0.00 0.0			6 0.00001			0.00004			002 1.415 002 1.405				
198 N	IW-to-RAS_PL-NP20	RS03 Treated	13.90	6.53	136	0.09	112.4	0.0028	0.0002	0.0232	38.8	.00007	5.1 (0.00000	0.00001	0.00001	1.35	0.13	0.01	0.00017	5.3	9.5	0.00 0.0	01 0	02 21.9	9 0.00001	0.00001	0.00019	0.00004	15 0	.01 0.0	002 1.334	8 0.0000	0.0005	0.0001	0.0000
	IW-to-RAS_PL-NP20 ase Case (NP20)	RS03 Treated SC01 Untreated	15.49 46.83		137 437	0.09			0.0002	0.0235	39.1 0			0.00000			1.33 0.95			0.00017	5.0 72.6		0.00 0.0		02 22.4				0.00004			002 1.315 001 0.878				
	ase Case (NP20)	SC01 Untreated	23.41	6.93	462	0.00	126.0	0.0110	0.6743	0.3513	116.7	.00011	250.4	0.02850	0.00223	0.00055	0.86	1.62	6.69	0.00012	87.4	41.4	0.27 0.14	176 6.	23 368.2	2 0.20563	0.00849	0.37369	0.01850	407 4	.58 0.0	0.819	3 0.1054	0.0399	0.0143	0.0107
	ase Case (NP20)	SC01 Untreated SC01 Untreated	20.98 19.58		374 344	0.00			0.4932			.00010					1.08			0.00015	85.8		0.22 0.14 0.23 0.11						7 0.01894 2 0.02435			001 1.015 001 1.010				
4 B	ase Case (NP20) ase Case (NP20)	SC01 Untreated	22.10	7.22	303	0.00	141.4	0.0134	0.3393	0.2843	75.6	.00009	123.2	0.02715	0.00128	0.00048	1.12	1.83	4.15	0.00016	108.3	27.7	0.21 0.1	311 9.	23 280.6	6 0.09587	7 0.00402	0.46226	0.02444	305 4	.43 0.0	002 1.048	3 0.0483	0.0498	0.0188	0.0067
5 B	ase Case (NP20)	SC01 Untreated SC01 Untreated	31.35 21.93		277 290	0.00			0.2817		69.2 0 71.6 0			0.02684			1.19			0.00017		25.3	0.19 0.1	46 9	67 265.9	9 0.07817	0.00329	0.47012	0.02515	283 4 322 4		002 1.130 002 1.058				
	ase Case (NP20) ase Case (NP20)	SC01 Untreated SC01 Untreated		7.32		0.00			0.3027			.00009					1.11			0.00016			0.23 0.2									002 1.058				
8 B	ase Case (NP20)	SC01 Untreated	21.11			0.00			0.2976			.00009								0.00016	163.4	27.6	0.26 0.2	28 14	91 345.8	8 0.08233	0.00340	0.69334	0.03658	359 5		002 1.049				
	ase Case (NP20) ase Case (NP20)	SC01 Untreated SC01 Untreated	22.82 15.52	7.32	280 306	0.00			0.2731		68.9 C			0.03600			1.19				152.6 183.1	26.2	0.24 0.2	63 13. 154 16.	89 325.0 57 381.7	7 0.08984	0.00316	0.64694	0.03432	340 4 395 5		002 1.129 002 1.004				
11 E	ase Case (NP20)	SC01 Untreated	22.62	7.33	277	0.00			0.2648			.00009								0.00017	177.9	26.3	0.27 0.2	67 16.	12 356.0	0.07301	0.00301	0.75579	0.03992	372 4	.90 0.0	002 1.100	3 0.0355	0.0799	0.0313	0.0071
	ase Case (NP20) ase Case (NP20)	SC01 Untreated SC01 Untreated	20.66 31.77		291 274	0.00			0.2910			.00009					1.10			0.00016			0.30 0.3						0.04438			002 1.040 002 1.141				
	ase Case (NP20)	SC01 Untreated	31.12	7.35	270	0.00			0.2539		65.9	.00009		0.03996			1.22	1.87	3.45	0.00017	182.4	25.5	0.27 0.3	15.	93 357.0	0.07018	0.00290	0.77885	0.04115	372 4	.68 0.0	002 1.147	8 0.0341	0.0813	0.0321	0.0070
	ase Case (NP20) ase Case (NP20)	SC01 Untreated SC01 Untreated	23.24 24.15	7.26	307 304	0.00			0.3252	0.4482	74.1 0	.00009		0.04761		0.00044	1.04			0.00015	219.5	29.7	0.33 0.3	61 18	72 428.6	6 0.09100	0.00370	0.93948	0.04907	441 5	.50 0.0	002 0.985	7 0.0445	0.0958	0.0385	0.0083
	ase Case (NP20)	SC01 Untreated	22.47	7.29	298	0.00			0.3077		72.6			0.04122			1.10				197.0	28.4	0.30 0.3	148 15.	93 390.0				0.04437			002 1.052				
	ase Case (NP20)	SC01 Untreated	25.98		279	0.00			0.2688			.00009		0.03837			1.17			0.00017			0.29 0.3						0.04314			002 1.114				
	ase Case (NP20) ase Case (NP20)	SC01 Untreated SC01 Untreated	24.77 27.05	7.32	282 281	0.00	148.3	0.0118	0.2766	0.3526	68.9 C			0.03656			1.16			0.00017	189.5	26.7	0.28 0.2			2 0.07497			0.04236			002 1.109 002 1.104			0.0325	
	ase Case (NP20) ase Case (NP20)	SC01 Untreated SC01 Untreated	23.97 24.27		294 287	0.00			0.2994		71.7	.00009		0.03540			1.12			0.00017			0.29 0.2						0.04208		.99 0.0	002 1.069 002 1.085	0 0.0413	0.0785	0.0320	0.0070
	ase Case (NP20) ase Case (NP20)	SC01 Untreated SC01 Untreated	27.10		287	0.00			0.2858			.00009					1.14			0.00017			0.28 0.2 0.28 0.2						0.04154			002 1.085 002 1.098				
	ase Case (NP20)	SC01 Untreated	20.15			0.00			0.3068			.00009								0.00016		28.3	0.28 0.2	718 11.	90 355.2											
	ase Case (NP20) ase Case (NP20)	SC01 Untreated SC01 Untreated	28.29 32.04	7.35	271 273	0.00			0.2524		66.2 C			0.02892			1.20	1.82	3.49	0.00017	170.0 170.6	25.6 25.9	0.26 0.2	36 10	96 321.2 69 320.7	7 0.06798	0.00286	0.74562	0.03931	347 4 351 4	.85 0.0	002 1.140 002 1.123	0.0336	0.0709	0.0294	0.0059
27 B	ase Case (NP20)	SC01 Untreated	30.91	6.87	292	0.04			0.2783			.00009					1.05	1.80	4.22	0.00015	165.0	28.4	0.25 0.2	105 10.	14 316.3	3 0.07433	0.00338	0.71709	0.03750	355 4	.84 0.0	0.986	5 0.0370	0.0677	0.0279	0.0060
28 B	ase Case (NP20) ase Case (NP20)	SC01 Untreated SC01 Untreated	23.50 27.05	6.65	298 293	0.07			0.2721		70.7 C	.00009		0.02413			0.96			0.00015		29.4	0.23 0.2 0.22 0.1	179 9. 189 8	22 294.6	0.07143	0.00349	0.65642	0.03430	334 4 316 4	26 0.0	002 0.922 002 0.912	0.0356	0.0617	0.0254	0.0058
30 E	ase Case (NP20)	SC01 Untreated	28.80	6.60	275	0.08	151.3	0.0283	0.2247	0.2073	65.3	.00009	79.1	0.01887	0.00098	0.00091	1.04	1.44	4.16	0.00016	128.3	27.1	0.19 0.1	02 7	33 245.4	4 0.05692	0.00301	0.54644	0.02879	289 3	.93 0.0	0.984	5 0.0284	0.0519	0.0210	0.0049
31 B	ase Case (NP20) ase Case (NP20)	SC01 Untreated SC01 Untreated	32.40 33.41		272 277	0.09			0.2198		64.6	.00009		0.01794			1.04			0.00016 0.00015			0.19 0.1						0.02814	286 3 294 4						
33 B	ase Case (NP20)	SC01 Untreated	36.84	6.50	284	0.11	153.0	0.0313	0.2339	0.2009	66.6	.00009	80.7 (0.01798	0.00098	0.00100	0.95	1.51	4.59	0.00015	132.6	28.5	0.20 0.1	03 7.	08 247.7	7 0.05793	0.00318	0.56445	0.02955	296 4	.10 0.0	0.898	4 0.0289	0.0524	0.0215	0.0048
34 B	ase Case (NP20)	SC01 Untreated SC01 Untreated	26.14	6.41	303 290	0.13 0.12			0.2644		70.5 C	.00009	91.1 (0.01820	0.00105	0.00110	0.83	1.56	5.15	0.00013			0.20 0.1	26 7	02 257.4	4 0.06636	0.00366	0.57051	0.02956	315 4 285 3	.20 0.0	002 0.771 002 0.886	6 0.0333	0.0531	0.0216	0.0052
	ase Case (NP20) ase Case (NP20)	SC01 Untreated	24.08	6.43	300	0.13	154.3	0.0325	0.2578	0.1913	70.4	.00010	88.7 (0.01616	0.00105	0.00109	0.86	1.47	4.99	0.00014	123.8	30.3	0.19 0.10	30 6.	01 241.6	6 0.06503	0.00360	0.52196	0.02722	289 3	.97 0.0	0.832	7 0.0327	0.0476	0.0197	0.0050
37 E	ase Case (NP20)	SC01 Untreated	22.80			0.12			0.2408								0.95	1.38	4.60	0.00015	114.1		0.18 0.1	08 5	30 225.7	7 0.06077	0.00335	0.48255	0.02533	272 3	.75 0.0	0.905	7 0.0306	0.0443	0.0181	0.0047
	ase Case (NP20) ase Case (NP20)	SC01 Untreated SC01 Untreated	29.29 32.07		267 271	0.10			0.2105		63.6 C			0.01354			1.06			0.00016			0.17 0.14 0.17 0.14						9 0.02512 7 0.02488			002 0.995 002 1.002				
40 B	ase Case (NP20)	SC01 Untreated	43.49	6.54	263	0.10	151.6	0.0303	0.2045	0.1576	62.5	.00009	68.7	0.01312	0.00092	0.00093	1.07	1.40	4.09	0.00016	114.6	25.9	0.17 0.1	06 4	98 212.7	7 0.04928	0.00276	0.49339	0.02606	263 3	.79 0.0	0.999	8 0.0247	0.0450	0.0185	0.0041
	ase Case (NP20) ase Case (NP20)	SC01 Untreated SC01 Untreated	28.80 34.23		300 276	0.14		0.0340	0.2602	0.1760	70.4 C			0.01424			1.02			0.00014			0.19 0.1 0.16 0.1						0.02658			002 0.818 002 0.969				
43 E	ase Case (NP20)	SC01 Untreated	25.90	6.37	302	0.15	155.4	0.0351	0.2639	0.1737	70.4	.00009	88.5	0.01395	0.00104	0.00110	0.82	1.56	5.22	0.00013	124.5	30.6	0.19 0.1	84 5.	03 237.4	4 0.06512	0.00364	0.53046	0.02749	295 4	.17 0.0	002 0.772	8 0.0329	0.0472	0.0196	0.0048
	ase Case (NP20) ase Case (NP20)	SC01 Untreated SC01 Untreated	32.42 22.66	6.43	280 308	0.13 0.16			0.2290	0.1542	72.0 C			0.01220		0.00102	0.96			0.00015	112.8		0.17 0.14			4 0.05577 2 0.06818			0.02531			002 0.912 002 0.764				
46 B	ase Case (NP20)	SC01 Untreated	35.54	6.47	267	0.12	152.0	0.0322	0.2112	0.1402	63.6	.00010	70.1	0.01073	0.00094	0.00099	1.04	1.35	4.25	0.00015	103.4	26.4	0.16 0.13	318 3.	87 198.1	1 0.05108	0.00291	0.44310	0.02339	251 3	.63 0.0	0.972	2 0.0258	0.0401	0.0163	0.0040
	ase Case (NP20) ase Case (NP20)	SC01 Untreated SC01 Untreated	34.49 32.41		278 286	0.13 0.14	152.3	0.0315	0.2262	0.1421	66.1 C			0.01062			1.00 0.93	1.33	4.45	0.00015	100.5	27.5	0.16 0.13	258 3.	70 199.4	4 0.05587 9 0.0586	0.00316	0.42734	0.02255	248 3 267 3	.58 0.0	002 0.955	0.0283	0.0382	0.0157	0.0042
49 B	ase Case (NP20)	SC01 Untreated	35.37	6.43	272	0.13	152.0	0.0334	0.2187	0.1354	64.7	.00010	72.5	0.00991	0.00096	0.00102	1.02	1.32	4.37	0.00015	98.4	26.8	0.15 0.13	240 3.	48 193.4	4 0.05336	0.00305	0.41974	0.02212	248 3	.55 0.0	0.954	6 0.0270	0.0379	0.0154	0.0040
50 B	ase Case (NP20)	SC01 Untreated SC01 Untreated	29.66 39.24			0.15			0.2390		67.5			0.01033			0.93			0.00014			0.16 0.1						0.02285			002 0.881				
52 B	ase Case (NP20) ase Case (NP20)	SC01 Untreated SC01 Untreated	39.24 35.76			0.14	102.0		0.2291		66.5			0.00969			0.96			0.00015	98.0	27.9	0.15 0.13 0.15 0.13	220 3.	29 195.9	9 0.05682	0.00325	0.41995	0.02191	251 3	.64 0.0	002 0.922 002 0.902	3 0.0288	0.0374	0.0153	0.0041
53 B	ase Case (NP20)	SC01 Untreated	33.78	6.40	280	0.14	152.5	0.0339	0.2302		66.4	.00010	76.1 (0.00920	0.00099	0.00107	0.98	1.32	4.59	0.00015	94.8	27.7	0.15 0.1	166 3.	09 191.0	0.05648	0.00324	0.40215	0.02115	245 3	.54 0.0	0.919	5 0.0287	0.0359	0.0146	0.0041
54 B	ase Case (NP20) ase Case (NP20)	SC01 Untreated SC01 Untreated	33.65 29.48	6.40	278 285	0.14 0.15		0.0334	0.2294		66.0 0 67.4 0			0.00912			0.98				96.8 98.6		0.15 0.1 0.16 0.1						0.02169 0.02198			002 0.918 002 0.883				
56 B	ase Case (NP20)	SC01 Untreated	36.47		278	0.14			0.2300			.00010								0.00015	95.1	27.5	0.15 0.1	56 2	88 190.0	0.05604	0.00319	0.40588	0.02135	243 3						
57 B	ase Case (NP20) ase Case (NP20)	SC01 Untreated SC01 Untreated	31.94 29.87	6.37	283 295	0.15 0.16	152.8 153.7		0.2383		67.0 C	.000010				0.00106	0.94	1.40	5.09	0.00014	97.5 100.8	28.1	0.15 0.1 0.16 0.1	203 2	91 194.0 97 201	0.05798 5 0.06239	0.00329	0.41628	0.02179	250 3 258 3	.72 0.0	0.883 002 0.823	9 0.0318	0.0365	0.0150	0.0041
59 B	ase Case (NP20)	SC01 Untreated	37.80			0.15	151.9	0.0340	0.2279	0.1219	65.7	.00010	74.5	0.00807	0.00098	0.00105	0.99	1.33	4.55	0.00015	90.0	27.3	0.14 0.1	93 2	61 183.0	0.05552	0.00317	0.38304	0.02016	238 3	.53 0.0	0.926	9 0.0282	0.0341	0.0138	0.0039

Year	Scenario	Station	Flow Rate (L/s)	pH (m	ig	Acidity (mg aCO3/L)	Alkalinity (mg CaCO3/L)	AI (mg/L)	As (mg/L)	Ca (mg/L)	Cd (mg/L)	CI (mg/L)	Co (mg/L)	Cr (mg/L)		DOC mg/L) (F F		K (mg/L	Mg) (mg/L)	Mn (mg/L)	Mo (mg/L)	NO3-N (mg/L)	Na (mg/L)	NI (mg/L)	Pb (mg/L)	Sb (mg/L)	Se (mg/L)	SO4 (mg/L)	Sr (mg/L)					V Zn	
60 Ba	se Case (NP20)	SC01 Untreated	27.85		295	0.17	,	0.0363	0.2567 0.1316	69.4	0.00010	83.7	0.00877	0.00103	0.00113	0.86	1.44 5	.15 0.0001	3 97	8 29.6	0.16	0.1168	2.81	197.8	0.06273	0.00358	0.41433	0.02153	257	3.80	0.0002	0.8070			0148 0.004	5
61 Ba	se Case (NP20)	SC01 Untreated	27.16	6.31	295	0.17	153.7	0.0344	0.2535 0.1282			83.0	0.00838	0.00104	0.00114		1.38 5	.07 0.0001	4 92.		0.15	0.1082	2.61	191.5	0.06237	0.00357	0.38828	0.02030	243	3.65	0.0002	0.8431 (0.0318 0.	0335 0.	0139 0.004	2
62 Ba	se Case (NP20) se Case (NP20)	SC01 Untreated SC01 Untreated	20.09 31.75		304 266	0.18			0.2675 0.1320 0.2121 0.1107		0.00010			0.00107		1.06		.27 0.0001				0.1069	2.47				0.37801								0135 0.004 0122 0.003	
64 Ba	se Case (NP20)	SC01 Untreated	31.37	6.39	281	0.15	152.8	0.0306	0.2341 0.1180	66.5	0.00009	75.4	0.00767	0.00098	0.00102	0.94	1.42 4	.71 0.0001	5 92.	7 27.8	0.15	0.1078	2.30	185.4	0.05623	0.00319	0.39694	0.02091	233	3.74	0.0002	0.9094 (0.0286 0.	.0336 0.	0142 0.003	9
65 Ba	se Case (NP20)	SC01 Untreated	34.28		270	0.14			0.2196 0.1118		0.00010			0.00096				.44 0.0001				0.1023					0.36800								0132 0.003	
67 Ba	se Case (NP20) se Case (NP20)	SC01 Untreated SC01 Untreated	26.45 30.12		292 280	0.17			0.2504 0.1217 0.2330 0.1145		0.00010	75.6	0.00760	0.00104	0.00111		1.34 4	.94 0.0001 .63 0.0001	4 85. 5 83.	28.9	0.14	0.1003	2.19	175.5	0.05686	0.00351	0.36044	0.01890	235 225						0128 0.004 0126 0.003	
68 Ba	se Case (NP20)	SC01 Untreated	32.55		279	0.15			0.2323 0.1133		0.00010	75.2	0.00695	0.00099	0.00105		1.32 4	.63 0.0001	5 82.	6 27.5	0.13	0.0966	1.99	174.3	0.05652	0.00322	0.34963	0.01848	224						0125 0.003	
69 Ba	se Case (NP20) se Case (NP20)	SC01 Untreated SC01 Untreated	18.25 27.73		312 275	0.19			0.2838 0.1309		0.00010			0.00110				.46 0.0001				0.1047					0.37909								0134 0.004 0117 0.003	
71 Ba	se Case (NP20)	SC01 Untreated	37.84	6.45	261	0.13	150.9	0.0313	0.2070 0.1021	62.7	0.00010	66.3	0.00604	0.00094	0.00097	1.08	1.24	.13 0.0001	6 76.	2 25.3	0.12	0.0909	1.68	160.3	0.04960	0.00282	0.32563	0.01741	210	3.31	0.0002	1.0132	0.0253 0.	0290 0.	0116 0.003	5
72 Ba	se Case (NP20) se Case (NP20)	SC01 Untreated SC01 Untreated	23.41 28.01		296 276	0.17			0.2622 0.1209 0.2300 0.1090		0.00010		0.00734	0.00105	0.00111	1.00		.17 0.0001		5 29.6 7 27.1		0.1020 0.0891					0.36943			3.73	0.0002	0.8080	0.0328 0.	0320 0.	0131 0.004 0113 0.003	2
	se Case (NP20)	SC01 Untreated	23.52		286	0.16			0.2457 0.1137		0.00010		0.00670	0.00102		0.93		.82 0.0001		5 28.2		0.0930	1.71				0.33495								0118 0.004	
75 Ba	se Case (NP20)	SC01 Untreated	19.92		292	0.17			0.2538 0.1156		0.00010			0.00104				.96 0.00014				0.0918					0.33558								0119 0.004	
76 Ba	se Case (NP20) se Case (NP20)	SC01 Untreated SC01 Untreated	29.18 38.04		263 265	0.13			0.2100 0.1002 0.2141 0.1002		0.00010		0.00564	0.00096	0.00097	1.10		.06 0.0001				0.0789	1.35				0.28296								0101 0.003 0115 0.003	
78 Ba	se Case (NP20)	SC01 Untreated	37.91		270	0.15	152.1	0.0329	0.2193 0.1019	64.4	0.00010	69.8	0.00577	0.00096			1.19 4	.46 0.0001	5 73.	7 26.4	0.12	0.0860		159.2	0.05251	0.00303	0.31079	0.01654	210	3.33	0.0002	0.9636 (0.0268 0.	.0276 0.	0110 0.003	6
	se Case (NP20)	SC01 Untreated SC01 Untreated	28.46 30.64		289	0.18			0.2473 0.1116 0.2288 0.1045		0.00010			0.00103		0.92		.96 0.0001				0.0870	1.67				0.30900								0109 0.004	
	se Case (NP20)	SC01 Untreated	33.17		285	0.18	153.8	0.0355	0.2423 0.1079	67.2	0.00010					0.91	1.23 4	.96 0.00014	4 77.	1 28.3	0.13	0.0890	1.66	167.6	0.05814	0.00336	0.32275	0.01695	223	3.50	0.0002	0.8596	0.0297 0.	0284 0.	0113 0.003	9
	se Case (NP20) se Case (NP20)	SC01 Untreated SC01 Untreated	38.17 30.61		274	0.17			0.2258 0.1024 0.2461 0.1085		0.00010	72.0 78.6	0.00564	0.00098		0.91		.60 0.0001				0.0817					0.29059								0102 0.003 0107 0.003	
84 Ba	se Case (NP20)	SC01 Untreated	36.09	6.35	276	0.17	152.3	0.0332	0.2264 0.1017	65.8	0.00010	72.5	0.00554	0.00099	0.00108	1.00	1.08 4	.59 0.0001	5 66.	8 27.1	0.11	0.0766	1.45	154.0	0.05497	0.00319	0.27582	0.01474	201	3.16	0.0002	0.9558 (0.0281 0.	.0247 0.	0.003	7
	se Case (NP20) se Case (NP20)	SC01 Untreated SC01 Untreated	53.41 30.51		262 299	0.15 0.20			0.2089 0.0954 0.2639 0.1134		0.00010			0.00094				.29 0.0001				0.0776					0.27320								0096 0.003 0106 0.004	
87 Ba	se Case (NP20)	SC01 Untreated	38.08	6.32	274	0.17	152.0	0.0358	0.2253 0.1005	65.2	0.00010	71.7	0.00536	0.00098	0.00111	1.00	1.05 4	.62 0.0001	5 65.	0 27.0	0.11	0.0762	1.46	150.8	0.05438	0.00319	0.26697	0.01421	205	3.13	0.0002	0.9321 (0.0278 0.	0247 0.	0.003	7
88 Ba	se Case (NP20)	SC01 Untreated	33.74		278 288	0.18			0.2304 0.1015 0.2466 0.1069		0.00010			0.00099				.72 0.0001				0.0752					0.26840								0094 0.003 0095 0.003	
	se Case (NP20) se Case (NP20)	SC01 Untreated SC01 Untreated	29.28 35.37		265	0.19			0.2466 0.1069		0.00010			0.00103				.35 0.0001		7 28.6 8 25.9		0.0766	1.48				0.27145								0098 0.003	
91 Ba	se Case (NP20)	SC01 Untreated	25.70		292	0.20	153.9	0.0357	0.2540 0.1077	68.9	0.00010	80.6	0.00584	0.00103			1.11 5	.19 0.0001	4 69.	8 29.2	0.12	0.0787		162.3	0.06148	0.00356	0.28560	0.01499	214	3.39	0.0002	0.8253	0.0315 0.	0252 0.	0100 0.004	ᅵ
92 Ba	se Case (NP20) se Case (NP20)	SC01 Untreated SC01 Untreated	21.79 22.14		293 282	0.19 0.18			0.2562 0.1091 0.2405 0.1039		0.00010	81.9 77.0	0.00587	0.00104	0.00116		1.07 5	.15 0.0001	4 66. 5 62.	6 29.2 1 27.8	0.12	0.0766					0.27087								0094 0.004 0088 0.003	
94 Ba	se Case (NP20)	SC01 Untreated	37.44		261	0.15			0.2107 0.0919		0.00010	65.6	0.00479	0.00093	0.00099		1.02 4	.32 0.0001	6 62.	9 25.5	0.11	0.0728					0.26366								0093 0.003	
95 Ba	se Case (NP20) se Case (NP20)	SC01 Untreated SC01 Untreated	37.93 30.96		275 284	0.17			0.2304 0.0992 0.2453 0.1047		0.00010			0.00099	0.00106	0.99		.64 0.0001 .86 0.0001				0.0719	1.24				0.25693								0090 0.003 0088 0.003	
97 Ba	se Case (NP20)	SC01 Untreated	30.71	6.36	271	0.16	151.3	0.0325	0.2260 0.0978	64.9	0.00010	71.9	0.00508	0.00098	0.00104	1.02	0.96 4	.48 0.0001	6 59.	0 26.4	0.11	0.0688	1.14	145.4	0.05494	0.00313	0.24262	0.01305	193	3.08	0.0002	0.9654	0.0281 0.	0224 0.	0085 0.003	7
	se Case (NP20) se Case (NP20)	SC01 Untreated SC01 Untreated	23.89 25.25		291 286	0.19			0.2564 0.1067 0.2477 0.1043		0.00010			0.00103				.92 0.0001				0.0748					0.26906								0094 0.004 0087 0.003	
	se Case (NP20)	SC01 Untreated	43.29		253	0.14			0.1984 0.0888		0.00010			0.00093				.97 0.0001				0.0637					0.24644								0075 0.003	
101 Ba	se Case (NP20) se Case (NP20)	SC01 Untreated SC01 Untreated	26.91 26.89	6.26	295 282	0.20			0.2643 0.1077 0.2427 0.1020		0.00010			0.00104		0.83		.36 0.0001		9 29.6		0.0764	1.32				0.27762								0096 0.004 0085 0.003	
	se Case (NP20)	SC01 Untreated	26.95		291	0.19			0.2586 0.1059		0.00010			0.00101		0.85		.26 0.0001				0.0747	1.21				0.26489								0092 0.004	
104 Ba	se Case (NP20)	SC01 Untreated	28.60		282	0.18			0.2431 0.1018		0.00010			0.00101				.92 0.00014				0.0696					0.24061								0083 0.003	
	se Case (NP20) se Case (NP20)	SC01 Untreated SC01 Untreated	38.42 28.46		269 284	0.17			0.2218 0.0948 0.2456 0.1020		0.00010		0.00479	0.00097		0.92		.50 0.0001				0.0637	1.21				0.22109		199						0077 0.003 0083 0.003	
107 Ba	se Case (NP20)	SC01 Untreated	33.18		271	0.17			0.2262 0.0963	65.0	0.00010	71.5		0.00098				.54 0.0001				0.0627					0.21549								0075 0.003	
	se Case (NP20) se Case (NP20)	SC01 Untreated SC01 Untreated	27.45 28.80		285	0.18			0.2480 0.1021 0.2294 0.0974		0.00010			0.00101				.58 0.0001				0.0675					0.23776								0082 0.003 0073 0.003	
	se Case (NP20)	SC01 Untreated	20.54		295	0.20			0.2636 0.1079		0.00010	83.8	0.00561	0.00106	0.00116		0.94 5	.23 0.0001	4 57.	7 29.3	0.11	0.0663					0.22911								0079 0.004	
	se Case (NP20) se Case (NP20)	SC01 Untreated SC01 Untreated	28.24 26.43		271 281	0.16 0.18			0.2287 0.0956 0.2453 0.1005		0.00010	76.7		0.00097		0.99		.61 0.0001		4 26.5 9 27.8		0.0641	1.00				0.22074		189 196		0.0002	0.9256	0.0280 0.	0210 0.	0077 0.003 0080 0.003	8
113 Ba	se Case (NP20)	SC01 Untreated	38.84		266	0.16			0.2187 0.0921		0.00010			0.00095		1.03		.46 0.0001				0.0598					0.20810								0.003	
114 Ba	se Case (NP20) se Case (NP20)	SC01 Untreated SC01 Untreated	38.65 30.31		264 294	0.16			0.2169 0.0921 0.2614 0.1059		0.00010	82.1	0.00453	0.00095	0.00105			.44 0.0001	5 50. 3 56.	4 25.8 9 29.4	0.09	0.0601					0.20199								0070 0.003 0077 0.004	
116 Ba	se Case (NP20)	SC01 Untreated	30.81		289	0.20			0.2510 0.1034		0.00010	79.4	0.00525	0.00103	0.00117			.10 0.00014	4 52.	7 28.7	0.10	0.0604	1.18				0.20499								0071 0.003	
117 Ba	se Case (NP20) se Case (NP20)	SC01 Untreated SC01 Untreated	28.46 32.63		285	0.19			0.2450 0.1016 0.2264 0.0943		0.00010			0.00102 0.00096		0.93		.94 0.0001 .63 0.0001				0.0582					0.19704								0068 0.003 0069 0.003	
119 Ba	se Case (NP20)	SC01 Untreated	30.94	6.31	275	0.18	152.1	0.0341	0.2323 0.0967	65.6	0.00010	72.9	0.00482	0.00098	0.00109	0.98	0.81 4	.71 0.0001	5 49.	5 27.0	0.10	0.0578	1.04	135.6	0.05612	0.00324	0.19487	0.01054	182	2.96	0.0002	0.9282 (0.0287 0.	.0189 0.	0068 0.003	7
120 Ba	se Case (NP20) se Case (NP20)	SC01 Untreated SC01 Untreated	33.80 29.98		274 281	0.18			0.2314 0.0955 0.2417 0.1004		0.00010		0.00476	0.00097	0.00108	0.97		.73 0.0001 .85 0.0001	5 50. 5 48	4 26.9 5 27.7	0.10	0.0587					0.19955				0.0002	0.9213	0.0284 0. 0.0303 n	0192 0. 0186 n	0069 0.003 0065 0.003	8
122 Ba	se Case (NP20)	SC01 Untreated	30.16	6.31	277	0.18	152.4	0.0348	0.2364 0.0981	66.1	0.00010	74.3	0.00488	0.00099	0.00111	0.96	0.80 4	.78 0.0001	5 48.	4 27.3	0.10	0.0569	1.03	135.6	0.05730	0.00331	0.18869	0.01019	183	2.94	0.0002	0.9111 (0.0294 0.	.0186 0.	0065 0.003	8
	se Case (NP20)	SC01 Untreated SC01 Untreated	33.34 25.31		273 285	0.17			0.2298 0.0950 0.2481 0.1021		0.00010			0.00097		0.98		.67 0.0001 .94 0.0001				0.0561					0.18964 0.18564								0066 0.003 0064 0.003	
125 Ba	se Case (NP20) se Case (NP20)	SC01 Untreated	34.67	6.35	263	0.16	151.1	0.0326	0.2167 0.0904	63.1	0.00010	67.0	0.00440	0.00094	0.00103	1.03	0.77 4	.44 0.0001	6 46.	4 25.7	0.09	0.0549	0.94	127.5	0.05143	0.00298	0.18372	0.01008	172	2.92	0.0002	0.9736 (0.0263 0.	.0182 0.	0.003	5
126 Ba	se Case (NP20)	SC01 Untreated SC01 Untreated	39.39 36.37	6.33	266 280	0.17	151.1	0.0337	0.2213 0.0916 0.2414 0.0992	63.5	0.00010	68.2	0.00447	0.00094		1.01 0.94	0.78 4	.56 0.0001	5 47.	4 26.0	0.09	0.0563		129.1	0.05239	0.00304	0.18723	0.01019		2.98	0.0002	0.9479 (0.0268 0.	.0186 0.	0065 0.003 0063 0.003	5
127 Ba	se Case (NP20) se Case (NP20)	SC01 Untreated	26.95		289	0.19			0.2414 0.0992 0.2535 0.1029		0.00010			0.00099				.18 0.0001				0.0560					0.18423								0064 0.003	
	se Case (NP20) se Case (NP20)	SC01 Untreated SC01 Untreated	29.55 30.80		286 268	0.20	153.1	0.0362	0.2477 0.1014 0.2213 0.0927	67.7	0.00010	77.9 69.0	0.00507	0.00101		1.02	0.77 5	.05 0.0001	4 46.		0.09	0.0544	1.12		0.06027		0.17726	0.00952	184 172						0061 0.003 0058 0.003	
	se Case (NP20) se Case (NP20)	SC01 Untreated	34.11		265	0.18			0.2213 0.0927		0.00010			0.00098				.47 0.0001				0.0520					0.16599								0058 0.003	
132 Ba	se Case (NP20)	SC01 Untreated	34.92		269	0.18	151.2	0.0349	0.2268 0.0936	64.2	0.00010	70.2	0.00457	0.00095	0.00108		0.74 4	.66 0.0001	5 44.	9 26.4	0.09	0.0541	1.03	128.1	0.05407	0.00314	0.17408	0.00946	177	2.93	0.0002	0.9256	0.0277 0.	.0179 0.	0.003	6
	se Case (NP20) se Case (NP20)	SC01 Untreated SC01 Untreated	38.37 27.08		275 295	0.19			0.2354 0.0958 0.2669 0.1070		0.00010	72.7 83.5	0.00473	0.00096	0.00111			.86 0.0001		1 27.1 6 29.6	0.09	0.0544					0.17793 0.18287								0061 0.003 0062 0.004	
135 Ba	se Case (NP20)	SC01 Untreated	35.50	6.29	282	0.20	152.1	0.0353	0.2444 0.0998	67.1	0.00010	76.7	0.00497	0.00100	0.00115	0.93	0.73 4	.98 0.0001	5 44.	3 27.9	0.09	0.0517	1.12	132.9	0.05937	0.00345	0.16676	0.00902	179	2.90	0.0002	0.8849 (0.0304 0.	0169 0.	0057 0.003	8
	se Case (NP20) se Case (NP20)	SC01 Untreated SC01 Untreated	24.83 23.46		294 281	0.21			0.2607 0.1052 0.2435 0.1003		0.00010	82.2 77.0	0.00531	0.00103	0.00119	0.86		.27 0.0001 .84 0.0001				0.0519					0.16851								0058 0.004 0054 0.003	
138 Ba	se Case (NP20)	SC01 Untreated	30.29	6.36	259	0.16	150.2	0.0325	0.2127 0.0894	62.4	0.00010	66.0	0.00429	0.00093	0.00102	1.06	0.67 4	.30 0.0001	6 39.	6 25.1	0.08	0.0486	0.85	120.2	0.05090	0.00294	0.15236	0.00851	164	2.74	0.0002	0.9952	0.0261 0.	0162 0.	0053 0.003	5
139 Ba	se Case (NP20)	SC01 Untreated SC01 Untreated	32.95 44.59		264 254	0.16 0.15			0.2182 0.0911 0.2065 0.0860		0.00010			0.00095				.36 0.0001		4 25.5 4 24.6		0.0469	0.86 0.91				0.15084								0052 0.003 0055 0.003	
141 Ba	se Case (NP20) se Case (NP20)	SC01 Untreated	29.55	6.24	293	0.21	153.0	0.0369	0.2628 0.1055	69.2	0.00010	82.5	0.00532	0.00103	0.00119	0.86	0.74 5	.30 0.0001	4 44.	7 29.1	0.10	0.0525	1.17	137.9	0.06417	0.00369	0.16615	0.00884	187	3.00	0.0002	0.8182	0.0329 0.	.0171 0.	0.004	0
142 Ba	se Case (NP20)	SC01 Untreated SC01 Untreated	35.06 26.49		269 293	0.18			0.2244 0.0943 0.2665 0.1054		0.00010			0.00097 0.00102				.54 0.0001 .44 0.0001				0.0466					0.14181								0049 0.003 0059 0.004	
	se Case (NP20) se Case (NP20)	SC01 Untreated	33.13	6.29	272	0.18	151.3	0.0343	0.2311 0.0940	64.7	0.00010	71.2	0.00459	0.00095	0.00109	0.96	0.69 4	.78 0.0001	5 41.	4 26.7	0.09	0.0492	1.04	125.2	0.05501	0.00321	0.15591	0.00853	170	2.87	0.0002	0.9122 (0.0282 0.	0163 0.	0054 0.003	6
145 Ba	se Case (NP20)	SC01 Untreated	23.13	6.20	301	0.23	154.2	0.0386	0.2750 0.1096	70.9	0.00010	86.6	0.00557	0.00106	0.00124	0.80	0.73	.55 0.0001	3 44.	2 30.2	0.10	0.0518	1.18	140.6	0.06747	0.00389	0.16061	0.00845	191	2.95	0.0002	0.7638	0.0346 0.	0168 0.	0.004	2

147 Base Case (MP20) SOFI Unfrashed 33.91 6.32 271 0.18 150.7 0.337 0.2281 0.046 6.097 0.0010 7.13 0.00461 0.0097 0.0010 7.14 0.00461 0.0097 0.0010 7.14 0.00461 0.0097 0.0010 7.14 0.00461 0.0097 0.0010 7.14 0.00461 0.0097 0.0010 7.14 0.00461 0.0097 0.0010 7.14 0.00461 0.0097 0.0010 7.14 0.00461 0.0097 0.0010 7.14 0.00461 0.0097 0.0010 7.14 0.00461 0.0097 0.0010 7.14 0.00461 0.0097 0.0010 7.14 0.00461 0.0098 0.0047 0.0010 7.14 0.00461 0.0098 0.0047 0.0010 7.14 0.00461 0.0098 0.0047 0.0010 7.14 0.00461 0.0098 0.0047 0.0010 7.14 0.00461 0.0098 0.0047 0.0010 7.14 0.00461 0.00461 0.0098 0.0047 0.0010 7.14 0.00461 0.0098 0.0047 0.0010 7.14 0.00461 0.0098 0.0047 0.0010 7.14 0.00461 0.0098 0.0047 0.0010 7.14 0.00461 0.0098 0.0047 0.00461 0.	(mg/L) (m
147 Base Case (PPZD) SCOT Unfresheld S.5.15 S.32 271 O.18 150.7 0.037 0.2281 0.0386 0.0487 0.0380 0.0282 0.0396 0.0386 0.0382 0.1382 0.0	9.9547 0.0283 0.0151 0.0048 0.0037 0.8692 0.0297 0.0164 0.0053 0.0038 0.038 0.038 0.038 0.038 0.038 0.038 0.038 0.038 0.038 0.038 0.038 0.038 0.038 0.058 0.057 0.0049 0.0038 0.9215 0.0285 0.0154 0.0047 0.0037 0.9015 0.0289 0.0156 0.0048 0.0037 0.916 0.0287 0.0158 0.0046 0.0037 0.916 0.0289 0.0152 0.0047 0.0037 0.916 0.0284 0.0152 0.0048 0.0038 0.916 0.028 0.038 0.928 0.028 0.0151 0.0048 0.0038 0.928 0.0285 0.0151 0.0046 0.0037 0.828 0.0285 0.0151 0.0046 0.0037 0.828 0.0285 0.0151 0.0046 0.0037 0.828 0.0285 0.0154 0.0047 0.0059 0.9285 0.0283 0.0144 0.0044 0.0056 0.0233 0.0383 0.0347 0.0044 0.0056 0.0033 0.9263 0.0283 0.0159 0.0047 0.0036 0.0035 0.0035 0.0035 0.0037 0.0036 0.0035 0.0035 0.0037 0.0037 0.0036 0.0035 0.0037 0.0037 0.0036 0.0035 0.0037 0.0037 0.0036 0.0035 0.0047 0.0036 0.0035 0.0035 0.0035 0.0047 0.0036 0.0035 0.0035 0.0047 0.0036 0.0035 0.0047 0.0036 0.0035 0.0047 0.0036 0.0035 0.0047 0.0036 0.0035 0.0047 0.0036 0.0035 0.0047 0.0036 0.0035 0.0047 0.0036 0.0045 0.0047 0.0036 0.0045 0.0047 0.0036 0.0045 0.0047 0.0036 0.0045 0.0047 0.0036 0.0045 0.0047 0.0036 0.0045 0.0047 0.0036 0.0045 0.0047 0.0036 0.0045 0.0047 0.0036 0.0045 0.0047 0.0036 0.0045 0
Fig. Base Case (MP20) SC01 Unfrested S.54 6.31 264 0.18 150.2 0.0353 0.2056 0.0952 0.09	0.9542 0.0271 0.0185 0.0047 0.0035 0.8813 0.0285 0.0157 0.0099 0.0033 0.9215 0.0285 0.0154 0.0047 0.0037 0.9015 0.0289 0.0156 0.0048 0.0037 0.9190 0.0297 0.0151 0.0046 0.0037 0.9181 0.0284 0.0152 0.0047 0.0037 0.8834 0.0298 0.0153 0.0048 0.0033 0.9281 0.0295 0.0151 0.0046 0.0037 0.8282 0.0295 0.0151 0.0046 0.0037 0.8283 0.0295 0.0151 0.0047 0.0037 0.8283 0.0336 0.0155 0.0049 0.0039 0.9285 0.0153 0.0049 0.0039 0.9285 0.0330 0.0155 0.0049 0.0037 0.9285 0.0330 0.0155 0.0049 0.0037 0.9285 0.0330 0.0155 0.0047 0.003
Signate Case (NP20) SCOT Unfrested 33.01 6.26 278 0.20 151.5 0.0382 6.24 0.09101 75.0 0.0483 0.00996 0.00111 0.98 0.65 4.94 0.00014 37.5 2.65 0.09 0.0461 1.05 1.22 0.05857 0.00329 0.15875 0.00783 174 2.70 0.00025 1.05 1.05 0.00025 0.000	0.8613 0.0298 0.0157 0.0049 0.0038 0.9215 0.0258 0.0154 0.0047 0.0037 0.9015 0.0289 0.0156 0.0048 0.0037 0.9015 0.0289 0.0156 0.0048 0.0037 0.9100 0.0267 0.0155 0.0046 0.0037 0.9100 0.0254 0.0152 0.0047 0.0037 0.8524 0.0258 0.0152 0.0047 0.0037 0.8628 0.0258 0.0154 0.0047 0.0037 0.8628 0.0258 0.0154 0.0047 0.0037 0.8628 0.0258 0.0154 0.0047 0.0037 0.8628 0.0258 0.0154 0.0049 0.0039 0.9250 0.0253 0.0159 0.0049 0.0036 0.9253 0.0253 0.0159 0.0049 0.0036 0.9253 0.0253 0.0155 0.0047 0.0036
15	9.915 0.0289 0.0156 0.0048 0.0037
155 Base Case (NP20) SC01 Unfreshed 34.19 6.29 273 0.19 150.8 0.0357 0.2311 0.0978 6.51 0.00010 7.15 0.00461 0.00996 0.00110 0.99 0.65 4.73 0.00015 35.9 2.85 0.008 0.0459 1.03 1.15 0.005066 0.00320 0.13347 0.00737 169 2.55 0.0002 155 0.00666 0.00000 0.00100 0.0010 0.	0.9190 0.0287 0.0151 0.0046 0.0037 0.9181 0.0284 0.0152 0.0047 0.0037 0.8834 0.0288 0.0153 0.0048 0.0038 0.9218 0.0285 0.0153 0.0048 0.0038 0.9218 0.0285 0.0151 0.0046 0.0037 0.8628 0.0255 0.0154 0.0047 0.0037 0.8232 0.0318 0.0155 0.0049 0.0039 0.9263 0.0283 0.0155 0.0049 0.0036 0.9630 0.0283 0.0155 0.0047 0.0039 0.0056 0.0058 0.0058 0.0047 0.0039 0.0058 0.0049 0.0058 0
156 Base Case (NP20)	0.9181 0.0284 0.0152 0.0047 0.0037 0.8834 0.0288 0.0155 0.0048 0.0038 0.9218 0.0285 0.0151 0.0046 0.0037 0.8828 0.0295 0.0154 0.0047 0.0037 0.8232 0.0318 0.0155 0.0049 0.0039 0.9263 0.0283 0.0149 0.0044 0.0036 0.8063 0.0320 0.0155 0.0047 0.0037
156 Base Case (NP20) SC01 Unifreated 36.4 6.32 270 0.19 151.0 0.084 0.2915 0.0947 6.45 0.00010 7.16 0.00482 0.00099 0.0010 0.091 0.094 0.044 4.92 0.00014 38.7 27.5 0.08 0.0484 1.07 121.2 0.05853 0.00320 0.13431 0.0773 172 2.55 0.00021 157 0.00852 0.0094 0.0085	0.9218 0.0285 0.0151 0.0046 0.0037 0.8828 0.0295 0.0154 0.0047 0.0037 0.8232 0.0318 0.0155 0.0049 0.0036 0.9263 0.0283 0.0149 0.0044 0.0036 0.8063 0.0320 0.0155 0.0047 0.0399
158 Base Case (NP20) SC01 Unifrented 32.0 6.28 2.55 0.19 150.7 0.356 0.2398 0.9971 6.256 0.00010 75.6 0.00010 75	0.8828 0.0295 0.0154 0.0047 0.037 0.8232 0.0318 0.0155 0.0049 0.0039 0.9263 0.0283 0.0149 0.0044 0.0036 0.8063 0.0320 0.0155 0.0047 0.0039
158 Base Case (NP20) SC01 Unfreated 30.99 6.24 286 0.20 151.6 0.0364 0.2586 0.1022 67 1 0.00010 7.10 0.0016 0.0016 0.0019 0.00 0.0016 0.0019 0.0016 0.0019 0.0016 0.0019 0.0016 0.0019 0.0016 0.0019 0.0016 0.0019 0.0016 0.0019 0.0018 0.0019 0.0018 0.0019 0.0018 0.0019 0.0018 0.0019 0.0018 0.0019 0.0018 0.0019 0.0018 0.0018 0.0019 0.0018 0.0018 0.0019 0.0018 0	0.9263 0.0283 0.0149 0.0044 0.0036 0.8063 0.0320 0.0155 0.0047 0.0039
16 Base Case (NP20)	0.8063 0.0320 0.0155 0.0047 0.0039
Fig. Base Case (NP20) SCD1 Unfreated 27.32 6.23 288 0.21 15.19 0.0360 0.2594 0.1024 6.22 0.00010 7.95 0.00511 0.00116 0.08116 0.00121 0.038 0.0254 0.00105 0.00121 0.038 0.0254 0.00105	
163 Base Case (NP20) SC01 Unirelated 31.82 6.37 259 0.16 149.4 0.0326 0.2132 0.0987 62.5 0.0001 6.52 0.00427 0.00093 0.01013 1.05 0.55 4.30 0.0016 3.1, 0.0015 3.0 0.042 0.0016 0.042 0.0016 0.	0.8425 0.0318 0.0144 0.0045 0.0040
166 Base Case (NP20) SC01 Unirealed 31.42 6.31 272 0.18 150.4 0.0319 0.2352 0.0940 6.48 0.00010 7.7 0.00462 0.00095 0.00106 0.94 0.61 4.81 0.00015 36.0 26.7 0.08 0.0426 0.93 120.6 0.05594 0.00321 0.13156 0.00731 159 2.31 0.0002 155 0.00016 0.0000000000000000000000000000000000	0.7877 0.0340 0.0147 0.0044 0.0041 0.9997 0.0263 0.0136 0.0039 0.0035
Fig. Base Case (NP20) SC01 Unireated 26.45 6.25 244 0.20 151.3 0.034 0.2515 0.1018 0.75 0.00010 72.7 0.0005 0.00101 0.00115 0.91 0.50 0.50 0.00014 35.1 28.0 0.08 0.0426 1.05 125.7 0.06154 0.0036 0.1242 0.00672 170 2.39 0.0002 168 Base Case (NP20) SC01 Unireated 32.55 6.31 272 0.18 150.3 0.0335 0.2340 0.0956 55.1 0.0010 72.7 0.0045 0.00097 0.00109 0.97 0.57 4.73 0.00015 33.4 26.6 0.08 0.0412 0.95 118.6 0.0336 0.12482 0.00672 170 2.39 0.0002 168 Base Case (NP20) SC01 Unireated 32.55 6.31 272 0.18 150.3 0.0335 0.2332 0.0952 65.0 0.0010 72.3 0.0456 0.0097 0.0109 0.97 0.57 4.73 0.00015 33.4 26.6 0.08 0.0410 0.96 118.6 0.05527 0.0325 0.1180 0.00653 160 2.32 0.0002 170 Base Case (NP20) SC01 Unireated 37.54 6.39 2.53 0.15 148.7 0.0321 0.0277 0.0970 6.33 0.00457 0.0009 0.0010 7.9 0.0010 7.9 0.0010 7.9 0.00107 0.0112 0.00107 0.0112 0.00107 0.0112 0.00107 0.0112 0.00107 0.0112 0.00107 0.0	0.9088 0.0287 0.0141 0.0045 0.0036
167 Base Case (NP20) SC01 Unitreated 30.13 6.30 272 0.18 150.3 0.0334 0.2340 0.0956 65.1 0.00010 72.7 0.0465 0.0097 0.00108 0.97 0.58 4.72 0.00015 33.5 26.6 0.08 0.0412 0.95 119.2 0.05661 0.0036 0.11852 0.06667 160 2.33 0.0002 168 Base Case (NP20) SC01 Unitreated 32.55 6.31 272 0.18 150.3 0.0335 0.2335 0.952 0.952 65.0 0.00010 72.3 0.0045 0.00097 0.00109 0.97 0.57 4.73 0.00015 33.4 26.6 0.08 0.0410 0.96 118.6 0.05627 0.00325 0.11803 0.00663 160 2.33 0.0002 169 Base Case (NP20) SC01 Unitreated 22.73 6.33 268 0.17 150.1 0.0324 0.2277 0.0939 64.3 0.0010 70.9 0.0045 0.0010 70.9 0.0045 0.0010 1.0 0.0553 0.0001 0.0010 0.001	0.9523 0.0268 0.0142 0.0042 0.0035 0.8686 0.0315 0.0140 0.0042 0.0039
169 Base Case (NP20) SC01 Unifreated 18.25 6.19 304 0.23 153.7 0.0378 0.2849 0.1122 71.7 0.00010 89.6 0.0574 0.00107 0.00123 0.77 0.64 5.66 0.00013 37.8 30.5 0.09 0.0452 1.10 136.8 0.07024 0.00400 0.12994 0.00685 185 2.49 0.0002 170 Base Case (NP20) SC01 Unifreated 27.73 6.33 268 0.17 150.1 0.0324 0.2777 0.0879 6.12 0.00015 7.0 0.00095 0.00105 1.01 0.55 4.54 0.00016 31.6 2.60 0.07 0.0396 0.84 116.4 0.05523 0.0316 0.11188 0.00538 155 2.22 0.0002 171 Base Case (NP20) SC01 Unifreated 37.84 6.39 253 0.15 148.7 0.0321 0.00015	0.9283 0.0290 0.0137 0.0041 0.0037
170 Base Case (NP20) SC01 Untreated 27.73 6.33 288 0.17 150.1 0.0324 0.2277 0.0399 6.43 0.00010 70.9 0.00457 0.00096 0.00105 1.01 0.55 4.54 0.00016 31.6 26.0 0.07 0.0396 0.84 116.4 0.05523 0.0316 0.11188 0.06538 156 2.22 0.0002 172 Base Case (NP20) SC01 Untreated 37.84 6.39 253 0.15 148.7 0.0321 0.2077 0.0870 6.12 0.00010 63.6 0.00111 0.00091 0.0099 0.08 0.54 4.20 0.0016 31.6 26.0 0.07 0.0398 0.84 116.4 0.05523 0.0316 0.11188 0.06538 156 2.22 0.0002 0.00010 0.00	0.9272 0.0288 0.0136 0.0041 0.0037
171 Base Case (NP20) SC01 Unifresided 37.84 6.39 253 0.15 148.7 0.0321 0.2077 0.0870 61.2 0.00010 63.6 0.00411 0.00091 0.00099 1.08 0.54 4.20 0.00016 30.3 24.4 0.07 0.0388 0.81 108.9 0.04939 0.00284 0.10967 0.00636 151 2.18 0.00021 172 0.00016 172 0.00016 0.0001	0.7371 0.0360 0.0146 0.0044 0.0043 0.9574 0.0283 0.0132 0.0039 0.0036
1/2 pase cuse (n=2u) Scutt critical see 1.24 285 0.24 285 0.20 152.0 0.0563 0.1258 0.0057 177 2.42 0.0002 0.0015 0.85 0.61 5.25 0.00013 35.8 28.6 0.09 0.0447 1.02 128.4 0.06393 0.00363 0.1258 0.00677 177 2.42 0.0002	1.0129 0.0253 0.0135 0.0038 0.0034
173 Base Case (NP20) SC01 Untreated 28.01 6.32 269 0.17 150.2 0.0338 0.2308 0.0953 6.46 0.00010 7.2 0 0.0044 0.00097 0.00107 1.00 0.55 4.60 0.00015 31.2 26.2 0.08 0.041 0.089 116.8 0.05513 0.0032 0.00509 160 2.18 0.0002	0.8077 0.0328 0.0146 0.0043 0.0040 0.9462 0.0288 0.0133 0.0037 0.0037
174 Base Case (NPZU) Scut officialed 25.32 0.20 276 0.19 151.3 0.0040 0.2405 0.0999 0.0010 70.0 0.0049 0.00049 0.0010 0.55 0.57 4.90 0.00014 32.5 27.3 0.00 0.0417 0.92 122.1 0.00004 0.0042 0.11479 0.00050 107 2.20 0.0002	0.8816 0.0308 0.0137 0.0039 0.0038
	0.8626 0.0319 0.0133 0.0039 0.0039 1.0437 0.0263 0.0121 0.0034 0.0035
177 Base Case (NP20) SC01 Untreated 38.04 6.37 258 0.16 149.6 0.0318 0.2148 0.0880 62.0 0.00010 65.1 0.00420 0.00001 1.04 0.54 4.40 0.00016 30.6 25.0 0.07 0.0392 0.82 110.0 0.05057 0.00292 0.10981 0.00633 150 2.18 0.0002	0.9776 0.0259 0.0132 0.0038 0.0034
	0.9634 0.0268 0.0131 0.0037 0.0035 0.8653 0.0309 0.0136 0.0036 0.0039
180 Base Case (NP20) SC01 Unifresited 30.64 6.29 270 0.19 150.8 0.0353 0.2294 0.0948 64.7 0.00010 71.1 0.00457 0.00096 0.00111 0.99 0.53 4.69 0.00015 30.2 26.5 0.07 0.0388 0.96 114.4 0.05534 0.00323 0.10221 0.00581 159 2.08 0.0002	0.9331 0.0283 0.0130 0.0035 0.0037
181 Base Case (NP20) SC01 Untreated 33.17 6.26 277 0.20 151.5 0.0363 0.2430 0.0975 65.8 0.00010 74.4 0.00478 0.00097 0.00114 0.91 0.56 5.03 0.00014 32.5 27.4 0.08 0.0410 1.06 118.7 0.05800 0.00338 0.11121 0.00613 166 2.20 0.0002	0.8594 0.0297 0.0136 0.0038 0.0038 0.9347 0.0278 0.0131 0.0034 0.0036
183 Base Case (NP20) SC01 Untreated 30.61 6.25 281 0.20 151.5 0.0363 0.2468 0.0995 66.7 0.00010 76.3 0.00490 0.00099 0.00116 0.91 0.54 5.06 0.00014 31.7 27.8 0.08 0.0397 1.10 119.7 0.05954 0.00347 0.10640 0.00589 165 2.14 0.0002	0.8636 0.0305 0.0131 0.0034 0.0038 0.8636 0.0305 0.0131 0.0036 0.0038
184 Base Case (NP20) SC01 Untreated 36.09 6.31 270 0.19 150.3 0.0339 0.2270 0.0939 64.6 0.00010 70.5 0.00453 0.00096 0.00111 1.00 0.51 4.65 0.00015 29.0 26.3 0.07 0.0363 1.00 112.8 0.05486 0.00321 0.09643 0.00558 153 2.00 0.00021	0.9556 0.0281 0.0122 0.0033 0.0037
	0.9894 0.0254 0.0128 0.0033 0.0034 0.7929 0.0330 0.0135 0.0036 0.0040
187 Base Case (NP20) SC01 Untreated 38.08 6.29 268 0.19 15.01 0.0355 0.2258 0.0938 6.40 0.00010 69.8 0.00449 0.00095 0.00113 1.00 0.50 4.67 0.00015 28.6 26.2 0.07 0.0378 1.07 111.4 0.05429 0.00320 0.09431 0.00539 158 1.95 0.00021 0.0000000000000000000000000000000000	0.9319 0.0278 0.0127 0.0032 0.0036
	0.9228 0.0285 0.0123 0.0032 0.0037 0.8622 0.0308 0.0127 0.0033 0.0039
190 Base Case (NP20) SC01 Unitreated 35.37 6.32 260 0.17 149.1 0.0338 0.2128 0.0893 62.5 0.00010 65.6 0.00423 0.00093 0.00107 1.05 0.48 4.40 0.00016 27.1 25.2 0.07 0.0355 0.95 106.9 0.05094 0.00300 0.09019 0.00532 148 1.90 0.0002	0.9899 0.0261 0.0121 0.0031 0.0035
	0.8251 0.0315 0.0127 0.0035 0.0039 0.8245 0.0321 0.0129 0.0034 0.0040
193 Base Case (NP20) SC01 Untreated 22.14 6.28 276 0.19 151.0 0.0352 0.2410 0.0988 66.0 0.00010 75.3 0.00484 0.00099 0.00112 0.95 0.51 4.82 0.00015 28.9 27.1 0.07 0.0374 0.92 116.9 0.05887 0.00339 0.09514 0.00539 160 1.97 0.0002	0.8965 0.0302 0.0124 0.0032 0.0038
	0.9865 0.0254 0.0123 0.0034 0.0034 0.9353 0.0285 0.0124 0.0033 0.0037
196 Base Case (NP20) SC01 Unitreated 30.96 6.29 279 0.19 150.6 0.0355 0.2457 0.1002 66.5 0.00010 76.8 0.00494 0.00100 0.00113 0.94 0.52 4.90 0.00015 29.6 27.3 0.08 0.0382 0.99 118.7 0.05011 0.00345 0.09784 0.00549 163 2.01 0.0002	0.8900 0.0308 0.0126 0.0033 0.0039
197 Base Case (NP20) SC01 Unitreated 30.71 6.33 266 0.17 149.3 0.0330 0.264 0.0936 6.39 0.00010 70.2 0.0045 0.00010 70.2 0.0045 0.00010 70.2 0.0045 0.0010 70.2 0.0045 0.0010 70.2 0.0010	0.9653 0.0281 0.0122 0.0032 0.0036 0.8371 0.0319 0.0129 0.0036 0.0039
199 Base Case (NP20) SC01 Unifresited 25.25 6.27 281 0.19 151.2 0.0340 0.2481 0.1003 67.0 0.00010 77.3 0.00497 0.00100 0.00112 0.92 0.52 4.96 0.00015 29.9 27.6 0.08 0.0371 0.95 119.5 0.06054 0.00347 0.09002 0.00558 160 2.03 0.0002	0.8849 0.0310 0.0122 0.0034 0.0039
	0.8786 0.0099 0.0116 0.0014 0.0007 0.8193 0.0105 0.0121 0.0016 0.0006
2 Base Case (NP2D) SC01 Treated 20.98 7.06 444 0.00 131.5 0.0109 0.0063 0.2951 126.5 0.00010 182.0 0.00057 0.00035 1.08 1.56 0.07 0.00015 85.8 31.1 0.03 0.0099 0.16 304.4 0.0030 0.00027 0.00996 0.00179 246 0.44 0.0001	1.0156 0.0075 0.0131 0.0017 0.0008
	1.0101 0.0063 0.0153 0.0021 0.0008 1.0483 0.0048 0.0157 0.0021 0.0008
5 Base Case (NP20) SC01 Treated 31.35 7.31 32 0.00 143.5 0.105 0.0042 0.2740 89.2 0.00009 102.7 0.00051 0.00037 0.00036 1.19 1.71 0.05 0.00017 110.5 23.8 0.03 0.0102 0.20 265.9 0.0186 0.00023 0.01210 0.00207 207 0.47 0.00021 0.00207 0.002	1.1305 0.0039 0.0157 0.0022 0.0009
	1.0584 0.0042 0.0182 0.0026 0.0008 1.1300 0.0037 0.0184 0.0026 0.0009
8 Base Case (NP20) SC01 Treated 21.11 7.28 339 0.00 147.0 0.0992 0.0042 0.3707 93.0 0.00009 111.9 0.00079 0.00035 0.00033 1.10 2.00 0.05 0.00016 163.4 25.8 0.04 0.0110 0.24 345.8 0.00133 0.00022 0.01641 0.00220 259 0.46 0.0002	1.0491 0.0041 0.0213 0.0031 0.0008
	1.1297 0.0038 0.0205 0.0030 0.0009
	1.0044 0.0044 0.0234 0.0035 0.0008 1.1003 0.0036 0.0235 0.0034 0.0008
12 Base Case (NP20) SC01 Treated 20.66 7.29 336 0.00 149.6 0.0099 0.0042 0.4210 91.6 0.00009 112.5 0.00089 0.00034 0.00033 1.10 2.08 0.06 0.00016 198.5 26.1 0.04 0.0129 0.27 392.2 0.00189 0.00021 0.01977 0.00234 291 0.47 0.00021 0.0	1.0408 0.0039 0.0254 0.0038 0.0008
	1.1412 0.0035 0.0238 0.0035 0.0009 1.1478 0.0034 0.0241 0.0035 0.0009
15 Base Case (NP20) SC01 Treated 23.24 7.26 358 0.00 150.3 0.0091 0.0045 0.4482 97.6 0.00009 126.0 0.00033 0.00033 0.00032 1.04 2.24 0.06 0.00015 219.5 27.7 0.05 0.0128 0.27 428.6 0.00210 0.00214 0.02149 0.00236 316 0.45 0.0002	0.9857 0.0045 0.0271 0.0041 0.0008
	1.0282 0.0044 0.0252 0.0039 0.0008 1.0527 0.0042 0.0242 0.0037 0.0008
18 Base Case (NP20) SC01 Treated 25.98 7.33 321 0.00 148.8 0.0098 0.0040 0.3666 87.4 0.00009 103.4 0.000009 103.4 0.000007 0.00037 0.00035 1.17 1.95 0.05 0.0017 190.1 24.8 0.04 0.0120 0.25 365.5 0.00176 0.00022 0.01917 0.00242 273 0.48 0.00002	1.1142 0.0036 0.0238 0.0036 0.0009
	1.1093 0.0038 0.0233 0.0035 0.0009 1.1048 0.0037 0.0235 0.0036 0.0008
21 Base Case (NP20) SC01 Treated 23.97 7.30 340 0.00 147.6 0.0097 0.0043 0.3488 93.4 0.00009 113.8 0.00074 0.00035 0.00034 1.12 1.95 0.06 0.00017 185.0 26.1 0.04 0.0118 0.23 363.8 0.00196 0.00022 0.01894 0.00234 277 0.47 0.0002	1.0690 0.0041 0.0228 0.0035 0.0008
	1.0857 0.0039 0.0224 0.0034 0.0008 1.0982 0.0037 0.0221 0.0034 0.0008
24 Base Case (NP20) SC01 Treated 20.15 7.29 347 0.00 147.0 0.0088 0.0043 0.3250 95.2 0.0009 115.1 0.00069 0.00035 0.00033 1.10 1.95 0.06 0.00016 180.7 26.5 0.04 0.0107 0.21 355.2 0.00198 0.00022 0.01845 0.00230 272 0.46 0.0002	1.0497 0.0042 0.0217 0.0034 0.0008
25 Base Case (NP20) SC01 Treated 28.29 7.35 311 0.00 146.7 0.0107 0.0039 0.2885 84.9 0.00009 93.9 0.00055 0.00037 0.00036 1.20 1.82 0.05 0.00017 170.0 24.0 0.04 0.0118 0.21 321.2 0.00164 0.00022 0.01787 0.00238 252 0.49 0.0002	1.1406 0.0034 0.0211 0.0032 0.0009
	1.1231 0.0034 0.0212 0.0032 0.0009 0.9865 0.0037 0.0201 0.0030 0.0008
28 Base Case (NP20) 9C01 Treated 23.50 6.65 346 0.07 150.9 0.0102 0.0038 0.2555 93.3 0.00009 97.8 0.00033 0.00035 0.96 1.68 0.06 0.0015 153.0 27.4 0.03 0.0089 0.17 294.6 0.00167 0.00020 0.01532 0.00195 240 0.40 0.00021	0.9226 0.0036 0.0179 0.0028 0.0007
29 Base Case (NP20) SC01 Treated 27.05 6.61 340 0.08 151.8 0.0110 0.0037 0.2341 91.6 0.00009 91.9 0.00049 0.00030 0.00030 0.00030 0.00030 0.00030 0.00010 141.1 27.1 0.03 0.0089 0.16 273.0 0.00157 0.00020 0.01435 0.00189 227 0.40 0.0002 0.00030 0.	. D 91301 D DD331 D D4671 D DD961 D DD071
31 Base Case (NP20) SC01 Treated 32.40 6.59 313 0.09 151.6 0.0136 0.0036 0.1994 84.1 0.00009 76.9 0.00045 0.00032 0.00039 1.04 1.42 0.06 0.0016 125.5 25.1 0.03 0.0107 0.16 238.9 0.0135 0.00020 0.01366 0.00190 209 0.42 0.0002	0.9120 0.0033 0.0167 0.0025 0.0007 0.9845 0.0028 0.0159 0.0023 0.0007

Year	Scenario	Station	Flow Rate (L/s)	рН	Hardness (mg CaCO3/L)	Acidity (mg CaCO3/L)	Alkalinity (mg CaCO3/L)	Al (mg/L)	As (mg/L)	B (mg/L)	Ca (mg/L)	Cd (mg/L)	CI (mg/L)	Co (mg/L)	Cr (mg/L)	Cu (mg/L)	DOC (mg/L)	F (mg/L) (Fe mg/L)	Hg (mg/L) (K (mg/L)		Mn M		Na (mg/L)	NI (mg/L)	Pb (mg/L)	Sb (mg/L) (SO4 Sr (mg/L) (mg/	T1 (mg/L)	TOC (mg/L)	CN (mg/L)	U (mg/L) (V Zn
32	Base Case (NP20)	SC01 Treated	33.41	6.55		0.10				0.2011		0.00009			0.00031	0.00038		1.47			130.4		0.03 0.0			0.00136		0.01386 0			40 0.0002				0.0024 0.000
33	Base Case (NP20)	SC01 Treated		6.50	328	0.11				0.2009		0.00009			0.00031						132.6		0.03 0.0					0.01365 0		215 0.					0.0024 0.000
34	Base Case (NP20)	SC01 Treated		6.41					0.0038			0.00009			0.00026					0.00013			0.03 0.0					0.01403 0							0.0024 0.000
	Base Case (NP20)	SC01 Treated SC01 Treated	34.37 24.08	6.49			153.2 154.3		0.0034	0.1893		0.00010			0.00029	0.00037		1.44		0.00015	123.8		0.03 0.0					0.01251 0		205 0. 207 0.			0.0030		0.0022 0.000 0.0022 0.000
37	Base Case (NP20) Base Case (NP20)	SC01 Treated		6.47		0.13			0.0034			0.00010			0.00027						114.1		0.03 0.0	077 0.1	225.7	0.00131		0.01221 0		197 0.					0.0022 0.000
38	Base Case (NP20)	SC01 Treated	29.29	6.54	307	0.10				0.1629		0.00010			0.00033			1.35			111.1		0.02 0.0					0.01231 0							0.0020 0.000
39	Base Case (NP20)	SC01 Treated SC01 Treated		6.55					0.0033			0.00010			0.00032					0.00016			0.02 0.0					0.01163 0							0.0020 0.000 0.0021 0.000
41	Base Case (NP20) Base Case (NP20)	SC01 Treated		6.40					0.0036			0.00009			0.00033			1.49		0.00014			0.02 0.0					0.01278 0							0.0021 0.000
42	Base Case (NP20)	SC01 Treated	34.23	6.48	319	0.12			0.0034			0.00010			0.00032				0.06	0.00016	102.5	25.4	0.02 0.0	085 0.1	203.6	0.00134	0.00020	0.01119 0	0.00178						0.000
43	Base Case (NP20)	SC01 Treated SC01 Treated		6.37					0.0037			0.00009			0.00025					0.00013			0.03 0.0					0.01289 0							0.0022 0.000 0.0020 0.000
45	Base Case (NP20) Base Case (NP20)	SC01 Treated		6.34					0.0034			0.00009			0.00030					0.00013			0.02 0.0					0.01176 0							0.0020 0.000
	Base Case (NP20)	SC01 Treated		6.47					0.0035			0.00010			0.00032		1.04				103.4		0.02 0.0					0.01179 0							0.0019 0.000
	Base Case (NP20)	SC01 Treated		6.45		0.13			0.0034			0.00010			0.00031		1.00				100.5		0.02 0.0	077 0.1	199.4	0.00135	0.00020	0.01078 0	0.00176	180 0.	40 0.0002	0.9552	0.0028	0.0120	0.0018 0.000
	Base Case (NP20) Base Case (NP20)	SC01 Treated SC01 Treated	35.37	6.40					0.0036	0.1483		0.00009			0.00029		0.93 1.02			0.00014	98.4		0.02 0.0					0.01189 0							0.0019 0.000 0.0018 0.000
50		SC01 Treated		6.37					0.0036		89.1	0.00010			0.00029					0.00014			0.02 0.0					0.01113 0							0.0018 0.000
	Base Case (NP20)	SC01 Treated		6.43					0.0036			0.00010			0.00030					0.00015	98.0		0.02 0.0					0.01095							0.0017 0.000
	Base Case (NP20) Base Case (NP20)	SC01 Treated SC01 Treated		6.40				0.0135	0.0036	0.1349		0.00010			0.00030		0.96	1.36		0.00015	98.7		0.02 0.0					0.01103 0			38 0.0002				0.0017 0.000 0.0017 0.000
54	Base Case (NP20)	SC01 Treated	33.65	6.40	322	0.14	152.4			0.1303	86.7	0.00010	75.4	0.00029	0.00030	0.00039	0.98	1.36	0.06	0.00015	96.8	25.7	0.02 0.0	086 0.1	192.2			0.01033 0		180 0.	39 0.0002	0.9186	0.0028	0.0118	0.0017 0.000
	Base Case (NP20)	SC01 Treated		6.37					0.0036			0.00010			0.00029					0.00014	98.6		0.02 0.0					0.01072 0							0.0017 0.000
	Base Case (NP20) Base Case (NP20)	SC01 Treated SC01 Treated		6.41		0.14 0.15		0.0131	0.0035			0.00010			0.00030	0.00039				0.00015	95.1 97.5	25.7	0.02 0.0	084 0.1 086 0.1				0.01062 0							0.0017 0.000 0.0017 0.000
58	Base Case (NP20)	SC01 Treated	29.87	6.33	343	0.16	153.7	0.0121	0.0036	0.1341	92.2	0.00009	83.4	0.00027	0.00027	0.00037	0.87	1.46	0.06	0.00014	100.8	27.5	0.02 0.0	074 0.1	201.5	0.00146	0.00019	0.01071 0	0.00156	187 0.	36 0.0002	0.8239	0.0032	0.0116	0.0017 0.000
59	Base Case (NP20)	SC01 Treated SC01 Treated		6.39		0.15 0.17				0.1219		0.00010			0.00031					0.00015	90.0		0.02 0.0					0.01042 0							0.0016 0.000
60	Base Case (NP20) Base Case (NP20)	SC01 Treated SC01 Treated		6.31					0.0037	0.1316					0.00027		0.86	1.44		0.00013	97.8		0.02 0.0					0.01064 0							0.0017 0.000
62	Base Case (NP20)	SC01 Treated	20.09	6.28	355	0.18	154.8	0.0119	0.0037	0.1320	95.5	0.00010	88.1	0.00026	0.00026	0.00037	0.83	1.37	0.06	0.00013	90.5	28.3	0.02 0.0	066 0.0	193.7	0.00154	0.00019	0.00962 0	0.00146	181 O.	34 0.0002	0.7885	0.0034	0.0104	0.0015 0.000
63	Base Case (NP20)	SC01 Treated SC01 Treated	31.75	6.44	307	0.13 0.15			0.0034		82.8	0.00010	69.1		0.00033					0.00016	79.7 92.7		0.02 0.0	083 0.1	167.6			0.00940 0							0.0015 0.000
65	Base Case (NP20) Base Case (NP20)	SC01 Treated SC01 Treated		6.39					0.0033			0.00009			0.00029		1.01			0.00015	92.7 86.1		0.02 0.0					0.00970 0							0.0016 0.000
66	Base Case (NP20)	SC01 Treated	26.45	6.32	339	0.17	153.3	0.0117	0.0035	0.1217	91.5	0.00010	81.8	0.00025	0.00028	0.00038	0.91	1.34	0.06	0.00014	85.7	27.0	0.02 0.0	065 0.0	183.2	0.00146	0.00019	0.00918 0	0.00156	170 0.	36 0.0002	0.8692	0.0032	0.0100	0.0015 0.000
67	Base Case (NP20)	SC01 Treated	30.12	6.37	324	0.15			0.0034	0.1145	87.4	0.00010	75.6	0.00026	0.00030	0.00039	0.97	1.32	0.06	0.00015	83.2	25.7	0.02 0.0	069 0.1	175.5	0.00136	0.00020	0.00916 0	0.00164	164 0. 163 0	38 0.0002	0.9287	0.0029	0.0100	0.0015 0.000
68	Base Case (NP20) Base Case (NP20)	SC01 Treated SC01 Treated		6.38					0.0034			0.00010			0.00030					0.00015	82.6 90.7		0.02 0.0					0.00911 0							0.0015 0.000 0.0015 0.000
70	Base Case (NP20)	SC01 Treated		6.39					0.0034						0.00031			1.26	0.06	0.00016	77.9	25.1	0.02 0.0	071 0.1				0.00884							0.0014 0.000
71	Base Case (NP20)	SC01 Treated		6.45					0.0035			0.00010			0.00033		1.08			0.00016	76.2		0.02 0.0					0.00937 0							0.0014 0.000
	Base Case (NP20) Base Case (NP20)	SC01 Treated SC01 Treated	23.41 28.01	6.30			154.3 152.3		0.0038			0.00010			0.00027 0.00031					0.00013	87.5 75.7		0.02 0.0					0.00967 0 0.00885 0							0.0015 0.000 0.0014 0.000
	Base Case (NP20)	SC01 Treated	23.52	6.34	332	0.16			0.0037			0.00010			0.00029			1.28		0.00015	79.5		0.02 0.0	076 0.0	174.0	0.00133	0.00019	0.00906 0	0.00155						0.0014 0.000
	Base Case (NP20)	SC01 Treated	19.92	6.31	340	0.17		0.0111		0.1156		0.00010			0.00028			1.29		0.00014	79.9		0.02 0.0					0.00854							0.0014 0.000
	Base Case (NP20) Base Case (NP20)	SC01 Treated SC01 Treated		6.45					0.0033			0.00010			0.00034					0.00017	67.1 76.3		0.02 0.0					0.00802 0							0.0013 0.000 0.0014 0.000
	Base Case (NP20)	SC01 Treated	37.91			0.14		0.0134		0.1002		0.00010	69.8		0.00032		1.02			0.00015	73.7		0.02 0.0				0.00020		0.00164	104			0.0027		0.0013 0.000
	Base Case (NP20)	SC01 Treated	28.46	6.29	336	0.18	153.9			0.1116		0.00010			0.00029		0.92	1.20		0.00014	74.5		0.02 0.0	0.0	168.0			0.00862 0							0.0013 0.000
	Base Case (NP20) Base Case (NP20)	SC01 Treated SC01 Treated		6.33				0.0134		0.1045		0.00010			0.00031		0.99	1.14		0.00015	70.7		0.02 0.0			0.00134		0.00833 0							0.0013 0.000 0.0013 0.000
	Base Case (NP20)	SC01 Treated	38.17	6.35	317	0.17			0.0036			0.00010			0.00031					0.00015	69.8		0.02 0.0					0.00844 0							0.0012 0.000
	Base Case (NP20)	SC01 Treated	30.61					0.0126	0.0036			0.00010			0.00028		0.91 1.00	1.18		0.00014	73.7 66.8		0.02 0.0					0.00823 0							0.0013 0.000
85	Base Case (NP20) Base Case (NP20)	SC01 Treated SC01 Treated		6.35					0.0034			0.00010			0.00031					0.00015	65.4		0.02 0.0					0.00755 0							0.0012 0.000
86	Base Case (NP20)	SC01 Treated	30.51	6.25	349	0.20	154.3	0.0128	0.0037	0.1134	93.8	0.00010	84.3	0.00022	0.00026	0.00038	0.84	1.18	0.06	0.00013	74.3	27.9	0.02 0.0	069 0.0	170.2	0.00150	0.00019	0.00821 0	0.00138	166 O.	34 0.0002	0.7931	0.0033	0.0090	0.0013 0.000
87	Base Case (NP20)	SC01 Treated SC01 Treated		6.32		0.17 0.18			0.0036						0.00031						65.0		0.02 0.0					0.00800 0							0.0012 0.000
89	Base Case (NP20) Base Case (NP20)	SC01 Treated SC01 Treated	29.28	6.31	322				0.0034		90.3	0.00010	78.9	0.00022	0.00030	0.00039	0.97	1.05	0.06	0.00015	65.5 66.7	26.7	0.02 0.0	068 0.0	158.2	0.00142	0.00019	0.00754 0	0.00145		36 0.0002	0.9230	0.0026	0.0084	0.0012 0.000 0.0012 0.000
90	Base Case (NP20)	SC01 Treated	35.37	6.36	306	0.16	151.1		0.0034		82.5	0.00010	67.4	0.00023	0.00032	0.00041	1.05	0.98	0.06	0.00016	60.8	24.2	0.02 0.0	077 0.1	143.2	0.00126	0.00020	0.00747 0	0.00162	142 0.	40 0.0002	0.9900	0.0026	0.0084	0.0001 0.000
91	Base Case (NP20) Base Case (NP20)	SC01 Treated SC01 Treated	25.70	6.25	341				0.0035		91.6	0.00010	80.6	0.00022	0.00027	0.00037	0.86			0.00014	69.8 66.6	27.2	0.02 0.0	058 0.0	162.3	0.00144	0.00019	0.00749 0	0.00140	155 O. 157 O.	34 0.0002	0.8253	0.0031	0.0083	0.0012 0.000 0.0011 0.000
93	Base Case (NP20)	SC01 Treated	22.14	6.31	328	0.18	152.9	0.0128	0.0036	0.1039	88.5	0.00010	77.0	0.00023	0.00029	0.00039	0.95	1.01	0.06	0.00015	62.1	25.9	0.02 0.0	070 0.0	152.6	0.00140	0.00019	0.00734 0	0.00148	149 0.	37 0.0002	0.8966	0.0030	0.0082	0.0011 0.000
94	Base Case (NP20)	SC01 Treated	37.44	6.38	301				0.0034		81.1	0.00010	65.6	0.00023	0.00032	0.00040	1.04	1.02	0.06	0.00016	62.9	23.8	0.02 0.0	077 0.1	143.7	0.00123	0.00020	0.00770 0	0.00163	141 0.	40 0.0002	0.9866	0.0025	0.0086	0.0012 0.000
	Base Case (NP20) Base Case (NP20)	SC01 Treated SC01 Treated		6.35				0.0126	0.0035	0.0992		0.00010			0.00031					0.00015	62.4 62.0		0.02 0.0 0.02 0.0					0.00734 0							0.0011 0.000 0.0011 0.000
	Base Case (NP20)	SC01 Treated		6.36					0.0035			0.00010			0.00029					0.00016	59.0		0.02 0.0					0.00730 0							0.0011 0.000
98	Base Case (NP20)	SC01 Treated	23.89	6.27	339	0.19			0.0036		91.3	0.00010	81.2	0.00022	0.00027	0.00037	0.88		0.06	0.00014	65.8	26.9	0.02 0.0	0.0	159.0	0.00146	0.00019	0.00730 0	0.00141	153 O.	35 0.0002	0.8372	0.0032	0.0081	0.0001 0.000
	Base Case (NP20) Base Case (NP20)	SC01 Treated SC01 Treated	25.25	6.30		0.18 0.14	153.2	0.0113	0.0035	0.1043		0.00010	78.9 62.6	0.00022	0.00029	0.00038	0.92	0.99		0.00015	51.2 52.3	26.4	0.02 0.0	055 0.0	153.0		0.00019	0.00672 0	0.00147				0.0031		0.0011 0.000 0.0010 0.000
	Base Case (NP20)	SC01 Treated		6.26	345	0.20		0.0154		0.1077		0.00010			0.00035		0.83	1.08		0.00018	67.9		0.02 0.0					0.00749 0			33 0.0002				0.0010 0.000
102	Base Case (NP20)	SC01 Treated	26.89	6.28	327	0.18	153.1	0.0139	0.0037	0.1020	88.3	0.00010	76.6	0.00022	0.00029	0.00039	0.93	0.98	0.06	0.00014	60.6	26.0	0.02 0.0	0.0	149.7	0.00140	0.00019	0.00744 0	0.00143	151 0.	36 0.0002	0.8679	0.0030	0.0084	0.0011 0.000
103	Base Case (NP20) Base Case (NP20)	SC01 Treated SC01 Treated	26.95 28.60	6.25		0.19 0.18	154.1 153.0		0.0037	0.1059	91.4	0.00010	81.1 76.6		0.00026		0.85			0.00013	65.1 59.5		0.02 0.0					0.00751 0		156 0. 150 0.	34 0.0002 36 0.0002	0.7994	0.0032	0.0083	0.0011 0.000 0.0010 0.000
	Base Case (NP20)	SC01 Treated	38.42	6.35	311	0.17			0.0037			0.00010	69.9	0.00023	0.00032	0.00040	1.02	0.96			54.7		0.02 0.0	0.0	138.7			0.00734 0							0.0010 0.000
	Base Case (NP20)	SC01 Treated	28.46	6.28	330	0.19	152.9		0.0036		88.9	0.00010	77.4	0.00022	0.00029	0.00038	0.92	0.95	0.06	0.00014	59.0	26.2	0.02 0.0	0.0	148.7	0.00141	0.00019	0.00685	0.00143	146 O.	36 0.0002	0.8713	0.0030	0.0078	0.0010 0.000
	Base Case (NP20) Base Case (NP20)	SC01 Treated SC01 Treated		6.34					0.0035			0.00010			0.00031					0.00015	53.6 58.9		0.02 0.0					0.00667 0 0.00675 0							0.0010 0.000 0.0010 0.000
109	Base Case (NP20)	SC01 Treated	28.80	6.33	317	0.17	151.8		0.0035		85.6	0.00010	72.8	0.00023	0.00031	0.00040	1.00	0.86	0.06	0.00015	52.2	25.0	0.02 0.0	070 0.0	138.8	0.00135	0.00020	0.00647 0	0.00151	138 O.	38 0.0002	0.9500	0.0029	0.0075	0.0009 0.000
110	Base Case (NP20)	SC01 Treated	20.54	6.25	344					0.1079		0.00010			0.00027		0.86	0.94	0.06	0.00014	57.7	27.3	0.02 0.0	060 0.0	152.9			0.00652 0		149 0.	34 0.0002	0.8178	0.0033	0.0074	0.0010 0.000
111	Base Case (NP20) Base Case (NP20)	SC01 Treated SC01 Treated		6.34		0.16 0.18			0.0036			0.00010			0.00030					0.00015	54.4 56.9		0.02 0.0					0.00695 0							0.0010 0.000 0.0010 0.000
113	Base Case (NP20)	SC01 Treated	38.84	6.36	307	0.16	151.3	0.0125	0.0034	0.0921	82.9	0.00010	68.2	0.00022	0.00032	0.00040	1.03	0.85	0.06	0.00016	51.7	24.3	0.01 0.0	066 0.0	134.1	0.00128	0.00020	0.00630 0	0.00156	132 0.	39 0.0002	0.9785	0.0027	0.0073	0.0010 0.000
114	Base Case (NP20)	SC01 Treated	38.65	6.34	305	0.16	151.1			0.0921	82.4	0.00010	67.7	0.00023	0.00032	0.00041	1.04	0.83	0.06	0.00015	50.4	24.1	0.01 0.0	083 0.1	132.3	0.00127	0.00020	0.00673 0	0.00153	136 0.	39 0.0002	0.9718	0.0027	0.0078	0.0009 0.000
115	Base Case (NP20) Base Case (NP20)	SC01 Treated SC01 Treated		6.24			154.1	0.0125	0.0037	0.1059	92.3	0.00010	79.4	0.00021	0.00026	0.00037	0.85	0.92	0.06	0.00013	56.9 52.7	27.3	0.02 0.0	0.58 0.0	149.8	0.00148	0.00019	0.00645 0 0.00595 0	0.00131	148 0.					0.0010 0.000 0.0009 0.000
117	Base Case (NP20)	SC01 Treated		6.29			153.2	0.0118	0.0035	0.1016	89.4	0.00010	77.7	0.00022	0.00029	0.00039	0.93	0.83	0.06	0.00015	50.7	26.2	0.02 0.0	056 0.0	140.7	0.00142	0.00019	0.00575	0.00142	137 0.	36 0.0002	0.8897	0.0031	0.0068	0.0009 0.000
																			_																

Year Scenario	Station	Flow Rate	pН	Hardness (mg	Acidity (mg	Alkalinity (mg	AI (==="I")	As	B (mg/L)	Ca	Cd	CI	Co	Cr	Cu	DOC	F	Fe	Hg	K	Mg	Mn	Mo NO				s		S04		TI	тос	CN	U	v	Zn
		(L/6)	Ľ	CaCO3/L)	CaCO3/L)	CaCO3/L)	(mg/L)	(mg/L)	0.0943	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)		(mg/L)	(mg/L)				(mg/L) (m					I/L) (mg/		1.	(mg/L)	(mg/L)			(mg/L)	(mg/L)
	SC01 Treated SC01 Treated	32.63 30.94		313 318	0.17 0.18		0.0130		0.0943		0.00010			0.00031					0.00015	50.2 49.5		0.01			34.2 0.00 35.6 0.00			0603 0.001					0.0028		0.0009	
120 Base Case (NP20)	SC01 Treated		6.31	317				0.0035			0.00010			0.00030					0.00015	50.4								0.001					0.0028			
	SC01 Treated SC01 Treated	29.98 30.16	6.30	326 322		152.6	0.0129	0.0036			0.00010			0.00029					0.00015	48.5 48.4			0.0066		87.7 0.00 85.6 0.00			0.001 0.001 0.001					0.0030		0.0009	
123 Base Case (NP20)	SC01 Treated	33.34	6.33	316	0.17	151.9	0.0123	0.0034	0.0950	85.2	0.00010	71.7	0.00022	0.00030	0.00039	0.98	0.79	0.06	0.00015	48.2	25.0	0.01	0.0063	0.09 13	3.2 0.00	133 0.000	20 0.00	582 0.001	147 13	1 0.37	7 0.0002	0.9351	0.0028	0.0069	0.0009	0.0007
124 Base Case (NP20)	SC01 Treated SC01 Treated	25.31	6.29	331 304	0.19 0.16		0.0121	0.0035	0.1021		0.00010			0.00029					0.00015	48.1 46.4								0.001 0.001 0.001					0.0031			
	SC01 Treated	39.39	6.33	307				0.0034		82.8	0.00010	68.2		0.00032					0.00015	47.4			0.0076	0.09 12	9.1 0.00	128 0.000	20 0.00	620 0.001	148 13				0.0027			
127 Base Case (NP20)	SC01 Treated	36.37		325 337	0.19 0.21			0.0036			0.00010			0.00029					0.00014	47.8 48.6			0.0072					599 0.001					0.0030			
	SC01 Treated SC01 Treated		6.23					0.0035			0.00010			0.00028					0.00014			0.01						0.001 0.543 0.001					0.0032			
130 Base Case (NP20)	SC01 Treated	30.80	6.31	309	0.18	151.3		0.0035				69.0	0.00022	0.00031	0.00040	1.02	0.72	0.06	0.00015	43.4	24.4	0.01	0.0073	0.09 12	6.0 0.00	129 0.000	20 0.00	572 0.001	148 12	9 0.38	0.0002	0.9572	0.0027	0.0069	0.0008	0.0007
	SC01 Treated SC01 Treated		6.33					0.0036			0.00010			0.00032 0.00030					0.00015 0.00015	43.0								0601 0.001					0.0027 0.0028			
	SC01 Treated		6.29	319			0.0139		0.0958		0.00010			0.00030					0.00013	46.1								0.001					0.0029			
	SC01 Treated	27.08	6.20	345	0.22			0.0039		92.9	0.00010	83.5	0.00021	0.00026	0.00038	0.83		0.07	0.00013	48.6	27.5	0.02	0.0073	0.08 14	2.0 0.00	151 0.000	118 0.00	0.001	121 14	6 0.32	2 0.0002	0.7684	0.0033	0.0071	0.0008	0.0006
	SC01 Treated SC01 Treated		6.29				0.0120	0.0035	0.0998		0.00010			0.00029		0.93	0.73		0.00015	44.3 45.3		0.01						0.001 0.001 0.001					0.0030			
137 Base Case (NP20)	SC01 Treated	23.46	6.29	327	0.19	152.2	0.0119	0.0035	0.1003	88.4	0.00010	77.0	0.00022	0.00029	0.00039	0.95	0.70	0.06	0.00015	41.8	25.8	0.01	0.0055	0.09 13	31.5 0.00	142 0.000	20 0.00	1497 0.001	139 12	9 0.36	5 0.0002	0.9051	0.0031	0.0061	0.0007	0.0007
	SC01 Treated SC01 Treated		6.36	299 304			0.0137	0.0035	0.0894		0.00010			0.00032			0.67		0.00016	39.6 39.4	23.5				0.2 0.00			0.001 0.001 0.001					0.0026		0.0008	
	SC01 Treated	44.59	6.38	292			0.0113		0.0860		0.00010			0.00032					0.00016	40.4								0586 0.001					0.0027			
	SC01 Treated	29.55	6.24	342				0.0036				82.5	0.00021	0.00027	0.00038	0.86	0.74		0.00014	44.7 38.3								512 0.001					0.0033			
	SC01 Treated SC01 Treated		6.33	311 343	0.18 0.21		0.0132	0.0035			0.00010			0.00032			0.65		0.00016									0509 0.001 0544 0.001		0.00			0.0028			
144 Base Case (NP20)	SC01 Treated	33.13	6.29	315	0.18	151.3	0.0127	0.0035	0.0940	84.9	0.00010	71.2	0.00021	0.00030	0.00039	0.96	0.69	0.06	0.00015	41.4	25.0	0.01	0.0064	0.09 12	5.2 0.00	132 0.000	119 0.00	0.001	140 12	6 0.37	7 0.0002	0.9122	0.0028	0.0064	0.0007	0.0007
	SC01 Treated SC01 Treated		6.20	353 299			0.0120		0.1096		0.00010			0.00025					0.00013	44.2 38.1								0.001 0.560 0.001					0.0035			
147 Base Case (NP20)	SC01 Treated	35.15	6.32	313	0.18	150.7	0.0124	0.0034	0.0946	84.7	0.00010	71.3	0.00022	0.00031	0.00040	1.00	0.64	0.06	0.00015	37.9	24.7	0.01	0.0061	0.09 12	2.7 0.00	134 0.000	20 0.00	1480 0.001	145 12	2 0.37	7 0.0002	0.9547	0.0028	0.0060	0.0007	0.0007
148 Base Case (NP20)	SC01 Treated SC01 Treated	32.97	6.27	322 305	0.19 0.18		0.0133	0.0036	0.0978		0.00010			0.00029					0.00014	41.1 37.2			0.0069 0.0082					0.001 0.545 0.001					0.0030			
	SC01 Treated		6.26		0.10			0.0036		87.2	0.00010	75.0	0.00022	0.00031	0.00039	0.93			0.00013	39.4								0504 0.001					0.0027			
151 Base Case (NP20)	SC01 Treated		6.32					0.0036		84.9	0.00010	71.8		0.00030					0.00015	37.6	24.9	0.01	0.0073					513 0.001					0.0029			
152 Base Case (NP20) 153 Base Case (NP20)	SC01 Treated SC01 Treated		6.29	317 316	0.19 0.19	151.0		0.0036	0.0961		0.00010			0.00030					0.00015 0.00015	38.0 36.9			0.0074					0.001 0.001 0.001					0.0029			
154 Base Case (NP20)	SC01 Treated	34.03	6.30	313	0.18	150.5	0.0135	0.0036	0.0947	84.6	0.00010	71.5	0.00022	0.00030	0.00040	0.98	0.63	0.06	0.00015	37.2	24.8	0.01	0.0071	0.09 12	1.5 0.00	134 0.000	119 0.00	506 0.001	139 12	5 0.36	5 0.0002	0.9181	0.0028	0.0063	0.0007	0.0007
155 Base Case (NP20)	SC01 Treated SC01 Treated		6.27 6.32					0.0036			0.00010			0.00029			0.64		0.00014 0.00015				0.0065 0.0070					0.001 0.001 0.001					0.0030 0.0028			
	SC01 Treated		6.28	319				0.0036			0.00010			0.00030					0.00013									508 0.001					0.0020			
158 Base Case (NP20)	SC01 Treated	30.09	6.24	334				0.0036		89.9	0.00010	79.6		0.00027				0.06	0.00014	39.4	26.5	0.01	0.0059	0.08 12				1475 0.001					0.0032			
	SC01 Treated SC01 Treated	38.04 28.00	6.31	311 335	0.18	150.0 151.8		0.0036			0.00010			0.00031		0.99	0.60	0.06	0.00015	35.4 38.9	26.6		0.0078	0.09 11	9.4 0.00	133 0.000	120 0.00	0.001 0.001 0.001	139 12 123 13				0.0028			
161 Base Case (NP20)	SC01 Treated	27.32	6.23	335	0.21	151.9	0.0113	0.0035	0.1024	90.4	0.00010	79.6		0.00027		0.88	0.62	0.06	0.00014	37.2	26.6	0.01	0.0046	0.08 12				1412 0.001		6 0.33	0.0002	0.8425	0.0032	0.0054	0.0006	0.0006
	SC01 Treated SC01 Treated		6.20	347 298				0.0037			0.00010			0.00026			0.63		0.00013	37.4								0.001 0466 0.001					0.0034			
	SC01 Treated	31.42	6.31	315	0.18		0.0109		0.0097		0.00010			0.00039	0.00038				0.00015	36.0	25.0					134 0.000		1418 0.001					0.0029		0.0007	
	SC01 Treated SC01 Treated		6.32					0.0035			0.00010			0.00031			0.58		0.00015	33.8 35.1			0.0072	0.09 11				484 0.001					0.0027			
	SC01 Treated		6.25	315			0.0119		0.1018		0.00010			0.00030					0.00014	33.5		0.01						0.001 0429 0.001					0.0032		0.0006	
	SC01 Treated		6.31	315				0.0034			0.00010			0.00030			0.57		0.00015									1428 0.001					0.0029			
169 Base Case (NP20) 170 Base Case (NP20)	SC01 Treated SC01 Treated	18.25 27.73	6.19	357 309			0.0112	0.0037	0.1122		0.00010			0.00024					0.00013	37.8 31.6								0.001 0.001 0.001					0.0036			
171 Base Case (NP20)	SC01 Treated	37.84	6.39	291	0.15	148.7	0.0142	0.0035	0.0870	78.9	0.00010	63.6	0.00023	0.00033	0.00041	1.08	0.54	0.06	0.00016	30.3	22.8	0.01	0.0081	0.10 10	8.9 0.00	123 0.000	20 0.00	1488 0.001	150 11	5 0.39	0.0002	1.0129	0.0025	0.0062	0.0006	0.0008
	SC01 Treated SC01 Treated	23.41	6.24	336 312				0.0038						0.00027					0.00013 0.00015	35.8	26.6	0.01						0.001 0446 0.001					0.0033			
174 Base Case (NP20)	SC01 Treated	23.52	6.28	324	0.19	151.3	0.0129	0.0037	0.0999	87.6	0.00010	76.8	0.00022	0.00029	0.00038	0.93	0.57	0.06	0.00014	32.9	25.5	0.01	0.0065	0.09 12	2.1 0.00	142 0.000	119 0.00	0.001	131 12	4 0.34	4 0.0002	0.8816	0.0031	0.0057	0.0006	0.0007
175 Base Case (NP20)	SC01 Treated SC01 Treated		6.26					0.0035		89.7	0.00010	79.5	0.00021	0.00028	0.00037				0.00014				0.0048					390 0.001					0.0032			
	SC01 Treated SC01 Treated		6.40					0.0034						0.00034					0.00017									0.001 0.001 0.001					0.0026			
178 Base Case (NP20)	SC01 Treated	37.91	6.32	303				0.0035		82.0	0.00010	67.4	0.00022	0.00031	0.00040	1.02	0.53	0.06	0.00015	30.4	23.9	0.01	0.0072	0.09 11	1.6 0.00	128 0.000	20 0.00	0.001	142 11	6 0.37	7 0.0002	0.9634	0.0027	0.0058	0.0006	0.0007
179 Base Case (NP20) 180 Base Case (NP20)	SC01 Treated SC01 Treated		6.25	328 313	0.20 0.19		0.0137	0.0037	0.1011		0.00010			0.00028				0.06	0.00014	32.1 30.2								0.001 0.001 0.001					0.0031			
181 Base Case (NP20)	SC01 Treated	33.17	6.26	322	0.20	151.5	0.0133	0.0036	0.0975	86.9	0.00010	74.4	0.00021	0.00028	0.00039	0.91	0.56	0.06	0.00014	32.5	25.6	0.01	0.0067	0.09 11	8.7 0.00	138 0.000	119 0.00	0.001	127 12	3 0.34	4 0.0002	0.8594	0.0030	0.0057	0.0006	0.0006
182 Base Case (NP20)	SC01 Treated SC01 Treated		6.30	310 327			0.0141	0.0036	0.0935		0.00010			0.00031					0.00015	29.8 31.7								0450 0.001 0409 0.001					0.0028		0.0006	
	SC01 Treated	36.09	6.31	312	0.19			0.0034			0.00010			0.00028					0.00014	29.0								380 0.001					0.0031			
185 Base Case (NP20)	SC01 Treated	53.41	6.37	294	0.17	148.9	0.0152		0.0879		0.00010	64.0	0.00022	0.00033	0.00042	1.06			0.00016	27.8	23.2	0.01	0.0087	0.10 10				478 0.001		6 0.38	0.0002	0.9894	0.0025	0.0062	0.0006	0.0008
	SC01 Treated SC01 Treated		6.21	341 310			0.0129	0.0037	0.1054		0.00010			0.00026			0.56		0.00013	32.8 28.6		0.01						0.001 0.001 0.001					0.0033			
188 Base Case (NP20)	SC01 Treated	33.74	6.27	315	0.19	150.2	0.0129	0.0035	0.0950	85.0	0.00010	71.4	0.00021	0.00030	0.00040	0.97	0.50	0.06	0.00015	29.0	24.9	0.01	0.0061	0.09 11	3.1 0.00	134 0.000	20 0.00	393 0.001	135 11	6 0.35	5 0.0002	0.9228	0.0028	0.0053	0.0005	0.0007
189 Base Case (NP20) 190 Base Case (NP20)	SC01 Treated SC01 Treated	29.28 35.37	6.25	328 299	0.21	151.3 149.1	0.0129	0.0036	0.1006	88.6	0.00010	77.0 65.6		0.00028		0.91		0.06	0.00014	30.2 27.1	26.0				18.8 0.00 16.9 0.00			0.001 0.001 0.001		2 0.33	0.0002	0.8622	0.0031	0.0053	0.0005	0.0006
191 Base Case (NP20)	SC01 Treated	25.70	6.22	333	0.21	151.7	0.0117	0.0035	0.1015	89.8	0.00010	78.6	0.00020	0.00027	0.00038	0.86	0.54	0.06	0.00014	31.6	26.5	0.01	0.0049	0.08 12	21.1 0.00	144 0.000	119 0.00	369 0.001	122 12	1 0.32	2 0.0002	0.8251	0.0031	0.0050	0.0005	0.0006
	SC01 Treated SC01 Treated		6.22					0.0037			0.00010			0.00027					0.00014	31.0 28.9								398 0.001 399 0.001					0.0032			
	SC01 Treated SC01 Treated	37.44	6.28	293	0.16			0.0036						0.00029					0.00015									0.001 0425 0.001					0.0030			
195 Base Case (NP20)	SC01 Treated	37.93	6.32	311	0.18	149.6	0.0127	0.0035	0.0944	84.2	0.00010	71.2	0.00022	0.00030	0.00039	0.99	0.51	0.06	0.00015	28.9	24.5	0.01	0.0062	0.09 11	3.3 0.00	134 0.000	20 0.00	401 0.001	137 11	5 0.36	5 0.0002	0.9353	0.0028	0.0054	0.0005	0.0007
	SC01 Treated SC01 Treated		6.29				0.0130	0.0036	0.1002		0.00010			0.00029					0.00015	29.6 27.9								0.001 0.001 0.001					0.0031			
198 Base Case (NP20)	SC01 Treated	23.89	6.24	332	0.20	151.4	0.0119	0.0036	0.1022	89.6	0.00010	79.5	0.00021	0.00027	0.00037	0.88	0.55	0.06	0.00014	31.4	26.2	0.01	0.0054	0.08 12	2.3 0.00	146 0.000	19 0.00	387 0.001	124 12	2 0.32	0.0002	0.8371	0.0032	0.0052	0.0005	0.0006
199 Base Case (NP20)	SC01 Treated RS03 Untreated		6.27 6.57	327 60			0.0114	0.0035	0.1003 0.0199		0.00010 0.00007			0.00029 0.00043					0.00015 0.00017	29.9 3.7								0.001 090 0.001					0.0031			
1 Base Case (NP20)	RS03 Untreated	14.34	6.57	113	0.09	114.1	0.0169	0.0218	0.0318	27.6	0.00007	6.0	0.00111	0.00044	0.00073	1.31	0.27	0.92	0.00017	16.4	10.7	0.02	0.0189	2.89 3	35.7 0.00	059 0.000	45 0.05	917 0.004	135 3	6 0.58	0.0002	1.2939	0.0000	0.0061	0.0026	0.0016
2 Base Case (NP20)	RS03 Untreated		6.56 6.50					0.0217	0.0322	27.1	0.00007			0.00045		1.32	0.28	0.90	0.00017 0.00017	17.1	10.5		0.0203							8 0.61	0.0002	1.3019	0.0000	0.0065	0.0027	0.0016
3 Base Case (NP20)	RS03 Untreated	13.99	0.50	115	U.10	115.2	0.0179	u.u230	u.u330	21.9	v.uuuu/	0.2	J.UJ 126	0.00045	0.000/4	1.2/	U.31	1.03	0.00017	19.5	11.1	0.02	0.0227		I U.UL	0.000	-0.0	240 U.005	~~ 4	U.00	0.0002	1.200/	0.0000	0.0072	0.0031	u.uu 10

F Sear Cases (NP20) R503 Universaled 15.66 6.55 109 0.09 0.016 0.016 0.017 0.027 57 0.0007 57 0.00	L) (mg/L) (mg/L) (mg/L) (mg/L
State Case (19/20) FSSS Universaled 22 st 2 st 7 108 0.099 108 st 0 st	99 0.0000 0.0071 0.0030 0.001
Figure Case (NP20) ROSS Unfreaded 15-79 6.57 108 0.09 19-4 0.0186 0.021 0.0007 2.5 0.00097 5.7 0.00097 0.00045 0.00077 1.3 0.28 0.08 0.00077 1.5 0.02 0.0180 2.4 2.4 0.00085 0.00048 0.00048 0.00047 0.0001 0.00048 0.00048 0.00049	35 0.0000 0.0062 0.0027 0.001
State Case (NP20) Residual NP20 Residual	03 0.0000 0.0064 0.0028 0.001
See Case (NP20) RS03 Unfreaded 17.77 6.58 110 0.08 112.1 0.168 0.0213 0.0297 27 0.00007 6.4 0.00007 1.36 0.08 0.00007 1.36 0.08 0.00007 1.36 0.00007	48 0.0000 0.0061 0.0026 0.001 24 0.0000 0.0063 0.0027 0.001
11 (Base Case (NP20) R503 Unrhanded 11.91 (6.56) 120 (0.09) 123.8 (0.0165) (0.0341 (0.0351 (0.0001 1.00046) (0.00072 (1.31 (0.32) (0.0001 1.00046) (0.00072 (1.31 (0.32) (0.0001 1.00046) (0.00072 (1.31 (0.32) (0.0001 1.00046) (0.00072 (1.31 (0.32) (0.0001 1.00046) (0.00072 (1.31 (0.32) (0.0007 (1.31 (0.00072 (1.31 (0.000	20 0.0000 0.0059 0.0027 0.001
12 (See Case (PP2D) R503 Universide 1 4.97 6.53 115 0.10 116.4 (0.971 0.020 0.0300 0.0007 6.50 0.00007 6.50 0.00007 6.50 0.00007 6.50 0.00007 6.50 0.00007 6.50 0.00007 6.50 0.00007 6.50 0.000000	01 0.0000 0.0063 0.0028 0.001
13 Base Cases (PR2D) R030 Unrelated 23.17 6.55 104 0.09 104.4 0.075 0.0007 1.00007 1.00007 1.00007 0.00004 1.00007 1.45 0.27 0.99 0.00007 1.45 0.077 0.0001 0.0004 1.00007 1.45 0.27 0.0000 1.0004 1.00007 1.45 0.27 0.0000 1.0004 1.00007 1.45 0.27 0.0000 1.0004 1.00007 1.45 0.27 0.0000 1.0004 1.00007 1.45 0.27 0.0000 1.0004 1.00007 1.45 0.27 0.0000 1.0004 1.00007 1.45 0.27 0.0000 1.0004 1.00007 1.45 0.27 0.0000 1.0004 1.00007 1.45 0.27 0.0000 1.0004 1.00007 1.45 0.27 0.0000 1.0004 1.00007 1.45 0.27 0.0000 1.0004 1.00007 1.45 0.27 0.0000 1.0004 1.00007 1.45 0.27 0.0000 1.0004 1.00007 1.45 0.27 0.0000 1.0004 1.00007 1.45 0.27 0.0000 1.0004 1.00007 1.45 0.27 0.0000 1.0004 1.00007 1.45 0.20 0.0004 1.000007 1.45 0.20 0.0004 1.00007 1.45 0.20 0.0004 1.00007 1.45 0.20 0.0004 1.00007 1.45 0.20 0.0004 1.00007 1.45 0.20 0.0004 1.00007 1.45 0.20 0.0004 1.00007 1.45 0.20 0.0004 1.00007 1.45 0.20 0.0004 1.00007 1.45 0.20 0.0004 1.00007 1.45 0.20 0.0004 1.00007 1.45 0.20 0.0004 1.45 0.00007 1.45 0.20 0.0004 1.45 0.20 0.00007 1.45 0.20 0.0004 1.45 0.20 0.0004 1.45 0.20 0.00007 1.45 0.20 0.00007 1.45 0.20 0.0004 1.45 0.20 0.00007 1.45 0.20 0.00007 1.45 0.20 0.0004 1.00007 1.45 0.20 0.00007 1.45 0.20 0.00007 1.45 0.20 0.00007 1.45 0.20 0.00007 1.45 0.20 0.00007 1.45 0.20 0.00007 1.45 0.20 0.00007 1.45 0.20 0.00007 1.45 0.20 0.00007 1.45 0.20 0.	14 0.0000 0.0057 0.0024 0.001 83 0.0000 0.0062 0.0027 0.001
14 [Base Case (PP20) R503 Unfroated 21.90 6.57 101 0.09 100.4 0.0172 0.0367 25.1 0.00007 5.1 0.00013 0.00044 0.00075 1.34 0.32 1.02 0.0016 14.7 9.3 0.02 0.0196 2.41 30.1 0.00055 0.00046 0.6651 0.00046 36 0.60 0.00021 1.16 [Base Case (PP20) R503 Unfroated 17.50 5.5 5 113 0.09 114.9 0.0165 0.0229 0.0385 27.4 0.00007 5.8 0.0003 0.0003 1.33 0.00 0.0004 0.00075 1.34 0.32 1.0005 0.00046 0.00051 0.00046 36 0.0004 0.00007 1.16 1.16 1.00 0.00 0.0004 0.00051 0.0004 0.00055 0.00046 0.0004 0.00051 0.0004 0.0	16 0.0000 0.0054 0.0027 0.001
16 Base Case (NP20) R503 Universide 17,10 6,5 5 114 0.09 116,6 0.0752 0.0229 0.0238 27,9 0.00007 5,9 0.00071 0.00045 0.00072 1.33 0.20 0.09 0.00071 1.56, 10.77 0.02 0.0177 0.024 0.0752 0.0552 0.00054 0.00045 0.00073 1.00045 0.00071 1.00045 0.00045 0.00045 0.00071 1.00045 0.00071 1.00045 0.00071 1.00045 0.00045 0.00045 0.00071 1.00045 0.00071 1.00045 0.0004	31 0.0000 0.0056 0.0024 0.001
Fig.	80 0.0000 0.0064 0.0028 0.001
18 Base Case (NP20) RS03 Untreated 18.47 6.57 105 0.09 106.3 0.015 0.0201 0.0253 2.50 0.00007 5.3 0.00062 0.00045 0.00073 1.40 0.25	29 0.0000 0.0056 0.0025 0.001
19 Base Case (NP20) R503 Unireated 19.36 6.55 105 0.09 19.2 0.0166 0.021 1 0.0259 2.56 0.00007 5.5 0.00054 0.00047 0.00044 0.00077 1.41 0.0 0.00057 0.00045 0.00077 1.41 0.00057 0.0	60 0.0000 0.0050 0.0022 0.001
Ease Case (NP20) R503 Unfreated 18.10 6.58 112 0.09 113.7 0.0146 0.0221 0.0272 27.4 0.00007 5.7 0.00063 0.00045 0.00077 1.35 0.02 0.0147 2.23 3.15 0.00052 0.0042 0.0559 0.00419 3.2 0.59 0.00021 1.35 0.0042 0.0559 0.00419 3.2 0.59 0.00021 1.35 0.0042 0.0559 0.00419 0.0073 1.39 0.02 0.0045 0.000021 1.35 0.0045 0.00021 1.35 0.004	44 0.0000 0.0053 0.0023 0.001
28 Base Case (MP20) RS03 Unfreated 19.11 6.58 109 0.08 111.5 0.096 0.020 0.055 27.0 0.00007 5.3 0.0005 0.00045 0.0007 13.9 0.25 0.86 0.0007 13.9 0.25 0.0004 0.0007 13.9 0.0002 1.35 0.00002 0.0004 0.0007 13.0 0.0005 0.00004 0.0007 13.0 0.0004 0.00007 13.0 0.0004 0.0007 13.0 0.0004 0.0007 13.0 0.0004 0.0007 13.0 0.0004 0.0007 13.0 0.0004 0.0007 13.0 0.0004 0.0007 13.0 0.0004 0.0007 13.0 0.0004 0.0007 13.0 0.0004 0.0007 13.0 0.0004 0.00007 13.0 0.0004 0.0007 13.0 0.0004 0.0007 13.0 0.0004 0.00007 13.0 0.0	88 0.0000 0.0051 0.0022 0.001 69 0.0000 0.0054 0.0024 0.001
26 Base Case (NP20) R503 Unfrested 15.30 6.56 115 0.09 11.46 0.0163 0.0226 0.0272 28.3 0.00007 5.9 0.0007 1.00007 1.0007 1.000007 1.000007 1.00007 1.00007 1.00007 1.00007 1.00007 1.00007 1.000007 1.00007 1.	68 0.0000 0.0051 0.0022 0.001
State Case (NP20)	67 0.0000 0.0049 0.0022 0.001
26 Base Case (NP20) R503 Unfrested 20.5 6.5 4 107 0.10 10.6 1 0.0176 0.0199 0.024 24.6 1.000007 5.3 0.0004 0.0004 0.00075 1.38 0.27 0.99 0.0016 15.3 9.2 10.0 0.02 0.0141 2.5 1 27.5 0.00052 0.00044 0.00473 0.00070 33 0.058 0.0002 1.4 1.2 1.2 1.2 1.2 1.2 1.2 1.2 1.2 1.2 1.2	11 0.0000 0.0052 0.0023 0.001 31 0.0000 0.0047 0.0020 0.001
28 Base Case (NP20) R503 Unfrested 14.59 6.54 110 0.09 110.0 0.0169 0.0225 0.0258 26.9 0.00007 5.5 0.00052 0.00045 0.00074 1.35 0.27 0.97 0.00017 14.8 10.4 0.0 0.1015 0.2 45 31.7 0.00052 0.00044 0.05395 0.00049 34 0.64 0.00021 1.35 0.0004 0.00045 0.00071 1.35 0.27 0.00017 14.8 10.4 0.2 0.1015 0.2 0.1015 0.2 45 31.7 0.00052 0.00044 0.05395 0.00049 34 0.64 0.00021 1.35 0.0004 0.00045 0.00071 1.35 0.2 0.0004 0.00045 0.00071 1.35 0.00017 1.41 1.05 0.0 0.0 0.015 0.2 45 31.7 0.00052 0.00044 0.00345 0.00071 1.35 0.00041 0.00045 0.00071 1.35 0.00041 0.00045 0.00071 1.35 0.00041 0.00045 0.00071 1.35 0.00041 0.00045 0.00071 1.35 0.00041 0.00045 0.00071 1.35 0.00041 0.00045 0.00071 1.35 0.00041 0.00045 0.00071 1.35 0.00041 0.00045 0.00071 1.35 0.00041 0.00045 0.00071 1.35 0.00041 0.00045 0.00071 1.35 0.00041 0.00045 0.00071 1.35 0.00041 0.00045 0.00071 1.35 0.00041 0.00045 0.00071 1.35 0.00041 0.00045 0.00071 1.35 0.00041 0.00045 0.00071 1.35 0.00041 0.00045 0.00071 1.35 0.00041 0.00045 0.00071 1.35 0.00041 0.00045 0.00071 1.35 0.00041 0.00044 0.00045 0.00071 1.35 0.00041 0.00044 0.00045 0.00071 1.35 0.00041 0.00044 0.00045 0.00071 0.00044 0.00045 0.0	85 0.0000 0.0049 0.0021 0.001
29 Base Case (NP20) R503 Universided 17.52 6.55 112 0.09 113.5 0.0167 0.0225 0.0260 27.4 0.00007 5.5 0.00008 0.00073 1.33 0.26 0.93 0.00017 1.4.1 10.6 0.0 0.0 0.143 2.32 31.8 0.00051 0.00043 0.05095 0.00098 33 0.61 0.00002 1.3 30 0.00007 0.0000 0.00000 0	20 0.0000 0.0055 0.0024 0.001 79 0.0000 0.0052 0.0023 0.001
30 Base Case (NP20) R503 Untreated 11,98 6.58 104 0.08 106.0 0.0166 0.020 0.0248 25,9 0.0007 5.2 0.0004 0.00054 0.0007 1.40 0.23 0.85 0.00017 12.3 9,7 0.02 0.0127 2.18 28.5 0.00051 0.0004 0.0039 0.00357 31 0.55 0.0002 1.3 10 Base Case (NP20) R503 Untreated 20.10 6.57 104 0.09 103.0 0.075 0.027 0.024 25,7 0.0007 5.0 0.0004 0.00055 1.41 0.24 0.33 0.0004 0.00057 1.41 0.24 0.30 0.00016 13.3 9.5 0.02 0.0135 2.46 28.2 0.00051 0.0004 0.04564 0.00357 32 0.56 0.0002 1.3 13 Base Case (NP20) R503 Untreated 20.61 6.55 102 0.10 100.1 0.0176 0.020 0.024 0.25 0.0007 5.0 0.0004 0.00057 1.41 0.24 0.33 0.00016 13.3 9.5 0.02 0.0135 2.46 28.2 0.00051 0.0004 0.04660 0.00564 33 0.59 0.0002 1.3 14 0.025 0.0005 0.0004 0.00056 0.0005	79 0.0000 0.0052 0.0023 0.001 65 0.0000 0.0050 0.0022 0.001
32 Base Case (NP20) RS03 Unfreated 19.95 6.54 103 0.09 103.0 0.0175 0.020 0.0244 25.5 0.00007 5.0 0.00044 0.00075 1.41 0.24 0.93 0.00016 13.0 9.5 0.02 0.0135 2.46 28.2 0.00051 0.00044 0.00564 33 0.59 0.0002 1.3 3 Base Case (NP20) RS03 Unfreated 13.90 6.50 112 0.10 1122 0.10 1122 0.010 1122 0.00007 5.6 0.00007 5.6 0.00007 5.6 0.00047 0.00045 0.00075 1.31 0.7 0.02 0.0157 2.63 3.3 0.00016 0.0004 0.00075 0.00044 0.00075 1.31 0.7 0.02 0.0157 2.63 3.3 0.00016 0.0004 0.00075 0.00044 0.00075 1.31 0.7 0.02 0.0157 2.63 0.00016 0.0004 0.00075 0.00044 0.000075 0.00044 0.000075 0.00044 0.000075 0.00044 0.000075 0.00044 0.000075 0.00044 0.00007	50 0.0000 0.0045 0.0020 0.001
33 Base Case (NP20) R503 Unireated 20.61 6.53 102 0.10 100.1 100.1 0.0176 0.0208 0.0239 25.1 0.00007 4.9 0.00043 0.00044 0.00075 1.42 0.24 0.96 0.00016 13.3 9.5 0.02 0.135 2.55 27.7 0.00051 0.00044 0.04680 0.00368 33 0.50 0.00021 1.3 8 Base Case (NP20) R503 Unireated 21.02 6.54 111 0.10 112.2 0.1017 0.0228 0.0254 27.2 0.00007 5.5 0.00045 0.00074 1.33 0.25 0.0001 0.00044 0.00077 0.00044 0.00074 0.00044 0.00074 0.00044 0.00074 0.00044 0.00074 0.00044 0.00074 0.00044 0.00074 0.00044 0.00074 0.00044 0.00075 0.00044 0.00075 0.00044 0.00075 0.00045 0.00016 1.33 0.0004 0.00047 0.00044 0.00047 0.00044 0.00047 0.00044 0.00047 0.00044 0.	68 0.0000 0.0046 0.0020 0.001 56 0.0000 0.0048 0.0020 0.001
38 Base Case (NP20) RS03 Untreated 13.90 6.50 112 0.10 112 0.0180 0.0240 0.0257 27.3 0.00007 5.6 0.00047 0.00075 1.31 0.27 1.05 0.0016 15.3 10.7 0.02 0.0157 2.53 32.3 0.00051 0.00047 0.05571 0.0044 37 0.68 0.0002 1.2 35 Base Case (NP20) RS03 Untreated 14.56 6.55 114 0.09 116.7 0.08 119.3 0.0159 0.0221 0.0257 2.80 0.00007 5.7 0.00042 0.00075 1.33 0.25 0.39 0.00017 13.3 10.5 0.02 0.0131 2.25 31.7 0.00050 0.00043 0.0446 0.00384 31 0.52 0.0007 1.33 0.25 0.39 0.00017 13.3 0.25 0.39 0.00017 13.5 10.8 0.02 0.0131 2.25 31.7 0.00050 0.00043 0.0446 0.00384 31 0.52 0.00017 13.3 0.25 0.39 0.00017 13.5 10.8 0.02 0.0131 2.25 31.7 0.00050 0.00043 0.0446 0.00384 31 0.52 0.0002 1.3 0.0005 0.00045 0.0007 0.00045 0.00045 0.0007 0.00045 0.00045 0.00045 0.00045 0.0007 0.00045 0.000	77 0.0000 0.0048 0.0020 0.001
36 Base Case (NP20) R503 Unfrested 21.02 6.54 111 0.10 1122 0.0171 0.0228 0.0254 27.2 0.00007 5.5 0.00043 0.00045 0.0071 1.33 0.25 0.97 0.00017 13.9 10.5 0.02 0.0138 2.42 31.0 0.00051 0.00045 0.00494 0.00387 33 0.62 0.00021 1.35 6Base Case (NP20) R503 Unfrested 14.56 6.56 114 0.09 115.7 0.015 0.015 0.023 0.0255 28.0 0.00007 5.7 0.0003 0.00045 0.0071 1.33 0.25 0.39 0.00017 13.5 10.8 0.02 0.0131 2.25 31.7 0.0005 0.00043 0.0446 0.00384 33 0.62 0.00021 1.35 0.00017 0.00017 0.0001	25 0.0000 0.0055 0.0024 0.001
37 Base Case (NP20) R503 Unfrested 14.68 6.69 115 0.08 119.3 0.0159 0.0221 0.0257 28.2 0.00007 5.7 0.00039 0.00045 0.00071 1.33 0.24 0.84 0.00017 12.1 10.8 0.02 0.019 2.01 3.1 0.00050 0.00041 0.04266 0.00359 29 0.55 0.0002 1.3 38 Base Case (NP20) R503 Unfrested 21.17 6.59 105 0.08 108.0 0.0165 0.0165 0.0243 26.1 0.00007 5.2 0.00007 0.00045 0.00072 1.40 0.21 0.80 0.00017 10.6 9.7 0.01 0.0199 2.05 27.2 0.00050 0.00041 0.04266 0.00359 29 0.55 0.0002 1.3 39 Base Case (NP20) R503 Unfrested 21.17 6.59 107 0.08 109.2 0.0165 0.0243 26.5 0.00007 5.2 0.00036 0.00045 0.00072 1.40 0.22 0.83 0.00017 11.2 9.9 0.01 0.0111 2.09 28.0 0.00050 0.00041 0.03884 0.00337 28 0.54 0.0002 1.3	74 0.0000 0.0049 0.0022 0.001 63 0.0000 0.0047 0.0021 0.001
38 Base Case (NP20) RS03 Untreated 18.61 6.59 105 0.08 108.0 0.0165 0.0197 0.0243 26.1 0.00007 5.1 0.00007 5.1 0.00007 0.0007 10.6 0.02 1.3 0.00017 10.6 9.7 0.01 0.0109 2.05 27.2 0.00050 0.00040 0.05005 0.00042 29 0.51 0.00007 1.0 0.0007 1.0	57 0.0000 0.0047 0.0021 0.001
39 Base Case (NP20) RS03 Untreated 21.17 6.59 107 0.08 109.2 0.0162 0.0204 0.0243 26.5 0.00007 5.2 0.00036 0.00045 0.00072 1.40 0.22 0.83 0.00017 11.2 9.9 0.01 0.0111 2.09 28.0 0.00050 0.00041 0.03884 0.00337 28 0.54 0.0002 1.30	61 0.0000 0.0040 0.0017 0.001
	08 0.0000 0.0040 0.0018 0.001 45 0.0000 0.0041 0.0017 0.001
	41 0.0000 0.0049 0.0022 0.001
42 Base Case (NP20) RS03 Unitreated 21.51 6.60 104 0.08 105.6 0.0163 0.0202 0.0205 25.8 0.00007 5.0 0.00007 0.00007 11.3 9.6 0.01 0.0114 2.06 27.2 0.00050 0.00040 0.03967 0.00338 29 0.56 0.0002 1.4	32 0.0000 0.0042 0.0018 0.001
43 Base Case (NP20) RS03 Untreated 14.39 6.51 115 0.10 115.3 0.0177 0.0238 0.0250 27.9 0.00007 5.6 0.000045 0.000075 1.32 0.25 1.03 0.00016 13.4 10.9 0.02 0.0131 2.62 30.7 0.00049 0.00047 0.04656 0.00368 33 0.63 0.0002 1.2	81 0.0000 0.0048 0.0020 0.001
	77 0.0000 0.0043 0.0018 0.001 11 0.0000 0.0049 0.0022 0.001
46 Base Case (NP20) RS03 Unfreated 21.08 6.55 101 0.09 101.4 0.0175 0.0199 0.0233 25.0 0.00007 4.8 0.00007 0.0004 0.00074 1.41 0.20 0.88 0.00017 10.7 9.4 0.01 0.0110 2.31 25.5 0.00050 0.00043 0.03569 0.00315 30 0.53 0.0002 1.3	96 0.0000 0.0041 0.0017 0.001
	75 0.0000 0.0041 0.0018 0.001
	53 0.0000 0.0042 0.0018 0.001 62 0.0000 0.0042 0.0017 0.001
50 Base Case (NP20) RS03 Untreated 16.92 6.54 106 0.09 105.8 0.0173 0.0217 0.0234 26.0 0.00007 5.1 0.00031 0.00044 0.00074 1.38 0.22 0.95 0.00016 11.8 9.9 0.01 0.0116 2.38 27.3 0.00049 0.00049 0.00044 0.04051 0.00338 31 0.60 0.0002 1.3	02 0.0000 0.0043 0.0018 0.001
	24 0.0000 0.0041 0.0017 0.001 91 0.0000 0.0041 0.0017 0.001
	64 0.0000 0.0040 0.0017 0.001
54 Base Case (NP20) RS03 Untreated 19.75 6.56 102 0.09 102.8 0.0971 0.0203 0.0228 25.4 0.00007 4.8 0.00028 0.00044 0.00074 1.44 0.20 0.89 0.00017 10.5 9.4 0.01 0.0104 2.28 25.3 0.00049 0.00042 0.03482 0.00310 29 0.55 0.0002 1.4	58 0.0000 0.0039 0.0016 0.001
55 Base Case (NP20) RS03 Uniresited 16.93 6.54 106 0.09 106.7 0.0173 0.0217 0.0212 0.023 25.8 0.00027 13.0 0.0024 0.00027 13.0 0.00024	67 0.0000 0.0040 0.0017 0.001 00 0.0000 0.0040 0.0017 0.001
	65 0.0000 0.0040 0.0017 0.001
	43 0.0000 0.0042 0.0018 0.001
	53 0.0000 0.0040 0.0016 0.001 40 0.0000 0.0042 0.0018 0.001
61 Base Case (NP20) RS03 Universited 16.03 6.54 112 0.10 113.5 0.0169 0.0234 0.0239 27.4 0.00007 5.4 0.00007 5.4 0.00007 11.3 0.22 0.99 0.00017 11.3 10.7 0.01 0.0104 2.38 28.4 0.00048 0.00045 0.03779 0.00327 29 0.60 0.0002 1.2	93 0.0000 0.0039 0.0017 0.001
62 Base Case (NP20) RS03 Untreated 12.19 6.56 120 0.09 125.1 0.0164 0.0244 0.0253 29.3 0.00007 6.0 0.00027 0.00046 0.00071 1.25 0.22 0.94 0.00017 11.1 11.5 0.01 0.0103 2.14 30.8 0.00047 0.00047 0.00044 0.03706 0.00328 29 0.59 0.0002 1.2	92 0.0000 0.0039 0.0017 0.001 61 0.0000 0.0035 0.0014 0.001
	55 0.0000 0.0034 0.0015 0.001
65 Base Case (NP20) RS03 Untreated 19.66 6.54 100 0.09 99.3 0.0174 0.0199 0.0222 24.7 0.00007 4.7 0.00025 0.00044 0.00075 1.43 0.18 0.91 0.00016 9.5 9.2 0.01 0.0003 2.36 23.5 0.00049 0.00043 0.0299 0.00284 28 0.53 0.0002 1.4	04 0.0000 0.0036 0.0015 0.001
66 Base Case (NP20) RS03 Untreated 15.88 6.55 111 0.09 112.3 0.0168 0.0228 0.0236 27.2 0.00007 5.3 0.00026 0.00045 0.00073 1.35 0.21 0.96 0.00017 10.7 10.4 0.01 0.0100 2.27 27.4 0.00048 0.00048 0.00048 0.00048 0.0002	82 0.0000 0.0038 0.0017 0.001 05 0.0000 0.0035 0.0015 0.001
	76 0.0000 0.0035 0.0015 0.001
69 Base Case (NP20) RS03 Untreated 10.61 6.54 122 0.09 125.9 0.0165 0.0250 0.0251 2.96 0.00007 6.0 0.00025 0.00046 0.00073 1.27 0.22 0.98 0.00017 10.8 11.6 0.01 0.0098 2.26 30.5 0.00047 0.00045 0.03549 0.00319 28 0.60 0.0002 1.2	33 0.0000 0.0038 0.0017 0.001
To Base Case (NP20) RS03 Untreated 17.26 6.59 110 0.08 113.8 0.0163 0.0211 0.0209 27.1 0.00007 5.3 0.00024 0.00046 0.00071 1.35 0.18 0.83 0.00017 8.8 10.2 0.01 0.0083 2.01 26.3 0.00048 0.00041 0.02736 0.00280 26 0.50 0.0002 1.35 0.00024 0.00041 0.00071 1.35 0.18 0.83 0.00017 8.8 10.2 0.01 0.0083 2.01 26.3 0.00048 0.00041 0.02736 0.00280 26 0.50 0.0002 1.35 0.00048 0.00041 0.00071	20 0.0000 0.0033 0.0014 0.001 46 0.0000 0.0033 0.0013 0.001
	46 0.0000 0.0033 0.0013 0.001 53 0.0000 0.0038 0.0016 0.001
73 Base Case (NP20) RS03 Unireated 17.65 6.57 109 0.09 111.8 0.0169 0.0217 0.0236 26.8 0.00027 5.2 0.00024 0.00045 0.00072 1.36 0.19 0.89 0.00017 9.2 10.2 0.01 0.0088 2.13 26.1 0.00048 0.00042 0.02896 0.00285 27 0.54 0.0002 1.3	03 0.0000 0.0034 0.0014 0.001
	26 0.0000 0.0035 0.0014 0.001 86 0.0000 0.0033 0.0014 0.001
	79 0.0000 0.0030 0.0014 0.001
77 Base Case (NP20) RS03 Unireated 23.27 6.56 99 0.09 99.6 0.0170 0.0190 0.022 24.7 0.00007 4.6 0.00022 0.00044 0.00074 1.45 0.16 0.85 0.00017 8.0 9.1 0.01 0.0078 2.24 22.1 0.00049 0.00042 0.02346 0.00252 25 0.49 0.0002 1.4	94 0.0000 0.0031 0.0012 0.001
	54 0.0000 0.0032 0.0013 0.001 00 0.0000 0.0036 0.0015 0.001
80 Base Case (NP20) RS03 Unireated 18.30 6.56 105 0.09 106.1 0.0171 0.0218 0.0228 2.58 0.00007 4.9 0.00023 0.00044 0.00073 1.38 0.18 0.19 0.00017 8.8 9.7 0.01 0.0085 2.23 24.3 0.0048 0.00043 0.02712 0.00272 27 0.54 0.0002 1.3	34 0.0000 0.0033 0.0014 0.001
81 Base Case (NP20) RS03 Unireated 18.55 6.52 105 0.10 104.7 0.0177 0.0216 0.0226 25.8 0.00007 4.9 0.00023 0.00044 0.00075 1.38 0.18 0.98 0.00016 9.2 9.8 0.01 0.0087 2.49 24.1 0.00048 0.00045 0.02772 0.00271 28 0.56 0.0002 1.3	03 0.0000 0.0034 0.0014 0.001
	02 0.0000 0.0034 0.0014 0.001 85 0.0000 0.0034 0.0014 0.001
84 Base Case (NP20) RS03 Unirested 22.28 6.57 102 0.09 102.9 0.0165 0.0202 0.022 25.3 0.00007 4.7 0.00022 0.00044 0.00073 1.43 0.17 0.87 0.00017 8.3 9.4 0.01 0.0077 2.14 23.1 0.00048 0.00041 0.02481 0.00261 24 0.52 0.0002 1.4	22 0.0000 0.0030 0.0013 0.001
85 Base Case (NP20) RS03 Unirested 32.87 6.58 94 0.08 94.0 0.0173 0.0182 0.0212 23.8 0.00007 4.2 0.00021 0.00043 0.00075 1.52 0.16 0.84 0.00016 7.77 8.5 0.01 0.0000 2.18 20.4 0.00049 0.00049 0.00243 26 0.50 0.0002 1.4	41 0.0000 0.0031 0.0012 0.001
	96 0.0000 0.0036 0.0015 0.001 87 0.0000 0.0032 0.0013 0.001
88 Base Case (NP20) RS03 Untreated 19.56 6.56 101 0.09 101.6 0.0168 0.0204 0.0220 25.1 0.00007 4.7 0.00021 0.00074 1.43 0.017 0.90 0.00016 8.3 9.3 0.01 0.0078 2.22 22.7 0.00048 0.00042 0.02472 0.00258 25 0.53 0.0002 1.4	24 0.0000 0.0031 0.0013 0.001
	73 0.0000 0.0032 0.0013 0.001

Year	Scenario	Station	Flow Rate	pН	Hardness (mg	Acidity (mg	Alkalinity (mg	Al	As	B (mg/L)	Ca	Cd	CI	Co	Cr	Cu	DOC	F	Fe	Hg	К (Mg	Mn		NO3-N	Na	NI (man)	Pb	Sb	Se	SO4	Sr			CN	U	V Zn
			(L/6)	ľ	CaCO3/L)	CaCO3/L)	CaCO3/L)	(mg/L)	(mg/L)			(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)			mg/L)		(mg/L)	$\overline{}$				(mg/L)		(mg/L)		(mg/L)	(mg/L) (mg/L) (ng/L) (mg/l
	Base Case (NP20) Base Case (NP20)	RS03 Untreated RS03 Untreated	21.95	6.58	101	0.08		0.0168	0.0197	0.0222	25.2	0.00007			0.00044	0.00073	1.43			0.00017	7.6 8.5		0.01 0		2.14		0.00048		0.02192		25 25		0.0002 1				.0012 0.00 .0013 0.00
92	Base Case (NP20)	RS03 Untreated		6.54					0.0238			0.00007				0.00072				0.00017	8.7	11.0	0.01 0	.0080	2.23		0.00047					0.53	0.0002 1	1.2624 (0.0000	0.0032	.0013 0.00
93	Base Case (NP20) Base Case (NP20)	RS03 Untreated RS03 Untreated	13.89 22.05	6.58	116	0.09			0.0230		28.3	0.00007				0.00071			0.88	0.00017	8.1 7.3	11.0	0.01 0	0075	2.03	27.2	0.00047	0.00042	0.02347	0.00261	25	0.49	0.0002 1	1.2588 0	0.0000 0	0.0031 0	.0012 0.00 .0011 0.00
95	Base Case (NP20)	RS03 Untreated	23.39	6.56	102	0.09	103.1	0.0169	0.0207	0.0222	25.4	0.00007	4.7	0.00021	0.00044	0.00074	1.43	0.16	0.91	0.00017	8.0	9.5	0.01 0	.0075	2.22	22.7	0.00048	0.00042	0.02319	0.00251	25	0.50	0.0002 1	1.4068 0	0.0000	0.0030	.0012 0.00
96	Base Case (NP20)	RS03 Untreated RS03 Untreated	19.21	6.59 6.58	106	0.08			0.0210		26.4 26.2					0.00073				0.00017	7.8				2.04	23.7	0.00048	0.00041	0.02288	0.00251	24						.0012 0.00 .0012 0.00
98	Base Case (NP20) Base Case (NP20)	RS03 Untreated		6.53	111	0.09			0.0226		27.2	0.00007	5.2	0.00021	0.00044	0.00074	1.35		0.96	0.00017	8.3				2.35	24.9	0.00048	0.00044	0.02348	0.00254	25	0.50	0.0002 1	1.3348 (0.0000	0.0030	.0012 0.00
99	Base Case (NP20)	RS03 Untreated RS03 Untreated	15.49 28.74	6.57	111				0.0222		27.4 25.3					0.00072	1.33			0.00017	7.8 6.9		0.01 0		2.11		0.00047										.0012 0.00 .0011 0.00
101	Base Case (NP20) Base Case (NP20)	RS03 Untreated	15.05	6.52	111	0.10	110.9	0.0175	0.0233	0.0229	27.1	0.00007	5.2	0.00021	0.00043	0.00076	1.36	0.17	1.04	0.00016	8.6	10.5	0.01 0	.0076	2.60	24.5	0.00048	0.00046	0.02442	0.00254	26	0.52	0.0002 1	1.3444 (0.0000	0.0031	.0013 0.00
102	Base Case (NP20)	RS03 Untreated RS03 Untreated		6.53 6.49		0.09			0.0221		26.4	0.00007				0.00074		0.16 0.17		0.00017	7.9 8.6	10.1 10.6		.0076	2.33	24.0	0.00048	0.00044	0.02227	0.00246	26 28						.0012 0.00 .0012 0.00
104	Base Case (NP20) Base Case (NP20)	RS03 Untreated	16.55		110	0.10			0.0232	0.0235	26.8		5.2			0.00073	1.31			0.00017	8.2	10.4	0.01 0		2.44		0.00047		0.02399		27	0.49	0.0002 1	1.2910 (0.0000	0.0032	.0012 0.00
	Base Case (NP20)	RS03 Untreated RS03 Untreated	24.10 16.37		103				0.0207		25.5 26.0	0.00007				0.00074		0.15		0.00017	7.3		0.01 0		2.22		0.00048										.0011 0.00
	Base Case (NP20) Base Case (NP20)	RS03 Untreated			105	0.09				0.0227		0.00007			0.00044		1.40			0.00017	7.3	9.7	0.01 0		2.18				0.02077		24						.0011 0.00 .0011 0.00
	Base Case (NP20) Base Case (NP20)	RS03 Untreated		6.53	108	0.10			0.0220		26.5		5.0 5.0		0.00044		1.38	0.16 0.16		0.00017	7.7		0.01 0		2.40		0.00048				25						.0011 0.00 .0011 0.00
	Base Case (NP20)	RS03 Untreated RS03 Untreated	12.35		117				0.0237		26.4				0.00045	0.00072				0.00017	7.7	9.9	0.01 0		2.09		0.00048				25						.0012 0.00
	Base Case (NP20) Base Case (NP20)	RS03 Untreated RS03 Untreated	17.09 15.56	6.55	109	0.09	112.3 113.8		0.0217	0.0237	26.8	0.00007	5.2 5.3		0.00045	0.00073	1.33	0.15 0.16		0.00017	7.0	10.3	0.01 0				0.00048		0.01822		25						.0010 0.00 ⁻
113	Base Case (NP20)	RS03 Untreated	24.20	6.55		0.09	101.9	0.0170	0.0202	0.0221	25.1	0.00007	4.7	0.00021	0.00044	0.00074	1.42	0.15	0.90	0.00017	6.9	9.4	0.01 0	.0064	2.45 2.28	21.4	0.00048	0.00043	0.01779	0.00224	24	0.42	0.0002 1	1.3977 (0.0000	0.0026	.0010 0.00
114	Base Case (NP20) Base Case (NP20)	RS03 Untreated RS03 Untreated	22.85 17.14	6.56	98	0.09	98.3		0.0196		24.5		4.4	0.00020		0.00074	1.46			0.00016	6.8 8.0		0.01 0		2.24	20.4	0.00048	0.00042	0.01783	0.00221	25	0.42	0.0002 1	1.4383 (0.0000	0.0028	.0010 0.00 .0012 0.00
116	Base Case (NP20)	RS03 Untreated	18.65	6.56	110	0.09	112.6	0.0168	0.0228	0.0232	27.1	0.00007	5.2	0.00021	0.00044	0.00073	1.34	0.16	0.95	0.00017	7.5	10.4	0.01 0	.0066		24.1	0.00047	0.00044	0.02003	0.00236		0.45	0.0002 1	1.3269 0	0.0000	0.0028	.0011 0.00
117	Base Case (NP20) Base Case (NP20)	RS03 Untreated RS03 Untreated		6.58		0.09			0.0223			0.00007				0.00073	1.35			0.00017	7.1 6.5		0.01 0		2.13		0.00047				23						.0011 0.00 .0010 0.00
119	Base Case (NP20)	RS03 Untreated	19.12	6.57	105	0.09	107.0	0.0167	0.0210	0.0226	26.0	0.00007	4.9	0.00020	0.00044	0.00073	1.40	0.15	0.89	0.00017	6.8		0.01 0	.0062	2.17	22.4	0.00048	0.00042	0.01753	0.00224	23	0.41	0.0002 1	1.3797 (0.0000	0.0026	.0010 0.00
120	Base Case (NP20)	RS03 Untreated RS03 Untreated	20.08	6.55	102	0.09			0.0204		25.3 26.9	0.00007	4.7	0.00020	0.00044	0.00074	1.42	0.14	0.90	0.00017	6.7 7.0	9.4	0.01 0	0062	2.29	21.3	0.00048				24	0.41	0.0002 1	1.4031 0	0.0000.0	0.0026 0	.0010 0.00 .0011 0.00
122	Base Case (NP20) Base Case (NP20)	RS03 Untreated	18.74	6.58	107	0.09	109.4	0.0166	0.0211	0.0229	26.4	0.00007	5.0	0.00020	0.00044	0.00073	1.39		0.87	0.00017	6.6	9.9	0.01 0	.0061	2.12	22.8	0.00048	0.00042	0.01674	0.00221	23	0.40	0.0002 1	1.3710 (0.0000	0.0026	.0010 0.00
123	Base Case (NP20)	RS03 Untreated RS03 Untreated		6.57	105	0.09			0.0207		25.9 27.7				0.00044		1.41	0.14 0.15		0.00017	6.5 6.8		0.01 0		2.22		0.00048				23						.0010 0.00
125	Base Case (NP20) Base Case (NP20)	RS03 Untreated	21.05	6.56	102	0.09	102.8	0.0171	0.0200	0.0223	25.2	0.00007	4.7	0.00020	0.00044	0.00074	1.42	0.14	0.88	0.00017	6.3	9.4	0.01 0	.0060	2.27	21.0	0.00048	0.00043	0.01507	0.00210	23	0.38	0.0002 1	1.3951 (0.0000	0.0025	.0009 0.00
126	Base Case (NP20)	RS03 Untreated RS03 Untreated	22.20 21.16	6.53					0.0197		24.2					0.00075		0.14		0.00016	6.5 7.2		0.01 0 0.01 0		2.42		0.00049										.0009 0.00 .0010 0.00
128	Base Case (NP20) Base Case (NP20)	RS03 Untreated		6.53					0.0224		26.3	0.00007				0.00073				0.00017	7.0						0.00048										.0010 0.00
129	Base Case (NP20)	RS03 Untreated		6.55					0.0224			0.00007				0.00073	1.34			0.00017	6.8 6.1				2.24		0.00047				23						.0010 0.00
	Base Case (NP20) Base Case (NP20)	RS03 Untreated RS03 Untreated	18.49 20.66	6.57	102	0.09	104.3	0.0168	0.0201	0.0224	25.4 25.3	0.00007			0.00044		1.41			0.00017	6.2	9.4	0.01 0		2.12		0.00048		0.01462		24		0.0002 1				.0009 0.00
132	Base Case (NP20) Base Case (NP20)	RS03 Untreated RS03 Untreated	20.49 21.17	6.54	101	0.09			0.0207		25.1	0.00007	4.6	0.00020	0.00043	0.00075	1.42	0.14	0.93	0.00016	6.5 6.6		0.01 0		2.39	20.7	0.00048	0.00044	0.01545	0.00209	24	0.39	0.0002 1	1.3953 (0.0000	0.0026	.0009 0.00 .0009 0.00
	Base Case (NP20)	RS03 Untreated		6.50	110				0.0240			0.00007				0.00076	1.33			0.00016	7.4		0.01 0		2.55		0.00048				26						.0010 0.00
	Base Case (NP20) Base Case (NP20)	RS03 Untreated RS03 Untreated	21.53 14.87	6.54	109	0.10	110.6 115.1		0.0228	0.0231		0.00007	5.1 5.3		0.00044	0.00074	1.34			0.00017	6.8	10.3	0.01 0		2.36		0.00048		0.01652		24						.0010 0.00
	Base Case (NP20)	RS03 Untreated	14.97	6.59	113	0.08			0.0229		27.6 27.8	0.00007	5.3	0.00021	0.00045	0.00071				0.00017	6.0	10.5		.0052			0.00047				22		0.0002 1	1.3263	0.0000	0.0024 0	.0010 0.00° .0009 0.00°
	Base Case (NP20) Base Case (NP20)	RS03 Untreated RS03 Untreated	19.03 21.62		103	0.08			0.0196		25.7 26.1					0.00072	1.41			0.00017	5.5 5.8		0.01 0		2.01		0.00048				22						0.00 0.00
140	Base Case (NP20)	RS03 Untreated	26.78	6.55	94	0.09	93.1	0.0176	0.0184	0.0211	23.6	0.00007	4.2	0.00020	0.00043	0.00075	1.50	0.12	0.87	0.00016	5.7	8.5	0.01 0	.0058	2.36	18.2	0.00049	0.00042	0.01254	0.00192	23	0.35	0.0002 1	1.4715 (0.0000	0.0024	.0008 0.00
	Base Case (NP20)	RS03 Untreated RS03 Untreated	17.08 21.92	6.54	108	0.10	109.0		0.0231		26.7	0.00007				0.00075	1.39		1.01	0.00016	6.9 5.8	10.1	0.01 0	0060	2.37	22.3	0.00047	0.00044	0.01683	0.00216	24						.0010 0.00
143	Base Case (NP20) Base Case (NP20)	RS03 Untreated	14.61	6.51	113	0.10	113.9	0.0178	0.0238	0.0234	27.5	0.00007	5.2	0.00021	0.00044	0.00075	1.32	0.15	1.03	0.00016	6.8	10.7	0.01 0	.0061	2.58	23.4	0.00047	0.00047	0.01576	0.00211		0.39	0.0002 1	1.3054 (0.0000	0.0026	.0009 0.00
144	Base Case (NP20) Base Case (NP20)	RS03 Untreated RS03 Untreated	18.82	6.52	103	0.10			0.0214		25.3 28.7	0.00007	4.7	0.00020	0.00044	0.00075	1.37			0.00016	6.3	9.6	0.01 0		2.48	20.9	0.00048	0.00045	0.01402	0.00203	24						.0009 0.00 .0010 0.00
146	Base Case (NP20)	RS03 Untreated	21.40	6.55	99	0.09	100.3	0.0176	0.0198	0.0222	24.7	0.00007	4.5	0.00020	0.00044	0.00074	1.41		0.88	0.00017	5.7			.0057	2.28	20.0	0.00048	0.00043	0.01248	0.00196		0.34	0.0002 1	1.3852 (0.0000	0.0024	.0008 0.00
147	Base Case (NP20) Base Case (NP20)	RS03 Untreated RS03 Untreated	21.94 18.37		104				0.0211		25.8 25.4					0.00074		0.14		0.00017	6.0		0.01 0		2.18		0.00048										.0009 0.00
149	Base Case (NP20)	RS03 Untreated	20.92	6.55	99	0.09	100.0	0.0175	0.0202	0.0220	24.7	0.00007	4.5	0.00020	0.00043	0.00074	1.43	0.13	0.90	0.00016	5.8	9.2	0.01 0	.0058	2.26	19.9	0.00048	0.00042	0.01298	0.00197	24	0.35	0.0002 1	1.4010 (0.0000	0.0025	.0009 0.00
150	Base Case (NP20) Base Case (NP20)	RS03 Untreated RS03 Untreated	17.11	6.54 6.56	104	0.09		0.0173	0.0217	0.0224	25.7 25.5	0.00007			0.00044	0.00074		0.14		0.00016	6.2 5.9		0.01 0		2.35	21.1	0.00048	0.00044	0.01385	0.00202	23	0.36	0.0002 1	1.3651 0	0.0000.0	0.0024 0	0.00 0.00
152	Base Case (NP20)	RS03 Untreated	21.76	6.56	102	0.09	102.7	0.0171	0.0206	0.0220	25.3	0.00007	4.6	0.00020	0.00043	0.00074	1.44	0.13	0.90	0.00016	5.8	9.4	0.01 0	.0056	2.24	20.3	0.00048	0.00042	0.01284	0.00196	23	0.35	0.0002 1	1.4132 (0.0000	0.0024	.0009 0.00
153	Base Case (NP20)	RS03 Untreated RS03 Untreated	20.80	6.57					0.0206		25.5	0.00007				0.00074 0.00074		0.13		0.00017	5.7 5.7		0.01 0 0.01 0				0.00048										.0008 0.00 .0008 0.00
155	Base Case (NP20) Base Case (NP20)	RS03 Untreated	17.06	6.54	105	0.09	105.9	0.0173	0.0216	0.0226	25.9	0.00007	4.8	0.00020	0.00044	0.00074	1.39	0.13	0.95	0.00017	6.0	9.8	0.01 0	.0054	2.36	21.1	0.00048	0.00044	0.01287	0.00198	23	0.34	0.0002 1	1.3698	0.0000	0.0024	.0009 0.00
	Base Case (NP20) Base Case (NP20)	RS03 Untreated RS03 Untreated		6.55 6.53					0.0212		25.6 25.4				0.00044	0.00075	1.40			0.00017	5.9 5.9	9.6 9.5	0.01 0		2.37		0.00048				23						.0008 0.00
158	Base Case (NP20)	RS03 Untreated	16.51	6.51	107	0.10	107.4	0.0177	0.0229	0.0228	26.3	0.00007	4.9	0.00020	0.00044	0.00075	1.35	0.14	1.02	0.00016	6.3	10.1	0.01 0	.0055	2.52	21.6	0.00048	0.00046	0.01349	0.00200	24	0.35	0.0002 1	1.3366 (0.0000	0.0024	.0009 0.00
	Base Case (NP20) Base Case (NP20)	RS03 Untreated RS03 Untreated	22.81 15.32	6.54	103 108	0.09	103.9 109.0		0.0213	0.0224	25.5 26.5	0.00007	4.7 5.0		0.00044	0.00075	1.40	0.13		0.00017	5.8 6.3	9.6	0.01 0		2.34 2.50		0.00048			0.00195	24		0.0002 1 0.0002 1				.0008 0.00
161	Base Case (NP20)	RS03 Untreated	16.09	6.54	111	0.10	112.8	0.0169	0.0234	0.0232	27.1	0.00007	5.2	0.00020	0.00044	0.00073	1.31	0.14	0.99	0.00017	6.1	10.5	0.01 0	.0050	2.36	22.7	0.00047	0.00045	0.01295	0.00200	22	0.34	0.0002 1	1.3006 (0.0000	0.0022	.0009 0.00
	Base Case (NP20) Base Case (NP20)	RS03 Untreated RS03 Untreated	12.21 20.91	6.56	119	0.09			0.0244		29.0 26.8	0.00007			0.00045		1.25			0.00017	5.9 5.2	11.3	0.01 0		2.12		0.00046				22						.0009 0.00 .0008 0.00
164	Base Case (NP20)	RS03 Untreated	19.00	6.55	106	0.09	106.6	0.0169	0.0212	0.0225	26.1	0.00007	4.8	0.00020	0.00044	0.00074	1.39	0.13	0.93	0.00017	5.6	9.8	0.01 0	.0046	2.38	20.9	0.00048	0.00044	0.01087	0.00189	21	0.32	0.0002 1	1.3759 (0.0000	0.0021	.0008 0.00
165	Base Case (NP20) Base Case (NP20)	RS03 Untreated RS03 Untreated	19.86 15.88	6.54	99	0.09			0.0199		24.6 27.0	0.00007				0.00075	1.43	0.12	0.91	0.00016	5.4 5.8	9.1	0.01 0	0052 0050	2.34	19.2	0.00048	0.00043	0.01074	0.00186	23	0.32	0.0002 1	1.4105 (0.0000.0	0.0023 0	.0008 0.00
167	Base Case (NP20)	RS03 Untreated	18.02	6.56	106	0.09	108.6	0.0167	0.0213	0.0229	26.2	0.00007	4.9	0.00020	0.00044	0.00073	1.38	0.13	0.89	0.00017	5.4	9.9	0.01 0	.0048	2.19	21.4	0.00048	0.00043	0.01075	0.00191	21	0.31	0.0002 1	1.3605 0	0.0000	0.0021	.0008 0.00
168	Base Case (NP20) Base Case (NP20)	RS03 Untreated RS03 Untreated	20.42 10.61	6.56	106	0.09			0.0214		26.2	0.00007			0.00044		1.38	0.13		0.00017	5.5 5.9	9.9	0.01 0	0048 0048	2.24		0.00048				21		0.0002 1				.0008 0.00
170	Base Case (NP20)	RS03 Untreated	17.26	6.59	109	0.08	113.4	0.0163	0.0211	0.0236	26.9	0.00007	5.1	0.00020	0.00045	0.00071	1.35	0.13	0.83	0.00017	5.1	10.1	0.01 0	.0045	2.00	22.4	0.00048	0.00041	0.00976	0.00191	21	0.29	0.0002 1	1.3320 (0.0000	0.0021	.0008 0.00
171	Base Case (NP20) Base Case (NP20)	RS03 Untreated RS03 Untreated		6.57		0.08			0.0194		25.0 27.3				0.00044		1.44			0.00017	5.0		0.01 0		2.14		0.00048										.0007 0.00 .0008 0.00
173	Base Case (NP20)	RS03 Untreated	17.65	6.57	108	0.09	111.4	0.0168	0.0217	0.0233	26.7	0.00007	5.0	0.00020	0.00045	0.00072	1.36	0.13	0.89	0.00017	5.3	10.1	0.01 0	.0049	2.12	22.0	0.00048	0.00042	0.01033	0.00190	22	0.30	0.0002 1	1.3403 (0.0000	0.0022	.0008 0.00
174	Base Case (NP20) Base Case (NP20)	RS03 Untreated RS03 Untreated	14.50 12.36	6.56 6.56	112 116					0.0239		0.00007	5.3	0.00020	0.00045	0.00073	1.33	0.13	0.91	0.00017 0.00017	5.4 5.4	10.6	0.01 0	0048	2.17	23.1	0.00047 0.00047	0.00043	0.01045	0.00191	22	0.30	0.0002 1	1.3126 0	0.0000 0	0.0022 0	.0008 0.00
113	Jac Case (NP20)	suo o . medied	12.00	0.00		0.05	120.7	5.5103	5.5252	5.5240	20.0		0.0		2.00040	2.00011		5.14	w. 21	3.00011	0.4	. 1.0	3.31 0		2.10	24.1				00130		U.23	0002	. 2000 1			

Year	Scenario	Station	Flow Rate (L/s)	рН	Hardness (mg CaCO3/L)	Acidity (mg CaCO3/L)	Alkalinity (mg CaCO3/L)	AI (mg/L)	As (mg/L)	B (mg/L)	Ca (mg/L)	Cd (mg/L)	CI (mg/L)	Co (mg/L)	Cr (mg/L)	Cu (mg/L)	DOC (mg/L)	F (mg/L)	Fe (mg/L)	Hg (mg/L)	K (mg/L)		Mn mg/L) (Na mg/L)	NI (mg/L)	Pb (mg/L)	Sb (mg/L)	Se (mg/L)	SO4 (mg/L)	Sr (mg/L)	TI (mg/L)	TOC (mg/L)	CN (mg/L)	U (mg/L)		Zn mg/L)
176 F	Base Case (NP20)	RS03 Untreated		6.62	108	0.08				0.0236		0.00007			0.00046					0.00018	4.7	- 1	0.01				0.00048			0.00187					0.0000			0.0016
177 E	Base Case (NP20)	RS03 Untreated	23.27	6.56	98	0.09	99.3	0.0170	0.0190	0.0218	24.6	0.00007	4.4	0.00020	0.00043	0.00074	1.45	0.12	0.85	0.00017	4.9	9.0	0.01	0.0046	2.23	18.9 (0.00048	0.00042				0.29	0.0002	1.4294	0.0000	0.0021	0.0007 0	
178	Base Case (NP20) Base Case (NP20)	RS03 Untreated RS03 Untreated	22.12 16.39	6.55	96 106	0.09			0.0192			0.00007			0.00043			0.12 0.13		0.00016	5.1 5.5		0.01	0.0049			0.00048								0.0000			
180 E	Base Case (NP20)	RS03 Untreated		6.56	104	0.09	105.7	0.0171	0.0211	0.0226		0.00007	4.7	0.00020	0.00044	0.00073	1.38	0.12		0.00017	5.2	9.7	0.01	0.0049	2.22		0.00048			0.00184		0.30			0.0000		0.0008	
181 E	Base Case (NP20) Base Case (NP20)	RS03 Untreated RS03 Untreated		6.52 6.55	104 102				0.0216			0.00007			0.00043		1.40	0.12 0.12		0.00016	5.5 5.3		0.01		2.48		0.00048								0.0000			
183 E	Base Case (NP20)	RS03 Untreated	17.56	6.53	105	0.10	105.9		0.0220		26.0	0.00007	4.8		0.00044		1.39			0.00016	5.5	9.8	0.01	0.0048	2.40		0.00048					0.31	0.0002	1.3685	0.0000	0.0022	0.0008 0	0.0015
184 E	Base Case (NP20) Base Case (NP20)	RS03 Untreated RS03 Untreated		6.57 6.58	101 94	0.09	93.7		0.0202			0.00007			0.00044		1.43	0.12 0.11		0.00017	5.0 4.8		0.01		2.13		0.00048								0.0000			
186 E	Base Case (NP20)	RS03 Untreated	16.91	6.54	107				0.0230		26.3	0.00007			0.00043		1.41			0.00016	5.7		0.01	0.0050	2.41		0.00047								0.0000			
187 E	Base Case (NP20) Base Case (NP20)	RS03 Untreated RS03 Untreated		6.56					0.0200			0.00007			0.00043		1.44	0.12 0.12		0.00016	5.0 5.0		0.01		2.20		0.00048								0.0000			
189 E	Base Case (NP20)	RS03 Untreated		6.56					0.0223			0.00007			0.00044		1.37	0.13		0.00017	5.3	10.1	0.01	0.0046	2.25	21.4	0.00047	0.00043	0.00968	0.00183	3 22	0.29	0.0002	1.3473	0.0000	0.0021	0.0007 0	0.0016
	Base Case (NP20) Base Case (NP20)	RS03 Untreated RS03 Untreated	21.95 14.21	6.58	101 107	0.08			0.0197 0.0221	0.0221		0.00007 0.00007			0.00044		1.43			0.00017	4.8 5.3		0.01		2.13		0.00048								0.0000			
192 E	Base Case (NP20)	RS03 Untreated	12.97	6.54	115	0.09	119.5	0.0169	0.0238	0.0242	28.1	0.00007	5.4	0.00021	0.00045	0.00072	1.28	0.13	0.95	0.00017	5.3	10.9	0.01	0.0046	2.22	23.7 (0.00047	0.00044	0.00978	0.00187	7 22	0.29	0.0002	1.2624	0.0000	0.0022	0.0008 0	0.0016
	Base Case (NP20) Base Case (NP20)	RS03 Untreated RS03 Untreated	13.89	6.58	115 99				0.0230			0.00007			0.00046		1.28	0.13		0.00017	5.0 4.8		0.01		2.03		0.00047								0.0000			
195 E	Base Case (NP20)	RS03 Untreated	23.39	6.56	102	0.09	102.7	0.0169	0.0207	0.0221	25.3	0.00007	4.6	0.00020	0.00044	0.00074	1.43	0.12	0.91	0.00017	5.1	9.4	0.01	0.0046	2.21	19.6	0.00048	0.00042	0.00917	0.00180	21	0.29	0.0002	1.4068	0.0000	0.0021	0.0007 0	0.0015
	Base Case (NP20) Base Case (NP20)	RS03 Untreated RS03 Untreated		6.59	106 105	0.08		0.0164	0.0210	0.0226		0.00007			0.00044		1.43	0.12		0.00017	4.9	9.7	0.01	0.0045	2.04		0.00048			0.00181		0.29			0.0000		0.0007 0	
198 E	Base Case (NP20)	RS03 Untreated	13.90	6.53	110	0.09	112.4	0.0170	0.0226	0.0232	27.1	0.00007	5.1	0.00020	0.00044	0.00074	1.35	0.13	0.96	0.00017	5.3	10.4	0.01	0.0045	2.35	21.9 (0.00047	0.00044	0.00953	0.00183	3 22	0.29	0.0002	1.3348	0.0000	0.0021	0.0007 0	0.0016
	Base Case (NP20) Base Case (NP20)	RS03 Untreated RS03 Treated	15.49 23.45		111 77				0.0222			0.00007			0.00045		1.33			0.00017	5.0 3.7		0.01		2.10 0.01		0.00047								0.0000			
1 E	Base Case (NP20)	RS03 Treated	14.34	6.57	139	0.09	114.1	0.0028	0.0002	0.0318	39.5	0.00007	6.0	0.00002	0.00001	0.00011	1.31	0.27	0.01	0.00017	16.4	9.9	0.00	0.0004	0.03	35.7 (0.00001	0.00001	0.00118	0.00009	25	0.01	0.0002	1.2939	0.0000	0.0016	0.0003 0	0.0000
	Base Case (NP20) Base Case (NP20)	RS03 Treated RS03 Treated		6.56 6.50					0.0002			0.00007			0.00001		1.32	0.28		0.00017	17.1 19.5		0.00	0.0004 0.0005	0.03		0.00001								0.0000			
4 E	Base Case (NP20)	RS03 Treated	15.81	6.53	140		114.4	0.0030	0.0002	0.0329		0.00007			0.00001		1.29	0.31		0.00017	18.8		0.00	0.0004	0.03		0.00001					0.01	0.0002	1.2699	0.0000	0.0018	0.0003 0	0.0000
	Base Case (NP20) Base Case (NP20)	RS03 Treated RS03 Treated	22.92 15.66	6.57	131 134	0.09		0.0028	0.0002			0.00007	5.6 5.7		0.00001	0.00010	1.38	0.28		0.00017	16.6 17.2		0.00		0.02		0.00001			0.00009		0.01			0.0000			
7 E	Base Case (NP20)	RS03 Treated RS03 Treated		6.57	133	0.09			0.0002			0.00007			0.00001			0.28		0.00017	16.3 17.2		0.00	0.0004	0.02		0.00001								0.0000			
	Base Case (NP20) Base Case (NP20)	RS03 Treated RS03 Treated		6.58	137	0.09			0.0002			0.00007			0.00001					0.00017	17.2		0.00				0.00001								0.0000			
10 E	Base Case (NP20)	RS03 Treated		6.56					0.0002			0.00007	6.4	0.00002	0.00001	0.00010	1.27	0.31		0.00017			0.00				0.00001								0.0000			
	Base Case (NP20) Base Case (NP20)	RS03 Treated RS03 Treated	16.41 14.97	6.55 6.53	138 142	0.09 0.10			0.0002		39.3 40.1	0.00007	5.9 6.0	0.00001	0.00001	0.00010	1.31	0.28	0.01	0.00017	15.1 16.9		0.00	0.0003	0.02	36.0 (0.00001	0.00001	0.00110	0.00008	9 26	0.01	0.0002	1.2914	0.0000	0.0015	0.0002 0	.0000
13 E	Base Case (NP20)	RS03 Treated	23.17	6.56	129	0.09			0.0002		36.9	0.00007	5.3	0.00001	0.00001	0.00011	1.40	0.27	0.01	0.00017				0.0003	0.02	31.2	0.00001	0.00001	0.00108	0.00008	3 24	0.01	0.0002	1.3816	0.0000	0.0014	0.0002 0	0.0000
14 E	Base Case (NP20) Base Case (NP20)	RS03 Treated RS03 Treated		6.57		0.09			0.0002			0.00007			0.00001		1.45	0.27		0.00016	14.7		0.00		0.02		0.00001								0.0000			
16 E	Base Case (NP20)	RS03 Treated	17.93	6.56	140	0.09			0.0002		39.7	0.00007	5.9	0.00001	0.00001	0.00010	1.33	0.30	0.01	0.00017	16.5		0.00	0.0004	0.02		0.00001								0.0000			
	Base Case (NP20) Base Case (NP20)	RS03 Treated RS03 Treated	17.10 18.87	6.58	141 130	0.09			0.0002		37.3	0.00007 0.00007	5.9	0.00001	0.00001	0.00010	1.34	0.29		0.00017	15.5		0.00	0.0003	0.02		0.00001			0.00009					0.0000			
	Base Case (NP20)	RS03 Treated		6.57	133				0.0002		38.1	0.00007	5.5		0.00001		1.38			0.00017	14.6		0.00		0.02		0.00001			0.0000					0.0000			
	Base Case (NP20) Base Case (NP20)	RS03 Treated RS03 Treated		6.55	129 138				0.0002			0.00007			0.00001			0.26		0.00017	14.1 15.0		0.00		0.02		0.00001								0.0000			
	Base Case (NP20)	RS03 Treated	18.11	6.58	135	0.08	111.5	0.0027		0.0265		0.00007		0.00001		0.00010	1.37	0.26		0.00017	13.9		0.00	0.0003	0.02	31.5		0.00001	0.00101		3 23	0.01			0.0000		0.0002 0	
	Base Case (NP20) Base Case (NP20)	RS03 Treated RS03 Treated		6.57 6.58	132 142			0.0028	0.0002	0.0259		0.00007	5.3		0.00001		1.39	0.25		0.00017	13.5 14.6		0.00		0.02		0.00001			0.00008					0.0000			
		RS03 Treated RS03 Treated	20.36	6.56	128 123			0.0028	0.0002	0.0252		0.00007			0.00001		1.40	0.24		0.00017	12.7		0.00				0.00001			0.00007					0.0000			
27 E	Base Case (NP20) Base Case (NP20)	RS03 Treated	20.52	6.54	132	0.10	106.1	0.0029	0.0002	0.0255	37.6	0.00007	5.3	0.00001	0.00001	0.00011	1.38	0.27	0.01	0.00016	15.2	9.2	0.00	0.0003	0.03	31.1 (0.00001	0.00001	0.00111	0.00008	3 25	0.01	0.0002	1.3620	0.0000	0.0014	0.0002 0	0.0000
28 E	Base Case (NP20)	RS03 Treated RS03 Treated		6.54 6.56	135 138				0.0002			0.00007			0.00001		1.35	0.27		0.00017	14.8		0.00		0.02		0.00001								0.0000			
30 E	Base Case (NP20) Base Case (NP20)	RS03 Treated	17.98	6.58	129	0.08	106.0	0.0028	0.0002	0.0248	37.0	0.00007	5.2	0.00001	0.00001	0.00010	1.40	0.23	0.01	0.00017	12.3	8.9	0.00	0.0003	0.02	28.5 (0.00001	0.00001	0.00087	0.00007	7 21	0.01	0.0002	1.3750	0.0000	0.0012	0.0002 0	0.0000
31 E	Base Case (NP20) Base Case (NP20)	RS03 Treated RS03 Treated		6.57 6.54	128 128	0.09			0.0002			0.00007			0.00001		1.41	0.23		0.00017	12.4		0.00		0.02		0.00001			0.00007	7 22				0.0000			
33 E	Base Case (NP20)	RS03 Treated	20.61	6.53	126	0.10	100.1	0.0029	0.0002	0.0239	35.9	0.00007	4.9	0.00001	0.00001	0.00011	1.42	0.24	0.01	0.00016	13.3	8.7	0.00	0.0003	0.03	27.7 (0.00001	0.00001	0.00094	0.00007		0.01	0.0002	1.3977	0.0000	0.0012	0.0002 0	0.0000
34 E	Base Case (NP20) Base Case (NP20)	RS03 Treated RS03 Treated		6.50 6.54		0.10 0.10			0.0002			0.00007			0.00001			0.27 0.25		0.00016	15.3 13.9	9.9	0.00				0.00001								0.0000			
36 E	Base Case (NP20)	RS03 Treated	14.56	6.56	141	0.09	116.7	0.0027	0.0002	0.0255	40.1	0.00007	5.7	0.00001	0.00001	0.00010	1.33	0.25	0.01	0.00017	13.5	10.0	0.00	0.0003	0.02	31.7	0.00001	0.00001	0.00097	0.00008		0.01	0.0002	1.3163	0.0000	0.0012	0.0002 0	0.0000
37 E	Base Case (NP20) Base Case (NP20)	RS03 Treated RS03 Treated		6.60	142 130	0.08 0.08			0.0002		40.4 37.3	0.00007	5.7 5.1		0.00001		1.33	0.24	0.01	0.00017	12.1 10.6		0.00				0.00001			0.00007	7 21 5 20				0.0000			
39 E	Base Case (NP20)	RS03 Treated	21.17	6.59	132	0.08	109.2	0.0027	0.0002	0.0243	37.9	0.00007	5.2	0.00001	0.00001	0.00010	1.40	0.22	0.01	0.00017	11.2	9.1	0.00	0.0002	0.02	28.0	0.00001	0.00001	0.00078	0.00007	7 20	0.01	0.0002	1.3808	0.0000	0.0011	0.0002 0	0.0000
	Base Case (NP20) Base Case (NP20)	RS03 Treated RS03 Treated	26.22 16.77	6.55	118 136	0.09			0.0002	0.0225	34.3	0.00007	4.5 5.4		0.00001		1.49			0.00016	10.7		0.00		0.02		0.00001			0.00008					0.0000			
42 E	Base Case (NP20)	RS03 Treated	21.51	6.60	128	0.08	105.6	0.0027	0.0002	0.0236	36.9	0.00007	5.0	0.00001	0.00001	0.00010	1.42	0.22	0.01	0.00017	11.3	8.8	0.00	0.0002	0.02	27.2	0.00001	0.00001	0.00079	0.00007		0.01	0.0002	1.4032	0.0000	0.0011	0.0002 0	0.0000
	Base Case (NP20) Base Case (NP20)	RS03 Treated RS03 Treated	14.39 18.51	6.51	141 129	0.10 0.10	115.3 104.2	0.0030	0.0002	0.0250		0.00007	5.6 5.1	0.00001	0.00001	0.00011	1.32	0.25		0.00016	13.4	9.1	0.00		0.03	30.7 (27.3 (0.00001	0.00001	0.00093		7 23	0.01			0.0000			0.0000
45 E	Base Case (NP20)	RS03 Treated	13.04	6.53	148	0.10	122.3	0.0029	0.0003	0.0258	41.6	0.00007	6.0	0.00001	0.00001	0.00011	1.26	0.26	0.01	0.00017	13.9	10.6	0.00	0.0003	0.02	33.0 (0.00001	0.00001	0.00099	0.00008	3 23	0.01	0.0002	1.2411	0.0000	0.0013	0.0002 0	0.0000
	Base Case (NP20) Base Case (NP20)	RS03 Treated RS03 Treated	21.08 21.62	6.55	125 130	0.09			0.0002			0.00007 0.00007			0.00001		1.41			0.00017	10.7		0.00		0.02		0.00001			0.00007					0.0000			
48 E	Base Case (NP20)	RS03 Treated	18.13	6.54	128	0.09	103.8	0.0029	0.0002	0.0232	36.8	0.00007	5.0	0.00000	0.00001	0.00011	1.42	0.21	0.01	0.00016	11.4	8.9	0.00	0.0002	0.02	26.4	0.00001	0.00001	0.00077	0.00007	7 21	0.01	0.0002	1.3953	0.0000	0.0011	0.0002 0	0.0000
	Base Case (NP20) Base Case (NP20)	RS03 Treated RS03 Treated	20.66 16.92	6.55 6.54	125 130				0.0002			0.00007			0.00001			0.21 0.22		0.00016	11.8		0.00				0.00001								0.0000			
51 E	Base Case (NP20) Base Case (NP20)	RS03 Treated RS03 Treated	24.18	6.56 6.56	129 128	0.09			0.0002			0.00007 0.00007			0.00001		1.41	0.21 0.21		0.00017	11.1	8.9	0.00				0.00001								0.0000			
53 E	Base Case (NP20)	RS03 Treated	20.60	6.57	128	0.09	104.7	0.0028	0.0002	0.0230	36.9	0.00007	4.9	0.00000	0.00001	0.00011	1.43	0.21	0.01	0.00017	10.8	8.8	0.00	0.0002	0.02	26.0	0.00001	0.00001	0.00073	0.00006	5 20	0.01	0.0002	1.4064	0.0000	0.0010	0.0002 0	0.0000
54 E	Base Case (NP20)	RS03 Treated RS03 Treated	19.75	6.56	127				0.0002		36.4	0.00007	4.8		0.00001		1.44	0.20		0.00017	10.5	8.7	0.00	0.0002	0.02	25.3	0.00001	0.00001	0.00070	0.00006	5 20				0.0000			
56 E	Base Case (NP20) Base Case (NP20)	RS03 Treated	22.05	6.55	129	0.09	104.9	0.0029	0.0002	0.0232	37.0	0.00007	5.0	0.00000	0.00001	0.00011	1.40		0.01	0.00017	10.8	9.0	0.00		0.02	26.0 (0.00001	0.00001	0.00072	0.00006	5 21	0.01	0.0002	1.3800	0.0000	0.0010	0.0002 0	0.0000
57 E	Base Case (NP20)	RS03 Treated	18.28	6.53	128		103.7	0.0029	0.0002	0.0229	36.8	0.00007	4.9	0.00000	0.00001	0.00011	1.42	0.20	0.01	0.00016		8.9	0.00	0.0002	0.02	25.6	0.00001	0.00001	0.00071	0.00006	5 21	0.01	0.0002	1.3965	0.0000	0.0010	0.0002 0	0.0000
59 E	Base Case (NP20) Base Case (NP20)	RS03 Treated RS03 Treated	22.69	6.51 6.54	134 129		104.6	0.0029	0.0002 0.0002	0.0231	36.8	0.00007 0.00007	5.0	0.00000	0.00001 0.00001	0.00011		0.20	0.01	0.00016 0.00017	11.7 10.7	8.9	0.00	0.0002	0.02	25.8 (0.00001 0.00001	0.00001	0.00071	0.00006	5 21	0.01	0.0002	1.3753	0.0000	0.0010	0.0002 0	0.0000
60 E	Base Case (NP20)	RS03 Treated RS03 Treated		6.51 6.54					0.0002 0.0002			0.00007								0.00016 0.00017				0.0002 0.0002								0.01	0.0002	1.3240	0.0000	0.0011	0.0002 0	.0000
01	Base Case (NP20)	ouv meateu	10.03	0.04	130	0.10	110.5	0.0020	0.0002	0.0203	09.2	J.00001	3.4	J.00000	3.00001	3.00011	1.01	0.22	0.01	0.00017	11.0	3.0	0.00	U.000Z	0.02	20.4		J.00001	0.00076	0.0000	- 20	0.01	3.0002		0.0000	J. 00 10	E	.5000

Year	Scenario	Station	Flow Rate	pH	Hardness (mg	Acidity (mg	Alkalinity (mg	Al	As	B (mg/L)	Ca	Cd	CI	Co	Cr	Cu	DOC	F	Fe	Hg	K		Mn N			NI	Pb	Sb	Se			ті тос		U	V Z
			(L/s)	Ľ	CaCO3/L)	CaCO3/L)	CaCO3/L)	(mg/L)	(mg/L)		(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)		(mg/L)	(mg/L)			mg/L) (mg) (mg/L)		(mg/L)			g/L) (r			(mg/L)	(mg/L) (mg
	Base Case (NP20) Base Case (NP20)	RS03 Treated RS03 Treated	12.19 20.88	6.56	148	0.09			0.0002			0.00007			0.00001					0.00017	11.1 9.1		0.00 0.0			8 0.0000 6 0.0000	1 0.0000		4 0.0000 8 0.0000			.0002 1.239			0.0002 0.0
64	Base Case (NP20)	RS03 Treated	18.98	6.55	132	0.09	107.0	0.0028	0.0002	0.0230	37.6	0.00007	5.1	0.00000	0.00001	0.00011	1.39	0.19	0.01	0.00017	9.8	9.1	0.00 0.0	002 0.	12 25.4	4 0.0000	1 0.0000	0.0006	2 0.0000	19	0.01 0	.0002 1.375	5 0.0000	0.0009	0.0001 0.0
65	Base Case (NP20)	RS03 Treated RS03 Treated		6.54				0.0029	0.0002			0.00007			0.00001	0.00011		0.18 0.21		0.00016	9.5 10.7		0.00 0.0			5 0.0000 4 0.0000	1 0.0000		0.0000						0.0001 0.0
67	Base Case (NP20) Base Case (NP20)	RS03 Treated	18.02	6.56	132	0.09	109.0	0.0028	0.0002	0.0233	37.8	0.00007	5.1	0.00000	0.00001	0.00011	1.38	0.19	0.01	0.00017	9.6	9.2	0.00 0.0	002 0.	25.8	0.0000	1 0.0000	0.0006	1 0.0000	6 19	0.01 0	.0002 1.360	0.0000	0.0009	0.0001 0.0
68	Base Case (NP20)	RS03 Treated RS03 Treated		6.56					0.0002			0.00007			0.00001					0.00017	9.7 10.8		0.00 0.0		12 25.6	6 0.0000	1 0.0000	0.0006	2 0.0000	6 19					0.0001 0.0
70	Base Case (NP20) Base Case (NP20)	RS03 Treated RS03 Treated		6.54					0.0002			0.00007			0.00001			0.22		0.00017	10.8		0.00 0.0				1 0.0000								0.0002 0.0
71	Base Case (NP20)	RS03 Treated	23.94	6.57	125	0.08	102.4	0.0029	0.0002	0.0226	36.0	0.00007	4.7	0.00000	0.00001	0.00011	1.44	0.17	0.01	0.00017	8.4	8.5	0.00 0.0	002 0.	12 23.	3 0.0000	1 0.0000	0.0005	1 0.0000	15 19	0.01 0	.0002 1.414	6 0.0000	0.0009	0.0001 0.0
72	Base Case (NP20)	RS03 Treated RS03 Treated	13.25	6.53	138				0.0002			0.00007			0.00001					0.00017	10.3 9.2		0.00 0.0			3 0.0000	1 0.0000		6 0.0000						0.0002 0.0 0.0001 0.0
74	Base Case (NP20) Base Case (NP20)	RS03 Treated		6.56					0.0002			0.00007			0.00001			0.19		0.00017	9.4		0.00 0.0				1 0.0000								0.0001 0.0
75	Base Case (NP20)	RS03 Treated		6.56					0.0002			0.00007			0.00001		1.28	0.19		0.00017	9.3	10.2	0.00 0.0	002 0.	12 28.3	3 0.0000	1 0.0000	0.00058	0.0000	6 18	0.01 0	.0002 1.268	6 0.0000	0.0009	0.0001 0.0
	Base Case (NP20) Base Case (NP20)	RS03 Treated RS03 Treated		6.62					0.0002			0.00007			0.00001					0.00018	7.9 8.0	9.3 8.3	0.00 0.0	001 0			1 0.0000		8 0.0000 7 0.0000						0.0001 0.0
	Base Case (NP20)	RS03 Treated	22.12	6.56	123	0.09			0.0002			0.00007			0.00001			0.16	0.01	0.00017	8.5		0.00 0.0		12 21.8	0.0000 0.0000	1 0.0000		2 0.0000						0.0001 0.0
79	Base Case (NP20)	RS03 Treated	16.39	6.55	132	0.09	108.3	0.0029	0.0002	0.0229	37.7	0.00007	5.0	0.00000	0.00001	0.00011	1.38	0.19	0.01	0.00017	9.6	9.2	0.00 0.0	002 0.	12 25.3	3 0.0000	1 0.0000	0.0006	1 0.0000	6 19	0.01 0	.0002 1.360	0.0000	0.0009	0.0001 0.0
	Base Case (NP20) Base Case (NP20)	RS03 Treated RS03 Treated		6.56					0.0002			0.00007			0.00001			0.18		0.00017	8.8 9.2		0.00 0.0				1 0.0000								0.0001 0.0
	Base Case (NP20)	RS03 Treated		6.55					0.0002			0.00007			0.00001					0.00016	8.9		0.00 0.0			5 0.0000			5 0.0000			.0002 1.380			0.0001 0.0
83	Base Case (NP20)	RS03 Treated	17.56	6.53	131	0.10	106.3		0.0002		37.4	0.00007	5.0	0.00000	0.00001	0.00011	1.39	0.18		0.00016	9.3		0.00 0.0	002 0.	12 24.5	5 0.0000	1 0.0000								0.0001 0.0
	Base Case (NP20)	RS03 Treated RS03 Treated	22.28 32.87	6.57	126				0.0002			0.00007			0.00001					0.00017	8.3	8.6 7.8	0.00 0.0	002 0			1 0.0000		0.0000						0.0001 0.0
	Base Case (NP20)	RS03 Treated	16.91	6.54	133	0.10			0.0002		37.9	0.00007	5.0	0.00000	0.00001		1.41	0.19	0.01	0.00016	9.9	9.2	0.00 0.0	002 0.	12 24.9	9 0.0000	1 0.0000				0.01 0	.0002 1.389	6 0.0000	0.0009	0.0001 0.0
	Base Case (NP20)	RS03 Treated	22.62	6.56	124	0.09			0.0002			0.00007		0.00000			1.44			0.00016	8.2	8.4	0.00 0.0	002 0.	12 22.4	4 0.0000	1 0.0000		9 0.0000						0.0001 0.0
	Base Case (NP20) Base Case (NP20)	RS03 Treated RS03 Treated	19.56	6.56	125 134	0.09			0.0002			0.00007			0.00001			0.17 0.18		0.00016	8.8		0.00 0.0				1 0.0000								0.0001 0.0 0.0001 0.0
90	Base Case (NP20)	RS03 Treated	21.95	6.58	125	0.08	102.6	0.0028	0.0002	0.0222	36.0	0.00007	4.7	0.00000	0.00001	0.00011	1.43	0.16	0.01	0.00017	7.6	8.5	0.00 0.0	001 0.	12 22.4	4 0.0000	1 0.0000	0.00044	4 0.0000	15 17	0.01 0	.0002 1.407	2 0.0000	0.0008	0.0001 0.0
91	Base Case (NP20)	RS03 Treated RS03 Treated	14.21 12.97	6.54	133		109.3 119.9		0.0002	0.0228		0.00007	5.1 5.6		0.00001			0.17 0.18		0.00017	8.5 8.7		0.00 0.0		24.5	5 0.0000 2 0.0000	1 0.0000		0.0000						0.0001 0.0
92	Base Case (NP20) Base Case (NP20)	RS03 Treated		6.58					0.0002			0.00007			0.00001			0.18		0.00017	8.1		0.00 0.0	002 0	12 27.		1 0.0000								0.0001 0.0
94	Base Case (NP20)	RS03 Treated	22.05	6.55	123	0.09	100.2	0.0029	0.0002	0.0222	35.4	0.00007	4.6	0.00000	0.00001	0.00011	1.42	0.15	0.01	0.00017	7.3	8.4	0.00 0.0	001 0.	12 21.6	6 0.0000	1 0.0000	0.00040	0.0000	15 17	0.01 0	.0002 1.398	0.0000	0.0007	0.0001 0.0
95	Base Case (NP20)	RS03 Treated RS03 Treated		6.56		0.09			0.0002			0.00007			0.00001			0.16 0.17		0.00017	8.0 7.8		0.00 0.0				1 0.0000								0.0001 0.0
97	Base Case (NP20) Base Case (NP20)	RS03 Treated	19.21			0.08	107.7		0.0002			0.00007			0.00001					0.00017	7.5		0.00 0.0				1 0.0000		2 0.0000						0.0001 0.0
98	Base Case (NP20)	RS03 Treated	13.90	6.53	137			0.0028	0.0002	0.0233	39.0	0.00007	5.2	0.00000	0.00001	0.00011	1.35	0.17	0.01	0.00017	8.3	9.6	0.00 0.0	001 0.	12 24.9	9 0.0000	1 0.0000	0.00047		15 18	0.01 0	.0002 1.334	0.0000	0.0008	0.0001 0.0
99	Base Case (NP20)	RS03 Treated RS03 Treated		6.57					0.0002 0.0002			0.00007			0.00001			0.17 0.15		0.00017 0.00017	7.8 6.9		0.00 0.0				1 0.0000								0.0001 0.0 0.0001 0.0
101	Base Case (NP20) Base Case (NP20)	RS03 Treated		6.52					0.0002			0.00007			0.00001					0.00017	8.6		0.00 0.0				1 0.0000								0.0001 0.0
102	Base Case (NP20)	RS03 Treated	15.49	6.53	133	0.09			0.0002		37.9	0.00007	5.1	0.00000	0.00001	0.00011	1.35	0.16	0.01	0.00017	7.9	9.3	0.00 0.0	002 0.	12 24.0		1 0.0000			15 18	0.01 0	.0002 1.330	7 0.0000	0.0008	0.0001 0.0
	Base Case (NP20) Base Case (NP20)	RS03 Treated RS03 Treated	14.64	6.49	137	0.11			0.0002			0.00007		0.00000	0.00001	0.00011		0.17	0.01	0.00017	8.6 8.2		0.00 0.0		25.0	0.0000	1 0.0000		8 0.0000			.0002 1.278			0.0001 0.0
	Base Case (NP20)	RS03 Treated	24.10	6.56	127				0.0002			0.00007			0.00001					0.00017	7.3			001 0	12 22.4	4 0.0000	1 0.0000	0.00040	0.0000	15 17					0.0001 0.0
	Base Case (NP20)	RS03 Treated		6.55	130				0.0002			0.00007			0.00001					0.00017	7.6		0.00 0.0		12 22.8	8 0.0000	1 0.0000	0.00042							0.0001 0.0
	Base Case (NP20) Base Case (NP20)	RS03 Treated RS03 Treated	20.75 15.87	6.57			106.7	0.0028	0.0002			0.00007			0.00001	0.00011	1.40	0.16 0.16		0.00017	7.3		0.00 0.0			8 0.0000 4 0.0000	1 0.0000					.0002 1.383			0.0001 0.0
	Base Case (NP20)	RS03 Treated	17.94	6.57	132	0.09			0.0002			0.00007			0.00001			0.16		0.00017	7.1		0.00 0.0	001 0.	12 23.4		1 0.0000								0.0001 0.0
110	Base Case (NP20)	RS03 Treated	12.35	6.55	144				0.0002			0.00007			0.00001					0.00017	7.7		0.00 0.0				1 0.0000		2 0.0000			.0002 1.281			0.0001 0.0
	Base Case (NP20) Base Case (NP20)	RS03 Treated RS03 Treated		6.52					0.0002			0.00007			0.00001			0.15		0.00017	7.0		0.00 0.0				1 0.0000		0.0000						0.0001 0.0
113	Base Case (NP20)	RS03 Treated	24.20	6.55	125	0.09	101.9	0.0028	0.0002	0.0221	36.0	0.00007	4.7	0.00000	0.00001	0.00011	1.42	0.15	0.01	0.00017	6.9	8.6	0.00 0.0	001 0	02 21.4	4 0.0000	1 0.0000	0.00036	6 0.0000	14 16	0.01 0	.0002 1.397	7 0.0000	0.0007	0.0001 0.0
114	Base Case (NP20)	RS03 Treated RS03 Treated		6.56					0.0002			0.00007			0.00001			0.14 0.16		0.00016	6.8 8.0		0.00 0.0				1 0.0000								0.0001 0.0
116	Base Case (NP20) Base Case (NP20)	RS03 Treated		6.56					0.0002			0.00007			0.00001					0.00017	7.5		0.00 0.0				1 0.0000								0.0001 0.0
117	Base Case (NP20)	RS03 Treated		6.58					0.0002			0.00007			0.00001			0.16		0.00017	7.1		0.00 0.0				1 0.0000								0.0001 0.0
118	Base Case (NP20) Base Case (NP20)	RS03 Treated RS03 Treated	19.63	6.57	127	0.09	104.1	0.0028	0.0002	0.0223	36.5	0.00007	4.7		0.00001			0.14 0.15	0.01	0.00017	6.5	8.7	0.00 0.0	001 0.	12 21.5	5 0.0000 4 0.0000	1 0.0000	0.0003	5 0.0000	4 16	0.01 0	0002 1.400	7 0.0000	0.0007	0.0001 0.0 0.0001 0.0
120	Base Case (NP20)	RS03 Treated	20.08	6.55	126	0.09	102.7	0.0029	0.0002	0.0221	36.2	0.00007	4.7	0.00000	0.00001	0.00011	1.42	0.14	0.01	0.00017	6.7	8.7	0.00 0.0	001 0.	12 21.3	3 0.0000	1 0.0000	0.00034	4 0.0000	14 16	0.01 0	.0002 1.403	0.0000	0.0007	0.0001 0.0
121	Base Case (NP20)	RS03 Treated	18.74	6.57	135				0.0002		38.5	0.00007	5.1		0.00001			0.15		0.00017	7.0	9.3	0.00 0.0	001 0.	12 23.4	4 0.0000	1 0.0000	0.00036		15 17					0.0001 0.0
123	Base Case (NP20) Base Case (NP20)	RS03 Treated RS03 Treated	20.67	6.58	129	0.09			0.0002		37.1	0.00007	4.8		0.00001				0.01	0.00017	6.6 6.5		0.00 0.0		12 21.9	9 0.0000	1 0.0000		2 0.0000	14 16	0.01 0	.0002 1.389	8 0.0000	0.0006	0.0001 0.0 0.0001 0.0
124	Base Case (NP20)	RS03 Treated	15.77	6.58	139	0.09	116.4	0.0027	0.0002	0.0236	39.7	0.00007	5.3	0.00000	0.00001	0.00010	1.35	0.15	0.01	0.00017	6.8	9.7	0.00 0.0	001 0.	12 24.4	4 0.0000	1 0.0000	0.0003	5 0.0000	15 16	0.01 0	.0002 1.335	4 0.0000	0.0007	0.0001 0.0
125	Base Case (NP20)	RS03 Treated		6.56					0.0002			0.00007			0.00001					0.00017	6.3		0.00 0.0				1 0.0000								0.0001 0.0
	Base Case (NP20) Base Case (NP20)	RS03 Treated RS03 Treated		6.53	120				0.0002			0.00007			0.00001					0.00016	7.2		0.00 0.0				1 0.0000		2 0.0000 7 0.0000						0.0001 0.0 0.0001 0.0
128	Base Case (NP20)	RS03 Treated	14.99	6.53	132	0.10	108.1	0.0028	0.0002	0.0227	37.7	0.00007	4.9	0.00000	0.00001	0.00011	1.37	0.15	0.01	0.00017	7.0	9.2	0.00 0.0	001 0.	12 22.6	6 0.0000	1 0.0000	0.00036	6 0.0000	4 17	0.01 0	.0002 1.350	0.0000	0.0007	0.0001 0.0
	Base Case (NP20) Base Case (NP20)	RS03 Treated RS03 Treated	18.01	6.55	135	0.09	111.6	0.0028	0.0002	0.0232		0.00007		0.00000	0.00001	0.00011	1.34	0.15 0.14		0.00017	6.8	9.4	0.00 0.0	001 0	12 23.3		1 0.0000					.0002 1.328			0.0001 0.0
	Base Case (NP20)	RS03 Treated		6.57					0.0002			0.00007			0.00001					0.00017	6.2		0.00 0.0				1 0.0000		0.0000			.0002 1.385			0.0001 0.0
132	Base Case (NP20)	RS03 Treated	20.49	6.54	125	0.09	101.4	0.0030	0.0002	0.0221	35.9	0.00007	4.6	0.00000	0.00001	0.00011	1.42	0.14	0.01	0.00016	6.5	8.6	0.00 0.0	001 0	12 20.7	7 0.0000	1 0.0000	0.0003	1 0.0000	17	0.01 0	.0002 1.395	3 0.0000	0.0007	0.0001 0.0
	Base Case (NP20) Base Case (NP20)	RS03 Treated RS03 Treated	21.17 14.20	6.50	123	0.10 0.10	98.5 110.4		0.0002			0.00007	4.5 5.1	0.00000	0.00001	0.00011	1.43			0.00016	6.6 7.4		0.00 0.0			0.0000	1 0.0000		2 0.0000 7 0.0000			.0002 1.406			0.0001 0.0
	Base Case (NP20)	RS03 Treated	21.53	6.54	135	0.10	110.6		0.0002		38.3	0.00007			0.00001			0.15		0.00017	6.8	9.5	0.00 0.0	001 0.	12 23.0		1 0.0000								0.0001 0.0
	Base Case (NP20)	RS03 Treated	14.87	6.56	139	0.09	115.1	0.0027	0.0002	0.0233	39.5	0.00007	5.3	0.00000	0.00001	0.00010	1.34	0.15	0.01	0.00017	6.6	9.7	0.00 0.0	001 0	12 23.8	0.0000	1 0.0000	0.0003	2 0.0000	14 15	0.01 0	.0002 1.327	0.0000	0.0006	0.0001 0.0
	Base Case (NP20) Base Case (NP20)	RS03 Treated RS03 Treated		6.59					0.0002	0.0239		0.00007			0.00001			0.15		0.00017	6.0 5.5		0.00 0.0				1 0.0000								0.0001 0.0
139	Base Case (NP20)	RS03 Treated	21.62	6.59	130	0.08	107.9	0.0027	0.0002	0.0228	37.4	0.00007	4.9	0.00000	0.00001	0.00010	1.41	0.14	0.01	0.00017	5.8	8.9	0.00 0.0	001 0.	21.8	0.0000	1 0.0000	0.00026	6 0.0000	14 15	0.01 0	.0002 1.389	0.0000	0.0006	0.0001 0.0
140	Base Case (NP20)	RS03 Treated	26.78	6.55	117	0.09			0.0002		33.8	0.00007	4.2		0.00001		1.50	0.12	0.01	0.00016	5.7	7.8	0.00 0.0	001 0.	18.2		1 0.0000			16	0.01 0	.0002 1.471	5 0.0000	0.0006	0.0001 0.0
141	Base Case (NP20) Base Case (NP20)	RS03 Treated RS03 Treated		6.54					0.0002			0.00007			0.00001			0.15 0.13		0.00016	6.9 5.8		0.00 0.0				1 0.0000								0.0001 0.0
143	Base Case (NP20)	RS03 Treated	14.61	6.51	139	0.10	113.9	0.0030	0.0002	0.0234	39.4	0.00007	5.2	0.00000	0.00001	0.00011	1.32	0.15	0.01	0.00016	6.8	9.8	0.00 0.0	001 0	13 23.4	4 0.0000	1 0.0000	0.0003	2 0.0000	14 17	0.01 0	.0002 1.305	4 0.0000	0.0007	0.0001 0.0
144	Base Case (NP20)	RS03 Treated RS03 Treated	18.82	6.52	127 145	0.10 0.10	103.0		0.0002	0.0224		0.00007	4.7	0.00000	0.00001	0.00011	1.37	0.14 0.15	0.01	0.00016	6.3 7.0	8.9	0.00 0.0	001 0	20.9	0.0000	1 0.0000	0.00028	0.0000	4 17 4 17					0.0001 0.0
145	Base Case (NP20) Base Case (NP20)	RS03 Treated RS03 Treated		6.52						0.0242		0.00007								0.00017		8.4	0.00 0.0	001 0											0.0001 0.0
	Base Case (NP20)	RS03 Treated		6.57						0.0224	36.9	0.00007	4.7							0.00017			0.00 0.0												0.0001 0.0

MATAKANUI GOLD LIMITED Appendix D

	_				_														_														_	_				
- 1	l			Flow Rate	l	Hardness	Acidity	Alkalinity	l ai l	As		Ca	Cd	l cı l	Co	Cr	Cu	DOC	_	Fe	Hq	. I	Mq	Mn	Мо	NO3-N	Na	NI	Pb	Sb	se	SO4 S	. I п	тос	CN	l l		Zn
Year		Scenario	Station	(L/S)	pH	(mg	(mg	(mg	(mn/l)	(mg/L)	B (mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)		(mg/L)	/ma/l \			(mg/L)					(mg/L)	(mg/L)	(mg/L)				/L) (mg/L)			/ma/l \	(mg/L)	
- 1				(20)	1	CaCO3/L) (CaCO3/L)	CaCO3/L)) [((g. L)		(9, -,	(9-2)	(9-2)	(g.c)	((g.c)	(9.2/	(9-2)	(9-2/	(g. = /	((9-2/	(9.2)	,,	(9.2)	(9.2)	(g.c)	(9-2)	(9.2)		(9-2) (,-, ((g.c)	(mgrz)	(g. = /	(9.2)	(9-2)
148	Base (Case (NP20)	RS03 Treated	18.37	6.54	127	0.09	102.	8 0.0029	0.0002	0.0221	36.3	0.00007	4.6	0.00000	0.00001	0.00011	1.42	0.13	0.01	0.00016	6.0	8.7	0.00	0.0001	0.02	20.5	0.00001	0.00001	0.00027	.00004	16 (.01 0.0002	1.4010	0.0000	0.0006	0.0001	0.0000
		Case (NP20)	RS03 Treated		6.55		0.09			0.0002	0.0220	35.4			0.00000		0.00011	1.43			0.00016	5.8	8.4		0.0001	0.02	19.9		0.00001				.01 0.0002		0.0000			
150	Base (Case (NP20)	RS03 Treated	17.11	6.54	129	0.09	104.8	8 0.0029	0.0002	0.0224	36.8	0.00007	4.7	0.00000	0.00001	0.00011	1.38	0.14	0.01	0.00016	6.2	8.9	0.00	0.0001	0.02	21.1	0.00001	0.00001	0.00028	.00004	16 (.01 0.0002	1.3651	0.0000	0.0006	0.0001	0.0000
151	Base (Case (NP20)	RS03 Treated	24.47	6.56	127	0.09	103.9	9 0.0029	0.0002	0.0223	36.5	0.00007	4.7	0.00000	0.00001	0.00011	1.42	0.13	0.01	0.00017	5.9	8.7	0.00	0.0001	0.02	20.7	0.00001	0.00001	0.00026	.00004	16 (.01 0.0002	1.3969	0.0000	0.0006	0.0001	0.0000
152	Base (Case (NP20)	RS03 Treated		6.56		0.09	102.7	7 0.0029	0.0002	0.0220	36.3	0.00007	4.6	0.00000	0.00001	0.00011	1.44	0.13	0.01	0.00016	5.8	8.6	0.00	0.0001	0.02	20.3	0.00001	0.00001	0.00026	.00004	16	.01 0.0002	1.4132	0.0000	0.0006	0.0001	0.0000
153	Base (Case (NP20)	RS03 Treated		6.57		0.09		8 0.0028	0.0002	0.0221	36.5	0.00007	4.6	0.00000	0.00001	0.00011	1.43	0.13	0.01	0.00017	5.7	8.7	0.00	0.0001	0.02	20.5	0.00001	0.00001	0.00025	.00004	16	.01 0.0002	1.4103	0.0000	0.0006	0.0001	0.0000
		Case (NP20)	RS03 Treated	19.92	6.56		0.09		0.0029	0.0002	0.0221	36.0	0.00007	4.6	0.00000	0.00001	0.00011	1.44	0.13	0.01	0.00017	5.7	8.6	0.00	0.0001	0.02	20.0	0.00001	0.00001	0.00024	.00004	16 (.01 0.0002	1.4193	0.0000	0.0006	0.0001	0.0000
		Case (NP20)	RS03 Treated		6.54		0.09			0.0002	0.0226		0.00007		0.00000		0.00011	1.39	0.13		0.00017	6.0	9.0		0.0001	0.02	21.1	0.00001	0.00001	0.00026			.01 0.0002		0.0000		0.0001	
		Case (NP20)	RS03 Treated	22.21			0.09			0.0002	0.0224	36.6			0.00000	0.00001	0.00011	1.40	0.13		0.00017	5.9	8.9		0.0001	0.02	20.7	0.00001	0.00001	0.00025			.01 0.0002				0.0001	0.0000
		Case (NP20)	RS03 Treated	18.39			0.09			0.0002	0.0222	36.4	0.00007	4.6			0.00011	1.42	0.13		0.00016	5.9	8.8		0.0001	0.02	20.3	0.00001	0.00001	0.00025			.01 0.0002		0.0000		0.0001	
		Case (NP20)	RS03 Treated		6.51	132	0.10		4 0.0030	0.0002	0.0228		0.00007		0.00000		0.00011	1.35	0.14		0.00016	6.3	9.3		0.0001	0.03	21.6						.01 0.0002		0.0000			
		Case (NP20)	RS03 Treated		6.54		0.09			0.0002	0.0224	36.5	0.00007		0.00000	0.00001	0.00011	1.40	0.13		0.00017	5.8	8.8		0.0001	0.02	20.6	0.00001	0.00001		.00004		.01 0.0003		0.0000			
		Case (NP20)	RS03 Treated	15.32		134	0.10			0.0002	0.0228	38.0		5.0		0.00001	0.00011	1.35			0.00016	6.3	9.4		0.0001	0.02	21.9		0.00001		.00004				0.0000			
		Case (NP20)	RS03 Treated	16.09		137	0.10			0.0002	0.0232	38.8			0.00000	0.00001	0.00011	1.31	0.14		0.00017	6.1	9.7		0.0001	0.02	22.7	0.00001	0.00001	0.00026			.01 0.0002	_	0.0000			
		Case (NP20)	RS03 Treated		6.56		0.09			0.0002	0.0247	41.6	0.00007	5.7	0.00000	0.00001	0.00010		0.14		0.00017	5.9	10.4		0.0001	0.02	25.4	0.00001	0.00001		.00004		.01 0.0003		0.0000		0.0001	
		Case (NP20)	RS03 Treated		6.59		0.08				0.0236	38.3		5.1			0.00010				0.00017	5.2	9.3		0.0001	0.02		0.00001	0.00001		.00004		.01 0.0003		0.0000			
		Case (NP20)	RS03 Treated	19.00			0.09			0.0002	0.0225	37.3	0.00007	4.8		0.00001	0.00011	1.39	0.13		0.00017	5.6	9.0		0.0001	0.02	20.9		0.00001	0.00022			.01 0.0002		0.0000		0.0001	0.0000
		Case (NP20)	RS03 Treated RS03 Treated		6.54		0.09			0.0002	0.0218	35.2	0.00007	4.4		0.00001	0.00011	1.43	0.12		0.00016	5.4 5.8	9.5		0.0001	0.02	19.2	0.00001	0.00001		.00004		.01 0.0002		0.0000		0.0001	0.0000
		Case (NP20)	RS03 Treated	15.88	6.55		0.09			0.0002	0.0231	38.6 37.6		5.1	0.00000		0.00011	1.35	0.13		0.00017		9.5		0.0001	0.02		0.00001	0.00001		.00004		.01 0.0003		0.0000		0.0001	0.0000
		Case (NP20)	RS03 Treated		6.56					0.0002	0.0229	37.5	0.00007		0.00000	0.00001	0.00011	1.38			0.00017	5.4	9.1		0.0001	0.02	21.4		0.00001		.00004		.01 0.000				0.0001	
		Case (NP20) Case (NP20)	RS03 Treated		6.54	149	0.09			0.0002	0.0227	42.1	0.00007		0.00000	0.00001	0.00011	1.27	0.13		0.00017	5.5	10.6		0.0001	0.02	25.3	0.00001	0.00001	0.00022			.01 0.000		0.0000		0.0001	0.0000
		Case (NP20)	RS03 Treated	17.26			0.09			0.0002	0.0236	38.5	0.00007	5.1	0.00000	0.00001	0.00010		0.14		0.00017	5.1	9.3		0.0001	0.02	22.4	0.00001	0.00001		.00004		.01 0.000				0.0001	0.0000
		Case (NP20)	RS03 Treated		6.57		0.08			0.0002	0.0238		0.00007		0.00000		0.00010	1,44	0.13		0.00017	5.0	8.4		0.0001	0.02	19.7	0.00001	0.00001				.01 0.000		0.0000		0.0001	
		Case (NP20)	RS03 Treated		6.53		0.10		6 0.0029		0.0234	39.1	0.00007	5.1		0.00001	0.00011	1.34	0.12		0.00017	5.8	9.6		0.0001	0.02	22.5		0.00001		.00004		.01 0.000		0.0000		0.0001	0.0000
		Case (NP20)	RS03 Treated	17.65		134	0.09			0.0002	0.0233	38.2		5.0	0.00000		0.00010		0.13		0.00017	5.3	9.3		0.0001	0.02	22.0		0.00001		.00004		.01 0.000		0.0000		0.0001	
		Case (NP20)	RS03 Treated	14.50			0.09			0.0002	0.0239	39.6	0.00007	5.3		0.00001	0.00010		0.13		0.00017	5.4	9.7		0.0001	0.02	23.1	0.00001	0.00001		.00004		.01 0.000		0.0000		0.0001	0.0000
		Case (NP20)	RS03 Treated		6.56		0.09			0.0002	0.0243		0.00007		0.00000		0.00010		0.14		0.00017	5.4	10.1		0.0001	0.02	24.1	0.00001	0.00001	0.00021			.01 0.0003		0.0000			
		Case (NP20)	RS03 Treated		6.62		0.08		6 0.0026	0.0002	0.0236		0.00007		0.00000		0.00010				0.00018	4.7	9.2			0.02	22.3		0.00001				.01 0.0002					
		Case (NP20)	RS03 Treated	23.27			0.09			0.0002	0.0218	35.2		4,4	0.00000	0.00001	0.00011	1.45	0.12		0.00017	4.9	8.3		0.0001	0.02	18.9	0.00001	0.00001	0.00017			.01 0.000		0.0000		0.0001	0.0000
		Case (NP20)	RS03 Treated	22.12			0.09	95.8	8 0.0029	0.0002	0.0213	34.4		4.2	0.00000	0.00001	0.00011	1.47	0.12		0.00016	5.1	8.0	0.00	0.0001	0.02	18.1	0.00001	0.00001	0.00019	.00004	15	.01 0.0003	1.4454	0.0000	0.0006	0.0001	0.0000
		Case (NP20)	RS03 Treated	16.39	6.55		0.09	107.8	8 0.0029	0.0002	0.0226	37.5	0.00007	4.8	0.00000	0.00001	0.00011	1.38	0.13	0.01	0.00017	5.5	9.1	0.00	0.0001	0.02	21.0	0.00001	0.00001	0.00022	.00004	16	.01 0.0003	1.3600	0.0000	0.0006	0.0001	0.0000
		Case (NP20)	RS03 Treated	18.30	6.56	128	0.09	105.7	7 0.0029	0.0002	0.0226	36.8	0.00007	4.7	0.00000	0.00001	0.00011	1.38	0.12	0.01	0.00017	5.2	8.9	0.00	0.0001	0.02	20.5	0.00001	0.00001	0.00020	.00004	15 (.01 0.0002	1.3634	0.0000	0.0006	0.0001	0.0000
		Case (NP20)	RS03 Treated	18.55	6.52	128	0.10	104.	3 0.0030	0.0002	0.0224	36.7	0.00007	4.7	0.00000	0.00001	0.00011	1.38	0.12	0.01	0.00016	5.5	8.9	0.00	0.0001	0.02	20.2	0.00001	0.00001	0.00020	.00004	16 (.01 0.0003	1.3603	0.0000	0.0006	0.0001	0.0000
		Case (NP20)	RS03 Treated	22.87			0.09			0.0002	0.0222	36.1	0.00007		0.00000	0.00001	0.00011	1.40	0.12		0.00016	5.3	8.7		0.0001	0.02	19.8	0.00001	0.00001		.00004		.01 0.0002		0.0000		0.0001	
		Case (NP20)	RS03 Treated	17.56			0.10			0.0002	0.0225	37.2	0.00007		0.00000	0.00001	0.00011	1.39	0.12		0.00016	5.5	9.0		0.0001	0.02	20.5		0.00001		.00004		.01 0.0002		0.0000		0.0001	
		Case (NP20)	RS03 Treated		6.57	125	0.09			0.0002	0.0220		0.00007		0.00000	0.00001	0.00011	1.43	0.12		0.00017	5.0	8.6		0.0001	0.02	19.6	0.00001	0.00001	0.00018			.01 0.0002		0.0000			
		Case (NP20)	RS03 Treated		6.58		0.08			0.0002	0.0210	33.9			0.00000	0.00001	0.00011	1.52	0.11		0.00016	4.8	7.7		0.0001	0.02	17.3	0.00001	0.00001	0.00017			.01 0.0003		0.0000			
		Case (NP20)	RS03 Treated		6.54		0.10			0.0002	0.0222		0.00007		0.00000	_	0.00011	1.41	0.13		0.00016	5.7	9.1			0.02		0.00001	0.00001				.01 0.0003					
		Case (NP20)	RS03 Treated	22.62		123	0.09	100.0		0.0002	0.0218	35.4	0.00007	4.4	0.00000	0.00001	0.00011	1.44	0.12		0.00016	5.0	8.4		0.0001	0.02	19.0	0.00001	0.00001	0.00018			.01 0.0002				0.0001	0.0000
		Case (NP20)	RS03 Treated		6.56		0.09			0.0002	0.0218	35.8	0.00007	4.5	0.00000	0.00001	0.00011	1.43	0.12		0.00016	5.0	8.5		0.0001	0.02	19.2	0.00001	0.00001		.00004		.01 0.0003				0.0001	0.0000
		Case (NP20)	RS03 Treated	17.40			0.09			0.0002	0.0229	38.1	0.00007	5.0			0.00011	1.37			0.00017	5.3	9.3		0.0001	0.02		0.00001	0.00001		.00004		.01 0.0003		0.0000		0.0001	
		Case (NP20)	RS03 Treated	21.95			0.08			0.0002	0.0221	35.9	0.00007	4.6		0.00001	0.00011	1.43	0.12		0.00017	4.8	8.5		0.0001	0.02	19.5		0.00001		.00004		.01 0.0002		0.0000		0.0001	0.0000
		Case (NP20)	RS03 Treated		6.54		0.09			0.0002	0.0227	37.8	0.00007	4.9			0.00011	1.36	0.12		0.00017	5.3	9.2		0.0001	0.02	21.1	0.00001	0.00001	0.00019			.01 0.0003		0.0000		0.0001	
		Case (NP20)	RS03 Treated		6.54	142	0.09			0.0002	0.0242	40.3	0.00007		0.00000		0.00010		0.13		0.00017	5.3	10.1		0.0001	0.02		0.00001	0.00001	0.00020			.01 0.0002		0.0000		0.0001	
		Case (NP20)	RS03 Treated		6.58		0.09			0.0002	0.0245	40.4	0.00007	5.5	0.00000	0.00001	0.00010	1.28	0.13		0.00017	5.0	10.0		0.0001	0.02	24.0		0.00001	0.00018			.01 0.0002		0.0000		0.0001	0.0000
		Case (NP20) Case (NP20)	RS03 Treated		6.55		0.09			0.0002	0.0221	35.3			0.00000		0.00011	1.42			0.00017	4.8 5.1	8.4 8.6		0.0001	0.02	19.1	0.00001	0.00001				.01 0.0003		0.0000		0.0001	0.0000
		Case (NP20)	RS03 Treated RS03 Treated	19.21			0.09			0.0002	0.0221	36.2 37.6	0.00007	4.6	0.00000	0.00001	0.00011	1.43	0.12		0.00017	4.9	8.6		0.0001	0.02	19.6 20.6	0.00001	0.00001	0.00018			.01 0.000		0.0000		0.0001	0.0000
		Case (NP20)	RS03 Treated	19.21			0.08			0.0002	0.0227	37.3	0.00007	4.8			0.00011	1.43	0.12		0.00017	4.9	8.9		0.0001	0.02	20.6	0.00001	0.00001	0.00017			.01 0.000		0.0000		0.0001	0.0000
		Case (NP20)	RS03 Treated		6.53		0.08			0.0002	0.0227	38.8			0.00000	0.00001	0.00011	1.42	0.12		0.00017	5.3	9.5		0.0001	0.02	21.9		0.00001		.00004		.01 0.000		0.0000		0.0001	
		Case (NP20)	RS03 Treated		6.57		0.09		7 0.0027		0.0232		0.00007				0.00011				0.00017	5.0		0.00		0.02				0.00019			.01 0.000					
199	Dane (Gase (HF2U)	11000 Heated	10.49	0.37	137	0.09	119.	0.0027	0.0002	0.0200	J5.1	0.00007	0.2	0.00000	0.00001	0.00010	1.00	U.13	0.01	0.00017	0.0	5.0	0.00	0.0001	U.UZ	22.4	U.UUUU I	0.00001	0.00010		14	.07 0.000	1.0102	0.0000	0.0000	0.0001	0.0000

APPENDIX E LIMITATIONS

This Document has been provided by Mine Waste Management Ltd (MWM) subject to the following limitations:

This Document has been prepared for the particular purpose outlined in MWM's proposal and no responsibility is accepted for the use of this Document, in whole or in part, in other contexts or for any other purpose.

The scope and the period of MWM's services are as described in MWM's proposal, and are subject to restrictions and limitations. MWM did not perform a complete assessment of all possible conditions or circumstances that may exist at the site referenced in this Document. If a service is not expressly indicated, do not assume it has been provided. If a matter is not addressed, do not assume that any determination has been made by MWM in regards to it.

Conditions may exist which were undetectable given the limited nature of the enquiry MWM was retained to undertake with respect to the site. Variations in conditions may occur between investigatory locations, and there may be special conditions pertaining to the site which have not been revealed by the investigation and which have not therefore been taken into account in the Document. Accordingly, additional studies and actions may be required.

In addition, it is recognised that the passage of time affects the information and assessment provided in this Document. MWM's opinions are based upon information that existed at the time of the production of this Document. It is understood that the services provided allowed MWM to form no more than an opinion of the actual conditions of the site at the time the site was reviewed and cannot be used to assess the effect of any subsequent changes in the quality of the site, or its surroundings, or any laws or regulations.

Any assessments made in this Document are based on the conditions indicated from published sources and the investigation described. No warranty is included, either express or implied, that the actual conditions will conform exactly to the assessments contained in this Document.

Where data supplied by the client or other external sources, including previous site investigation data, have been used, it has been assumed that the information is correct unless otherwise stated. No responsibility is accepted by MWM for incomplete or inaccurate data supplied by others.

MWM may have retained subconsultants affiliated with MWM to provide services for the benefit of MWM. To the maximum extent allowed by law, the Client acknowledges and agrees it will not have any direct legal recourse to, and waives any claim, demand, or cause of action against, MWM's affiliated companies, and their employees, officers and directors.

This Document is provided for sole use by Matakanui Gold Limited and is confidential to it and its professional advisers. No responsibility whatsoever for the contents of this Document will be accepted to any person other than the Client. Any use which a third party makes of this Document, or any reliance on or decisions to be made based on it, is the responsibility of such third parties. MWM accepts no responsibility for damages, if any, suffered by any third party as a result of decisions made or actions based on this Document.

MWM acknowledges that this report will be relied on by a Panel appointed under the Fast Track Approvals Act 2024 and these disclaimers do not prevent that reliance.







5 Sir William Pickering Drive Christchurch 8053, New Zealand

T. +64 3 242 0221

E. admin@minewaste.com.au

MEMORANDUM

Recipient: Damian Spring – Matakanui Gold Limited

From: Paul Weber – Mine Waste Management

Date: 31 May 2025

Cc: Mary Askey – Matakanui Gold Limited

Document Number: J-NZ0233-011-M-Rev1

Document Title: Water Quality Database QA/QC

Mine Waste Management Limited (MWM) has provided this memorandum to Matakanui Gold Limited for the proposed Bendigo-Ophir Gold Project (BOGP Project). MWM has been engaged to provide advice regarding quality assurance / quality control (QA/QC) of water quality data loaded into the BOGP water quality database. It is recommended that the following issues are considered for QA/QC:

- Quality assurance (QA) of data is required.
- Quality control (QC) including duplicate samples, replicate testing, blanks, and water reference standards should be used.
- Quality assurance of data is required.
- Management of limits of reporting (LOR).
- Ensuring the LOR is appropriate for the potential constituents of concern (PCOC) to confirm whether they are elevated against recommended water quality guidelines.
- Analysis of data to confirm whether further ongoing testing is required if results are consistently lower than the recommended water quality guidelines.

BACKGROUND

An important aspect of ensuring data are suitable and meet the data quality objectives (DQOs) is to undertake QA/QC where:

- Quality assurance (QA) is defined as the system of documented processes and procedures that ensure quality and includes aspects including training, equipment calibration, sampling procedures, and record-keeping.
- Quality control (QC) is defined as the operational activities that confirm the quality assurance methods are functional, and that the information collected is accurate, precise, and properly recorded.

This memorandum provides advice on QA/QC of water quality data once it is entered into the water quality database. It assumed data management processes are appropriate to avoid the input of

erroneous data and that transcription errors are avoided. It is assumed that all chain of custody (COC) forms and certificates of analysis (COA) are stored and are filed in a logical manner to provide proof of data should it be gueried.

QUALITY CONTROL

For duplicate samples, replicate testing of the same sample, and inter-laboratory duplicates, a quantitative measure of the variability (or reproducibility of the data) should be undertaken (e.g., precision). Precision should be measured by the relative percent difference (RPD). Note: Small concentration changes at low analyte concentrations (typically defines as <10x LOR) will result in larger calculated variations in precision – the significance of this large change should be considered in the context of the DQOs (e.g., Standards Australia, 2005).

A quantitative measure of the closeness of reported data to the true value is required (e.g., accuracy). One way to determine accuracy of the dataset is to compare the ionic balance of water samples for reference samples and duplicates. This approach provides a larger dataset (rather than one measurement) to consider accuracy.

Recommended QC:

 Calculation of RPD for duplicate samples, replicate samples, inter-laboratory duplicate samples where:

$$RPD = [(R1 - R2) / ((R1 + R2)/2)] \times 100$$

Where:

R1 is sample 1; and

R2 is sample 2.

- Where a RPD of ≤20% should be used as an indicator for determining appropriate discrepancies between laboratories. A RPD of ≤20% was adopted as:
 - the samples were taken at the same time; and
 - the water samples are expected to be homogeneous.
- Calculation of ionic balance (IB) for duplicate samples, replicate samples, and inter-laboratory duplicate samples where:
 - Measured ion concentrations are first converted to milliequivalents per litre (meg/L):

$$Meg/L = (C/MW)*V*1000)$$

Where:

C is the concentration in mg/L;

MW is the molecular weight in g/mol; and

V is the valence of the substance

Page 2 MWM-S004-Rev2

- Iron and manganese are both assumed to have charge of +2, because the ferrous and manganous species of these elements are the primary water-soluble forms.
- Positively charged ion concentrations are summed to obtain a Cation Sum, and negatively charged ions are summed to obtain an Anion Sum.
- An ionic balance (IB) (Charge balance) is determined by:

 $IB = [((\Sigma Cation (meq/L) - \Sigma Anion (meq/L)) / (\Sigma Cation (meq/L) + \Sigma Anion (meq/L)] x 100]$

An Ionic Balance of <10% is considered reasonable.

QUALITY ASSURANCE

Data should undergo quality assurance processes including graphical analysis to identify outlier/anomalous samples. For projects involving the disturbance of sulfide minerals this should include:

- Comparison of field pH and EC to laboratory pH and EC
- Time series plots of PCOC concentrations to identify outliers with checks against water quality guidelines to identify parameters that are elevated.
- Evaluation of sulfate concentrations versus PCOC concentrations to understand any relationships and identify outlier data (noting sulfate is often correlated with other contaminants at mining operations where sulfide minerals are disturbed).
- Evaluation of pH versus metal concentrations. Assessment of pH can be a useful guide to the reliability of data and if metals remain elevated above typical metal hydrolysis pH values (Table 1) then the data reliability should be considered.
- Comparison of Total N measurements against the sum of nitrogenous compounds (Nitrite-N, Nitrate-N, Ammoniacal-N).

Table 1. Minimum metal hydroxide solubility.

Metal	pH corresponding to minimum metal hydroxide solubility
Ferric iron, Fe ³⁺	~3.5
Antimony, Sb2+	4.2
Aluminium, Al ³⁺	4.5
Lead, Pb ²⁺	6.5
Copper, Cu ²⁺	7.0
Ferrous iron, Fe ²⁺	8.0
Zinc, Zn ²⁺	8.5
Nickel, Ni ²⁺	9.3
Cadmium, Cd ²⁺	10.0
Manganese, Mn ²⁺	10.6

Source: INAP (2014).

Page 3 MWM-S004-Rev2

When outlier/anomalous samples are identified by the QA process, the first step is to check the laboratory COA and confirm there are no transcription errors (i.e., data not loaded into the database correctly). If the reported data are correct, then the next step is to query the issue with the laboratory requesting the data management procedures are checked and for the sample to be retested. If the results are the same, then another confirmatory sample may need to be submitted. If this is not possible then the data should be presented but not used (unless conservative assumptions are being used), with an explanation of why the data are considered erroneous.

LIMITS OF REPORTING

Limits of reporting (LOR) need to be considered as being suitable or whether lower limits are required. For instance:

- Ensuring the LOR is appropriate for the PCOC to confirm whether they are elevated against recommended water quality guidelines. If water quality guidelines are lower than the LOR, then lower LORs may be required.
- However, consideration should be given to practical quantification limits (PQLs). For instance, the typical LOR for HS⁻, Hg, and Ag is often higher than ANZG (2018) guidelines and lower LOR are often not practical.
- LOR need to be clearly recorded in the database noting that LOR can change between laboratories and analytes. Preference is that the '<' symbol is maintained in the database and post processing outside the database (e.g., for analysis purposes) converts this to a number than can be used (e.g., ½ the LOR) with the conversion process clearly explained.

PCOC MONITORING REQUIREMENTS

Generally, if any parameter is within 50% of the adopted trigger limits (e.g., resource consent limits or the ANZG (2018) guideline limits, etc) they are considered potentially elevated and ongoing monitoring is recommended to confirm trends and/or potential hazards. This approach is similar to using 50% of maximum acceptable value (MAV) for drinking water where it is used as a screening level for follow up action (NZ Government, 2022).

If there is a robust water quality database available for a project that includes:

- Multiple sites within the project area to understand typical PCOC concentrations including critical locations;
- Assessment of mineralised and unmineralised areas to understand typical PCOC concentrations;
- Assessment of areas affect by historical mining activities and areas not affected by historical mining activities;
- At least two years of monthly monitoring data¹ (to address seasonality) during different flow regimes (low, median, and high flow);

Page 4 MWM-S004-Rev2

.

¹ ANZG (2018) notes that site-specific guideline values should be based on at least 2 years of monthly monitoring data from an appropriate site: https://www.waterquality.gov.au/anz-quidelines/quideline-values/derive/reference-data

- Trend analysis to confirm no increasing trends for PCOC or high variability of results;
- Evaluation of whether changes have occurred within the catchment that could affect PCOC concentrations;
- · Approval of recommended water quality limits by a subject matter expert in ecotoxicity,

then it would be reasonable to cease routine analysis for the PCOC that are > 50% of the recommended water quality compliance criteria for the BOGP (i.e., a MEQ < 0.5). These proposed water quality criteria are provided in Ryder (2025).

CLOSING REMARKS

Please do not hesitate to contact Paul Weber at +64 3 242 0221 or paul.weber@minewaste.com.au should you wish to discuss this memorandum in greater detail.

Page 5 MWM-S004-Rev2

REFERENCES

- Australian and New Zealand Environment and Conservation Council (ANZG) and Agriculture and Resource Management Council of Australia and New Zealand (ARMCANZ), 2018. Australian and New Zealand Guidelines for Fresh and Marine Water Quality. Canberra.
- Australian Standards, 2005. AS 4482.1-2005 Guide to the Investigation and Sampling of Sites with Potentially Contaminated Soil- Non-volatile and Semi-volatile Compounds.
- INAP, 2014. Global Acid Rock Drainage Guide (GARD Guide) Rev1 International Network for Acid Prevention. http://www.gardguide.com/images/5/5f/TheGlobalAcidRockDrainageGuide.pdf
- NZ Government, 2022. Water Services (Drinking Water Standards for New Zealand) Regulations 2022. Available: https://www.legislation.govt.nz/regulation/public/2022/0168/latest/versions.aspx
- Ryder, G., 2025. Bendigo-Ophir Gold Project: Recommended water quality compliance limits for the Bendigo-Ophir Gold Project. Report for Matakanui Gold by Greg Ryder Consulting.

Page 6 MWM-S004-Rev2