



CRCXXXX – s9 Land Use Consent

Applicant: NTP Development Holdings Limited

Duration:

	<b>Limits</b>
1.	The works authorised by this resource consent are limited to the excavation of land associated with the development of an industrial subdivision at Pound Road Industrial Development at 173 Pound Road, legally described as: Lot 3 DP 33334, Lot 2 DP 33334, Lot 10 DP 23834, Lot 2 DP 23834, Lot 1 DP 33334, Lot 2 DP 20738, Lot 1 DP 20738, Lot 2 DP 38418, Lot 7 DP 23834, Lot 6 DP 23834, Lot 2 DP 24156, Lot 1 DP 24156, Lot 1 DP 23834, Lot 1 DP 38418 and has a total area of approximately 60 hectares ( <b>ha</b> ).
2.	The works shall be undertaken in accordance with the attached design plan, plan CRCXXX which forms a part of this consent.
3.	The maximum depth of excavation for the works authorised by this resource consent must not exceed 5.5 metres below ground level.  <i>Advice Note: It will be up to the Consent Holder to demonstrate compliance with the maximum excavation depth. This can be done, for example, via reference to a specified datum and reduced levels from that datum or via site specific survey points or other measurements.</i>
	<b>Prior to Commencement</b>
4.	Prior to any bulk earthworks occurring on the site (excluding Lots 400 and 401), further investigation of any outstanding areas of land not already investigated including the 94 Barbers Road bund, shall be undertaken via a Preliminary Site Investigation (PSI) and/or a Detailed Site Investigation (DSI) as required.
5	Prior to any bulk earthworks occurring within Lots 400 and Lot 401, further investigation of this land shall be undertaken via a Preliminary Site Investigation (PSI) and/or a Detailed Site Investigation (DSI) as required, with the results submitted to Canterbury Regional Council, Attention: Compliance Manager and Contaminated Land Team.
5.	All contaminated land must be remedied prior to earthworks occurring on the site. <i>Advice note: This condition does not apply to Lots 400 and 401, which will require separate remediation prior to any works commencing on these two balance lots.</i>
6.	Any contaminated land identified on Lots 400 and 401 through the investigations required under Condition 5 of this resource consent shall be remediated prior to earthworks occurring within either of those Lots.
7.	Prior to commencement of the works described in Condition (1), all personnel working on the site must be made aware of, and have access to, the following: a. The contents of this resource consent document and all associated documents, including the Earthworks Management Plan prepared by Dave Lovell Smith and attached as Appendix 13; and b. Resource Consents and all associated documents, including the Erosion and Sediment Control Plan (ESCP). c. Resource Consents and all associated documents, including the Erosion and Sediment Control Plan (ESCP) as set out in Condition (X).
8.	At least 15 working days prior to the commencement of works to remediate contaminated land, the consent holder must submit a Remedial Action Plan (RAP) to Canterbury Regional Council, Attention: Compliance Manager for certification that it complies with the conditions of this consent.  The RAP required under condition (X) must: a. Outline the proposed soil sampling procedure to identify the extent of contamination, including guidelines used to analyze samples; b. Detail a procedure for managing any discovery of contaminated soil or material; c. Describe the methodology for soil removal and how soil will be prevented from being entrained in stormwater; d. Outline where the contaminated soil will be displaced of; and e. Describe any validation sampling that will be undertaken.



9.	<p>The RAP may be amended at any time. Any amendments must be:</p> <ol style="list-style-type: none"> <li>Only for the purpose of improving the efficacy of the management of contaminated soil and must not result in an increase of sediment being discharged from the site; and</li> <li>Consistent with the conditions of this resource consent; and</li> <li>Submitted in writing to the Canterbury Regional Council, Attention: Compliance Manager, prior to any amendment being implemented.</li> </ol>
10.	<p>The ESCP must:</p> <ol style="list-style-type: none"> <li>include a map showing the location of all works;</li> <li>Detailed plans showing the location of sediment control measures, on-site catchment boundaries, and sources of run-off;</li> <li>Detail how best practicable measures are taken to minimize discharges of sediment-laden stormwater run-off beyond the boundaries of the site; <ul style="list-style-type: none"> <li>Include drawings and specifications of designated sediment control measures, if these are not designed and installed in accordance with the ESCT;</li> <li>Detail the methodology for stabilizing the site entrance and exit points and any measures employed to prevent off-site tracking of sediment and other materials from the site.</li> </ul> </li> <li>Include a confirmation that the erosion and sediment control devices have been sized appropriately in accordance with the ESCT;</li> <li>Include a programme of works, including a proposed timeframe for each stage of the works and the earthworks methodology;</li> <li>Detail the management of any stockpiled material;</li> <li>Detail inspection and maintenance of the sediment control measures.</li> <li>Detail sampling procedures and protocols;</li> <li>Define the discharge points where stormwater is discharged onto land / infiltrates into land;</li> <li>Include a description of dust mitigation to be used and details of best practicable options to be applied to mitigate dust and sediment discharge beyond the site boundary;</li> <li>Detail the methodology for stabilizing the site if works are paused for more than five working days or abandoned;</li> <li>detail the methodology for stabilizing the site and appropriate decommissioning of all erosion and sediment control measures after works have been completed; and</li> <li>Include measures such as a Chemical Treatment Plan should the use of water treatment chemicals be required.</li> </ol> <p><i>Note the use of Water treatment chemicals may require additional consent under section 15 of the Resource Management Act.</i></p>
11.	<ol style="list-style-type: none"> <li>The ESCP must be submitted to the Canterbury Regional Council, Attention: Compliance Manager, after the commencement of resource consent and at least 10 working days prior to works commencing, for approval that it complies with the ESCT and the conditions of this resource consent;</li> <li>The discharge must not commence until approval has been received from the Canterbury Regional Council that the ESCP is consistent with the ESCT or equivalent industry guideline; and</li> <li>Notwithstanding Condition (9(a)), if the ESCP has not been reviewed and/or approved within ten working days of the Compliance Manager receiving the ESCP, the discharge may commence.</li> </ol>
12.	<p>The ESCP may be amended at any time. Any amendments must be:</p> <ol style="list-style-type: none"> <li>Only for the purpose of improving the efficacy of the erosion and sediment control measures and must not result in reduced discharge quality; and</li> <li>For the purpose of applying best practicable measures to mitigate [dust and] sediment transport off-site;</li> <li>Consistent with the conditions of this resource consent; and</li> <li>Submitted in writing to the Canterbury Regional Council, Attention: Compliance Manager, prior to any amendment being implemented.</li> </ol>
13.	<p>Erosion and sediment control measures must be inspected at least once per day, as well as following any rainfall event that results in more than five millimeters of rainfall at the site. Any accumulated sediment must be removed, and repairs made, as necessary, to ensure effective functioning of measures and devices. Records of any inspections must be kept and provided to the Canterbury Regional Council on request.</p>



14.	If the consent holder abandons work on-site, or pauses works for more than five working days, adequate preventative and remedial measures must be taken to control sediment discharged from exposed or unconsolidated surfaces. These measures must be maintained for so long as necessary to prevent sediment discharges from the earth worked areas.
15.	At least 10 working days prior to the commencement of works on site, the Canterbury Regional Council, Attention: Compliance Manager (via <a href="mailto:ECinfo@ecan.govt.nz">ECinfo@ecan.govt.nz</a> ) must be informed of the commencement of works.
16.	At least 10 working days prior to commencement of works on site, the consent holder must request a pre-construction site meeting with the Canterbury Regional Council, Attention: Compliance Manager (via <a href="mailto:ECinfo@ECan.govt.nz">ECinfo@ECan.govt.nz</a> ), and all relevant parties, including the primary contractor. At a minimum, the following must be covered at the meeting: <ul style="list-style-type: none"> <li>a. Scheduling and staging of the works;</li> <li>b. Responsibilities of all relevant parties, including confirmation that the person (or persons) implementing the ESCP on the site is (are) suitably trained and/or experienced;</li> <li>c. Contact details for all relevant parties;</li> <li>d. Expectations regarding communication between all relevant parties;</li> <li>e. Procedures for implementing any amendments;</li> <li>f. Site Inspection; and</li> <li>g. Confirmation that all relevant parties have copies of the consents of this resource consent document and all associated erosion and sediment control plans and any other discharge treatment methodologies employed.</li> </ul>
<b>During works</b>	
17.	All practicable measures must be taken to: <ul style="list-style-type: none"> <li>a. Minimise soil disturbance to that necessary to carry out the works described under Condition 1;</li> <li>b. Prevent soil erosion;</li> <li>c. Avoid placing excavated material in a position where it may enter: <ul style="list-style-type: none"> <li>i. any neighbouring site;</li> <li>ii. a surface water body; and/or</li> <li>iii. the [territorial authority's] reticulated stormwater network, or any other private or public stormwater devices.</li> </ul> </li> </ul>
18.	All earthworks shall be managed to avoid the potential for cross-contamination of materials to occur, in particular movement of contaminated soil around the site and/or deposition of contaminated soil on other parts of the site shall be avoided.
19.	Tracking of material off-site during the works must be avoided at all times.  In the event that material is tracked off-site, the tracked material must be removed as soon as practicable.
20.	Excess soil or waste materials removed from the application site shall be taken to a consented site whose waste acceptance criteria would be met. Evidence of waste disposal such as weighbridge receipt shall be reported in the SVR.
<b>Installation of Culverts – Fish Protection</b>	
21.	The consent holder shall ensure that all practicable measures are undertaken to ensure that there is no stranding of fish in pools or channels up and downstream of the works.
22.	Any pump used to take water in accordance with condition (x) of CRCXXX must be fitted with fish screens in general accordance with the Christchurch City Council's "Standards for Temporary Fish Screens on Christchurch City Council Projects" (2023).
23.	A Fish Management Plan shall be prepared by a suitably qualified freshwater ecologist and submitted to the Canterbury Regional Council for their records (via <a href="mailto:ECinfo@ecan.govt.nz">ECinfo@ecan.govt.nz</a> ). The Plan should include the following information as a minimum: <ul style="list-style-type: none"> <li>a. Locations where the Plan will be implemented;</li> <li>b. Methods to ensure fish cannot access works areas</li> <li>c. Protocols to be followed including methods to rescue and relocate fish;</li> <li>d. Person/s responsible for ensuring the plan is implemented;</li> <li>e. Protocols if pest fish are encountered;</li> </ul>



	f. Protocols to ensure fish are not entrained in pumps during pumping (water pumping should have fish screens with a maximum mesh width and height size of three millimeters).
24.	<p>In the event that fish are required to be salvaged and relocated to an appropriate waterway. The fish salvage must include the following measures;</p> <ul style="list-style-type: none"> <li>a. Be conducted by or under supervision of a certified, suitably qualified and experienced freshwater ecologist;</li> <li>b. Be in general accordance with Canterbury Regional Council and Christchurch City Council's "fish Salvage Guidance for Works in Waterways" (12 October 2017);</li> <li>c. The fish must be relocated to a habitat deemed suitable by the certified, suitably qualified and experienced freshwater ecologist;</li> <li>d. The certified, suitably qualified and experienced freshwater ecologist must hold any necessary permits and approvals required by the Ministry for Primary Industries, Department of Conservation and Fish and Game to conduct fish salvage.</li> </ul>
25.	<p>Following the completion of works, the consent holder shall provide to the Canterbury Regional records (via <a href="mailto:ECinfo@ecan.govt.nz">ECinfo@ecan.govt.nz</a>) of any fish captured and relocated. This record shall include:</p> <ul style="list-style-type: none"> <li>a. The location where fish were captured;</li> <li>b. The species and number of fish captured; and</li> <li>c. The location where fish were relocated</li> </ul>
	<b>Discovery of Contaminated Soil or Materials</b>
26.	<p>In the event that any contaminated soil or material is uncovered by the works, a contamination discovery protocol must be implemented, including but not limited to the following steps:</p> <ul style="list-style-type: none"> <li>a. Earthworks within ten metres of discovered contaminant soil or material must cease immediately;</li> <li>b. All practicable steps must be taken to prevent the contaminated material becoming entrained in stormwater. Immediate steps must include, where practicable: <ul style="list-style-type: none"> <li>i. Diverting any stormwater runoff from surrounding areas away from the contaminated material; and</li> <li>ii. Minimizing the exposure of the contaminated material, including covering the contaminants with an impervious cover;</li> </ul> </li> <li>c. Notification of the Canterbury Regional Council, Attention: Contaminated Sites Manager, within 24 hours of the discovery;</li> <li>d. Earthworks within ten metres of discovered contaminant soil or material must not recommence until a suitably qualified and experienced contaminated land practitioner (SQEP) confirms to Canterbury Regional Council, Attention: Compliance Manager, that continuing works does not represent a significant risk to the environment;</li> </ul> <p>All records and documentation associated with the discovery must be kept and copies must be provided to the Canterbury Regional Council upon request.</p>
27.	<ul style="list-style-type: none"> <li>a. Any material removed from the site during the works that is potentially or confirmed as contaminated, must be disposed of at a facility authorised to receive such material.</li> <li>b. Disposal dockets shall be retained and provided to Canterbury Regional Council upon request, Attention: Compliance Manager.</li> </ul>
	<b>Spills</b>
28.	<p>All practicable measures must be taken to avoid spills of fuel or any other hazardous substances within the site. These measures must include:</p> <ul style="list-style-type: none"> <li>a. Refueling of machinery and vehicles must not occur within 20 metres of: <ul style="list-style-type: none"> <li>i. open excavations;</li> <li>ii. exposed groundwater; and</li> <li>iii. stormwater devices.</li> </ul> </li> <li>b. A spill kit must be kept on site that is capable of absorbing the quantity of oil and petroleum products that may be spilt on site at any one time, remains on site at all times.</li> <li>c. In the event of a spill of fuel or any other hazardous substance, the spill must be cleaned up as soon as practicable, the stormwater system must be inspected and cleaned, and measures taken to prevent a recurrence;</li> <li>d. The Canterbury Regional Council, Attention: Compliance Manager, must be informed within 24 hours of a spill event exceeding five litres and the following information provided:</li> </ul>



	<ul style="list-style-type: none"> <li>i. The date, time, location and estimated volume of the spill;</li> <li>ii. The cause of the spill;</li> <li>iii. the type of hazardous substance(s) spilled;</li> <li>iv. Clean up procedures undertaken;</li> <li>v. Details of the steps taken to control and remediate the effects of the spill on the receiving environment;</li> <li>vi. An assessment of any potential effect of the spill; and</li> </ul> <p>Measures to be undertaken to prevent a recurrence.</p>
	<b>Artesian Aquifer Interception</b>
29.	<p>In the event of an interception of unanticipated levels of artesian flows, all practicable measures must be undertaken to remedy or mitigate any change in aquifer pressure water quality or temperature. This must include:</p> <ul style="list-style-type: none"> <li>a. The contractor must immediately cease all works within the immediate area of excavation that caused the interception of the artesian flows;</li> <li>b. The contractor must determine and document whether the flow is constant or increasing, if the turbidity is constant or increasing and if the flow is confined to the excavation.</li> <li>c. The contractor must notify the site engineer and/or other appropriate personnel to determine the emergency measures required to arrest the artesian flow. Emergency measures must include, but not be limited to: <ul style="list-style-type: none"> <li>i. The installation of a layer of impermeable material to the extent required to reform a capping layer over the aquifer to prevent the upward movement of groundwater through the confining layer; or</li> <li>ii. Inserting a vertical pipe in the aquifer interception point (if practicable) and provide for a secure seal against the pipe to enable the stabilisation of the artesian flow in the pipe, and to determine the above ground water level to assess any further measures.</li> </ul> </li> <li>d. The temporary artesian flow beyond the excavation must be controlled and mitigated with appropriate erosion and sediment control measures; e. The Canterbury Regional Council, Attention: Compliance Manager must be notified as soon as practicable but no later than two working days after the interception; and Upon remediation and arresting of flow from the aquifer interception, the construction methodology must be reconsidered and, if required, revised to avoid future interceptions of the aquifer.</li> </ul>
	<b>Accidental Discovery of Archaeological Material</b>
30.	<ul style="list-style-type: none"> <li>a. Any activity which may modify, damage or destroy a pre-1900 archaeological site or material must follow the archaeological authority process under the Heritage New Zealand Pouhere Taonga Act 2014. An archaeological authority is required from Heritage New Zealand to modify, damage or destroy any archaeological site, whether recorded or not in the New Zealand Heritage List/Rārangī Kōrero.</li> <li>b. In the event of accidental discovery of any archaeological material, all works must cease immediately in the part of the site known, or suspected, to be an archaeological site.</li> <li>c. The Canterbury Regional Council, Heritage New Zealand Pouhere Taonga and Papatipu Rūnanga, as well as the New Zealand Police in the case of discovery of kōiwi/human bones, must be informed immediately of the disturbance, and the archaeological authority process under the Heritage New Zealand Pouhere Taonga Act 2014 must be followed.</li> <li>d. In the event of the accidental discovery of Māori archaeological sites or material, the attached accidental discovery protocol for Māori archaeology must be followed in addition to the process under the Heritage New Zealand Pouhere Taonga Act 2014.</li> <li>e. To ensure that all statutory and cultural requirements have been met, any works in the part of the site subject to the archaeological discovery must not recommence until authorised by the Canterbury Regional Council and: <ul style="list-style-type: none"> <li>i. Upon completion of the archaeological authority process referred to under (c); and</li> <li>ii. In the event of the accidental discovery of Māori archaeological sites or material, and in addition to (c) upon completion of the process referred to under (d); and</li> <li>iii. In the event of the discovery of kōiwi/human bones, immediately advise the New Zealand police.</li> </ul> </li> </ul>
	<b>After Completion of Works</b>
31.	<p>Within two weeks of the completion of each stage of works authorised by this resource consent:</p> <ul style="list-style-type: none"> <li>a. All disturbed areas must be stabilized and/or revegetated; and</li> <li>b. All spoil and other waste materials from the works must be removed from site.</li> </ul>



32.	Within 3 months of the completion of earthworks on the site, a Site Validation Report (SVR) shall be provided to Canterbury Regional Council. The SVR shall be prepared by a SQEP in contaminated land.
	<b>Administration</b>
33.	The Canterbury Regional Council may annually, on the last working day of May or November, serve notice of its intention to review the conditions of this resource consent for the purposes of: <ol style="list-style-type: none"> <li>Dealing with adverse effect on the environment which may arise from the exercise of this resource consent, and which is not appropriate to deal with at a later stage; or</li> <li>Requiring the adoption of the best practicable option to remove or reduce any adverse effect on the environment.</li> </ol>
34.	If this resource consent is not exercised before 31 January 2031, it lapses in accordance with Section 125 of the Resource Management Act 1991.  <i>Advice note: Exercised is defined as implementing any requirements to operate this consent <u>and</u> undertaking the activity as described in these conditions and/or application documents.</i>

## Resource Consent: CRCXXX (s14 – water permit)

Applicant: NTP Development Holdings Limited

	Limits
1.	The activities authorised by this consent shall be limited to: <ol style="list-style-type: none"> <li>The temporary instream damming of the Paparua Water Race Network at 173 Pound Road, legally described as: Lot 3 DP 33334, Lot 2 DP 33334, Lot 10 DP 23834, Lot 2 DP 23834, Lot 1 DP 33334, Lot 2 DP 20738, Lot 1 DP 20738, Lot 2 DP 38418, Lot 7 DP 23834, Lot 6 DP 23834, Lot 2 DP 24156, Lot 1 DP 24156, Lot 1 DP 23834, Lot 1 DP 38418 to facilitate the take and use of water for non-consumptive purposes; and</li> <li>The temporary non-consumptive take and use of water from the Paparua Water Race Network at 173 Pound Road, legally described as: Lot 3 DP 33334, Lot 2 DP 33334, Lot 10 DP 23834, Lot 2 DP 23834, Lot 1 DP 33334, Lot 2 DP 20738, Lot 1 DP 20738, Lot 2 DP 38418, Lot 7 DP 23834, Lot 6 DP 23834, Lot 2 DP 24156, Lot 1 DP 24156, Lot 1 DP 23834, Lot 1 DP 38418 for the purpose of bypassing flows around the locations of the culvert installation.</li> </ol>
2.	The works shall be undertaken in accordance with the attached design plan, plan CRCXXX which forms a part of this consent.
3.	Water may only be taken under Condition (1) for no longer than 12 weeks as an overall total, with no longer than 2 weeks continuous.
4.	All water taken in accordance with Conditions 1 and 2 must be discharged back into the lateral channel of the PWNR.
	<b>Water Take</b>
5.	Over pumping of the Paparua Water Race Network must be carried out at a rate that maintains existing water levels at the time of pumping. Over-pumping must not result in a reduction of water levels in the upstream reach.
6.	Water taken from over-pumping the Paparua Water Race Network and removing water from the culvert installation sites shall be returned to the Paparua Water Race Network, immediately downstream of the culvert installation sites.
	<b>Fish Protection</b>
7.	Any pump used to take water in Condition (1) must be fitted with fish screens in general accordance with the Christchurch City Council's "Standards for Temporary Fish Screens on Christchurch City Council Projects" (2023).



	<b>Administration</b>
8.	The Canterbury Regional Council may, once per year, on any of the last five working days of May or November, serve notice of its intention to review the conditions of this consent for the purposes of: a. Dealing with any adverse effect on the environment that may arise from the exercise of the consent or b. Requiring the adoption of the best practicable option to remove or reduce any adverse effect on the environment.
9.	If this resource consent is not exercised before X January 2031, it lapses in accordance with Section 125 of the Resource Management Act 1991.  <i>Advice note: 'Exercised' is defined as implementing any requirements to operate this consent and undertaking the activity as described in these conditions and/or application documents.</i>

## Resource Consent CRCXXX (s15 – Discharge Permit – Construction Phase)

Applicant: NTP Development Holdings Limited

	<b>Limits</b>
1.	The discharges authorised under this resource consent is limited to: a. The discharge of surface water to the lateral channel of the Paparua Water Race Network at Pound Road (173 Pound Road, legally described as: Lot 3 DP 33334, Lot 2 DP 33334, Lot 10 DP 23834, Lot 2 DP 23834, Lot 1 DP 33334, Lot 2 DP 20738, Lot 1 DP 20738, Lot 2 DP 38418, Lot 7 DP 23834, Lot 6 DP 23834, Lot 2 DP 24156, Lot 1 DP 24156, Lot 1 DP 23834, Lot 1 DP 38418) associated with the non-consumptive take and use authorised by resource consent CRCXXXX. b. Sediment-laden stormwater from exposed areas during earthworks to land via temporary soak pits within the site at Pound Road (173 Pound Road, legally described as: Lot 3 DP 33334, Lot 2 DP 33334, Lot 10 DP 23834, Lot 2 DP 23834, Lot 1 DP 33334, Lot 2 DP 20738, Lot 1 DP 20738, Lot 2 DP 38418, Lot 7 DP 23834, Lot 6 DP 23834, Lot 2 DP 24156, Lot 1 DP 24156, Lot 1 DP 23834, Lot 1 DP 38418).
2.	Sediment laden stormwater must be discharged: a. In accordance with the Erosion and Sediment Control Plan (ESCP) required by Condition (X) of this resource consent; b. Onto and/or into land via temporary soak pits.
	<b>Prior to Commencement of Works</b>
3.	Prior to commencement of the works described in Condition (1) all personnel working on the site must be made aware of, and have access to, the following: a. The contents of this resource consent document and all associated erosion and sediment control plans and other discharge treatment methodologies; b. Resource Consents CRCXXX and CRCXXX and all associated documents.
4.	All erosion and sediment control measures detailed in the ESCP required by Condition (6) of this resource consent must be installed prior to the commencement of any earthworks or stripping of vegetation and topsoil occurring on the site.
5.	At least 10 working days prior to the commencement of works on site, the Canterbury Regional Council, Attention: Compliance Manager (via <a href="mailto:ECinfo@ecan.govt.nz">ECinfo@ecan.govt.nz</a> ) must be informed of the commencement of works.
	<b>Erosion and Sediment Control</b>





6.	<p>The discharges authorised under this resource consent must occur in accordance with an ESCP. The ESCP must:</p> <ul style="list-style-type: none"> <li>a. Detail best practicable sediment control measures that will be implemented to ensure compliance with the conditions of this resource consent;</li> <li>b. Be prepared by a suitably qualified person with experience in erosion and sediment control in accordance with: <ul style="list-style-type: none"> <li>i. Canterbury Regional Council's <i>Erosion and Sediment Control Toolbox for the Canterbury Region</i> (ESCT), which can be accessed under <a href="http://escanterbury.co.nz/">http://escanterbury.co.nz/</a>; or</li> <li>ii. An equivalent industry guideline. If an alternative guideline is used, the ESCP must provide details of the relevant alternative methods used and an explanation of why they are more appropriate than the ESCT; and</li> </ul> </li> <li>c. Be signed by an engineer or suitably qualified person with experience in erosion and sediment control, confirming that the erosion and sediment control measures for the site are appropriately sized and located in accordance with the ESCT or alternative guideline.</li> </ul>
7.	<p>The ESCP must:</p> <ul style="list-style-type: none"> <li>a. Include a map showing the location of all works;</li> <li>b. Detailed plans showing the location of sediment control measures, on-site catchment boundaries, and sources of run-off;</li> <li>c. Detail how best practicable measures are taken to minimize discharges of sediment-laden stormwater run-off beyond the boundaries of the site; <ul style="list-style-type: none"> <li>i. include drawings and specifications of designated sediment control measures, if these are not designed and installed in accordance with the ESCT;</li> <li>ii. Detail the methodology for stabilizing the site entrance and exit points and any measures employed to prevent off-site tracking of sediment and other materials from the site;</li> </ul> </li> <li>d. Include a confirmation that the erosion and sediment control devices have been sized appropriately in accordance with the ESCT;</li> <li>e. Include a programme of works, including a proposed timeframe for each stage of the works and the earthworks methodology;</li> <li>f. Detail the management of any stockpiled material;</li> <li>g. Detail inspection and maintenance of the sediment control measures;</li> <li>h. Detail sampling procedures and protocols;</li> <li>i. Define the discharge points where stormwater is discharged onto land / infiltrates into land;</li> <li>j. Include a description of dust mitigation to be used and details of best practicable options to be applied to mitigate dust and sediment discharge beyond the site boundary;</li> <li>k. Detail the methodology for stabilizing the site if works are paused for more than five working days or abandoned;</li> <li>l. detail the methodology for stabilizing the site and appropriate decommissioning of all erosion and sediment control measures after works have been completed; and</li> <li>m. include measures such as Chemical Treatment Plan should the use of water treatment chemicals be required.</li> </ul>
8.	<p>The ESCP must be submitted to the Canterbury Regional Council Attention: Compliance Manager, after the commencement of the resource consent and at least 10 working days prior to works commencing.</p>
9.	<p>The ESCP may be amended at any time. Any amendments must be:</p> <ul style="list-style-type: none"> <li>a. Only for the purpose of improving the efficacy of the erosion and sediment control measures and must not result in reduced discharge quality; and</li> <li>b. For the purpose of applying best practicable measures to mitigate sediment transport off-site;</li> <li>c. Consistent with the conditions of this resource consent; and</li> <li>d. Submitted in writing to the Canterbury Regional Council, Attention: Compliance Manager, prior to any amendment being implemented.</li> </ul>
10.	<p>Erosion and Sediment Control measures must be inspected at least once per day, as well as following any rainfall event that results in more than five millimetres of rainfall at the site. Any accumulated sediment must be removed, and repairs made, as necessary, to ensure effective functioning of measures and devices. Records of any inspections must be kept and provided to the Canterbury Regional Council on request.</p>





	<b>During the works</b>
11.	<p>The discharge to surface water described in Condition 1(a) must not at any time:</p> <ul style="list-style-type: none"> <li>a. Have a concentration of Total Suspended Solids (TSS) exceeding 50 milligrams per litre; and</li> <li>b. Result in within the receiving waterbodies: <ul style="list-style-type: none"> <li>i.the production of any oil or grease films;</li> <li>ii.the production of any floatable or suspended materials;</li> <li>iii.the production any sludge or emulsion deposited on the bed.</li> </ul> </li> </ul>
12.	<ul style="list-style-type: none"> <li>a. Prior to the discharge of water in accordance with Conditions (1)(a) of this resource consent, a set of laboratory calibrated samples must be made up in clear bottles containing the following concentrations of TSS: <ul style="list-style-type: none"> <li>i. 0 milligrams per litre;</li> <li>ii.50 milligrams per litre;</li> <li>iii.100 milligrams per litre;</li> </ul> </li> <li>b. The calibrated samples must be: <ul style="list-style-type: none"> <li>i. prepared using representative soil samples from the site and then calibrated by a suitable laboratory to the unique combination of soil types at the site and the TSS concentrations detailed under (a); and</li> <li>ii.be replaced by a newly prepared sample every six months.</li> </ul> </li> <li>c. The set of calibrated samples must be held on site.</li> <li>d. Records of the laboratory calibration, including records of replacement samples prepared must be kept and provided to Canterbury Regional Council on request.</li> </ul>
13.	<p>During the discharge to surface water described in Condition (1)(a), samples of discharge water must be:</p> <ul style="list-style-type: none"> <li>a. Taken by a suitably qualified person and in accordance with best practicable sampling methodology;</li> <li>b. Collected in clean containers at the end of the sediment treatment system prior to the discharge to land or water;</li> <li>c. Collected one, two, four, and 24 hours after the discharge has commenced, and once per day thereafter if discharge exceeds one working day; and</li> <li>d. Visually compared to the calibrated samples prepared in accordance with Condition (X).</li> </ul>
14.	<p>If it becomes apparent at any stage during water quality monitoring detailed in Conditions (X) and/or (X) that a maximum TSS concentration of 50 milligrams per litre in the discharge will not, or is unlikely to be achieved, or if the visual assessment and observations undertaken in accordance with Condition (X) indicate a sheen of oil or grease or discoloration, or any sludge or emulsion below the water surface, then:</p> <ul style="list-style-type: none"> <li>a. the discharge must cease immediately;</li> <li>b. the discharge can only recommence once amendments have been made to the treatment process such that: <ul style="list-style-type: none"> <li>i. a TSS concentration of 50 milligrams per litre in the treated discharged is achieved;</li> <li>ii. the source of the sheen of oil or grease, discoloration, or any sludge or emulsion below the water surface, has been removed.</li> </ul> </li> </ul>
15.	<p>All practicable measures must be taken to:</p> <ul style="list-style-type: none"> <li>a. minimize soil disturbance to that necessary to minimise the potential for sediment-laden stormwater runoff to be generated;</li> <li>b. Prevent soil erosion as a result of stormwater runoff generated from the works area;</li> <li>c. Avoid placing excavated material in a position where it may become entrained in stormwater runoff and discharged to: <ul style="list-style-type: none"> <li>i. Any surface water body;</li> <li>ii. Any neighbouring site; and/or</li> <li>iii. The CCC reticulated stormwater network.</li> </ul> </li> </ul>
16.	<ul style="list-style-type: none"> <li>a. Tracking of material off-site during the works must be avoided at all times.</li> <li>b. In the event that material is tracked off-site, the tracked material must be removed as soon as practicable.</li> </ul>
	<b>Stockpiling of Contaminated Material/Soil</b>



17.	<p>Stockpiling of contaminated material or soils must be avoided where possible. In the event that temporary stockpiling of suspected contaminated or contaminated material is required, then the contaminated material stockpiles must be managed as below:</p> <ul style="list-style-type: none"> <li>a. Stockpiled contaminated material or soils must be kept separate from uncontaminated excavated soils stockpiles and any virgin aggregate or other material also stockpiled on-site; and</li> <li>b. Stockpiled contaminated material must be placed on polythene sheeting or similar impervious material to prevent contamination of underlying material; and</li> <li>c. Stockpiled contaminated material must include a perimeter bund or berm installed to prevent runoff leaving the area and stormwater from other areas entering the stockpile area; and</li> <li>d. Stockpiled material must be covered or dampened during dry and windy conditions so as to prevent wind erosion; and</li> <li>e. If any rainfall is forecasted that has the potential to cause runoff from the stockpiles, or if the stockpiles are left overnight, over the weekend or over public holidays, the stockpiled material must be covered with plastic sheeting or a suitable material such as clean topsoil, or otherwise stabilised, to prevent stormwater runoff coming into contact with contaminated material.</li> </ul> <p><i>Advice note: For the purpose of this condition, temporary stockpiling means material being stockpiled for no longer than the overall construction period or the stage of construction if construction occurs in stages, whichever is the shorter period, and only for as long as reasonably necessary. The overall requirement to avoid, where possible, the stockpiling of contaminated material or soils prevails.</i></p>
	<b>Spills</b>
18.	<p>All practicable measures must be taken to avoid spills of fuel or any other hazardous substances within the site. These measures must include:</p> <ul style="list-style-type: none"> <li>a. Refueling of machinery and vehicles must not occur within 20 metres of: <ul style="list-style-type: none"> <li>i. open excavations;</li> <li>ii. exposed groundwater; and</li> <li>iii. stormwater devices.</li> </ul> </li> <li>b. A spill kit must be kept on site that is capable of absorbing the quantity of oil and petroleum products that may be spilt on site at any one time, remains on site at all times.</li> <li>c. In the event of a spill of fuel or any other hazardous substance, the spill must be cleaned up as soon as practicable, the stormwater system must be inspected and cleaned, and measures taken to prevent a recurrence;</li> <li>d. The Canterbury Regional Council, Attention: Compliance Manager, must be informed within 24 hours of a spill event exceeding five litres and the following information provided: <ul style="list-style-type: none"> <li>i. The date, time, location and estimated volume of the spill;</li> <li>ii. The cause of the spill;</li> <li>iii. the type of hazardous substance(s) spilled;</li> <li>iv. Clean up procedures undertaken;</li> <li>v. Details of the steps taken to control and remediate the effects of the spill on the receiving environment;</li> <li>vi. An assessment of any potential effect of the spill; and</li> <li>vii. Measures to be undertaken to prevent a recurrence.</li> </ul> </li> </ul>
	<b>Upon Completion of Works</b>
19.	<p>Erosion and sediment control measures must not be decommissioned until the site is stabilised and the stormwater system for the developed site is functioning. Decommissioning of the measures must be undertaken in the following order:</p> <ul style="list-style-type: none"> <li>a. All disturbed areas must be stabilised and re-vegetated within two weeks of the completion of the works;</li> <li>b. Any visible debris, litter, sediment and hydrocarbons must be removed from all sediment control measures and disposed at a suitable facility; and</li> <li>c. Erosion and sediment control measures must be removed.</li> </ul>



20.	Upon completion of works and the removal of erosion and sediment control measures, any visible sediment accumulated on impervious surfaces within or immediately adjacent to the works site must be removed to minimise the risk of sediment becoming entrained in stormwater. All sediment removed must be disposed of at a suitable facility.
	<b>Administration</b>
21.	The Canterbury Regional Council may, once per year, on any of the last five working days of May or November, serve notice of its intention to review the conditions of this consent for the purposes of: a. Dealing with any adverse effect on the environment that may arise from the exercise of the consent or b. Requiring the adoption of the best practicable option to remove or reduce any adverse effect on the environment.
22.	If this resource consent is not exercised by 31 January 2031, it lapses in accordance with Section 125 of the Resource Management Act 1991.  <i>Advice note: 'Exercised' is defined as implementing any requirements to operate this consent and undertaking the activity as described in these conditions and/or application documents.</i>

## Resource Consent: CRCXXXX (s15 – Discharge permit – Operational Phase)

Applicant: NTP Development Holdings Limited

	Limits
1.	The activity authorised under this resource consent is limited to the discharge of stormwater generated from: a. Roofs b. Roads c. Berms d. Footpaths e. Hardstand and impervious surface areas  associated with the proposed industrial subdivision 'Pound Road Industrial Development' labelled as 'Lots 1 to X' on Plan CRCXXXXA attached to and forming part of this consent.
2.	Stormwater must only be discharged onto and into land within the boundary of the site in accordance with Conditions (4) to (15) of this resource consent.
3.	Unless treatment is provided, the discharge of roof stormwater must not arise from: a. Copper building materials; or b. Unpainted galvanized sheet materials.
	<b>Individual Lot Stormwater Systems</b>
4.	Stormwater must be discharged into land via the following stormwater system: a. Stormwater from roofs shall be discharged via a sealed system that excludes all other stormwater to soakage pits; b. A minimum of one infiltration test at the location of each of the proposed soakage pits; c. The soakpits and associated detention shall have a minimum capacity to attenuate and dispose all rainfall events up to and including the 24 hour duration two percent annual exceedance probability event from the contributing catchment; d. Stormwater in excess of the specified event in Condition 4(d) must be directed towards the roading reserve.



5	<p>The individual lot soak pits must:</p> <ul style="list-style-type: none"> <li>a. Along with its associated detention, store and dispose of all stormwater from the contributing catchment for up to and including the 24 hour duration two percent annual exceedance probability event from the contributing catchment;</li> <li>b. Have a base that extends into free draining soil strata; and</li> <li>c. Have a factor of safety of three incorporated into the soak pit design to account for reduction of infiltration performance over time (clogging).</li> <li>d. Be sized and designed based on infiltration tests completed at the proposed soakpit location and target depth;</li> <li>e. Have a maximum depth to the base of 5.5 metres below natural ground level.</li> </ul>
7.	Stormwater generated within each individual site must only be discharged onto and into land within the boundary of each individual site.
8.	The discharges must not arise from a site where any of the activities or industries listed in Schedule 2 of the Land and Water Regional Plan attached as Appendix CRCXXX, which forms part of this consent, are conducted or operated.
9.	For the avoidance of doubt, Conditions (10) to (15) do not apply to the individual lot discharges from roof surfaces covered by Conditions (4) to (8).
<b>Overall Subdivision Stormwater System</b>	
10.	Stormwater from roads, footpaths, berms, hardstand areas, impervious surfaces, and excess stormwater run-off from industrial lots must be conveyed via kerb and channel to submerged outlet sumps and treated via a first flush infiltration basin and/or soakpits system to meet the water quality requirements of the Land and Water Regional Plan water quality outcomes and standards set out in Table 1, Schedules 5 and 8 and Section 5 to 15 (whichever applies) are being met or will be met prior to being discharged to ground as shown on the attached Plans CRCXXXXXXXB and CRCXXXXXXXC which forms part of this resource consent.
11.	<p>The infiltration basin and/or soakpits shall:</p> <ul style="list-style-type: none"> <li>a. Along with its associated detention, store and dispose of all rainfall events up to and including the 24 hour duration two percent annual exceedance probability event from the contributing catchment;</li> <li>b. Have a base that extends into free draining soil strata; and</li> <li>c. Have a factor of safety of [three] incorporated into the soak pit design to account for reduction of infiltration performance over time (clogging);</li> <li>d. Be sized and designed based on infiltration tests completed at the proposed soakpit location and target depth.</li> <li>e. Have a maximum depth to the base of 5.5 meters below natural ground level.</li> </ul>
12.	Where the capacity of the primary stormwater system is exceeded, stormwater must be directed towards the internal roading network and to the CCC stormwater network in Pound Road or Waterloo Road.
13.	All sumps must be fitted with submerged outlets capable of trapping at least 60 litres of hydrocarbons.
14.	Stormwater shall not pond in any open detention area for longer than 48 hours after the cessation of any storm event.
15.	Stormwater shall only be discharged onto and into land via the stormwater system detailed under Condition (10) of this resource consent.
<b>Design plans</b>	
16.	<p>At least 20 working days prior to the installation of the stormwater system the consent holder or lot owner shall submit to the Canterbury Regional Council, Attention Compliance Manager:</p> <ul style="list-style-type: none"> <li>a. Final detailed design plans for the stormwater system/component.</li> <li>b. A certificate signed by a Chartered Professional Engineer (CPEng) with stormwater system design and construction experience confirming that: <ul style="list-style-type: none"> <li>i. The stormwater system has been designed in accordance with the Conditions of this resource consent; and</li> </ul> </li> </ul>



	c. A statement signed by the CPEng confirming that they are competent to certify the engineering work.
17.	<p>At least 10 working days of the installation of the stormwater system, the consent holder shall submit to the Canterbury Regional Council, Attention: Compliance Manager:</p> <ul style="list-style-type: none"> <li>a. All as built design plans of the [stormwater system/component/etc.] installed;</li> <li>b. A certificate signed by a CPEng with stormwater system design and construction experience confirming that confirming that the installed [stormwater system/component/etc.] complies with the conditions of this resource consent; and</li> <li>c. A statement signed by the CPEng confirming that they are competent to certify the engineering work.</li> </ul>
	<b>Inspection and maintenance</b>
18.	<p>The soakage pits must be inspected at least once every six months, and the following maintenance carried out if necessary:</p> <ul style="list-style-type: none"> <li>a. Inspecting the [list of components] at least once every [three/six/twelve] month(s) depending on which first flush treatment solution has been designed for the individual site.</li> <li>b. Removing any visible hydrocarbons, debris or litter within ten working days of the inspection.</li> <li>c. Removing any accumulated sediment in the [infiltration components] within five working days of the inspection.</li> <li>d. Removing any accumulated sediment in the sumps and [component] when the sediment occupies more than one quarter of the depth below the invert of the outlet pipe.</li> <li>e. Repairing any scour or erosion within ten working days of the inspection.</li> </ul>
19.	Any material, including sediment, hydrocarbons and other contaminants removed in accordance with condition X of this consent shall be disposed of at a location or facility authorised to receive such material.
20.	<p>Records of the inspection and maintenance of the stormwater system must be kept. The records must include, but not be limited to, information that demonstrates compliance with Conditions X, X and X of this consent. Copies of these records must be provided to the Canterbury Regional Council on request. These records must include, but not be limited to:</p> <ul style="list-style-type: none"> <li>a. Date and details of inspections of the stormwater system;</li> <li>b. Date and details of any maintenance work, repairs and upgrades to the stormwater system, including removal of material and its disposal;</li> <li>c. Any complaints received about the stormwater discharge.</li> </ul>
	<b>Spills</b>
21.	<p>All practicable measures must be taken to avoid spills of fuel or any other hazardous substances within the site. These measures must include:</p> <ul style="list-style-type: none"> <li>a. Refueling of machinery and vehicles must not occur within 20 metres of: <ul style="list-style-type: none"> <li>i. open excavations;</li> <li>ii. exposed groundwater; and</li> <li>iii. stormwater devices.</li> </ul> </li> <li>b. A spill kit must be kept on site that is capable of absorbing the quantity of oil and petroleum products that may be spilt on site at any one time, remains on site at all times.</li> <li>c. In the event of a spill of fuel or any other hazardous substance, the spill must be cleaned up as soon as practicable, the stormwater system must be inspected and cleaned, and measures taken to prevent a recurrence;</li> <li>d. The Canterbury Regional Council, Attention: Compliance Manager, must be informed within 24 hours of a spill event exceeding five litres and the following information provided: <ul style="list-style-type: none"> <li>i. The date, time, location and estimated volume of the spill;</li> <li>ii. The cause of the spill;</li> <li>iii. the type of hazardous substance(s) spilled;</li> <li>iv. Clean up procedures undertaken;</li> <li>v. Details of the steps taken to control and remediate the effects of the spill on the receiving environment;</li> <li>vi. An assessment of any potential effect of the spill; and</li> </ul> </li> </ul>



	vii. Measures to be undertaken to prevent a recurrence.
22.	<p>All best practicable options shall be used to contain spills or leaks of any hazardous substance from being discharged via the stormwater system. These shall include, but not be limited to the following:</p> <ul style="list-style-type: none"> <li>a. Using a tank filling procedure to minimise spills during any fuel delivery;</li> <li>b. Making spill kits available to contain or absorb any hazardous substances used or stored on the site;</li> <li>c. Maintaining signs to identify the location of the spill kits; and</li> <li>d. Maintaining written procedures in clearly visible locations that are to be undertaken to contain, remove and dispose of any spilled hazardous substance.</li> </ul>
	<b>Administration</b>
23.	<p>The Canterbury Regional Council may, once per year, on any of the last five working days of May or November, serve notice of its intention to review the conditions of this consent for the purposes of:</p> <ul style="list-style-type: none"> <li>a. Dealing with any adverse effect on the environment that may arise from the exercise of the consent or</li> <li>b. Requiring the adoption of the best practicable option to remove or reduce any adverse effect on the environment.</li> </ul>
24.	<p>If this resource consent is not exercised before 31 January 2031, it lapses in accordance with Section 125 of the Resource Management Act 1991.</p> <p><i>Advice note: 'Exercised' is defined as implementing any requirements to operate this consent and undertaking the activity as described in these conditions and/or application documents.</i></p>