



Fencing				
PW	1.2m Post & Wire	H4 post, 4mm wire and H3.2 battens. Timber stained with approved stain colour		

  

Code	Botanical Name	Common Name	Grade	Spacing
<b>Specimen Trees - Streets</b>				
○	<i>Dacrydium cupressinum</i>	rimu	45L	Marked
○	<i>Dacrycarpus dacrydioides</i>	kahikatea	45L	Marked
<b>ERP Enhancement Riparian Planting</b>				
	<i>Astelia grandis</i>	swamp astelia	1L	1.5m
	<i>Austroderia fulvida</i>	toetoe	1L	1.5m
	<i>Blechnum novae-zelandiae</i>	kiokio	1L	1.5m
	<i>Carex virgata</i>	pukio / swamp sedge	1L	1.5m
5%	<i>Carpodetus serratus</i>	putaputaweta	10L	1.5m
	<i>Coprosma tenuicaulis</i>	swamp coprosma	1L	1.5m
5%	<i>Cordyline australis</i>	ti kouka	1L	1.5m
5%	<i>Leptospermum scoparium</i>	manuka	1L	1.5m
	<i>Machaerina sinclairii</i>	pepepe	1L	1.5m
5%	<i>Meliccytus ramiflorus</i>	mahoe	10L	1.5m
	<i>Phormium cookianum</i>	wharariki	1L	1.5m
1%	<i>Vitex lucens</i>	pūriri	10L	1.5m

**NOTES:**

All plans are to be read in conjunction with Awa Architecture Plan Set and Maven Civil Plan Set.

Prior to excavating tree pits and planting specimen trees, confirm on site there are no clashes with underground services. Notify the Landscape Architect if any clashes are likely to occur.

All trees shall be at least 1.5m high at the time of planting and once established must be maintained at a height of at least 3m thereafter (with the exception of any proposed fruit trees)



SHEET LOCATION PLAN - NTS

