

Takitimu North Link Stage 2 – ~~Proposed Draft~~ Resource Consent Conditions (25 February 2026)

Resource Consent RM24-0466- DC.01

The following resource consents authorise the Consent Holder to undertake activities associated with the construction, operation and maintenance of the Project:

- (a) Discharge permits under the RNRP (s15 RMA):
 1. Discharge: Discharging temporary contaminants to land, discharging temporary stormwater to water, discharge of chemical flocculants during earthworks, discharge of dewatering fluid, discharge of cement to groundwater during piling.
- (b) Resource consent under the Resource Management (National Environmental Standards for Freshwater) Regulations 2020 (Clause 45):
 1. Construction of specified infrastructure (Clause 45(5)): Discharge of water within, or within a 100m setback from, a Natural Wetland for the purpose of constructing specified infrastructure, and there is a hydrological connection, the discharge will enter the Natural Wetland and will or is likely to change the water level range or hydrological function of the Natural Wetland.

The resource consents are subject to the following conditions:

1 Definitions

- 1.1 The definitions that apply to this Consent, where relevant, are provided in Appendix 1.

2 Purpose

- 2.1 The purpose of this Consent is to authorise and set conditions for:
 - (a) The temporary discharge of sediment contaminated stormwater and dewatering fluid to land, to water or to land where it may enter water;
 - (b) The discharge of chemical flocculants during earthworks; and
 - (c) The discharge of cement to groundwater during piling, associated with the construction of the Project.

3 Consent lapse and expiry

- 3.1 Pursuant to section 123 of the RMA and Schedule 5, cl 26 of the FTAA, this Consent shall expire 20 years after the commencement of this Consent.
- 3.2 This Consent shall lapse 20 years after the commencement of this Consent.
- 3.3 The Conditions of this Consent relate to construction of the Project and only apply to construction activities. Upon Completion of Construction these conditions will no longer apply.

4 Location

- 4.1 The activities authorised by the Consents shall occur from near Loop Road (map reference: 1870005mN, 5823384mE NZTM2000) to the east of the Waipapa Stream (map reference: 1864989mN, 5827810mE NZTM2000), on land designated by the New Zealand Transport Agency under section 171 of the RMA for the construction, operation and maintenance of a State highway.

5 Review of consent conditions

- 5.1 BOPRC may serve notice on the Consent Holder under section 128(1) of the RMA of its intention to review the conditions of these Consents at any time within six months of the first, second, third and fourth anniversaries of the date of commencement of Construction Works, and thereafter five yearly. The purpose of such a review is to deal with any adverse effect on the environment which may result from the consented activity and which it is appropriate to deal with at a later stage.

6 General and Management Plans

- 6.1 ~~The Takitimu North Link – Stage 2 Project must be carried out in general accordance with the plans and information submitted with the Substantive Application for Approvals dated 1 August 2025 and supporting documents, except where they are amended through another process provided for in these conditions such as certification of a management plan or through the outline plan of works process.~~

- 6-16.2 The Consent Holder shall prepare, submit to BOPRC and implement the Management Plans (as defined in Appendix 1), in accordance with the decision pathway, timeframe and duration as specified in the relevant conditions of the Consents. If BOPRC advises (within the relevant timeframe) that a Management Plan that has been provided to the BOPRC for certification is not suitable to certify and provides reasons for this, the Consent Holder shall re-submit the Management Plan to BOPRC for certification in accordance with the requirements as specified in the relevant condition addressing that Management Plan.

- 6-26.3 Conditions 6.43 – 8.3 apply to all plans defined as a 'Management Plan' in Appendix 1 (unless stated otherwise).

- 6-36.4 The preparation of all Management Plans shall be undertaken and signed off by a SQEP (unless stated otherwise).

- 6-46.5 The Consent Holder may prepare Management Plans in parts to address specific activities or to reflect the staged implementation of Project Works.

- 6-56.6 The Consent Holder may update a Management Plan by submitting the amendment in writing to BOPRC for certification ~~or for information~~ in accordance with the requirements as specified in the relevant condition addressing that Management Plan.

- 6-66.7 The Consent Holder shall ensure that Management Plans, including any amendments, are accessible on-site and updated within 10 Working Days of any amendments being certified by BOPRC ~~or provided to BOPRC for information~~.

- 6-76.8 The Consent Holder shall provide drafts of the Management Plans (as defined in Appendix 1), including, where practicable, any updated Management Plans under Condition 6.5, to Pirirākau and Ngāti Taka before the Management Plan is to be provided to BOPRC in accordance with the corresponding timeframe requirement in the relevant Management Plan condition and shall provide at least 10 Working Days for their comments. The Consent Holder shall consider any written feedback received from Pirirākau and Ngāti Taka and incorporate suggestions from the written feedback as the Consent Holder considers appropriate. The relevant Management Plan shall include a summary of written feedback received from Pirirākau and Ngāti Taka, and outline how feedback has been incorporated into the Management Plan and, if not, the reasons for that.

7 Deemed-Certification-Approval of Management Plans

- 7.1 The Consent Holder shall not commence any Project Works (Construction Works, or Enabling Works, as applicable to the relevant Management Plan) within an area to which a Management Plan condition(s) applies until the required Management Plan has been certified ~~or otherwise provided to by BOPRC for information~~, in accordance with the relevant condition.

- 7-27.1 ~~If the applicable Management Plan (or amendment) required under these conditions has been submitted to BOPRC for certification in accordance with the relevant condition, and the number of Working Days specified in the condition for submission of the Management Plan to Council has passed, and BOPRC has not certified the Management Plan (or amendment), or advised that the Management Plan (or amendment) is not suitable to certify, the Management Plan will be deemed to~~

Commented [EW1]: Introduction of a "condition 1" that frames the conditions and approved works based on the specimen design - ensures flexibility around the outcome of the detailed design process and the management effects by way of management plans

Commented [EW2]: Any reference to for information has been removed. Applies to other conditions also. See decision report for further rationale.

~~have been certified and the Consent Holder may commence Project Works in accordance with the applicable Management Plan (or amendment) as submitted.~~

Commented [EW3]: Any reference to deemed certification has been removed. See decision report for further rationale.

8 Management Plan(s) for Enabling Works

- 8.1 Where a Management Plan is required to be prepared before the start of Project Works by a condition of the Consents, the Consent Holder may prepare an area or activity-specific Enabling Works version of that Management Plan(s) to authorise the Enabling Works covered by that Management Plan condition(s). A subsequent Management Plan will need to be prepared before the start of the remaining Project Works subject to those Management Plan condition(s).
- 8.2 Any Enabling Works version of a Management Plan shall be prepared in general accordance with the requirements of the applicable Management Plan condition(s), with the scope modified to be commensurate with the nature, scale and effects of the proposed Enabling Works and include an explanation of how it will be incorporated into any subsequent Management Plan(s).
- 8.3 At least 20 Working Days before the start of the relevant Enabling Works, the Enabling Works version of that Management Plan shall be provided to BOPRC for ~~information, or for~~ certification that it complies with the relevant conditions.

9 Use of Construction Equipment, Machinery and Other Plant

- 9.1 No fuel storage or machinery refuelling shall occur where fuel could enter a Waterbody in the event of a spillage.
- 9.2 The Consent Holder shall take all practicable measures to prevent fuels, lubricants, hazardous and/or dangerous materials, concrete or cement based substances from entering any Waterbody or surface water.

10 Chemical Treatment Management Plan

- 10.1 The Consent Holder shall prepare a **Chemical Treatment Management Plan (CTMP)**. The purpose of the CTMP is to determine whether chemical treatment will enhance the efficiency of sediment retention ponds and decanting earth bunds, and, if so, set out the details of a chemical treatment management system to achieve that outcome.
- 10.2 The CTMP shall include:
- (a) The protocols and procedures for bench testing to determine which ESC measures will benefit from the use of flocculants, including the effectiveness, suitability and optimal rates of application of the specific flocculant proposed to be applied (including assumptions);
 - (b) If the analysis in (a) indicates that chemical treatment will enhance the efficiency of sediment retention ponds and / or decanting earth bunds:
 1. The chemical flocculant(s) to be used;
 2. Details of the types of ESC devices to be treated;
 3. Specific design details including structures, methodology and timing of application of the flocculation system; calculations and dilution, including details of optimum dosage (and assumptions), and how chemical dosage has been adjusted to the minimum level necessary to achieve the most effective flocculent in terms of sediment removal;
 4. Chemical storage location(s) and methods for secure storage of chemical flocculants;
 5. Monitoring, maintenance and contingency management, including a record system and pH limits for discharges;
 6. A spill contingency plan, which will include:
 - i. A requirement to report spills directly to any Waterbody or drain to BOPRC as soon as is practicable; and

- ii. A record of any accidental spills (including date, location, Waterbody (if applicable), volume of spills and actions taken to recover spilled product) that the Consent Holder will update in the event that spills occur;
- iii. A list of equipment to be kept on site to deal with any spills; and
- iv. The contact details of the person responsible for the operation and maintenance of the chemical treatment system.

10.3 At least 20 Working Days before the start of Construction Works, the CTMP shall be submitted to BOPRC for certification that the CTMP satisfies the requirements of Condition 10.2.

10.4 The Consent Holder shall implement the CTMP for the duration of Construction Works.

11 Discharging Contaminants to Water or Land where it may enter water

11.1 The Consent Holder shall ensure that no discharge resulting from the exercise of this Consent shall result in any of the following at a point 50 metres downstream of discharge after reasonable mixing:

- (a) The production of conspicuous oil or grease films, scums or foams, or floatable or suspended materials;
- (b) Any conspicuous change in the colour or visual clarity;
- (c) Emission of objectionable odour;
- (d) Any significant adverse effect on aquatic life;
- (e) The natural temperature of water being changed by more than three degrees celsius; and
- (f) Aquatic organisms being rendered unsuitable for human consumption by the presence of contaminants.

11.2 The Consent Holder shall ensure that all sediment laden runoff from the site is treated by sediment retention and treatment structures. These structures are to be fully operational before bulk earthworks commence and shall be maintained by the Consent Holder to perform at least at 80% of their operational capacity.

ADVICE NOTES

- 1 The Consent Holder shall pay the BOPRC such administrative charges as are fixed from time to time by BOPRC in accordance with section 36 of the RMA.
- 2 The Consent Holder shall send all monitoring reports and notification required by these conditions to the Regulatory Compliance Manager, PO Box 364, Whakatāne 3158, or email compliance_data@boprc.govt.nz (compliance reporting) or notify@boprc.govt.nz (compliance notifications).
- ~~3 For the avoidance of doubt, the deemed certification process in Condition 7 applies to Management Plan(s) for Enabling Works.~~
- 4 Consent RM25-0466-LC.01 also contains conditions that may be relevant to this Consent.

DRAFT

APPENDIX 1 - DEFINITIONS

The table below defines the acronyms and terms used in these conditions. Defined terms are capitalised.

Abbreviation/term	Meaning/definition
ARI	Average recurrence interval (the average time period between rainfall or flow events that equal or exceed a given magnitude).
At Risk and / or Threatened Species	Species identified as 'at risk' and / or 'threatened' under the relevant New Zealand Threat Classification series.
BOPRC	Bay of Plenty Regional Council, being the Chief Executive, or authorised delegate.
Clean fill	Has the same meaning as in the ' <i>The WasteMINZ Technical Guidelines for Disposal to Land Version 3.1 (2023)</i> '.
CLMG1	Ministry for the Environment <i>Contaminated land management guidelines No 1: Reporting on contaminated sites in New Zealand</i> (Revised 2021).
CLMG5	Ministry for the Environment <i>Contaminated land management guidelines No 5: Site investigation and analysis of soils</i> (Revised 2021).
Completion of Construction	When construction of the Project (or the relevant part of the Project) is complete, and the Project (or the relevant part of the Project) is operational.
Consent	The relevant consent or consents that the conditions apply to, being: <ul style="list-style-type: none"> • RM25-0466-LC.01; and / or • RM25-0466-LC.02; and / or • RM25-0466-BC.01; and / or • RM25-0466-WT.01; and / or • RM25-0466-DC.02; and / or • RM25-0466-DC.01; and / or • RM25-0466-DC.03; and / or • RM25-0466-WT.02.
Consents	Consents RM25-0466-LC.01, RM25-0466-LC.02, RM25-0466-BC.01, RM25-0466-WT.01, RM25-0466-DC.02, RM25-0466-DC.01, RM25-0466-DC.03, RM25-0466-WT.02 (unless otherwise specified).
Consent Holder	New Zealand Transport Agency Waka Kotahi
Construction Works	Activities undertaken to construct the Project, excluding Enabling Works.

Abbreviation/term	Meaning/definition
Designation	Designation D203 (Road purposes – State Highway 2) and Designation D181 (Road for access to State Highway 2) in the Western Bay of Plenty District Plan.
Designation Boundary	The boundary of the area of land subject to the Proposed Designation.
DOC	The Department of Conservation
Enabling Works	<p>Preparatory works and investigations to enable Construction Works, including the following activities:</p> <ul style="list-style-type: none"> • Archaeological investigations • Geotechnical investigations • Formation of access for site investigations • Establishing construction yards and offices • Constructing and sealing (if necessary) access roads and accesses to private properties and the Project • Contaminated land investigations • Demolition or removal works, including contaminated land clearance • Fencing • Vegetation protection or removal works • Protection and relocation of utilities • Establishment of mitigation measures (such as screen planting) for Enabling Works
ESC	Erosion and Sediment Control
FTAA	Fast Track Approvals Act 2024
Large Storm Event	A 10 year average recurrence interval storm or larger storm event

Abbreviation/term	Meaning/definition
Management Plan(s)	<p>The following plans and reports (which are collectively referred to as Management Plans):</p> <ul style="list-style-type: none"> • Erosion and Sediment Control Plan • Site Specific Erosion and Sediment Control Plan • Construction Management Plan • Biosecurity Management Plan • Construction Air Quality Management Plan • Chemical Treatment Management Plan • Ecological Management Plan including subplans as follows: <ul style="list-style-type: none"> ○ Marine Monitoring Plan ○ Wetland Management Plan ○ Aquatic Fauna Management and Monitoring Plan ○ Avifauna Management Plan ○ Bat Management Plan if required under LC.01 Condition 27.2 ○ Stream Management and Monitoring Plan • Culverts and Stream Hydraulic Design Report • Groundwater Drawdown Monitoring Plan • Detailed Site Investigation • Contaminated Site Management Plan • Remedial Action Plan if required under DC.02 Condition 11.1 • Site Validation Report if required under DC.02 Condition 12.1 • Works Completion Report if required under DC.02 Condition 14.1 • Tangata Whenua Values Monitoring and Management Plan • Stormwater Operation and Maintenance Plan • Final Stormwater Design
Merrin Wetland	The Wetland complex identified in Schedule 1 to Appendix 1.

Abbreviation/term	Meaning/definition
Natural Wetland(s)	<p>A Wetland that is not:</p> <ul style="list-style-type: none"> (a) in the coastal marine area; (b) a deliberately constructed wetland, other than a wetland constructed to offset impacts on, or to restore, an existing or former natural inland wetland; or (c) a wetland that has developed in or around a deliberately constructed water body, since the construction of the water body; or (d) a wetland that: <ul style="list-style-type: none"> (i) is within an area of pasture used for grazing; and (ii) has vegetation cover comprising more than 50% exotic pasture species; unless (iii) the wetland is a location of a habitat of a threatened species identified under clause 3.8 of the National Policy Statement for Freshwater Management 2020.
Ōmokoroa Wetland	The Wetland complex identified in Schedule 2 to Appendix 1.
PSI	Preliminary Site Investigation
Project	The construction, operation and maintenance of Takitimu North Link Stage 2.
Project Representative	The person or persons appointed by the Consent Holder (or their nominated contractor) to be the main and readily accessible point of contact for anyone wanting information about the Project.
Project Works	All Enabling Works and Construction Works.
Trigger Event	An event in which there is greater than 100mm of rainfall over any 24 hours, 50mm rainfall within 6 hours, or rainfall intensity of 25mm/hr.
RMA	Resource Management Act 1991
RNRP	Bay of Plenty Regional Natural Resources Plan
SSESCP	Site Specific Erosion and Sediment Control Plan
Stabilisation, Stabilised, Stabilised area	Refers to an area inherently resistant to erosion, such as rock, or an area rendered resistant to erosion by the application of stabilisation methods, such as the use of mulch, aggregate, geotextile, or other method approved through the certified SSESCP. Where vegetation is to be used on a surface that is not otherwise resistant to erosion, the surface is considered stabilised once an 80% vegetation cover has been established.
Stage of Work	A specific works area or new land disturbing activity associated with construction of the Project as nominated by the Consent Holder.

Abbreviation/term	Meaning/definition
SQEP	Suitably Qualified Experienced Person - a person (or persons) who can provide sufficient evidence to demonstrate their suitability and competence in the relevant field of expertise.
Unwanted organisms (and/or pests)	As defined in s2 of the Biosecurity Act 1993.
Watercourse(s)	Perennial or intermittent rivers and streams, including modified rivers and streams, but not overland flow paths, artificial watercourses, conveyance channels, Natural Wetlands or Wetlands.
Waterbody	A Watercourse, lake, Wetland, Natural Wetland or aquifer
Wetland(s)	Includes permanently or intermittently wet areas, shallow water, and land water margins that support a natural ecosystem of plants and animals that are adapted to wet conditions.
Working Day	<p>A day of the week other than—</p> <ul style="list-style-type: none"> (a) Saturday, a Sunday, Waitangi Day, Good Friday, Easter Monday, Anzac Day, the Sovereign's birthday, Te Rā Aroki a Matariki/Matariki Observance Day, and Labour Day; and (b) if Waitangi Day or Anzac Day falls on a Saturday or a Sunday, the following Monday; and (c) a day in the period commencing on 20 December in any year and ending with 10 January in the following year.

SCHEDULE 1 TO APPENDIX 1 – MERRIN WETLAND COMPLEX



Indicative extent of Merrin Wetland restoration (white outline), freshwater wetland (blue outline/fill), saltmarsh wetland (green outline/fill).

SCHEDULE 2 TO APPENDIX 1 - ŌMOKOROA WETLAND COMPLEX



Indicative extent of Ōmokoroa Wetland restoration (white outline), freshwater wetland (blue outline/fill), saltmarsh wetland (green outline/fill).