

Memo – Earthworks

To: Vineway Limited

From: Jordan Chiswell
Cc: James Kitchen,
Date: 30/06/2025

Subject:- Addendum to Earthworks Report

This memo supersedes table 1 in section 5.2 of the Delmore Earthworks Report

Area	Unit	Stage 1	Stage 2AB	Stage 2CDE	Site Wide	Assumptions
Earthworks area	m²	240,000	155,000	189,000	584,000	
Net Cut Volume	m³	377,000	356,000	480,000	1,213,000	Finish surface to existing
						topo level
Topsoil Strip	m³	48,000	31,000	37,800	116,800	Assumed 200mm deep
Volume						topsoil across earthworks
						area
Maximum Cut	m				15	
Depth						
Net Fill Volume	m³	351,000	283,000	380,000	1.014,000	Finish surface to existing
						topo level
Topsoil Respread	m³	48,000	31,000	37,800	116,800	Assumed 200mm deep
Volume						across earthworks area
Maximum Fill depth	m				15	
Clay	m³	26,000	73,000	100,000	199,000	Bulk volume, no compaction
Deficit/(surplus)		excess cut	excess cut	excess cut	excess cut	accounted for
Topsoil	m³	0	0	0	0	There are a number of
Deficit/(surplus)						locations throughout site for
						excess topsoil to be disposed
						safely if required
Total Earthworks	m³	728,000	639,000	860,000	2,227,000	
Volume						
(Cut + Fill)						