



Geotechnical Report


Proposed Delmore Residential Development
Russell Road and Upper Ōrewa Road, Wainui


Geotechnical Report


Proposed Delmore Residential Development

Russell Road and Upper Ōrewa Road, Wainui

Report prepared for: Vineway Ltd

Report prepared by: 

Report reviewed by:  cal Engineer, CPEng

Report approved for issue by: 

Report reference: 240065-Q

Date: 19 December 2025

Copies to: Vineway Ltd Electronic copy
Riley Consultants Ltd Electronic copy

Issue	Details	Date
1.0	Final	19 December 2025

Contents

1.0	Introduction	1
2.0	Project Background	1
2.1	Site Description	1
2.2	Proposed Development	2
2.3	Site Geology	3
2.4	Aerial Photographs and GIS Records	4
2.5	Geomorphology	4
2.5.1	Stage 1	4
2.5.2	Stage 2	5
2.6	Related Reports	6
3.0	Investigations	7
3.1	Fieldwork	7
3.2	Laboratory Testing	8
3.2.1	Water Content Testing	8
3.2.2	Standard Compaction Testing	8
3.2.3	Atterberg Limit Testing	8
3.2.4	Particle Size Distribution Testing	8
3.2.5	Soaked CBR Testing	8
4.0	Investigation Findings	8
4.1	Topsoil	9
4.2	Alluvium	9
4.3	Colluvium	9
4.4	East Coast Bays Formation	9
4.5	Northland Allochthon – Hukerenui Mudstone	10
4.6	Groundwater Level and Monitoring	10
4.7	Laboratory Test Results	11
4.7.1	Water Content	11
4.7.2	Standard Compaction	13
4.7.3	Atterberg Limits and Linear Shrinkage	14
4.7.4	Particle Size Distribution	14
4.7.5	California Bearing Ratio (CBR)	15
5.0	Geotechnical Considerations	15
5.1	Slope Stability	15
5.1.1	Qualitative Slope Stability Assessment	15
5.1.2	Quantitative Slope Stability Assessment	16
5.1.3	Geotechnical Model and Analysis Parameters	16
5.1.4	Quantitative Stability Analysis Results	18
5.1.5	Discussion on Slope Stability	45
5.1.6	Stability Enhancement Measures	46
5.1.7	PC120 Landslide Risk Assessment	47
5.1.7.1	Batter Stability	48
5.2	Groundwater Impact Assessment	49
5.2.1	Culvert Groundwater Drawdown	54
5.3	Liquefaction and Lateral Spreading	54
5.4	Building Foundations	54

5.5	Retaining Walls.....	55
5.6	Earthworks.....	56
5.6.1	Stripping and Site Preparation	56
5.6.2	Cut and Fill Materials.....	56
5.6.3	Rock Excavation	57
5.6.4	Cut Subgrade Protection	57
5.6.5	Erosion and Sediment Control.....	58
5.6.6	Compaction.....	58
5.6.7	Benching of Slopes	59
5.6.8	Underfill, Subsoil and Counterfort Drainage	59
5.7	Fill Induced Settlements	60
5.8	Rubbish Pits.....	60
5.9	Stormwater Control	61
5.10	Effluent Disposal	61
5.11	Services	62
5.12	Roads	63
5.13	Inspections	63
5.14	Proposed Geotechnical Consent Conditions.....	63
6.0	Further Input.....	63
7.0	Summary	64
8.0	Limitation.....	64

Appendices

Appendix A:	Field Investigation Data
Appendix B:	Typical Details – Piezometer Installation and Drainage
Appendix C:	Groundwater Monitoring Results
Appendix D:	Laboratory Test Results
Appendix E:	PC120 Landslide Risk Assessment
Appendix F:	Slope Stability Analysis
Appendix G:	Groundwater Impact Assessment
Appendix H:	Proposed Geotechnical Consent Conditions
Appendix I:	Riley Sketches: 240065-SK001; SK100, SK110 to -124; SK130 to -131; SK140 to -144; SK160 to -177, SK180 to -189, SK190 to -193 SK195 to -199

Geotechnical Report

Proposed Delmore Residential Development

Russell Road and Upper Ōrewa Road, Wainui

1.0 Introduction

The following report outlines a geotechnical engineering assessment for the proposed residential subdivision known as Delmore. The project involves the subdivision of just over 109ha in six (6) contiguous lots (88, 130, and 132 Upper Ōrewa Road and 53A, 53B, and 55 Russell Road) and construction of a master-planned urban, residential development of approximately 1,250 dwellings.

This report has been prepared by Riley Consultants Ltd (Riley) to support the consenting process for the proposed Delmore Development. It presents the results of sub-surface investigations, in-situ and laboratory soils testing and slope stability analysis together with our comments and recommendations pertaining to the satisfactory development of the site. It is intended to be used in support of a substantive application under the fast-track approvals process.

2.0 Project Background

2.1 Site Description

The site is located on the northern side of Russell Road and Upper Ōrewa Road, Wainui, comprising six rural properties including 53A Russell Road (Lot 1 DP 497022), 53B Russell Road (Lot 2 DP 497022), 55 Russell Road (Lot 1 DP 336616) and 88 Upper Ōrewa Road (Lot 2 DP 418770), 130 Upper Ōrewa Road (Lot 2 DP 153477) and 132 Upper Ōrewa Road (Lot 1 DP 153477). There is a paper road running north-south along the boundaries of 53B Russell Road and 88 Upper Ōrewa Road.

The site is bounded by neighbouring residential properties to the south and south-east, the Ara Hills residential development (currently under construction) to the north and east, and the Nukumea Scenic Reserve and other Significant Ecological Areas (SEA) to the north and west.

The site currently consists of lifestyle block/farm properties, comprising several associated residential dwellings, and an inactive deer farm. There are hay stores, cattle yards, farm sheds and shipping containers across the site. The vegetation comprises a combination of pasture, pine forest, native bush and windbreaks. The pine forest is in the north-eastern corner of the site while the bulk of the native bush is in the western and northern portions and generally confined within the alignment of the gullies. The pasture is generally located within the central and southern portions where there are 15m to 20m long windbreaks planted along paddock boundaries.

The site is characterised by a stream, which flows to the east through the middle of the site at 132 and 130 Upper Ōrewa Road, through the southern part of the site at 88 Upper Ōrewa Road and 53B and 53A Russell Road and then again through the middle of the site at 55 Russell Road.

All overland flow paths on-site flow down to this stream. The Auckland Council GeoMaps indicate an area of approximately 50m either side of the central stream, and smaller corridors around the tributary streams, are prone to flooding.

The topography of the site is characterised by gullies and slopes. In the eastern and central part of the site the moderate slopes, typically from 10° to 25° and steepening up to 27° in some places, grade from the top of the ridges and down into the gullies. At the eastern boundary, the maximum elevation difference from the top of the ridge down to the gully is approximately 45m at an approximate 20° gradient. The middle part of this area is shallower, with typical gradients between 5° and 15°, indicating a difference in underlying ground conditions. The western part of the site has more undulating and extreme topography, with steeper slopes, typically from 25° to 35°, steepening up to 40° to 45° in places, particularly around areas of existing instability. The elevation difference from the highest ridge in the northern part of the site down to the gully is approximately 65m.

There are multiple small, dammed farm ponds on the site that appear to be shallow (~2m-3m) depth:

- Southern portion of 130 Upper Ōrewa Road – ~300m²
- Central northern portion of 130 Upper Ōrewa Road – ~1500m²
- North-eastern portion of 53B Russell Road – ~100m²
- Western portion of 53B Russell Road – ~50m²

The central constructed pond within 130 Upper Ōrewa Road is damming watercourses flowing to the south and has formed behind a culvert causing a wetland to form with dense reed growth.

To the west of the northern constructed pond is an old farm structure once used for deer farming. To the east of the pond on the shallow slopes is a waste pit, covering an area of approximately 85m². There are other small storage sheds around site but most of the remaining farm structures are in the vicinity of the main dwelling on the property.

There are electrical and communication overhead lines, as well as other underground services, servicing the existing dwellings and properties on-site.

2.2 Proposed Development

The proposed development is understood to comprise approximately 1,213 residential lots and dwellings, neighbourhood parks, together with supporting transport and servicing infrastructure.

Subdivision and construction will occur in two stages, comprising six substages. Stage 1 comprises 53A, 53B and 55 Russell Road, and Stage 2 comprises properties 88, 130, and 132 Upper Ōrewa Road.

Preparatory earthworks across the site comprises cut of approximately 1,440,000m³ and fill of approximately 990,000m³. Earthworks plans indicate that cut and fill earthworks will take place over much of the site and be up to 15m depth. These earthworks are proposed to re-contour the site primarily to form the residential lots.

The designated two lane urban arterial road, running from SH1 and Grand Drive in the east along the site's northern side, and then down its western side to the southern boundary of the site, will be constructed as part of the project. There will be walking and cycling infrastructure along the side of this road. Homes within the site will be serviced by 27 local roads. The site's internal road network will connect to the external road network at three points. A total of 40 jointly owned access lots are used to connect the internal lots.

A total of 64 different housing typologies will be used across the site. These include stand-alone and duplex housing options. The ground floor areas of the houses range between 97m² to 175m². Each housing typology will be paired with typology-specific landscaping comprising mostly native species, with a combination of low, medium, and high-level vegetation.

Walkways will be provided throughout the site, with some routes provided from the site to the Scenic Reserve to the north. A neighbourhood park is shown indicatively within the middle of the site. Existing riparian native vegetation will be restored, and further enhancement planting will be undertaken. Existing areas of vegetation subject to consent notices will also be restored and enhanced with planting in places. These green spaces will be supported by on-street planting.

On-site effluent treatment will be provided by a temporary treatment plant located in the southern portion of Stage 1. Treated effluent is proposed to be disposed via specifically designed trenches located near the gully invert to the east of the treatment plant and areas of dripper lines at dispersed locations around Stage 1. The treatment plant, disposal trenches and dripper lines are being designed by Apex Water Ltd.

2.3 Site Geology

From a review of the 1:250,000 GNS Online Geological Map, the site is underlain by the following geological units:

- Northland Allochthon (Hukerenui Mudstone) – underlying the central/eastern portions of the site (central part of 53B Russell Road).
- East Coast Bays Formations – underlying most of the site.
- Pakiri Formation – underlying the northern part of the site.

The Waitemata Group deposits, represented as East Coast Bays Formation (ECBF) and Pakiri Formation (PF) materials, are sedimentary materials. The most widespread geological unit is the Miocene-age Waitemata Group that underlies the materials of the Northland Allochthon (NA) where present. The ECBF is described as comprising alternating sandstone and mudstone with variable volcanic content and interbedded volcanoclastic grit. The regional dip of the ECBF within the site is inferred to be 30° to the north-west. The PF comprises alternating thick bedded, volcanic rich, graded sandstone, and siltstone.

The materials of the Northland Allochthon are older materials that have been thrust over the younger ECBF and PF materials. The NA materials, mapped as Hukerenui Mudstone. These materials are typically described as sheared mudstone and are often red, green and grey in colour.

Tauranga Group Alluvium is also mapped as being present to the immediate south of the site. Based on-site stratigraphy and our experience with neighbouring sites, we consider that alluvial materials are likely to be present in the vicinity of waterways and gully inverts within the lower lying parts of the site. Tauranga Group generally comprises silts and sands, with the potential for localised peat lenses. These materials have generally been subjected to pre-consolidation; however, they may contain localised areas of very soft ground.

The approximate extent of the geological units is shown on the appended Riley Sketch SK131 in Appendix I.

2.4 Aerial Photographs and GIS Records

A review of historical aerial photographs circa 1940 available on Auckland Council (Council) GIS Maps and Retrolens Historical Image Resource was undertaken. Based on a desktop review of the photographs, no obvious signs of deep-seated global type movement were noted in the historical aerial photographs. However, shallow instability, likely confined to surficial soils similar to those observed on-site as a part of our assessment were evident. Detailed descriptions of such instabilities associated with moderate to steep sloping areas and gully features are outlined in the geomorphology section below.

2.5 Geomorphology

Geomorphological mapping was undertaken by Riley on 8 April 2024 for Stage 1 of the site and 1 November 2024 for Stage 2.

2.5.1 Stage 1

The site is situated within an approximately east-west trending valley that drains to the east, with Russell Road following a ridgeline to the south that forms a drainage divide. The topography is dominated by a number of generally north-south trending ridges and gullies that grade down to a stream at the base of the valley near the central portion of the site that flows toward the coast. There are tributary valleys and streams across the site that are to remain as part of the development. The site consists of three main tributary catchments, and approximately three minor catchments.

The more elevated areas of the north-eastern slopes consist of benches with gently inclined terraces above relatively short steeper slopes. The southern north facing slopes show signs of localised shallow instability, predominantly within the upper reaches of gully features.

There were areas of localised instability across the site. Areas of more significant instability were identified on the steeper slopes located to the north of 53B Russell Road, and near the centre of the 55 Russell Road to the east of the property boundary fence, north of the central stream.

The upper reaches of the southern trending gully at 53B Russell Road is dominated by hummocky undulating ground, with mid slope benches and swampy waterlogged ground with dense pockets of reeds. These characteristics are typically associated with shallow soil movement and poor drainage. This is an area inferred to be underlain by materials of the Northland Allochthon and is in the vicinity of the contact between geological units.

Within 55 Russell Road and to the east of the boundary fence with 53B, a notable more prominent relic slip is evident. This was observed as a broad scarp feature running perpendicular to the slope direction, approximately 100m in length. This runout from this shallow slump movement extends southward toward the central stream, and is characterised by hummocky, undulating and waterlogged ground. The runout has been incised over time, forming channels through the weaker unconsolidated material.

No obvious spring locations were noted during the geomorphological walkover on-site.

2.5.2 Stage 2

South

Stage 2 is located to the west of Stage 1 and extends around the same east-west trending valley feature with the same main west-east trending stream flowing through the site. The north-western portion of Stage 2 forms the head of a larger tributary catchment on the site, with a number of secondary tributary streams flowing south.

Along the southern boundary of Stage 2 a broad spur stems off from an approximately north-west trending ridgeline. Upper Ōrewa Road generally follows the ridgeline along the southern boundary of the site. An existing dwelling is situated centrally on this spur feature. The spur generally tapers out at moderate to steep slopes towards the west, north and east.

To the north and west of the spur, slopes generally grade at moderate to steep slopes into the stream of the east-west channel, to the north, and into a north-west orientated gully to the west. Dense vegetation is present within the gullies and adjacent the east-west orientated central stream. On the lower reaches of the northern slopes of the spur is a minor constructed pond for stock with an overflow to the north that leads into the central stream. Localised shallow instability was observed to the east of the spur, predominantly within the upper reaches of the gully feature.

There were noted areas of localised instability on the steeper slopes located to the north of the spur, the south facing slopes on the northern side of the central stream, and on the eastern side of the spur feature. The north facing steep slopes of the spur show evidence of soil creep as evidenced by small terrace features parallel to the slope and hummocky ground. There is a mid-slope bench that is waterlogged with pockets of reeds. The southern facing slopes on the northern side of the central stream show signs of large historic instability with a series of benches being formed. There is evidence of soil creep across adjacent slopes in the form of undulating and hummocky ground, terrace features, and trees tilted/rotated back in the direction of the slope.

In the eastern part of the southern site, there are two incised gullies sloping west into the vegetated central stream which show evidence of potential tunnel gully erosion. The presence of tunnel gully erosion is assessed to be attributed to the underlying ground conditions, likely more silty and sandy materials.

North

The east-west trending stream passes the toe of the spur within the southern portion of Stage 2 and extends to the western site boundary. It also branches to the north into the northern portion of Stage 2.

The northern portion of Stage 2 is dominated by a north-south facing valley basin. The western boundary consists of an approximately north-south orientated ridge, with a steep backdrop towards the west and more moderate to gentle runout towards the east towards the central stream. A prominent spur branches off the ridge toward the south-east toward the centre of the site.

The northern boundary consists of a south-west-north-east orientated ridgeline with multiple approximately south trending spurs and erosional gullies extending into the site. These are moderately to steeply inclined slopes dominated by the growth of gorse and other vegetation.

The eastern boundary of Stage 2 consists of a ridge feature extending in a south-easterly direction.

The slopes tend to shallow towards the centre of this portion of Stage 2 down to a basin. The flow paths here converge into a wetland that discharges to the south. The lower reaches of the basin were noted to consist of boggy, waterlogged ground, with dense localised pockets of reeds. To the south there is a culvert crossing the stream. The culvert has been undermined on the southern side, where a small slip has occurred. To the south the land becomes densely vegetated adjacent the stream.

There were noted areas of instability on the steeper western and east facing slopes either side of the central stream. The steeper slopes show signs of shallow soil movement in the form of small terraces on more moderate gradients and shallow localised slumping on steeper slopes and near gully heads. Localised instability was noted around the edges of streams, especially those that have been relatively deeply incised.

2.6 Related Reports

The following geotechnical reports that are available to us have been reviewed during the preparation of this assessment:

- Geotechnical Assessment Report, prepared by CMW Geosciences Ltd for Ara Hills Stage 3A (formerly Stage 8), dated 15 June 2021, ref: AKL2020-0312AB Rev.0;
- Geotechnical Design Report – South Eastern Package, prepared by Tetra Tech Coffey for Ara Hills Stage 2, dated 8 November 2021, ref: AKLGE290955AA-AA;
- Geotechnical Design Report – Western Package, prepared by Tetra Tech Coffey for Ara Hills Stage 2, dated 26 November 2021, ref: AKLGE290955AA-AB; and
- Geotechnical Completion Report, prepared by CMW Geosciences Ltd for Ara Hills Stage 3-A1, dated 15 September 2022, ref: AKL2020-0312AI Rev.2.

3.0 Investigations

3.1 Fieldwork

Riley has undertaken two phases of site investigation across Stage 1 and Stage 2 in November and December 2024, comprising test pits, hand auger boreholes, and machine boreholes. The scope of the completed investigation is summarised below.

- Phase 1
 - 20 hand auger boreholes (HA1 to HA8, HA11 to HA22) to maximum 5m depth, or refusal.
 - Shear vane tests were typically undertaken at 0.5m intervals.
 - Scala penetrometer testing (Scala) was carried out in place of shear vanes in granular materials.
 - Scala's were carried out at the base of hand auger boreholes to maximum 2m depth, or refusal.
 - 11 groundwater monitoring standpipes (HA1, HA2, HA5, HA6, HA7, HA11, HA13, HA16, HA19, HA20 and HA21) were installed, with a response zone from base of hand auger to 1m below ground level.
 - 53 test pits (TP1 to TP10, TP12 to TP54) to maximum 6.0m depth.
 - Shear vane tests were typically undertaken at 1.0m intervals.
- Representative soil samples were recovered from selected test pit locations for subsequent laboratory testing.
- Phase 2
 - 65 hand auger boreholes (HA101 to HA165) to maximum 5m depth, or refusal.
 - Shear vane tests were typically undertaken at 0.5m intervals.
 - Scala's were carried out at the base of selected hand auger boreholes to maximum 2m depth, or refusal.
 - Six machine boreholes (MH01 to MH06) to maximum 19.5m depth.
 - Eight groundwater monitoring standpipes installed as nested piezometers (two per borehole) in four machine boreholes (MH01, MH02, MH04, and MH06).

The locations of the site investigation points are shown on sketch, site plans Sketches: 240065-SK110 to SK124 (Appendix I). The results of all in-situ testing, together with descriptions and depths of strata encountered during the drilling are presented on the test pit and borehole logs appended in Appendix A.

3.2 Laboratory Testing

The following laboratory tests were scheduled on collected samples in Stages 1 and 2. The tests were undertaken by Babbage Geotechnical Laboratory, which is an IANZ Accredited Testing Laboratory, in accordance with NZS4402. The results of these laboratory tests are discussed in Section 4.7 and appended in Appendix D.

- Eight Standard Compaction tests (standard five point with shear vane tests).
- Six Atterberg Limit tests.
- Five Particle Size Distribution Test by Hydrometer.
- Two Soaked CBR Tests

The following tests were undertaken by Riley. Riley is not an accredited laboratory.

- 36 water content tests.

3.2.1 Water Content Testing

Thirty-six samples were obtained for moisture content testing. These tests were carried out by Riley in accordance with NZS4402 Test Number 2.1. The test results are appended and summarised in Section 4.7. This testing was carried out to assist with establishing soil moisture conditioning requirements for potential earthworks.

3.2.2 Standard Compaction Testing

Eight Standard Compaction tests to NZS4402 Test Number 4.1.1 were carried out on representative samples of ECBF and NA. This testing was carried out on potential cut/borrow material to establish appropriate compaction control criteria. The results are outlined in Section 4.7, and the laboratory reports are appended.

3.2.3 Atterberg Limit Testing

Six Atterberg Limits tests were carried out in accordance with NZS4402 Test Numbers: 2.1, 2.1, 2.3, and 2.4 on representative samples of ECBF and NA. The results are outlined in Section 4.7.

3.2.4 Particle Size Distribution Testing

Five particle size distribution tests were carried in accordance with NZS4402 Test Number 2.8.4 on samples of ECBF. Test results are appended and are outlined in Section 4.7.

3.2.5 Soaked CBR Testing

Two soaked CBR tests were carried out in accordance with NZS4402 Test Numbers 2.1, 4.1.1 and 6.1.1. Test results are appended and are outlined in Section 4.7.

4.0 Investigation Findings

The finding of the investigation outlined in Section 3.1 are summarised below.

4.1 Topsoil

Topsoil was encountered within all test pits and hand augers, up to a depth of approximately 0.4m below ground level (bgl). TP51 (located in the north-western part of Stage 2) encountered a 100mm band of peat underlying the topsoil layer.

4.2 Alluvium

Alluvial soils were encountered in HA107, HA115, HA118, and HA135 (which were drilled within the gullies), to depths between 1.5m and 4.7m depth. The alluvial soils typically comprised clayey silt and silty clay, ranging from moist to wet and with trace rootlets and organic material, including wood, flax and humus. HA135 also recorded a layer of silty sand overlying the residual weathered soils.

4.3 Colluvium

Colluvium was encountered within nine test pits (TP2, 4-7, 28, 42, 47-48, 54) and eight hand augers (HA2, 6, 7, 106, 110, 122-124), typically between 0.4m bgl and 0.9m bgl underlying topsoil. These soils generally consisted of stiff to very stiff silts and some clays.

Notable depths of Colluvium were encountered in HA122, HA123 and HA124 in the central part of Stage 1, specifically to depths of 3.0m, 2.35m, and 2.1m, respectively (3.0m due to target depth of hand auger), and in TP47, TP48, and TP54 in the central eastern part of Stage 2, specifically to depths of 3.5m, 5.0m, and 4.9m, respectively (5.0m due to target depth of test pits). It is inferred that these thick colluvium deposits are associated with previous areas of instability.

Colluvium within these three test pits (TP47, TP48, and TP54) typically consisted of firm to stiff silts with some clays. In TP48 and TP54, layers of medium to coarse, sand and gravel between 3m and 5m bgl were noted.

4.4 East Coast Bays Formation

ECBF residual soils were encountered in the majority of test pits underlying the topsoil and colluvium and generally comprise stiff to hard silts, clays, and sands. The depth of residual soils varied from 2.8m to greater than 5m depth across the site.

It is difficult to distinguish between coarser ECBF residual soils from the Pakiri Formation. Although PF is identified on the geological map as underlying the northernmost part of the site PF soils were not recorded during the site investigation. The engineering properties of the residual soils are similar and would not change the recommendations made in this report.

In 29 test pits across the site, weathered ECBF rock was encountered underlying the residual ECBF soil. The encountered ECBF rock was typically moderately weathered extremely weak to weak siltstone and sandstone.

Scala testing at the base of hand augers within ECBF typically reached refusal at depths between 4.3m to 6.9m bgl. Refusal of the Scala was not reached within the base of three hand augers only (HA19, 20, and 22).

ECBF weathered rock was encountered in five machine borehole locations (MH01, MH02, MH03, MH04 and MH06) underlying varying thicknesses of residual soils (up to 9.35m in MH02) and the Northland Allochthon in MH01, at 7.65m depth. It was typically logged as highly weathered to unweathered grey siltstone and sandstone, with bedding planes ranging from 0° to 10° and joints, typically smooth, planar and with no infill.

4.5 Northland Allochthon – Hukerenui Mudstone

The residual soil of the Hukerenui Mudstone of the Northland Allochthon Group materials was encountered underlying the topsoil and Colluvium within 7 test pits (TPI, 5-7, 19-20, 23) on Stage 1 of the site. The Northland Allochthon was encountered in the central area of 53B, as well as at the western boundary. Both areas are associated with reeds and wet ground, and shallower slope gradient.

The residual soils generally comprised stiff silts and sands and were generally dry to moist, above the groundwater table. In all these test pit locations, the residual soil was underlain by weathered rock, typically encountered between 2.0m bgl to 3.7m bgl. The Hukerenui Mudstone was typically described as completely to moderately weathered extremely weak to weak siltstones and sandstones. The siltstone was typically sheared and muddy.

Cores of slightly weathered Hukerenui Mudstone were recovered in MH01 and MH05. MH05 reached target depth at 9.1m, recovering slightly weathered dark grey sandstone. MH01 recovered slightly weathered light grey and red, pervasively sheared mudstone to 7.65m depth where it reached the unconformable contact with the East Coast Bays Formations.

4.6 Groundwater Level and Monitoring

Groundwater was encountered in multiple investigation locations during the investigation completed in November and December 2024.

Within the test pits, groundwater was encountered during excavation within 12 of the 53 locations (TPI5, 17, 21, 23, 26-27, 37-38, 41, 43, 48, 51) at depths between 2.0m and 5.2m below existing ground level.

During drilling of the hand augers, groundwater was encountered in 13 of the 20 locations (HA1-3, 5-7, 11-13, 15-17, 19) at depths between 1.5m and 4.8m below existing ground level. Groundwater monitoring standpipes were installed within 11 hand augers (HA1, 2, 4-7, 11, 13, 16, 19-21), as detailed in Table 1. The standpipes on Stage 1 (HA1, 2, 4-7, 11) were installed between 6-7 November 2024 and the standpipes on Stage 2 (HA13, 16, 19-21) were installed between 18-20 November 2024.

Groundwater monitoring standpipes were installed as nested piezometers in four of the machine boreholes (MH01, MH02, MH04, and MH06) to capture potential shallow and deep groundwater regimes.

Groundwater monitoring of the installed standpipes was initially undertaken for two consecutive weeks following installation and then will be monitored at monthly intervals.

Standpipes in HA13 and HA16 are located in areas of reeds. Monitoring of these points indicates an elevated groundwater level in comparison to other monitoring points. Groundwater levels within such areas are often elevated all year round. HA19 is located within a hummocky area with a head scarp upslope. The monitoring of this locations has also shown elevated groundwater levels.

Table 1: Measured Groundwater Levels in Piezometers

Stage	Hole ID	Response Zone (m bgl)	Ground-water Level ¹ (m bgl)	Groundwater Levels (m bgl)				
				21/11/24	28/11/24	05/12/24	19/12/24	16/01/25
Stage 1	HA1	1.0 – 5.0	3.6	No access ²	No access ²	– ³	No access ²	No access ²
	HA2	1.0 – 5.0	3.0	2.53	2.59	–	2.96	2.62
	HA5	1.0 – 5.0	4.8	5.48	4.77	–	N/E ⁴	N/E
	HA6	1.0 – 4.5	4.37	3.69	3.69	–	3.48	3.87
	HA7	1.0 – 5.0	3.78	3.5	No access ²	–	3.06	3.74
	HA11	1.0 – 4.1	3.3	3.29	3.35	–	3.19	3.46
	MH01	1.5 – 2.5	–				0.69	1.26
	MH01	4.5 – 6.5	–				2.91	2.39
	MH02	2.0 – 6.0	–				3.28	3.93
	MH02	8.0 – 11.0	–				3.58	3.93
	MH04	6.0 – 8.0	–				5.49	5.84
	MH04	13.0 – 15.0	–				9.30	9.42
	MH06	3.0 – 5.0	–				3.04	4.15
	MH06	6.5 – 8.5	–				6.45	6.92
Stage 2	HA13	1.0 – 4.0	2.26		1.98	2.07	2.07	2.66
	HA16	1.0 – 4.7	2.6		2.26	2.33	2.22	2.73
	HA19	1.0 – 5.0	2.96		0.81	0.94	Dest-royed ⁵	–
	HA20	1.0 – 4.0	N/E		N/E	N/E	N/E	N/E
	HA21	1.0 – 5.0	N/E		4.83	4.92	N/E	N/E

¹ Groundwater level measured during drilling of hand auger and machine borehole.

² Monitoring points were unable to be accessed due to cattle.

³ Dashed line denotes not measured.

⁴ N/E denotes not encountered.

⁵ Destroyed by cattle.

4.7 Laboratory Test Results

4.7.1 Water Content

Riley carried out moisture content tests on a total of 36 samples. Results are presented in Table 2.

Table 2: Soil Water Content Percentages

Stage	Test Number	Geological Unit	Investigation ID	Depth (m)	Water Content (%)
Stage 1	1	Northland Allochthon	TP7	0.6-0.8	49.7
	2		TP7	2.0-2.3	47.3
	3		TP7	2.8-3.1	36.6
	4		TP7	4.2-4.5	33.3
	5	East Coast Bays Formation	TP10	1.5-1.8	39.4
	6		TP10	2.4-2.7	38.5
	7		TP10	3.6-3.8	22.6
	8		TP16	1.0-1.2	52.3
	9		TP16	2.0-2.2	50.3
	10		TP3	1.0-2.0	43.9
	11		TP3	4.0-5.0	41.9
	12	Northland Allochthon	TP1	0.5-2.0	66.3
	13		TP1	2.9 -4.6	28.4
Stage 2	14	Not Tested			
	15				
	16	East Coast Bays Formation	TP41	1.0-2.0	36.5
	17		TP41	3.2-4.6	41.1
	18		TP27	1.1-2.1	53.3
	19		TP27	4.6-5.2	52.5
	20		TP27	5.2-5.4	35.4
	21		TP25	1.0-2.0	40.1
	22		TP25	4.0-5.5	32.0
	23		TP25	3.5-4.5	48.2
	24		TP30	0.5-1.2	48.2
	25		TP30	1.5-2.1	53.1
	26		TP30	2.8-3.1	52.7
	27		TP30	3.45-4.1	52.0
	28		TP36	1.1-2.0	55.2
	29		TP36	2.2-3.3	54.3
	30		TP36	3.8-4.6	41.7
	31		TP38	1.0-2.0	49.7
	32		TP39	0.3-0.9	40.9
	33		TP39	1.0-2.0	47.3
	34		TP39	3.5-4.5	58.9
	35		TP47	1.0-2.0	32.4
	36		TP47	4.0-5.0	30.9
	37		TP49	1.0-2.0	34.9
	38		TP49	4.0-5.0	53.1

The results indicate that there is a relatively wide spread of moisture content results. They also indicated the upper 2m–3m of the soil profile has moisture contents typically 10%–20% higher than the deeper soils. The results are summarised in Table 3.

Table 3: Summary of Riley Soil Moisture Contents

Stage	Geological Unit	Maximum Moisture Content (%)	Minimum Moisture Content (%)	Average Moisture Content (%)
1	Northland Allochthon	66.3	28.4	43.6
1	East Coast Bays Formation	52.3	22.6	41.3

4.7.2 Standard Compaction

The Standard compaction test results are summarised in Table 4. Test results are appended.

Table 4: Standard Compaction Test Results

Stage	Investigation ID	Geological Unit	Depth (m)	As Received Moisture Content (%)	Maximum Dry Density (t/m ³)	Optimum Moisture Content (%)
Stage 1	TP3	East Coast Bays Formation	4.0 – 5.0	42.4	1.54	20
	TP7	Northland Allochthon	0.6 – 0.8	49.4	1.25	36
	TP10	East Coast Bays Formation	2.4 – 2.7	36.1	1.53	21
	TP10		3.6 – 3.8	23.4	1.60	21
Stage 2	TP25	East Coast Bays Formation	4.0 – 5.0	33.5	1.52	21
	TP27		4.6 – 5.2	52.3	1.33	31
	TP41		3.6 – 4.6	48.1	1.43	25
	TP47		1.0 – 2.0	37.2	1.42	29

The standard compaction tests returned a maximum dry density of 1.25t/m³ (TP7) at an optimum moisture content (OMC) of 36% for a sample comprising Northland Allochthon soils. The OMC was approximately 13% lower than the as received soil moisture content.

For samples taken from ECBF soils the maximum dry densities were between 1.33t/m³ (TP27) and 1.60t/m³(TP10). The test results indicate that the OMC is approximately 15% to 20% below the natural moisture content.

As with the soil moisture contents presented in Tables 2 and 3 above, the as received soil moisture content test results indicate that there is significant variability in the soil moisture. The test results also indicate that soil moisture content conditioning in the order of 10% to 20% will likely be required to dry back to the optimum moisture content.

4.7.3 Atterberg Limits and Linear Shrinkage

Atterberg Limits testing was undertaken on six representative samples of materials, between 0.6m and 5.0m depth. Testing was undertaken to NZS 4402:1986 and is IANZ endorsed. Test results are presented in the Table 5. Full laboratory reports appended. The testing was undertaken to assist with assessing the site soil plasticity and expansivity characteristics. Further expansive soil testing will be required as part of geotechnical completion reporting following earthworks.

Table 5: Atterberg Limit and Linear Shrinkage Test Results

Stage	Investigation ID	Geological Unit	Depth (m)	Liquid Limit (%)	Plastic Limit (%)	Plasticity Index (%)	As Received Water Content (%)
Stage 1	TP3	East Coast Bays Formation	4.0 – 5.0	46	26	20	43.2
	TP7	Northland Allochthon	0.6 – 0.8	86	33	53	49.6
	TP10	East Coast Bays Formation	3.6 – 3.8	52	18	34	24.0
	TP16		1.0 – 1.2	109	34	75	50.5
Stage 2	TP41	East Coast Bays Formation	3.2 – 4.6	55	23	32	47.5
	TP47		1.0 – 2.0	76	25	51	37.4

The Atterberg Limit test results indicate that all samples tested have a USCS classification of either CL (clay of low plasticity, TP3) or CH (clay of high plasticity). We do note however, that for the TP10 sample, only the soil fraction passing the 425µm sieve was used. While this is consistent with the testing standard, it could result in the plasticity being overstated for this sample. In general, field descriptions of the sampled material indicated a lower plasticity and clay content than those reported in the laboratory tests.

Soils that are dry of the plastic limit will not behave in a plastic manner and will likely become difficult to compact to an engineered standard. Considering the proximity of the OMC (see Section 4.7.2 above) to the plastic limit, it will be important that care is taken to ensure that soil moisture contents are not more than 2-3% below the OMC following conditioning.

4.7.4 Particle Size Distribution

The particle size distribution tests were carried out on samples obtained from TP10, TP30, TP36, and TP41 to assess the soil textures for assessment of the soil category for treated effluent soakage. Test results are presented in Table 6.

Table 6: Particle Size Distribution Test Results

Stage	Geological Unit	Investigation ID	Depth (m)	Clay (%)	Silt (%)	Sand (%)	Gravel (%)
Stage 1	East Coast Bays Formation	TP10	2.4 – 2.7	18	23	58	1
		TP10	3.6 – 3.8	24	63	13	0
Stage 2		TP30	3.5 – 4.1	26	64	10	0
		TP36	3.8 – 4.6	12	25	63	0
		TP41	3.2 – 4.6	20	44	36	0

4.7.5 California Bearing Ratio (CBR)

Two soaked CBR tests were undertaken on soil samples recovered from TP30 at 3.5m to 4.1m depth and TP36 at 3.8m to 4.6m depth. These were undertaken to assist with assessments of the preliminary subgrade CBR for road pavement design. A portion of the TP36 sample comprised completely weathered sandstone and siltstone which was observed by the laboratory to be easily broken over a 9.5mm sieve. The tests returned soaked CBRs of 1% and 2%, respectively. We note that the samples tested were described as being sandy with low to moderate plasticity and both had moisture contents above the OMC. These results are considered to be atypical for the geological units present here. The combination of the sandy soil composition and elevated moisture content is a likely explanation for the low laboratory CBR values.

5.0 Geotechnical Considerations

Based on the results of our field investigations, Riley considers the proposed development should be suitable for the ground conditions encountered, subject to the recommendations below.

5.1 Slope Stability

Qualitative and quantitative stability assessments have been carried out for the purpose of addressing the requirements of Section E36 of the AUP together with relevant considerations with respect to Section 106 of the RMA. A PC120 landslide risk assessment has also been carried out.

5.1.1 Qualitative Slope Stability Assessment

The instability features described in Section 2.5 together with Northland Allochthon deposits and its interface with the ECBF present complex stability issues that will need to be addressed. Similar land instability features were understood to be present at the adjacent Ara Hills development.

As outlined in Section 2.5, areas of the development are affected by existing significant instability features by including head scarps, hummocky, undulating and waterlogged ground across portions of the site. Due to the presence of these instability features, we consider that such portions of the land will require stability enhancement to ensure suitable accessways and building platforms are available for future residential development. We consider that these enhancements will need to comprise a combination of palisade walls, shear keys, buttress fills, and mechanically stabilised earth fills.

However, there are also some localised areas (particularly in the south-east corner of the development) that are free of observed existing instability features and where gradients are sufficiently gentle such that they unlikely to require stability enhancement works to support future dwelling development.

5.1.2 Quantitative Slope Stability Assessment

To provide a quantitative assessment of the available Factor of Safety (FoS) against instability for the post-development ground surface, analyses have been undertaken for cross sections A to P plus AE and AG for Stage 1 and Q to AD plus AF and AH for Stage 2. Approximately 50% of sections have also been analysed for the pre-development contours (aside from Section J, where the current ground profile comprises an effectively flat stream bed and therefore can be qualitatively assessed as having no current credible risk of instability). The results of these analyses are compared to the post-development analysis results to assess whether the proposal affects the stability of slopes near site boundaries and streams.

The analysed cross sections have been chosen based on the post development profile (the critical condition) and capture the 'worst case profile', for example the deepest cuts and fills, or greatest retained heights. For some sections this means that the critical post development alignment is not orthogonal to the steepest natural contours.

The analyses also include a cross-section (P) for the post development ground surface in the vicinity of the proposed water/wastewater treatment plant and potential effluent discharge trench locations. For the potential effluent discharge trench locations, groundwater conditions within the trenches have been assumed to be at the surface for all analysed conditions. This essentially means that through the modelling process (even though the groundwater table was lower during investigations in the vicinity) the ground downslope of the trenches has been treated as saturated for all analysed conditions. We consider that this is an appropriately conservative approach.

For the purpose of the stability assessments, we have utilised the software Slide 2. The analyses have been undertaken using the Morgenstern Price method of analysis for non-circular slip surfaces. The stability analysis results are outlined below. The analyses consider long term groundwater levels, temporary saturated ground conditions and a ULS seismic scenario. For the ULS seismic scenario a peak ground acceleration of 0.19g (as per the MBIE guidelines) was used.

5.1.3 Geotechnical Model and Analysis Parameters

With respect to the comments on-site geomorphology in Section 2.5 above, deep-seated instability within the underlying rock mass is considered unlikely. The instability features that have been observed within the site are considered likely to have occurred as a result of saturation of the soil profile during extreme/seasonal wet periods or in the case of portions of Stage 2 due to saturation of a sandy horizon just above the underlying rock. Consistent with the comments on-site geomorphology, we have considered circular and non-circular instability mechanisms within the soil profile.

The stability analysis considered assumed normal groundwater conditions, extreme saturated conditions and ULS seismic conditions. The normal groundwater level is inferred based on the groundwater encountered at the investigation locations. The extreme groundwater condition was modelled as 80% saturation of the surficial soil layers above the long-term water table using an R_u coefficient of 0.44. Extreme (transient) groundwater conditions are assumed to occur infrequently and persist for a relatively short period following heavy rainfall events. This is approximately equivalent to a 1m deep water table during the transient scenario for locations where the existing groundwater level is at 5m depth. Where the existing water table is shallower, the approximately equivalent water table would be closer to the ground surface. We consider this approach is appropriately conservative.

In addition, to examine the potential effects of porewater pressure developing in the bulk subdivisional fill, such as in the event of a complete drainage system failure, a portion of the cross sections have been analysed to include 50% saturation of the engineered fill as part of the extreme groundwater scenario (in addition to the post-development surcharges). An equivalent R_u value of 0.27 was adopted in the Slide2 models to simulate this 50% soil saturation.

The normal groundwater level was used for the ULS seismic event case. For all cases, because there will be subsoil drains beneath the subdivisional fill, it was analysed as being drained.

The cross-sections have been analysed with surcharges of 10kPa, 12kPa, and 24kPa to simulate future building platforms, local roads and the NOR road respectively to demonstrate that the addition of post-development surcharges will not have a significant effect on the overall stability of the proposed development. Surcharges of.

A Geomorphic Assessment was undertaken by Morphum Environmental (Morphum) in October 2025, which indicated that some streams on-site show evidence of incision. Continued erosion along the identified stream reaches may result in the set-back distance between the stream and the proposed structures being less than 10m. Morphum's assessment notes that whilst a 10m riparian setback is generally appropriate for the development, localised widening between 1-2m is expected. Therefore, the analysis on these specific cross sections (Sections B, E, F, H, L, R, V, Z, AA, AB, AE, AF, AG, AH) has also considered the potential for downcutting and widening of the streams, and the potential impact on stability enhancement measures at these locations. As per Morphum's advice this analysis allows for a downcut and widened stream (at the location of the current stream) having dimensions of 2m depth, and 3m width with vertical side banks.

A FoS greater than 1.5 is required for permanent slopes under long-term groundwater conditions, while a FoS greater than 1.3 is acceptable for temporary transient groundwater conditions during temporary elevated conditions. A FoS greater than 1 is required for the ULS seismic event scenario. These target FoS are generally consistent with the Auckland Council Code of Practice for Land Development, with the exception of the seismic case which the proposed target is more conservative. For the scenario of partial fill saturation a target FoS of 1.0 is considered appropriate given that it would take a very extreme rainfall event in combination with a complete drainage system failure to result in the fill becoming saturated to this degree. We consider that with careful underfill/subsoil/counterfort drainage design that complete drainage failure is extremely unlikely

In accordance with the Ministry of Business, Innovation and Employment (MBIE) and the New Zealand Geotechnical Society (NZGS) Module 1 Guidelines, a ULS Peak Ground Acceleration (PGA) of 0.19g has been used for the Auckland region. This value has been determined with a ULS (Ultimate Limit State) return period of 500 years.

Where individual cross-sections extend across gullies, the stability analysis has been undertaken to consider potential slip surfaces on both sides of the gullies.

For these analyses, the effective stress soil parameters presented in Table 7 were adopted.

Table 7: Soil Parameters

Material Names	Unit Weight (kN/m ³)	Cohesion (kPa)	Phi (deg)
Engineered Fill	18	8	32
Gully mullock	17	2	22
Colluvium	17	2	25
Firm NA	18	3	22
Stiff NA	18	5	25
Very Stiff NA	18	5	30
Weak NA layer	19	0	12
Very weak NA rock	20	5	25
Weak NA rock	20	5	30
Medium Dense ECBF	18	2	30
Firm ECBF	18	5	26
Stiff ECBF	18	5	28
Very Stiff ECBF	18	7	30
Very weak ECBF rock	20	10	35
Weak ECBF rock	20	20	40

Full details of the stability analyses are appended and summarised below.

5.1.4 Quantitative Stability Analysis Results

The results are summarised in Table 8 and Table 9 below.

Table 8: Summary of Stability Analysis Results – Pre and Post Development (Stage 1)

Cross-Section	Profile	Scenario	Comments
A	Pre-development	Long Term Groundwater Conditions	FoS less than the required values for all cases.
		Temporary Elevated Groundwater Conditions	
		Seismic	
	Post-development	Long Term Groundwater Conditions	FoS less than the required values for all cases. Stability enhancement measures required.
		Temporary Elevated Groundwater Conditions	
		Seismic	
		50% Fill Saturation	
		Long Term Groundwater Conditions (Stability enhancement)	Adequate FoS achieved for slip surfaces encroaching into the lots (i.e. FoS less than the target values occur outside the lots), with inclusion of stability enhancement measures for long term, temporary elevated groundwater and 50% fill saturation conditions. FoS less than 1 for seismic conditions but deformations calculated using the Jibson (2007) method are between 0mm and 5mm, which is considered to be acceptable based on MBIE guidelines.
		Temporary Elevated Groundwater Conditions (Stability enhancement)	
		Seismic (Stability enhancement)	Proposed Enhancement: Tiered retaining walls between the road and the northern boundary (1.5m spacing, 390kN shear capacity per pile, piles 11m long). Palisade walls (1.5m spacing, 66kN shear capacity per pile, piles 5-6m long) required at the base of the central and upper fill/stepped areas. The lower fill area needs to be substantially undercut down to the NA rock (3m-5m depth over a width of 40m-50m). Geogrid REB slopes (20kN/m long-term strength at 0.6m vertical intervals, 2m long) required for fill batters.
		50% Fill Saturation (Stability enhancement)	

Cross-Section	Profile	Scenario	Comments
B	Pre-development	Long Term Groundwater Conditions	FoS adequate for all cases.
		Temporary Elevated Groundwater Conditions	
		Seismic	
	Post-development	Long Term Groundwater Conditions	FoS less than the required values for all cases. Stability enhancement measures required.
		Temporary Elevated Groundwater Conditions	
		Seismic	
		50% Fill Saturation	
		Long Term Groundwater Conditions (Stability enhancement)	Adequate FoS achieved for slip surfaces encroaching into the lots (i.e. FoS less than the target values occur outside the lots), with inclusion of stability enhancement measures. Proposed Enhancement: Cantilever wall at top of slope (1.5m spacing, 185kN shear capacity per pile, piles 6m long) and retaining wall at mid slope fill batter (1.5m spacing, 66kN shear capacity per pile, piles 6m long). Geogrid REB slope (20kN/m long term strength at 0.6m vertical intervals, 8-10m long) with palisade wall shear piles beneath (1.5m spacing, 640kN shear capacity per pile, piles 9m long) over lower portions of the slope.
		Temporary Elevated Groundwater Conditions	
		Seismic (Stability enhancement)	
		50% Fill Saturation (Stability enhancement)	

Cross-Section	Profile	Scenario	Comments
C	Post-development	Long Term Groundwater Conditions	FoS less than the required values for all cases, except the seismic case. Stability enhancement measures required.
		Temporary Elevated Groundwater Conditions	
		Seismic	
		50% Fill Saturation	
		Long Term Groundwater Conditions (Stability enhancement)	Adequate FoS achieved with inclusion of stability enhancement measures. Proposed Enhancement: Palisade walls at top of slope (1.5m spacing, 66kN shear capacity per pile, piles 6m long). Geogrid REB slope (20kN/m long term strength at 0.6m vertical intervals, 2-3m long) over the lower portions of the slope. Colluvium to be excavated and replaced with engineered fill.
		Temporary Elevated Groundwater Conditions (Stability enhancement)	
		Seismic (Stability enhancement)	
		50% Fill Saturation (Stability enhancement)	
D	Pre-development	Long Term Groundwater Conditions	FoS adequate for all cases.
		Temporary Elevated Groundwater Conditions	
		Seismic	
	Post-development	Long Term Groundwater Conditions	FoS less than the required values for temporary elevated groundwater conditions. Stability enhancement measures required.
		Temporary Elevated Groundwater Conditions	
		Seismic	
		50% Fill Saturation	

Cross-Section	Profile	Scenario	Comments
		Long Term Groundwater Conditions (Stability enhancement)	<p>Adequate FoS achieved with inclusion of stability enhancement measures.</p> <p>Proposed Enhancement: Palisade wall (1.5m spacing, 280kN shear capacity per pile, piles 5m long) with geogrid REB slope (20kN/m long term strength at 0.6m vertical intervals, 6m long) above, over lower portion of the slope.</p>
		Temporary Elevated Groundwater Conditions (Stability enhancement)	
		Seismic (Stability enhancement)	
		50% Fill Saturation (Stability enhancement)	
E	Post-development	Long Term Groundwater Conditions	FoS less than the required for both the northern and southern slope. Stability enhancement measures required.
		Temporary Elevated Groundwater Conditions	
		Seismic	
		50% Fill Saturation	
		Long Term Groundwater Conditions (Stability enhancement)	<p>Adequate FoS achieved for slip surfaces encroaching into the lots for both northern and southern slopes (i.e. FoS less than the target values occur outside the lots), with inclusion of stability enhancement measures.</p> <p>Proposed Enhancement: For both northern and southern slopes a palisade wall (1.5m spacing, 66kN shear capacity per pile, piles 5m long) with geogrid REB slope (20kN/m long term strength at 0.6m vertical intervals, 4-5m long) above.</p>
		Temporary Elevated Groundwater Conditions (Stability enhancement)	
		Seismic (Stability enhancement)	
		50% Fill Saturation (Stability enhancement)	

Cross-Section	Profile	Scenario	Comments
F	Pre-development	Long Term Groundwater Conditions	FoS adequate for all cases.
		Temporary Elevated Groundwater Conditions	
		Seismic	
	Post-development	Long Term Groundwater Conditions	FoS less than the required values for all cases. Stability enhancement measures required.
		Temporary Elevated Groundwater Conditions	
		Seismic	
		50% Fill Saturation	
		Long Term Groundwater Conditions (Stability enhancement)	Adequate FoS achieved for slip surfaces encroaching into the lots (i.e. FoS less than the target values occur outside the lots), with inclusion of stability enhancement measures. Proposed Enhancement: Approx 1.5m high cantilever retaining wall (1.5m spacing, 66kN shear capacity per pile, piles 3m long) at top of slope. Geogrid REB slope (20kN/m long term strength at 0.6m vertical intervals, 7m long) with palisade wall shear piles beneath (1.5m spacing, 280kN shear capacity per pile, piles 6m long) over lower fill slope.
		Temporary Elevated Groundwater Conditions (Stability enhancement)	
		Seismic (Stability enhancement)	
		50% Fill Saturation (Stability enhancement)	
G	Post development	Long Term Groundwater Conditions	Adequate FoS are available for all cases considered. Stability enhancement measures are not required.
		Temporary Elevated Groundwater Conditions	
		Seismic	
		50% Fill Saturation	

Cross-Section	Profile	Scenario	Comments
H	Pre-development	Long Term Groundwater Conditions	FoS adequate for all cases.
		Temporary Elevated Groundwater Conditions	
		Seismic	
	Post-development	Long Term Groundwater Conditions	FoS less than the required values for all cases. Stability enhancement measures required.
		Temporary Elevated Groundwater Conditions	
		Seismic	
		50% Fill Saturation	
		Long Term Groundwater Conditions (Stability enhancement)	Adequate FoS achieved with inclusion of stability enhancement measures. Proposed Enhancement: Palisade wall (1.5m spacing, 66kN shear capacity per pile, piles 3m long) below geogrid REB slope (20kN/m long term strength at 0.6m vertical intervals, 10m long).
		Temporary Elevated Groundwater Conditions (Stability enhancement)	
		Seismic (Stability enhancement)	
		50% Fill Saturation (Stability enhancement)	

Cross-Section	Profile	Scenario	Comments
I	Pre-development	Long Term Groundwater Conditions	FoS less than the required values for all cases.
		Temporary Elevated Groundwater Conditions	
		Seismic	
	Post-development	Long Term Groundwater Conditions	FoS less than the required values for all cases, except 50% saturation case. Stability enhancement measures required.
		Temporary Elevated Groundwater Conditions	
		Seismic	
		50% Fill Saturation	
		Long Term Groundwater Conditions (Stability enhancement)	Adequate FoS achieved with inclusion of stability enhancement measures for long term, temporary elevated groundwater conditions and 50% fill saturation conditions. FoS less than 1 for seismic conditions but deformations calculated using the Jibson (2007) method are between 0 and 3mm, which is considered to be acceptable, based on MBIE guidelines. Proposed Enhancement: Palisade wall (1.5m spacing, 185kN shear capacity per pile, piles 5m long) with geogrid REB slope (20kN/m long-term strength at 0.6m vertical intervals, 2m long).
		Temporary Elevated Groundwater Conditions (Stability enhancement)	
		Seismic (Stability enhancement)	
		50% Fill Saturation (Stability enhancement)	

Cross-Section	Profile	Scenario	Comments
J	Post-development	Long Term Groundwater Conditions	FoS less than the required values for all cases. Stability enhancement measures required. Groundwater at the surface in the gully for all cases.
		Temporary Elevated Groundwater Conditions	
		Seismic	
		50% Fill Saturation	
		Long Term Groundwater Conditions (Stability enhancement)	Adequate FoS achieved with inclusion of stability enhancement measures. Proposed Enhancement: Geogrid REB slope (45kN/m long term strength at 0.6m vertical intervals, varying between 8-29m long, including double ended grids). Gully mullock undercut and replaced with engineered fill.
		Temporary Elevated Groundwater Conditions (Stability enhancement)	
		Seismic (Stability enhancement)	
		50% Fill Saturation (Stability enhancement)	
K	Post-development	Long Term Groundwater Conditions	FoS less than the required values for all cases for slip surfaces encroaching within the fill embankment. Stability enhancement measures required. Groundwater at the surface in the gully for all cases.
		Temporary Elevated Groundwater Conditions	
		Seismic	
		50% Fill Saturation	
		Long Term Groundwater Conditions (Stability enhancement)	Adequate FoS achieved with inclusion of stability enhancement measures. The minimum FoS for all cases occurs outside the embankment. FoS for slip surfaces encroaching within the fill embankment are above target values, which is acceptable.
		Temporary Elevated Groundwater Conditions (Stability enhancement)	

Cross-Section	Profile	Scenario	Comments
		Seismic (Stability enhancement)	Proposed Enhancement: Geogrid REB slope (23kN/m long term strength at 0.6m vertical intervals, varying between 6-25m long, including double ended grids). Gully mullock undercut and replaced with engineered fill.
		50% Fill Saturation (Stability enhancement)	
L	Post-development	Long Term Groundwater Conditions	FoS less than the required values for all cases (excluding seismic) for slip surfaces encroaching within the fill embankment. Stability enhancement measures required.
		Temporary Elevated Groundwater Conditions	
		Seismic	
		50% Fill Saturation	
		Long Term Groundwater Conditions	Adequate FoS achieved with inclusion of stability enhancement measures. The minimum FoS for all cases occurs outside the development area. Proposed Enhancement: REB slope (20kN/m long-term strength at 0.6m vertical intervals, 2m long).
		Temporary Elevated Groundwater Conditions	
		Seismic	
		50% Fill Saturation	
M	Pre-development	Long Term Groundwater Conditions	FoS less than the required values for long term and temporary elevated groundwater conditions.
		Temporary Elevated Groundwater Conditions	
		Seismic	
	Post-development	Long Term Groundwater Conditions	FoS less than the required values for all cases. Stability enhancement measures required.
		Temporary Elevated Groundwater Conditions	
		Seismic	
		50% Fill Saturation	

Cross-Section	Profile	Scenario	Comments
		Long Term Groundwater Conditions (Stability enhancement)	<p>Adequate FoS achieved with inclusion of stability enhancement measures for long term, temporary elevated groundwater conditions and 50% fill saturation conditions. Some slip surfaces over the eastern natural slope are below the target values, but these don't encroach to be within the lots.</p> <p>FoS less than 1 for seismic conditions but deformations calculated using the Jibson (2007) method are between 0 and 3mm, which is considered to be acceptable.</p> <p>Proposed Enhancement: Geogrid REB slope (20kN/m long term strength at 0.6m vertical intervals, 2-15m long) over a palisade wall (1.5m spacing, 66kN shear capacity per pile, piles 8m long).</p>
		Temporary Elevated Groundwater Conditions (Stability enhancement)	
		Seismic (Stability enhancement)	
		50% Fill Saturation (Stability enhancement)	
N	Post-development	Long Term Groundwater Conditions	FoS less than the required values for all cases for slip surfaces occurring within the steep batter adjacent to the northern boundary. Stability enhancement measures required.
		Temporary Elevated Groundwater Conditions	
		Seismic	
		50% Fill Saturation	
		Long Term Groundwater Conditions (Stability enhancement)	<p>Adequate FoS achieved for all scenarios with inclusion of stability enhancement measures</p> <p>Proposed Enhancement: Two 3m high retaining walls (1.5m spacing, 240kN shear capacity per pile, piles 8m long) along the northern boundary with an 18 degree slope in between them. Approx 2.7m high cantilever retaining wall (1.5m spacing, 98kN shear capacity per pile, piles 5m long) at cut in slope.</p>
		Temporary Elevated Groundwater Conditions (Stability enhancement)	
		Seismic (Stability enhancement)	
		50% Fill Saturation (Stability enhancement)	

Cross-Section	Profile	Scenario	Comments
O	Post-development	Long Term Groundwater Conditions	FoS less than the required values for all cases for slip surfaces occurring within the steep batter adjacent to the northern boundary. Stability enhancement measures required.
		Temporary Elevated Groundwater Conditions	
		Seismic	
		50% Fill Saturation	
		Long Term Groundwater Conditions (Stability enhancement)	Adequate FoS achieved for all scenarios with inclusion of stability enhancement measures
		Temporary Elevated Groundwater Conditions (Stability enhancement)	
		Seismic (Stability enhancement)	
		50% Fill Saturation (Stability enhancement)	
P	Post-development	Long Term Groundwater Conditions	FoS less than the required values for all cases for the batter slope above the WWTP and fill batter above effluent disposal trench. Stability enhancement measures required.
		Temporary Elevated Groundwater Conditions	
		Seismic	
		50% Fill Saturation	
		Long Term Groundwater Conditions (Stability enhancement)	Adequate FoS achieved for all scenarios with inclusion of stability enhancement measures
		Temporary Elevated Groundwater Conditions (Stability enhancement)	
			Proposed Enhancement: A 2.1m high retaining wall (1.5m spacing, 66kN shear capacity per pile, piles 6m long) with an 18 degree slope above sloping up to the

Cross-Section	Profile	Scenario	Comments
AE	Post-development	Seismic (Stability enhancement)	southwestern boundary. Fill batter requires geogrid REB slope (20kN/m long term strength at 0.6m vertical intervals, 6m long).
		50% Fill Saturation (Stability enhancement)	
		Long Term Groundwater Conditions	FoS less than the required values for all cases. Stability enhancement measures required.
		Temporary Elevated Groundwater Conditions	
		Seismic	
		50% Fill Saturation	
		Long Term Groundwater Conditions (Stability enhancement)	Adequate FoS achieved for all scenarios with inclusion of stability enhancement measures. Proposed Enhancement: Geogrid REB slope (20kN/m long term strength at 0.6m vertical intervals, 5m long) over a palisade wall (1.5m spacing, 640kN shear capacity per pile, piles 5m long). One 4m high retaining wall (1.5m spacing, 280kN shear capacity per pile, piles 8m long) along the top of the slope. Two 2-3m high retaining walls (1.5m spacing, 100kN shear capacity per pile, piles 5m long) at cut faces between lots.
		Temporary Elevated Groundwater Conditions (Stability enhancement)	
		Seismic (Stability enhancement)	
		50% Fill Saturation (Stability enhancement)	

Cross-Section	Profile	Scenario	Comments
AG	Post development	Long Term Groundwater Conditions	FoS less than the required values for all cases. Stability enhancement measures required.
		Temporary Elevated Groundwater Conditions	
		Seismic	
		50% Fill Saturation	
		Long Term Groundwater Conditions (Stability enhancement)	Adequate FoS achieved for slip surfaces encroaching into the lots (i.e. FoS less than the target values occur outside the lots), with inclusion of stability enhancement measures. Proposed Enhancement: Cantilever wall at top of slope (1.5m spacing, 185kN shear capacity per pile, piles 6m long) and palisade wall at mid slope fill batter (1.5m spacing, 66kN shear capacity per pile, piles 6m long). Geogrid REB slope (20kN/m long term strength at 0.6m vertical intervals, 10m long) with palisade wall shear piles beneath (1.5m spacing, 640kN shear capacity per pile, piles 9m long) over lower portions of the slope.
		Temporary Elevated Groundwater Conditions (Stability enhancement)	
		Seismic (Stability enhancement)	
		50% Fill Saturation (Stability enhancement)	
AI	Post development	Long Term Groundwater Conditions	FoS less than the required values for all cases in both failure directions. Stability enhancement measures required.
		Temporary Elevated Groundwater Conditions	
		Seismic	
		50% Fill Saturation	
		Long Term Groundwater Conditions (Stability enhancement)	
		Temporary Elevated Groundwater Conditions (Stability enhancement)	

Cross-Section	Profile	Scenario	Comments
		Seismic (Stability enhancement)	<p>Adequate FoS achieved for slip surfaces encroaching into the lots (i.e. FoS less than the target values occur outside the lots), with inclusion of stability enhancement measures.</p> <p>Eastern side - Proposed Enhancement: Geogrid REB slope (20kN/m long term strength at 0.6m vertical intervals, 6m long), with underlying colluvium and gully mullock removed.</p> <p>Western side - Proposed Enhancement: Geogrid REB slope (20kN/m long term strength at 0.6m vertical intervals, 7m long) over a palisade wall (1.5m spacing, 240kN shear capacity per pile, piles 6m long).</p>
		50% Fill Saturation (Stability enhancement)	

Table 9: Summary of Stability Analysis Results – Post Development (Stage 2)

Cross-Section		Scenario	Comments
Q	Post development	Long Term Groundwater Conditions	FoS less than the required values for all cases. Stability enhancement measures required.
		Temporary Elevated Groundwater Conditions	
		Seismic	
		50% Fill Saturation	
		Long Term Groundwater Conditions (Stability enhancement)	Adequate FoS achieved for all scenarios with inclusion of stability enhancement measures.
		Temporary Elevated Groundwater Conditions (Stability enhancement)	
		Seismic (Stability enhancement)	Proposed Enhancement: Palisade wall (1.5m spacing, 185kN shear capacity per pile, piles 5m long) below the toe of the engineered fill with geogrid REB slope (20kN/m long-term strength at 0.6m vertical intervals, 4m long) above.
		50% Fill Saturation (Stability enhancement)	
R	Pre-development	Long Term Groundwater Conditions	FoS less than the required values for temporary elevated groundwater conditions.
		Temporary Elevated Groundwater Conditions	
		Seismic	
	Post development	Long Term Groundwater Conditions	FoS less than the required values for all cases. Stability enhancement measures required.
		Temporary Elevated Groundwater Conditions	
		Seismic	

Cross-Section		Scenario	Comments
		50% Fill Saturation	
		Long Term Groundwater Conditions (Stability enhancement)	Adequate FoS achieved for slip surfaces encroaching into the lots (i.e. FoS less than the target values occur outside the lots), with inclusion of stability enhancement measures.
		Temporary Elevated Groundwater Conditions	One 3.7m high retaining wall (1.5m spacing, 240kN shear capacity per pile, piles 9m long).
		Seismic (Stability enhancement)	
		50% Fill Saturation (Stability enhancement)	
S	Post development	Long Term Groundwater Conditions	FoS less than the required values for all cases. Stability enhancement measures required.
		Temporary Elevated Groundwater Conditions	
		Seismic	
		50% Fill Saturation	
		Long Term Groundwater Conditions (Stability enhancement)	Adequate FoS achieved for all scenarios with inclusion of stability enhancement measures. Proposed Enhancement: Palisade wall (1.5m spacing, 640kN shear capacity per pile, piles 5m long) below the toe of the engineered fill with geogrid REB slope (20kN/m long-term strength at 0.6m vertical intervals, 5m long) above.
		Temporary Elevated Groundwater Conditions	
		Seismic (Stability enhancement)	
		50% Fill Saturation (Stability enhancement)	
	Pre-development	Long Term Groundwater Conditions	FoS less than the required values for temporary elevated groundwater and seismic conditions.

Cross-Section		Scenario	Comments
T		Temporary Elevated Groundwater Conditions	
		Seismic	
	Post development	Long Term Groundwater Conditions	FoS less than the required values for temporary elevated groundwater conditions. Stability enhancement measures required.
		Temporary Elevated Groundwater Conditions	
		Seismic	
		50% Fill Saturation	
		Long Term Groundwater Conditions (Stability enhancement)	Adequate FoS achieved with inclusion of stability enhancement measures. Proposed Enhancement: Palisade wall (1.5m spacing, 280kN shear capacity per pile, piles 7.5m long) below the toe of the engineered fill with geogrid REB slope (20kN/m long term strength at 0.6m vertical intervals, 4m long) above. Counterfort drains also to be installed behind the REB slope to approx. 4m depth, and 10-15m long, at a 10-15m spacing.
		Temporary Elevated Groundwater Conditions (Stability enhancement)	
		Seismic (Stability enhancement)	
		50% Fill Saturation (Stability enhancement)	

Cross-Section		Scenario	Comments
U	Post development	Long Term Groundwater Conditions	FoS less than the required values for all conditions. Stability enhancement measures required.
		Temporary Elevated Groundwater Conditions	
		Seismic	
		50% Fill Saturation	
		Long Term Groundwater Conditions (Stability enhancement)	Adequate FoS achieved with inclusion of stability enhancement measures. Proposed Enhancement: 7m high retaining wall (1.5m spacing, 390kN shear capacity per pile, piles approx. 17m long) with an 18 degree batter sloping up to the site boundary. Engineered fill batter within the lower portions of the slope to comprise a REB slope (20kN/m long term strength at 0.6m vertical intervals, approx. 5m long with an undercut of approx. 2.5m).
		Temporary Elevated Groundwater Conditions (Stability enhancement)	
		Seismic (Stability enhancement)	
		50% Fill Saturation (Stability enhancement)	
V	Pre-development	Long Term Groundwater Conditions	FoS less than the required values for temporary elevated groundwater and seismic conditions.
		Temporary Elevated Groundwater Conditions	
		Seismic	
	Post development	Long Term Groundwater Conditions	FoS less than the required values for all conditions. Stability enhancement measures required.
		Temporary Elevated Groundwater Conditions	
		Seismic	
		50% Fill Saturation	

Cross-Section		Scenario	Comments
		Long Term Groundwater Conditions (Stability enhancement)	Adequate FoS achieved with inclusion of stability enhancement measures. Some slip surfaces over the southern natural slope and stream on northern side are below the target values but these don't encroach into the lots. FoS less than 1 for seismic conditions (R-L) but deformations calculated using the Jibson (2007) method are between 0mm and 5mm, which is considered to be acceptable based on MBIE guidelines.
		Temporary Elevated Groundwater Conditions (Stability enhancement)	
		Seismic (Stability enhancement)	Proposed Enhancement: Adjacent to the south facing slope a palisade wall (1.5m spacing, 200kN shear capacity per pile, piles approx. 13.5m long). For the northern fill slope an REB slope is required (40kN/m long term strength at 0.6m vertical intervals, 14-15m long. A palisade wall (1.5m spacing, 640kN shear capacity per pile, piles 8m long) is required at the toe of the fill batter. Counterfort drains also to be installed below the REB slope to approx. 5m depth and extending 15 to 20m upslope of the REB slope, at a 10-15m spacing.
		50% Fill Saturation (Stability enhancement)	
W	Post development	Long Term Groundwater Conditions	FoS less than the required values for all conditions. Stability enhancement measures required.
		Temporary Elevated Groundwater Conditions	
		Seismic	
		50% Fill Saturation	
		Long Term Groundwater Conditions (Stability enhancement)	Adequate FoS achieved with inclusion of stability enhancement measures. Proposed Enhancement: Palisade wall (1.5m spacing, 600kN shear capacity per pile, piles 7m long) installed at the base of each fill batter with REB slope above (23kN/m long term strength at 0.6m vertical intervals, 7-12m long. The upper slope excavated down to the platform level to facilitate REB construction.
		Temporary Elevated Groundwater Conditions (Stability enhancement)	
		Seismic (Stability enhancement)	

Cross-Section		Scenario	Comments
		50% Fill Saturation (Stability enhancement)	
X	Pre-development	Long Term Groundwater Conditions	FoS less than the required values for temporary elevated groundwater conditions.
		Temporary Elevated Groundwater Conditions	
		Seismic	
	Post development	Long Term Groundwater Conditions	FoS less than the required values for all groundwater conditions. Stability enhancement measures required.
		Temporary Elevated Groundwater Conditions	
		Seismic	
		50% Fill Saturation	
		Long Term Groundwater Conditions (Stability enhancement)	Adequate FoS achieved with inclusion of stability enhancement measures. Proposed Enhancement: Palisade wall (1.5m spacing, 600kN shear capacity per pile, piles 8m long) with geogrid REB slope (23kN/m long term strength at 0.6m vertical intervals, 10m long). Counterfort drains also to be installed below the REB slope to approx. 5m depth, daylighting below the REB slope and extending 15m to 20m upslope of the REB slope, at a 10m-15m spacing.
		Temporary Elevated Groundwater Conditions (Stability enhancement)	
		Seismic (Stability enhancement)	
		50% Fill Saturation (Stability enhancement)	

Cross-Section		Scenario	Comments
Y	Pre-development	Long Term Groundwater Conditions	Adequate FoS in all conditions.
		Temporary Elevated Groundwater Conditions	
		Seismic	
	Post development	Long Term Groundwater Conditions	FoS less than the required values for all cases. Stability enhancement measures required.
		Temporary Elevated Groundwater Conditions	
		Seismic	
		50% Fill Saturation	
		Long Term Groundwater Conditions (Stability enhancement)	Adequate FoS achieved with inclusion of stability enhancement measures for all cases. FoS less than required for normal and extreme groundwater locations on locations between lots, however overall, large scale stability is adequate. Proposed Enhancement: All fill batters to include geogrid REB slope (20kN/m long term strength at 0.6m vertical intervals, 3m-6m long). Palisade wall to be located at the base of the near vertical fill slopes (1.5m spacing, 100kN shear capacity per pile, 5m-7m long). All near vertical cuts to be supported by cantilever type retaining walls (1.5m spacing, 100kN shear capacity per pile, 9m long).
		Temporary Elevated Groundwater Conditions (Stability enhancement)	
		Seismic (Stability enhancement)	
		50% Fill Saturation (Stability enhancement)	
Z	Post development	Long Term Groundwater Conditions	FoS less than the required values for all cases for slip surfaces encroaching on the platform. Stability enhancement measures required.
		Temporary Elevated Groundwater Conditions	No saturated fill case has been analysed as no fill has been proposed.
		Seismic	

Cross-Section		Scenario	Comments
		Long Term Groundwater Conditions (Stability enhancement)	Adequate FoS achieved for slip surfaces encroaching within the platform area with inclusion of stability enhancement measures. Proposed Enhancement: Proposed Enhancement: Palisade wall on the downslope edge of the platform (1.5m spacing, 250kN shear capacity per pile, piles approx. 7m long).
		Temporary Elevated Groundwater Conditions (Stability enhancement)	
		Seismic (Stability enhancement)	
AA	Post development	Long Term Groundwater Conditions	FoS less than the required values for all cases. Stability enhancement measures required.
		Temporary Elevated Groundwater Conditions	
		Seismic	
		50% Fill Saturation	
		Long Term Groundwater Conditions (Stability enhancement)	Adequate FoS achieved for large scale slope stability with inclusion of stability enhancement measures. Proposed Enhancement: Geogrid REB slope (40kN/m long-term strength at 0.6m vertical intervals, varying between varying from 5m-8m long) extending down into natural slope profile. Approx 4m deep, 16m wide shear key required below the REB slope. All steep cut batters to be supported by cantilever retaining walls (1.5m spacing, 100kN shear capacity per pile, piles approx. 5m long).
		Temporary Elevated Groundwater Conditions (Stability enhancement)	
		Seismic (Stability enhancement)	
		50% Fill Saturation (Stability enhancement)	

Cross-Section		Scenario	Comments
AB	Pre-development	Long Term Groundwater Conditions	FoS less than the required values for temporary elevated groundwater and seismic conditions.
		Temporary Elevated Groundwater Conditions	
		Seismic	
	Post development	Long Term Groundwater Conditions	FoS less than the required values for all cases. Stability enhancement measures required.
		Temporary Elevated Groundwater Conditions	
		Seismic	
		50% Fill Saturation	
		Long Term Groundwater Conditions (Stability enhancement)	Adequate FoS achieved with inclusion encroaching within the platform area with inclusion of stability enhancement measures.
		Temporary Elevated Groundwater Conditions (Stability enhancement)	
		Seismic (Stability enhancement)	<p>Proposed Enhancement: Geogrid REB slope (30kN/m long-term strength at 0.6m vertical intervals, 14m long). Approx 5m deep, 15m wide geogrid reinforced shear key required below the REB slope. Palisade wall to be located at the base of the near fill slope (1.5m spacing, 480kN shear capacity per pile, 8m long).</p> <p>All steep cut batters to be supported by cantilever retaining walls (1.5m spacing, 100kN shear capacity per pile, piles 5m long). Counterfort drains also to be installed behind the REB slope to approx. 5m depth, extending 15 to 20m upslope of the REB slope, at a 10m-15m spacing.</p>
		50% Fill Saturation (Stability enhancement)	

Cross-Section		Scenario	Comments
AC	Pre-development	Long Term Groundwater Conditions	Adequate FoS in all conditions.
		Temporary Elevated Groundwater Conditions	
		Seismic	
	Post development	Long Term Groundwater Conditions	FoS less than the required values for all cases for slip surfaces. Stability enhancement measures required.
		Temporary Elevated Groundwater Conditions	No saturated fill case has been analysed as no fill has been proposed.
		Seismic	
		Long Term Groundwater Conditions (Stability enhancement)	Adequate FoS achieved with inclusion of stability enhancement measures. Proposed Enhancement: Soil nails (1.2m spacing, 50kN tensile capacity, 5m long) over the upper soil portion of the cut batter adjacent to the western boundary.
		Temporary Elevated Groundwater Conditions (Stability enhancement)	
		Seismic (Stability enhancement)	
AD	Post development	Long Term Groundwater Conditions	FoS less than the required values for all cases. Stability enhancement measures required.
		Temporary Elevated Groundwater Conditions	
		Seismic	
		50% Fill Saturation	
		Long Term Groundwater Conditions (Stability enhancement)	

Cross-Section		Scenario	Comments
		Temporary Elevated Groundwater Conditions (Stability enhancement)	Adequate FoS achieved for all scenarios with inclusion of stability enhancement measures. Proposed Enhancement: Geogrid REB slope (20kN/m long term strength at 0.6m vertical intervals, 5-9m long). Palisade wall below the REB slope (1.5m spacing, 480kN shear capacity per pile, piles 7-10m long). Counterfort drains also to be installed from approximately 10m below the toe of the REB slope to approx. 5m depth, extending 15m to 20m upslope of the REB slope, at a 10m-15m spacing.
		Seismic (Stability enhancement)	
		50% Fill Saturation (Stability enhancement)	
AF	Post development	Long Term Groundwater Conditions	Adequate FoS for development area in all conditions.
		Temporary Elevated Groundwater Conditions	
		Seismic	
		50% Fill Saturation	
		Long Term Groundwater Conditions (Stability enhancement)	Adequate FoS achieved in development area for all scenarios with inclusion of stability enhancement measures – added to take into account steeper slopes in vicinity. Proposed Enhancement: Geogrid REB slope (20kN/m long term strength at 0.6m vertical intervals, 2m long).
		Temporary Elevated Groundwater Conditions (Stability enhancement)	
		Seismic (Stability enhancement)	
		50% Fill Saturation (Stability enhancement)	

Cross-Section		Scenario	Comments
AH	Post development	Long Term Groundwater Conditions	FoS less than the required values for all cases. Stability enhancement measures required.
		Temporary Elevated Groundwater Conditions	
		Seismic	
		50% Fill Saturation	
		Long Term Groundwater Conditions (Stability enhancement)	Adequate FoS achieved for slip surfaces encroaching within the platform area with inclusion of stability enhancement measures. Proposed Enhancement: Geogrid REB slope (30kN/m long-term strength at 0.6m vertical intervals, 15m long). Approx 3m deep, 17m wide shear key required below the REB slope. Palisade wall to be located at the base of the near fill slope (1.5m spacing, 280kN shear capacity per pile, 10m long).
		Temporary Elevated Groundwater Conditions (Stability enhancement)	
		Seismic (Stability enhancement)	
		50% Fill Saturation (Stability enhancement)	

5.1.5 Discussion on Slope Stability

The slope stability analyses results show an unacceptable FoS against instability is available across significant portions of the site without stability enhancement, typically as a result of the combination of saturated groundwater conditions and steep proposed slopes. The analysis results indicate that the existing instability features are likely caused by saturated groundwater conditions. Accordingly, the control of both surface water and groundwater is important.

As mentioned in earlier sections, several existing instability features have been identified that will need to be remediated. The measures considered to be required to ensure that adequate FoS against instability are outlined in Tables 8 and 9 above and discussed below.

The results for the sections that include the allowance for stream downcutting and widening with the proposed stability enhancement measures the FoS achieve the required values as per the CoP. It is noted that where minimum FoS values below the CoP requirements are shown on the sections, these are either outside the proposed development area or specifically relate to the ULS seismic loading case. Where ULS seismic FoS values are less than 1.0, seismic deformations were calculated using the Jibson (2007) method as described above.

The results for all the pre-development contour scenarios analysed indicate that:

- Where the existing slope returned acceptable FoS values, the proposed development with stability enhancement measures also returned acceptable FoS values; and
- Where the existing slope returned low FoS values, the proposed development with stability enhancement measures either returned acceptable FoS values (within the development area) or returned FoS values no worse than the existing slope (beyond the development area).

These findings indicate that the proposed development will not negatively impact the stability of existing slopes at the site, including near the site boundaries nor through streams immediately beyond the proposed development areas.

The 50% saturation conditions returned FoS values greater than 1.0 within the development area, indicating that slope instability is unlikely in this scenario. Some of the models returned minimum FoS values less than 1.0, however these failure surfaces are all located on natural slopes remote from the development area and any stability enhancement features, i.e. the FoS in these areas is not reduced from pre-development FoS for this scenario. This analysis assumes that the subsoil drains have become ineffective (e.g. blocked or impaired function). The subsoil drainage to be installed as part of the development will utilise TNZ F/2 compliant drainage material. This grade of drainage material should adequately mitigate the risk of subsoil drainage becoming blocked or needing long-term maintenance. However, to ensure the long-term performance of the drains over their design life, an Operation and Maintenance Plan will be prepared and provided as part of completion reporting where these drains are proposed. Proposed consent conditions for this are included in Appendix H.

5.1.6 Stability Enhancement Measures

In order to provide an adequate FoS against slope instability for the building lots, the associated accessways and batters, we consider that the following concept stability enhancement measures need to be incorporated into the subdivision design:

- **Subsoil drainage** beneath all engineered fills (configuration including cross bench, main lines and herringbone laterals) to minimise the risk of soil profile saturation and provide a degree of control over groundwater levels.
- All fill slopes steeper than 1v in 3h should have **geogrid reinforcement** (e.g. reinforced earth batter, REB) of varying lengths included. Most fill batters that are on the edges of the gullies vary between approximately 45 and 70 degrees. At some locations an inground **palisade wall** is required to be installed below the toe of the REB slopes and REB walls.
- For perimeter cut batters in the western, eastern and southern parts of the site a cantilever type **retaining wall** could be constructed to a height sufficient to reduce the batter gradient to 1v in 3h. Depending on the height of the retaining wall, tiebacks may be required.
- For the areas in the vicinity of cross-sections A, I, and M within the central portion of Stage 1 a suitable option is to excavate the unstable ground and substantially rework the Northland Allochthon slope to form a **shear key** with **subsoil drainage**. **Geogrid** reinforcement will also need to be incorporated in the fill batters.
- Specifically for cross-section A, **palisade retaining walls** are required to support the mid and upper fill platforms.
- Two, tiered **retaining walls** are required to support the northern boundary cut.
- Internal batters between lot platforms are to be supported by **cantilever or gravity type retaining walls**.
- For retaining/palisade locations where the required unfactored shear capacity (see Tables 8 and 9 above) is less than 150kN, 400mm–450mm timber SED piles should be satisfactory. For **retaining/palisade walls** that the stability analysis indicates require an unfactored shear capacity of at least 200kN, 400kN or 640kN, steel piles in the order of 310UC97's to 310UC158's or steel reinforced concrete piles likely the range of 600mm to 750mm–diameter will likely be required. These indicative pile sizes will need to be reviewed and refined during detailed design.
- At some locations **counterfort** (e.g. trench type) drains are required to either below and/or above REB slopes (this is predominantly within Stage 2) to provide control over ground saturation. These drains are typically 5m deep and at 10m–15m spacing and typically in the order of 20m long.
- **Shear keys** (with and without geogrid reinforcement) are also proposed below the REB slopes at several locations, predominantly within Stage 2. The shear keys are indicated to be 3m–9m deep and 10m to 17m wide and extend into the underlying rock mass.

The preliminary proposed locations and extents of these measures are indicated on the appended Sketches SK140 to SK144, SK180 to SK184 (including inferred geology and geomorphological model) and SK185 to SK189 (including cut/fill isopachs). The general conceptual configuration of these measures is also indicated on the appended sketches. The in-ground walls, soil nails, REB slopes, retaining walls and earthworks measures (e.g. shear keys and subsoil drainage) will require specific geotechnical input to the detailed design.

The proposed measures have addressed channel incision and widening in response to Morphem geomorphic recommendations. Specifically, steepened REB or REB slopes, adjusted shear key dimensions and updated palisade wall capacities have been implemented at particular reaches as necessary. In addition, all other batters steeper than 1v in 4h will require further geotechnical input during detailed design. The final extent and locations of the proposed remedial stability measures will need to be confirmed on-site by Riley during construction.

In some locations, the geogrid reinforcement of the REB walls and proposed infrastructure, such as stormwater and wastewater culverts, will interact. Where the proposed stormwater and wastewater pipes cross the gullies, they are vertically offset from the culverts at the base of the gullies and located within the upper part of the REB wall. Accordingly, we consider that they should not adversely affect the feasibility of the REB walls and provision will be made for them during detailed design and construction of the stability enhancement measures.

In addition to the enhancement measures, it is also important that surface water is controlled to ensure that all runoff from impervious areas is collected and piped to suitable locations remote from the building platforms and accessways. Uncontrolled discharges of stormwater onto steep slopes should be avoided. Recommended measures to discharge stormwater are discussed further in Section 5.9.

Furthermore, we recommend that where possible, the existing vegetation should be supplemented with new plantings, and the steep proposed slopes should also be vegetated. The contribution of vegetation to overall ground stability should not be underestimated. From review of the Greenwood Associates proposed Revegetation Plan we understand that substantial re-vegetation of the steeper slopes adjacent to the streams is proposed. This is consistent with our recommendation above.

5.1.7 PC120 Landslide Risk Assessment

The recent effects of Plan Change 120 (PC120) and resulting updates to the Auckland Unitary Plan Chapter E36, now require a landslide hazard risk assessment for sites mapped as within or proximate to landslide hazards to be prepared in accordance with Appendix 24 of PC120. Given the large development area and our experience at the site, Riley considered that multiple risk assessments needed to be undertaken to adequately address what we consider to be multiple landslide hazards at the site.

The development will comprise activities of varying sensitivity to natural hazards in line with Chapter J1 (development of residential dwellings being a *sensitive* activity, but roads and utilities being a *less sensitive* activity by definition). Auckland Council's Geomaps indicate that there are multiple known landslides mapped within or proximate to the site, and the site lies within areas of varying susceptibility to landslides (both shallow and deep-seated, with susceptibility classes ranging from Low to Very High). This has triggered the need to undertake a landslide hazard assessment using PC120 Appendix 24.

Riley undertook seven separate assessments to adequately quantify the landslide risk across the site. Six of these assessments related to building platforms proximate to specific potential landslide hazards (and required both semi-quantitative and quantitative assessments be undertaken). The seventh assessment considers the landslide risk to roads and utilities and focuses on the entire site as a whole (where only a semi-quantitative assessment was required). The required landslide scenarios (to simulate the highest likelihood, median, and maximum credible potential landslides in accordance with Appendix 24) were tailored specifically to each assessment to represent the critical landslides that could potentially affect the development aspects being assessed.

Refer to Appendix E for the risk assessment calculations, parameter selection, and justification for each. In summary, with construction of the stability enhancement measures proposed below, the landslide risk levels for all scenarios, for each of the seven assessments have been calculated to be Low (acceptable) in accordance with PC120 requirements.

5.1.7.1 Batter Stability

The boundary between Stages 1 and 2 is temporarily proposed to comprise a 1(V):2.5(H) cut batter. This temporary batter will be formed during Stage 1 cut to fill earthworks and later removed as part of the proposed Stage 2 cut. Additional stability analysis on a representative section of this temporary slope under normal and extreme groundwater conditions, and under ULS seismic conditions, has been undertaken. The results indicate that the FoS values available for this temporary slope achieve the minimum outlined in the CoP. Full details of these stability analyses are in Appendix F (Section: Proposed Temp Cut Stage 1-2).

The construction methodology of the batters, especially in relation to walls that are near the boundary, will need to be considered as part of detailed design. A partial top-down construction methodology will be employed. The construction sequence is to be: (1) Cut down to the top of the boundary wall and form the batter above it. (2) Drill the wall pile holes and concrete them in place. (3) Progressively excavate and install the wall rails and drainage - in a hit and miss pattern over short lengths of wall. This construction sequence will ensure that the full batter height does not need to be formed before the retaining wall is installed. The final construction sequence will be confirmed during detailed design.

5.2 Groundwater Impact Assessment

An assessment has been made of the impact of the proposed development on groundwater conditions in accordance with the requirements of Section E7 of the AUP. The assessment considers the impact of the development proposal for groundwater diversion activities. The results are contained within Table 10 below. The results are also discussed below.

As outlined in Section 2.5, the site contains a series of ridges and gullies. We consider that this topography has led to the formation of localised groundwater regimes between the gullies. Further, groundwater level monitoring to date indicates that groundwater is likely perched on top of the shallow rock that is present throughout the site. The proposed earthworks generally involve cutting from the elevated ridge lines and filling on their side slopes as well as across the gullies to construct accessways. Subsoil (underfill) drains will be installed as part of the earthworks.

Any groundwater intercepted by these will be returned to the streams/wetlands in the gullies and will not be diverted to other catchments. Therefore, the size of the water catchments is not being altered and all pre-development surface and groundwater that would otherwise have passed through the wetlands/gullies is still directed there following development. As such, we consider that the proposed excavations should not alter the receiving flows for the downstream catchments.

The groundwater intercepted upslope of the wetlands by site earthworks, subsoil and retaining wall drainage should be discharged into the wetlands/gullies at the nearest practical point to where the water is collected. It should be discharged at discrete locations via appropriately designed energy dissipation devices (e.g. over rock rip-rap or similar) to minimise the erosion risk. Because of the discrete nature of the discharges, there may be some localised concentration of water at the drain outlets from pre-development conditions, but overall, all the groundwater that would otherwise have entered the wetlands should still be directed to them.

There are some areas where it is proposed to form cut batters adjacent to the external boundary of the development and where the groundwater table is likely to be intercepted. These are primarily proposed along the northern and eastern boundaries of Stage 1 where cuts of up to approximately 8m and 12.5m respectively are proposed. There are also some smaller cuts of approximately 4-5m along the southern boundary of Stage 1. Within Stage 2 there are cuts of up to 14m mid-way along the western boundary and 12m in the northern end of the eastern boundary. Elsewhere, where there are boundary cuts on the eastern and southern boundaries, they are in the range of 8m-9m depth.

Based on review of the groundwater level monitoring data collected to date, we consider that the boundary cuts will exceed the permitted activity rules in relation to E7 of the AUP. See Table 10.

Table 10: Auckland Unitary Plan Chapter E – Auckland Wide, Part 7 Taking, using, Damming and Diversion of Water and Drilling

Rule		Activity	Applicability to this Site
E7.6.1.6	Dewatering or groundwater level control associated with a groundwater diversion permitted under Standard E7.6.1.10, all of the following must be met – Permitted Activities	<ul style="list-style-type: none"> • The water take must not be geothermal water; • The water take must not be for a period of more than ten days where it occurs in peat soils, or 30 days in other types of soil or rock; and • The water take must only occur during construction. 	Does not comply: Diversion is permanent.
E7.6.1.10. (1)	Diversion of groundwater caused by any excavation (including trench) or tunnel – Permitted Activities	<p>All of the following activities are exempt from the Standards E7.6.1.10(2) – (6):</p> <ul style="list-style-type: none"> • Pipes cables or tunnels including associated structures, which are drilled or thrust and are less than 1.2m in external diameter; • Pipes including associated structures up to 1.5m in external diameter where a closed faced or earth pressure balanced machine is used; • Piles up to 1.5m in external diameter are exempt from these standards; • Diversions for no longer than ten days; or • Diversions for network utilities and road network linear trenching activities that are progressively opened, closed and stabilised where the part of the trench that is open at any given time is no longer than ten days. 	Does not comply: Permanent diversion due to groundwater drawdown for proposed site earthworks

Rule		Activity	Applicability to this Site
E7.6.1.10. (2)		Any excavation that extends below natural groundwater level, must not exceed: <ul style="list-style-type: none"> • 1ha in total area; and • 6m depth below the natural ground level 	Does not comply: The total cut area is greater than 1ha. The maximum depth of excavation is locally between 4m and 14m below the natural ground level where cuts are proposed adjacent to the property boundary.
E7.6.1.10. (3)		The natural groundwater level must not be reduced by more than 2m on the boundary of the adjoining site	Complies: Our assessment indicates for Stage 1 a worst-case total drawdown of the groundwater table of 1.8m along parts of the northern boundary and the northern part of the eastern boundary. For Stage 2, the maximum groundwater drawdown at the site boundary is calculated to be 1.6m and occurs along the southern boundary. Elsewhere, due to the proximity of rock to the ground surface the groundwater drawdown is limited to the top of the rock. The deepest being 5.2m (for approximately 3.2m of groundwater drawdown) along the southern part of the eastern boundary adjacent to Ara Hills.
E7.6.1.10. (4)		Any structure, excluding sheet piling that remains in place for no more than 30 days, that physically impedes the flow of groundwater through the site must not: <ul style="list-style-type: none"> • Impede the flow of groundwater over a length of more than 20m; and • extend more than 2m below the natural groundwater level. 	Complies: The required stability enhancement measures should not impede groundwater flows.

Rule	Activity	Applicability to this Site
E7.6.1.10. (5)	<p>The distance to any existing building or structure (excluding timber fences and small structures on the boundary) on an adjoining site from the edge of any:</p> <ul style="list-style-type: none"> trench or open excavation that extends below natural groundwater level must be at least equal to the depth of the excavation; tunnel or pipe with an external diameter of 0.2 – 1.5m that extends below natural groundwater level must be 2m or greater; or a tunnel or pipe with an external diameter of up to 0.2m that extends below natural groundwater level has no separation requirement. 	<p>Partly Complies:</p> <p>The minimum distance from the Stage 1 bulk excavation to the nearest structure is >20m (greater than 9m maximum depth of excavation adjacent to the site boundary). The nearest structure considered is an adjacent consented road for Stages 6/7 of the AV Jennings Ltd Ara Hills Development. All other existing dwellings are located at least 40m away from the boundary cuts.</p> <p>For Stage 2 a farm shed is adjacent to the southern boundary. This shed is approximately 6m from the closest excavation and is in proximity to the maximum excavation along the southern boundary.</p> <p>Elsewhere around the perimeter of Stage 2 the nearest structure considered is an adjacent consented road for Stages 6/7 of the AV Jennings Ltd Ara Hills Development which is approximately 20m from the edge of the cuts on the eastern boundary. There are no other existing structures located within 40m of the boundary cuts.</p>

Rule		Activity	Applicability to this Site
E7.6.1.10. (6)		<p>The distance from the edge of any excavation that extends below natural groundwater level, must not be less than:</p> <ul style="list-style-type: none"> • 50m from the Wetland Management Areas Overlay; • 10m from a scheduled Historic Heritage Overlay; or • 10m from a lawful groundwater take. 	<p>Complies:</p> <p>The excavation edge is in excess of 50m from any wetland management overlays, greater than 10m from scheduled historic heritage overlays and lawful groundwater takes. Groundwater drawdown will occur in the cut slopes above the wetlands but as the groundwater will still be directed to the gullies at the site there should be no reduction in water reaching them.</p>

The ground conditions comprise a combination of engineered fill, NA and ECBF rock. Based on experience and published literature, a permeability value of $1 \times 10^{-7} \text{m/s}$ is considered to be representative of the soils present in Stage 1. For Stage 2 a permeability value of $1 \times 10^{-6} \text{m/s}$ was adopted to account for the presence of materials with increased silt/sand contents and lower plasticity.

Groundwater measurements indicate that the proposed excavations could induce groundwater drawdown of up to 1.8m along parts of the northern boundary and the northern part of the eastern boundary of Stage 1. For Stage 2, the maximum groundwater drawdown at the site boundary is calculated to be 1.6m and occurs along the southern boundary. At some locations groundwater drawdown is considered likely to extend beyond the site boundaries.

The extent of groundwater drawdown has been assessed in accordance with the Powrie & Preen (1994a) formula within CIRIA C515 (Groundwater Control – Design and Practice). We have assessed the magnitude of the associated settlement at the location of maximum groundwater drawdown (i.e. being at the base of the deepest excavations adjacent to the site boundary). The maximum calculated settlement at the site boundary is ~16mm which occurs along the northern-eastern boundary of Stage 1, with calculated settlements for the other locations considered being less than 6mm at the site boundary apart from the southern boundary of Stage 2 where the maximum calculated settlement is ~12mm. Consequently, we consider that the effect of this is negligible with respect to neighbouring sites. There are also no existing structures within the extent of the calculated groundwater drawdown around the perimeter the development. The nearest existing structure (farm shed) is approximately 40m beyond the southern part of the eastern boundary of Stage 1. Therefore, it is considered that there should be no adverse effect on structures or water take beyond the site boundary. Although some excavation is proposed above the wetlands, as the groundwater will still be directed to the gullies at the site there should be no reduction in water reaching them.

Therefore, there should be no influence on the groundwater table extending beyond the site boundary except at the limited locations as outlined above. There are no existing structures within the zone of influence and therefore the drawdown effect on neighbouring sites is expected to be negligible. Calculations are appended in Appendix G. We also consider that due to the limited extent of the groundwater drawdown, there should be no adverse effect on the groundwater source.

5.2.1 Culvert Groundwater Drawdown

A review of WWLA Ltd Draft Culvert Hydrology Report (dated: 23 June 2025, ref: WWLA1147) which focuses on longitudinal groundwater flows through the wetland, indicates that that a temporary, localised groundwater drawdown of up to 0.5m is expected in the immediate vicinity of the culverts. We also understand from WWLA that the flows will not be adversely constricted by the proposed culverts. We consider that due to the very limited depth and likely extent, the temporary groundwater drawdown should not result in any adverse geotechnical impacts. Specifically, this should not result in intolerable settlement of the culverts, the earthworks fills above them, or the immediate surrounds.

5.3 Liquefaction and Lateral Spreading

The age, consistency, composition, and stress history of the soil and groundwater conditions (discussed above) are not consistent with soils that are prone to liquefaction and lateral spreading. Therefore, liquefaction and lateral spreading is considered to be unlikely to occur here during a ULS seismic event.

5.4 Building Foundations

Away from the gully inverts, the relatively stiff natural soils have been encountered. We consider that these stiff soils and the engineered fill to be placed as part of subdivisional development works should be suitable to provide a geotechnical ultimate bearing capacity of 300kPa for the design of conventional shallow-type strip and pad foundations for NZS 3604 type residential structures up to three levels high and setback more than 5m from slopes with gradients exceeding 1v in 4h, except where dwellings are located above a REB slope in which case a setback of 3m is likely to be required. This will need to be confirmed during detailed design and subsequent geotechnical completion reporting. The stability analyses indicate that following construction of the stability enhancement measures no specific Building Restriction Line is required. This will need to be reviewed during preparation of the Geotechnical Completion Report following completion of the site development earthworks.

In any event, specific site investigation and foundation design will be required for all structures that extend downslope of or are within 5m of land with gradients exceeding 1v in 4h. This will be confirmed in a geotechnical completion report to be prepared following completion of site earthworks. In addition, a Building Restriction Zone plan will be included in the GCR which will include specific design zones and no-build zones.

The ground below any future service/bridge/building foundations etc. should comprise either stiff, inorganic natural soils, underlying rock, or engineered fill (placed, compacted, and tested under guidance from a geotechnical engineer and compliant with the compaction criteria described in Section 5.6.5). Any soft and/or organic soils below future foundations should be removed (and replaced with engineered fill as necessary). Alternatively, structures could be designed as fully suspended on piled foundations extending through soft/organic soils and embedded into stiff, inorganic natural soils or underlying rock below such that no reliance is placed on the soft/organic soils for support. All foundation excavations should be observed by a geotechnical engineer to confirm founding conditions during construction.

From review of the laboratory test results, our preliminary assessment of the expansive soil class for lots underlain by Northland Allochthon soils (either natural or fill) is High to Extreme in terms of AS 2870. Areas underlain by soils of the ECBF deposits are likely to be Moderately to Highly expansive. Accordingly, building foundations should be designed in accordance with B1/AS1 or AS 2870 provided that in the former case the foundation depths are consistent with those recommended in these standards. We consider that required foundation depths are likely to be in the range of 600mm to 900mm, for foundations designed in accordance with B1/AS1 dependent on the final assessed expansive site classifications across the development. Alternatively, a specifically designed raft-type foundation system could be utilised.

Further testing is recommended during preparation of the GCR following site earthworks to delineate areas of high expansivity.

5.5 Retaining Walls

In addition to the measures required for stability enhancement as discussed in Section 5.1.7, wherever near vertical batters greater than 0.6m in height are proposed between adjacent building platforms, they should be supported by specifically design retaining walls.

For specific design of the walls, we envisage that the following parameters may be used:

- K_a (active) earth pressure modified for ground slope behind for free standing walls.
- K_0 (at rest) earth pressure coefficients should be modified for slopes and surcharges for all walls in close proximity to future structures, driveways, or near proposed lot boundaries.
- Retained Soils: Refer Table 7 in Section 5.1.3 for soil effective stress parameters.
- Embedment: Refer Table 7 in Section 5.1.3 for soil effective stress parameters. or $S_u = 50\text{kPa}$ for Brom's solution.
- Allowance for building and boundary surcharge loading as applicable.
- The retaining walls should be constructed with appropriate toe drainage and backfilled to their full height with lightly tamped, granular material that complies with the TNZ F/2 specification. Toe drainage should be connected into an approved stormwater disposal system.

These values should be appropriate for the soils encountered. However, if significant zones of soft strata are exposed during the excavations, the designs should be revised, and Riley should be contacted for further advice.

Groundwater is likely to be encountered during construction; accordingly, allowance should be made for the use of sumps and pumps.

5.6 Earthworks

The drawings provided to us indicate that earthworks comprising cuts and fills up to 15m respectively. These are primarily associated with easing of site gradients and the formation of associated roads. Where design batter gradients are steeper than 1v in 4h further geotechnical input will be required during detailed design.

An earthworks specification should be prepared to assist the earthworks contractor. The key elements are broadly outlined below.

5.6.1 Stripping and Site Preparation

All topsoil, organic soils and non-engineered fill should be stripped from the proposed earthworks areas, and either stockpiled (well clear of the earthworks) for re-spreading (if suitable) at the completion of earthworks or removed from site. Where topsoil is re-spread its depth should be less than 300mm. All debris from demolition of the existing structures should be removed from site and the subgrade inspected by a geotechnical professional familiar with the contents of this report to assess if any undercutting is required.

Our investigations to date indicate that soft and/or organic soils are present to depths typically in the range of 1.5m (HA107, eastern part of Stage 1) to 4m (HA135, north-western corner of Stage 1) in the low-lying parts of the site, specifically in the base of gullies. These will need to be undercut at locations where culverts and/or fills are proposed. Prior to placement of any fill, a geotechnical professional familiar with the contents of this report, should inspect the formed subgrade to observe the exposed soils and assess if further undercutting is required. The excavated material should be replaced with earth fill, placed and compacted in accordance with Section 5.6.6.

5.6.2 Cut and Fill Materials

The site cuts will predominantly comprise Northland Allochthon and Waitemata Group soils that are present across the site. These should be suitable, with conditioning for use as engineered fill. Due to the variable soil plasticity and clay content of the soils, some of the siltier soils are likely to be difficult to earthwork. It is also likely that weathered sandstones and siltstones will make up a portion of the site fills. These materials are expected to break down into predominantly low plasticity soils under earthworks compaction. Accordingly, it will be important that soils of a high plasticity are blended with the more silty/sandy soils to assist with placement and compaction of earthworks fill consistent with the requirements of NZS 4431. In this regard it will be important that the earthworks contractor's methodology gives consideration to the distribution of high and low plasticity soils across the development.

Although not encountered during our investigations, any pumiceous soils encountered should be excluded from the earthworks. The suitability of any existing fill for inclusion in the site earthworks should be determined on-site by a qualified Geotechnical Engineer/Geologist familiar with the contents of this report.

Based on the groundwater level monitoring to date, we expect that groundwater will be encountered during site earthworks cuts. We envisage the Contractor should be able to suitably manage groundwater inflows through the construction of subsoil drainage, in combination with the use of temporary sumps and pumps. In any event, the contractor will need to ensure that their earthworks methodology allows for the interception of the groundwater table. We would expect this to be included in the Contractors Construction Management Plan.

As outlined above, moisture content conditioning will likely be required to dry back the fill materials to enable compaction at the OMC. Care will need to be taken to not over-dry the fill material. The earthworks contractor should be aware that the laboratory test results indicate the OMC for NA fill is approximately 5-15% higher than the OMC for the Waitemata Group soils. Accordingly, the NA fill materials should not be conditioned to the same moisture content as the WG materials. If over-drying occurs, then the materials should be wet back up to optimum moisture content. From the laboratory test results, we anticipate that conditioning may require alteration of the moisture content by up to approximately 20%. While we anticipate that conditioning will primarily be achieved through discing and mixing, lime/cement stabilisation is also expected to be suitable enable the soils to be placed to the required compaction criteria.

5.6.3 Rock Excavation

The cuts beyond 2.0m depth in the Northland Allochthon zone and 2.8m depth in the Waitemata Group zone could encounter weak weathered rock comprising weathered sandstones and siltstones. The approximate extent of rock that is likely to be exposed at finished level is shown on the appended Sketch SK130 in Appendix I.

Test pits were undertaken with a 12 to 13-tonne excavator with a 900mm wide general-purpose rock bucket which refused within the less weathered sandstone and siltstone bedrock of the Waitemata Group and Northland Allochthon. The proposed earthworks plan involves the excavations well below the test pit depths. The results of the machine boreholes give an indication of the character of the natural of materials below the test pit depths.

Considering the investigation data, our assessment is that the materials should be readily excavated using conventional earthworks plant (e.g. excavators with rock buckets and/or bulldozers with rippers). However, the Contractor should make their own assessment based on their envisaged earthworks methodology and machinery they have available.

Following excavation, these materials are likely to breakdown under compaction and should be suitable for inclusion within the engineered fill provided it is appropriately conditioned and mixed with materials of sufficient plasticity.

5.6.4 Cut Subgrade Protection

Where Northland Allochthon rock is exposed at the surface or immediately beneath topsoil, the rock may be subject to rapid weathering and degradation, due to dilation of defects resulting from stress relief. The exposure of the rock may also result in increasing surface water infiltration, due to the high permeability of the rock mass relative to the residual soils. This can result in a reduction of the available FoS against instability in the vicinity.

To mitigate this, wherever Northland Allochthon rock is present within 0.6m to 1m depth below cut earthworks levels, it should be undercut and replaced with a clean compacted clay fill cap. The undercuts should be of sufficient depth to ensure that the clay cap has a minimum thickness of 0.6m to 1m. The final thickness will need to be subject to on-site assessment by the geotechnical engineer during earthworks and give consideration to the characteristics of the exposed rock. In areas where ECBF rock is exposed at the finished surface, consideration should be given to over excavating and replacement with compacted clay fill to more readily facilitate installation of private service reticulation (e.g. power, telephone, gas, stormwater, wastewater) and to ensure that where possible dwelling foundations are not directly underlain by rock and soils (e.g. to mitigate potential differential settlements) for the lots. Further geotechnical input will be required as construction works progress.

5.6.5 Erosion and Sediment Control

The development proposes to implement erosion and sediment controls in accordance with Auckland Council's Erosion and Sediment Control Guide for Land Disturbing Activities (GD05). This includes:

- Limiting the extent of open earthworks at any one time (total exposed area and duration),
- Progressive stabilisation of completed areas
- Appropriately sized sediment retention devices (e.g. SRPs, decanting earth bunds)
- Stabilised construction entrances and diversion channels.

The scale and nature of the proposed works, proximity to receiving environments, and local catchment characteristics have been considered in preparing the erosion and sediment control strategy. This includes the use of staging and sequencing to minimise the potential for cumulative effects from uncontrolled sediment discharge.

5.6.6 Compaction

Earthworks fill compaction testing should be undertaken at or in excess of the frequency recommended in NZS 4431. We envisage that earthworks control will be undertaken principally using allowable air voids and shear strength criteria, although maximum dry density and optimum moisture content may also be used.

Compaction of the filling should be carried out to certifiable standards (NZS 4431) with conventional plant and should be under engineering control. The standard compaction test results indicate that the soils should be suitable to be compacted to comply with the compaction criteria of NZS4431. The preliminary fill compaction criteria are shown in Table 11.

Table 11: Fill Compaction Control Criteria

Material	Test	Average Value Not Less Than	Minimum Single Value Not Less Than
Cohesive Fill	Shear Vane – Undrained Shear Strength	NA	150kPa
	Nuclear Densometer – Air Void %	8%	10%

Note: NA = Not Applicable

Average to be determined as a rolling mean value over five consecutive tests

A specific methodology for placement and testing may be required for inclusion of Northland Allochthon/Waiemata Group rock within the engineered fill if the earthworks contractor has difficulty achieving the above compaction criteria. Further laboratory standard compaction testing will be required for fills comprising a mix of soil and rock materials. However, in general, we consider that a similar specification to that for cohesive fill is expected to be suitable.

5.6.7 Benching of Slopes

Benching of slopes should be undertaken in accordance with NZS 4431 prior to commencement of filling. This is particularly important for any earthworks within the areas adjacent to or within the gullies, steep slopes and existing instability features requiring enhancement. We consider that underfill/subsoil drainage will likely be required in these areas. The extent of underfill/subsoil drainage will need to be confirmed on-site during earthworks.

5.6.8 Underfill, Subsoil and Counterfort Drainage

Underfill and subsoil drainage should consist of 160mm-diameter highway grade drain coils with filter sock, encapsulated within an all passing drainage aggregate to the TNZ F/2 specification. The extent of the underfill and subsoil drains will need to be confirmed during detailed design and on-site during subdivisional works. For a preliminary estimate of total subsoil/underfill drain lengths, it can be assumed that a subsoil drain is required along the base of each cut bench for its full length together with associated cross bench, main line, herringbone lateral drains. These should discharge via regularly spaced lateral drains to collector manholes or suitable outfall locations with appropriately designed outfall structures.

For the deeper fills subsoil drains may need to be installed within the fill to manage internal pore water pressures with respect to a potential adverse effect on slope stability and fill induced settlements. This will be considered further during detailed design. See Section 5.7 below for further comment.

They will need to be surveyed included in as-built drawings as part of completion documentation. Typical underfill and counterfort drain details (Sketches SK202 and SK203) are appended in Appendix B.

5.7 Fill Induced Settlements

Deep fills of the nature proposed on this site may be subject to ongoing settlement for a period following completion of the works. Due to the composition of the underlying soils being very stiff to hard and the relatively shallow overburden profile, settlements due to fills are anticipated to be minor in magnitude. Our experience indicates that with appropriate gully preparation (e.g. undercutting of soft/organic soils) and subsoil drainage, settlements typically attenuate soon after earthworks are finished.

Despite the above, we have specifically considered the settlements that may occur within the deepest fill in Stage 1. The likely induced 1D settlement has been calculated using the following parameters:

- Unit weight of fill and natural soils = 18kN/m^3
- $C_u(\text{fill}) = 150\text{kPa}$ (note this is the minimum value to satisfy fill compaction criteria)
- $M_v(\text{fill}) \sim 1/(300 \times 150) \sim 0.000022\text{m}^2/\text{kN}$
- Fill Height = 15m (maximum proposed fill height within Stage 1 of the development)
- Max stress at the base of the fill = $18 \times 15 = 270\text{kPa}$
- Average stress within the fill (for internal fill settlement) = $270/2 = 135\text{kPa}$

Therefore, internal settlement within the fill = $135 \times 15 \times 0.000022 = 45\text{mm}$.

For this fill area and any other locations where fills are proposed over suspected compressible materials and where fill depths exceed 5m , settlement monitoring points should be installed at the finished surface following the completion of filling and be subject to survey monitoring to confirm that settlement rates have sufficiently attenuated for the proposed development. The inclusion of subsoil drains at 3m – 5m vertical intervals within such fills will shorten the drainage path length and thereby reduce the time for fill internal settlement attenuation. For the proposed fill depths, we anticipate that fill induced settlements are likely to be in the order of 25mm – 50mm consistent with the calculation above.

The number, positioning and frequency of post construction monitoring is to be confirmed with the Geotechnical Engineer during construction.

5.8 Rubbish Pits

The presence of rubbish pits is not uncommon within a farm setting and there may be locations within the development that contain areas of buried rubbish. Where encountered within the development area during site works, they should be excavated and backfilled with clean clay fill, placed and compacted in accordance with NZS 4431. All material excavated from rubbish pits within the development area should be removed from site.

5.9 Stormwater Control

It is important that due care is paid to the design and construction of appropriate stormwater disposal systems. These systems should serve to collect all stormwater runoff from roofs, water tank overflows, decks, driveways and other paved areas, together with discharges from and other subsoil drains. All stormwater discharges should be piped to suitable outfall locations, such as gully bases, ponds and creeks etc.

Stormwater dispersal/soakage (e.g. raingardens, swales, soak pits) and outfall structures should be designed by a chartered professional engineer experienced in stormwater design and familiar with the contents of this report. They would typically be lined. This is beneficial from a geotechnical standpoint with respect to slope stability. Stormwater soakage into Northland Allochthon soils is not recommended due to potential effects on the underlying rock mass and local stability. Where stormwater devices are excavated into Northland Allochthon materials, care will need to be taken to ensure that there is 0.6m to 1m thick clay cap over the underlying rock mass. In any event further geotechnical input will be required during detailed design of such devices to ensure that adequate FoS against instability are maintained.

For lots that are adjacent to the local gullies, discharge of stormwater over the engineered fill batters should be suitable, provided that the discharge from individual lots is via an approved energy dissipation device and flow rates are sufficiently low to prevent scour of the batter surface. To this end we recommend that erosion protection is installed with geotechnical input. This will be reviewed during detailed design.

We have reviewed the available McKenzie and Co Ltd drawings and consider that they are generally in alignment with our recommendations above with respect to stormwater control.

5.10 Effluent Disposal

The field investigation findings and laboratory PSD test results indicate that the natural soils present at the site are generally consistent with soil category 5 as described in the Auckland Council guideline document for design of on-site wastewater management – GDO6. This indicates an application rate of 8mm–12mm/day for trench type application and 2mm–3mm/day for pressure compensating dripper lines, for effluent that has been subject to secondary treatment.

The available investigation data indicates the groundwater table at the time of drilling was beyond 3m depth (i.e. at least 1m below the base of the discharge trenches). Underfill drainage upslope of the discharge trenches and dripper lines should also assist with controlling the groundwater level.

The on-site effluent discharge system is being designed by others. However, with respect to maintaining adequate FoS against ground instability we consider that the trench locations proposed by McKenzie & Co Ltd within Stage 1 immediately to the east of the Treatment Plant should be suitable. Dripper irrigation within the bush area in the north-eastern part of Stage 1 and at the other proposed dispersed locations advised to us should also be suitable with respect to stability provided the dripper line application rate gives due allowance for the land gradient and separation distances as per GD06. Dripper lines should not be placed on land with gradients steeper than 1v in 3h without further geotechnical input. This will be reviewed during detailed design.

Subsoil drainage outlet and T-Diffuser locations will need to be carefully considered to ensure that they do not discharge directly above any areas of dripper lines. This will be reviewed during detailed design.

5.11 Services

If soils of low plasticity are encountered, they are considered to be susceptible to collapse, erosion and internal piping in trenches excavated below the water table. For services constructed in such soils and where pipe gradients are steep, we recommend that seepage collars should be constructed at regular intervals (i.e. upstream of each manhole) along the service line trenches to prevent the migration of the fine soil fraction along the trenches and associated erosion and subsidence.

The contractor should also expect to encounter Northland Allochthon and or Waitemata Group rock for portions of service pipeline alignment. The contractor should ensure that their construction methodology is suitable for formation of pipe trenches in such ground conditions.

It is recommended that installation of stormwater lines be undertaken utilizing trench shields and/or battering provided the shoring methodology complies with the relevant NZ standards and legislation. The use of sumps and pumps will also likely be required to control groundwater inflows during service line installation.

Where proposed stormwater lines are oriented parallel to contour, it may also be necessary to install a 110mm-diameter perforated drain coil (with sock) in the base of the trenches to ensure that water within the trenches does not adversely affect slope stability. This is important for services in close proximity to the steep slopes present in parts of the site. In any event geotechnical input will be required during detailed design for this. For much of the service lines, it will also be necessary to ensure that the trench backfill is compacted to normal engineering standards (e.g. NZS 4431). This is particularly important for those service lines that are located in areas where materials of the Northland Allochthon are present.

5.12 Roads

We recommend that a programme of Scala be undertaken during site earthworks to confirm the available CBR at the road subgrade level. It will also be important that the suitable drainage measures are installed to help protect the subgrade. Based on our investigations to date we anticipate that a subgrade CBR of 3% to 4% should be available within the natural Waitemata Group and Northland Allochthon soils exposed at subgrade level, while for engineered clay fill, we would expect a CBR of at least 5% to be available. A CBR in excess of 7% should be expected for areas where rock is exposed at subgrade level.

5.13 Inspections

The opinions, recommendations and comments given in this report result from the application of normal methods of site investigation. As factual evidence has been obtained solely from test pits and boreholes, which by their nature only provide information about a relatively small volume of subsoils, there may be special conditions pertaining to this site which have not been disclosed by the investigation, and which have not been taken into account in the report. Considering this and the nature of the ground conditions, it is important that we are given the opportunity of inspecting the site clearing operations, earthworks operations and site drainage works to ensure that the ground conditions encountered are as anticipated from the findings of this report. If they are not, we would be on hand to recommend the most appropriate design and/or construction modifications.

We would appreciate at least 24 hours' notice prior to site inspections.

Upon satisfactory completion of these aspects of the works, we would then be in a position to issue an appropriate geotechnical completion report.

5.14 Proposed Geotechnical Consent Conditions

The proposed geotechnical consent conditions are appended in Appendix H. These address the geotechnical monitoring and reporting requirements primarily in relation to earthworks and groundwater drawdown associated with the site development works.

6.0 Further Input

There are some areas of the site in the north-eastern part of Stage 1 and across Stage 2 where only limited investigations were able to be carried out due to access constraints (e.g. tracks not passable for machinery or dense vegetation). Further investigations will be required within these areas as part of inputs for detailed design of the development.

In addition, to improve the reliability of the ground model, reduce associated uncertainties and to assist with detailed design of the stability enhancement measures, further field investigations are proposed. This additional investigation would be undertaken to support the future detailed design phase but would not be required as part of the fast-track consenting process. See appended sketch, ref: SK190-193 (Rev A), showing the approximate areas within the site where further investigation is intended to be undertaken as part of the detailed design process.

7.0 Summary

Based on the field investigation findings and geotechnical assessments, we consider that the proposed development is suitable for the site subject to the recommendations outlined in this report. These are summarised below.

- As a result of our qualitative and quantitative stability assessments, we consider that adequate FoS against instability should be available across the site with construction of stability enhancement measures as discussed in Section 5.1.
- While the proposed development does not meet the permitted E7 AUP standards with respect to groundwater drawdown, the extent of groundwater drawdown is limited and there are no structures within the zone of influence of the groundwater drawdown.
- Shallow foundations are considered to be appropriate for NZS 3604 type residential dwellings up to three levels where setback from the steeper slopes and clear of stability enhancement measures.
- The soils encountered on-site have been assessed as likely ranging from Class M (Moderate) to E (Extreme), with respect to AS 2870:1996. Further expansive soils laboratory testing is recommended at the geotechnical completion reporting stage to delineate areas of differing expansive soil classification.
- Earthworks should be undertaken in accordance with NZS 4431. Preliminary soil compaction criteria and earthworks recommendations are provided.
- Geotechnical observations and testing will be required during site development earthworks and service line installation.
- Further geotechnical input will be required for the detailed design of the stability enhancement measures. Due to access constraints and to improve ground model reliability, further geotechnical investigations are also required at some locations to support detailed design of the stability enhancements.

8.0 Limitation

This report has been prepared solely for the benefit of Vineway Ltd as our client with respect to the brief and Auckland Council in processing the consent. The reliance by other parties on the information or opinions contained in the report shall, without our prior review and agreement in writing, be at such parties' sole risk.

Recommendations and opinions in this report are based on data from limited test positions. The nature and continuity of subsoil conditions away from the test positions are inferred, and it must be appreciated that actual conditions could vary considerably from the assumed model.